


SHEET NUM.										PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	6	7	11	13	14	01/IMS/PV	02/SAF/OT										
<b>PAVEMENT</b>																		
	700						700				253	01001	700	SY	PAVEMENT REPAIR, AS PER PLAN (A)	4		
	300						300				253	01001	300	SY	PAVEMENT REPAIR, AS PER PLAN (B)	4		
	300						300				254	01601	300	SY	PATCHING PLANED SURFACE, AS PER PLAN	4		
							23,829				407	20000	23,829	GAL	NON-TRACKING TACK COAT			
							7,783				424	12000	7,783	CY	FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B ( 1" THICKNESS )			
							268				617	10100	268	CY	COMPACTED AGGREGATE ( 1" AVG. THICKNESS )			
	15.4						15.4				618	40600	15.4	MILE	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)			
											850	10010	30.96	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)			
											850	10110	1,500	FT	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)			
											850	10130	2,090	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)			
							280,143				897	01010	280,143	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A ( 1" DEPTH )			
							38				897	01010	38	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A ( 1/2" DEPTH )			
<b>TRAFFIC CONTROL</b>																		
											717	00100	717	EACH	RPM			
											717	54000	717	EACH	RAISED PAVEMENT MARKER REMOVED			
											7.74	14010	7.74	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6" ( WHITE )			
											7.74	14010	7.74	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6" ( YELLOW )			
											15.48	14110	15.48	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"			
											2,090	14310	2,090	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, CHANNELIZING LINE, 12"			
											1,500	14410	1,500	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 6"			
<b>MAINTENANCE OF TRAFFIC</b>																		
											500	11110	500	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE ( DURING CONSTRUCTION OPERATIONS )			
											LS	12420	LS		DETOUR SIGNING			
											2	12470	2	EACH	WORK ZONE SPEED LIMIT SIGN			
											5	12500	5	EACH	REPLACEMENT SIGN			
											10	12600	10	EACH	REPLACEMENT DRUM			
											4	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	6		
											30.96	20056	30.96	MILE	WORK ZONE LANE LINE, CLASS I, 6", 807 PAINT			
											15.48	22056	15.48	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 807 PAINT ( WHITE )			
											15.48	22056	15.48	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 807 PAINT ( YELLOW )			
											4,180	23110	4,180	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 12", 807 PAINT			
											3,000	24102	3,000	FT	WORK ZONE DOTTED LINE, CLASS I, 6", 807 PAINT			
											4	18700	4	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY			
<b>INCIDENTALS</b>																		
											LS	11000	LS		MAINTAINING TRAFFIC			
											LS	10000	LS		MOBILIZATION			

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER  
REB

REVIEWER  
XXX MM-DD-YY

PROJECT ID  
105341

SHEET TOTAL  
P.10 14