


**ITEM 614, MAINTAINING TRAFFIC**

A MINIMUM OF ONE LANE OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES, EXCEPT FOR A PERIOD NOT TO EXCEED 21 CONSECUTIVE CALENDAR DAYS FOR EACH OF THE PROJECT WORK LOCATIONS WITH DETOURS.

NOTICE OF CLOSURE SIGNS (W20-H13), SHALL BE ERECTED BY THE CONTRACTOR PRIOR TO THE SCHEDULED ROAD OR RAMP CLOSURE IN ACCORDANCE WITH THE NOTICE OF CLOSURE TIME TABLE BELOW. (AT THE APPROVAL OF THE ENGINEER, PORTABLE CHANGABLE MESSAGE SIGNS MAY BE USED IN LIEU OF THE STANDARD FLATSHEET SIGN FOR CLOSURE DURATIONS OF LESS THAN 1 WEEK.)



W20-H14

THE SIGNS SHALL BE ERECTED ON THE RIGHT-HAND SIDE OF THE ROAD FACING TRAFFIC. THEY SHALL BE PLACED SO AS NOT TO INTERFERE WITH THE VISIBILITY OF ANY OTHER TRAFFIC CONTROL SIGNS. ON ROADWAYS, THEY SHOULD BE ERECTED AT OR NEAR THE POINT OF CLOSURE.

NOTICE OF CLOSURE SIGN TIME TABLE		
ITEM	DURATION OF CLOSURE	SIGN DISPLAYED TO PUBLIC
RAMP & ROAD CLOSURES	≥ 2 WEEKS	14 CALENDER DAYS PRIOR TO CLOSURE
	> 12 HOURS < 2 WEEKS	7 CALENDER DAYS PRIOR TO CLOSURE
	< 12 HOURS	2 BUSINESS DAYS PRIOR TO CLOSURE

THE SIGN SHALL DISPLAY THE DATE OF THE CLOSURE IN MMM-DD FORMAT AND THE NUMBER OF DAYS OF THE CLOSURE. THE LASTLINE OF THE W20-H13 SIGN LISTS A PHONE NUMBER WHICH AMOTORIST MAY CALL FOR ADDITIONAL INFORMATION. THIS IS TOBE A SPECIFIC OFFICE WITHIN THE DISTRIC RATHER THAN THE GENERAL SWITCHBOARD NUMBER.

THE CONTRACTOR SHALL PROVIDE, ERECT AND MAINTAIN SIGNS AND SIGN SUPPORTS, AS DETAILED IN THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, AND TYPE III BARRICADES, PER SCD MT-101.60 AT THE FOLLOWING LOCATIONS:

- CLE-132-2121  
STA. 1174+00 & STA. 1171+00
- WAR-123-0151  
STA. 78+00 & STA. 81+50

FOR MORE DETAILS SEE DETOURS ON THE SHEETS LISTED IN THE TABLE CALLED PROJECT LOCATIONS WITH DETOURS TABLE ON THIS SHEET.

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH CMS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

**PROJECT LOCATIONS WITH DETOURS TABLE**

PROJECT WORK LOCATION	DETOUR PLAN SHEET
CLE-132-2121	7
WAR-123-0151	8

**ITEM 614 - DETOUR SIGNING**

THE CONTRACTOR SHALL PROVIDE, MAINTAIN, AND SUBSEQUENTLY REMOVE ALL DETOUR SIGNING AND SUPPORTS AS SHOWN ON SHEETS ~~SMDO03~~ AND ON STANDARD CONSTRUCTION DRAWING MT-101.60. ALL WORK SHALL BE PAID FOR UNDER ITEM 614, DETOUR SIGNING.

**WINDOW CONTRACT TABLE**

USE THE FOLLOWING INFORMATION IN COMBINATION WITH THE PROPOSAL NOTE 129 - WINDOW CONTRACT. THE CONTRACTOR WILL BID THE NUMBER OF CALENDAR DAYS TO COMPLETE THE PROJECT AS LISTED IN THE PROPOSAL. IF THE CONTRACTOR FAILS TO COMPLETE THE CRITICAL WORK ITEMS IN THE WINDOW SPECIFIED, THE CONTRACTOR WILL BE SUBJECT TO LIQUIDATED DAMAGES PER CMS 108.07

DESCRTIPTION OF CRITICAL WORK	CALENDER DAYS TO COMPLETE	DISINCENTIVE \$ PER DAY	WORK WINDOW	
			START	END
COMPLETE ALL WORK AT CLE-132-2121	21	\$1000	7/5/2022	7/26/2022
COMPLETE ALL WORK AT WAR-123-0151	21	PER CMS 108.07	CONTRACT EXECUTION DATE	PROJECT COMPLETION DATE

COMPLETE ALL WORK AT THESE LOCATIONS WITHIN THE SPECIFIED TIME PERIODS, WHEN THROUGH TRAFFIC MAY BE DETOURED AS SHOWN ON THE SHEETS LISTED IN THE TABLE CALLED PROJECT LOCATIONS WITH DETOURS TABLE ON THIS SHEET. A DISINCENTIVE SHALL BE ASSESSED IN THE AMOUNT OF \$1000 FOR EACH CALENDAR DAY THAT ALL THE LANES ARE NOT OPEN AND AVAILABLE TO TRAFFIC FOR EACH LOCATION. PRIOR TO OPENING ROADWAY TO TRAFFIC, ALL PERMANENT PAVEMENT MARKINGS SHALL BE IN PLACE.

I:\ProjectData\CLE\00802\_CLE-132-2121\Design\M01\Sheets\00802\_MND01.dgn\_Sheet 9/23/2021 11:59:16 AM gtfreeman

CALCULATED  
GTF  
CHECKED  
SKK

MAINTENANCE OF TRAFFIC GENERAL NOTES

CLE / WAR-132 / 123  
-21.21 / 1.51