Environmental Design Group
The community impact people.

Subject: CLI-28/124-4.52/5.47/0.54 PID 102731 Project No.: 18-00114-010

CLI-124-0054 Non-Struct. Qtys - Tracings Sheet 1 of 1

Calc. by: SAC Date: 5/10/20 Check by: RMS Date: 5/18/20

Roadway																											
Item 201 Ext. 11000, Clearing and Grubbing																	**LUMP**										
Item 202, Ext. 23010, Pavement Removed, Asphalt															**See Pavement Calcs**												
Item 203, Ext. 10000, Excavation															**See Earthwork Calcs**												
Item 203, Ext. 20000, Embankment															**See Earthwork Calcs**												
Item 204, Ext. 10000, Subgrade Compaction															**See Pavement Calcs**												
Item Special, 69050100, Mailbox Support System, Single																											
	CLI-28-0547:				Sta. 6+75, RT											**1**	**EACH**										
Erosion Control																											
Item 601 Ext. 32100, Rock Channel Protection, Type B with Filter																											
	CLI-28-0452:				Outlet channel															**43**	**CU YD**						
Item 659 Ext. 10000, Seeding and Mulching															**See Cross Sections**												
Drainage																											
Item 611 Ext. 04600, 12" Conduit, Type C																											
	CLI-124-0054:				SW quad															**31**	**FT**						
Traffic Control																											
Item 642 Ext. 00090, Edge Line, 4"																											
	CLI-124-0054:				Sta. 6+46 to Sta. 7+06, LT =															60	FT						
					Sta. 6+46 to Sta. 7+06, RT =															60	FT						
																Total =				120	FT	=		**0.02**	**MILE**		
Item 642 Ext. 00290, Center Line																											
	CLI-124-0054:				Sta. 6+46 to Sta. 7+06, CL =															60	FT			**0.01**	**MILE**		