Environmental Design Group
The community impact people.

Subject: CLI-28/124-4.52/5.47/0.54 PID 102731 Project No.: 18-00114-010

CLI-28-0547 Non-Structure Qtys - Tracings Sheet 1 of 1

Calc. by: SAC Date: 5/10/20 Check by: RMS Date: 5/18/20

Roadway							
Item 201 Ext. 11000, Clearing and Grubbing			**LUMP**				
Item 202, Ext. 23010, Pavement Removed, Asphalt			**See Pavement Calcs**				
Item 202, Ext. 35100, Pipe Removed, 24" and Under							
CLI-28-0547:	SE Quad, 12"	18	FT				
Item 202, Ext. 58100, Catch Basin Removed							
CLI-28-0547:	SE Quad, CB-3A	**1**	**EACH**				
Item 203, Ext. 10000, Excavation			**See Earthwork Calcs**				
Item 203, Ext. 20000, Embankment			**See Earthwork Calcs**				
Item 204, Ext. 10000, Subgrade Compaction			**See Pavement Calcs**				
Erosion Control	(None)						
Drainage							
Item 611 Ext. 04600, 12" Conduit, Type C							
CLI-28-0547:	SE quad			18	FT		
Item 611 Ext. 98180, Catch Basin, No. 3A							
CLI-28-0547:	SE quad			1	EACH		
Traffic Control							
Item 642 Ext. 00090, Edge Line, 4"							
CLI-28-0547:	Sta. 288+35 to Sta. 289+07, LT (Cadd measured) =			83	FT		
	Sta. 288+35 to Sta. 289+07, RT (Cadd measured) =			56	FT		
		Total =		139	FT =	**0.03**	**MILE**
Item 642 Ext. 00290, Center Line							
CLI-28-0547:	Sta. 288+35 to Sta. 288+77, CL =			42	FT =	**0.01**	**MILE**
Item 642 Ext. 00490, Stop Line							
CLI-28-0547:	Sta. 288+77, RT =			**38**	**FT**		