


STATION RANGE	TYPICAL SECTION	SIDE	DISTANCE (D)	AVERAGE WIDTH (W)	SURFACE AREA (A) A=DxW/9	CADD GENERATED AREA	202	204	254	254	301	304	407	407	441	441	
							PAVEMENT REMOVED	SUBGRADE COMPACTION	PAVEMENT PLANING, ASPHALT CONCRETE (T=1-1/4")	PAVEMENT PLANING, ASPHALT CONCRETE (T=1-1/4"-3")	ASPHALT CONCRETE BASE, PG64-22, (449)	AGGREGATE BASE	NON-TRACKING TACK COAT (0.06 GAL/SY)	NON-TRACKING TACK COAT (0.08 GAL/SY)	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)	
			FT	FT	SY	SY	SY	SY	SY	SY	CY	CY	GAL	GAL	CY	CY	
<b>RESURFACING</b>																	
<b>LEFT SHOULDER</b>																	
7+55.00		9+00.00	LT	145.00	5.25	84.58			84.58					6.77	2.94		
9+00.00		9+45.00	LT	45.00	6.00	30.00			30.00					2.40	1.04		
9+45.00		9+83.65	LT	38.65	6.00	25.77				25.77				2.06	0.89		
10+20.58		10+60.00	LT	39.42	6.00	26.28				26.28				2.10	0.91		
10+60.00		11+25.00	LT	65.00	6.00	43.33			43.33								
11+25.00		12+49.00	LT	124.00	4.00	55.11			55.11					4.41	1.91		
<b>RIGHT SHOULDER</b>																	
7+55.00		7+88.00	RT	33.00	2.00	7.33			7.33					0.59	0.25		
7+88.00		8+13.00	RT	25.00	4.00	11.11			11.11					0.89	0.39		
8+13.00		9+45.00	RT	132.00	6.00	88.00			88.00					7.04	3.06		
9+45.00		9+83.65	RT	38.65	6.00	25.77				25.77				2.06	0.89		
10+20.58		10+60.00	RT	39.42	6.00	26.28				26.28				2.10	0.91		
10+60.00		12+49.00	RT	189.00	6.00	126.00			126.00					10.08	4.38		
<b>LEFT LANE</b>																	
7+55.00		9+45.00	LT	190.00	11.75	248.06			248.06					19.84	8.61		
9+45.00		9+83.65	LT	38.65	12.00	51.53				51.53				4.12	1.79		
10+20.58		10+60.00	LT	39.42	12.00	52.56				52.56				4.20	1.83		
10+60.00		12+49.00	LT	189.00	11.15	234.15			234.15					18.73	8.13		
<b>RIGHT LANE</b>																	
7+55.00		9+45.00	RT	190.00	11.65	245.94			245.94					19.68	8.54		
9+45.00		9+83.65	RT	38.65	12.00	51.53				51.53				4.12	1.79		
10+20.58		10+60.00	RT	39.42	12.00	52.56				52.56				4.20	1.83		
10+60.00		12+49.00	RT	189.00	12.25	257.25			257.25					20.58	8.93		
<b>FULL DEPTH PAVEMENT</b>																	
9+83.65		9+88.00	LT/RT	4.35	36.93	17.85	17.85										
9+83.65		9+88.00	LT/RT	4.35	38.00	18.37		18.37				3.06					
9+83.65		9+88.00	LT/RT	4.35	36.67	17.72					2.95						
9+83.65		9+88.00	LT/RT	4.35	36.00	17.40							4.32		0.60	0.85	
10+16.24		10+20.58	LT/RT	4.34	36.89	17.79	17.79										
10+16.24		10+20.58	LT/RT	4.34	38.00	18.32		18.32				3.05					
10+16.24		10+20.58	LT/RT	4.34	36.67	17.68					2.95						
10+16.24		10+20.58	LT/RT	4.34	36.00	17.36							4.32		0.60	0.84	
<b>SUBTOTALS</b>							35.64	36.69	1430.86	312.28	5.90	6.12	8.64	135.98	60.23	1.69	
<b>TOTALS CARRIED TO SHEET GENERAL SUMMARY</b>							36	37	1431	313	6	6	145		61	2	

PAVEMENT CALCULATIONS



DESIGNER  
**AMB**  
 REVIEWER  
 SDS 11/07/24  
 PROJECT ID  
**113008**  
 SHEET TOTAL  
 P.1 1