STRUCTURE QUANTITY CALCULATIONS BRIDGE No. COL-PARK DRIVE SFN 1560346 PARK DRIVE OVER LESLIE RUN

Prepared for:
Village of East Palestine
85 North Market Street
East Palestine, OH 44413



Prepared by:
MS Consultants, Inc.
One Cascade Plaza
Suite 140
Akron, Ohio 44308

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	1	of	32	

ITEM	EXTENSION	UNIT	DESCRIPTION
202	11003	LUMP	STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN
		LS	

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	2	of	32

ГЕМ	EXTENSION	UNIT	DESCRIPTION
603	11100	LUMP	COFFERDAMS AND EXCAVATION BRACING
		LS	

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	3	of	32

503	04404			
	21101		CY	UNCLASSIFIED EXCAVATION, AS PER PLAN
	ABUTMENTS	44.83 10 6.6 2 5918	FT FT FT EA	LENGTH WIDTH AVG. HEIGHT NO. OF ABUTMENTS VOLUME
,	WINGWALLS	3.94 3.5 5.5 4	FT FT FT EA	LENGTH WIDTH AVG. HEIGHT NO. OF ABUTMENTS
		303	CF	VOLUME

230 CY

Project	Park Drive Bridge over Leslie Run	Calculated By_	<u>TVB</u>	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	4	of	32	

ITEM	EXTENSION	UNIT	DESCRIPTION
505	11100	LS	PILE DRIVING EQUIPMENT MOBILIZATION
			<u>LS</u>

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	5	of	32	

			UNIT	DESCRIPTION
507	00100		FT	STEEL PILES HP10X42, FURNISHED
				SUB TOTAL TOTAL
	Rear Abutme	ent		
	Estimated Length (ft)	# of Piles	Length (ft)	
	50.0	11	550.0	550.00
	Forward Abu	tment		
	Estimated Length (ft)	# of Piles	Length (ft)	
	45.0	11	495.0	495.00
				TOTAL 1,045

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	6	of	32	

ITEM	EXTENSION		UNIT	DESCRIPTION	
507	00150		FT	STEEL PILES HP10X42, DRIVEN	
				SUB TOTA TO	TAL
	Rear Abutme	nt			
	Real Abutille	:110			
	Estimated Length (ft)	# of Piles	Length (ft)		
	45.0	11	495.0	49	5.00
	Forward Abu	tment			
	Estimated Length (ft)	# of Piles	Length (ft)		
	40.0	11	440.0	44	0.00
				TOTAL	935

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	7	of	32	

ITEM	EXTENSION	UNIT	DESCRIPTION		
507	93300	EACH	STEEL POINTS OR SHOES		
				SUB TOTA	TOTAL
	Rear Abutment				
	# of Piles				
	11				11.00
	Forward Abutment				
	# of Piles				
	11				11.00
			-	TOTAL	22

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	8	of	32

ITEM	EXTENSION	UNIT	DESCRIPTION	
509	10000	POUND	EPOXY COATED REINFORCING STEEL	
			LBS.	
SUPER	RSTRUCTURE		5923	
	ABUTMENTS		15512	
SIDEWA	LK AND CURB		2274	
	PARAPETS		N/A	
	RAILING*		N/A	

^{*}RAILING REINFORCING ON BRIDGE INCLUDED FOR PAYMENT WITH ITEM 517E75120

TOTAL 23,709 LB

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21	
Description	ESTIMATED QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	9	of	32	

ITEM	EXTENSION	UNIT	DESCRIPTION
511	31610	CU YD	CLASS QC2 CONCRETE, SUPERSTRUCTURE
	162		DECK AREA (FROM CADD)
	36.8		DECK WIDTH
	0.50 0.32		DECK THICKNESS AREA DUE TO CAMBER (1ST HALF OF SPAN)
	0.32		AREA DUE TO CAMBER (13T HALF OF SPAN) AREA DUE TO CAMBER (2ND HALF OF SPAN)
	0.02		,
	834	.0 CF	DECK VOLUME
	1.58	B FT	DIAPHRAGM HT (SUBRTRACTED DECK THICKNESS)
	36.8	B FT	DIAPHRAGM LENGTH
	1.0	FT	DIAPHRAGM WIDTH
	58.3	S CF	DIAPHRAGM VOLUME (REAR Only)
	- <u>0.0</u>	CF	DEDUCT FOR APPR SLAB SEAT
	892	.3 CF	TOTAL SUPERSTRUCTURE CONCRETE VOLUME
	34.0	CY	SUPERSTRUCTURE CONCRETE VOLUME

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21	
Description	ESTIMATED QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	10	of	32	

ITEM	EXTENSION		UNIT	DESCRIPTI	ON			
511	34448		CY	CLASS QC2	2 CONCRETE E	BRIDGE DE	ECK (PA	ARAPET)
BARRIER	LEFT REAR	26.5 1.25 33.1	SQ FT FT CF	AREA (FROM CADD) WIDTH VOLUME				
	LEFT FWD	27 1.25 33.8	SQ FT FT CF	AREA (FROM CADD) WIDTH VOLUME				
	LEFT FWD	4.25 0.875 3.7	SQ FT FT CF	AREA (FROM CADD) WIDTH VOLUME				
	RIGHT REAR	32.9 1.25 41.1	SQ FT FT CF	AREA (FROM CADD) WIDTH VOLUME				
	RIGHT FWD	27.5 1.25 34.4	SQ FT FT CF	AREA (FROM CADD) WIDTH VOLUME				
<u>CAPS</u>	LEFT REAR	7.06 1.4 0.5 4.9 1.10	FT FT FT CF CF	LENGTH WIDTH THICK. VOLUME TOP	LEFT FWD	7.2 1.4 0.5 5.0 1.12	FT FT FT CF CF	LENGTH WIDTH THICK. VOLUME TOP
	RIGHT REAR	8.8 1.4 0.5 6.2 1.37	FT FT FT CF CF	LENGTH WIDTH THICK. VOLUME TOP	RIGHT FWD	7.3 1.4 0.5 5.1 1.13	FT FT FT CF CF	LENGTH WIDTH THICK. VOLUME TOP
	TOTAL VOL =	172.06	CF					
		7.0	СҮ	SUPERSTRUCTURE	CONCRETE VO	DLUME		

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	11	of	32	

Г				
ITEM	EXTENSION	l	UNIT	DESCRIPTION
511	43512		CU YD	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING
BREASTW	/ALLS:	7.804 7.333 36.83 36.83 3.00 2.50	FT FT FT FT FT	AVG. HEIGHT OF REAR ABUTMENT BREASTWALL AVG. HEIGHT OF FORWARD ABUTMENT BREASTWALL REAR ABUTMENT BREASTWALL LENGTH FORWARD ABUTMENT BREASTWALL LENGTH REAR ABUTMENT THICKNESS FORWARD ABUTMENT THICKNESS
		1537.6	CU FT	VOLUME
FOOTINGS	3 :	342.7 342.7 3.0 3.0	FT FT FT	Rear Ftg Plan Area Fwd Ftg Plan Area Rear Ftg Thk Fwd Ftg Thk
		2056.0	CU FT	VOLUME
WINGWAL	.LS:	83 83 84 75 1.5	SQ FT SQ FT SQ FT SQ FT FT	REAR ABUT. SW WINGWALL SURFACE AREA REAR ABUT. SE WINGWALL SURFACE AREA FORWARD ABUT. NW WINGWALL SURFACE AREA FORWARD ABUT. NE WINGWALL SURFACE AREA WINGWALL THICKNESS
		487.4	CU FT	VOLUME
				151

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21	
Description	ESTIMATED QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	12	of	32	

ITEM	EXTENSION	UNIT	DESCRIPTION
511	51511	CU YD	CLASS QC2 CONCRETE, SIDEWALK, AS PER PLAN
	On Deck: 44 6.42 0.77 1 2.42 0.67	FT EAST SIDEW FT FT WEST CUR FT FT	SIDEWALK WIDTH AVG. SIDEWALK THICKNESS NO. OF SIDES
	<u>288.1</u>	CF	VOLUME
(On Appr Slabs:		
	1 34.97 5 0.47 1		ALK LENGTH SIDEWALK WIDTH AVG. SIDEWALK THICKNESS NO. OF SIDES
	15.72 2.163 0.58 1		LENGTH AVG. CURB WIDTH AVG. CURB THICKNESS NO. OF SIDES
	102.3	<u>CF</u>	VOLUME
	14	CY	VOLUME

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	13	of	32	

-			Sileet 13 0i 32
ITEM	EXTENSION	UNIT	DESCRIPTION
512	10050	SQ YD	SEALING OF CONCRETE SURFACES (NON-EPOXY)
	SIDEWALK ON DE	ECK:	
	LT. SIDEWALK LE RT. SIDEWALK LE PERIMETER =		36.79 FT 36.79 FT 6.54 FT
	TOTAL AREA =		481.2 SF
	SIDEWALK ON AF	PROACH SLAB	oS:
	LT. SIDEWALK LE RT. SIDEWALK LE PERIMETER =		50 FT 50 FT 6.5 FT
	TOTAL AREA =		650 SF

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	14	of	32

ITEM	EXTENSION	UNIT	DESCRIPTION
512	10100	SQ YD	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)
	ABUTMENT AND WING	GWALL:	
	REAR ABUTMENT:		
	486.0	SQ FT	AREA REAR ABUTMENT FACE
	WINGWA	LLS	
	41.17	FT FT	TOP LENGTH TO BE SEALED (Both Sides)
	1.5 0.5	FT	WALL THICKNESS ADD 6" BEHIND WALL
	82.3	SQ FT	
	568.3	SQ FT	REAR SUBTOTAL
ı	FORWARD ABUTMEN		ADEA FORMARD ARLITMENT FACE
	512.0	SQFI	AREA FORWARD ABUTMENT FACE
	MINICIAVA		
	WINGWA	LLS	
I	42 1.5	FT FT	TOP PERIMETER TO BE SEALED WALL THICKNESS
	0.5 84	FT SQ FT	ADD 6" BEHIND WALL AREA OF TOP AND BEHIND WALL
	596.0	SQ FT	FORWARD SUBTOTAL
		30(11	FORWARD SOBIOTAL
DECK /	AND RAILING:		
	1	FT	BEAM DEPTH
	0.5 4	FT FT	DECK THICKNESS BEAM UNDERSIDE (BDM REQUIREMENT)
	71.46	FT	TWICE THE BEAM LENGTH (BOTH SIDES)
I	228.88 234.67	SF SF	LT. RAILING AREA (N&F FACE AND TOP/SIDES) RT. RAILING AREA (N&F FACE AND TOP/SIDES)
	856.58	SQ FT	DECK SUBTOTAL
1			

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	15	of	32

ITEM	EXTENSION		UNIT	DESCRIPTION
512	44400		SY	TYPE B WATERPROOFING
	FWD. ABUT.: _	4.0 1.42 9 51	FT FT SF	LENGTH HEIGHT NO. OF BEAMS
		5.67	SY	

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	16	of	32	

ITEM	EXTENSION		UNIT	DESCRIPTION
512	75010		SQ FT	SPECIAL - SEALING, MISC.: ARCHITECTURAL STAINING
	RAILING			
		88	SF	LT. RAILING ON DECK AREA
		88	SF	RT. RAILING ON DECK AREA
		72	SF	PILASTERS (ASSUME 4.5' HT. x 4' LENGTH IN 4 LOC.)
		26.145	SF	LT. RAILING ON APPROACH AREA (ASSUME 42" HT.)
		27.125	SF	RT. RAILING ON APPROACH AREA (ASSUME 42" HT.)
		2		NO. OF FACES TO BE STAINED PER RAILING
		17.5	SF	PILASTER FRONT/BACK EXPOSED FACE
		17.5	SF	RAILING ON APPROACH ENDS
		676.54	SQ FT	RAILING TOTAL

677 SF

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	17	of	32	

ITEM	EXTENSION	UNIT	DESCRIPTION
515	12031	EACH	PRESTRESSED CONCRETE COMPOSITE BOX BEAM BRIDGE MEMBERS, LEVEL 1, CB17-48, AS PER PLAN (LENGTH = 42.92')

9 EACH

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	18	of	32

ITEM	EXTENSION	UNIT	DESCRIPTION
516	12302	FT	STRIP SEAL EXPANSION JOINT ANCHORED WITH ELASTOMERIC CONCRETE
		36.83 FT 1	LENGTH SIDES
			37 FT

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	02/02/22
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	02/02/22
		Sheet	19	of	32

ITEM	EXTENSION		UNIT		DESCRIPTION
516	12310		LB		SIDEWALK COVER PLATE
		4.57	F-T		EAST SIDEWALK I ENSTLI
		4.57	FT		EAST SIDEWALK LENGTH
		0	FT		WEST CURB LENGTH
		4.57	FT		TOTAL LENGTH
		0.375	IN		PLATE THICK.
		1.5	FT		PLATE WIDTH
		1.0	POUND		(10) STAINLESS STEEL ANCHORS
		106			WEIGHT
				106	LB

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	20	of	32	

ITEM	EXTENSION		UNIT	DESCRIPTION
	EXTENSION			BECOKII HON
516	13600		SQ FT	1" PREFORMED EXPANSION JOINT FILLER
		3.83 1.25	FT FT	BETWEEN EACH WINGWALLS AT BRIDGE LIMITS HEIGHT WIDTH
		4		NUMBER OF LOCATIONS
		19.2	SQ FT	TOTAL
		1.85 28 2.6 8.50	FT FT FT FT	BETWEEN DECK AND APP. SLAB AT F.A. DEPTH UNDER ROADWAY LENGTH UNDER ROADWAY DEPTH UNDER SIDEWALK AND CURB LENGTH UNDER SIDEWALK AND CURB
		73.9	SQ. FT	TOTAL
				94 SQ FT

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	21	of	32	

ITEM	EXTENSION		UNIT	DESCRIPTION
516	13900		SF	2" PREFORMED EXPANSION JOINT FILLER
		2.1 1.75	FT FT	BETWEEN EACH WINGWALL AND BEAM DEPTH OF BEARINGS + BEAMS + DECK LENGTH
		4		NUMBER OF WINGWALLS
		14.7	SQ FT	TOTAL
		1.25 6.5 6.5 7.5 6.25	FT FT FT FT	BETWEEN WINGWALL AND APP. SLAB (REAR AND FORWARD DEPTH LENGTH (LEFT REAR) LENGTH (RIGHT REAR) LENGTH (LEFT FWD.) LENGTH (RIGHT FWD.)
		26.75	FT	TOTAL LENGTH
		33.4	SQ FT	TOTAL
		0.85 1.7	FT FT	ADD AREA AT APPR SLAB HAUNCH NEAR SEAT DEPTH LENGTH
		4		NUMBER OF LOCATIONS
		5.8	SQ. FT	TOTAL
				54

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	22	of	32

ITEM	EXTENSION		UNIT	DESCRIPTION
516	25000		SF	NYLON REINFORCED NEOPRENE SHEETING
	REAR ABUT.:	4.0 3.0 2 24	FT FT SF	LENGTH WIDTH NO. OF LOCATIONS
R.A.	@ APP. SLAB: _	2.75 3.0 2 16.5	FT SF	LENGTH WIDTH NO. OF LOCATIONS
	FWD. ABUT.: _	4.0 3.0 2 24	FT FT SF	LENGTH WIDTH NO. OF LOCATIONS

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	23	of	32	

ITEM	EXTENSION	UNIT	DESCRIPTION
516	43101	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES ONLY (NEOPRENE), AS PER PLAN
		9 2 2	NUMBER OF BEAMS ENDS OF BRIDGE BEARINGS PER END
		36	EACH_

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	24	of	32	

ITEM	EXTENSION	UNIT	DESCRIPTION
517	75120	FT	RAILING (CONCRETE PARAPET WITH TWIN STEEL TUBE RAILING)
		Length Left Side	44 FT
		Length Right Side	44 FT

88.00 FT

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	25	of	32

Abutment Length (ft) Width (ft) Height Volume (CY) Rear Stem Fwd. Stem 36.83 2.00 6.59 17.98 Fwd. Stem 36.83 2.00 6.19 16.89	ITEM	EXTENSION	UNIT		DESCRI	PTION	
(ft) (ft) (ft) (CY) Rear Stem 36.83 2.00 6.59 17.98 Fwd. Stem 36.83 2.00 6.19 16.89	518	21200	CU YD		POROUS	BACKFILL WITH GEOTEXTILE FA	BRIC
Rear Stem 36.83 2.00 6.59 17.98 Fwd. Stem 36.83 2.00 6.19 16.89		Abutment	-		-		
Fwd. Stem 36.83 2.00 6.19 16.89							
		Rear Stem	36.83	2.00	6.59	17.98	
D 1111		Fwd. Stem	36.83	2.00	6.19	16.89	
Rear Wings 9 2.00 2.54 1.69		Rear Wings	9	2.00	2.54	1.69	
Fwd. Wings 9.7759 2.00 2.54 1.84		Fwd. Wings	9.7759	2.00	2.54	1.84	

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	26	of	32	

ITEM	EXTENSION		UNIT		DESCRIPTION
518	40000		FT		6" PERFORATED CORRUGATED PLASTIC PIPE
		50.17 50.83	FT FT		LENGTH BEHIND REAR ABUTMENT LENGTH BEHIND FORWARD ABUTMENT
				101	FT

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	27	of	32

	EXTENSION		UNIT	DESCRIPTION
518	40010		FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS
		10	FT	AT REAR ABUTMENT LEFT WINGWALL
		10	FT	AT REAR ABUTMENT RIGHT WINGWALL
		10	FT	AT FORWARD ABUTMENT LEFT WINGWALL
		10	FT	AT FORWARD ABUTMENT RIGHT WINGWALL

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	28	of	32	

ITEM	EXTENSION	UNIT	DESCRIPTION
526	25000	SY	REINFORCED CONCRETE APPROACH SLABS (T=15")
	863.1 863.6	SF SF	REAR APPROACH AREA (CADD) FWD APPROACH AREA (CADD)
	1727	SQ FT	
			192 SY

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	29	of	32

ITEM	EXTENSION	UNIT	DESCRIPTION
526	90010	FT	TYPE A INSTALLATION
		33.61 FT 34.04 FT	AT REAR APPROACH SLAB AT FORWARD APPROACH SLAB
			68 FT

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	30	of	32	

ITEM	EXTENSION	UNIT	DESCRIPTION
SPECIAL	530E00200	LUMP	SPECIAL - STRUCTURES: VIBRATION MONITORING
		LS	

Project	Park Drive Bridge over Leslie Run	Calculated By_	TVB	Date	04/29/21	
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22	
		Sheet	31	of	32	

ITEM	EXTENSION		UNIT	DESCRIPTION
SPECIAL	530E13000		SQ FT	SPECIAL - FORM LINER
	DAILING			
	RAILING			
		88	SF	LT. RAILING ON DECK AREA
		88	SF	RT. RAILING ON DECK AREA
		72	SF	PILASTERS (ASSUME 4.5' HT. x 4' LENGTH IN 4 LOC.)
		54.145	SF	LT. RAILING ON APPROACH AREA (ASSUME 42" HT.)
		55.125	SF	RT. RAILING ON APPROACH AREA (ASSUME 42" HT.)
		2		NO. OF FACES TO BE STAINED PER RAILING
		17.5	SF	PILASTER FRONT/BACK EXPOSED FACE
		17.5	SF	RAILING ON APPROACH ENDS
		788.54	SQ FT	RAILING TOTAL

789 SF

Project	Park Drive Bridge over Leslie Run	Calculated By	TVB	Date	04/29/21
Description	ESTIMATED BRIDGE QUANTITIES	Checked By	SJR	Date	01/12/22
		Sheet	32	of	32

ITEM	EXTENSION		UNIT		DESCRIPTION
846	00110		CF		POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM
		20	INCH		WIDTH
		3	INCH		DEPTH
		34	FEET		LENGTH
		2	EACH		PLACES (REAR & FWD APPROACH SLAB)
				29	CF