SHEET NUMBER									PARTICIPATION		ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
·	6-10	11	14	15	16-17	19-22	60-61		01/ENH/ 21/CCEO	02/NFP/ 04/CCEO						
															PAVEMENT	
						1988			1988		301	56000	1988	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
				181		2140			2321		304	20001	2321	CY	AGGREGATE BASE, AS PER PLAN (LIMESTONE)	9
						4187			1365	2822	407	10000	4187	GAL	TACK COAT	
						491			491		411	10000	491	CY	STABILIZED CRUSHED AGGREGATE	
						1672			626	1046	441	50000	1672	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
						1166				1166	441	50200	1166	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448)	
					1	539			539	1	441	50300	539	1 CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (448)	
				154					154		452	10010	154	SY	6" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
				932					932		452	12010	932	SY	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P	
				42					42		609	12000	42	FT	COMBINATION CURB AND GUTTER, TYPE 2	
														2	**TRAFFIC CONTROL**	
							2.91		2.91		618	41000	2 2.91	MILE	RUMBLE STRIPES, EDGE LINE (ASPHALT CONCRETE)	
							3		3		620	00500	3	EACH	DELINEATOR, POST GROUND MOUNTED	
							99		99		621	00100	99	EACH	RPM	
							99		99		621	54000	99	EACH	RAISED PAVEMENT MARKER REMOVED	
							308		308		630	02100	308	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	
							82.8		82.8		630	03100	82.8	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
							181.2		181.2		630	80100	181.2	SF	SIGN, FLAT SHEET	
							17		17		630	85100	17	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
							9		9		630	86010	9	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND REERECTION	
							4		4		630	97700	4	EACH	SIGNING, MISC.: SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON (RRFB) SIGN ASSEMBLY	10
							1.49		1.49		642	00100	1.49	MILE	EDGE LINE, 4", TYPE 1	
							2.84		2.84		642	00104	2.84	MILE	EDGE LINE, 6", TYPE 1	
							2.91		2.91		642	00300	2.91	MILE	CENTER LINE, TYPE 1	
							7478		7478		642	00404	7478	FT	CHANNELIZING LINE, 12", TYPE 1	
							48		48		642	00500	48	FT	STOP LINE, TYPE 1	
							88		88		642	00620	88	FT	CROSSWALK LINE, 12", TYPE 1	
							100		100		642	00630	100	FT	CROSSWALK LINE, 24", TYPE 1	
							2		2		642	01400	2	EACH	WORD ON PAVEMENT, 72", TYPE 1	
							6		6		642	01410	6	EACH	WORD ON PAVEMENT, 96", TYPE 1	
							12		12		642	19000	12	EACH	SHARED LANE MARKING, TYPE 1	
							66		66		642	20802	66	FT	YIELD LINE, TYPE 1	
															MAINTENANCE OF TRAFFIC	
		50							50		410	12000	50	CY	TRAFFIC COMPACTED SURFACE, TYPE A OR B	
		25							25		614	13000	25	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
		24							24		616	10000	24	MGAL	WATER	
															INCIDENTALS	
									LS		103	05000	LS		PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYMENT BOND	
									LS		614	11000	LS		MAINTAINING TRAFFIC	
									LS		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
									LS		624	10000	LS		MOBILIZATION	

ADDENDUM		
1	1-20-25	REVISE QUANTITIES, DESCRIPTION
2	1-21-25	REVISE DESCRIPTION

CALCULATED JGW
CHECKED PRS

GENERAL SUMMARY

COS-CR621-0.00
SHARED USE PATH

F:\2023\22069 COS-CR621-0.00\117099\400-Engineering\Roadway\Sheets\117099_GG002.dgn 1/22/2025 4:04:33 PM SMorr

SHEET NO.	REFERENCE NO.	FROM STATION	TO STATION	SIDE	CODE	SIZE (INCHES)	618 RUMBLE STRIPES, EDGE LINE (ASPHALT CONCRETE)	620 DELINEATOR, POST MOUNTED	621 △2 RPM	621 RAISED PAVEMENT MARKER REMOVED	630 GROUND MOUNTED SUPPORT, NO. 2 POST	630 GROUND MOUNTED SUPPORT, NO. 3 POST	630 SIGN, FLAT SHEET	630 REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	630 REMOVAL OF GROUND MOUNTED POST SUPPORT AND REERECTION	630 SIGNING, MISC.: SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON (RRFB) SIGN ASSEMBLY	642 EDGE LINE, 4", TYPE 1 (WHITE)	642 EDGE LINE, 6", TYPE 1 (WHITE)	642 CENTER LINE, TYPE 1 (BROKEN, SINGLE)	642 CENTER LINE, TYPE 1 (SOLID, DOUBLE)	642 CHANNELIZING LINE, 12", TYPE 1	642 STOP LINE, TYPE 1	642 CROSSWALK LINE, 12", TYPE 1	642 CROSSWALK LINE, 24", TYPE 1	642 WORD ON PAVEMENT, 72", TYPE 1	642 WORD ON PAVEMENT, 96", TYPE 1	642 SHARED LANE MARKING, TYPE 1	642 YIELD LINE, TYPE 1
						IN. X IN.	MILE	EACH	EACH	EACH	FT	FT	SF	EACH	EACH	EACH	MILE	MILE	MILE	MILE	FT	FT	FT	FT	EACH	EACH	EACH	FT
SIGNING (CR621)																											
		EXISTING	PROPOSED																								
62	S-1	106+24.00	106+25.00	LT										1.0	1.0												
63	S-2	117+17.21	117+18.00	RT										2.0	1.0												
66	S-6		145+69.00	RT	W11-15-36	36 X 36						13.8	9.0														
					W16-9P-24	24 X 12							2.0														
66	S-7		146+04.00	RT	R1-5-36	36 X 36					23.0		9.0														
66	B-1		146+40.00	RT												1.0											
66	B-2		146+60.00	LT												1.0											
66	S-8		147+56.00	LT	R1-5-36	36 X 36					23.0		9.0														
66	S-9		147+91.00	LT	W11-15-36	36 X 36						13.8	9.0														
					W16-9P-24	24 X 12							2.0														
67	S-11A	157+70.40	157+20.00	RT										3.0	1.0												
67	S-15	161+67.62	161+65.00	RT										1.0	1.0												
68	S-17	165+31.90	165+32.00	LT										2.0	1.0												
68	S-18	165+31.90	165+32.00	LT										2.0	1.0												
68	S-19	167+91.42	167+90.00	LT										3.0	1.0												
68	S-20	169+60.36	169+60.00	LT										1.0	1.0												
68	S-21	173+39.30	179+38.00	RT										2.0	1.0												
69	S-22		176+94.00	RT	W11-15-36	36 X 36						13.8	9.0														
					W16-9P-24	24 X 12							2.0														
69	S-23		177+29.00	RT	R1-5-36	36 X 36					23.0		9.0														
69	B-3		177+65.00	LT												1.0											
69	B-4		177+85.00	RT												1.0											
69	S-26		178+62.00	LT	R1-5-36	36 X 36					23.0		9.0														
69	S-27		179+02.00	RT	W11-15-36	36 X 36						13.8	9.0														
					W16-9P-24	24 X 12							2.0														
SIGNING (JACKSON STREET)																											
69	S-30		300+75.00	LT	W16-1P-18	18 X 24					10.5		3.0														
69	S-29		300+60.00	RT	R4-11-30	30 x 30					11.0		6.3														
69	S-29A		300+60.00	RT	W16-1P-18	18 X 24					10.5		3.0														
70	S-31		302+60.00	RT	W16-1P-18	18 X 24					10.5		3.0														
70	S-32		302+70.00	LT	W16-1P-18	18 X 24					10.5		3.0														
70	S-36		304+70.00	RT	W16-1P-18	18 X 24					10.5		3.0														
70	S-37		304+80.00	RT	W16-1P-18	18 X 24					10.5		3.0														
71	S-40		305+70.00	RT	W16-1P-18	18 X 24					10.5		3.0														
71	S-41		306+45.00	LT	R4-11-30	30 x 30					11		6.3														
71	S-41A		306+45.00	LT	W16-1P-18	18 X 24					10.5		3.0														
SIGNING (CANAL STEET)																											
71	S-44		400+65.00	RT	R4-11-30	30 x 30					11		6.3														
71	S-44A		400+65.00	RT	W16-1P-18	18 X 24					10.5		3.0														
71	S-45		400+75.00	LT	W16-1P-18	18 X 24					10.5		3.0														
72	S-46		403+10.00	RT	W16-1P-18	18 X 24					10.5		3.0														
72	S-47		403+20.00	RT	R4-11-30	30 x 30					11		6.3														
72	S-47A		403+20.00	RT	W16-1P-18	18 X 24					10.5		3.0														
SIGNING (BROAD STREET)																											
72	S-48		499+19.00	RT	W11-15-36	36 X 36						13.8	9.0														
					W16-9P-24	24 X 12							2.0														
72	S-49		499+54.00	RT	R1-5-36	36 X 36					23.0		9.0														
72	S-50		500+23.00	LT	R1-5-36	36 X 36					23.0		9.0														
72	S-51		500+58.00	LT	W11-15-36	36 X 36						13.8	9.0														
					W16-9P-24	24 X 12							2.0														
SUBTOTALS CARRIED TO SHEET NO. 61											308.0	82.8	181.2	17.0	9.0	4.0											

ADDENDUM

△2	1-21-25	REVISE DESCRIPTION

CALCULATED JGW
CHECKED PRS

TRAFFIC CONTROL SUBSUMMARY

COS-CR621-0.00
SHARED USE PATH

F:\2023\22069 COS-CR621-0.00\117099\400-Engineering\Traffic\Sheets\117099_TS001.dgn 1/22/2025 4:06:07 PM SMorr

SHEET NO.	REFERENCE NO.	FROM STATION	TO STATION	SIDE	CODE	SIZE (INCHES)	618 RUMBLE STRIPES, EDGE LINE (ASPHALT CONCRETE)	620 DELINEATOR, POST MOUNTED	621 △2 RPM	621 RAISED PAVEMENT MARKER REMOVED	630 GROUND MOUNTED SUPPORT, NO. 2 POST	630 GROUND MOUNTED SUPPORT, NO. 3 POST	630 SIGN, FLAT SHEET	630 REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	630 REMOVAL OF GROUND MOUNTED POST SUPPORT AND REERECTION	630 SIGNING, MISC.: SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON (RRFB) SIGN ASSEMBLY	642 EDGE LINE, 4", TYPE 1 (WHITE)	642 EDGE LINE, 6", TYPE 1 (WHITE)	642 CENTER LINE, TYPE 1 (BROKEN, SINGLE)	642 CENTER LINE, TYPE 1 (SOLID, DOUBLE)	642 CHANNELIZING LINE, 12", TYPE 1	642 STOP LINE, TYPE 1	642 CROSSWALK LINE, 12", TYPE 1	642 CROSSWALK LINE, 24", TYPE 1	642 WORD ON PAVEMENT, 72", TYPE 1	642 WORD ON PAVEMENT, 96", TYPE 1	642 SHARED LANE MARKING, TYPE 1	642 YIELD LINE, TYPE 1
						IN. X IN.	MILE	EACH	EACH	EACH	FT	FT	SF	EACH	EACH	EACH	MILE	MILE	MILE	MILE	FT	FT	FT	FT	EACH	EACH	EACH	FT
MARKING (SHARED USE PATH)																											
62		101+60.03	102+83.74																123.71								
62		102+83.74	104+14.92															133.05	133.05		134.00						
62		104+14.92	106+35.93															221.21	221.02		221.02						
62		106+35.93	107+66.32															131.02	130.39		130.39						
62		107+66.32	108+16.32															50.43	50.00		50.00						
62-63		108+16.32	119+95.02															1178.70	1178.70		1178.70						
63-64		119+95.02	122+09.70															219.69	218.26		216.83						
64		122+09.70	127+00.18															490.48	490.48		490.48						
64		127+00.18	130+65.60															368.97	367.96		366.94						
64-65		130+65.60	134+94.00															428.40	428.40		428.40						
65		134+94.00	136+33.63															138.27	138.66		139.05						
65-66		136+33.63	147+08.33															1074.70	1074.70		1074.70						
66-67		147+08.33	158+08.30															1099.97	1099.97		1099.97						
67		158+08.30	161+97.69															385.61	386.69		377.77						
67		161+97.69	164+55.69															257.99	257.99		257.99						
67-68		164+55.69	166+97.80															236.82	238.33		239.84						
68-69		166+97.80	177+36.17															1038.37	1038.37		1038.37						
69		177+36.17	177+69.79															33.12	32.06		32.77						
MARKING (CR 621)																											
62		101+63.16	102+83.74				240.60		2.00	2.00							240.60			123.40							
62		102+83.74	104+14.92				257.46		2.00	2.00							124.60	132.86		128.74							
62		104+14.92	106+36.08				442.04		3.00	3.00							221.02	221.02		220.87							
62		106+36.08	107+66.65				260.78		2.00	2.00							130.39	130.39		130.07							
62		107+66.65	108+16.32				100.00		1.00	1.00							50.00	50.00		50.00							
62-63		108+16.32	119+95.02				2357.40		15.00	15.00							1178.70	1178.70		1178.70							
63-64		119+95.02	122+09.70				425.67		3.00	3.00							209.70	215.97		212.82							
64		122+09.70	127+00.18				980.96		6.00	6.00							490.48	490.48		490.48							
64		127+00.18	130+65.60				728.21		5.00	5.00							361.87	366.34		364.10							
64-65		130+65.60	134+94.00				856.80		5.00	5.00							428.40	428.40		428.40							
65		134+94.00	136+33.63				280.27		2.00	2.00							140.99	139.28		140.14							
65-66		136+33.63	147+08.22				2149.40		13.00	13.00							1074.70	1074.70		1074.59			44.00	50.00		1	11.00
66-67		147+08.22	158+08.30				2199.94		14.00	14.00							1099.97	1099.97		1099.97					1	1	11.00
67		158+08.30	161+97.69				778.78		5.00	5.00							389.39	389.39		389.39							
67		161+97.69	164+55.69				516.00		3.00	3.00							258.00	258.00		258.00							
67-68		164+55.69	166+97.80				488.16		3.00	3.00							247.41	240.75		244.08							
68-69		166+97.80	177+36.17				2076.74		13.00	13.00							1038.37	1038.37		1038.37					1	1	11.00
69		177+36.17	179+35.00				237.66	3.00	2.00	2.00							198.83	38.83		198.83			44.00	50.00		1	11.00
MARKING (AIRPORT ROAD)																											
67			200+54.18	LT																		39.00					
MARKING (JACKSON STREET)																											
69		300+46.50																				8.50					
69		300+65.00	300+75.00																							2	
70		302+60.00	302+70.00																							2	
70		304+70.00	304+70.00																							2	
71		306+35.00	306+45.00																							2	
MARKING (CANAL DRIVE)																											
71		400+65.00	400+75.00	LT																						2	
72		403+10.00	403+20.00	RT																						2	
MARKING (BROAD STREET)																											
72		499+19.00	500+58.00																								
SUBTOTAL THIS SHEET							15376.87	3	99.00	99.00							7883.42	14980.25	7608.74	7770.95	7477.22	47.50	88.00	100.00	2	6	12	66
SUBTOTALS FROM SHEET 60											308.0	82.8	181.2	17.0	9.0	4.0											
SUBTOTAL							15376.87	3	99.00	99.00	308.0	82.8	181.2	17.0	9.0	4.0	7883.42	14980.25	7608.74	7770.95	7477.22	47.50	88.00	100.00	2	6	12	66
CONVERT APPLICABLE ITEMS TO MILES (/5280)							2.91										1.49	2.84	1.44	1.47							
TOTALS CARRIED TO GENERAL SUMMARY							**2.91**	**3**	**99**	**99**	**308**	**82.8**	**181.2**	**17**	**9**	**4**	**1.49**	**2.84**	**1.44**	**1.47**	**7478**	**48**	**88**	**100**	**2**	**6**	**12**	**66**
01/ENH/21/CCEO							**2.91***	**3**	**99***	**99***	**308***	**82.8***	**181.2***	**17***	**9***	**4***	**1.49***	**2.84***	**1.44***	**1.47***	**7478***	**48***	**88***	**100***	**2***	**6***	**12***	**66***

ADDENDUM

△2	1-21-25	REVISE DESCRIPTION

CALCULATED JGW
CHECKED PRS

TRAFFIC CONTROL SUBSUMMARY

COS-CR621-0.00 SHARED USE PATH

F:\2023\22069 COS-CR621-0.00\117099\400-Engineering\Traffic\Sheets\117099_TS001.dgn 1/22/2025 4:06:15 PM SMorr