

PLAN SPLIT	COUNTY	ROUTE	LOG POINT TO LOG POINT		DIRECTION	LENGTH		AVERAGE WIDTH			TYPICAL SECTION NUMBER (SEE TYP SECTION SHEETS)	PAVEMENT AREA	254	255	255	257	441		407	
			MILE	FEET		INDISE SHOULDER	TRAVELED WAY (LANES)	OUTSIDE SHOULDER	PAVEMENT PLANING, ASPHALT CONCRETE (1.5")	FULL DEPTH PAVEMENT REMOVAL AND RIGID REPLACEMENT, TYPE 1, CLASS QCMS			FULL DEPTH PAVEMENT SAWING	DIAMOND GRINDING PORTLAND CEMENT CONCRETE PAVEMENT	ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (449) (PG64-22)	TACK COAT (0.09 GAL/SY)				
			STRAIGHT LINE MILEAGE					FT	FT	FT	SQ YD	SQ YD	SQ YD	FT	SQ YD	IN THICK	CU YD	GAL		
**NO CONCRETE PAVEMENT REPAIR WORK ON BRIDGES. PAVEMENT REPAIR WORK IN LOCATIONS AS DIRECTED BY THE ENGINEER.																				
US 30 EASTBOUND																				
01/NHS/04	CRA	30	0.00	0.32	EB	0.32	1690	4.00	24.00	10.00	1	7,136		428	1446	428				
01/NHS/04	CRA	30	0.32	1.21	EB	0.89	4699	4.00	24.00	15.75	1	22,843		1,371	4626	1,371				
01/NHS/04	CRA	30	1.21	1.30	EB	0.09	475	4.00	24.00	10.00	1	2,006		120	407	120				
01/NHS/04	CRA	30	1.30	1.97	EB	0.67	3538	4.00	24.00	15.75	1	17,199		1,032	3483	1,032				
01/NHS/04	CRA	30	1.97	2.24	EB	0.27	1426	4.00	50.00	10.00	1	10,141		608	2054	608				
01/NHS/04	CRA	30	2.24	2.47	EB	0.23	1214	4.00	24.00	10.00	1	5,126		308	1039	308				
01/NHS/04	CRA	30	2.47	2.76	EB	0.29	1531	4.00	24.00	15.75	1	7,443		447	1508	447				
01/NHS/04	CRA	30	2.76	3.39	EB	0.63	3326	4.00	24.00	10.00	1	14,044		843	2844	843				
01/NHS/04	CRA	30	3.39	3.76	EB	0.37	1954	4.00	38.00	15.75	1	12,539		752	2540	752				
01/NHS/04	CRA	30	3.76	4.07	EB	0.31	1637	4.00	24.00	10.00	1	6,912		415	1400	415				
01/NHS/04	CRA	RAMP A	0.00	0.26	OFF	0.26	1373	3.00	15.75	6.00	3	3,776		227	765	227				
US 30 WESTBOUND																				
01/NHS/04	CRA	30	0.00	0.14	WB	0.14	739	4.00	50.00	10.00	1	5,256		315	1065	315				
01/NHS/04	CRA	30	0.14	0.37	WB	0.23	1214	4.00	24.00	10.00	1	5,126		308	1039	308				
01/NHS/04	CRA	30	0.37	1.23	WB	0.86	4541	4.00	24.00	15.75	1	22,075		1,325	4471	1,325				
01/NHS/04	CRA	30	1.23	1.28	WB	0.05	264	4.00	24.00	10.00	1	1,115		67	226	67				
01/NHS/04	CRA	30	1.28	1.95	WB	0.67	3538	4.00	24.00	15.75	1	17,199		1,032	3483	1,032				
01/NHS/04	CRA	30	1.95	2.21	WB	0.26	1373	4.00	24.00	10.00	1	5,798		348	1175	348				
01/NHS/04	CRA	30	2.21	2.36	WB	0.15	792	4.00	50.00	10.00	1	5,632		338	1141	338				
01/NHS/04	CRA	30	2.36	2.48	WB	0.12	634	4.00	24.00	10.00	1	2,677		161	543	161				
01/NHS/04	CRA	30	2.48	2.77	WB	0.29	1531	4.00	24.00	15.75	1	7,443		447	1508	447				
01/NHS/04	CRA	30	2.77	3.25	WB	0.48	2534	4.00	24.00	10.00	1	10,700		642	2167	642				
01/NHS/04	CRA	30	3.25	3.58	WB	0.33	1742	4.00	38.00	10.00	1	10,065		604	2039	604				
01/NHS/04	CRA	30	3.58	4.01	WB	0.43	2270	4.00	24.00	15.75	1	11,035		662	2235	662				
01/NHS/04	CRA	RAMP B	0.00	0.21	ON	0.21	1109	3.00	15.75	6.00	2	3,050		183	618	183				
EXTRA QUANTITY FOR INTERSECTIONS												4,549	4,549			1.5	190	410		
EASTBOUND MAINLINE QUANTITY SUBTOTAL												105,389		6,323	21,347	6,323				
EASTBOUND RAMP QUANTITY SUBTOTAL												3,776		227	765	227				
WESTBOUND QUANTITY SUBTOTAL												104,121		6,247	21,092	6,247				
WESTBOUND RAMP QUANTITY SUBTOTAL												3,050		183	618	183				
GRAND TOTAL QUANTITY CARRIED TO GENERAL SUMMARY												4,549	12,980	43,822	12,980	190	410			

PAVEMENT AND SHOULDER DATA SHEET

DESIGN AGENCY	DISTRICT 3
ENGINEERING TEAM FOUR	
DESIGNER	JLB
REVIEWER	NRF 05/15/24
PROJECT ID	87724
SHEET TOTAL	P.13 20