REF. NO.	SHEET NUM. 5	7	11	12	20	21	22	25			PART. 01/SAF/PV	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																TRAFFIC SIGNALS CONTINUED	
								6			6	625	32000	6	EACH	GROUND ROD	
								175			175	625	36010	175	FT	UNDERGROUND WARNING/MARKING TAPE	
								12			12	632	05007	12	EACH	VEHICULAR SIGNAL HEAD, (LED), 3-SECTION, 12" LENS, 1-WAY, POLYCARBONATE, AS PER PLAN, BLACK	23
								12			12	632	25000	12	EACH	COVERING OF VEHICULAR SIGNAL HEAD	
								824			824	632	40500	824	FT	SIGNAL CABLE, 5 CONDUCTOR, NO. 14 AWG	
								961			961	632	40700	961	FT	SIGNAL CABLE, 7 CONDUCTOR, NO. 14 AWG	
								4			4	632	64010	4	EACH	SIGNAL SUPPORT FOUNDATION	23
								165			165	632	69300	165	FT	POWER CABLE, 3 CONDUCTOR, NO. 4 AWG	
								1			1	632	70001	1	EACH	POWER SERVICE, AS PER PLAN	23
								3			3	632	77233	3	EACH	SIGNAL SUPPORT, MECHANICAL DAMPER FOR TC-81.21 MAST ARM (GREATER THAN 39' IN LENGTH), AS PER PLAN	22
								1			1	632	80503	1	EACH	SIGNAL SUPPORT, TYPE TC-81.21, DESIGN 11, AS PER PLAN	23
								1			1	632	81001	1	EACH	COMBINATION SIGNAL SUPPORT, TYPE TC-81.21, DESIGN 4, AS PER PLAN	23
								2			2	632	81091	2	EACH	COMBINATION SIGNAL SUPPORT, TYPE TC-81.21, DESIGN 13, AS PER PLAN	23
								1			1	632	90101	1	EACH	REMOVAL OF TRAFFIC SIGNAL INSTALLATION, AS PER PLAN	23
							1				1	632	90400	1	EACH	SIGNALIZATION, MISC.: TEST HOLE PERFORMED	22
								1			1	633	65511	1	EACH	CABINET, TYPE TS-2, AS PER PLAN	23
								1			1	633	67101	1	EACH	CABINET FOUNDATION, AS PER PLAN	23
								1			1	633	67201	1	EACH	CONTROLLER WORK PAD, AS PER PLAN	23
								1			1	633	75001	1	EACH	UNINTERRUPTIBLE POWER SUPPLY (UPS), 1000 WATT, AS PER PLAN	23
								2			2	809	69000	2	EACH	ADVANCE RADAR DETECTION	24
								4			4	809	69100	4	EACH	STOP LINE RADAR DETECTION	23
								1			1	809	69122	1	EACH	ATC V6.24 CONTROLLER, AS PER PLAN	24
								1			1	809	69200	1	EACH	EMERGENCY VEHICLE PREEMPTION	24
								4			4	809	69210	4	EACH	PREEMPT RECEIVING UNIT	24
								876			876	809	69220	876	FT	PREEMPT DETECTOR CABLE	24
								1			1	809	69230	1	EACH	PREEMPT PHASE SELECTOR	24
								4			4	809	69240	4	EACH	PREEMPT CONFIRMATION LIGHT	24
																TRAFFIC CONTROL	
P-6					26	26					52	630	02100	52	FT	GROUND MOUNTED SUPPORT, NO. 2 POST	
P-7			2	2							4	630	85100	4	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
P-7			2	2							4	630	86002	4	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
EL-1					0.08	0.12					0.2	642	00100	0.2	MILE	EDGE LINE, 4", TYPE 1	
LL-1					0.03	0.03					0.06	642	00200	0.06	MILE	LANE LINE, 4", TYPE 1	
DY-1						0.01					0.01	642	00300	0.01	MILE	CENTER LINE, TYPE 1	
CL-1					456	433					889	642	00400	889	FT	CHANNELIZING LINE, 8", TYPE 1	
SL-1					47	59					106	642	00500	106	FT	STOP LINE, TYPE 1	
TL-1					85	93					178	642	00700	178	FT	TRANSVERSE/DIAGONAL LINE, TYPE 1	
CM-1					150	137					287	642	00720	287	FT	CHEVRON MARKING, TYPE 1	
LA-1					5	5					10	642	01300	10	EACH	LANE ARROW, TYPE 1	
																MAINTENANCE OF TRAFFIC	
	64										64	614	11110	64	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
	1										1	SPECIAL	61411300	1	EACH	WORK ZONE TRAFFIC SIGNAL	5
MT-1		2									2	614	12384	2	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (BIDIRECTIONAL)	5
MT-3		20									20	614	13310	20	EACH	BARRIER REFLECTOR, TYPE 1 (BI-DIRECTIONAL)	5
MT-4		18									18	614	13360	18	EACH	OBJECT MARKER, TWO WAY	5
		4									4	614	13600	4	EACH	MAINTENANCE OF TRAFFIC, ONE LANE CLOSURE ON A TWO LANE HIGHWAY	
MT-5		0.78									0.78	614	22200	0.78	MILE	WORK ZONE EDGE LINE, CLASS I, 4", 740.06, TYPE I	
MT-8		101									101	614	23400	101	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 8", 740.06, TYPE I	
MT-6		1050									1050	614	24400	1050	FT	WORK ZONE DOTTED LINE, CLASS I, 4", 740.06, TYPE I	
	0.5										0.5	616	10000	0.5	MGAL	WATER	
MT-7		913									913	622	41100	913	FT	PORTABLE BARRIER, UNANCHORED	
		0.04									0.04	642	30030	0.04	MILE	REMOVAL OF PAVEMENT MARKING	
																INCIDENTALS	
											LS	614	11000	LS		MAINTAINING TRAFFIC	5
											LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LS	624	10000	LS		MOBILIZATION	

CALCULATED SJB
CHECKED CLC

GENERAL SUMMARY

CUY-322-15.59