

SHEET NUM.							PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5		7			01/SAF/OT	02/SAF/OT							
													EROSION CONTROL	
						995	5	832	30000	1,000	EACH	EROSION CONTROL		
													TRAFFIC CONTROL	
			120.74			119.54	1.2	850	10010	120.74	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)		
			17,130			17,130		850	10110	17,130	FT	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)		
			35,015			35,015		850	10130	35,015	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)		
			71.67			71.67		850	20010	71.67	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE)		
			7,040			7,040		850	20110	7,040	FT	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE)		
			28,995			28,995		850	20130	28,995	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (CONCRETE)		
			99.45			98.89	0.56	807	12010	99.45	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, EDGE LINE, 6"		
			92.96			92.32	0.64	807	12110	92.96	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, LANE LINE, 6"		
			54,805			54,805		807	12310	54,805	FT	WET REFLECTIVE EPOXY PAVEMENT MARKING, CHANNELIZING LINE, 12"		
			24,170			24,170		807	12410	24,170	FT	WET REFLECTIVE EPOXY PAVEMENT MARKING, DOTTED LINE, 6"		
			9,205			9,205		807	12430	9,205	FT	WET REFLECTIVE EPOXY PAVEMENT MARKING, DOTTED LINE, 12"		
													MAINTENANCE OF TRAFFIC	
100	200					199	1	614	11110	200	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE		
						99.5	0.5	630	97800	100	SF	SIGNING, MISC.: ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY THE ENGINEER	4	
													INCIDENTALS	
						LS	LS	614	11000	LS		MAINTAINING TRAFFIC		
						LS	LS	624	10000	LS		MOBILIZATION		

GENERAL SUMMARY

DESIGN AGENCY



DESIGNER
FLK

REVIEWER
FLK 07/16/20

PROJECT ID
113633

SHEET TOTAL
P.6 | 10

ROUTE	LOCATION	850	850	850		850	850	850		807	807	807	807	807
		GROOVING FOR 6" RECESSED PAVEMENT MARKING (ASPHALT)	GROOVING FOR 6" RECESSED PAVEMENT MARKING (ASPHALT)	GROOVING FOR 12" RECESSED PAVEMENT MARKING (ASPHALT)		GROOVING FOR 6" RECESSED PAVEMENT MARKING (CONCRETE)	GROOVING FOR 6" RECESSED PAVEMENT MARKING (CONCRETE)	GROOVING FOR 12" RECESSED PAVEMENT MARKING (CONCRETE)		WET REFLECTIVE EPOXY PAVEMENT MARKING, 6" EDGE LINE	WET REFLECTIVE EPOXY PAVEMENT MARKING, 6" LANE LINE	WET REFLECTIVE EPOXY PAVEMENT MARKING, 12" CHANNELIZING LINE	WET REFLECTIVE EPOXY PAVEMENT MARKING, 6" DOTTED LINE	WET REFLECTIVE EPOXY PAVEMENT MARKING, 12" DOTTED LINE
		MILE	FEET	FEET		MILE	FEET	FEET		MILE	MILE	FEET	FEET	FEET
IR-90	E. 162nd St. to SR-2 Split/US-20 Interchange	62.04	9030	19625						30.74	35.38	17335	9030	2290
	Bridge Decks					4.08								
IR-271	Summit/Cuyahoga County Line to Express Lanes End	4.11		2060		64.95	7040	27975		37.36	31.70	25735	7040	4300
IR-480	Lorain/Cuyahoga County Line to Rocky River Bridge	54.59	8100	13330		1.59		1020		31.35	25.88	11735	8100	2615
	Bridge Decks					1.05								
TOTALS		120.74	17130	35015		71.67	7040	28995		99.45	92.96	54805	24170	9205

SUBSUMMARY

DESIGN AGENCY



DESIGNER

FLK

REVIEWER

FLK 07/16/20

PROJECT ID

113633

SHEET

P.7

TOTAL

10