

**STORM WATER POLLUTION PREVENTION PLAN**

THE LOCATION AND TIMING OF ALL EROSION AND SEDIMENT CONTROL ITEMS SHALL BE FIELD ADJUSTED TO PREVENT SIGNIFICANT IMPACTS ON RECEIVING WATERS. IMPLEMENTATION OF THE STORM WATER POLLUTION PREVENTION PLAN SHALL CONTINUE THROUGHOUT THE DURATION OF THE PROJECT OR UNTIL SUCH TIME THAT THE UPSLOPE DISTURBED AREAS ARE STABILIZED.

INSTALLATION OF SEDIMENT BASINS/DAMS, PERIMETER FILTER FABRIC FENCE, AND DITCH CHECKS SHALL BE AS PER CONSTRUCTION AND MATERIAL SPECIFICATION 207.03.

ALL REASONABLE ATTEMPTS SHOULD BE MADE TO MINIMIZE THE TOTAL AREA OF DISTURBED LAND.

AREAS TO REMAIN DORMANT FOR MORE THAN 45 DAYS SHOULD BE IMMEDIATELY STABILIZED WITH CONSTRUCTION SEEDING AND MULCHING, EROSION CONTROL MATTING OR OTHER APPROPRIATE EROSION CONTROL MEASURES.

THE FOLLOWING ITEMS HAVE BEEN CARRIED FORWARD TO THE GENERAL SUMMARY.

- ITEM 832 – STORM WATER POLLUTION PREVENTION PLAN .....**LS**
- ITEM 832 – STORM WATER POLLUTION PREVENTION INSPECTIONS .....**LS**
- ITEM 832 – STORM WATER POLLUTION PREVENTION INSPECTION SOFTWARE.....**LS**

**ITEM SPECIAL – WATER SERVICE CONNECTION CAPPING**

THE CONTRACTOR SHALL COMPLY WITH ALL CITY OF CLEVELAND WATER DEPARTMENT REQUIREMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PERMITS AND PAYMENTS. CONTRACTOR SHALL PROVIDE AN 11 INCH X 17 INCH, 1:10 SCALE DRAWING OF THE PROJECT LOCATION CLEARLY MARKING THE LOCATION AND DEPTH OF THE WATER SERVICE CONNECTION TO THE PROJECT ENGINEER AT THE COMPLETION OF THE PROJECT.

PRIOR TO CAPPING THE SEWER SERVICE CONNECTION, THE LICENSED SEWER BUILDER MUST OBTAIN A SEWER BULKHEAD PERMIT FROM THE CITY OF CLEVELAND – DIVISION OF WATER POLLUTION CONTROL (WPC). PERMITS ARE TO BE SUBMITTED TO WPC.

ADDRESS:  
DIVISION OF WATER POLLUTION CONTROL (WPC)  
12302 KIRBY AVENUE  
CLEVELAND, OH 44108

ANY QUESTIONS FOR THE BULKHEAD WILL BE ANSWERED BY WPC CUSTOMER SERVICE AT 216-664-2513.

ITEM SPECIAL – WATER SERVICE CONNECTION CAPPING .....**LS**

DESIGN AGENCY



DESIGNER  
JRF

REVIEWER  
KD 01-05-23

PROJECT ID  
115830

SHEET	TOTAL
5	7