SHEET NUMBER										PART.	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
OFFICE CALCS		5	6	7	8	9	25	26	30	01 / BRO		EXT	TOTAL			
															TRAFFIC CONTROL	
							0.04	0.2		0.24	644	00104	0.24	MILE	EDGE LINE, 6"	
							0.04	0.2		0.24	644	00300	0.24	MILE	CENTER LINE	
							2			2	644	01300	2	EACH	LANE ARROW	
															STRUCTURE OVER 20 FOOT SPAN (CUY-43-0480)	
									LS	LS	202	11203	LS		PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	28
									LS	LS	503	11101	LS		COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN	28
									500	500	503	21100	500	CY	UNCLASSIFIED EXCAVATION	
									8,036	8,036	509	10000	8,036	LB	EPOXY COATED STEEL REINFORCEMENT	
									100	100	509	20001	100	LB	CONCRETE REINFORCEMENT, REPLACEMENT OF EXISTING CONCRETE REINFORCEMENT, AS PER PLAN	28
									19	19	511	46000	19	SY	CLASS QC1 CONCRETE, RETAINING/WINGWALL NOT INCLUDING FOOTING	
									18	18	511	51510	18	CY	CLASS QC2 CONCRETE, SIDEWALK	
									75	75	512	10100	75	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
									39	39	512	10101	39	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), AS PER PLAN(PERMANENT GRAFFITI PROTECTION)	35
									70	70	512	33000	70	SY	TYPE 2 WATERPROOFING	
									246	246	512	33010	246	SY	TYPE 3 WATERPROOFING	
									50	50	516	13600	50	SF	1" PREFORMED EXPANSION JOINT FILLER	
									70	70	517	74501	70	FT	RAILING, CONCRETE, AS PER PLAN	28
									29	29	518	21050	29	SY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	
									51	51	518	40000	51	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	
									13	13	518	40010	13	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	
									487	487	SPECIAL	53013000	487	SF	FORM LINER	28
									98	98	601	32201	98	CY	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER, AS PER PLAN	28
									60	60	611	70001	60	FT	CONDUIT, TYPE A, PRECAST REINFORCED CONCRETE THREE SIDED FLAT TOPPED CULVERT, AS PER PLAN (30'-0" X 7'-0" RISE)	28
															MAINTENANCE OF TRAFFIC	
					40					40	614	11110	40	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
						8				8	614	12380	8	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL)	
				10						10	614	13000	10	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	
						0.22				0.22	614	21200	0.22	MILE	WORK ZONE CENTER LINE, CLASS I, 740.06, TYPE I	
						1.49				1.49	614	22200	1.49	MILE	WORK ZONE EDGE LINE, CLASS I, 4", 740.06, TYPE I	
						196				196	614	23400	196	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 8", 740.06, TYPE I	
						65				65	614	24400	65	FT	WORK ZONE DOTTED LINE, CLASS I, 4", 740.06, TYPE I	
						20				20	614	26400	20	FT	WORK ZONE STOP LINE, CLASS I, 740.06, TYPE I	
				6						6	614	18601	6	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	7
										LS	615	10000	LS		(1) ROADS FOR MAINTAINING TRAFFIC	
						663				663	615	20000	663	SY	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A	
						1,370				1,370	622	41110	1,370	FT	PORTABLE BARRIER, ANCHORED	
															INCIDENTALS	
				LS						LS	614	11000	LS		MAINTAINING TRAFFIC	
		3								3	619	16011	3	MNTH	FIELD OFFICE, TYPE B, AS PER PLAN	5
			LS							LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
										LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

CUY-43-4.80

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 11/10/2026 TIME: 3:34:33 PM USER: RSpino
pw:\\msg-us-nc-pw.bentley.com:msg-us-nc-pw-01\Documents\Projects\ODOT\117649\400-Engineering\Roadway\Sheets\117649_GG002.dgn

REVISIONS
(1) - DATED 11/10/2026

DESIGN AGENCY
Mannik Smith GROUP

DESIGNER MDF
REVIEWER DRK 07/29/26
PROJECT ID 117649
SHEET 16 TOTAL 46