SHEET NUMBER												PART.		ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
OFFICE CALCS	8	11	13	66	67	68	69	70	84	85		01/NHS			EXT	TOTAL			
																		STRUCTURE REPAIR (GEA-422-2750R)	
										100		100		509	20001	100	LB	CONCRETE REINFORCEMENT, REPLACEMENT OF EXISTING CONCRETE REINFORCEMENT, AS PER PLAN	P.78/204
										189		189		512	10100	189	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
										189		189		512	74000	189	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES	
										422		422		513	10201	422	LB	STRUCTURAL STEEL MEMBERS, LEVEL UF, AS PER PLAN	P.78/204
										104		104		514	20001	104	SF	FIELD PAINTING OF DAMAGED STRUCTURAL STEEL, AS PER PLAN	P.80/204
										6		6		516	46701	6	EACH	RESET BEARING, AS PER PLAN	P.78/204
										LS		LS		516	47001	LS		JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN	P.78/204
										27		27		519	11100	27	SF	PATCHING CONCRETE STRUCTURE	
										2		2		SPECIAL	53000400	2	EACH	STRUCTURES: CLEANING OF BRIDGE SEAT	P.80/204
																		MAINTENANCE OF TRAFFIC	
			750									750		614	11110	750	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
						4	4	3				11		614	12380	11	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL)	
LS												LS		614	12420	LS		DETOUR SIGNING	
						76	78	23				177		614	13310	177	EACH	BARRIER REFLECTOR, TYPE 1, ONE-WAY	
						76	75	21				172		614	13350	172	EACH	OBJECT MARKER, ONE WAY	
		12										12		614	18601	12	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	P.11
								0.44				0.44		614	21100	0.44	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT, YELLOW , DOUBLE SOLID	
						1.85	2.53	3.1				7.48		614	22110	7.48	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT, WHITE	
						1.5	2.13	1.9				5.53		614	22110	5.53	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT, YELLOW	
						2,239	2,675	6,030				10,944		614	23210	10,944	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 12", 642 PAINT	
						2,784	2,433	2,719				7,936		614	24200	7,936	FT	WORK ZONE DOTTED LINE, CLASS I, 4", 642 PAINT	
						1,309	357					1,666		615	25000	1,666	SY	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS B	
												LS		615	10000	LS		ROADS FOR MAINTAINING TRAFFIC	
						3,641	3,552	1,030				8,223		622	41100	8,223	FT	PORTABLE BARRIER, UNANCHORED	
																		INCIDENTALS	
LS												LS		614	11000	LS		MAINTAINING TRAFFIC	
LS												LS		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
LS												LS		624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

CUY/GEA-BH-FY2027 MISC PART 1

MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 7/14/2026 TIME: 3:15:32 PM USER: N.Ballard
G:\DE\Clients\ODOT\10018793 D12 BH\119485\400-Engineering\Roadway\Sheets\119485_GG007.dgn

DESIGN AGENCY
WOOLPERT

DESIGNER
ICB

REVIEWER
MS 09/24/25

PROJECT ID
119485

SHEET P.77 TOTAL 204