

REF. NO.	PHASE	LOCATION	STATION		SIDE	614		614		614		614		614		614		614		614		614		622		644		644		644		644		646		646		646		646				
			FROM	TO		EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH			
PB	1	I.R. 480	441+25	458+45	RT	1	36	36															1720																					
CH	1	I.R. 480	431+70	462+05	RT																																							
CH	1	I.R. 480	431+70	462+05	RT																																							
CH	1	I.R. 480	431+70	462+05	RT																																							
EW	1	I.R. 480	431+70	462+05	RT																																							
EY	1	I.R. 480	431+70	462+05	RT																																							
EW	1	S.R. 10	458+40	473+00	LT																																							
EW	1	S.R. 10	473+92	476+22	LT																																							
EW	2	S.R. 10	450+55	454+22	RT																																							
EW	2	S.R. 10	454+80	471+61	RT																																							
SUBTOTAL																																												
<b>TOTALS CARRIED TO GENERAL SUMMARY</b>						1	36	36	0.58	1.29	4527	4578	1720	0.58	0.25	0.87	0.58	0.46	0.87																									

REVISIONS	NUMBER	DATE	DESCRIPTION
	1	02/06/20	ADDED ITEMS AND REVISED QUANTITIES

1

**MAINTENANCE OF TRAFFIC SUBSUMMARY**

**CUY-480-6.47 / VAR PAINT**

CALCULATED  
KDW  
CHECKED  
TWG

P:\DDT\12\0004\_CUY-480-06.47\_VAR\_Paint\22131\_Design\Roadway\Sheets\22131\_GG002.dgn Sheet 2/6/2020 1:14:04 PM CMT008

SHEET NUM.											PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	CALCULATED ERK	CHECKED TWG
5	6	8	GEN	01/IMS/BR	02/NHS/BR															
																	<b>MAINTENANCE OF TRAFFIC</b>			
					25						25	SPECIAL	51912510	25	SY	PATCHING CONCRETE BRIDGE DECK				
						100					100	614	11110	100	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE				
											1	614	12336	1	EACH	WORK ZONE IMPACT ATTENUATOR (UNIDIRECTIONAL)				
					50						50	614	13000	50	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC				
											36	614	13310	36	EACH	BARRIER REFLECTOR, TYPE I, ONE-WAY				
											36	614	13350	36	EACH	OBJECT MARKER, ONE WAY				
						24					24	614	18601	24	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN			5	
											0.58	614	22110	0.58	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT				
											1.29	614	22210	1.29	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 740.06, TYPE I				
											4,527	614	23210	4,527	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 12", 642 PAINT				
											4,578	614	23410	4,578	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 12", 740.06, TYPE I				
											1,720	622	41000	1,720	FT	PORTABLE BARRIER, 32"				
																	<b>INCIDENTALS</b>			
											LS	LS	614	11000	LS	MAINTAINING TRAFFIC				
									28		LS	LS	619	16020	28	MNTH	FIELD OFFICE, TYPE C			
											LS	LS	624	10000	LS	MOBILIZATION				



REVISIONS	NUMBER	DATE	DESCRIPTION
	1	02/06/20	ADDED ITEMS AND REVISED QUANTITIES

**GENERAL SUMMARY**  
**CUY-480-6.47 / VAR PAINT**