| SHEET NUM. 2 | SHEET NUM. 3 | SHEET NUM. 8 | SHEET NUM. GEN | PART. 01/IMS/BR | ITEM | ITEM EXT | GRAND TOTAL | UNIT | DESCRIPTION | SEE SHEET NO. |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | **ROADWAY** | |
| LS | | | | LS | 201 | 11001 | LS | | CLEARING AND GRUBBING, AS PER PLAN | 2 |
| | 3,000 | | | 3,000 | 607 | 98000 | 3,000 | FT | FENCE, MISC.: CONSTRUCTION FENCE | 3 |
| | | | | | | | | | **EROSION CONTROL** | |
| | | | | 5,000 | 832 | 30000 | 5,000 | EACH | EROSION CONTROL | |
| | | | | | | | | | **PAVEMENT** | |
| 2,540 | | | | 2,540 | 254 | 01000 | 2,540 | SY | PAVEMENT PLANING, ASPHALT CONCRETE, DEPTH = 1 1/2" | |
| 215 | | | | 215 | 407 | 10000 | 215 | GAL | TACK COAT | |
| 105 | | | | 105 | 442 | 20000 | 105 | CY | ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (448), (PG70-22M) | |
| 6,640 | | | | 6,640 | 618 | 40100 | 6,640 | FT | RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE) | |
| | | | | | | | | | **TRAFFIC CONTROL** | |
| | | 0.11 | | 0.11 | 642 | 00300 | 0.11 | MILE | CENTER LINE, TYPE 1 | |
| | | 2.6 | | 2.6 | 644 | 00104 | 2.6 | MILE | EDGE LINE, 6" | |
| | | 3.9 | | 3.9 | 644 | 00204 | 3.9 | MILE | LANE LINE, 6" | |
| | | 990 | | 990 | 644 | 01510 | 990 | FT | DOTTED LINE, 6" | |
| | | 1.02 | | 1.02 | 646 | 10010 | 1.02 | MILE | EDGE LINE, 6" | |
| | | 1.53 | | 1.53 | 646 | 10110 | 1.53 | MILE | LANE LINE, 6" | |
| | | | | | | | | | **STRUCTURE OVER 20 FOOT SPAN (CUY-90-0758)** | |
| | | 342,700 | | 342,700 | 514 | 00050 | 342,700 | SF | SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL | |
| | | 342,700 | | 342,700 | 514 | 00056 | 342,700 | SF | FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT | 3 |
| | | 342,700 | | 342,700 | 514 | 00060 | 342,700 | SF | FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT | 3 |
| | | 342,700 | | 342,700 | 514 | 00066 | 342,700 | SF | FIELD PAINTING STRUCTURAL STEEL, FINISH COAT | 3 |
| | | 1 ~~250~~ | | ~~250~~ | 514 | 00504 | ~~250~~ 1 | MNHR | GRINDING FINS, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL | |
| | | 130 | | 130 | 514 | 10000 | 130 | EACH | FINAL INSPECTION REPAIR | |
| | | | | | | | | | **STRUCTURE OVER 20 FOOT SPAN (CUY-90-1372)** | |
| | | 3,000 | | 3,000 | 513 | 21501 | 3,000 | LB | REPLACEMENT OF DETERIORATED END CROSSFRAMES, AS PER PLAN | 3, 21 |
| | | LS | | LS | 513 | 95020 | LS | | STRUCTURAL STEEL, MISC.: RE-WELD END CROSSFRAME MEMBERS | 3, 21 |
| | | 2 | | 2 | 513 | 95030 | 2 | EACH | STRUCTURAL STEEL, MISC.: REPAIR OF DAMAGED MEMBERS - DRILLING | 21 |
| | | 210,500 | | 210,500 | 514 | 00050 | 210,500 | SF | SURFACE PREPARATION OF EXISTING STRUCTURAL STEEL | |
| | | 210,500 | | 210,500 | 514 | 00056 | 210,500 | SF | FIELD PAINTING OF EXISTING STRUCTURAL STEEL, PRIME COAT | 3 |
| | | 211,000 | | 211,000 | 514 | 00060 | 211,000 | SF | FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT | 3 |
| | | 211,000 | | 211,000 | 514 | 00066 | 211,000 | SF | FIELD PAINTING STRUCTURAL STEEL, FINISH COAT | 3 |
| | | 1 ~~170~~ | | ~~170~~ | 514 | 00504 | ~~170~~ 1 | MNHR | GRINDING FINS, TEARS, SLIVERS ON EXISTING STRUCTURAL STEEL | |
| | | 100 | | 100 | 514 | 10000 | 100 | EACH | FINAL INSPECTION REPAIR | |

| REVISIONS | NUMBER | DATE | DESCRIPTION |
|---|---|---|---|
| | 1 | 9/9/21 | REVISED QUANTITIES |

CALCULATED KDW
CHECKED TWG

# GENERAL SUMMARY

CUY-90-07.58/13.72
PAINT



P:\ODT\12\0012_CUY-90-7.5813.72 Paint\25617\Design\Roadway\Sheets\25617_GG001.dgn Sheet 9/10/2021 8:37:17 AM CMT007