Design Exception Request

CUY-90-6.83

PID: 76779; Request 12

Letting Type: ODOT-Let

Design Designation			
I-90; 6.84-14.94			
Current ADT (2025)	163,000	Td	0
Design Year ADT (2045)	217,000	Design Speed	60
Design Hourly Volume (2045)	21,500	Legal Speed	60
Directional Distribution	58	Design Functional Class	1 - Interstates
Trucks (24hr B&C)	6	Functional Class Area Type	Urban
		NHS Project	Yes



Submitted By:

E-SIGNED by Jim Sima
on 2023-06-01 11:55:42 EST

Jim Sima
(Engineer of Record)

J.S.

Engineer of Record Seal

Approved by:

E-SIGNED by Adam Koenig
on 2023-06-01 13:54:40 EST

Adam Koenig

Approval Date: 3/2/2023

Design Exception Request

CUY-90-6.83

PID: 76779; Request 12

Controlling Criteria Identification			
Section: I-90; 6.84-14.94			
Controlling Criteria	**Standard**	**Existing (a.)**	**Proposed**
Lane Width			
Shoulder Width	10 feet	Varies 4 feet to 6 feet	Varies 4 feet to 6 feet
Horizontal Curve Radius			
Maximum Grade			
SSD (Horizontal & Crest Vertical)			
Pavement Cross Slope			
Superelevation Rate			
Vertical Clearance			
Design Loading Structural Capacity			
(a.) "Existing" may be N/A (i.e. New alignment or new ramp)			

Project Description

Full depth pavement reconstruction of Interstate 90 from the Hilliard Blvd to I-490 in the cities of Rocky River, Lakewood and Cleveland, OH. Project includes full depth ashpalt concrete pavement for mainline I-90, and full depth concrete pavement for service interchange ramps. Project also includes drainage upgrades including replacement of portions of storm sewer trunk line and laterals, signing, pavement marking and ITS upgrades.

Section Description

For Ramp WN, per L&D Volume 1 Figure 303-1, one 10' wide shoulder is required since the ramp is 2 lanes wide from Sta. 138+67 to 148+00.

Proposed Mitigation

none

Support for Deviation (Benefit-cost, R/W, Environmental, Constructability, Coordination with Other Projects, Relationship between any crash patterns and proposed design exception, etc.):

Due to the width of the existing bridge over IR 490 and the associated retaining and wing walls, the existing widths will be maintained.

Does the requested Design Exception location fall within a Safety Integrated Project (SIP) Map Location?

Yes, Red Location

Does the crash analysis (GCAT and CAM Tool) show any patterns that would be adversely impacted by the proposed Design Exception?

No