2LMN

Calculated:	RTF	Date:	8/5/2023	Stage Review Submission:	Final
Checked:	JAH	Date:	8/5/2023	PID/Job No.:	76779
Concurred:	RTF	Date:	8/5/2023	Bridge No.:	CUY-00090-10.620
Back Checked:	JAH	Date:	8/5/2023	SFN:	1808249
Released:	JAH	Date:	8/5/2023		
Project:	CUY-90-6.83 - Part 1				
Subject:	**DETAILED QUANTITIES FOR LUMP SUM ITEMS**				

514	*27800*	*LS*		*FIELD PAINTING, MISC.: COATING SYSTEM REPAIR*
				Only replacing bottom L-angle
		2	EA	Bays
				Determine perimeter of angle
		0.3125	in	Flange Thickness
		4.00	in	Flange Width 1
		4.00	in	Flange Width 2
		16.00	in	Approx perimeter of L4 angles
		1.33	ft	Approx perimeter
		11.33	ft	Length of Angle
		15.11	SF	Surface Area, one item
		31	SF	Area to be painted