



PROJECT LOCATION #1: DEF-15-10.52
LATITUDE 41°19'29" LONGITUDE 84°25'07"



● - PROJECT LOCATION


PROJECT LOCATION #2: HAN-15-22.46 R
LATITUDE 40°59'03" LONGITUDE 83°33'24"



PROJECT LOCATION #3: VAN-224-8.13
LATITUDE 40°51'05" LONGITUDE 84°38'58"

PROJECT LOCATION #4: VAN-224-8.38
LATITUDE 40°51'05" LONGITUDE 84°38'40"

PROJECT LOCATION #5: VAN-224-8.65
LATITUDE 40°51'05" LONGITUDE 84°38'22"



UTILITIES

THERE ARE NO UNDERGROUND UTILITIES SHOWN ON THIS PLAN. THE NATURE OF THE WORK REQUIRED BY THIS PROJECT WILL NOT AFFECT ANY KNOWN UNDERGROUND UTILITIES THAT EXIST UNDER, OR ADJACENT TO, THE WORK AREA.

CLEARING AND GRUBBING

ALTHOUGH THERE ARE NO TREES OR STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE LIMITS OF THE PROJECT, A LUMP SUM QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR ITEM 201, CLEARING AND GRUBBING. ALL PROVISIONS AS SET FORTH IN THE SPECIFICATIONS UNDER THIS ITEM ARE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 201, CLEARING AND GRUBBING.

PERSONAL PROTECTIVE EQUIPMENT (PPE)

THE CONTRACTOR SHALL FOLLOW ALL REQUIREMENTS OF SECTIONS XXIV AND XXXIV OF THE OHIO DEPARTMENT OF TRANSPORTATION SAFETY AND HEALTH STANDARD OPERATING PROCEDURE 220-006(SP) EFFECTIVE: NOVEMBER 1, 2018 (EXCEPT AS AMENDED BELOW) AND ALL SUBSEQUENT UPDATES POSTED AT THE FOLLOWING WEBSITE:

<https://www.transportation.ohio.gov/about-us/policies-and-procedures/procedures/220-006-sp>

AMENDMENTS TO THE REQUIREMENTS OF THIS DOCUMENT ARE:

XXIV. HEAD PROTECTION (HARD HATS)
ALL PERSONS WITHIN THE RIGHT-OF-WAY OF ANY HIGHWAY OR ANY OTHER TYPE OF ROADWAY OR CONSTRUCTION SITE WHO ARE EXPOSED TO EITHER TRAFFIC (VEHICLES USING THE HIGHWAY FOR PURPOSES OF TRAVEL) OR CONSTRUCTION EQUIPMENT WITHIN THE WORK AREA, REGARDLESS OF JOB TYPE, SHALL WEAR APPROPRIATE HEAD PROTECTION. ALL HARD HATS MUST MEET OR EXCEED ANSI Z89.1-2009 TYPE 1, CLASS E-G REQUIREMENTS.

XXXIV. SAFETY APPAREL AND VEST (HIGH VISIBILITY)
ALL PERSONS WITHIN THE RIGHT-OF-WAY OF ANY HIGHWAY OR ANY OTHER TYPE OF ROADWAY OR CONSTRUCTION SITE WHO ARE EXPOSED TO EITHER TRAFFIC (VEHICLES USING THE HIGHWAY FOR PURPOSES OF TRAVEL) OR CONSTRUCTION EQUIPMENT WITHIN THE WORK AREA, REGARDLESS OF JOB TYPE, SHALL WEAR A HIGH-VISIBILITY SAFETY VEST THAT MEETS THE PERFORMANCE CLASS II OR CLASS III REQUIREMENTS OF THE ANSI/ISEA 107-2015 PUBLICATION ENTITLED "AMERICAN NATIONAL STANDARD FOR HIGH-VISIBILITY SAFETY APPAREL AND ACCESSORIES."

WORKERS MAY WEAR AN ANSI CLASS II OR ANSI CLASS III APPROVED RAIN SUIT, JACKET OR OTHER APPAREL WITHOUT A SAFETY VEST OVER IT.

CONTACT INFORMATION

THE CONTRACTOR SHALL NOT BEGIN WORK IN A COUNTY UNTIL CONTACTING THE COUNTY MANAGER AND PROJECT ENGINEER. BELOW IS A CONTACT LIST FOR COUNTY MANAGERS:

DEFIANCE COUNTY

CONTACT	TITLE	OFFICE NUMBER	CELL NUMBER
JASON HOSCHAK	DEPARTMENT MANAGER	(419) 999-6721	-
BRITNNI RIVERS	TRANSPORT MGR3	(419) 999-6722	-
JEFF HOLTSBERRY	TRANSPORT MGR1	(419) 999-6728	-

HANCOCK COUNTY

CONTACT	TITLE	OFFICE NUMBER	CELL NUMBER
DEIDRA MILLER	DEPARTMENT MANAGER	(419) 999-6731	-
TODD NOIROT	TRANSPORT MGR2	(419) 999-6732	-
JAMES HEACOCK	TRANSPORT MGR3	(419) 999-6738	-

VAN WERT COUNTY

CONTACT	TITLE	OFFICE NUMBER	CELL NUMBER
KYLE FIELDS	DEPARTMENT MANAGER	(419) 999-6771	-
BRYAN HOERSTEN	TRANSPORT MGR2	(419) 999-6778	-
PAT MCCONN	TRANSPORT MGR2	(419) 999-6772	-

EXISTING PLANS

EXISTING PLANS MAY BE INSPECTED IN THE ODOT DISTRICT 1 OFFICE IN LIMA, OH. EXISTING PLANS MAY ALSO BE INSPECTED AT THE OFFICE OF CONTRACTS SITE FOR THE PROJECT.

ENVIRONMENTAL COMMITMENTS

NO EQUIPMENT OR MATERIALS CAN BE PLACED PERMANENTLY OR TEMPORARILY BELOW THE ORDINARY HIGH WATER MARK OF BUCKSKIN CREEK AT THE DEF-SR 15-10.52 BRIDGE.

ODOT WILL ACQUIRE ALL NECESSARY WATERWAY PERMITS PRIOR TO THE START OF CONSTRUCTION. CONDITIONS OF THESE PERMITS WILL BE PROVIDED IN THE CONTRACT AS SPECIAL PROVISIONS. ODOT WILL PROVIDE THE WATERWAY PERMITS TO THE CONTRACTOR AT THE PRE-CONSTRUCTION MEETING. THE CONTRACTOR IS RESPONSIBLE FOR FOLLOWING ALL THE SPECIAL PROVISIONS OF THE WATERWAY PERMITS THROUGHOUT THE DURATION OF THE CONTRACT.

EROSION CONTROL

THE QUANTITY BELOW HAS BEEN CARRIED TO THE GENERAL SUMMARY FOR EROSION CONTROL:

ITEM 832 EROSION CONTROL 1000 EACH

ITEM 251 - PARTIAL DEPTH PAVEMENT REPAIR (441)

A QUANTITY OF THIS ITEM SHALL BE PROVIDED FOR USE AS DIRECTED BY THE ENGINEER. THE ITEM SHALL CONSIST OF RE-PAIRING AREAS EXHIBITING SURFACE DETERIORATION ADJACENT TO THE APPROACH SLABS BEING OVERLAI AND PLACING ITEM 441 ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (449), PG64-22. IN ADDITION, THIS ITEM SHALL BE USED TO PROVIDE A SMOOTH TRANSITION INTO THE OVERLAI APPROACH SLABS AS DIRECTED BY THE ENGINEER. FOR PLACEMENT OF ITEM 441, A PG64-22 BINDER IS REQUIRED, AND IT SHALL BE PLACED IN TWO ONE AND HALF INCH LIFT THICKNESS. THE ENGINEER SHALL DETERMINE WHICH ARE TO BE REPAIRED. UNLESS OTHERWISE DIRECTED BY THE ENGINEER, THIS ITEM SHALL BE PERFORMED AFTER THE COMPLETION OF THE ABUTTING APPROACH SLAB OVERLAY WORK.

PAYMENT SHALL BE BASED ON THE ACTUAL NUMBER OF SQUARE YARDS OF SURFACE PAVEMENT REPAIR.

ITEM 253 - PAVEMENT REPAIR

A QUANTITY OF THIS ITEM SHALL BE PROVIDED FOR USE AS DIRECTED BY THE ENGINEER. THIS ITEM SHALL CONSIST OF CUTTING AND REMOVING DETERIORATED PAVEMENT FULL DEPTH ADJACENT TO THE APPROACH SLABS BEING OVERLAI AND PLACING 301 ASPHALT CONCRETE BASE, PG64-22. THE MAXIMUM COMPACTED DEPTH OF ANY ONE LAYER SHALL BE 6 INCHES. THE FULL DEPTH PAVEMENT REPAIRS SHALL HAVE A SURFACE COURSE APPLIED PER THE NOTE AND REQUIREMENTS FOR ITEM 251, PARTIAL DEPTH PAVEMENT REPAIR (441). PAYMENT FOR THE SURFACE COURSE SHALL BE INCLUDED WITH ITEM 251. UNLESS OTHERWISE DIRECTED BY THE ENGINEER, THIS ITEM SHALL BE PERFORMED AFTER THE COMPLETION OF THE ABUTTING APPROACH SLAB OVERLAY WORK.

PAYMENT SHALL BE BASED ON THE ACTUAL NUMBER OF CUBIC YARDS OF PAVEMENT REPAIR.

ENVIRONMENTAL COMMITMENT

AN ASBESTOS SURVEY OF THE HAN-SR 15-22.46 SFN:3200698 LOCATION, SCHEDULED FOR RENOVATION, WAS CONDUCTED BY A CERTIFIED ASBESTOS HAZARD EVALUATION SPECIALIST. THE SURVEY DETERMINED 160 SF OF NON-FRIABLE REGULATED ASBESTOS-CONTAINING MATERIALS IS PRESENT ON THE STRUCTURE WHICH IS IN EXCESS OF THE ALLOWABLE REGULATORY LIMITS AND REQUIRES ABATEMENT. THE QUANTITIES AND LOCATIONS OF THE REGULATED ASBESTOS-CONTAINING MATERIALS ARE PRESENTED WITHIN THE ASBESTOS SURVEY REPORT INCLUDED IN THE SPECIAL PROVISIONS ATTACHED TO THE PLANS. THE CONTRACTOR SHALL ENSURE THE ABATEMENT, TRANSPORT, AND DISPOSAL OF ASBESTOS CONTAINING MATERIAL IS CONDUCTED IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS. THE CONTRACTOR SHALL ENSURE THAT ALL DOCUMENTATION RELATED TO THE ABATEMENT, TRANSPORT, AND DISPOSAL OF ASBESTOS CONTAINING MATERIALS IS SUBMITTED TO THE PROJECT ENGINEER FOR RECORD KEEPING WITHIN TWO WEEKS OF COMPLETION.

A COPY OF THE OHIO ENVIRONMENTAL PROTECTION AGENCY (OPEA) NOTIFICATION OF DEMOLITION AND RENOVATION FORMS, PARTIALLY COMPLETED BY THE BRIDGE OWNER, HAS BEEN INCLUDED AT THE END OF THE ASBESTOS SURVEY REPORT IN THE SPECIAL PROVISIONS. THE CONTRACTOR SHALL COMPLETE AND SIGN THE FORMS AND SUBMIT THEM TO:

OHIO EPA, DAPC ASBESTOS
50 W. TOWN STREET, 7th FLOOR OR P.O. BOX 1049
COLUMBUS, OH 43216-1049

OR SUBMIT THE FORMS ELECTRONICALLY (ELECTRONIC SUBMISSION INSTRUCTIONS PROVIDED ON THE FORMS), AT LEAST 10 WORKING DAYS PRIOR TO THE START OF ANY RENOVATION WORK. THE CONTRACTOR SHALL PROVIDE A COPY OF THE COMPLETED AND SIGNED FORMS TO THE ENGINEER. INFORMATION REQUIRED ON THE FORMS SHALL INCLUDE AT A MINIMUM: 1) THE ODOT PROJECT NUMBER, 2) THE CONTRACTOR'S NAME, ADDRESS, AND TELEPHONE NUMBER, 3) THE SCHEDULED DATES FOR THE START AND COMPLETION OF BRIDGE RENOVATIONS.

BASIS FOR PAYMENT: THE CONTRACTOR SHALL FURNISH ALL FEES, LABOR, AND MATERIAL NECESSARY TO COMPLETE AND SUBMIT THE OPEA NOTIFICATION OF DEMOLITION AND RENOVATION FORMS. PAYMENTS FOR THIS WORK SHALL BE INCIDENTAL TO THE ITEM 202 STRUCTURE REMOVAL ITEM(S) IN THE PLAN.

GENERAL NOTES

DESIGNER
CRS

REVIEWER

XXX MM-DD-YR

PROJECT ID

113342

SHEET

TOTAL

P.3

17

ITEM 614 MAINTAINING TRAFFIC

A MINIMUM OF 1 LANE OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES BY USE OF THE EXISTING PAVEMENT OR THE COMPLETED PAVEMENT.

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH C&MS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

NOTIFICATION OF TRAFFIC RESTRICTIONS

THROUGHOUT THE DURATION OF THE PROJECT, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITTEN NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO ALLOW THE PROJECT ENGINEER TO MEET THE REQUIRED TIME FRAMES SET FORTH IN THE TABLE BELOW TO INFORM THE SPECIAL HAULING PERMITS SECTION (HAULING.PERMITS@DOT.OHIO.GOV) AND THE DISTRICT PUBLIC INFORMATION OFFICE (PIO). THIS NOTIFICATION SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE BOARDS.

INFORMATION SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL CONSTRUCTION ACTIVITIES THAT IMPACT OR INTERFERE WITH TRAFFIC AND SHALL LIST THE SPECIFIC LOCATION, TYPE OF WORK, ROAD STATUS, DATE AND TIME OF RESTRICTION, DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, NUMBER OF LANES CLOSED, MINIMUM VERTICAL CLEARANCE, MINIMUM WIDTH OF DRIVABLE PAVEMENT, DETOUR ROUTES, IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

NOTIFICATION OF TRAFFIC RESTRICTIONS TIME TABLE		
ITEM	DURATION OF CLOSURE	NOTICE DUE TO PERMITS & PIO
RAMP & ROAD CLOSURES	>= 2 WEEKS	21 CALENDAR DAYS PRIOR TO CLOSURE
	> 12 HOURS & < 2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOSURE
	< 12 HOURS	4 BUSINESS DAYS PRIOR TO CLOSURE
LANE CLOSURES AND RESTRICTIONS	>= 2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOSURE
	< 2 WEEKS	5 BUSINESS DAYS PRIOR TO CLOSURE
START OF CONSTRUCTION & TRAFFIC PATTERN CHANGES	N/A	14 CALENDAR DAYS PRIOR TO IMPLEMENTATION

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTIFICATION TIME TABLE.

ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE DURING CONSTRUCTION OPERATIONS

USE OF LAW ENFORCEMENT OFFICERS (LEOS) BY CONTRACTORS OTHER THAN THE USES SPECIFIED BELOW WILL NOT BE PERMITTED AT PROJECT COST. LEOS SHOULD NOT BE USED WHERE THE OMUTCD INTENDS THAT FLAGGERS BE USED.

IN ADDITION TO THE REQUIREMENTS OF C&MS 614 AND THE OMUTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHALL BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS:

DURING THE ENTIRE ADVANCE PREPARATION AND CLOSURE SEQUENCE WHERE COMPLETE BLOCKAGE OF TRAFFIC IS REQUIRED.

IN ADDITION TO THE REQUIREMENT OF C&MS 614 AND THE OMUTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHOULD BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS AS APPROVED BY THE ENGINEER:

FOR LANE CLOSURES: DURING INITIAL SET-UP PERIODS, TEAR DOWN PERIODS, SUBSTANTIAL SHIFTS OF A CLOSURE POINT OR WHEN NEW LANE CLOSURE ARRANGEMENTS ARE INITIATED FOR LONG-TERM LANE CLOSURES/SHIFTS (FOR THE FIRST AND LAST DAY OF MAJOR CHANGES IN TRAFFIC CONTROL SETUP).

FOR OPERATIONS WITHOUT POSITIVE PROTECTION OCCURRING WITHIN 10 FEET OF AN OPEN TRAVELED LANE THAT MEET ALL OF THE FOLLOWING CRITERIA:

ON A MULTI-LANE DIVIDED INTERSTATE, OTHER FREEWAY OR EXPRESSWAY; AND AN AUTHORIZED SPEED LIMIT OF 45 MPH OR GREATER THAT IS IN EFFECT AT THE TIME OF THE OPERATION; AND, AADT OF 50,000 (OR AADT OF 30,000 WITH 25% OR HIGHER PERCENT TRUCKS)

"WITHOUT POSITIVE PROTECTION" MEANS USE OF DRUMS, CONES, SHADOW VEHICLE, ETC, WITHOUT PROTECTION FROM PORTABLE BARRIER OR OTHER RIGID BARRIER ALONG THE WORK AREA. THIS PHRASE DOES NOT APPLY TO CASES WHERE POSITIVE PROTECTION IS REQUIRED. MOBILE OPERATIONS ARE REGARDED AS "WITHOUT POSITIVE PROTECTION". FOR WORK ZONES USING A COMBINATION OF BARRIER AND TEMPORARY TRAFFIC CONTROL DEVICES (CONES, DRUMS, ETC), THE DESIGNATION SHALL BE BASED UPON THE TYPE OF DEVICES USED IN THE AREA THAT WORKERS ARE LOCATED.

IF MULTIPLE ACTIVE LOCALIZED QUALIFYING WORK AREAS OCCUR WITHOUT POSITIVE PROTECTION, PER MAINLINE TRAFFIC DIRECTION, PROVIDE A UNIFORMED LEO AND OFFICIAL PATROL CAR IN ADVANCE OF:

THE FIRST ACTIVE WORK AREA THAT DRIVERS WILL ENCOUNTER; OR THE ACTIVE WORK AREA LATERALLY CLOSEST TO THE OPEN TRAVELED LANE; OR OTHER LOCATION AS APPROVED BY THE ENGINEER. THE UNIFORMED LEO AND OFFICIAL PATROL CAR MAY RELOCATE AMONG THE LISTED LOCATIONS AS APPROPRIATE AS THE OPERATIONS PROCEED IN THE LOCALIZED QUALIFYING WORK AREAS.

IN GENERAL, LEOS SHOULD BE POSITIONED IN ADVANCE OF AND ON THE SAME SIDE AS THE LANE RESTRICTION (OR AT THE POINT OF ROAD CLOSURE), AND TO MANUALLY CONTROL TRAFFIC MOVEMENTS THROUGH SIGNALIZED INTERSECTIONS IN WORK ZONES.

LEOS SHOULD NOT FORGO THEIR TRAFFIC CONTROL RESPONSIBILITIES TO APPREHEND MOTORISTS FOR ROUTINE TRAFFIC VIOLATIONS. HOWEVER, IF A MOTORIST'S ACTIONS ARE CONSIDERED TO BE RECKLESS, THEN PURSUIT OF THE MOTORIST IS APPROPRIATE.

THE LEOS WORK AT THE DIRECTION OF THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR SECURING THE SERVICES OF THE LEOS WITH THE APPROPRIATE AGENCIES AND COMMUNICATING THE INTENTIONS OF THE PLANS WITH RESPECT TO DUTIES OF THE LEOS. THE ENGINEER SHALL HAVE FINAL CONTROL OVER THE LEOS' DUTIES AND PLACEMENT, AND WILL RESOLVE ANY ISSUES THAT MAY ARISE BETWEEN THE TWO PARTIES.

ENSURE PROVIDED LEOS HAVE BEEN TRAINED APPROPRIATE TO THE JOB DECISIONS THEY ARE REQUIRED TO MAKE WHILE ON THE PROJECT, IN ACCORDANCE WITH C&MS 614.03.

THE LEO SHALL REPORT IN TO THE CONTRACTOR PRIOR TO THE START OF THE SHIFT, IN ORDER TO RECEIVE INSTRUCTIONS REGARDING SPECIFIC WORK ASSIGNMENTS DURING HIS/HER SHIFT. THE LEO IS EXPECTED TO STAY AT THE PROJECT SITE FOR THE ENTIRE DURATION OF HIS/HER SHIFT. THE LEO SHALL REPORT TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT. SHOULD IT BE NECESSARY TO LEAVE THE PROJECT SITE, THE LEO SHALL NOTIFY THE ENGINEER. THE CONTRACTOR SHALL PROVIDE THE LEO WITH A TWO-WAY COMMUNICATION DEVICE THAT SHALL BE RETURNED TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT.

LEOS (WITH PATROL CAR) REQUIRED BY THE TRAFFIC MAINTENANCE TASKS ABOVE SHALL BE PAID FOR ON A UNIT PRICE (HOURLY) BASIS UNDER ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE 15 HOURS

THE HOURS PAID SHALL INCLUDE ANY MINIMUM SHOW-UP TIME REQUIRED BY THE LAW ENFORCEMENT AGENCY INVOLVED.

ANY ADDITIONAL COSTS (ADMINISTRATIVE OR OTHERWISE) INCURRED BY THE CONTRACTOR TO OBTAIN THE SERVICES OF A LEO ARE INCLUDED WITH THE BID UNIT PRICE FOR ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE.

ITEM 614 - WORK ZONE PAVEMENT MARKING

WORK ZONE PAVEMENT MARKING SHALL BE COMPLETE AND IN PLACE ON ALL NEW PAVEMENT PRIOR TO EXPOSING IT TO TRAFFIC. THE FOLLOWING ESTIMATED QUANTITY FOR THIS ITEM HAS BEEN PROVIDED FOR USE AS DIRECTED BY THE ENGINEER.

ITEM 614 - WORK ZONE CENTER LINE, CLASS II = 0.80 MILE**DUST CONTROL**

THE CONTRACTOR SHALL FURNISH AND APPLY WATER FOR DUST CONTROL AS DIRECTED BY THE ENGINEER. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED FOR DUST CONTROL PURPOSES:

ITEM 616, WATER = 6 MGAL

ITEM 614, PORTABLE CHANGEABLE MESSAGE SIGNS, AS PER PLAN

THE CONTRACTOR SHALL FURNISH, INSTALL, MAINTAIN AND REMOVE, WHEN NO LONGER NEEDED, A CHANGEABLE MESSAGE SIGN. THE SIGN SHALL BE OF A TYPE SHOWN ON A LIST OF APPROVED PCMS UNITS AVAILABLE ON THE OFFICE OF MATERIALS MANAGEMENT WEB PAGE. THE LIST CONTAINS CLASS A AND B UNITS WITH MINIMUM LEGIBILITY DISTANCES OF 800 FEET AND 650 FEET, RESPECTIVELY.

EACH SIGN SHALL BE TRAILER-MOUNTED AND EQUIPPED WITH A FUNCTIONAL DIMMING MECHANISM, TO DIM THE SIGN DURING DARKNESS, AND A TAMPER AND VANDAL PROOF ENCLOSURE. EACH SIGN SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE ON-SITE PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT. THE SIGN SHALL ALSO BE CAPABLE OF BEING POWERED BY AN ELECTRICAL SERVICE DROP FROM A LOCAL UTILITY COMPANY. THE PCMS SHALL BE DELINEATED IN ACCORDANCE WITH C&MS 614.03.

PLACEMENT, OPERATION, MAINTENANCE AND ALL ACTIVATION OF THE SIGNS BY THE CONTRACTOR SHALL BE AS DIRECTED BY THE ENGINEER. THE PCMS SHALL BE LOCATED IN A HIGHLY VISIBLE POSITION YET PROTECTED FROM TRAFFIC. THE CONTRACTOR SHALL, AT THE DIRECTION OF THE ENGINEER, RELOCATE THE PCMS TO IMPROVE VISIBILITY OR ACCOMMODATE CHANGED CONDITIONS. WHEN NOT IN USE, THE PCMS SHALL BE TURNED OFF. ADDITIONALLY, WHEN NOT IN USE FOR EXTENDED PERIODS OF TIME, THE PCMS SHALL BE TURNED AWAY FROM ALL TRAFFIC.

THE ENGINEER SHALL BE PROVIDED ACCESS TO EACH SIGN UNIT AND SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE ODOT PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT, AND TO REVISE SIGN MESSAGES, IF NECESSARY.

ALL MESSAGES TO BE DISPLAYED ON THE SIGN WILL BE PROVIDED BY THE ENGINEER. A LIST OF ALL REQUIRED PRE-PROGRAMMED MESSAGES WILL BE GIVEN TO THE CONTRACTOR AT THE PROJECT PRECONSTRUCTION CONFERENCE. THE SIGN SHALL HAVE THE CAPABILITY TO STORE UP TO 99 MESSAGES. MESSAGE MEMORY OR PRE-PROGRAMMED DISPLAYS SHALL NOT BE LOST AS A RESULT OF POWER FAILURES TO THE ON-BOARD COMPUTER. THE SIGN LEGEND SHALL BE CAPABLE OF BEING CHANGED IN THE FIELD. THREE-LINE PRESENTATION FORMATS WITH UP TO SIX MESSAGE PHASES SHALL BE SUPPORTED. PCMS FORMAT SHALL PERMIT THE COMPLETE MESSAGE FOR EACH PHASE TO BE READ AT LEAST TWICE.

THE PCMS SHALL CONTAIN AN ACCURATE CLOCK AND PROGRAMMING LOGIC WHICH WILL ALLOW THE SIGN TO BE ACTIVATED, DEACTIVATED OR MESSAGES CHANGED AUTOMATICALLY AT DIFFERENT TIMES OF THE DAY FOR DIFFERENT DAYS OF THE WEEK.



DESIGNER
CRS

REVIEWER

XXX MM-DD-YR

PROJECT ID

113342

SHEET TOTAL

P.4 17

ALLOW REMOTE SIGN ACTIVATION, MESSAGE CHANGES, MESSAGE ADDITIONS AND REVISIONS TO TIME OF DAY PROGRAMS. THE SYSTEM SHALL ALSO PERMIT VERIFICATION OF CURRENT AND PROGRAMMED MESSAGES. THE PCMS UNIT SHALL BE MAINTAINED IN GOOD WORKING ORDER BY THE CONTRACTOR IN ACCORDANCE WITH THE PROVISIONS OF C&MS 614.07. THE CONTRACTOR SHALL, PRIOR TO ACTIVATING THE UNIT, MAKE ARRANGEMENTS, WITH AN AUTHORIZED SERVICE AGENT FOR THE PCMS, TO ASSURE PROMPT SERVICE IN THE EVENT OF FAILURE. ANY FAILURE SHALL NOT RESULT IN THE SIGN BEING OUT OF SERVICE FOR MORE THAN 12 HOURS, INCLUDING WEEKENDS. FAILURE TO COMPLY MAY RESULT IN AN ORDER TO STOP WORK AND OPEN ALL TRAFFIC LANES AND/OR IN THE DEPARTMENT TAKING APPROPRIATE ACTION TO SAFELY CONTROL TRAFFIC. THE ENTIRE COST TO CONTROL TRAFFIC, ACCRUED BY THE DEPARTMENT DUE TO THE CONTRACTOR'S NONCOMPLIANCE, WILL BE DEDUCTED FROM MONEYS DUE, OR TO BECOME DUE THE CONTRACTOR ON HIS CONTRACT.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR 24-HOUR-PER-DAY OPERATION AND MAINTENANCE OF THESE SIGNS ON THE PROJECT FOR THE DURATION OF THE PHASES WHEN THE PLAN REQUIRES THEIR USE.

PAYMENT FOR THE ABOVE DESCRIBED ITEM SHALL BE AT THE CONTRACT UNIT PRICE. PAYMENT SHALL INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, FUELS, LUBRICATING OILS, SOFTWARE, HARDWARE AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK.

ITEM 614, PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN 4 SIGN MONTHS (ASSUMING 2 PCMS SIGN(S) FOR 2 MONTH(S))

ITEM 614, MAINTAINING TRAFFIC (LANES OPEN DURING HOLIDAYS OR SPECIAL EVENTS)

NO WORK SHALL BE PERFORMED ON SR-15 AND ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR SPECIAL EVENTS:

NEW YEAR'S GENERAL/REGULAR ELECTION DAY (NOV)

THANKSGIVING CHRISTMAS

MEMORIAL DAY FOURTH OF JULY

LABOR DAY

THE PERIOD OF TIME THAT THE LANES ARE TO BE OPEN DEPENDS ON THE DAY OF THE WEEK ON WHICH THE HOLIDAY OR SPECIAL EVENT FALLS. THE FOLLOWING SCHEDULE SHALL BE USED TO DETERMINE THIS PERIOD:

DAY OF HOLIDAY OR SPECIAL EVENT	TIME ALL LANES MUST BE OPEN TO TRAFFIC
SUNDAY	12:00N FRIDAY THROUGH 6:00 AM MONDAY
MONDAY	12:00N FRIDAY THROUGH 6:00 AM TUESDAY
TUESDAY	12:00N MONDAY THROUGH 6:00 AM WEDNESDAY
TUESDAY (GEN./REG. ELECTION)	5:00 AM TUESDAY THROUGH 12:00 AM WEDNESDAY
WEDNESDAY	12:00N TUESDAY THROUGH 6:00 AM THURSDAY
THURSDAY	12:00N WEDNESDAY THROUGH 6:00 AM FRIDAY
THURSDAY (THANKSGIVING ONLY)	6:00 AM WEDNESDAY THROUGH 6:00 AM MONDAY
FRIDAY	12:00N THURSDAY THROUGH 6:00 AM MONDAY
SATURDAY	12:00N FRIDAY THROUGH 6:00 AM MONDAY

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS, THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE PER THE LANE VALUE CONTRACT (PN 127).

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH C&MS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

ITEM 614, WORK ZONE SPEED LIMIT SIGN

THE FOLLOWING WORK ZONE SPEED ZONE (WZSZ) SPEED LIMIT REVISION(S) HAVE BEEN APPROVED FOR USE ON THIS PROJECT WHEN WORK ZONE CONDITIONS AND FACTORS ARE MET AS DESCRIBED BELOW:

WZSZ REVISION NUMBER(S) COUNTY-ROUTE-SECTION(S) DIRECTION(S)

WZ- HAN-15-22.46R

POTENTIAL WZSZ LOCATIONS SHALL HAVE AN ORIGINAL (PRE-CONSTRUCTION) POSTED SPEED LIMIT OF 55 MPH OR GREATER, A QUALIFYING WORK ZONE CONDITION OF AT LEAST 0.5 MILE IN LENGTH, AN EXPECTED WORK DURATION OF AT LEAST THREE HOURS, AND A WORK ZONE CONDITION IN PLACE THAT REDUCES THE EXISTING FUNCTIONALITY OF THE TRAVEL LANES OR SHOULDERS (I.E., LANE CLOSURE, LANE SHIFT, CROSSOVER, CONTRAFLOW AND/OR SHOULDER CLOSURE). THE LENGTH OF THE WORK ZONE CONDITION IS MEASURED FROM THE BEGINNING OF THE TAPER FOR THE SUBJECT WORK ZONE CONDITION IMPACTING THE TRAVEL LANES AND/OR SHOULDER TO THE END OF THE DOWNSTREAM TAPER, WHERE DRIVERS ARE RETURNED TO TYPICAL ALIGNMENT. AN EXPECTED WORK DURATION OF AT LEAST THREE HOURS IS REQUIRED TO BALANCE THE ADDITIONAL EXPOSURE CREATED BY INSTALLING AND REMOVING WZSZ SIGNING WITH THE TIME NEEDED TO COMPLETE THE WORK.

IF THE WORK ZONE MEETS THESE MINIMUM CRITERIA, IT SHALL BE ANALYZED FURTHER USING TABLE 1 BELOW TO DETERMINE IF AND WHEN IT QUALIFIES FOR A SPEED LIMIT REDUCTION. DEPENDING ON THE ORIGINAL POSTED SPEED LIMIT, THE TYPE OF TEMPORARY TRAFFIC CONTROL USED, AND WHETHER OR NOT WORKERS ARE PRESENT, A WARRANTED WZSZ WILL VARY IN THE APPROVED SPEED LIMIT TO BE POSTED OVER TIME.

C&MS ITEM 614, PARAGRAPH 614.02(B), INDICATES THAT TWO DIRECTIONS OF A DIVIDED HIGHWAY ARE CONSIDERED SEPARATE HIGHWAY SECTIONS. THEREFORE, IF THE WORK ON A MULTI-LANE DIVIDED HIGHWAY IS LIMITED TO ONLY ONE DIRECTION, A SPEED LIMIT REDUCTION IN THE DIRECTION OF THE WORK DOES NOT AUTOMATICALLY CONSTITUTE A SPEED LIMIT REDUCTION IN THE OPPOSITE DIRECTION. EACH DIRECTION SHALL BE ANALYZED INDEPENDENTLY FROM EACH OTHER.

ALL WZSzs FLUCTUATE BETWEEN TWO APPROVED REDUCED SPEED LIMITS OR BETWEEN AN APPROVED REDUCED SPEED LIMIT AND THE ORIGINAL POSTED SPEED LIMIT. ONLY ONE OF TWO SIGNING STRATEGIES SHALL BE USED TO IMPLEMENT A WZSZ.

WZSzs USING DSL SIGN ASSEMBLIES SHALL BE IN ACCORDANCE WITH THIS NOTE, APPROVED LIST, SUPPLEMENTAL SPECIFICATIONS (SS) 808 AND 908, AND TRAFFIC SCD MT-104.10.

ONLY ONE WARRANTED SPEED LIMIT APPLIES AT ANY ONE TIME; SPEED LIMIT REDUCTIONS ARE NOT CUMULATIVE. WZSzs SHALL NOT BE USED FOR MOVING/MOBILE ACTIVITIES, AS DEFINED IN OMUTCD PART 6.

WHEN LOOKING UP THE WARRANTED WORK ZONE SPEED LIMITS, ALWAYS USE THE ORIGINAL, PRECONSTRUCTION, POSTED SPEED LIMIT. DO NOT USE A PRIOR OR CURRENT WORK ZONE SPEED LIMIT AS A LOOK UP VALUE IN THE TABLE. POSITIVE PROTECTION IS GENERALLY REGARDED AS PORTABLE BARRIER OR OTHER RIGID BARRIER IN USE ALONG THE WORK AREA WITHIN THE SUBJECT WARRANTED WORK ZONE CONDITION. WITHOUT POSITIVE PROTECTION IS GENERALLY REGARDED AS USING DRUMS, CONES, SHADOW VEHICLE, ETC., ALONG THE WORK AREA WITHIN THE SUBJECT WARRANTED WORK ZONE CONDITION. WORKERS ARE CONSIDERED AS BEING PRESENT WHEN ON-SITE, WORKING WITHIN THE SUBJECT WARRANTED WORK ZONE CONDITION. WHEN THE WORK ZONE CONDITION REDUCING THE EXISTING FUNCTIONALITY OF THE TRAVEL LANES OR SHOULDERS IS REMOVED, THE SPEED LIMIT DISPLAYED SHALL RETURN TO THE ORIGINAL POSTED SPEED LIMIT.


TABLE 1: WARRANTED WORK ZONE SPEED LIMITS (MPH) FOR WORK ZONES ON HIGH-SPEED (55 MPH OR GREATER) MULTI-LANE HIGHWAYS

ORIGINAL POSTED SPEED LIMIT	WITH POSITIVE PROTECTION WORKERS PRESENT	WITH POSITIVE PROTECTION WORKERS NOT PRESENT	WITHOUT POSITIVE PROTECTION WORKERS PRESENT	WITHOUT POSITIVE PROTECTION WORKERS NOT PRESENT
65	55	60	50	60

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 808, DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY 4 SNMT

ESTIMATING 2 DSL SIGN ASSEMBLIES FOR 2 MONTHS



DESIGNER
CRS

REVIEWER

XXX MM-DD-Y

PROJECT ID

113342

SHEET

TOTAL

P.5 17

ITEM 622 PORTABLE BARRIER, UNANCHORED

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AT HAN-15-22.46 R LOCATION AS DIRECTED BY THE ENGINEER AND THE STANDARD CONSTRUCTION DRAWINGS.

ITEM 614, WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL) = 2 EACH
ITEM 622, PORTABLE BARRIER, UNANCHORED = 1,056 FT

WORK ZONE MARKINGS AND SIGNS

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AT LOCATIONS IDENTIFIED BY THE ENGINEER FOR WORK ZONE PAVEMENT MARKINGS AND SIGNS PER THE REQUIREMENTS OF C&MS 614.04 AND 614.11.

ITEM 614, WORK ZONE EDGE LINE, CLASS I, 6", 873, TYPE I = 2.25 MILE

ITEM 614, WORK ZONE DOTTED LINE, CLASS I, 6", 873, TYPE I = 2,860 FT

REMOVAL OF PAVEMENT MARKINGS

AS PER C&MS SECTION 614.11.G., THE CONTRACTOR SHALL REMOVE AND COVER CONFLICTING PAVEMENT MARKINGS WITHIN THE WORK ZONES. THE CONTRACTOR SHALL COVER CONFLICTING MARKINGS PER C&MS 614.11.G.1.b. USING REMOVABLE BLACKOUT TAPE TO THE SATISFACTION OF THE PROJECT ENGINEER. PAYMENT TO REMOVE/ COVER CONFLICTING MARKINGS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC.

DELINEATION OF PORTABLE AND PERMANENT BARRIER

BARRIER REFLECTORS AND OBJECT MARKERS SHALL BE INSTALLED ON ALL PORTABLE BARRIER (PB) USED FOR TRAFFIC CONTROL; AND, ON PERMANENT CONCRETE BARRIER (INCLUDING BRIDGE PARAPETS) LOCATED WITHIN 5 FEET OF THE EDGE OF THE ADJACENT TRAVEL LANE.

BARRIER REFLECTORS SHALL CONFORM TO C&MS 626, EXCEPT THAT THE SPACING SHALL BE AS PER TRAFFIC SCD MT-101.70. OBJECT MARKERS AND THEIR INSTALLATION SHALL CONFORM TO C&MS 614.03 AND SCD MT-101.70. WHEN THE PB CONTAINS GLARE SCREEN, ONE SET OF THREE VERTICAL STRIPES OF SHEETING SHALL BE CONSIDERED EQUIVALENT TO AN OBJECT MARKER, ONE-WAY.

INCREASED BARRIER DELINEATION, AS SPECIFIED HEREIN, SHALL BE INSTALLED ON ALL PB AND PERMANENT CONCRETE BARRIER LOCATED WITHIN 5 FEET OF THE EDGE OF THE TRAVELED LANE UNDER EITHER OF THE FOLLOWING CONDITIONS: ALONG TAPERS AND TRANSITION AREAS; OR ALONG CURVES (OUTSIDE ONLY) WITH DEGREE OF CURVATURE GREATER THAN OR EQUAL TO 3 DEGREES.

THE INCREASED BARRIER DELINEATION SHALL CONSIST OF EITHER DELINEATION PANELS OR THE TRIPLE STACKING OF WORK ZONE BARRIER REFLECTORS.

DELINIEATION PANELS SHALL CONSIST OF PANELS OF DELINIEATION, APPROXIMATELY 34 INCHES LONG AND 6 INCHES WIDE AND SHALL BE "CRIMPED." PANELS SHALL BE INSTALLED AND SPACED PER TRAFFIC SCD MT-101.70.

TRIPLE-STACKED BARRIER REFLECTORS SHALL CONSIST OF ALIGNING THREE BARRIER REFLECTORS VERTICALLY, AT LOCATIONS WHERE A SINGLE BARRIER REFLECTOR WOULD BE OTHERWISE ATTACHED. THERE SHALL BE NO OPEN SPACE BETWEEN THE ADJACENT BARRIER REFLECTORS. THE TRIPLE-STACKED BARRIER REFLECTORS SHALL CONFORM TO C&MS 626, EXCEPT THAT THEY SHALL BE SPACED AND ALIGNED PER TRAFFIC SCD MT-101.70.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE PLANS AND CARRIED TO THE GENERAL SUMMARY:

ITEM 614, BARRIER REFLECTOR, TYPE 1 (ONE-WAY) = 22 EACH

ITEM 614, OBJECT MARKER, ONE-WAY = 22 EACH

ITEM 614, INCREASED BARRIER DELINEATION = 200 FEET

PAYMENT SHALL BE FULL COMPENSATION FOR ALL MATERIAL, LABOR, INCIDENTALS AND EQUIPMENT NECESSARY FOR FURNISHING, INSTALLING, MAINTAINING AND REMOVING EACH OF THE ABOVE ITEMS.

ALONG RUNS OF INCREASED BARRIER DELINEATION WHERE THIS ITEM IS PROVIDED, THE QUANTITY SHALL BE MEASURED AS THE ENTIRE LENGTH OF THE RUN OF INCREASED BARRIER DELINEATION, INCLUDING THE SPACES BETWEEN THE INDIVIDUAL DELINEATION PANELS OR STACKS OF BARRIER REFLECTORS.

MAINTAINING TRAFFIC NEAR RUMBLE STRIPS

TRAFFIC IS NOT PERMITTED TO RUN ON OR CROSS OVER ANY RUMBLE STRIPS AT ANY TIME. RUMBLE STRIPS MUST BE FILLED WHEN THEY CONFLICT WITH THE MAINTENANCE OF TRAFFIC LANE CONFIGURATION. THIS INCLUDES LOCATIONS OF LANE SHIFTS ENTERING AND EXITING A WORK ZONE. THE RUMBLE STRIPS SHALL BE FILLED OR ELIMINATED BY PLANING AND PAVING TO PROVIDE A SMOOTH RIDE TO THE SATISFACTION OF THE PROJECT ENGINEER. ONCE TRAFFIC IS RETURNED TO ITS FINAL CONFIGURATION, RUMBLE STRIPS THAT WERE REMOVED SHALL BE RESTORED TO THE PRECONSTRUCTION CONDITION TO THE SATISFACTION OF THE PROJECT ENGINEER.

THE FOLLOWING ARE ESTIMATED LOCATIONS AND LENGTHS OF RUMBLE STRIP REMOVAL AND REPLACEMENT. THE ACTUAL LENGTHS MAY VARY.

LOCATION: HAN-15-22.46R; EB OUTSIDE SHOULDER = 2,860 FT
(AT WORK ZONE TAPERS. TRAFFIC CAN STRADDLE RUMBLE STRIPS IN BETWEEN TAPERS)

LOCATION: HAN-15-22.46R; EB INSIDE SHOULDER = 2,860 FT
(AT WORK ZONE TAPERS. TRAFFIC CAN STRADDLE RUMBLE STRIPS IN BETWEEN TAPERS)

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AT LOCATIONS THAT MAY REQUIRE RUMBLE STRIP REMOVAL AND REPLACEMENT. THE ESTIMATED QUANTITIES ARE BASED ON AN AVERAGE WIDTH OF 3 FEET.


ITEM 254 - PAVEMENT PLANING, ASPHALT CONCRETE, 1 1/2" = 1,907 SY

ITEM 407 - NON-TRACKING TACK COAT = 153 GAL

ITEM 441 - ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG64-22 (1 1/2") = 79 CY

ITEM 618 - RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE) = 5,720 FT

WINDOW CONTRACT TABLE (PN 129)				
DESCRIPTION OF CRITICAL WORK	CALENDAR DAYS TO COMPLETE	DISINCENTIVE \$ PER DAY	WORK WINDOW	
			START	END
SINGLE LANE CLOSURES FOR WORK ON HAN-15-22.46 R	60	\$7,000	COMPLETED CONTRACT	COMPLETION DATE



DESIGNER

CRS

REVIEWER

XXX MM-DD-YR

PROJECT ID

113342

SHEET

TOTAL

P.6

17

SHEET NUMBER

3	4	5	6	10	12	13	14	15	16	17	PART. 01/NFP/13	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
											2.25	614	22210	2.25	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 740.06, TYPE I	
											2,860	614	24402	2,860	FT	WORK ZONE DOTTED LINE, CLASS I, 6", 740.06, TYPE I	
6											6	616	10000	6	MGAL	WATER	
											5,720	618	40100	5,720	FT	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)	
											1,056	622	41100	1,056	FT	PORTABLE BARRIER, UNANCHORED	
											4	808	18700	4	SNMT	DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY	5
																INCIDENTALS	
											LS	614	11000	LS		MAINTAINING TRAFFIC	
											LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY



DESIGNER
CRS
REVIEWER
XXX MM-DD-YY
PROJECT ID
113342
SHEET TOTAL
P.8 17

ITEM 843 - PATCHING CONCRETE STRUCTURES WITH TROWELABLE MORTAR

A QUANTITY IS INCLUDING IN THE ESTIMATED QUANTITIES TO REPAIR ANY DETERIORATED AREAS ON THE BOTTOM OF DECK SLABS WITH ITEM 843 - PATCHING CONCRETE STRUCTURES WITH TROWELABLE MORTAR, WHERE THE DEPTH OF PATCH IS EQUAL TO OR LESS THAN 3", AS NOTED ON SHEETS 6-11.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER SQ FT FOR ITEM 843 - PATCHING CONCRETE STRUCTURE WITH TROWELABLE MORTAR WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 512 - SEALING OF CONCRETE SURFACES (EPOXY-URETHANE), AS PER PLAN

THE CONTRACTOR SHALL SEAL ALL LOCATIONS THAT HAVE QUANTITIES INCLUDED IN THE GENERAL SUMMARY FOR THE AREAS ON BRIDGES NOTED ON SHEETS 10-11.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER SQ YD FOR ITEM 512 - SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN

A QUANTITY OF THIS ITEM IS INCLUDED IN THE ESTIMATED QUANTITIES OF EACH STRUCTURE TO REPAIR ANY DETERIORATED AREAS ON THE ABUTMENTS AND DECK SLABS WHERE THE DEPTH OF THE PATCH IS GREATER THAN 3", AS NOTED ON SHEETS 6-11.

PRIOR TO THE SURFACE CLEANING SPECIFIED IN 519.04 AND WITHIN 24 HOURS OF PLACING PATCHING MATERIAL, BLAST CLEAN ALL SURFACES TO BE PATCHED INCLUDING THE EXPOSED REINFORCING STEEL. ACCEPTABLE METHODS INCLUDE HIGH-PRESSURE WATER BLASTING WITH OR WITHOUT ABRASIVES IN THE WATER, ABRASIVE BLASTING WITH CONTAINMENT, OR VACUUM ABRASIVE BLASTING.

PAYMENT FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER SQ FT FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK.

EXISTING STRUCTURE VERIFICATION

DETAILS AND DIMENSIONS HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURES AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURES AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO C&MS, SECTIONS 102.05 AND 105.02. BASE CONTRACT BID PRICES UPON A RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURES. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS THAT HAVE BEEN VERIFIED IN THE FIELD. COPIES OF THE EXISTING PLANS ARE ON FILE AND AVAILABLE TO BE INSPECTED AT THE DISTRICT 1 OFFICE IN LIMA.

ITEM SPECIAL - PILE ENCASEMENT

ENCASE ALL STEEL PIPE-PILES (EXCEPT FOR DEF-15-10.52) FOR THE CAPPED PILE PIERS IN CONCRETE CONFORMING TO C&MS 511 (F'C = 4.0 KSI). PROVIDE A CONCRETE SLUMP BETWEEN 6 TO 8 INCHES WITH THE USE OF A SUPERPLASTICIZER. PLACE THE CONCRETE WITHIN A FORM THAT CONSISTS OF POLYETHYLENE PIPE (707.33), OR PVC PIPE (707.42) WHICH SHALL BE LEFT IN PLACE. THE ENCASEMENT SHALL EXTEND FROM 3 FEET BELOW THE FINISHED GROUND SURFACE UP TO THE CONCRETE PIER CAP. POSITION THE PIPE SO THAT AT LEAST 3 INCHES OF CONCRETE COVER IS PROVIDED AROUND THE EXTERIOR OF THE PILE.

THE DEPARTMENT WILL MEASURE PILE ENCASEMENT BY THE NUMBER OF FEET. THE DEPARTMENT WILL DETERMINE THE SUM AS THE LENGTH MEASURED ALONG THE AXIS OF EACH PILE FROM THE BOTTOM OF THE ENCASEMENT TO THE BOTTOM OF THE PIER CAP. THE DEPARTMENT WILL PAY FOR ACCEPTED QUANTITIES AT THE CONTRACT PRICE FOR ITEM - SPECIAL, PILE ENCASEMENT.

ITEM 509 - EPOXY COATED REINFORCING STEEL, AS PER PLAN

IN ADDITION TO THE PROVISIONS OF ITEM 509, FIELD BEND AND/OR FIELD CUT THE REINFORCING STEEL DESIGNATED IN THE PLANS, AS NECESSARY, IN ORDER TO MAINTAIN THE REQUIRED CLEARANCES AND BAR SPACINGS. REPAIR ALL DAMAGE TO THE EPOXY COATING, AS A RESULT OF THIS WORK, ACCORDING TO C&MS 709.00.

ITEM SPECIAL - STEEL DRIP STRIP

DRIP STRIPS SHALL CONFORM TO SCD DS-1-92.

ITEM SPECIAL - PATCHING CONCRETE STRUCTURE ABUTMENT BACKWALL

IN ADDITION TO THE WORK ITEMS REQUIRED IN 519, THIS ITEM WILL INCLUDE, THE WIDENING OF THE ABUTMENT SEATS AS DETAILED IN THESE PLANS AND DESCRIBED IN THE FOLLOWING NOTE.

PROVIDE A CONCRETE MIX AT A SLUMP THAT ALLOWS THE CONCRETE MIX TO BE PUMPED THROUGH A 4" DIAMETER ACCESS HOLE FROM THE TOP OF THE DECK, FILLING THE PATCH LOCATIONS OF THE UNDERSIDE OF THE DECK, THE ABUTMENT SEAT AND VERTICAL ABUTMENT WALL.

WHEN PERFORMING THE DISINTEGRATED CONCRETE REMOVAL, PROVIDE PATCHES WITH A MINIMUM DEPTH OF 4 INCHES AND NO GREATER THAN 6 INCHES. AREAS TO BE PATCHED WILL HAVE SQUARED EDGES AND BE ROUGHLY SQUARE OR RECTANGLE IN SHAPE.

AVOID DAMAGING OR DEBONDING THE REINFORCING, OR SHATTERING THE CONCRETE, BEYOND THE AREA TO BE PATCHED. AFTER LOCATING THE EXISTING REINFORCING STEEL USING A PACHOMETER, DRILL 4" DIAMETER HOLES THROUGH THE BRIDGE DECK MISSING THE REBAR.

DRILL DOWEL HOLES FOR THE INSTALLATION OF THE EPOXY COATED REINFORCING STEEL. INSTALL THE REINFORCING STEEL ACCORDING TO ITEM 510 USING EPOXY GROUT, 705.20. IF AN EXISTING STEEL BAR IS ENCOUNTERED AT THE SAME LOCATION AS A PROPOSED DOWEL HOLE MOVE THE DOWEL HOLE TO EITHER SIDE OF THE EXISTING BAR. THE DEPARTMENT WILL PAY FOR THE DOWEL HOLES AND GROUT AT THE UNIT PRICE FOR ITEM 510 - DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT.

AFTER PLACEMENT OF THE REINFORCING STEEL AND THE DRILLING OF THE HOLES, PUMP THE CONCRETE INTO THE CORE HOLES UNTIL THE PATCH AREAS ARE FILLED AND ALL AIR VOIDS ARE DETERMINED TO HAVE BEEN ELIMINATED.

THE SLAB BRIDGE SEAT WILL ALSO BE WIDENED TO MATCH THE EXISTING ABUTMENT FOOTER WIDTH. REFER TO THE RESPECTIVE STRUCTURE SHEET FOR MORE DETAILS REGARDING THE WIDENING.

PLACE THE CONCRETE THROUGH THE 4" DIAMETER CORE HOLES BY PUMPING AND FREE FALL. ASSURE THE CONCRETE HAS COMPLETELY FILLED THE PATCH VOIDS BEFORE MOVING TO ANOTHER 4" ACCESS HOLE. USE VIBRATION EQUIPMENT TO HELP CONSOLIDATE THE CONCRETE MIX. CONTINUE PLACING THE CONCRETE INTO THE CORE HOLES AND FINISH THE CONCRETE IN THE HOLES LEVEL WITH THE DECK CONCRETE.

WHEN THE FORMWORK IS REMOVED, THE PROJECT ENGINEER WILL DETERMINE IF THE NEW CONCRETE IS FLUSH WITH THE UNDERSIDE OF THE DECK. IF THERE ARE VOIDS FOUND BETWEEN THE NEW CONCRETE AND THE UNDERSIDE OF THE DECK, THE CONTRACTOR WILL PRESSURE GROUT THE VOIDS UNTIL ALL MATERIAL IS FOUND TO BE IN CONTACT WITH ONE ANOTHER. THE GROUT MATERIAL WILL ACHIEVE AND LEAST 4000 PSI IN 7 DAYS AND CONSIST OF CEMENT AND SAND MEETING ODOT MATERIAL SPECIFICATIONS.

THE DEPARTMENT WILL MEASURE THE NUMBER OF CUBIC YARDS DETERMINED BY THE CALCULATIONS FROM THE PLAN DIMENSION FOR THE ABUTMENT WIDENING WORK. THE DEPARTMENT WILL MEASURE THE NUMBER OF CUBIC YARDS FOR THE PATCHED AREAS BY DETERMINING THE SQUARE YARDAGE OF ACTUAL PATCHED AREAS AND MULTIPLYING BY A DEPTH OF 0.167 YARDS TO CALCULATE THE VOLUME OF CUBIC YARDS.

THE DEPARTMENT WILL PAY FOR ACCEPTED QUANTITY OF CUBIC YARDS.

PAYMENTS FOR ALL OF THE ABOVE SHALL BE AT THE UNIT PRICE BID PER CU. YD. FOR ITEM SPECIAL - PATCHING CONCRETE STRUCTURE, MISC.: ABUTMENT BACKWALL, WHICH SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE ABOVE WORK, EXCEPT FOR THE EPOXY COATED REINFORCING STEEL WHICH WILL BE PAID FOR SEPARATELY.

ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN

THIS ITEM SHALL CONFORM TO SS 848 WITH THE FOLLOWING CONDITIONS AND REVISIONS:

THE OVERLAY MATERIAL SHALL MEET THE FOLLOWING CRITERIA: MINIMUM 4 LBS/CY MACRO-SYNTHETIC FIBERS (1.5 IN. MIN. TO 2.25 IN. MAX.) MEETING ASTM C1116 TYPE III SHALL BE ADDED TO THE MIX.

THE MACRO-SYNTHETIC FIBERS SHALL BE INCORPORATED INTO THE MIX IN SUCH A WAY THAT NO 'BALLING' OCCURS. UPON INSPECTION OF THE MIX AT THE TIME OF PLACEMENT, IF ANY 'BALLING' OCCURS, THE ENGINEER SHALL REJECT THE REMAINDER OF THE LOAD AT ANY TIME DURING THE POUR. IT IS IMPORTANT TO FOLLOW INDUSTRY STANDARDS AND ASTM SPECIFICATIONS ON THE PREMIXING OF THE CEMENT, AGGREGATE, AND MACRO-SYNTHETIC FIBERS PRIOR TO THE ADDITION OF WATER AND ADMIXTURES. PROVIDE MACRO-SYNTHETIC FIBERS THAT ARE MONOFILAMENT FIBERS MADE FROM VIRGIN POLYPROPYLENE, POLYETHYLENE, OR CO-POLYMERS THAT ARE INERT TO ALKALI ATTACK. ENSURE THE MACRO-SYNTHETIC FIBERS HAVE A MINIMUM TENSILE STRENGTH OF 70 KSI, A MINIMUM MODULUS OF ELASTICITY OF 800 KSI, A MINIMUM FILAMENT DIAMETER OF 0.012 INCHES, AND ASPECT RATIO BETWEEN 60 AND 100, AND ARE BETWEEN 1.5 AND 2.25 INCHES IN LENGTH. FIBERS WITH AN ASPECT RATIO GREATER THAN 60 REQUIRES A BLOWER TO INHIBIT BALLING AND MATTING OF FIBERS (ACI 544.3R-08). STORE THE MACRO-SYNTHETIC FIBERS ACCORDING TO THE MANUFACTURE'S RECOMMENDATION AND KEEP THE MATERIAL FREE FROM DUST, DIRT AND MOISTURE.

USE A MINIMUM DOSAGE RATE OF MACRO-SYNTHETIC FIBERS OF 4.0 LBS/CY OF CONCRETE. DETERMINE THE FINAL PROPOSED DOSAGE RATE THROUGH MIX TESTING. ENSURE THE FIBER REINFORCED CONCRETE MEETS OR EXCEEDS A MINIMUM EQUIVALENT FLEXURAL STRENGTH RATIO OF 25% ACCORDING TO ASTM C 1609. MACRO-SYNTHETIC FIBERS IS TO BE USED AS AN ADMIXTURE TO CONTROL CRACKING AND IS NOT TO BE USED TO SUPPLEMENT OR REPLACE REINFORCING STEEL IN THE DESIGN. ENSURE THE FINAL PROPOSED MIX IS WORKABLE AND ABLE TO BE PRODUCED SUCH THAT BALLING OR CLUMPING OF THE FIBERS IS NOT A PROBLEM AS DETERMINED BY THE ENGINEER. UTILIZE A LABORATORY REGULARLY INSPECTED BY THE CEMENT AND CONCRETE REFERENCE LABORATORY (CCRL) OF THE NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY, OR OTHER APPROVED REFERENCE LABORATORY, TO PERFORM THE TESTING. BEFORE USE, SUBMIT DOCUMENTATION TO THE PROJECT ENGINEER CERTIFYING BOTH THE MACRO-SYNTHETIC FIBERS AND THE MIX MEET OR EXCEED THE REQUIRED PROPERTIES. SAMPLING WILL BE ALLOWED FOR TESTING PURPOSES. A DEMONSTRATION OF THE MIX PRODUCTION OR TRIAL MIX, MAY BE REQUIRED BY THE ENGINEER PRIOR TO PLACING ANY OF THE MIX ON THE PROJECT.

THE BATCH WEIGHTS SHALL BE CORRECTED TO COMPENSATE FOR THE MOISTURE CONTAINED IN THE AGGREGATE AT THE TIME OF USE.

CONCRETE SUPPLIERS SHOULD RECOGNIZE THAT ADMIXTURES MAY HAVE AN EFFECT ON STRENGTH, ENTRAINED AIR CONTENT, WORKABILITY, ETC. OF THEIR CONCRETE MIXES. THE CONCRETE SUPPLIERS CHOICE OF ONE OF THESE ADMIXTURES DOES NOT ALLEVIATE MEETING DESIGN REQUIREMENTS.



DESIGNER
CRS

REVIEWER

XXX MM-DD-Y

PROJECT ID


113342

SHEET

TOTAL

P.9

17




NOTES

DETAILS SHOWN ARE TAKEN FROM EXISTING PLANS AND ARE FOR REFERENCE ONLY
ALL DIMENSIONS CONSIDERED APPROXIMATE
ALL PATCHING LOCATIONS ARE APPROXIMATE

EXISTING STRUCTURE

TYPE: CONTINUOUS CONCRETE SLAB WITH CAPPED PILE PIERS AND ABUTMENTS
SPAN: 22'-0", 27'-6", 22'-0" C/C BRGS.
ROADWAY: 40'-0" f/f GUARDRAIL
SKEW: 10° R.F.
WEARING SURFACE: $\frac{3}{4}$ " MONOLITHIC CONCRETE
APPROACH SLABS: 20' LONG (STD. DWG. AS-1-54)
ALIGNMENT: TANGENT
STRUCTURAL FILE NUMBER: 2000458
DATE BUILT: 1957



EPOXY URETHANE SEALING - 2.23' ON EDGE X 73.02' PER EDGE X 2 EDGES + 14 SF PER WINGWALL X 4 WINGWALLS = 43 SF

PATCHING = 180 SF

ROCK CHANNEL PROTECTION TYPE B WITHOUT FILTER = 65 CY


PROPOSED WORK

1.) PLACE ROCK CHANNEL PROTECTION ABOVE OHWM ALONG BANKS OF CHANNEL
2.) PERFORM CONCRETE PATCHING AS DETAILED ON SHEETS 10 & 11.


SITE PLAN
DEF-15-10.52
SR-15 OVER BUCKSKIN CREEK



DESIGNER	CHECKER
ISR	XXX
REVIEWER	XXX MM-DD-Y
PROJECT ID	113342
SUBSET	TOTAL
1	8
SHEET	TOTAL
P.10	17



◻ - ITEM 519 - PATCHING CONCRETE STRUCTURES, AS PER PLAN



NOTES

DETAILS SHOWN ARE TAKEN FROM EXISTING PLANS AND ARE FOR REFERENCE ONLY

ALL DIMENSIONS CONSIDERED APPROXIMATE

ALL PATCHING LOCATIONS ARE APPROXIMATE


EXISTING STRUCTURE	
TYPE:	CONTINUOUS CONCRETE SLAB WITH CAPPED PILE PIERS AND ABUTMENTS
SPAN:	22'-0", 27'-6", 22'-0" C/C BRGS.
ROADWAY:	40'-0" F/F GUARDRAIL
SKEW:	10° R.F.
WEARING SURFACE:	3/4" MONOLITHIC CONCRETE
APPROACH SLABS:	20' LONG (STD. DWG. AS-1-54)
ALIGNMENT:	TANGENT
STRUCTURAL FILE NUMBER:	2000458
DATE BUILT:	1957




DESIGNER	CHECKER
ISR	XXX
REVIEWER	
XXX	MM-DD-Y
PROJECT ID	113342
SUBSET	TOTAL
2	8
SHEET	TOTAL
P.11	17

PROPOSED WORK

- 1.) PLACE ROCK CHANNEL PROTECTION ABOVE OHWM ALONG BANKS OF CHANNEL
- 2.) PERFORM CONCRETE PATCHING AS DETAILED ON SHEETS 10 & 11.



APPROACH SLABS REMOVED AND
REPLACED PER AS-1-15 (15")





REMOVE ASPHALT AND PLACE NON-REINFORCED
CONCRETE PAVEMENT 15"

133 SY OF APPROACH SLAB AREA
85 SY OF CONCRETE PAVEMENT AREA
85 SY OF SUBGRADE COMPACTION
26 SF OF CONCRETE PATCHING
112 FT OF JOINT SEALER
34 DOWEL HOLES

889 SF OF PARTIAL DEPTH PAVEMENT REPAIR IF NEEDED
15 CY OF PAVEMENT REPAIR IF NEEDED

DECK OVERLAY QUANTITIES
150 FT OF STEEL DRIP STRIP
267 SY DECK AREA
80 SY OF HAND CHIPPING
5 CY OF VARIABLE OVERLAY MATERIAL
5 CY OF FULL DEPTH REPAIR




17 - D801 BARS PER ABUTMENT = 332 LB OF REINFORCING STEEL

EXISTING STRUCTURE	
TYPE:	CONTINUOUS REINFORCED CONCRETE SLAB WITH CONC. PIERS AND PEDESTAL ABUT.
SPAN:	18'-0", 22'-6", 18'-0" C/C BRGS.
ROADWAY:	40'-0" F/F GUARDRAIL
SKEW:	NONE
WEARING SURFACE:	1" MONOLITHIC CONCRETE
APPROACH SLABS:	25' LONG (STD. DWG. AS-1-54)
ALIGNMENT:	TANGENT
STRUCTURAL FILE NUMBER:	3200698
DATE BUILT:	1963



PROPOSED WORK	
1.) POUR CURTAIN WALLS	
2.) PATCH CONCRETE	
3.) REMOVE EXISTING OVERLY $\pm 2"$ MICRO-SIL. CONC. HYDRODEMO. 1"	
4.) OVERLAY DECK WITH 3" OF SUPERPLASTICIZED DENSE CONCRETE	
5.) REPLACE APPROACH SLABS AND ADJACENT CONCRETE PAVEMENT	
6.) REPAIR ASPHALT PAVEMENT AS NEEDED	

PLAN VIEW
HAN-15-22.46 R
S.R. 15 OVER HOY DITCH




DESIGNER CRS	CHECKER XXX
REVIEWER XXX	MM-DD-Y
PROJECT ID 113342	
SUBSET 3	TOTAL 8
SHEET P.12	TOTAL 17

ABUTMENT DETAILS
HAN-15-22.46 R
OVER HOY DITCH



TYPE-1




ITEM SPECIAL - PATCHING CONCRETE STRUCTURE: ABUTMENT BACKWALL




DESIGNER	CHECKER
CRS	XXX
REVIEWER	
XXX	MM-DD-YY
PROJECT ID	
113342	
SUBSET	TOTAL
4	8
SHEET	TOTAL
P.13	17

EXISTING STRUCTURE

PROPOSED WORK



SOUTH SIDE OF BRIDGE PROFILE VIEW




NORTH SIDE OF BRIDGE PROFILE VIEW

GENERAL PLAN


PILE ENCASEMENT - 11' PER PILE X 16 PILES = 176'

EPOXY URETHANE SEALING - 2.33' PER EDGE X 60' AN EDGE
X 2 EDGES = 31 SY

PATCHING = 42 SF



NOTE: ALL PATCHING PERFORMED WITH ITEM 843 TROWELABLE MORTAR OCCURS ON THE UNDERSIDE OF THE DECK SLAB



EXISTING STRUCTURE	
TYPE: CONTINUOUS REINFORCED CONCRETE SLAB WITH CAPPED PILE SUBSTRUCTURE	
SPAN: 22'-0", 27'-6", 22'-0" C/C BRGS.	
ROADWAY: 42'-8" F/F GUARDRAIL	
SKEW: 30° R.F.	
WEARING SURFACE: 1" MONOLITHIC CONCRETE	
APPROACH SLABS: 25' LONG (STD. DWG. AS-1-54)	
ALIGNMENT: TANGENT	
STRUCTURAL FILE NUMBER: 8102406	
DATE BUILT: 1968	

PROPOSED WORK	
1.) PERFORM DECK PATCHING AS DETAILED ON THIS SHEET	


PILE ENCASEMENT - 11' PER PILE X 16 PILES = 176'

EPOXY URETHANE SEALING - 2.33' ON EDGE X 73.24' PER EDGE X 2 EDGES = 38 SY


PATCHING = 14 SY TROWELABLE MORTAR = 52 SF

PLAN VIEW

- - ITEM 519, PATCHING CONCRETE STRUCTURES, AS PER PLAN
- - ITEM 843, PATCHING CONCRETE STRUCTURES WITH TROWELABLE MORTAR



SOUTH PROFILE VIEW




NORTH PROFILE VIEW



PATCHING PLAN
VAN-224-8.38
US-224 OVER MADDUX CREEK

SFN 8102406
DESIGN AGENCY


DESIGNER ISR	CHECKER XXX
REVIEWER XXX	MM-DD-YY
PROJECT ID 113342	
SUBSET 6	TOTAL 8
SHEET P.15	
TOTAL 17	



EXISTING STRUCTURE	
TYPE: CONTINUOUS REINFORCED CONCRETE SLAB WITH CAPPED PILE SUBSTRUCTURE	
SPAN: 22'-0", 27'-6", 22'-0" C/C BRGS.	
ROADWAY: 42'-8" F/F GUARDRAIL	
SKEW: 15° R.F.	
WEARING SURFACE: 1" MONOLITHIC CONCRETE	
APPROACH SLABS: 25' LONG (STD. DWG. AS-1-54)	
ALIGNMENT: ON 7° SPIRAL LEFT	
STRUCTURAL FILE NUMBER: 8102430	
DATE BUILT: 1968	




PILE ENCASEMENT - 12' PER PILE X 16 PILES = 192'
EPOXY URETHANE SEALING - 2.33' ON EDGE X 73.06' PER EDGE
X 2 EDGES = 38 SY
PATCHING = 25 SF

PROPOSED WORK	
1.) PERFORM DECK PATCHING AS DETAILED ON THIS SHEET	
2.) PERFORM EPOXY CRACK INJECTION AS DETAILED ON THIS SHEET	

DESIGNER	CHECKER
ISR	XXX
REVIEWER	
XXX	MM-DD-Y
PROJECT ID	
113342	
SUBSET	TOTAL
7	8
SHEET	TOTAL
P.16	17


PATCHING PLAN
VAN-224-8.65

US-224 OVER MADDUX CREEK



FOWARD ABUTMENT TRANSVERSE SECTION

TOTAL EPOXY INJECTION = 20'



SLAB EDGES PROFILE VIEW

ABUTMENT DETAILS
VAN-224-8.65
11S 224 OVER MADDUX CREEK

BUTMENT DETAILS
VAN-224-8.65
OVER MADDox CREEK

115



DESIGNER	CHECKER
ISR	XXX
REVIEWER	
XXX MM-DD-YY	
PROJECT ID	
113342	
SUBSET	TOTAL
8	8
SHEET	TOTAL
P.17	17



OHIO DEPARTMENT OF
TRANSPORTATION

Asbestos Inspection Reporting Form

Date

County Route

Section PID

Requesting ODOT District Office

Regulating OEPA District Office and Address

Date of the Asbestos Inspection

Name and Address of the company conducting the asbestos inspection

Name, signature, and asbestos hazard evaluation number of the person writing the report



OHIO DEPARTMENT OF
TRANSPORTATION

Description sampling locations and how each location was determined (use additional pages if needed)

Name, signature, and asbestos hazard evaluation number of each person who selected samples from the structure (use additional pages if needed)

Name	Signature	Asbestos Evaluation #
<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>
<input type="text"/>	<input type="text"/>	<input type="text"/>



SUPPORTING INFORMATION

Laboratory Analytical Report

Blueprint, diagram or written description with the following:

- Type, location and amount of confirmed regulated asbestos containing material
- Location and collection date of each bulk sample
- Location and amounts of suspected asbestos containing material, both friable and non-friable

NOTE: The OEPA Notification of Demolition and Renovation Form with the appropriate Sections I, II, III, IV, VI and VII must be completed by the licensed asbestos hazard evaluation specialist and included with the report submission to ODOT prior to submission to OEPA or the local air authority with jurisdiction.

OEPA Notification of Demolition and Renovation Form

Work on projects cannot begin until 10 working days after a COMPLETE original notification form, including payment, is submitted to Ohio EPA. Instructions and a worksheet for fee calculation are available at epa.ohio.gov/asbestos. This form can be completed, and payment made, at ebiz.epa.ohio.gov. Questions? asbestos@epa.ohio.gov or (614) 466-0061.



Appendix A:
Bridge Asbestos Inspection Location Photos

Appendix B: Laboratory Analytical Report



The Identification Specialists

Analysis Report
prepared for
Allied Environmental Services, Inc.

Report Date: 12/15/2025

Project Name: ODOT Bridge Maintenance

Project #: 116743, 113342

SanAir ID#: 25083406



NVLAP LAB CODE 600227-0

11709 Chesterdale Road, Cincinnati, Ohio 45246
888.895.1177 | 513.438.6066 | LabReports@SanAir.com | SanAir.com



SanAir ID Number

25083406

FINAL REPORT

12/15/2025 12:46:03 PM

Name: Allied Environmental Services, Inc.
Address: 585 Liberty Commons Parkway
Lima, OH 45804
Phone: 419-227-4004

Project Number: 116743, 113342
P.O. Number:
Project Name: ODOT Bridge Maintenance
Collected Date: 11/19/2025
Received Date: 12/15/2025 9:45:00 AM

Dear Matt Stapleton,

We at SanAir would like to thank you for the work you recently submitted. The 2 sample(s) were received on Monday, December 15, 2025 via FedEx. The final report(s) is enclosed for the following sample(s): 1-A, 1-A-1.

These results only pertain to this job and should not be used in the interpretation of any other job. This report is only complete in its entirety. Refer to the listing below of the pages included in a complete final report.

Sincerely,

A handwritten signature in black ink that reads "Maureen Y. Haley".

Maureen Y. Haley
Asbestos Laboratory Manager
SanAir Technologies Laboratory

Final Report Includes:

- Cover Letter
- Analysis Pages
- Disclaimers and Additional Information

Sample conditions:

- 2 samples in Good condition.



SanAir ID Number

25083406

FINAL REPORT

12/15/2025 12:46:03 PM

Name: Allied Environmental Services, Inc.
Address: 585 Liberty Commons Parkway
Lima, OH 45804
Phone: 419-227-4004

Project Number: 116743, 113342
P.O. Number:
Project Name: ODOT Bridge Maintenance
Collected Date: 11/19/2025
Received Date: 12/15/2025 9:45:00 AM

Analyst: Hedge, Emily

Asbestos Bulk PLM EPA 600/R-93/116

SanAir ID / Description	Stereoscopic Appearance	Components		Asbestos Fibers
		% Fibrous	% Non-fibrous	
1-A / 25083406-001 Back Wall + Bridge Slab	Grey Non-Fibrous Homogeneous		85% Other	15% Chrysotile
1-A-1 / 25083406-002 Back Wall + Bridge Slab	Grey Non-Fibrous Homogeneous		85% Other	15% Chrysotile

Analyst:

Approved Signatory:

Analysis Date: 12/15/2025

Date: 12/15/2025

Disclaimer and Additional Information

This report is the sole property of the client named on the SanAir Technologies Laboratory, Inc. (SanAir) chain-of-custody (COC). Results in the report are confidential information intended only for the use by the client named on the COC. Neither results nor reports will be discussed with or released to any third party without our client's written permission to maintain client confidentiality. The final report cannot be reproduced, except in full, without written authorization from SanAir to assure that parts of the report are not taken out of context. This report and any information contained within shall not be edited, altered, or modified in any way by any persons or agencies receiving, viewing, distributing, or otherwise possessing a copy of this final report. The laboratory reserves the right to perform amendments to any finalized report, of which shall supersede and make obsolete any previous editions. Such changes, modifications, additions, or deletions shall be effective immediately upon notice thereof, which may be given by means including, but not limited to, posting on the SanAir client portal website, electronic or conventional mail, or by any other means. The information provided in this report applies only to the samples submitted in the condition they were received at the laboratory and is relevant only for the date, time, and location of sampling. Samples were received in good condition unless otherwise noted on the report. The accuracy of the results is dependent upon the client's sampling procedure and information provided to the laboratory by the client on the COC, which includes the project name, project number, P.O. number, sample collection dates, special instructions, samples collected by, sample numbers, sample identifications/location, sample type, selected analysis type, and total area or volume that may affect the validity of the results. SanAir assumes no responsibility for the sampling procedure and will provide evaluation reports based solely on the sample and information provided by the client. SanAir assumes no responsibility or liability for the manner in which results are used or interpreted. This report does not constitute and shall not be used to claim product, process, system, or person certification, approval, or endorsement by NVLAP, NIST, NELAC, AIHA LAP, LLC or any other agency of the U.S. government; all or some tests contained in this report may not be accredited by every local, state, and federal regulatory agency. Refer to the SanAir website at www.sanair.com for copies of current certificates and scopes of various accreditations, certifications, and licenses or contact the laboratory at iaq@sanair.com for inquiries regarding the status or scope of an accreditation or certification.

Fibers smaller than 5-microns cannot be seen with this method due to scope limitations. Polarized- light microscopy is not consistently reliable in detecting asbestos in floor covering and similar non-friable organically bound materials. Quantitative transmission electron microscopy is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos containing. Samples are held for a period of 60 days.

Asbestos Accreditations, Certifications, and Licenses

National Voluntary Laboratory Accreditation Program (NVLAP) Lab Code 600227-0

State of Connecticut Department of Public Health Registration Number: PH-0817

State of Rhode Island Department of Health, Certification Number: PLM00144, TEM00144

State of West Virginia Bureau for Public Health, Analytical Laboratory Number: LT000637

Texas Department of State Health Services License Number: 300510

25083406

From: Steve Carr <steve@Alliedesi.com>
Sent: Monday, December 15, 2025 9:31 AM
To: Support <support@sanair.com>; Constance Stimmel <connie@Alliedesi.com>
Cc: AsbestosVA <AsbestosVA@sanair.com>; AsbestosOH <AsbestosOH@sanair.com>; Sales <Sales@sanair.com>
Subject: RE: [Reply Needed] 113342 - Lab Confirmation

EXTERNAL EMAIL: DO NOT
CLICK on links or attachments
unless you recognize the sender
and know the content is safe.

Please proceed with the analysis. The customer used the wrong CoC, but we've since corrected that. Regular 24-hour T/A is fine.

Thanks,

Steven D. Carr | CEO

Allied Environmental Services, Inc. | 585 Liberty Commons Parkway Lima, OH 45804
T: 419-227-4004 | F: 419-229-4106 | Cell: 419-302-3247 | www.alliedesi.com
ISN #400-116603 |

Confidentiality Notice: This e-mail message, from Allied Environmental Services, Inc., including any attachment(s), is for the sole use of the intended recipient(s) and may contain confidential and privileged information. If you are not the intended recipient, you are hereby notified that any action taken on the contents of this e-mail is strictly prohibited.

From: Support <support@sanair.com>
Sent: Monday, December 15, 2025 9:24 AM
To: Steve Carr <steve@Alliedesi.com>; Constance Stimmel <connie@Alliedesi.com>; Rolland Dunifon <rolland@Alliedesi.com>; Matthew Stapleton <stapleton@Alliedesi.com>; Trent Stucky <Trent@Alliedesi.com>; Tyler Beemer <tyler@Alliedesi.com>
Cc: AsbestosVA <AsbestosVA@sanair.com>; AsbestosOH <AsbestosOH@sanair.com>; Sales <Sales@sanair.com>
Subject: Re: [Reply Needed] 113342 - Lab Confirmation
Importance: High

[EXTERNAL EMAIL WARNING]

Good Morning,

I am looking to follow up on the asbestos project mentioned below (please see email below). Please advise as needed.

Please let me know if you have any questions.

Let us know how we are doing! [Click Here](#) for comments, complaints, and compliments.

Respectfully,

Cecelia Toler
Customer Service Representative
SanAir Technologies Laboratory, Inc.
10501 Trade Court
N. Chesterfield, VA 23236
Phone 804-897-1177 Ext 208
Fax 804-897-0070

RMB DEC 15 2025 9:45am

Page 5 of 8

25083406

www.SanAir.com**The Identification Specialists**

Asbestos, Lead & Metals, Microbiology, Legionella, Materials Science Testing

**2018, 2019, 2020, and 2021 Winner of Top work places in Richmond**

The information transmitted herewith is sensitive information intended only for use to the individual or entity to which it is addressed. If the reader of this message is not the intended recipient, you are hereby notified that any review, retransmission, dissemination, distribution, copying or other use of, or taking of any action in reliance upon, this information is strictly prohibited. If you have received this communication in error, please contact the sender and delete the material from your computer.

From: Support <support@sanair.com>**Sent:** Monday, December 8, 2025 12:35 PM**To:** Steve Carr <steve@alliedesi.com>; Connie Stimmel <connie@alliedesi.com>; Rollo Dunifon<rolland@alliedesi.com>; Matt Stapleton<stapleton@alliedesi.com>; trent@alliedesi.com <trent@alliedesi.com>; Tyler Beemer
<tyler@alliedesi.com>**Cc:** AsbestosVA <AsbestosVA@sanair.com>; AsbestosOH <AsbestosOH@sanair.com>; Sales
<Sales@sanair.com>**Subject:** [Reply Needed] 113342 - Lab Confirmation

Project Number: 113342

Good Afternoon,

The Ohio lab received samples this morning for project number 113342, however, the chain of custody is for DMD Environmental, Inc (please see attached). Please advise if SanAir is to proceed with analysis, and if so, the turnaround time you are looking for.

Please let me know if you have any questions.

Respectfully,

Cecelia Toler
Customer Service Representative
SanAir Technologies Laboratory, Inc.
10501 Trade Court
N. Chesterfield, VA 23236
Phone 804-897-1177 Ext 208
Fax 804-897-0070
www.SanAir.com

12 MB DEC 15 2025 9:45 am
Page 6 of 8

3424 West Laskey Road, Toledo, Ohio 43622-4032
Bill to Ohio Department of Transportation
1885 N McCullough St, Lima, OH 45801
Paige Dunn Paige.Dunn@dot.ohio.gov
CL

CHAIN OF CUSTODY

Project No.: 116743

Client: **Opcon**

Project: Bridge Maintenance

Item No. Sample ID Date Sampled

1119125

2

63

2000-01-02

111

51

6

7

888

Vertical line

Relinquished by: / / Date: / / Time: / : /

Wilson Library
11/29/25 3:20

Relinquished by: _____ Date _____
Time _____

Project No.:		Project Manager and Phone No.:		Analysis	
Client:		Sampler's Name:			
Project:		Sampler's Signature:			
Item No.	Sample ID	Date Sampled	Sample Location	PLM	PCM
1	1-A	11/19/25	Beck wall & Bridge slab	All	
2					
3					
4					
5					
6					
7					
8					
9					
10					
Relinquished by:	Date	Time	Received by:	Date	Time
<i>Jason Wenz</i>	11/19/25	3:20	<i>Diego Ourn</i>	11/19/25	3:20pm
Relinquished by:	Date	Time	Received by:	Date	Time
<i>Jason Wenz</i>					

3424 West Laskey Road, Toledo, Ohio 43623-4032
1311 N. Ohio Department of Transportation
1485 N McCullough St., Lima, OH 45838

DMDEnv@att.net

Telephone (419) 473-1980

Faximile (419) 473-1980

Paige Dunn Paige.Dunn@dot.ohio.gov

CHAIN OF CUSTODY

Page _____ of _____

Project No.:	113342			Project Manager and Phone No.:	Clark Schlatter 419-999-6856			Analysis
Client:	ODOT			Sampler's Name:	Jason Averman			
Project:	Bridge Maintenance			Sampler's Signature:	Jason Averman			
Item No.	Sample ID	Date Sampled			PLM	PCM		
1	1-A-1	11/19/25			Back wall & Bridge slab	All		
2								
3								
4								
5								
6								
7								
8								
9								
10								
Relinquished by:	Date	Time	Received by:	Date	Time	Relinquished by:	Date	Time
	11/19/25	3:30pm	Paige Dunn	11/19/25	3:30pm			
Relinquished by:	Date	Time	Received by:	Date	Time	Relinquished by:	Date	Time

Appendix C:
OEPA Notification of Demolition and Renovation Form

Ohio Only	EPA Use	Notification #:	Postmarked: / /	Received: / /	<input type="checkbox"/> Hand-Delivered
-----------	---------	-----------------	-----------------	---------------	---

1) Notification Information (Check all that apply)

<input type="checkbox"/> Original	<input type="checkbox"/> Revision # (count):	<input type="checkbox"/> Installation	<input type="checkbox"/> Emergency	<input type="checkbox"/> Annual	<input type="checkbox"/> Cancellation	Project County:
<input type="checkbox"/> NESHAP Residential Exemption						

2) Owner, Asbestos Abatement Contractor, Billing and Fire Department InformationRevised?

Owner			
Name: _____		Is this a company? <input type="checkbox"/> Yes <input type="checkbox"/> No	
Address: _____		Contact Person: _____	
City: _____	State: _____	Zip: _____	
Email: _____	Phone: () -	Fax: () -	
Asbestos Abatement Contractor (if applicable)			
Name: _____		License #: AC	Expiration Date: / /
Address: _____		Contact Person: _____	
City: _____	State: _____	Zip: _____	
Email: _____	Phone: () -	Fax: () -	
Billing Contact (Entity paying for original notification)			
Is this contact associated with the <input type="checkbox"/> Owner, <input type="checkbox"/> Asbestos Abatement Contractor, or <input type="checkbox"/> Demolition Contractor (if not installation)?			
Address: _____		Contact Person: _____	
City: _____	State: _____	Zip: _____	
Email: _____	Phone: () -	Fax: () -	
Fire Department (if applicable)			
Name: _____			
Address: _____		Contact Person: _____	
City: _____	State: _____	Zip: _____	
Email: _____	Phone: () -	Fax: () -	

3) Ohio Asbestos Hazard Evaluation Specialist and Evaluation ProcedureRevised?

Evaluation Specialist: _____	Certification #: ES	Expiration Date: / /
Procedure, including analytical methods, employed to detect the presence of and to estimate the quantity of regulated asbestos-containing material (RACM) and Category I and Category II non-friable asbestos-containing material: <input type="checkbox"/> PLM <input type="checkbox"/> Point Count <input type="checkbox"/> TEM <input type="checkbox"/> Other Method (Explain Below): _____		

4) Procedures to be followed should unexpected RACM be discovered (check all that apply)Revised?

<input type="checkbox"/> Stop work and keep wet	<input type="checkbox"/> Evacuate area	<input type="checkbox"/> Demarcate area	<input type="checkbox"/> Contact licensed abatement contractor
<input type="checkbox"/> Contact district office/local air authority			
<input type="checkbox"/> Other (Explain): _____			

5) Planned Demolition (check all that apply)Revised?

Describe demolition work to be performed and method(s) to be employed, including demolition techniques to be used:	
<input type="checkbox"/> Implosion <input type="checkbox"/> Fire Training <input type="checkbox"/> Wet Methods <input type="checkbox"/> Manual Demolition <input type="checkbox"/> Mechanical Demolition <input type="checkbox"/> Other (Explain): _____	
Description of affected facility components (include attachment if necessary): _____	



6) Asbestos Description and Engineering Controls (if asbestos is being abated)**Revised?**

For the material listed in each project, describe the type(s) of ACM to be abated, engineering controls and work practices to be used to minimize emissions and ensure proper waste handling:

Type of ACM to be abated:	<input type="checkbox"/> Surfacing	<input type="checkbox"/> Mechanical	<input type="checkbox"/> Other		
Engineering Controls:	<input type="checkbox"/> Wet Methods	<input type="checkbox"/> Glove Bag	<input type="checkbox"/> NPE	<input type="checkbox"/> AFD	<input type="checkbox"/> Other:
Work Practices:	<input type="checkbox"/> Intact Removal	<input type="checkbox"/> Manual	<input type="checkbox"/> Mechanical	<input type="checkbox"/> Other:	

7) Asbestos Waste Transporter (if applicable)**Revised?**

Transporter #1 Name:			
Address:		Contact Person:	
City:	State:		Zip: -
Email:	Phone: () -		Fax: () -
Transporter #2 Name (if applicable):			
Address:		Contact Person:	
City:	State:		Zip: -
Email:	Phone: () -		Fax: () -

8) Asbestos Waste Disposal Site (if applicable)**Revised?**

Name:			
Address:		Contact Person:	
City:	State:		Zip: -
Email:	Phone: () -		Fax: () -

9) Emergency Demolition (complete if you checked "Emergency" above and "Demolition" for any project)**Revised?**

A copy of the issued order, including the following information, must be attached to this notification.			
Government Official Issuing Order:		Title:	
Agency:		Authority of Order (Citation of Code):	
Date of Order: / /		Demolition Date: / /	

10) Emergency Renovation/Abatement (complete if you checked "Emergency" above and "Renovation/Abatement" for any project)**Revised?**

Date of Emergency: / /		Time of Emergency: : <input type="checkbox"/> a.m. <input type="checkbox"/> p.m.	
Description of Sudden, Unexpected Event:			
Explanation of how the event caused unsafe conditions or equipment damage:			

11) Attestation**Revised?**

In accordance with Ohio Administrative Code rule 3745-20-03(A)(4)(p), I certify that at least one person trained as required by paragraph (B) of rule 3745-20-04 of the Administrative Code will supervise the stripping and removal described by this notification. I acknowledge that the submission of false or misleading statements is prohibited by law and I certify that facts contained in this notification are true, accurate, and complete.

Signature:	Date: / /
Name:	Title:
Organization:	



ASBESTOS INSPECTION REPORTING TEMPLATE | OCTOBER 2022

Please complete Section 2 for the address included with this notification. If the project is an "Installation" per OAC 3745-20, complete a separate Section 2 page for each address associated with this notification.

Ohio EPA Use Only Project ID #:

A. Facility Description

Revised?

Building Name (if applicable):	Site Location (specific):		
Address:			
City:	State: OH	Zip: -	
Building Size (square feet):		No. of Floors:	Age:
Present Use:		Prior Use:	

B. Type of Operation (check all that apply)

Revised?

<input type="checkbox"/> Demolition	<input type="checkbox"/> Renovation/Abatement – Type: <input type="checkbox"/> Removal <input type="checkbox"/> Repair <input type="checkbox"/> Encapsulation <input type="checkbox"/> Enclosure
-------------------------------------	--

C. Asbestos Present (check one)

Revised?

<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> No, previously abated	Year Abated:
------------------------------	-----------------------------	--	--------------

D. Approximate Amount of Asbestos-Containing Materials (complete table below and Section 1 #6 if asbestos is present)

Revised?

	Material to be Removed			Material NOT to be Removed	
	RACM	Non-friable Asbestos-Containing Material		Non-friable Asbestos-Containing Material	
		Category I	Category II	Category I	Category II
Pipes (linear feet)					
Surface area on other facility components (ft ²)					
Volume if length or area cannot be measured (ft ³)					

E. Asbestos Abatement Schedule and Abatement Specialist (original notification is required 10 working days prior to the start of work)

Revised?

Setup Date: / /	Abatement Date: / /	Complete Date: / /					
(Shift 1) Time start/end on site	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Sunday
Abatement Specialist Name:			Certification #: AS			Expiration Date: / /	
(Shift 2) Time start/end on site	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Sunday
Abatement Specialist Name:			Certification #: AS			Expiration Date: / /	

F. Demolition Contractor (if applicable)

Revised?

Name:			
Address:	Contact Person:		
City:	State:	Zip: -	
Email:	Phone: () -	Fax: () -	

G. Demolition Schedule (original notification is required 10 working days prior to the start of work)

Revised?

Start Date: / /	Complete Date: / /
-----------------	--------------------

H. Project Hold

Revised?

Asbestos Abatement Offsite/On Hold as of Date: / /	Asbestos Abatement On Site/Off Hold, Work Resume Date: / /
Demolition Offsite/On Hold as of Date: / /	Demolition On Site/Off Hold, Work Resume Date: / /

