SHEET NUMBER												PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
									7	8	10	01/IMS	02/NHS						
																		TRAFFIC CONTROL	
											100.69	27.41	73.28	807	12010	100.69	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, EDGE LINE, 6"	
											51.61	12.53	39.08	807	12110	51.61	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, LANE LINE, 6"	
											8.17		8.17	807	12200	8.17	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, CENTER LINE	
											4,118	2,228	1,890	807	12300	4,118	FT	WET REFLECTIVE EPOXY PAVEMENT MARKING, CHANNELIZING LINE, 8"	
											23,978	15,018	8,960	807	12310	23,978	FT	WET REFLECTIVE EPOXY PAVEMENT MARKING, CHANNELIZING LINE, 12"	
											12,033	8,018	4,015	807	12410	12,033	FT	WET REFLECTIVE EPOXY PAVEMENT MARKING, DOTTED LINE, 6"	
											15.88		15.88	850	10000	15.88	MILE	GROOVING FOR 4" RECESSED PAVEMENT MARKING, (ASPHALT)	
											53.24	37.36	15.88	850	10010	53.24	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
											6,752	6,752		850	10110	6,752	FT	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
											37		37	850	10120	37	FT	GROOVING FOR 8" RECESSED PAVEMENT MARKING, (ASPHALT)	
											15,018	15,018		850	10130	15,018	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT)	
											0.46		0.46	850	20000	0.46	MILE	GROOVING FOR 4" RECESSED PAVEMENT MARKING, (CONCRETE)	
											99.06	2.58	96.48	850	20010	99.06	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE)	
											5,281	1,266	4,015	850	20110	5,281	FT	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE)	
											4,081	2,228	1,853	850	20120	4,081	FT	GROOVING FOR 8" RECESSED PAVEMENT MARKING, (CONCRETE)	
											8,960		8,960	850	20130	8,960	FT	GROOVING FOR 12" RECESSED PAVEMENT MARKING, (CONCRETE)	
																		MAINTENANCE OF TRAFFIC	
										120		30	90	614	11110	120	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
									41			12	29	614	12460	41	EACH	WORK ZONE MARKING SIGN	
									4			1	3	614	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	7
									6			2	4	614	20560	6	MILE	WORK ZONE LANE LINE, CLASS III, 6", 642 PAINT	
									1				1	614	21550	1	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
																		INCIDENTALS	
												LS	LS	103	05000	LS		PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYMENT BOND	
												LS	LS	614	11000	LS		MAINTAINING TRAFFIC	
												LS	LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER NRE

REVIEWER JMF 04/01/26

PROJECT ID 124245

SHEET P.9 TOTAL 10

D02 R-WR & WR FY27

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 11/23/2026 TIME: 7:37:51 AM PLTDRV: OHDOT_PDF_Color.pltcfg PENTBL: OHDOT_PenC.tbl USER: Nicholas.Emerine@dot.ohio.gov WORKSPACE: OHDOTCEv02 WORKSET: 124245 PRODUCT: OpenRoadsDesigner 24.00.00.205
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 02_D02\124245\400-Engineering\Roadway\Sheets\124245_GG001.dgn

LOCATION	COUNTY	LOCATION DESCRIPTION	S.L.M. TO S.L.M.			FUNDING	PAVEMENT TYPE	SIDE	807 WET REFLECTIVE EPOXY PAVEMENT MARKING, EDGE LINE, 6" WHITE MILE	807 WET REFLECTIVE EPOXY PAVEMENT MARKING, EDGE LINE, 6" YELLOW MILE	807 WET REFLECTIVE EPOXY PAVEMENT MARKING, LANE LINE, 6" MILE	807 WET REFLECTIVE EPOXY PAVEMENT MARKING, CENTER LINE MILE	807 WET REFLECTIVE EPOXY PAVEMENT MARKING, CHANNELIZING LINE, 8" WHITE FT	807 WET REFLECTIVE EPOXY PAVEMENT MARKING, CHANNELIZING LINE, 12" WHITE FT	807 WET REFLECTIVE EPOXY PAVEMENT MARKING, DOTTED LINE, 6" WHITE FT	807 WET REFLECTIVE EPOXY PAVEMENT MARKING, DOTTED LINE, 6" YELLOW FT	850 GROOVING FOR 4" RECESSED PAVEMENT MARKING, (ASPHALT) MILE	850 GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT) MILE	850 GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT) FT	850 GROOVING FOR 8" RECESSED PAVEMENT MARKING, (ASPHALT) FT	850 GROOVING FOR 12" RECESSED PAVEMENT MARKING, (ASPHALT) FT	850 GROOVING FOR 4" RECESSED PAVEMENT MARKING, (CONCRETE) MILE	850 GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE) MILE	850 GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE) FT	850 GROOVING FOR 8" RECESSED PAVEMENT MARKING, (CONCRETE) FT	850 GROOVING FOR 12" RECESSED PAVEMENT MARKING, (CONCRETE) FT
1	HEN	US-24	15.86	TO	19.57	02/NHS	CONCRETE	LT/RT	7.42	7.42	7.42											22.26			
1	LUC	US-24	0.00	TO	11.57	02/NHS	CONCRETE	LT/RT	23.14	23.14	23.14			8960	3335							69.42	3335		8960
1	LUC	US-24	SR-295 INTERCHANGE			02/NHS	CONCRETE	LT/RT	0.95	0.91	0.09											1.95			
1	LUC	US-24	SR-64 INTERCHANGE			02/NHS	CONCRETE	LT/RT	0.98	0.96	0.07		660									2.01		660	
2	WOO	IR-75 NORTHBOUND	24.96	TO	26.51	01/IMS	ASPHALT	RT	1.55	1.55	2.03			3770				5.13			3770				
2	WOO	IR-75 SOUTHBOUND	24.96	TO	26.86	01/IMS	ASPHALT	LT	1.90	1.90	2.86			3396	895			6.66	895		3396				
2	WOO	NB-75 TO NB-475 RAMP	0.08	TO	0.39	01/IMS	ASPHALT	RT	0.31	0.31								0.62							
2	WOO	NB-75 TO NB-475 RAMP	0.39	TO	0.45	01/IMS	CONCRETE	RT	0.06	0.06												0.12			
2	WOO	NB-75 TO NB-475 RAMP	0.45	TO	0.49	01/IMS	ASPHALT	RT	0.04	0.04								0.08							
2	WOO	NB-75 TO NB-475 RAMP	0.49	TO	0.54	01/IMS	CONCRETE	RT	0.05	0.05												0.10			
2	WOO	NB-75 TO NB-475 RAMP	0.54	TO	0.94	01/IMS	ASPHALT	RT	0.40	0.40				860	1072			0.80	1072		860				
2	WOO	SB-475 TO NB-75 RAMP	34.13	TO	33.92	01/IMS	ASPHALT	LT	0.21	0.21	0.21							0.63							
2	WOO	SB-475 TO NB-75 RAMP	33.92	TO	33.87	01/IMS	CONCRETE	LT	0.05	0.05	0.05											0.15			
2	WOO	SB-475 TO NB-75 RAMP	33.87	TO	33.64	01/IMS	ASPHALT	LT	0.23	0.23	0.17				1622			0.63	1622						
2	WOO	SB-75 TO NB-475 RAMP	33.53	TO	34.30	01/IMS	ASPHALT	LT	0.77	0.77	0.77			576	515			2.31	515		576				
2	WOO	SB-475 TO SB-75 RAMP	0.60	TO	0.29	01/IMS	ASPHALT	LT	0.31	0.31								0.62							
2	WOO	SB-75 TO SR-25 RAMP	33.67	TO	34.37	01/IMS	ASPHALT	LT	0.70	0.70				1210	15			1.40	15		1210				
2	WOO	IR-475 SOUTHBOUND	0.68	TO	2.06	01/IMS	ASPHALT	LT	1.38	1.38	1.59			2296	793			4.35	793		2296				
2	WOO	IR-475 SOUTHBOUND	2.06	TO	2.10	01/IMS	CONCRETE	LT	0.04	0.04	0.04											0.12			
2	WOO	IR-475 SOUTHBOUND	2.10	TO	2.22	01/IMS	ASPHALT	LT	0.12	0.12	0.12							0.36							
2	WOO	IR-475 SOUTHBOUND	2.22	TO	2.25	01/IMS	CONCRETE	LT	0.03	0.03	0.03											0.09			
2	WOO	IR-475 SOUTHBOUND	2.25	TO	3.93	01/IMS	ASPHALT	LT	1.68	1.68	1.68							5.04							
2																									
2	WOO	IR-475 NORTHBOUND	0.95	TO	2.05	01/IMS	ASPHALT	RT	1.10	1.10	1.10			2910	1840			3.30	1840		2910				
2	WOO	IR-475 NORTHBOUND	2.05	TO	2.09	01/IMS	CONCRETE	RT	0.04	0.04	0.04											0.12			
2	WOO	IR-475 NORTHBOUND	2.09	TO	2.22	01/IMS	ASPHALT	RT	0.13	0.13	0.13							0.39							
2	WOO	IR-475 NORTHBOUND	2.22	TO	2.25	01/IMS	CONCRETE	RT	0.03	0.03	0.03											0.09			
2	WOO	IR-475 NORTHBOUND	2.25	TO	3.93	01/IMS	ASPHALT	RT	1.68	1.68	1.68							5.04							
2	WOO	SR-25 INTERCHANGE	NB-475	TO	SR-25	01/IMS	CONCRETE	RT	0.20	0.19			590		224							0.39	224	590	
2	WOO	SR-25 INTERCHANGE	SR-25	TO	NB-475	01/IMS	CONCRETE	RT	0.24	0.23			687		437							0.47	437	687	
2	WOO	SR-25 INTERCHANGE	SB-475	TO	SR-25	01/IMS	CONCRETE	LT	0.22	0.24			365		100							0.46	100	365	
2	WOO	SR-25 INTERCHANGE	SR-25	TO	SB-475	01/IMS	CONCRETE	LT	0.24	0.23			586		505							0.47	505	586	
3	WOO	US-20	12.36	TO	13.92	02/NHS	ASPHALT	LT/RT	3.12		3.12	3.12					6.24	6.24							
3	WOO	US-20	13.60	TO	13.62	02/NHS	CONCRETE	LT/RT	0.04		0.04	0.04									0.08	0.08			
3	WOO	US-20	13.62	TO	13.92	02/NHS	ASPHALT	LT/RT	0.60		0.60	0.60	37				1.20	1.20		37					
3	WOO	US-20	13.92	TO	14.02	02/NHS	CONCRETE	LT/RT	0.20		0.20	0.10	778		180	180					0.20	0.40	360	778	
3	SAN	US-20	0.00	TO	0.09	02/NHS	CONCRETE	LT/RT	0.18		0.18	0.09	415		220	100					0.18	0.36	320	415	
3	SAN	US-20	0.09	TO	2.20	02/NHS	ASPHALT	LT/RT	4.22		4.22	4.22					8.44	8.44							
TOTALS CARRIED TO GENERAL SUMMARY									54.56	46.13	51.61	8.17	4118	23978	11753	280	15.88	53.24	6752	37	15018	0.46	99.06	5281	4081	8960

SUBSUMMARY

DESIGN AGENCY

DESIGNER NRE

REVIEWER JMF 04/01/26

PROJECT ID 124245

SHEET P.10 TOTAL 10

D02 R-WR & WR FY27

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 11/23/2026 TIME: 7:37:57 AM PLTDRV: OHDOT_PDF_Color.pltdg PENTBL: OHDOT_PenC.tbl USER: Nicholas.Emerine@dot.ohio.gov WORKSPACE: OHDOTCEv02 WORKSET: 124245 PRODUCT: OpenRoadsDesigner 24.00.00.205
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 02_D0211242445\400-Engineering\Roadway\Sheets\1242245_GC001.dgn