

PROJECT DESCRIPTION

THE PURPOSE OF THIS PROJECT IS TO REMOVE TREES AS PER ITEM 201, AND PRUNE TREES AS PER ITEM 666. ALL TREES SHALL BE REMOVED FROM THE RIGHT-WAY AND DISPOSED OF AS PER SECTIONS 105.16 AND 107.10 OF THE C&MS. THIS MAY INCLUDE WORK ON ANY OR ALL ROUTES AND ODOT FACILITIES IN THE EIGHT COUNTIES OF DISTRICT THREE, OF THE OHIO DEPARTMENT OF TRANSPORTATION.

BEFORE BEGINNING WORK AT ANY LOCATION, CONTACT THE OHIO UTILITIES PROTECTION SERVICE AT OHIO811.ORG AND/OR ANY UTILITIES WHICH MAY BE IN THE AREA. TAKE CARE TO NEITHER DISTURB NOR DISRUPT UTILITY SERVICE.

CLEAN UP AND DISPOSE OF TREES, BRANCHES, CHIPS AND OTHER DEBRIS CREATED BY PERFORMING PROJECT WORK. BURNING IS PROHIBITED.

RESTORE ALL AREAS DISTURBED DUE TO PERFORMING THIS WORK, INCLUDING SEEDING AND MULCHING ALL AREAS DESIGNATED BY THE ENGINEER. RESTORATION OF AREAS SHALL CONFORM TO 105.16 AND 107.10 OF C&MS. SEEDING AND MULCHING IS INCIDENTAL TO THE VARIOUS BID ITEMS OF THIS PLAN.

RESPONSIBILITY FOR DAMAGE CLAIMS

AT THE PRECONSTRUCTION MEETING SUBMIT A FULL DISCLOSURE OF OPERATIONAL AND ENVIRONMENTAL PLANS AS FOLLOWS:

- 1) A CONTINGENCY PLAN FOR FIELD OPERATIONS, AND
- 2) A RESPONSIBLE FOLLOW-UP COMPLAINT PROCEDURE

TAKE EVERY PRECAUTION IN OPERATIONS TO AVOID PROPERTY DAMAGE AND ASSUME ALL LIABILITY FOR ANY DAMAGE RESULTING FROM CONTRACTOR'S ACTIONS, ERRORS, OR OMISSIONS, AND HOLD THE STATE OF OHIO DEPARTMENT OF TRANSPORTATION HARMLESS. INVESTIGATE ALL DAMAGE COMPLAINTS PROMPTLY.

ANY DAMAGE TO PRIVATE OR ODOT PROPERTY SHALL BE IMMEDIATELY REPAIRED OR REPLACED, AT THE DIRECTION OF THE ENGINEER, BY THE CONTRACTOR AT NO COST TO THE STATE.

METHOD OF AUTHORIZATION FOR ITEM 201

DO NOT PERFORM ANY TREE REMOVAL UNTIL AN AUTHORIZATION FORM IS RECEIVED FROM THE ENGINEER.

A COPY OF THE TREE REMOVAL WORK ORDER FORM IS INCLUDED IN THIS PLAN.

OBTAIN A COMPLETED, SIGNED WORK ORDER FOR EACH LOCATION BEFORE BEGINNING WORK. WHEN MULTIPLE ORDERS HAVE BEEN ISSUED AND REMAIN INCOMPLETE, WORK ON THE LOCATIONS IN ORDER OF PRIORITY AS DIRECTED BY THE ENGINEER.

WITHIN 21 DAYS OF RECEIVING A WORK ORDER, COMPLETE THE WORK. COMPLETE ALL WORK BEFORE BEGINNING WORK AT NEW LOCATIONS UNLESS OTHERWISE APPROVED BY THE ENGINEER.

WORK ORDER INTERIM COMPLETION DATE

WITHIN 21 DAYS OF RECEIVING A WORK ORDER THE CONTRACTOR SHALL COMPLETE THE WORK ORDER.

21 DAYS AFTER NOTIFICATION SHALL BE CONSIDERED AN INTERIM COMPLETION DATE. A DISINCENTIVE OF \$1000.00 PER DAY SHALL BE APPLIED FOR ANY PORTION OF A CALENDAR DAY THAT HAS EXCEEDED AN INTERIM COMPLETION DATE.

ITEM 201 TREE REMOVED, VARIOUS SIZES, (WORK ORDER)

MULTI-STEM TREE SIZES SHALL BE DETERMINED BY MEASURING THE DIAMETER OF EACH INDIVIDUAL LEADER AT A HEIGHT OF 54 INCHES ABOVE THE GROUND.

ANY TREE UNDER 3 INCHES WITHIN A 10 FOOT RADIUS OF ANY PAID TREE SHALL BE REMOVED AND BE INCIDENTAL TO ITEM OF WORK.

PAYMENT FOR ITEM 201 TREE REMOVED, VARIOUS SIZES, AS PER PLAN SHALL BE AT THE UNIT BID PRICE AND SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO PERFORM THE ABOVE-DESCRIBED WORK.

100	EACH	TREE REMOVED, 18" (WORK ORDER)
20	EACH	TREE REMOVED, 30" (WORK ORDER)
10	EACH	TREE REMOVED, 48" (WORK ORDER)
6	EACH	TREE REMOVED, 60" (WORK ORDER)

ITEM 201: TREE REMOVED, 3" - 12" SIZE (WORK ORDER)

THIS WORK CONSISTS OF CLEARING SMALL TREES RANGING IN SIZE FROM 3 TO 12 INCH DIAMETER.

PAYMENT FOR ITEM 201: TREE REMOVED, 3" - 12" SIZE SHALL BE AT THE UNIT BID PRICE AND SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO PERFORM THE ABOVE-DESCRIBED WORK.

200	EACH	SPECIAL, TREE REMOVED, 3" - 12" (WORK ORDER)
-----	------	--

ITEM 201 TREE REMOVED, VARIOUS SIZES, (CONSTRUCTION PROJECTS)

FOR INFORMATION ONLY, AND FOR BIDDING CONSIDERATIONS, THE FOLLOWING QUANTITIES OF TREES ARE TO BE REMOVED BY THIS CONTRACT ASSOCIATED WITH THE PROJECT ID (PID). ADDITIONAL INFORMATION MAY BE FOUND ON THE PROJECT BY CONTACTING THE ODOT DISTRICT THREE OFFICE. THE BELOW ESTIMATED QUANTITIES ARE CARRIED TO THE GENERAL SUMMARY.

PROJECT IDENTIFICATION		ITEM 201 TREE REMOVED				
PID	CRS	SPECIAL, 3" - 12"	18" (>12" - 24")	30" (>24" - 36")	48" (>36" - 60")	60" (OVER 60")
114968	ASD/WAY-71/83-13.75/10.73	23	10			
116773	ASD-250-22.09/22.57	24	27			
118353	ERI-269-3.67	2	2	3		
116774	HUR-250-12.91	6	1			
120749	LOR-057-6.38	25	8			1
122038	LOR-057-20.90	8	3			
120472	MED-042-6.37	4				
116777	MED-094-19.93	22	9	1		
117045	RIC-95-4.48-11.25		4	1		
114960	RIC-96/603-16.73/7.94	7	7	2	1	
108034	RIC-309-08.73	53	2	1		
120153	WAY-585-6.49	45	11	3	2	
TOTAL		219	84	11	3	1

ENDANGERED BAT HABITAT REMOVAL

THE PROJECT IS LOCATED WITHIN THE KNOWN HABITAT RANGES OF THE FEDERALLY LISTED AND PROTECTED INDIANA BAT AND NORTHERN LONG-EARED BAT. NO TREES SHALL BE REMOVED UNDER THIS PROJECT FROM APRIL 1 THROUGH SEPTEMBER 30. ALL NECESSARY TREE REMOVAL SHALL OCCUR FROM OCTOBER 1 THROUGH MARCH 31. THIS REQUIREMENT IS NECESSARY TO AVOID AND MINIMIZE IMPACTS TO THESE SPECIES AS REQUIRED BY THE ENDANGERED SPECIES ACT. FOR THE PURPOSES OF THIS NOTE, A TREE IS DEFINED AS A LIVE, DYING, OR DEAD WOODY PLANT, WITH A TRUNK THREE INCHES OR GREATER IN DIAMETER AT A HEIGHT OF 4.5 FEET ABOVE THE GROUND SURFACE, AND WITH A MINIMUM HEIGHT OF 13 FEET.

INTERIM COMPLETION DATE REQUIREMENTS

ALL NECESSARY TREE REMOVAL FOR SITE PID 117045 (RIC-95-4.48-11.25) SHALL OCCUR FROM NOVEMBER 15 TO MARCH 15.

THE CONTRACT WILL BE SUBJECT TO DAILY DISINCENTIVES FOR FAILURE TO COMPLETE ALL THE REQUIRED WORK, AND ASSOCIATED INCIDENTALS RELATED TO THE WORK, IN THE AMOUNT OF \$800 PER DAY. DAILY DISINCENTIVES ARE APPLICABLE TO THE WORK REQUIRED TO THE INTERIM COMPLETION DATE ONLY. THE CONTRACT IS STILL SUBJECT TO LIQUIDATED DAMAGES AS OUTLINED IN C&MS 108.07 FOR THE REMAINDER OF THE CONTRACT.

GENERAL SUMMARY	
DESIGN AGENCY DISTRICT 3  ENGINEERING TEAM THREE	
DESIGNER JED	
REVIEWER KCK	02/2026
PROJECT ID 116009	
SHEET P.004	TOTAL P.005