SHEET NUM.											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
					19	20	21	26	27	28	01/SAF/OT/ AKRON	02/SAF/OT/ CANT	03/SAF/OT/ YOUN						
																		ROADWAY	
											LS	LS	LS	201	11000	LS		CLEARING AND GRUBBING	
								159	8	146	159	8	146	202	23000	313	SY	PAVEMENT REMOVED	
					300			987		564	1,167		684	202	30001	1,851	SF	WALK REMOVED, AS PER PLAN	6
					100			556	21	1,028	616	21	1,068	202	32001	1,705	FT	CURB REMOVED, AS PER PLAN	6
								88	7	71	88	7	71	202	32501	166	FT	CURB AND GUTTER REMOVED, AS PER PLAN	6
								18			18			203	20000	18	CY	EMBANKMENT	
								53			53			204	10000	53	SY	SUBGRADE COMPACTION	
								1,396	258	467	1,396	258	467	608	10001	2,121	SF	4" CONCRETE WALK, AS PER PLAN	7
					560						360		200	608	12001	560	SF	5" CONCRETE WALK, AS PER PLAN	7
					400				542	6,759		542	7,159	608	52001	7,701	SF	CURB RAMP, AS PER PLAN	6
					112	104	504	27		42	107	608	74	608	53021	789	SF	DETECTABLE WARNING, AS PER PLAN	6
					800			4,116			4,916			608	98000	4,916	SF	WALKWAY, MISC.: AKRON CURB RAMP	6
										319			319	608	98000	319	SF	WALKWAY, MISC.:REMOVE AND REUSE DECORATIVE BRICK WALK	6
																		EROSION CONTROL	
											1,000	1,000	1,000	832	30000	3,000	EACH	EROSION CONTROL	
																		PAVEMENT	
								171	23	308	171	23	308	251	01001	502	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), AS PER PLAN	6
								137	8	130	137	8	130	253	01001	275	SY	PAVEMENT REPAIR, AS PER PLAN	6
								22			22			452	12011	22	SY	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC 1P, AS PER PLAN	6
								41	6		41	6		609	12001	47	FT	COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN	7
								120		126	120		126	609	26001	246	FT	CURB, TYPE 6, AS PER PLAN	7
								189	54	152	189	54	152	609	72001	395	SY	CONCRETE MEDIAN, AS PER PLAN	7

TRAFFIC GENERAL SUMMARY

DESIGN AGENCY

DESIGNER
RSH

REVIEWER
LAS 10/23/20

PROJECT ID
113278

SHEET 15 TOTAL 92

D04 PSIP Phase 2

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 3/19/2021 TIME: 1:18:50 PM USER: rhanna
Q:\ODOT_OP\0117061A.00 - STW-Safety Dsgn 2019 PID108656\003 PSIP D4 Final Dsn CE Clean\113278\400-Engineering\Traffic\Sheets\113278_TG001.dgn