



MAPS ARE FOR CONVENIENCE ONLY,
DESIGNATED ROUTES AND LOCATIONS
SHALL BE GOVERNED BY DATA SHEETS.

PORTION TO BE IMPROVED ———

I:\ProjectData\05\102498\Design\Roadway\Sheets\102498_GM005.dgn Sheet 9/10/2021 1:41:20 PM jutzl

I:\ProjectData\05\02498\Design\Roadway\Sheets\02498_G0006.dgn Sheet 10/6/2021 10:55:14 AM jluTZI

LICKING COUNTY RAISED PAVEMENT MARKERS														
LOCATION	COUNTY	ROUTE	BEGIN LOG POINT SLM	END LOG POINT SLM	LENGTH		RPM REFLECTOR	PRISMATIC RETRO-REFLECTOR COLORS					REMARKS	
								ONE-WAY		TWO-WAY				
					MILES	LIN.FT.	EACH	WHITE	YELLOW	YELLOW / YELLOW	WHITE / RED	YELLOW / RED		
1	LIC	S.R. 16	7.22	14.10	6.88	36,326	720	64		584	72		PATASKALA CORP. TO S.R. 37	
			14.10	14.24	0.14	739	S.R. 16/37 SE RAMP (SEE NEXT SHEET)							
		S.R. 16 EB	14.24	16.96	2.72	14,362	197				197		S.R. 37 TO NEWARK CORP.	
		S.R. 16 WB	14.24	16.96	2.72	14,362	199				199		S.R. 37 TO NEWARK CORP.	
LOCATION 1 TOTAL							1,116							
2	LIC	S.R. 37 EB	12.22	15.90	3.68	19,430	167	162			5		S.R. 37 SLM 16.21 = S.R. 16 SLM 14.24	
			15.90	16.21	0.31	1,637	14	14						
		S.R. 37 WB	12.22	15.96	3.74	19,747	172	165			7		S.R. 37 SLM 16.21 = S.R. 16 SLM 14.24	
			15.96	16.21	0.25	1,320	26	11			15			
LOCATION 2 TOTAL							379							
3	LIC	U.S. 40	10.25	13.26	3.01	15,893	322	16		201	105		KIRKERSVILLE CORP. TO S.R. 37	
			13.26	14.39	1.13	5,966	90	16		74				S.R. 37 TO HEBRON CORP.
				16.41	19.61	3.20	16,896	242	16		223	3		HEBRON CORP. TO S.R. 13
				19.61	28.51	8.90	46,992	607	16		591			S.R. 13 TO 4 LANE TRANSITION
LOCATION 3 TOTAL							939							
4	LIC	U.S. 62	0.00	3.13	3.13	16,526	208			208		FRANKLIN CO. TO JOHNSTOWN CORP.		
			5.41	10.57	5.16	27,245	341			341			JOHNSTOWN CORP. TO SLM	
LOCATION 4 TOTAL							549							
5	LIC	I.R. 70 EB	9.65	15.72	6.07	32,050	319	268			51		2-LANE	
			15.72	19.43	3.71	19,589	371	317			54		3-LANE	
		I.R. 70 WB	9.65	15.72	6.07	32,050	310	268			42		2-LANE	
			15.72	19.43	3.71	19,589	367	317			50		3-LANE	
LOCATION 5 TOTAL							1,367							
6	LIC	S.R. 158	0.00	0.77	0.77	4,066	51			51		FAIRFIELD CO. TO CONCRETE PVMT.		
			0.77	1.13	0.36	1,901	75			40	35	CONCRETE PVMT.		
			1.13	2.28	1.15	6,072	108	32		76		CONCRETE PVMT. TO U.S. 40		
LOCATION 6 TOTAL							234							
7	LIC	S.R. 161 EB	1.01	1.66	0.65	3,432	29	29					NEW ALBANY CORP. TO MINK ST.	
			1.66	2.99	1.33	7,022	92	59			33		MINK ST. INTERCHANGE	
			2.99	8.84	5.85	30,888	318	258			60		MINK ST. TO S.R. 37	
		S.R. 161 WB	1.01	1.66	0.65	3,432	29	29					NEW ALBANY CORP. TO MINK ST.	
		1.66	2.99	1.33	7,022	93	59			34		MINK ST. INTERCHANGE		
		2.99	8.84	5.85	30,888	316	258			58		MINK ST. TO S.R. 37		
	LOCATION 7 TOTAL							877						
	8	LIC	S.R. 310	1.72	2.61	0.89	4,699	148	32		84	32	S.R. 310 TO PATASKALA CORP.	
5.52				10.05	4.53	23,918	449	54		350	45	PATASKALA CORP. TO S.R. 161		
10.05				13.45	3.40	17,952	304	39		238	27	S.R. 161 TO S.R. 37		
LOCATION 8 TOTAL							901							
9	LIC	S.R. 586	0.00	11.35	11.35	59,928	935	32		903		MUSKINGUM CO. TO KNOX CO.		
LOCATION 9 TOTAL							935							
10	LIC	S.R. 668	0.00	2.73	2.73	14,414	321	16		305		MUSKINGUM CO. TO U.S. 40		
LOCATION 10 TOTAL							321							
LICKING COUNTY TOTAL (CARRIED TO NEXT SHEET)							7,618							

LICKING COUNTY RAISED PAVEMENT MARKERS

LOCATION	COUNTY	INTERCHANGE	RAMP	PAVEMENT TYPE	621 RPM REFLECTOR	PRISMATIC RETRO-REFLECTOR COLORS					REMARKS
						ONE-WAY		TWO-WAY			
						WHITE	YELLOW	YELLOW / YELLOW	WHITE / RED	YELLOW / RED	
1A	LIC	S.R. 16/ S.R. 37	NW RAMP	ASPHALT	16					16	
			NW LOOP		32			11	21		
			SE RAMP		9				9		
			SW RAMP		29			11	18		
LOCATION 1A TOTAL					86						
5A	LIC	I.R. 70/ S.R. 37	NW RAMP	CONCRETE	10					10	
			NE RAMP		48			30	18		
			SE RAMP		10				10		
			SW RAMP		48			30	18		
LOCATION 5A TOTAL					116						
5B	LIC	I.R. 70/ S.R.79	NW RAMP	CONCRETE	21					21	
			NE RAMP		44			18	26		
			NE LOOP		13				13		
			SE RAMP		21				21		
			SW RAMP		47			21	26		
			SW LOOP		12				12		
LOCATION 5B TOTAL					158						
7A	LIC	S.R. 161/ BEECH RD.	NW RAMP	CONCRETE	24			7	17		
			NE RAMP		63			44	19		
			SE RAMP		23			7	16		
			SW RAMP		50			26	24		
LOCATION 7A TOTAL					160						
7B	LIC	S.R. 161/ MINK RD.	NW RAMP	CONCRETE	12					12	
			NE RAMP		51			33	18		
			SE RAMP		14				14		
			SW RAMP		43			27	16		
LOCATION 7B TOTAL					120						
7C	LIC	S.R. 161/ S.R. 310	NW RAMP	CONCRETE	14					14	
			NE RAMP		42			22	20		
			SE RAMP		16				16		
			SW RAMP		47			22	25		
LOCATION 7C TOTAL					119						
7D	LIC	S.R. 161/ S.R. 37	NW RAMP	CONCRETE	15					15	
			NE RAMP		42			21	21		
			SE RAMP		14				14		
			SW RAMP		38			16	22		
LOCATION 7D TOTAL					109						
TOTAL CARRIED FROM PREVIOUS SHEET					7,618						
LICKING COUNTY TOTAL (CARRIED TO GENERAL SUMMARY)					8,486						

I:\ProjectData\05\102498\Design\Roadway\Sheets\02498_G0007.dgn Sheet 9/10/2021 1:44:32 PM jlutzi

CALCULATED
LIME
CHECKED
JSL

LICKING SUB-SUMMARY (RAMPS)

D05 - RPM - FY2022

17
21

I:\ProjectData\05\02498\Design\Roadway\Sheets\02498_GG00.dgn Sheet 9/10/2021 4:56 PM jjutzi

SHEET NUMBER									PLAN SPLIT	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET
2	3	11	12	14	15	17	19	20	01/NFP/OT						
TRAFFIC CONTROL															
500									500	621	00101	500	EACH	RPM, AS PER PLAN	2
		9,936	4,536	9,504	3,515	8,486	7,573	5,144	48,694	621	00300	48,694	EACH	RPM REFLECTOR	
MAINTENANCE OF TRAFFIC															
	150								150	614	11110	150	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
INCIDENTALS															
									LS	614	11000		LS	MAINTAINING TRAFFIC	
									LS	624	10000		LS	MOBILIZATION	

<table border="1" style="width: 100%; height: 100%;"> <tr> <td style="text-align: center;">CALCULATED</td> <td style="text-align: center;">LIME</td> <td style="text-align: center;">CHECKED</td> <td style="text-align: center;">JSL</td> </tr> </table>	CALCULATED	LIME	CHECKED	JSL	GENERAL SUMMARY
CALCULATED	LIME	CHECKED	JSL		
D05 - RPM - FY 2022					
<table border="1" style="width: 100%; height: 100%;"> <tr> <td style="text-align: center;">21</td> <td style="text-align: center;">21</td> </tr> </table>		21	21		
21	21				