From: Shonk, Christopher
Sent: Wednesday, September 14, 2022 12:05 PM
To: DOT Cen Contracts AddendaD05
Subject: RE: Prebid Question for 220501, PID 102530

All,

The following Prebid question has been answered as follows:

Enter the answer below

Company	SMCI
Project Number	220501
Question	On plan sheet 20 of 21 calls for removal of curtain wall, is this being re-installed? if so,qty for concrete and rebar if needed should be added into general summary. Plan note on sheet 3 calls out removal only however "epoxy coating as per CMS 509.09" this would in apply that curtain wall is being re-installed. please advise.
Submitted	9/14/2022 11:50:09 AM
Answer	The curtain wall shown for removal on sheet 20 of 21 will not be re-installed. The epoxy coating is for the cut existing rebar ends after the removal.
Counter	4

Chris Shonk, P.E.
Project Manager
ODOT District 5
9600 Jacksontown Road SE, Jacksontown, Ohio 43030
740.323.5110
transportation.ohio.gov

OHIO DEPARTMENT OF TRANSPORTATION

From: Office of Contracts <Do.Not.Reply@dot.state.oh.us>
Sent: Wednesday, September 14, 2022 11:50 AM
To: DOT Cen Contracts AddendaD05 <Prebid.D05@dot.ohio.gov>

Cc: DOT Prebid <prebid@dot.ohio.gov>
Subject: Prebid Question for 220501, PID 102530

Project Number: 220501
PID: 102530
Question Number Counter: 4
Letting Date: 9/15/2022

Company: SMCI
Question:
On plan sheet 20 of 21 calls for removal of curtain wall, is this being re-installed? if so,qty for concrete and rebar if needed should be added into general summary. Plan note on sheet 3 calls out removal only however "epoxy coating as per CMS 509.09" this would in apply that curtain wall is being re-installed. please advise.

Reason Code: 08-Clarification

Click here to view this item

Please address the following Prebid Question as soon as possible, but no later than 2 working days from today's date. If the question will require a change to the contract documents (an addendum), you must respond within 2 working days that an addenda is forthcoming. All Prebid Questions submitted prior to 10AM, 4 working days prior to the bid opening require a response. Prebid Questions submitted after 10AM, 4 working days prior to a bid opening must be accepted and reviewed and a response should be provided if possible.

Reponses to any Prebid Questions that require Central Office input (i.e. DBE/EDGE Goal, Contractor % of Work, Website Issues) and addenda should be sent to Prebid@dot.state.oh.us.