


				PARTICIPATION	ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE
P.02	P.03-P.04	P.06		01/IMS/21	EXT.	TOTAL				SHEET
										NO.
									TRAFFIC CONTROL	
100.00		3735.86		3835.86	642 00104	3835.86	MILE	EDGE LINE, 6", TYPE 1		
50.00		1355.89		1405.89	642 00204	1405.89	MILE	LANE LINE, 6", TYPE 1		
50.00		1032.31		1082.31	642 00300	1082.31	MILE	CENTER LINE, TYPE 1		
5000		428285		433285	642 00404	433285	FT	CHANNELIZING LINE, 12", TYPE 1		
2500		199246		201746	642 01510	201746	FT	DOTTED LINE, 6", TYPE 1		
									MAINTENANCE OF TRAFFIC	
	80			80	614 11110	80	HOURL	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE		
									INCIDENTALS	
	LS			LS	614 11000	LS		MAINTAINING TRAFFIC		
	LS			LS	624 10000	LS		MOBILIZATION		
	4			4	624 15001	4	EACH	MOBILIZATION, AS PER PLAN, A		P.04
	4			4	624 15001	4	EACH	MOBILIZATION, AS PER PLAN, B		P.04


GENERAL SUMMARY

DESIGN AGENCY

 DESIGNER
RAM
 REVIEWER
 XXX MM-DD-YY
 PROJECT ID
105853
 SHEET TOTAL
 P.5 P.21

SHEET	COUNTY	642									
		00104	00104	00204	00300	00404	01510				
		EDGE LINE, 6", TYPE 1	EDGE LINE, 6", TYPE 1	LANE LINE, 6", TYPE 1	CENTER LINE, TYPE 1	CHANNELIZING LINE, 12", TYPE 1	DOTTED LINE, 6", TYPE 1				
		WHITE MILE	YLW. MILE	MILE	MILE	FEET	FEET				
P.07	DELAWARE COUNTY	340.31	69.26	142.99	144.17	32860	24580				
P.08	FAYETTE COUNTY	255.34	56.76	56.76	102.41	7060					
P.09	FRANKLIN COUNTY	110.74	72.68	115.60	22.11	44692	12914				
P.10	FRANKLIN COUNTY	56.99	56.99	91.95		43548	11120				
P.11	FRANKLIN COUNTY	62.02	62.02	90.28		55834	39690				
P.12	FRANKLIN COUNTY	67.89	55.39	61.70	6.34	36510.00	15650.00				
P.13	FRANKLIN COUNTY	176.36	176.36	402.16		27050	13480				
P.14	FRANKLIN COUNTY	34.21	34.21	6.46		56078	46262				
P.15	FRANKLIN COUNTY	28.43	28.43	10.63		58270	8440				
P.16	FRANKLIN COUNTY	53.25	37.83	68.87	14.18	30238	13920				
P.17	MADISON COUNTY	383.90	100.20	158.09	146.18	16680	13190				
P.18	MARION COUNTY	259.46	16.98	18.56	124.60	3770					
P.19	MORROW COUNTY	373.45	53.52	100.64	135.72	9930					
P.20	PICKAWAY COUNTY	349.73	12.88	12.94	169.07	1215					
P.21	UNION COUNTY	328.00	22.28	18.26	167.52	4550					
	SUBTOTAL	2880.07	855.79	1355.89	1032.31	428285	199246				
	TOTAL CARRIED TO GENERAL SUMMARY	3735.86	355.89	1032.31	428285	199246					

PAVEMENT MARKING SUBSUMMARY

ROUTE	SLM		TOTAL MILES	NUMBER OF APPLICATIONS	642							LOCATION	
	FROM	TO			EDGE LINE, 6", TYPE 1	EDGE LINE, 6", TYPE 1	LANE LINE, 6", TYPE 1	CENTER LINE, TYPE 1	CHANNELIZING LINE, 12", TYPE 1	DOTTED LINE, 6", TYPE 1	FROM	TO	
	MILE	MILE			MILE	MILE	FEET	FEET					
SR19	0.00	10.40	10.40	1	20.81			10.40				US-42	CRAWFORD CO. LINE
US42	0.00	25.77	25.77	1	47.98			25.77				DELAWARE CO. LINE	RICHLAND CO. LINE
SR61	0.00	3.33	3.33	0	PERFORMED WITH PID 110060							DELAWARE CO. LINE	PROJECT LIMITS
SR61	3.33	22.86	19.53	1	39.06			19.53				PROJECT LIMITS	PROJECT LIMITS
SR61	22.86	25.27	2.41	0	PERFORMED WITH PID 112847							PROJECT LIMITS	CRAWFORD CO. LINE
I71N	0.00	12.19	12.19	2	24.38	24.38	48.76					DELAWARE CO. LINE	PROJECT LIMITS
I71N	12.19	19.53	7.34	0	PERFORMED WITH PID 114110							PROJECT LIMITS	PROJECT LIMITS
I71N	19.53	19.92	0.39	2	0.78	0.78	1.56					PROJECT LIMITS	RICHLAND CO. LINE
I71S	19.92	19.53	0.39	2	0.78	0.78	1.56					RICHLAND COUNTY LINE	PROJECT LIMITS
	19.53	12.19	7.34	0	PERFORMED WITH PID 114110							PROJECT LIMITS	PROJECT LIMITS
	12.19	0.00	12.19	2	24.38	24.38	48.76					PROJECT LIMITS	DELAWARE CO. LINE
I71N	1.65		0.25	2	0.50	0.50		1160				RAMP TO	SR-61
I71N	2.14		0.24	2	0.48	0.48		700				RAMP FROM	SR-61
I71N	11.08		0.14	2	0.28	0.28		1250				RAMP EXIT	REST AREA
I71N	11.54		0.20	2	0.40	0.40		1440				RAMP ENTRANCE	REST AREA
I71S	11.39		0.12	2	0.24	0.24		1260				RAMP EXIT	REST AREA
I71S	10.96		0.17	2	0.34	0.34		1240				RAMP ENTRANCE	REST AREA
I71S	2.31		0.25	2	0.50	0.50		2200				RAMP FRAM	SR-61
I71S	1.82		0.23	2	0.46	0.46		680				RAMP TO	SR-61
SR95A	0.00	1.15	1.15	0	PERFORMED WITH PID 110582							BEGIN ROUTE AT SR-95R	END ROUTE AT SR-95R
SR95R	0.00	5.47	5.47	1	10.94			5.47				MARION CO. LINE	PROJECT LIMITS
SR95R	5.47	8.13	2.66	0	PERFORMED WITH PID 110582							PROJECT LIMITS	PROJECT LIMITS
SR95R	8.13	19.73	11.60	1	23.20			11.60				PROJECT LIMITS	KNOX CO. LINE
SR97	0.00	5.94	5.94	1	11.88			5.94				BEGIN ROUTE	END ROUTE
SR229	0.00	5.43	5.43	1	10.86			5.43				DELAWARE CO. LINE	PROJECT LIMITS
SR229	5.43	6.50	1.07	0	PERFORMED WITH PID 110583							PROJECT LIMITS	PROJECT LIMITS
SR229	6.50	15.28	8.78	1	17.56			8.78				PROJECT LIMITS	KNOX CO. LINE
SR314	0.00	26.02	26.02	2*	104.08			26.02				KNOX CO. LINE	RICHLAND CO. LINE
					*TWO APPLICATIONS OF EDGE LINE, ONE APPLICATION OF CENTERLINE TO BE USED ON MRW SR314								
SR529	0.00	8.33	8.33	1	16.66			8.33				MARION CO. LINE	END ROUTE AT SR 61
SR656	0.00	5.38	5.38	1	10.76			5.38				DELAWARE CO. LINE	END ROUTE AT SR 229
SR746	0.00	3.07	3.07	1	6.14			3.07				BEGIN ROUTE AT US-42	MARION CO. LINE
TOTAL CARRIED TO SUBUMMARY, SHEET P.06					373.45	53.52	100.64	135.72	9930				

DESIGN AGENCY

 DESIGNER
RAM
 REVIEWER
 XXX MM-DD-YY
 PROJECT ID
105853
 SHEET TOTAL
 P.19 P.21