Page #
ASPH CALC

PAVEMENT CALC SHEET 2

Split #	STATION RANGE			TYPICAL SECTION	SIDE	DISTANCE (D)	AVERAGE WIDTH (W)	SURFACE AREA (A) A=DxW/9	CADD GENERATED AREA	PAVEMENT REMOVED ASPHALT OPTION	PAVEMENT REMOVED, ASPHALT ASPHALT OPTION	SUBGRADE COMPACTION ASPHALT OPTION	PAVEMENT PLANING, ASPHALT CONCRETE ASPHALT OPTION	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (447), AS PER PLAN ASPHALT OPTION	NON-TRACKING TACK COAT ASPHALT OPTION	ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446) ASPHALT OPTION	ASPHALT CONCRETE BASE, PG64-22 ASPHALT OPTION	ASPHALT CONCRETE BASE, PG64-22 ASPHALT OPTION	AGGREGATE BASE ASPHALT OPTION	CEMENT STABILIZED SUBGRADE, 12 INCHES DEEP ASPHALT OPTION
									ITEM_CODE	202E23000	202E23010	204e10000	254E01000	442E10301	407E20000	442E10100	302E46000	302E46000	304E20000	206E15010
									ADDITIONAL_DESCRIPTION	ASPHALT OPTION	ASPHALT OPTION	ASPHALT OPTION	ASPHALT OPTION	ASPHALT OPTION	ASPHALT OPTION	ASPHALT OPTION	ASPHALT OPTION	ASPHALT OPTION	ASPHALT OPTION	ASPHALT OPTION
									TYPICAL SECTION LEGEND NUMBER											
									RATE / THICKNESS / ETC					0.04		0.05	0.15	0.15	0.17	
										202	202	204	254	442	407	442	302	302	304	206
						FT	FT	SY	SY	SY	SY	SY	SY	CY	GAL	CY	CY	CY	CY	SY
		TO																		
	163+61.21		163+86.21		CONC	25.00			81.80	81.80										
	163+61.21		163+86.21		ASPH	25.00			125.23		125.23									
	163+61.21		163+86.21		6" OFFSET	25.00			215.40										35.90	
	165+61.69		165+86.69		CONC	25.00			92.46	92.46										
	165+61.69		165+86.69		ASPH	25.00			136.87		136.87									
	165+61.69		165+86.69		6" OFFSET	25.00			224.80										37.47	
	165+86.69		279+31.20		CONC	11344.51	24.00	30252.03		30252.03										
	165+86.69		279+31.20		ASPH	11344.51	40.00	50420.04			50420.04									
	165+86.69		279+31.20		EOS	11344.51	60.00	75630.07						3151.25	4159.65	3676.46				
	165+86.69		279+31.20		4" OFFSET	11344.51	60.67	76474.60							4206.10		11683.62			
	165+86.69		279+31.20		6" OFFSET	11344.51	61.67	77735.10							4275.43			11876.20		
	165+86.69		279+31.20		6" OFFSET	11344.51	62.67	78995.60											13165.93	
	94+00.00		96+00.00		18" OFFSET	200.00	63.00	1400.00				1400.00								
	96+00.00		100+00.00		22" OFFSET	400.00	63.67	2829.78												2829.78
	100+00.00		108+00.00		18" OFFSET	800.00	63.00	5600.00				5600.00								
	108+00.00		128+00.00		22" OFFSET	2000.00	63.67	14148.89	27.44											14176.33
	128+00.00		136+00.00		18" OFFSET	800.00	63.00	5600.00				5600.00								
	136+00.00		157+24.60		22" OFFSET	2124.60	63.67	15030.36	191.85											15222.21
	157+24.60		157+49.60		22" OFFSET	25.00	63.67	176.86												176.86
	159+13.16		159+38.16		22" OFFSET	25.00	63.67	176.86												176.86
	159+38.16		163+61.21		22" OFFSET	423.05	63.67	2992.84	358.00											3350.84
	163+61.21		163+86.21		22" OFFSET	25.00	63.67	176.86												176.86
	165+61.69		165+86.69		22" OFFSET	25.00	63.67	176.86												176.86
	165+86.69		180+00.00		22" OFFSET	1413.31	63.67	9998.38	2430.00											12428.38
	180+00.00		188+00.00		18" OFFSET	800.00	63.00	5600.00	883.00			6483.00								
	188+00.00		196+00.00		22" OFFSET	800.00	63.67	5659.56	560.00											6219.56
	196+00.00		204+00.00		18" OFFSET	800.00	63.00	5600.00	84.44			5684.44								
	204+00.00		214+00.00		22" OFFSET	1000.00	63.67	7074.44												7074.44
	214+00.00		228+00.00		18" OFFSET	1400.00	63.00	9800.00				9800.00								
	228+00.00		238+00.00		22" OFFSET	1000.00	63.67	7074.44												7074.44
	238+00.00		242+00.00		18" OFFSET	400.00	63.00	2800.00				2800.00								
	242+00.00		275+00.00		22" OFFSET	3300.00	63.67	23345.67												23345.67
	275+00.00		279+00.00		18" OFFSET	400.00	63.00	2800.00				2800.00								
	279+00.00		279+31.20		22" OFFSET	31.20	63.67	220.72												220.72
	279+31.20		290+00.00		SB	1068.80	60.00	7125.33					7125.33	296.89	997.55					
									SUBTOTALS	30426.29	50682.14	40167.44	7125.33	3448.14	13638.73	3676.46	11683.62	11876.20	13239.30	92649.83
Total									TOTALS CARRIED TO GENERAL SUMMARY	30427	50683	40168	7126	3449	13639	3677	11684	11877	13240	92650