



OHIO DEPARTMENT OF TRANSPORTATION

CENTRAL OFFICE • 1980 WEST BROAD STREET • COLUMBUS, OH 43223
JOHN R. KASICH, GOVERNOR • JERRY WRAY, DIRECTOR

2/18/2016

Project 160112 **Addendum No. 1**
PID No. 93568
AUG – SR 37 – 8.97
Bridge Repair
Letting: March 1, 2016

Notice to all Bidders and Suppliers to please be advised of the attached Proposal Addendum.

The Department utilizes Bid Express (<http://www.bidx.com>) as the official medium for electronic bid submittal. All bidders must prepare bids and submit them online via Bid Express.

Addenda amendments must be acknowledged in the miscellaneous section of the Expedite (EBS) file and all amendments loaded in order for your bid to be considered for award of this project. Bid express will not accept bids that do not have amendments incorporated. Failure to incorporate changed quantities or items in your Expedite (EBS) submissions will result in the rejection of your bid.

**Proposal Addendum
For
D07-BH-FY16; PID 93568
Project 160112**

Please be advised of the following: Revise note Item 202 Bridge Rail Removed for Reuse, As Per Plan

Plan sheet revisions: Yes

Sheet 4/43 Replace the ITEM 202-BRIDGE RAIL REMOVED FOR REUSE, AS PER PLAN note with the following:

ITEM 202-BRIDGE RAIL REMOVED FOR REUSE, AS PER PLAN

THIS ITEM OF WORK CONSIST OF REMOVING THE ENTIRE LINEAR FEET OF BRIDGE RAIL ATTACHED TO THE SLAB EDGE THAT WILL BE REPLACED. THIS WORK INCLUDES THE REMOVAL OF ALL HARDWARE, POST, BLOCKOUTS, AND GUARDRAIL PANELS. THIS MATERIAL SHALL BE STORED WITHIN THE STATES RIGHT OF WAY UNTIL NEEDED TO BE REATTACHED TO NEW DECK EDGE. THE REINSTALLATION OF EXISTING BRIDGE RAIL AND POSTS REMOVED SHALL BE INCLUDED IN THIS ITEM FOR PAYMENT.

Answers to Prebid Questions: Yes

Q1: Submitted 2/16/16 at 3:23 pm

A1: Reinstallation is to be included in Bridge Railing Removed for Reuse pay item. An addendum is forthcoming to modify the note in the plans to clarify.