



ESTIMATED QUANTITIES - STRUCTURE No.: BUT-75-0115 (SFN: 0901571) (01/IMS/BR FUNDING SPLIT)								
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	PIERS	SUPER.	GEN.
202	11201	LUMP	LS	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN			LUMP	
509	20000	100	LB	REINFORCING STEEL, REPLACEMENT OF EXISTING REINFORCING STEEL				100
510	10001	10	EACH	DOWEL HOLES, AS PER PLAN				10
511	34410	8	CY	CLASS QC2 CONCRETE, SUPERSTRUCTURE				8
512	10100	743	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)				743
512	74000	682	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES				682
842	10000	5000	LBS	CORRECTING ELEVATION OF CONCRETE APPROACH SLABS WITH HIGH DENSITY POLYURETHANE				5000
607	39994	360	FT	TEMPORARY VANDAL FENCE, TYPE B				360
607	98200	LUMP	LS	FENCE MISC.: VANDAL PROTECTION FENCE REMOVED AND REBUILT			LUMP	

ESTIMATED QUANTITIES - STRUCTURE No.: BUT-75-0219 (SFN: 0901636) (01/IMS/BR FUNDING SPLIT)								
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	PIERS	SUPER.	GEN.
202	11201	LUMP	LS	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN			LUMP	
503	21300	LUMP	LS	UNCLASSIFIED EXCAVATION			LUMP	
509	10000	9123	LB	EPOXY COATED REINFORCING STEEL				9123
509	30020	13015	FT	NO. 4 GFRP DEFORMED BARS				13015
509	40000	7413	LB	REINFORCING STEEL, MISC.: GALVANIZED REINFORCING				7413
509	20000	100	LB	REINFORCING STEEL, REPLACEMENT OF EXISTING REINFORCING STEEL				100
510	10001	1736	EACH	DOWEL HOLES, AS PER PLAN				1592 144
511	34460	124	CY	CLASS QC SCC CONCRETE, BRIDGE DECK (PARAPET)				124
512	10100	743	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)				743
512	74000	101	SY	REMOVAL OF EXISTING COATINGS FROM CONCRETE SURFACES				101
516	13600	17	SF	1" PREFORMED EXPANSION JOINT FILLER				17
516	31010	16	FT	2" DEEP JOINT SEALER				16
842	10000	5000	LBS	CORRECTING ELEVATION OF CONCRETE APPROACH SLABS WITH HIGH DENSITY POLYURETHANE				5000
526	25000	43	SY	REINFORCED CONCRETE APPROACH SLABS (T=15")				43
530	13000	2466	SF	FORM LINER				2466
607	39994	721	FT	TEMPORARY VANDAL FENCE, TYPE B				721
625	25500	822	FT	CONDUIT, 3", 725.04				822
607	39901	721	FT	VANDAL PROTECTION FENCE, 6' STRAIGHT, COATED FABRIC, AS PER PLAN (ALTERNATE 1)				721
607	40000	721	FT	SPECIAL - VANDAL PROTECTION FENCE - AESTHETIC VANDAL PROTECTION FENCE (ALTERNATE 2)				721

ESTIMATED QUANTITIES - STRUCTURE No.: PRE-127-0227 (SFN: 6802311) (02/STR/BR FUNDING SPLIT)								
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	PIERS	SUPER.	GEN.
503	11100	LUMP	LS	COFFERDAMS AND EXCAVATION BRACING				LUMP
512	10100	2648	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)		2648		
516	47001	LUMP	LS	JACKING AND TEMPORARY SUPPORT OF SUPERSTRUCTURE, AS PER PLAN				LUMP
519	11101	537	SF	PATCHING CONCRETE STRUCTURE, AS PER PLAN		537		
519	100	2180	SF	SPECIAL - COMPOSITE FIBER WRAP SYSTEM (SEE PROPOSAL NOTE 519)		2180		
842	10000	4000	LBS	CORRECTING ELEVATION OF CONCRETE APPROACH SLABS WITH HIGH DENSITY POLYURETHANE				4000

ESTIMATED QUANTITIES - STRUCTURE No.: HAM-42-0000 (SFN: 6802311) (03/S>2/BR FUNDING SPLIT)								
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	PIERS	SUPER.	GEN.
202	11201	LUMP	LS	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN			LUMP	
518	43300	100	FT	6" PIPE DOWNSPOUT, INCLUDING SPECIALS, 748.06				100
518	62100	200	FT	STRUCTURE DRAINAGE, MISC.: CLEANING BRIDGE DRAINAGE SYSTEM			LUMP	

ESTIMATED QUANTITIES - STRUCTURE No.: HAM-71-0320 (SFN: 3114260) (04/IMS/BR FUNDING SPLIT)								
ITEM	EXTENSION	TOTAL	UNIT	DESCRIPTION	ABUT.	PIERS	SUPER.	GEN.
202	11201	LUMP	LS	PORTIONS OF STRUCTURE REMOVED, AS PER PLAN			LUMP	
509	10000	239	LB	EPOXY COATED REINFORCING STEEL				239
509	20000	100	LB	REINFORCING STEEL, REPLACEMENT OF EXISTING REINFORCING STEEL				100
510	10001	10	EACH	DOWEL HOLES, AS PER PLAN				10
511	34410	5	CY	CLASS QC2 CONCRETE, SUPERSTRUCTURE				5
513	20001	22	EACH	WELDED STUD SHEAR CONNECTORS, AS PER PLAN				22

