

I:\ProjectData\09-GR-FY2021\Design\Roadway\Sheets\00883_G001.dgn Sheet 3/5/2021 3:18:39 PM ewoodbr

SHEET NUM.													PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
2	3	5	6	7	8	9	10	11	12	13	14	15	02/SAF/O T	01/STR/O T						
ROADWAY																				
													LS	LS	201	11000	LS	CLEARING AND GRUBBING		
		2,100	775	1,400	500	150	150	700	1,950	2,625	1,675		12,025		202	38000	12,025	FT	GUARDRAIL REMOVED	
		84	31	56	20	6	6	28	78	105	67		481		202	42000	481	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A	
		42	16	29	10	3	3	14	39	53	35	4	244	4	209	60201	248	STA	LINEAR GRADING, AS PER PLAN	
		880	310	560	200	60	60	280	780	1,055	670	40	4,855	40	209	70000	4,895	CY	BORROW	
50													50		209	72001	50	STA	PREPARING SUBGRADE FOR SHOULDER PAVING, AS PER PLAN	
		2,100	775	1,400	500	150	150	700	1,950	2,625	1,675	362	12,025	362	606	15050	12,387	FT	GUARDRAIL, TYPE MGS	
		84	31	56	20	6	6	28	78	105	67	2	481	2	606	26100	483	EACH	ANCHOR ASSEMBLY, TYPE E	
EROSION CONTROL																				
	45,708												45,500	208	659	10000	45,708	SY	SEEDING AND MULCHING	
	6,856.12												6,825	31.12	659	14000	6,856.12	SY	REPAIR SEEDING AND MULCHING	
	6.42												6.14	0.28	659	20000	6.42	TON	COMMERCIAL FERTILIZER	
	9.84												9.41	0.43	659	31000	9.84	ACRE	LIME	
	142.74												136.5	6.24	659	35000	142.74	MGAL	WATER	
													900	100	832	30000	1,000	EACH	EROSION CONTROL	
PAVEMENT																				
125													125		441	50701	125	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), (UNDER GUARDRAIL), AS PER PLAN	
TRAFFIC CONTROL																				
		84	31	56	20	6	6	28	78	105	67	6	481	6	626	00112	487	EACH	BARRIER REFLECTOR, TYPE 3	
	100												100		630	03100	100	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
	50												50		630	85100	50	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
	50												50		630	86010	50	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND REERECTION	
INCIDENTALS																				
													0.9	0.1	614	11000	LS		MAINTAINING TRAFFIC	
													0.9	0.1	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													0.9	0.1	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

D09 - GR - FY 2021

CALCULATED	JBS	CHECKED	CLC
------------	-----	---------	-----

