

SHEET NUM.										PART.			ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
P.4	P.7									01/NFP/21			EXT	TOTAL				
										LS			201	11000	LS		CLEARING AND GRUBBING	
	1,275									1,275			202	38000	1,275	FT	GUARDRAIL REMOVED	
	100									100			202	38001	100	FT	GUARDRAIL REMOVED, AS PER PLAN	P.4
	12,812.5									12,812.5			202	38101	12,812.5	FT	GUARDRAIL REMOVED FOR STORAGE, AS PER PLAN	P.4
	50									50			202	42000	50	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A	
	12									12			202	42040	12	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T	
	4									4			202	47000	4	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
	173									173			209	60201	173	STA	LINEAR GRADING, AS PER PLAN	P.3
	1,732									1,732			203	40000	1,732	CY	BORROW	
	100									100			517	75600	100	FT	DEEP BEAM BRIDGE RETROFIT RAILING	
	100									100			606	13000	100	FT	GUARDRAIL, TYPE 5	
	12,887.5									12,887.5			606	15050	12,887.5	FT	GUARDRAIL, TYPE MGS	
	1,725									1,725			606	15100	1,725	FT	GUARDRAIL, TYPE MGS WITH LONG POSTS	
	100									100			606	17350	100	FT	GUARDRAIL, TYPE MGS, 25' LONG-SPAN	
	2									2			606	26050	2	EACH	ANCHOR ASSEMBLY, MGS TYPE B	
	4									4			606	26100	4	EACH	ANCHOR ASSEMBLY, TYPE E	
	37									37			606	26150	37	EACH	ANCHOR ASSEMBLY, MGS TYPE E, MASH 2016	
	25									25			606	26500	25	EACH	ANCHOR ASSEMBLY, TYPE T	
	4									4			606	35140	4	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 4	
	15									15			SPECIAL	69050100	15	EACH	MAILBOX SUPPORT SYSTEM, SINGLE	P.3
	5									5			SPECIAL	69050200	5	EACH	MAILBOX SUPPORT SYSTEM, DOUBLE	P.3
	25									25			SPECIAL	69050350	25	EACH	MAILBOX REMOVED AND RESET	P.3
																	EROSION CONTROL	
14,417										14,417			659	10000	14,417	SY	SEEDING AND MULCHING	
721										721			659	14000	721	SY	REPAIR SEEDING AND MULCHING	
1.95										1.95			659	20000	1.95	TON	COMMERCIAL FERTILIZER	
3										3			659	31000	3	ACRE	LIME	
78										78			659	35000	78	MGAJ	WATER	
										1,000			832	30000	1,000	EACH	EROSION CONTROL	
																	TRAFFIC CONTROL	
	206									206			626	00112	206	EACH	BARRIER REFLECTOR, TYPE 3 BI-DIRECTIONAL	
100										100			630	03100	100	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
25										25			630	85100	25	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
																	INCIDENTALS	
										LS			614	11000	LS		MAINTAINING TRAFFIC	P.4
										LS			624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

 DESIGNER: JRH
 REVIEWER: JRH
 EMB 10-08-24
 PROJECT ID: 109870
 SHEET TOTAL: P.6 | P.10