

SHEET NUMBER													PART. 01/NFP	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.05	P.06	P.07		P.09		P.11													
																		ROADWAY	
													LS	201	11000	LS		CLEARING AND GRUBBING	
				1									1	202	42040	1	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T	
				1									1	202	42820	1	EACH	ANCHOR ASSEMBLY REMOVED FOR REUSE, TYPE T	
				285									285	203	10000	285	CY	EXCAVATION	
				1,288									1,288	204	10000	1,288	SY	SUBGRADE COMPACTION	
				16									16	204	45000	16	hour	PROOF ROLLING	
				212.5									212.5	606	15050	212.5	FT	GUARDRAIL, TYPE MGS	
				3									3	606	26550	3	EACH	ANCHOR ASSEMBLY, MGS TYPE T	
				1									1	606	27910	1	EACH	ANCHOR ASSEMBLY REBUILT, MGS TYPE T	
				2									2	606	35102	2	EACH	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 2	
				2									2	622	25000	2	EACH	CONCRETE BARRIER END SECTION, TYPE D	
													2,000	832	30000	2,000	EACH	EROSION CONTROL	
				17									17	611	04900	17	FT	12" CONDUIT, TYPE D	
				285									285	304	20000	285	CY	PAVEMENT AGGREGATE BASE	
													8	625	00480	8	EACH	TRAFFIC SURVEILLANCE CONNECTION, UNFUSED PERMANENT	
						3,739							3,739	625	22990	3,739	FT	NO. 6 AWG 600 VOLT DISTRIBUTION CABLE	
						1,053							1,053	625	23000	1,053	FT	NO. 4 AWG 600 VOLT DISTRIBUTION CABLE	
						7,941							7,941	625	23100	7,941	FT	NO. 2 AWG 600 VOLT DISTRIBUTION CABLE	
						939							939	625	25410	939	FT	CONDUIT, 2", 725.052	
						1,844							1,844	625	25506	1,844	FT	CONDUIT, 3", 725.052	
						183							183	625	25908	183	FT	CONDUIT, JACKED OR DRILLED, 725.052, 2"	
						663							663	625	25908	663	FT	CONDUIT, JACKED OR DRILLED, 725.052, 3"	
						2,783							2,783	625	29010	2,783	FT	TRENCH, 30" DEEP	
						32							32	625	30700	32	EACH	PULL BOX, 725.08, 18"	
				2		58							60	625	32000	60	EACH	GROUND ROD	
						2,783							2,783	625	36011	2,783	FT	UNDERGROUND WARNING/MARKING TAPE, AS PER PLAN	P.10
						8							8	625	76000	8	EACH	ARC FLASH CALCULATIONS AND LABEL (ITS SITES)	
						8							8	633	67101	8	EACH	CABINET FOUNDATION, AS PER PLAN	P.10
						8							8	809	01900	8	EACH	ITS PULL BOX WITH PAD AND STANDARD LID ASSEMBLY, 32" WIDE, TYPE 1	
						7							7	809	51001	7	EACH	ITS POWER SERVICE, GROUND MOUNTED, 120/240V, 60 AMP, AS PER PLAN	P.10
						1							1	809	52001	1	EACH	ITS POWER SERVICE, GROUND MOUNTED, 240/480V, 60 AMP, AS PER PLAN	P.10
						8							8	809	60040	8	EACH	CCTV IP-CAMERA SYSTEM, QUAD MULTI-VIEW FIXED WITH PTZ	
						8							8	809	61040	8	EACH	CCTV POLE, 70' TALL	
						8							8	809	61090	8	EACH	CCTV LOWERING UNIT	
						8							8	809	65000	8	EACH	ITS CABINET - GROUND MOUNTED	
						1							1	809	65100	1	EACH	STEP-DOWN TRANSFORMER, 3KVA	
						LS							LS	809	70100	LS		TRAINING	
																		MAINTENANCE OF TRAFFIC	
													160	614	11110	160	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
													16	614	18600	16	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN	
													5	616	10000	5	MGAL	WATER	
																		INCIDENTALS	
LS													LS	614	11000	LS		MAINTAINING TRAFFIC	
													LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER

GBS

REVIEWER

DAH 07/15/26

PROJECT ID

122391

SHEET

P.08

TOTAL

23