

MAINTENANCE OF TRAFFIC (cont'd)

Order Of Operations

The location number given to each location of work is to differentiate the location and is not intended to direct the Contractor to perform work in any specific order. Work at each location can occur concurrently.

The majority of work on **Location 1** shall not start before August 1, 2022.
The exception to this being pavement on IR-90 EB from MM 205.4 to the East end of the job where the Full Depth Rigid Pavement Removal and Flexible Replacement and Pavement Repair, As Per Plan "A" items shall be completed by May 25, 2022.

72 hours prior to work starting at each location or closure, a PCMS shall be placed as directed by the Engineer, to inform the motoring public of upcoming work or closures.

Following is a list of work to be performed and how traffic will be maintained at each location.

Work Location 1 (IR-90 – Overlay Repairs):
Refer to Sheet "Location 1 – General Notes" of the plans.

Work Location 2 (SR-528 – Resurfacing) :
Refer to Sheet "Location 2 – General Notes" of the plans.

Work Location 3 (SR-615 – Resurfacing) :
Refer to Sheet "Location 3 – General Notes" of the plans.

Work Location 4 (Lake County FSMF - Resurfacing) :
Refer to Sheet "Location 4 – General Notes" of the plans.

Work Location 5 (IR-480 - Resurfacing) :
Refer to Sheet "Location 5 – General Notes" of the plans

DESIGN AGENCY



DESIGNER
JAG

REVIEWER
EMK 12/13/21

PROJECT ID
103305

SHEET TOTAL
P.12 44