


D3/D4/D12 ITS CAMERA ADDITIONS

MODEL: Sheet\_SurvFl\_PAPER SIZE: 34x22 (in.) DATE: 4/22/2024 TIME: 9:36:34 AM USER: AndersonN  
 p:\wsp-us-pw-bentley.com\wsp-us-pw-02\Documents\OH - OHIO Projects\118895\400-Engineering\Roadway\Sheets\118895\_GG001.dgn

SHEET NUM.										PART.			ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
P.5	P.6	P.7	P.9	P.12	P.13					01/NFP/44			EXT	TOTAL				
																	ROADWAY	
				LS						LS			201	11000	LS		CLEARING AND GRUBBING	
				14						14			202	75000	14	FT	FENCE REMOVED	
				1,375						1,375			203	10000	1,375	CY	EXCAVATION	
				6,145						6,145			204	10000	6,145	SY	SUBGRADE COMPACTION	
8													204	45000	8	HOUR	PROOF ROLLING	
				1,375						1,375			304	20000	1,375	CY	AGGREGATE BASE	
				112.5						112.5			606	15050	112.5	FT	GUARDRAIL, TYPE MGS	
				4						4			606	26500	4	EACH	ANCHOR ASSEMBLY, TYPE T	
				1						1			607	61200	1	EACH	GATE, TYPE CLT	
																	EROSION CONTROL	
7,000										7,000			659	10000	7,000	SY	SEEDING AND MULCHING	
1										1			659	20000	1	TON	COMMERCIAL FERTILIZER	
40										40			659	35000	40	MGAL	WATER	
11,760										11,760			832	30000	11,760	EACH	EROSION CONTROL	
																	TRAFFIC SURVEILLANCE	
				4,207						4,207			625	22900	4,207	FT	NO. 3/8 AWG 2400 VOLT DISTRIBUTION CABLE	
				8,940						8,940			625	22900	8,940	FT	NO. 6 AWG 600 VOLT DISTRIBUTION CABLE	
				510						510			625	23000	510	FT	NO. 4 AWG 600 VOLT DISTRIBUTION CABLE	
				2,090						2,090			625	23100	2,090	FT	NO. 2 AWG 600 VOLT DISTRIBUTION CABLE	
				222						222			625	25408	222	FT	CONDUIT, 2", 725.051	
				9,985						9,985			625	25410	9,985	FT	CONDUIT, 2", 725.052	
				704						704			625	25504	704	FT	CONDUIT, 3", 725.051	
				3,632						3,632			625	25900	3,632	FT	CONDUIT, JACKED OR DRILLED, 2"725.052, SCHEDULE 80	
				10,502						10,502			625	29010	10,502	FT	TRENCH, 30" DEEP	
				103						103			625	30700	103	EACH	PULL BOX, 725.08, 18"	
				152						152			625	32001	152	EACH	GROUND ROD, AS PER PLAN	P.9
				6						6			625	34001	6	EACH	POWER SERVICE, AS PER PLAN, A	P.10
				11						11			625	34001	11	EACH	POWER SERVICE, AS PER PLAN, B	P.10
				1						1			625	34001	1	EACH	POWER SERVICE, AS PER PLAN, C	P.10
				3						3			625	34001	3	EACH	POWER SERVICE, AS PER PLAN, D	P.10
				2						2			625	34001	2	EACH	POWER SERVICE, AS PER PLAN, E	P.10
				1						1			625	34001	1	EACH	POWER SERVICE, AS PER PLAN, F	P.10
					1					1			625	34001	1	EACH	POWER SERVICE, AS PER PLAN, G	P.10
					2					2			625	34001	2	EACH	POWER SERVICE, AS PER PLAN, H	P.10
					1					1			625	34001	1	EACH	POWER SERVICE, AS PER PLAN, I	P.10
					1					1			625	34001	1	EACH	POWER SERVICE, AS PER PLAN, J	P.10
					1					1			625	34001	1	EACH	POWER SERVICE, AS PER PLAN, K	P.10
					1					1			625	34001	1	EACH	POWER SERVICE, AS PER PLAN, L	P.10
					1					1			625	34001	1	EACH	POWER SERVICE, AS PER PLAN, M	P.10
					660					660			625	36010	660	FT	UNDERGROUND WARNING/MARKING TAPE	
					875					875			625	36011	875	FT	UNDERGROUND WARNING/MARKING TAPE, AS PER PLAN	P.9
				9						9			625	98000	9	EACH	LIGHTING, MISC.:STEP-DOWN TRANSFORMER AND SUPPORT	P.9
				7						7			632	70400	7	EACH	CONDUIT RISER, 2" DIAMETER	
				32						32			633	67101	32	EACH	CABINET FOUNDATION, AS PER PLAN	P.9
				38						38			809	02000	38	EACH	32" ITS PULL BOX WITH PAD AND STANDARD LID ASSEMBLY	
				2						2			809	02002	2	EACH	32" ITS PULL BOX WITH PAD AND HINGED LID ASSEMBLY	
				384						384			809	24500	384	FT	CONDUIT, 4", MULTICELL, HDPE WITH 4 - 1" INNERDUCTS	
				32						32			809	60040	32	EACH	CCTV IP-CAMERA SYSTEM, QUAD MULTI-VIEW FIXED WITH PTZ	
				32						32			809	61002	32	EACH	CCTV CONCRETE POLE, 70 FEET	
				4						4			809	61090	4	EACH	CCTV LOWERING UNIT	
				32						32			809	65000	32	EACH	ITS CABINET - GROUND MOUNTED	
				3						3			809	65990	3	EACH	ITS DEVICE, MISC.: REMOVAL OF POLE OR DEVICE	P.9
			LS		LS					LS			809	70050	LS		AS-BUILT CONSTRUCTION PLANS	
																	MAINTENANCE OF TRAFFIC	
																	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
																	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	P.6
																	WATER	
																	MAINTAINING ITS DURING CONSTRUCTION	

GENERAL SUMMARY

DESIGN AGENCY  
  
 WSP USA, Inc.  
 2 Miranova Pl,  
 Suite 450  
 Columbus, OH 43215

DESIGNER  
 ELK

REVIEWER  
 BPT 03/26/24

PROJECT ID  
 118895

SHEET TOTAL  
 P.8 | 55