

# Estimated Quantities

## Instructions

The requested information on this form is necessary the creation of the official Engineer's Estimate. If any of the following items are listed as "Lump Sum" in the construction plans, specific quantities must be provided. This form is for Consultant use only. Districts shall input this information into the ODOT Plan Package Submittal SharePoint site.

CRS [DEL-315-0.86](#) PID [110446](#)

### Item 201 - Tree and Stump Removals (*List by Size*):

[18" Stumps - 144 each](#)

[30" Stumps - 19 each](#)

[48" Stumps - 1 each](#)

### Item 202 - Structure(s)/Portions of Structure(s) Removed (*List Structures & Associated Quantities*):

[SFN 2103281 - DEL-315-0.87](#)

[Wingwalls Removed - 10.75 Cu. Yd.](#)

[Headwall - 1.67 Cu. Yd.](#)

### Item 502 - Structure(s) for Maintaining Traffic (*List Structures & Associated Quantities*):

[N/A](#)

### Item 503 - Unclassified Excavation (*Cubic Yards*):

[135 Cu. Yd.](#)

### Item 509 - Reinforcing Steel (List Structure(s), Item (*i.e., Wall, Deck, Parapet*), & Pounds of Steel):

[SFN 2103281 - DEL-315-0.87](#)

[Wingwalls - 2,934 lbs](#)

[Footings - 3,340 lbs](#)

[Collar - 1,342 lbs](#)

### Item 513 - Structural Steel (List Structure(s), Item (*i.e., Wall, Deck, Parapet*), & Pounds of Steel):

[N/A](#)

### Item 514 - Steel Surfaces to be Painted (*List Structures & Square Footage of Steel*):

[N/A](#)

### Item 518 - Porous Backfill (*Cubic Yards*):

[Porous Backfill With Geotextile Fabric - 26 Cu. Yd.](#)

### Item 615 - Roads and Pavement for Maintaining Traffic (*Earthwork & Pavement Cubic Yards*):

[N/A](#)

### Miscellaneous Items:

[See next page.](#)

Misc Items Cont.:

Item 202Removal Misc.: T Post - 2 each

Item 202Removal Misc.: Solar Ground light - 3 each

Item 202Removal Misc.: Electrical Outlet - 2 each

Item 202Removal Misc.: Sign Removed - 1 each

Item 202Removal Misc.: Irrigation System (sprinkler heads) - 2 each

Item 202Removal Misc.: Stone Wall - 40 Ft.

Item 202Removal Misc.: Conduit - 40 Ft.

Item 202 - Removal Misc.: Concrete Pad - 43 Sq. Ft.

Item 611 - CONDUIT, MISC.: 43"X68" CONDUIT, TYPE C; (706.04) - 352 ft.

Item 611 - CONDUIT, MISC.:TYPE B FOR DRAINAGE DISCHARGE CONTINUANCE - 40 Ft.

Item 611 - CONDUIT, MISC.:TYPE C FOR DRAINAGE DISCHARGE CONTINUANCE - 40 Ft.

Item 611 - CONDUIT, MISC.:TYPE E FOR DRAINAGE DISCHARGE CONTINUANCE - 40 Ft.

Item 611 - CONDUIT, MISC.:TYPE F FOR DRAINAGE DISCHARGE CONTINUANCE - 40 Ft.

Item 253 - PAVEMENT REPAIR, MISC.:REMOVE AND REPLACE BRICK PAVERS - 22 Sq. Yd.

Item 625 - LIGHT POLE, MISC.: 23'-6" ROUND TAPERED ALUMINIUM WITH 10' DAVIT, AS PER PLAN - 8 each

Item 625 - PULL BOX, MISC.: 725.06, (13"x24"), AS PER PLAN - 3 each

Item 661 - PLANTING, MISC.: 10" GRAY WASHED RIVER STONE MULCH - 52 Sq. Yd.