

I:\ProjectData\11437\Design\Roadway\Sheets\11437_GG001.dgn

SHEET NUM.												PART.				ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	
5	6	9	10	11	12	14	21	22	23	24	25	01/S<2/PV	02/S<2/BR	03/SAF/OT	04/SAF/OT							
						4,150						4,150				202	38000	4,150	FT	ROADWAY		
						13						13				202	42000	13	EACH	GUARDRAIL REMOVED		
						12						12				202	42040	12	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A		
						2						2				202	42050	2	EACH	ANCHOR ASSEMBLY REMOVED, TYPE T		
						1						1				202	42810	1	EACH	ANCHOR ASSEMBLY REMOVED, TYPE B		
						4						4				202	47000	4	EACH	ANCHOR ASSEMBLY REMOVED FOR REUSE, TYPE E		
						158						158				203	20001	158	CY	BRIDGE TERMINAL ASSEMBLY REMOVED	12	
						56						56				209	15000	56	STA	EMBANKMENT, AS PER PLAN		
		19.15										19.15				209	60500	19.15	MILE	RESHAPING UNDER GUARDRAIL		
						4,150						4,150				606	15050	4,150	FT	LINEAR GRADING		
						15						15				606	26150	15	EACH	GUARDRAIL, TYPE MGS		
						12						12				606	26500	12	EACH	ANCHOR ASSEMBLY, MGS TYPE E (MASH 2016)		
						1						1				606	27850	1	EACH	ANCHOR ASSEMBLY, TYPE T		
						12						12				606	35140	12	EACH	ANCHOR ASSEMBLY REBUILT, TYPE E		
						8						8				606	35170	8	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 4		
																				BRIDGE TERMINAL ASSEMBLY, TYPE BR-1		
	11											11				623	39500	11	EACH	MONUMENT BOX ADJUSTED TO GRADE		
	4											4				SPECIAL	69050100	4	EACH	MAILBOX SUPPORT SYSTEM, SINGLE	6	
	2											2				SPECIAL	69050200	2	EACH	MAILBOX SUPPORT SYSTEM, DOUBLE	6	
																				EROSION CONTROL		
												5,000				832	30000	5,000	EACH	EROSION CONTROL		
																				PAVEMENT		
750												750				251	01030	750	CY	PARTIAL DEPTH PAVEMENT REPAIR (442)		
75												75				253	02000	75	CY	PAVEMENT REPAIR		
		14,521										14,521				407	10000	14,521	GAL	TACK COAT (0.09 GAL/SY)		
		9,463										9,463				408	10001	9,463	GAL	PRIME COAT, AS PER PLAN	5	
		4,494										4,494				424	12000	4,494	CY	FINE GRADED POLYMER ASPHALT CONCRETE, TYPE B		
						1,321						1,321				617	10100	1,321	CY	COMPACTED AGGREGATE		
						50,543							50,543			618	40900	50,543	FT	RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)		
													50,543			874	20000	50,543	FT	LONGITUDINAL JOINT PREPARATION		
						6,130						6,130				897	01010	6,130	SY	PAVEMENT PLANING, ASPHALT CONCRETE, CLASS A (VARIABLE)		
						39						39				897	02000	39	SY	PATCHING PLANED SURFACE		
																				TRAFFIC SURVEILLANCE		
																10	625	31510	10	EACH	PULL BOX REMOVED	
																68	632	90030	68	FT	REMOVAL OF MISCELLANEOUS TRAFFIC SIGNAL ITEM -EXISTING LOOP LEAD-IN CABLE	
																140	632	90500	140	FT	SIGNALIZATION, MISC.: UNLASH AND RELASH MESSENGER WIRE	9
																1	809	69000	1	EACH	ADVANCE RADAR DETECTION	
																2	809	69100	2	EACH	STOP LINE RADAR DETECTION	
																				TRAFFIC CONTROL		
						691						691				621	00100	691	EACH	RPM		
						698						698				621	54000	698	EACH	RAISED PAVEMENT MARKER REMOVED		
						48						48				626	00110	48	EACH	BARRIER REFLECTOR, TYPE 2 (BIDIRECTIONAL)		
						19.62						19.62				642	00104	19.62	MILE	EDGE LINE, 6", TYPE 1		
						9.81						9.81				642	00300	9.81	MILE	CENTER LINE, TYPE 1		
						655						655				644	00500	655	FT	STOP LINE		
						2						2				644	01000	2	EACH	RAILROAD SYMBOL MARKING		
																				STRUCTURE REPAIR (ERI-13-0367)		
							68					68				202	98200	68	FT	REMOVAL MISC.: JOINT SEALER	20	
							68					68				516	31000	68	FT	JOINT SEALER		
																				STRUCTURE REPAIR (ERI-13-0652)		
								69				69				202	98200	69	FT	REMOVAL MISC.: JOINT SEALER	20	
								51				51				409	30000	51	FT	SAWING AND SEALING ASPHALT CONCRETE PAVEMENT JOINTS		
								69				69				516	31000	69	FT	JOINT SEALER		
																				STRUCTURE REPAIR (ERI-80-1380)		
																409	30000	50	FT	SAWING AND SEALING ASPHALT CONCRETE PAVEMENT JOINTS		
																				STRUCTURE REPAIR (ERI-99-0096)		
																202	98200	68	FT	REMOVAL MISC.: JOINT SEALER	20	
																409	30000	68	FT	SAWING AND SEALING ASPHALT CONCRETE PAVEMENT JOINTS		
																519	12300	30	SY	PATCHING CONCRETE BRIDGE DECK - TYPE B		

GENERAL SUMMARY

ERI-SMOOTH-FY 2021

