

SHEET NUM.											PART.			ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.07	P.08	P.10	P.11	P.16	P.20	P.22	P.37	P.45	P.48	P.62	01/NHS/OT	02/NHS/PV	03/NHS/BR						
																	TRAFFIC CONTROL		
										8		8		620	60500	8	EACH	REMOVAL OF DELINEATOR, POST SURFACE MOUNTED	
										606		606		621	00100	606	EACH	RPM	
										902		902		621	54000	902	EACH	RAISED PAVEMENT MARKER REMOVED	
							137					137		626	00110	137	EACH	BARRIER REFLECTOR, TYPE 2 1-WAY	
							86					86		626	00114	86	EACH	BARRIER REFLECTOR, TYPE 4 1-WAY	
8												8		630	80100	8	SF	SIGN, FLAT SHEET	
										0.36		0.36		807	12010	0.36	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, EDGE LINE, 6"	
										0.18		0.18		807	12110	0.18	MILE	WET REFLECTIVE EPOXY PAVEMENT MARKING, LANE LINE, 6"	
										25.53		25.53		807	14010	25.53	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, EDGE LINE, 6"	
										12.76		12.76		807	14110	12.76	MILE	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, LANE LINE, 6"	
										250		250		807	14430	250	FT	WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING, DOTTED LINE, 12"	
										38.29		38.29		850	10010	38.29	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (ASPHALT)	
										250		250		850	10130	250	FT	GROOVING FOR 2" RECESSED PAVEMENT MARKING, (ASPHALT)	
										0.54		0.54		850	20010	0.54	MILE	GROOVING FOR 6" RECESSED PAVEMENT MARKING, (CONCRETE)	
																		MAINTENANCE OF TRAFFIC	
		300										300		614	11110	300	hour	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
				4								4		614	12380	4	EACH	WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL)	
			111									111		614	13310	111	EACH	BARRIER REFLECTOR, TYPE 1, 1-WAY	
			37									37		614	13350	37	EACH	OBJECT MARKER, ONE WAY	
			4									4		614	18601	4	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	P.11
		25.84										25.84		614	20560	25.84	MILE	WORK ZONE LANE LINE, CLASS III, 6", 642 PAINT	
		51.68										51.68		614	22360	51.68	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
			5									5		616	10000	5	MGAL	WATER	
				1,900								1,900		622	41100	1,900	FT	PORTABLE BARRIER, UNANCHORED	
																		INCIDENTALS	
											LS	LS	LS	614	11000	LS		MAINTAINING TRAFFIC	
											LS	LS	LS	623	10001	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	P.08
											LS	LS	LS	624	10000	LS		MOBILIZATION	
																		FOR STRUCTURES QUANTITIES, SEE SHEET P.74	

GENERAL SUMMARY

