													PARTICIPATION 01/S>2/05	02/S>2/05	03/S>2/05	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
				6-7		8-9		11		19		20									
																				ROADWAY	
										200			200			202	38001	200	FT	GUARDRAIL REMOVED, AS PER PLAN	7
								1.39					1.19	0.20		209	60500	1.39	STA	LINEAR GRADING	
				5									5			623	39500	5	EA	MONUMENT BOX ADJUSTED TO GRADE	
																				EROSION CONTROL	
				11									11			659	00300	11	CY	TOPSOIL	
				100									100			659	10000	100	SY	SEEDING AND MULCHING	
				5									5			659	14000	5	SY	REPAIR SEEDING AND MULCHING	
				5									5			659	15000	5	SY	INTER-SEEDING	
				0.01									0.01			659	20000	0.01	TON	COMMERCIAL FERTILIZER	
				0.02									0.02			659	31000	0.02	ACRE	LIME	
				1									1			659	35000	1	MGAL	WATER	
													1000			832	30000	1000	EACH	EROSION CONTROL	
																				DRAINAGE	
				4									4			611	99654	4	EACH	MANHOLE ADJUSTED TO GRADE	
																				WATERWORKS	
				4									4			638	10800	4	EACH	VALVE BOX ADJUSTED TO GRADE	
																				PAVEMENT	
				150										50	100	251	01041	150	SY	PARTIAL DEPTH PAVEMENT REPAIR (ASPHALT CONCRETE BASE), AS PER PLAN, 5.5"	7
				5											5	253	01001	5	SY	PAVEMENT REPAIR, AS PER PLAN, (CATCH BASIN), 11"	7
								30131					28887	1244		254	01000	30131	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 1.5"	
								4218					4044	174		407	20000	4218	GAL	NON-TRACKING TACK COAT	
								1247					1195	52		442	10000	1247	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A, (446)	
								48					41	7		617	10100	48	CY	COMPACTED AGGREGATE	
				2									2			617	25000	2	MGAL	WATER	
																				TRAFFIC CONTROL	
												286	286			621	54000	286	EA	RAISED PAVEMENT MARKER REMOVED	
												1.05	0.85	0.20		644	00100	1.05	MILE	EDGE LINE, 4"	
												0.85	0.85			644	00200	0.85	MILE	LANE LINE, 4"	
												1.60	1.50	0.10		644	00300	1.60	MILE	CENTER LINE, 4"	
												1276	1276			644	00400	1276	FT	CHANNELIZING LINE, 8"	
												384	374	10		644	00500	384	FT	STOP LINE	
												1645	1645			644	00620	1645	FT	CROSSWALK LINE, 12"	
												190	190			644	00700	190	FT	TRANSVERSE/DIAGONAL LINE	
												21	21			644	01300	21	EA	LANE ARROW	
												11	11			644	01400	11	EA	WORD ON PAVEMENT, 72"	
												230	230			644	01500	230	FT	DOTTED LINE	
																				TRAFFIC SIGNALS	
				18									18			632	26501	18	EA	DETECTOR LOOP, AS PER PLAN	7
				18									18			632	27201	18	EA	LOOP DETECTOR TIE-IN, AS PER PLAN	7
																				MAINTENANCE OF TRAFFIC	
						32							32			614	11110	32	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	9
						8							8			614	12460	8	EA	WORK ZONE MARKING SIGN	
						0.85							0.85			614	20550	0.85	MILE	WORK ZONE LANE LINE, CLASS III, 642 PAINT	
						1.60							1.50	0.10		614	21550	1.60	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
						1276							1276			614	23680	1276	FT	WORK ZONE CHANNELIZING LINE, CLASS III, 642 PAINT	
						230							230			614	24610	230	FT	WORK ZONE DOTTED LINE, CLASS III, 4", 642 PAINT	
						384							374	10		614	26610	384	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
						1645							1645			614	27250	1645	FT	WORK ZONE CROSSWALK LINE, CLASS III, 12", 642 PAINT	
						21							21			614	30650	21	EA	WORK ZONE ARROW, CLASS III, 642 PAINT	
						11							11			614	31620	11	EA	WORK ZONE WORD ON PAVEMENT, 72", CLASS III, 642 PAINT	
																				INCIDENTALS	
													LS			614	11000	LS		MAINTAINING TRAFFIC	
													LS			623	10001	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING, AS PER PLAN	7
													LS			624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER
RAM

REVIEWER
XXX MM-DD-YY

PROJECT ID
106264

SHEET P.10 TOTAL 20

FRA-256-0.00

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 3/6/2023 TIME: 7:38:07 AM USER: rmcnelll
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 06\Franklin\106264\400-Engineering\Roadway\Sheets\106264_GG001.dgn