

V:\Projects\ANY\K4\3397\CADD\DSGN\06406\Design\Traffic\Sheets\06406\_IS001.dgn Sheet 2/23/2021 4:54:02 PM 5584

PAVEMENT MARKING SUBSUMMARY

SHEET NO.	REFERENCE	STATION		STREET	SIDE	621				644			647
						RAISED PAVEMENT MARKER REMOVED	RPM, ONE WAY, W @ 80' SPACING	RPM, TWO WAY, Y/Y @ 80' SPACING	RPM, TWO WAY, W/R @ 40' SPACING	EDGE LINE, 6" (WHITE)	CENTER LINE, SOLID, DOUBLE	CHANNELIZING LINE, 8"	LANE ARROW
47	EL-1	224+13.40	233+45.81	S.R 104	LT					937			
47, 48	EL-2	224+13.46	257+82.50	S.R 104	RT	2	2			3370			
47, 48	EL-3	233+89.11	257+82.50	S.R 104	LT	2	2			2398			
47	CL-1	224+19.24	233+14.35	S.R 104	LT	7		11			900		
47	CL-2	224+19.24	230+14.17	S.R 104	RT			7			600		
47	CL-3	230+14.17	230+63.86	S.R 104	RT			1			51		
47	CL-4	234+17.25	239+57.00	S.R 104	LT	6		7			543		
47	CL-5	234+17.25	239+57.00	S.R 104	RT			7			543		
47, 48	CL-6	239+57.00	254+75.10	S.R 104	RT	15		19			1518		
48	CL-7	254+75.10	257+82.50	S.R 104	LT	3		3			308		
48	CL-8	254+75.10	257+82.50	S.R 104	RT	2		2			263		
47	LA-1	231+08.34		S.R 104	LT/RT								1
47	LA-2	231+96.34		S.R 104	LT/RT								1
47	LA-3	232+84.34		S.R 104	LT/RT								1
47	CH-1	230+63.86	233+14.35	S.R 104	RT				6		251		
48	CH-2	257+50.00	257+82.50	S.R 104	RT				1		33		
TOTAL FEET										6705	4726	284	
TOTAL MILES										1.27	0.90	0.05	
SUBTOTAL							4	57	7				
TOTALS CARRIED TO GENERAL SUMMARY						37		68		1.27	0.90	284	3

SIGNING SUBSUMMARY

SHEET NO.	REFERENCE	STATION	STREET	SIDE	SIGN CODE	630				
						GROUND MOUNTED SUPPORT, NO. 3 POST	SIGN, FLAT SHEET	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	SIGN POST REFLECTOR
47	R-1	228+25	S.R 104	LT				1	1	
47	R-2	229+00	S.R 104	RT				1	1	
47	R-3	237+47	S.R 104	LT				1	1	
47	R-4	237+47	S.R 104	RT				1	1	
48	R-5	254+86	S.R 104	LT				1	1	
48	R-6	254+86	S.R 104	LT				1	1	
48	R-7	255+53	S.R 104	RT				1	1	
47	S-1	228+25	S.R 104	LT	W16-8P-30	13	8.25			1
47	S-2	229+00	S.R 104	RT	W16-8P-30	13	8.25			1
47	S-3	230+14	S.R 104	RT	R3-H8ba-30	13	6.25			
47	S-4	237+45	S.R 104	LT	W16-8P-30	13	8.25			1
47	S-5	237+47	S.R 104	RT	W16-8P-30	13	8.25			1
48	S-6	254+86	S.R 104	LT	D14-H14-30	26	7.50			
48	S-7	254+86	S.R 104	LT	R2-1-30	13	5.00			
48	S-8	255+53	S.R 104	RT	R2-1-30	13	5.00			
TOTALS CARRIED TO GENERAL SUMMARY						117	57	7	7	4

CALCULATED  
NMG  
CHECKED  
AJS

SIGNING AND PAVEMENT MARKING SUBSUMMARY

FRA -104 -4.43