

Estimated Quantities

Instructions

The requested information on this form is necessary the creation of the official Engineer's Estimate. If any of the following items are listed as "Lump Sum" in the construction plans, specific quantities must be provided. This form is for Consultant use only. Districts shall input this information into the ODOT Plan Package Submittal SharePoint site.

CRS PID
FRA-33-8.75 108081

Item 201 - Tree and Stump Removals (*List by Size*):

<u>SIZES</u>	<u>NO. TREES</u>	<u>NO. STUMPS</u>	<u>TOTAL</u>
18"	36	5	41
30"	4	0	4
48"	2	2	4

Item 202 - Structure(s)/Portions of Structure(s) Removed (*List Structures & Associated Quantities*):

1988366: 108 FT 8'X8' CONCRETE ARCH REMOVAL
20 FT OF 84" CORRUGATED METAL PIPE ARCH REMOVAL
NOTE HEADWALL REMOVAL QUANTIFIED SEPARATELY IN PLANS

Item 502 - Structure(s) for Maintaining Traffic (*List Structures & Associated Quantities*):

N/A

Item 503 - Unclassified Excavation (*Cubic Yards*):

Listed in Plans.

Item 509 - Reinforcing Steel (List Structure(s), Item (*i.e., Wall, Deck, Parapet*), & Pounds of Steel):

N/A

Item 513 - Structural Steel (List Structure(s), Item (*i.e., Wall, Deck, Parapet*), & Pounds of Steel):

N/A

Item 514 - Steel Surfaces to be Painted (*List Structures & Square Footage of Steel*):

N/A

Item 518 - Porous Backfill (*Cubic Yards*):

N/A

Item 615 - Roads and Pavement for Maintaining Traffic (*Earthwork & Pavement Cubic Yards*):

Listed in Plans.

Miscellaneous Items:

ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN INCLUDES:
291 FT OF ITEM 507 - W18X130 STEEL SOLDIER PILES
65 CY OF ITEM 518 - POROUS BACKFILL WITH FILTER FABRIC
266 FT OF ITEM 524 - 24" DIAMETER DRILLED SHAFTS, ABOVE BEDROCK
25 FT OF ITEM 524 - 24" DIAMETER DILLED SHAFTS, INTO BEDROCK
880 SF OF TIMBER LAGGING