


SHEET NUM.							PART.		ITEM	ITEM	GRAND	UNIT	DESCRIPTION	SEE SHEET NO.
9	10	11	12	13			OFFICE CALCS	01/SAF/PV	EXT	TOTAL				
													ROADWAY	
15								15	202	35100	15	FT	PIPE REMOVED, 24" AND UNDER	
1								1	202	8100	1	EACH	CATCH BASIN REMOVED	
							26	26	203	10000	26	CY	EXCAVATION	
				52				2	204	10000	2	CY	SUBGRADE COMPACTION	
				1				1	204	45000	1	HOUR	PROOF ROLLING	
													DRAINAGE	
5								5	611	00900	5	FT	6" CONDUIT, TYPE B	
10								10	611	04400	10	FT	12" CONDUIT, TYPE B	
1								1	611	98371	1	EACH	CATCH BASIN, NO. 6, AS PER PLAN	4
													PAVEMENT	
					10,744			10,744	254	01000	10,744	SY	PAVEMENT PLANING, ASPHALT CONCRETE, (1.5")	
298								298	255	20000	298	FT	FULL DEPTH PAVEMENT SAWING	
					13			13	301	46000	13	CY	ASPHALT CONCRETE BASE, PG64-22	
					9			9	304	20001	9	CY	AGGREGATE BASE, AS PER PLAN	4
					604			604	407	20000	604	GAL	NON-TRACKING TACK COAT	
					450			450	442	20000	450	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (448)	
					3			3	861	11300	3	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5 MM, TYPE A (448)	
													TRAFFIC CONTROL	
	132							133	621	00100	133	EACH	RPM	
	76		1					77	621	54000	77	EACH	RAISED PAVEMENT MARKER REMOVED	
				86				86	630	03100	86	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
				1				1	630	72520	1	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-16.22, DESIGN 7	
					2			2	630	79200	2	EACH	SIGN ATTACHMENT ASSEMBLY, MAST ARM	
					1			1	630	79500	1	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	
					68			68	630	80100	68	SF	SIGN, FLAT SHEET	
					1			1	630	84900	1	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
					1			1	630	85100	1	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
								2	630	86002	2	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
					1			1	630	87500	1	EACH	REMOVAL OF POLE MOUNTED SIGN AND DISPOSAL	
					1			1	630	84510	1	EACH	RIGID OVERHEAD SIGN SUPPORT FOUNDATION	
	0.83							0.83	644	00104	0.83	MILE	EDGE LINE, 6"	
	0.2	0.02						0.22	644	00204	0.22	MILE	LANE LINE, 6"	
								0.68	644	00300	0.68	MILE	CENTER LINE	
	686							686	644	00400	686	FT	CHANNELIZING LINE, 8"	
	44		57					101	644	00500	101	FT	STOP LINE	
	175							175	644	00630	175	FT	CROSSWALK LINE, 24"	
			20					20	644	00720	20	FT	CHEVRON MARKING	
	8			12				20	644	01300	20	EACH	LANE ARROW	
	2			2				4	644	01400	4	EACH	WORD ON PAVEMENT, 72"	
	393							393	644	30000	393	FT	REMOVAL OF PAVEMENT MARKING	
													TRAFFIC SIGNALS	
					420			420	632	90030	420	FT	REMOVAL OF MISCELLANEOUS TRAFFIC SIGNAL ITEM: LOOP LEAD-IN CBALE	19
					80			80	632	90500	80	FT	SIGNALIZATION, MISC.: UNLASH AND RELASH MESSENGER WIRE	19
					2			2	809	69001	2	EACH	ADVANCE RADAR DETECTION, AS PER PLAN	19
					3			3	809	69101	3	EACH	STOP LINE RADAR DETECTION, AS PER PLAN	19

GENERAL SUMMARY

DESIGN AGENCY

 2800 Corporate Exchange Drive, Suite 250,
 Columbus, OH 43221

DESIGNER
JAG

REVIEWER
JDC 12-17-21

PROJECT ID
110799

SHEET TOTAL
 7 | 23