
# STATE OF OHIO
# DEPARTMENT OF TRANSPORTATION

# *FRA-71-19.10*

## *CITY OF COLUMBUS*
## *CLINTON TOWNSHIP*
## *FRANKLIN COUNTY*




### *LOCATION MAP*

*LATITUDE: 42°02'45" LONGITUDE: 82°59'50"*

*PORTION TO BE IMPROVED*
*INTERSTATE HIGHWAY*
*FEDERAL ROUTES*
*STATE ROUTES*
*COUNTY & TOWNSHIP ROADS*
*OTHER ROADS*

### *DESIGN DESIGNATION*

*SEE SHEET 2*

### *DESIGN EXCEPTIONS*

*SEE SHEET 2*

### *ADA DESIGN WAIVERS*

*NONE REQUIRED*

### *INDEX OF SHEETS:*


| | | | |
|---|---|---|---|
| *TITLE SHEET* | *P.1* | *STRUCTURES (20' & OVER)* | |
| *DESIGN DESIGNATIONS* | *P.2* | *COMMON STRUCTURE GENERAL NOTES & DETAILS* | *P.382* |
| *SCHEMATIC PLANS* | *P.3 - P.7* | *FRA-71-18.750B (SFN 2506467)* | *P.383 - P.385* |
| *TYPICAL SECTIONS* | *P.8 - P.26* | *FRA-71-18.750 (SFN 2507838)* | *P.386 - P.389* |
| *GENERAL NOTES* | *P.27 - P.30* | *FRA-71-20.080 (SFN 2507951)* | *P.390 - P.393* |
| *MAINTENANCE OF TRAFFIC* | *P.31 - P.218, (P.212-P.216 NOT USED)* | *FRA-71-20.750 (SFN 2507986)* | *P.394 - P.406* |
| *PLAN AND PROFILES (I-71/RAMPS)* | *P.219 - P.247* | *FRA-71-23.460 (SFN 2508133/2508168)* | *P.407 - P.420* |
| *CROSS SECTIONS (I-71)* | *P.248 - P.271* | *FRA-71-24.460 (SFN TBD)* | *P.421 - P.485* |
| *CROSS SECTIONS (RAMPS)* | *P.272 - P.288* | *FRA-71-26.460 (SFN TBD)* | *P.486 - P.549* |
| *PLAN & PROFILE (MORSE ROAD)* | *P.289* | *GEOTECHNICAL PROFILES* | *P.550 - P.618* |
| *PLAN & PROFILE (S.R. 161)* | *P.290* | | |
| *CROSS SECTIONS (S.R. 161)* | *P.291 - P.292* | | |
| *PAVEMENT DETAILS* | *P.293 - P.301* | | |
| *STORM SEWER PROFILES* | *P.302 - P.309* | | |
| *CULVERT DETAILS* | *P.310* | | |
| *RETAINING WALL* | *P.311 - P.312* | | |
| *WATER WORK* | *P.313 - P.314* | | |
| *NOISE BARRIER* | *P.315 - P.317* | | |
| *TRAFFIC CONTROL* | *P.318 - P.352* | | |
| *ITS PLANS* | *P.353 - P.365* | | |
| *LIGHTING* | *P.366 - P.379, P.367A* | | |
| *LANDSCAPING* | *P.380 - P.381* | | |


### *FEDERAL PROJECT NUMBER*

E191777

### *RAILROAD INVOLVEMENT*

NORFOLK SOUTHERN

### *PROJECT DESCRIPTION*

*I-71 BRIDGE REPLACEMENT AND MAINLINE PROFILE ADJUSTMENT OVER MORSE ROAD & S.R. 161. I-71 BRIDGE REHABILITATION AT 2ND AVENUE, 17TH AVENUE, HIAWATHA PARK DRIVE, AND COOKE ROAD. ADDITIONAL PROJECT IMPROVEMENTS INCLUDE ITS AND LIGHTING.*

### *EARTH DISTURBED AREAS*

| | |
|---|---|
| *PROJECT EARTH DISTURBED AREA:* | *30.7 ACRES* |
| *ESTIMATED CONTRACTOR EARTH DISTURBED AREA:* | *1.0 ACRES* |
| *NOTICE OF INTENT EARTH DISTURBED AREA:* | *31.7 ACRES* |

### *LIMITED ACCESS*

*THIS IMPROVEMENT IS ESPECIALLY DESIGNED FOR THROUGH TRAFFIC AND HAS BEEN DECLARED A LIMITED ACCESS HIGHWAY OR FREEWAY BY ACTION OF THE DIRECTOR IN ACCORDANCE WITH THE PROVISIONS OF SECTION 5511.02 OF THE OHIO REVISED CODE.*

### *2023 SPECIFICATIONS*

*THE STANDARD SPECIFICATIONS OF THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, INCLUDING SUPPLEMENTAL SPECIFICATIONS LISTED IN THE PLANS, CHANGES LISTED IN THE PROPOSAL SHALL GOVERN THIS THIS IMPROVEMENT.*

*I HEREBY APPROVE THESE PLANS AND DECLARE THAT THE MAKING OF THIS IMPROVEMENT WILL NOT REQUIRE THE CLOSING TO TRAFFIC OF THE HIGHWAY EXCEPT AS NOTED ON SHEET P.36 , AND THAT PROVISIONS FOR THE MAINTENANCE AND SAFETY OF TRAFFIC WILL BE AS SET FORTH ON THE PLANS AND ESTIMATES.*

Anthony C. Turowski, P.E.
District 06 Deputy Director

Pamela Boratyn
Director, Department of Transportation

# STAGE 2 SUBMITTAL
# 03/31/2026

| *STANDARD CONSTRUCTION DRAWINGS* | *SUPPLEMENTAL SPECIFICATIONS* | *SPECIAL PROVISIONS* |
|---|---|---|
| | | |

| *ENGINEER'S SEAL:* | *ENGINEER'S SEAL:* |
|---|---|
| *SIGNED:* | *SIGNED:* |
| *DATE:* | *DATE:* |

3961-E

**UNDERGROUND UTILITIES**
Contact Two Working Days Before You Dig
OHIO811.org Before You Dig
OHIO811, 8-1-1, or 1-800-362-2764
(Non members must be called directly)


*PLAN PREPARED BY:*
Jacobs
*2 EASTON OVAL, SUITE 500*
*COLUMBUS, OH 43219*


TITLE SHEET

DESIGN AGENCY: Jacobs
DESIGNER: CGL
REVIEWER: MCK 03/20/26
PROJECT ID: 109164
SHEET: P.1 TOTAL: 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 2:15:00 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Roadway\Sheets\109164_GT001.dgn

## DESIGN DESIGNATION: I-71 (NORTH OF I-670)

| | |
|---|---|
| CURRENT ADT (2030) | 162,618 |
| DESIGN YEAR ADT (2050) | 192,838 |
| DESIGN HOURLY VOLUME (2050) | 17,355 |
| DIRECTIONAL DISTRIBUTION | 0.53 (SB) |
| TRUCKS (24 HOUR B&C) | 16,438 |
| DESIGN SPEED | 65 MPH (SB) / 55 MPH (NB) |
| LEGAL SPEED | 65 MPH (SB) / 55 MPH (NB) |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: I-71 (NORTH OF 5TH AVE)

| | |
|---|---|
| CURRENT ADT (2030) | 164,708 |
| DESIGN YEAR ADT (2050) | 192,149 |
| DESIGN HOURLY VOLUME (2050) | 17,293 |
| DIRECTIONAL DISTRIBUTION | 0.51 (SB) |
| TRUCKS (24 HOUR B&C) | 23,555 |
| DESIGN SPEED | 65 MPH (SB) / 55 MPH (NB) |
| LEGAL SPEED | 65 MPH (SB) / 55 MPH (NB) |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: I-71 (NORTH OF 11TH AVE)

| | |
|---|---|
| CURRENT ADT (2030) | 156,362 |
| DESIGN YEAR ADT (2050) | 181,755 |
| DESIGN HOURLY VOLUME (2050) | 16,358 |
| DIRECTIONAL DISTRIBUTION | 0.52 (SB) |
| TRUCKS (24 HOUR B&C) | 22,297 |
| DESIGN SPEED | 65 MPH |
| LEGAL SPEED | 65 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: I-71 (NORTH OF 17TH AVE)

| | |
|---|---|
| CURRENT ADT (2030) | 152,007 |
| DESIGN YEAR ADT (2050) | 173,400 |
| DESIGN HOURLY VOLUME (2050) | 15,606 |
| DIRECTIONAL DISTRIBUTION | 0.50 (NB) |
| TRUCKS (24 HOUR B&C) | 21,242 |
| DESIGN SPEED | 65 MPH |
| LEGAL SPEED | 65 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: I-71 (NORTH OF HUDSON ST)

| | |
|---|---|
| CURRENT ADT (2030) | 152,914 |
| DESIGN YEAR ADT (2050) | 172,156 |
| DESIGN HOURLY VOLUME (2050) | 15,494 |
| DIRECTIONAL DISTRIBUTION | 0.51 (NB) |
| TRUCKS (24 HOUR B&C) | 20,987 |
| DESIGN SPEED | 65 MPH |
| LEGAL SPEED | 65 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: I-71 (NORTH OF WEBER RD)

| | |
|---|---|
| CURRENT ADT (2030) | 152,344 |
| DESIGN YEAR ADT (2050) | 172,502 |
| DESIGN HOURLY VOLUME (2050) | 15,525 |
| DIRECTIONAL DISTRIBUTION | 0.52 (NB) |
| TRUCKS (24 HOUR B&C) | 20,657 |
| DESIGN SPEED | 65 MPH |
| LEGAL SPEED | 65 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: I-71 (NORTH OF NORTH BROADWAY)

| | |
|---|---|
| CURRENT ADT (2030) | 146,392 |
| DESIGN YEAR ADT (2050) | 165,125 |
| DESIGN HOURLY VOLUME (2050) | 14,861 |
| DIRECTIONAL DISTRIBUTION | 0.52 (NB) |
| TRUCKS (24 HOUR B&C) | 19,717 |
| DESIGN SPEED | 65 MPH |
| LEGAL SPEED | 65 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: I-71 (NORTH OF COOKE RD)

| | |
|---|---|
| CURRENT ADT (2030) | 142,056 |
| DESIGN YEAR ADT (2050) | 159,943 |
| DESIGN HOURLY VOLUME (2050) | 14,395 |
| DIRECTIONAL DISTRIBUTION | 0.53 (NB) |
| TRUCKS (24 HOUR B&C) | 19,190 |
| DESIGN SPEED | 65 MPH |
| LEGAL SPEED | 65 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: I-71 (NORTH OF MORSE RD)

| | |
|---|---|
| CURRENT ADT (2030) | 134,014 |
| DESIGN YEAR ADT (2050) | 151,444 |
| DESIGN HOURLY VOLUME (2050) | 13,630 |
| DIRECTIONAL DISTRIBUTION | 0.53 (NB) |
| TRUCKS (24 HOUR B&C) | 17,746 |
| DESIGN SPEED | 65 MPH |
| LEGAL SPEED | 65 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: I-71 (NORTH OF SR 161)

| | |
|---|---|
| CURRENT ADT (2030) | 129,542 |
| DESIGN YEAR ADT (2050) | 151,092 |
| DESIGN HOURLY VOLUME (2050) | 13,598 |
| DIRECTIONAL DISTRIBUTION | 0.53 (NB) |
| TRUCKS (24 HOUR B&C) | 16,709 |
| DESIGN SPEED | 65 MPH |
| LEGAL SPEED | 65 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: I-71 (NORTH OF I-270)

| | |
|---|---|
| CURRENT ADT (2030) | 173,490 |
| DESIGN YEAR ADT (2050) | 207,077 |
| DESIGN HOURLY VOLUME (2050) | 18,637 |
| DIRECTIONAL DISTRIBUTION | 0.52 (NB) |
| TRUCKS (24 HOUR B&C) | 22,937 |
| DESIGN SPEED | 65 MPH |
| LEGAL SPEED | 65 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 01 INTERSTATE (URBAN) |

## DESIGN DESIGNATION: SR 161

| | |
|---|---|
| CURRENT ADT (2030) | 46,692 |
| DESIGN YEAR ADT (2050) | 49,990 |
| DESIGN HOURLY VOLUME (2050) | 4,499 |
| DIRECTIONAL DISTRIBUTION | 0.51 (WB) |
| TRUCKS (24 HOUR B&C) | 1,661 |
| DESIGN SPEED | 45 MPH |
| LEGAL SPEED | 45 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 03 OTHER PRINCIPAL ARTERIAL (URBAN) |

## DESIGN DESIGNATION: MORSE RD

| | |
|---|---|
| CURRENT ADT (2030) | 33,754 |
| DESIGN YEAR ADT (2050) | 36,794 |
| DESIGN HOURLY VOLUME (2050) | 3,311 |
| DIRECTIONAL DISTRIBUTION | 0.52 (EB) |
| TRUCKS (24 HOUR B&C) | 553 |
| DESIGN SPEED | 45 MPH |
| LEGAL SPEED | 45 MPH |
| DESIGN FUNCTIONAL CLASSIFICATION: | 03 OTHER PRINCIPAL ARTERIAL (URBAN) |

## DESIGN EXCEPTIONS

SHOULDER WIDTHS: SHEETS P.14, P.15, P.17, P.18, P.20
PAVEMENT CROSS SLOPES: SHEETS P.17, P.18, P.19

DESIGN DESIGNATIONS

DESIGN AGENCY
Jacobs

DESIGNER JOH
REVIEWER MCK 03/20/26
PROJECT ID 109164
SHEET P.2 TOTAL 618

FRA-71-19.10


MODEL: Design Designations PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 1:01:01 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Roadway\Sheets\109164_GT001.dgn


FRA-71-19.10

MODEL: Schematic Plan - GB001 PAPERSIZE: 86x34 (in.) DATE: 2/11/2026 TIME: 7:21:36 AM PITDRV: DHOST_PDF_LP.shx(d) PSTBL: DHOST_Plot.ctb USER: Chris.Lawrence@jacobs.com WORKSPACE: D:\HOST\CAD WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 JACOBS SOLUTIONS INC. THIS DRAWING CONTAINS PROPRIETARY AND CONFIDENTIAL INFORMATION.

**PRIMARY CONTROL POINTS SET ALONG PROPOSED I-71**

| POINT NUMBER | I-71 CL STATION | I-71 CL OFFSET | GROUND COORDINATES | | GPS ELEV. | LEVELED ELEV. | DESCRIPTION |
|---|---|---|---|---|---|---|---|
| | | | NORTHING | EASTING | | | |
| S-0 | 1490+99.88 | -823.89 | 622221.5675 | 196909.7014 | 924.010 | 924.044 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-1 | 1487+85.14 | -89.70 | 621603.4591 | 197415.7089 | 914.214 | 914.233 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-2 | 1478+27.40 | -94.81 | 620756.2212 | 196969.0865 | 916.534 | 916.520 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-3 | 1418+93.63 | -81.12 | 615021.0357 | 195515.9365 | 930.943 | 930.933 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-4 | 1415+27.64 | -488.63 | 614675.0201 | 195091.3314 | 914.357 | 914.360 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-5 | 1411+79.28 | -82.29 | 614307.5617 | 195480.4841 | 929.745 | 929.731 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-6 | 1384+35.65 | -80.39 | 611567.0040 | 195350.7229 | 910.054 | 910.076 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-7 | 1372+10.25 | -79.66 | 610343.2497 | 195292.5681 | 906.103 | 906.099 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-8 | 1323+33.53 | -74.78 | 606253.6083 | 192920.6813 | 891.060 | 891.069 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-9 | 1315+45.33 | -82.84 | 605516.8364 | 192601.1571 | 895.479 | 895.498 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-10 | 1311+81.96 | -71.79 | 605154.9137 | 192520.7132 | 895.854 | 895.816 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-11 | 1263+89.79 | -66.36 | 600355.9508 | 192667.8775 | 875.523 | 875.486 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-12 | 1258+61.83 | -68.46 | 599828.7148 | 192695.6440 | 876.042 | 876.041 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-13 | 1219+52.27 | -68.17 | 595921.2399 | 192945.4034 | 869.020 | 869.004 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-14 | 1211+40.91 | -59.69 | 595124.1908 | 193137.0878 | 861.932 | 861.918 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-15 | 1202+27.64 | -57.15 | 594260.4998 | 193431.2267 | 841.997 | 841.923 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-16 | 1183+62.38 | -57.98 | 592436.9624 | 193574.3806 | 847.342 | 847.327 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-17 | 1174+07.81 | -59.21 | 591495.6541 | 193417.3781 | 835.304 | 835.297 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-18 | 1149+28.95 | -58.48 | 589007.7837 | 193436.6083 | 844.955 | 844.937 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-19 | 1143+34.17 | -61.64 | 588414.2725 | 193552.2778 | 833.466 | 833.443 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-20 | 1130+63.58 | -58.91 | 587298.3820 | 194192.9343 | 850.556 | 850.538 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-21 | 1115+98.18 | -56.75 | 586416.0794 | 195373.2177 | 862.819 | 862.786 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-22 | 1113+13.88 | -56.44 | 586244.7043 | 195591.4257 | 862.260 | 862.229 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-23 | 1080+25.46 | -56.14 | 583218.8295 | 196342.3508 | 860.425 | 860.373 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-24 | 1077+62.07 | -56.08 | 582956.7286 | 196339.7688 | 859.142 | 859.092 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-25 | 1072+23.58 | -56.62 | 582421.5006 | 196315.0988 | 850.302 | 850.243 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-26 | 1059+85.83 | -58.15 | 581187.6251 | 196221.6362 | 822.065 | 822.008 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-27 | 1048+93.46 | -54.49 | 580109.8841 | 196144.7896 | 813.484 | 813.431 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-28 | 1042+09.80 | -67.67 | 579417.2307 | 196079.8963 | 802.935 | 802.840 | CLASS B 3/4" X 30" IRON PIN SET W/ALUM ODOT CONTROL TABLET |
| S-29 | 1030+89.11 | -70.85 | 578287.5165 | 196043.2098 | 796.378 | 796.335 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |
| S-30 | 1019+05.30 | -61.13 | 577112.5941 | 196219.5083 | 802.726 | 802.701 | CLASS A POURED IN PLACE CONC. W/ALUM ODOT CONTROL TABLET |




*CURVE DATA: I71NB-1*
*P.I. = STA. 966+24.88*
*Δ = 13°51'26" RT*
*Dc = 01°00'00"*
*R = 5,729.58'*
*T = 696.25'*
*L = 1,385.71'*
*E = 42.15'*
*Emax = EXISTING*

*CURVE DATA: I71NB-2*
*P.I. = STA. 983+17.15*
*Δ = 15°34'52" LT*
*Dc = 01°30'00"*
*R = 3,819.72'*
*T = 522.59'*
*L = 1,038.74'*
*E = 35.58'*
*Emax = EXISTING*

*CURVE DATA: I71SB-1*
*P.I. = STA. 984+35.13*
*Δ = 16°35'30" LT*
*Dc = 01°30'00"*
*R = 3,819.72'*
*T = 556.96'*
*L = 1,106.12'*
*E = 40.39'*
*Emax = EXISTING*

*CURVE DATA: I670W1-1*
*P.I. = STA. 3986+99.11*
*Δ = 12°14'15" LT*
*Dc = 02°45'00"*
*R = 2,083.48'*
*T = 223.35'*
*L = 445.00'*
*E = 11.94'*
*Emax = EXISTING*

*CURVE DATA: I670W1-2*
*P.I. = STA. 3991+51.07*
*Δ = 08°02'50" LT*
*Dc = 01°45'00"*
*R = 3,274.05'*
*T = 230.30'*
*L = 459.85'*
*E = 8.09'*
*Emax = EXISTING*

*CURVE DATA: I670V7-1*
*P.I. = STA. 4987+15.75*
*Δ = 02°21'52" LT*
*Dc = 01°30'00"*
*R = 3,819.72'*
*T = 402.52'*
*L = 802.07'*
*E = 21.15'*
*Emax = EXISTING*

*CURVE DATA: I670V7-2*
*P.I. = STA. 4984+33.30*
*Δ = 02°21'04" LT*
*Dc = 01°00'00"*
*R = 5,729.58'*
*T = 117.58'*
*L = 235.12'*
*E = 1.21'*
*Emax = EXISTING*

*CURVE DATA: I71-1*
*P.I. = STA. 1032+82.82*
*Δ = 12°41'23" RT*
*Dc = 01°28'00"*
*R = 3,906.53'*
*T = 434.38'*
*L = 865.2'*
*E = 24.08'*
*Emax = EXISTING*

*CURVE DATA: I71-2*
*P.I. = STA. 1075+88.40*
*Δ = 04°19'55" LT*
*Dc = 00°30'00"*
*R = 11,459.16'*
*T = 433.39'*
*L = 866.37'*
*E = 8.19'*
*Emax = EXISTING*

*CURVE DATA: I71-3*
*P.I. = STA. 1106+24.16*
*Δ = 56°44'53" LT*
*Dc = 02°30'00"*
*R = 2,291.83'*
*Ls = 300.00*
*Θs = 03°45'00"*
*LT = 200.04'*
*ST = 100.04'*
*Lc = 1,969.93'*
*Ts = 1,388.71'*
*Es = 314.79'*
*Emax = EXISTING*
*S.C. = 1095+35.45*
*C.S. = 1115+05.37*

*CURVE DATA: STHC-1*
*P.I. = STA. 5012+52.32*
*Δ = 17°33'33" LT*
*Dc = 04°00'00"*
*R = 1,432.40'*
*Ls = 200.00'*
*Θs = 04°00'00"*
*LT = 133.37'*
*ST = 66.70'*
*Lc = 238.98'*
*Ts = 321.39'*
*Es = 18.16'*
*Emax = EXISTING*
*S.C. = 5011+30.94*
*C.S. = 5013+69.92*

*CURVE DATA: STHC-2*
*P.I. = STA. 5018+81.38*
*Δ = 29°44'24" RT*
*Dc = 09°30'00"*
*R = 603.11'*
*Ls = 200.00'*
*Θs = 09°30'00"*
*LT = 133.53'*
*ST = 66.84'*
*Lc = 113.05'*
*Ts = 260.78'*
*Es = 23.75'*
*Emax = EXISTING*
*S.C. = 5018+20.60*
*C.S. = 5019+33.66*

*CURVE DATA: STHC-3*
*P.I. = STA. 5023+58.00*
*Δ = 20°13'15" LT*
*Dc = 06°00'00"*
*R = 954.93'*
*T = 170.28'*
*L = 337.01'*
*E = 15.06'*
*Emax = EXISTING*


*N08°28'23"W*
*N26°24'49"W*
*N03°19'35"E*

HORIZONTAL SCALE IN FEET
0 100 200 400

# SCHEMATIC PLAN
# BEGIN WORK TO STA. 1110+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CGL
REVIEWER
MCK 02/19/26
PROJECT ID
109164
SHEET P.3 TOTAL 618




*CURVE DATA: I71-3*
*P.I. = STA. 1106+24.16*
*Δ = 56°44'53" LT*
*Dc = 02°30'00"*
*R = 2,291.83'*
*Ls = 300.00'*
*Θs = 03°45'00"*
*LT = 200.04'*
*ST = 100.04'*
*Lc = 1,969.93'*
*Ts = 1,388.71'*
*Es = 314.79'*
*Emax = EXISTING*
*S.C. = 1095+35.45*
*C.S. = 1115+05.37*

*SPIRAL DATA: I71-4*
*P.I. = STA. 1123+87.19*
*Ls = 250.00'*
*Θs = 02°30'00"*
*LT = 166.68'*
*ST = 83.35'*
*x = 249.95'*
*y = 3.64'*
*k = 124.99'*
*p = 0.91'*
*C = 249.98'*
*Start = Sta. 1122+20.51*
*End = Sta. 1124+70.51*
*C.B. = N55°58'34"W*

*CURVE DATA: I71-5*
*P.I. = STA. 1136+32.89*
*Δ = 44°10'10" RT*
*Dc = 02°00'00"*
*R = 2,864.79'*
*T = 1,162.38'*
*L = 2,208.47'*
*E = 226.84'*
*Emax = EXISTING*

*SPIRAL DATA: I71-6*
*P.I. = STA. 1147+93.95*
*Ls = 287.32'*
*Θs = 03°35'29"*
*LT = 172.44'*
*ST = 114.97'*
*x = 287.07'*
*y = 10.80'*
*k = 107.72'*
*p = 0.90'*
*C = 287.27'*
*Start = Sta. 1146+78.98*
*End = Sta. 1149+66.30*
*C.B. = N07°59'07"W*

*CURVE DATA: I71-7*
*P.I. = STA. 1160+25.92*
*Δ = 10°33'58" RT*
*Dc = 00°30'00"*
*R = 11,459.16'*
*T = 1,059.63'*
*L = 2,113.24'*
*E = 48.89'*
*Emax = EXISTING*

*CURVE DATA: I71-8*
*P.I. = STA. 1173+92.11*
*Δ = 06°14'43" RT*
*Dc = 01°00'00"*
*R = 5,729.58'*
*T = 312.57'*
*L = 624.52'*
*E = 8.52'*
*Emax = EXISTING*

*CURVE DATA: I71-9*
*P.I. = STA. 1193+28.51*
*Δ = 29°42'28" LT*
*Dc = 01°15'00"*
*R = 4,583.66'*
*T = 1,215.67'*
*L = 2,376.62'*
*E = 158.47'*
*Emax = EXISTING*

*CURVE DATA: I71-10*
*P.I. = STA. 1217+10.76*
*Δ = 16°12'05" RT*
*Dc = 01°00'00"*
*R = 5,729.58'*
*T = 815.52'*
*L = 1,620.15'*
*E = 57.75'*
*Emax = EXISTING*

HORIZONTAL SCALE IN FEET
0 100 200 400


# SCHEMATIC PLAN
## STA. 1110+00.00 TO STA. 1230+00.00

DESIGN AGENCY
Jacobs

DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT ID: 109164
SHEET: P-4 TOTAL: 618

FRA-71-19.10

MODEL: Schematic Plan - GB20 MAPSHEET: 66x34 (in.) DATE: 2/17/2026 TIME: 7:23:07 AM PITDRV: DHDOT_PDF_V1.prtdat PITSTBL: DHDOT_Plot.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CHDOTCIVIL3D WORKSET: DEFAULT PRODUCT: OpenRoadsDesigner 24.00.0.25
FILE: N:\Projects\Transportation\Highway\Colorado\Fairplay\109164_Hwy 285 at CR 71 & CR 5 Intersection Improvements\Design\Roadway\Plan Sheets\FRA-71-19.10.dwg




*CURVE DATA: I71-11*
*P.I. = STA. 1318+02.63*
*Δ = 45°31'52" RT*
*Dc = 01°30'00"*
*R = 3,819.72'*
*Ls = 250.00'*
*Θs = 01°52'30"*
*LT = 166.68'*
*ST = 83.34'*
*Lc = 2,785.41'*
*Ts = 1,728.25'*
*Es = 323.45'*
*Emax = 0.050*
*S.C. = 1303+24.38*
*C.S. = 1331+09.80*

*CURVE DATA: I71-12*
*P.I. = STA. 1359+02.77*
*Δ = 39°33'14" LT*
*Dc = 01°30'00"*
*R = 3,819.72'*
*Ls = 250.00'*
*Θs = 01°52'30"*
*LT = 166.68'*
*ST = 83.34'*
*Lc = 2,386.92'*
*Ts = 1,498.69'*
*Es = 240.14'*
*Emax = EXISTING*
*S.C. = 1346+54.09*
*C.S. = 1370+41.01*

*CURVE DATA: MORB-1*
*P.I. = STA. 3321+05.52*
*Δ = 29°46'27" RT*
*Dc = 03°00'00"*
*R = 1,909.86'*
*T = 507.71'*
*L = 992.47'*
*E = 66.33'*
*Emax = 0.050*

*CURVE DATA: MORC-1*
*P.I. = STA. 4299+26.82*
*Δ = 06°36'00" RT*
*Dc = 01°30'00"*
*R = 3,819.72'*
*T = 220.24'*
*L = 440'*
*E = 6.34'*
*Emax = 0.041*

*CURVE DATA: MORC-2*
*P.I. = STA. 4303+89.72*
*Δ = 14°30'37" RT*
*Dc = 03°00'00"*
*R = 1,909.86'*
*T = 243.14'*
*L = 483.67'*
*E = 15.41'*
*Emax = 0.050*

*SPIRAL DATA: MORC-3*
*P.I. = STA. 4306+80.26*
*Ls = 150.00'*
*Θs = 02°15'00"*
*LT = 100.01'*
*ST = 50.01'*
*x = 149.94'*
*y = 3.93'*
*k = 75.00'*
*p = 0.49'*
*C = 149.99'*
*Start = Sta. 4306+30.25*
*End = Sta. 4307+80.25*
*C.B. = N19°23'00"E*

*CURVE DATA: MORC-4*
*P.I. = STA. 4310+54.05*
*Δ = 16°59'40" LT*
*Dc = 08°00'00"*
*R = 716.20'*
*Ls = 100.00'*
*Θs = 04°00'00"*
*LT = 66.68'*
*ST = 33.35'*
*Lc = 112.43'*
*Ts = 157.08'*
*Es = 8.54'*
*Emax = EXSITING*
*S.C. = 4309+96.97*
*C.S. = 4311+09.40*

*SPIRAL DATA: MORD-1*
*P.I. = STA. 5302+39.87*
*Ls = 250.00'*
*Θs = 00°56'15"*
*LT = 166.67'*
*ST = 83.34'*
*x = 249.99'*
*y = 1.36'*
*k = 125.00'*
*p = 0.34'*
*C = 250.00'*
*Start = Sta. 5300+73.20*
*End = Sta. 5303+23.20*
*C.B. = N04°41'06"W*

*CURVE DATA: MORD-2*
*P.I. = STA. 5304+58.68*
*Δ = 02°01'55" LT*
*Dc = 00°45'00"*
*R = 7,639.44'*
*T = 135.48'*
*L = 270.93'*
*E = 1.20'*
*Emax = 0.018*

*CURVE DATA: MORD-3*
*P.I. = STA. 5309+47.68*
*Δ = 09°06'08" RT*
*Dc = 02°59'18"*
*R = 1,917.34'*
*T = 152.62'*
*L = 304.6'*
*E = 6.06'*
*Emax = 0.034*

*CURVE DATA: SINCA-1*
*P.I. = STA. 2322+90.10*
*Δ = 27°18'30" LT*
*Dc = 19°45'00"*
*R = 290.11'*
*T = 70.47'*
*L = 138.27'*
*E = 8.44'*
*Emax = 0.058*

*SPIRAL DATA: SINCA-2*
*P.I. = STA. 2324+60.52*
*Ls = 300.00'*
*Θs = 29°37'30"*
*LT = 202.87'*
*ST = 102.62'*
*x = 278.97'*
*y = 100.29'*
*k = 148.67'*
*p = 12.80'*
*C = 296.45'*
*Start = Sta. 2323+57.90*
*End = Sta. 2326+57.90*
*C.B. = N45°58'34"E*

*CURVE DATA: SINCA-3*
*P.I. = STA. 2329+05.37*
*Δ = 06°10'50" RT*
*Dc = 01°15'00"*
*R = 4,583.66'*
*T = 247.47'*
*L = 494.45'*
*E = 6.68'*
*Emax = 0.028*

*SPIRAL DATA: SINCE-1*
*P.I. = STA. 6321+67.37*
*Ls = 200.00'*
*Θs = 38°00'00"*
*LT = 136.54'*
*ST = 69.59'*
*x = 191.38'*
*y = 42.85'*
*k = 98.55'*
*p = 10.88'*
*C = 196.12'*
*Start = Sta. 6320+30.83*
*End = Sta. 6322+30.83*
*C.B. = N08°00'21"E*

*CURVE DATA: SINCE-2*
*P.I. = STA. 6323+35.18*
*Δ = 69°22'34" LT*
*Dc = 38°00'00"*
*R = 150.78'*
*T = 104.36'*
*L = 182.57'*
*E = 32.59'*
*Emax = 0.060*

1 POT STA. 45+64.26
2 POT STA. 55+10.59
3 POT STA. 6317+89.49
4 TS STA. 6320+30.83
5 SC STA. 6322+30.83
6 PT STA. 6324+13.40
7 PI STA. 53+08.88

A1 N03°08'20"E
B1 S87°32'56"E
A2 S86°56'35"E
B2 N86°45'05"W


HORIZONTAL SCALE IN FEET
0 100 200 400

# SCHEMATIC PLAN
## STA. 1230+00.00 TO STA. 1350+00.00

DESIGN AGENCY
Jacobs
DESIGNER CGL
REVIEWER MCK 02/19/26
PROJECT ID 109164
SHEET P.5 TOTAL 618

FRA-71-19.10

MODEL: Schematic Plan - GB03 PAPERSIZE: 66x34 (in.) DATE: 2/11/2026 TIME: 7:23:14 AM PITDRV: DWGT_PDF_IF_LAYOUT_PITDRV_DWGT_PDF_IF_LAYOUT_PITDRV_DWGT_PDF_IF_LAYOUT_PITDRV_




PI STA. 43+43.67
PI STA. 53+84.66
POT STA. 56+28.66

S88°09'26"E
N09°07'27"E
N22°58'43"W
N24°13'20"W
N86°55'57"W

*CURVE DATA: I71-12*
*P.I. = STA. 1359+02.77*
*Δ = 39°33'14" LT*
*Dc = 01°30'00"*
*R = 3,819.72'*
*Ls = 250.00'*
*Θs = 01°52'30"*
*LT = 166.68'*
*ST = 83.34'*
*Lc = 2,386.92'*
*Ts = 1,498.69'*
*Es = 240.14'*
*Emax = EXISTING*
*S.C. = 1346+54.09*
*C.S. = 1370+41.01*

*CURVE DATA: I71-13*
*P.I. = STA. 1450+88.71*
*Δ = 24°44'23" RT*
*Dc = 00°28'00"*
*R = 12,277.67'*
*T = 2,692.64'*
*L = 5,301.35'*
*E = 291.8'*
*Emax = EXISTING*

*CURVE DATA: S161A-1*
*P.I. = STA. 2404+74.99*
*Δ = 07°31'50" RT*
*Dc = 01°30'00"*
*R = 3,819.72'*
*T = 251.38'*
*L = 502.03'*
*E = 8.26'*
*Emax = EXISTING*

*SPIRAL DATA: S161A-2*
*P.I. = STA. 2408+79.57*
*Ls = 250.00'*
*Θs = 11°52'30"*
*LT = 153.93'*
*ST = 96.88'*
*x = 248.74'*
*y = 19.94'*
*k = 101.36'*
*p = 2.95'*
*C = 249.54'*
*Start = Sta. 2407+25.64*
*End = Sta. 2409+75.64*
*C.B. = N14°51'48"E*

*CURVE DATA: S161A-3*
*P.I. = STA. 2410+32.84*
*Δ = 09°07'59" RT*
*Dc = 08°00'00"*
*R = 716.20'*
*T = 57.2'*
*L = 114.16'*
*E = 2.28'*
*Emax = EXISTING*

*SPIRAL DATA: S161A-4*
*P.I. = STA. 2411+39.86*
*Ls = 150.00'*
*Θs = 06°00'00"*
*LT = 100.06'*
*ST = 50.05'*
*x = 149.56'*
*y = 10.46'*
*k = 74.97'*
*p = 1.31'*
*C = 149.93'*
*Start = Sta. 2410+89.80*
*End = Sta. 2412+39.80*
*C.B. = N35°17'21"E*

*SPIRAL DATA: S161A-5*
*P.I. = STA. 2414+53.16*
*Ls = 125.00'*
*Θs = 10°56'15"*
*LT = 83.49'*
*ST = 41.81'*
*x = 124.55'*
*y = 7.93'*
*k = 62.42'*
*p = 1.99'*
*C = 124.80'*
*Start = Sta. 2413+69.66*
*End = Sta. 2414+94.66*
*C.B. = N33°38'39"E*

*CURVE DATA: S161A-6*
*P.I. = STA. 2415+44.26*
*Δ = 17°13'38" LT*
*Dc = 17°30'00"*
*R = 327.40'*
*T = 49.60'*
*L = 98.44'*
*E = 3.74'*
*Emax = EXISTING*

*CURVE DATA: S161B-1*
*P.I. = STA. 3408+38.14*
*Δ = 24°05'40" LT*
*Dc = 07°30'00"*
*R = 763.94'*
*Ls = 250.00'*
*Θs = 09°22'30"*
*LT = 166.90'*
*ST = 83.55'*
*Lc = 71.26'*
*Ts = 288.65'*
*Es = 20.69'*
*Emax = EXISTING*
*S.C. = 3407+99.49*
*C.S. = 3408+70.75*

*SPIRAL DATA: SR161B-2*
*P.I. = STA. 3413+87.79*
*Ls = 250.00'*
*Θs = 15°37'30"*
*LT = 167.32'*
*ST = 83.93'*
*x = 248.15'*
*y = 22.61'*
*k = 124.69'*
*p = 5.67'*
*C = 249.17'*
*Start = Sta. 3412+20.47*
*End = Sta. 3414+70.47*
*C.B. = N29°25'39"W*

*CURVE DATA: SR161B-3*
*P.I. = STA. 3416+13.17*
*Δ = 34°35'06" LT*
*Dc = 12°30'00"*
*R = 458.37'*
*T = 142.70'*
*L = 276.68'*
*E = 21.70'*
*Emax = EXISTING*

*SPIRAL DATA: SR161B-4*
*P.I. = STA. 3418+14.12*
*Ls = 200.00'*
*Θs = 12°30'00"*
*LT = 133.67'*
*ST = 66.97'*
*x = 197.47'*
*y = 28.93'*
*k = 99.84'*
*p = 3.63'*
*C = 199.58'*
*Start = Sta. 3417+47.15*
*End = Sta. 3419+47.15*
*C.B. = N82°46'03"W*

*CURVE DATA: SR161C-1*
*P.I. = STA. 4416+67.65*
*Δ = 29°05'35" RT*
*Dc = 13°00'00"*
*R = 440.74'*
*T = 114.36'*
*L = 223.79'*
*E = 14.6'*
*Emax = EXISTING*

*CURVE DATA: S161C-2*
*P.I. = STA. 4422+66.45*
*Δ = 28°17'03" LT*
*Dc = 07°30'00"*
*R = 763.94'*
*Ls = 200.00'*
*Θs = 07°30'00"*
*LT = 133.45'*
*ST = 66.78'*
*Lc = 177.12'*
*Ts = 292.98'*
*Es = 26.13'*
*Emax = EXISTING*
*S.C. = 4421+73.47*
*C.S. = 4423+50.59*

*CURVE DATA: S161D-1*
*P.I. = STA. 5424+16.80*
*Δ = 26°32'51" RT*
*Dc = 07°00'00"*
*R = 818.51'*
*Ls = 250.00'*
*Θs = 08°45'00"*
*LT = 166.87'*
*ST = 83.52'*
*Lc = 129.25'*
*Ts = 318.74'*
*Es = 25.73'*
*Emax = EXISTING*
*S.C. = 5423+48.06*
*C.S. = 5424+77.31*

*CURVE DATA: S161D-2*
*P.I. = STA. 5433+89.78*
*Δ = 05°57'16" RT*
*Dc = 00°45'00"*
*R = 7,639.44'*
*T = 397.32'*
*L = 793.92'*
*E = 10.32'*
*Emax = EXISTING*

HORIZONTAL SCALE IN FEET
0 100 200 400


# SCHEMATIC PLAN
## STA. 1350+00.00 TO STA. 1460+00.00

DESIGN AGENCY
Jacobs

DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT ID: 109164
SHEET: P.6 TOTAL: 618

FRA-71-19.10

MODEL: Schematic Plan - GB004 PAGESIZE: 66x34 (in.) DATE: 2/11/2026 TIME: 7:23:21 AM PTDRV: DHDOT_PDF_11 pltbl: PSTBL: DHDOT_Plot.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: DHDOTD01 WORKSET: 00154 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. This file is CUI // LIMITED DISTRIBUTION // Proprietary Information. Unauthorized Use, Disclosure or Distribution is Prohibited.




*CURVE DATA: I71-13*
*P.I. = STA. 1450+88.71*
*Δ = 24°44'23" RT*
*Dc = 00°28'00"*
*R = 12,277.67'*
*T = 2,692.64'*
*L = 5,301.35'*
*E = 291.8'*
*Emax = EXISTING*

HORIZONTAL SCALE IN FEET
0 100 200 400

# SCHEMATIC PLAN
# STA. 1460+00.00 TO END WORK

DESIGN AGENCY
Jacobs

DESIGNER
CGL


REVIEWER
MCK 02/19/26

PROJECT ID
109164

SHEET P.7 TOTAL 618

FRA-71-19.10


MODEL: Schematic Plan - GB05 MATERIAL: 6in14.5in | DATE: 2/17/2026 TIME: 7:23:27 AM PITDRV: DHDOT_PDF_V-14.tbl& PENTBL: DHDOT_Plan.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: DHDOTCIVIL3D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.0.25
ALL INFORMATION CONTAINED HEREIN IS THE PROPERTY OF THE STATE OF OHIO DEPARTMENT OF TRANSPORTATION AND IS NOT TO BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT IS SPECIFICALLY FURNISHED WITHOUT THE WRITTEN PERMISSION OF THE DEPARTMENT.




EXISTING SUPERELEVATED SECTION - IR-71

STA. 1112+00.00± TO STA. 1117+00.00±

(HIAWATHA PARK DRIVE BRIDGE: STA. 1113+28.70 TO STA. 1115+44.66)





EXISTING NORMAL SECTION - IR-71

STA. 1250+00.00± TO STA. 1300+75.00±

(COOKE ROAD BRIDGE: STA. 1256+21.72 TO STA. 1258+46.27)

## EXISTING LEGEND

- (A) 2"± ASPHALT CONCRETE COURSE
- (B) 2½"± ASPHALT CONCRETE COURSE
- (B+) 3"± ASPHALT CONCRETE COURSE
- (C) 4½"± ASPHALT CONCRETE COURSES
- (D) 5¼"± ASPHALT CONCRETE COURSES
- (E) 3" - 4½"± ASPHALT CONCRETE COURSES
- (E+) 3" - 6¾"± ASPHALT CONCRETE COURSES
- (F) 3¾" - 5¼"± ASPHALT CONCRETE COURSES
- (G) 5¾" - 7"± ASPHALT CONCRETE COURSES
- (H) 2¾"± BITUMINOUS AGGREGATE BASE
- (I) 3"± BITUMINOUS AGGREGATE BASE
- (J) 4"± BITUMINOUS AGGREGATE BASE
- (K) 5¼"± BITUMINOUS AGGREGATE BASE
- (L) 5½"± BITUMINOUS AGGREGATE BASE
- (M) 6"± BITUMINOUS AGGREGATE BASE
- (N) 7"± BITUMINOUS AGGREGATE BASE
- (O) 10"± BITUMINOUS AGGREGATE BASE
- (P) 11"± BITUMINOUS AGGREGATE BASE
- (Q) 13"± BITUMINOUS AGGREGATE BASE
- (R) 15½"± ASPHALT CONCRETE BASE
- (S) 8"± MACADAM BASE
- (T) 3"± WATERPROOFED AGGREGATE BASE COURSE
- (T+) 6" - 10½" PLAIN CONCRETE PAVEMENT
- (U) 8"± PORTLAND CEMENT CONCRETE BASE
- (V) 9"± PORTLAND CEMENT CONCRETE BASE
- (V+) 10" CONCRETE BASE
- (W) 10"± REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT
- (X) 12"± REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT
- (Y) 12¾"± REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT
- (Z) 6"± AGGREGATE BASE
- (AA) 7"± AGGREGATE BASE
- (BB) 8"± AGGREGATE BASE
- (CC) 9"± AGGREGATE BASE
- (DD) 12½"± AGGREGATE BASE
- (EE) VARIABLE DEPTH AGGREGATE BASE
- (FF) 3" - 7"± STABILIZED CRUSHED AGGREGATE
- (GG) 5"± STABILIZED CRUSHED AGGREGATE
- (HH) 7"± STABILIZED CRUSHED AGGREGATE
- (II) 6"± SUBBASE
- (JJ) 7"± SUBBASE
- (KK) 9"± SUBBASE
- (LL) 10"± SUBBASE
- (MM) VARIABLE DEPTH SUBBASE
- (NN) CONCRETE BARRIER, TYPE B-50
- (OO) CONCRETE BARRIER, TYPE C-50
- (PP) CONCRETE BARRIER, TYPE D-50
- (QQ) CONCRETE BARRIER
- (RR) CONCRETE BARRIER, TYPE B
- (SS) CONCRETE BARRIER, TYPE D
- (TT) EXISTING UNDERDRAINS
- (UU) 4"± CONCRETE CAP
- (VV) CONCRETE CURB
- (VW) 9"± PLAIN CONCRETE PAVEMENT
- (XX) CONCRETE CURB AND GUTTER
- (YY) CONCRETE MEDIAN
- (ZZ) CONCRETE SIDEWALK





EXISTING RIGID PAVEMENT ALTERNATE #1

IR-71: MAINLINE PAVEMENT

STA. 1309+05.00± TO STA. 1317+25.00±

(INCLUDES RAMP AND GORE AREAS)




EXISTING FLEXIBLE PAVEMENT ALTERNATE #2

IR-71: NOSE REPLACEMENT

(EXACT LIMITS UNKNOWN - USED TO REPLACE ORIGINAL CONCRETE NOSES IN EXISTING GORE AREAS VARYING FROM 2' TO 10' WIDE.)

MORSE RD, RAMP C


EXISTING TYPICAL SECTIONS
I-71

DESIGN AGENCY
Jacobs

DESIGNER MCK
REVIEWER BAP 03/24/26
PROJECT ID 109164
SHEET P.8 TOTAL 618

FRA-71-19.10


MODEL: Cx_Typ_Sections - Sheet: 1 PWPREQD: 66x44 in | DATE: 3/17/2026 TIME: 7:23:55 AM PCTBW: ON|OFF: |PSF: |LAYER: |PENTBL: ON|OFF: |PSF: |LAYER: |PENTBL: ON|OFF: |PSF: |LAYER: |PENTBL: USER: Chris.Lawrence1@jacobs.com WORKSPACE: ON|OFF|SAVE WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. THIS DRAWING AND ITS CONTENTS ARE THE PROPERTY OF JACOBS AND SHALL NOT BE REPRODUCED OR PUBLISHED WITHOUT THE PRIOR WRITTEN CONSENT OF JACOBS.




EXISTING SUPERELEVATED SECTION - IR-71

STA. 1300+75.00± TO STA. 1313+00.00±


(MORSE ROAD BRIDGE: STA. 1311+84.64 TO STA. 1313+00.00)




EXISTING SUPERELEVATED SECTION - IR-71

STA. 1313+00.00± TO STA. 1333+55.00±

(MORSE ROAD BRIDGE: STA. 1313+00.00 TO STA. 1314+10.10)




EXISTING NORMAL SECTION - IR-71

STA. 1333+55.00± TO STA. 1344+05.00±

EXISTING TYPICAL SECTIONS
I-71

DESIGN AGENCY
Jacobs

DESIGNER
MCK


REVIEWER
BAP 03/24/26

PROJECT ID
109164

SHEET P-9 TOTAL 618


FRA-71-19.10

MODEL: Cx_Typ_Sections - Sheet 2 PAPERSIZE: 66x44 in | DATE: 3/17/2026 TIME: 7:23:00 AM PITONY: ONDOT_PSI_LF.pltcfg PENTBL: ONDOT_Plot.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: ONDOTDistrict WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. Unauthorized use or distribution prohibited. This file is subject to the limited rights set forth in the applicable ODOT contract. Use pursuant to Section 1709.66 of the Ohio Revised Code may be permitted.





EXISTING NORMAL SECTION - I-71

STA. 1402+00.00± TO STA. 1423+85.00±
(SR 161 BRIDGE: STA. 1414+93.80 TO STA. 1417+16.30)





EXISTING SHOULDER SECTION

STA. 1421+10.00± TO STA. 1423+85.00±




EXISTING DECELERATION SECTION

STA. 1377+00.00± TO STA. 1395+10.00±




EXISTING DECELERATION SECTION

STA. 1395+10.00± TO STA. 1402+25.00±

EXISTING TYPICAL SECTIONS
I-71

DESIGN AGENCY
Jacobs

DESIGNER
MCK


REVIEWER
BAP 03/24/26

PROJECT ID
109164


SHEET P.10 TOTAL 618

FRA-71-19.10


MODEL: Ex_Typ_Sections - Sheet 3 PWPREDIR: 64x44 in. | DATE: 20250305 TIME: 7:23:01 AM PITCHY: ON|OFF: ON|PSF_PSF_1.pltcfg PENTBL: ON|OFF_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: ON|OUTLOUD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS.




EXISTING NORMAL SECTION - I-71
STA. 1423+85.00± TO STA. 1450+00.00±




EXISTING ACCELERATION SECTION - I-71
STA. 1430+35.00± TO STA. 1436+60.00±




EXISTING SHOULDER SECTION - I-71
STA. 1436+60.00± TO STA. 1450+00.00±


EXISTING TYPICAL SECTIONS
I-71

DESIGN AGENCY
Jacobs

DESIGNER
MCK
REVIEWER
BAP 03/24/26
PROJECT ID
109164
SHEET P.11
TOTAL 618


FRA-71-19.10

MODEL: Ex_Typ_Sections - Sheet 4 - PWP8028 - 66x44 in. | DATE: 3/17/2026 - TIME: 7:23:03 AM - PCTDEV: DWGPT_PW.ctb - PCTBL: DWGPT_Pen.tbl - USER: Chris.Lawrence1@jacobs.com - WORKSPACE: D:\ROOTS\x0 - WORKSET: 109164 - PRODUCT: OpenRoadsDesigner 24.00.0.25
ALL RIGHTS RESERVED. THIS DRAWING AND ITS CONTENTS ARE THE PROPERTY OF JACOBS AND SHALL NOT BE REPRODUCED, PUBLISHED OR USED IN ANY WAY WITHOUT THE PRIOR WRITTEN PERMISSION OF JACOBS.





EXISTING SUPERELEVATED SECTION - RAMP

MORSE RD, RAMP D - STA. 5303+88.00± TO STA. 5310+00.00±





EXISTING SUPERELEVATED SECTION - RAMP

SINCLAIR RD, RAMP A - STA. 2322+13.00± TO STA. 2325+63.00±





EXISTING SUPERELEVATED SECTION - RAMP

MORSE RD, RAMP B - STA. 3318+00.00± TO STA. 3320+87.00±
MORSE RD, RAMP C - STA. 4301+20.00± TO STA. 4305+00.00±




EXISTING SUPERELEVATED SECTION - RAMP

SINCLAIR RD, RAMP E - STA. 6320+74.00± TO STA. 6323+47.00±




EXISTING TWO-WAY RAMP SECTION

SINCLAIR RD, RAMP A - STA. 2319+08.00± TO STA. 2322+13.00±
SINCLAIR RD, RAMP E - STA. 6323+47.00± TO STA. 6326+46.00±

EXISTING TYPICAL SECTIONS
RAMPS

FRA-71-19.10

MODEL: Ex. Typ. Sections - Sheet 5 PWPREQD: 66x44 in | DATE: 3/17/2026 TIME: 7:23:03 AM PITCHY: DHDOT_PSI_1-pltcfg PENTBL: DHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: DHDOTGIS02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DRAWINGS ARE PROPRIETARY AND COPYRIGHTED MATERIAL. THEY ARE NOT TO BE USED FOR ANY PURPOSE WHATSOEVER WITHOUT THE WRITTEN CONSENT OF THE ENGINEER.

DESIGN AGENCY
Jacobs


DESIGNER
MCK

REVIEWER
BAP 03/24/26


PROJECT ID
109164

SHEET P.12 | TOTAL 618

FRA-71-19.10
MODEL: Cs_Typ_Section - Sheet: RMPR028_66x44 in | DATE: 3/17/2026 TIME: 7:23:03 AM PCTOPI: DWGPT_PSI_31.pltcfg, PENTBL: DWGPT_Print.ctb USER: ChrisLawrence1@jacobs.com WORKSPACE: DWGOUT0x03 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. THIS DRAWING AND ITS CONTENTS ARE THE PROPERTY OF JACOBS AND SHALL NOT BE REPRODUCED, PUBLISHED OR USED IN ANY WAY WITHOUT THE PRIOR WRITTEN PERMISSION OF JACOBS.




EXISTING NORMAL SECTION - MORSE RD.
STA. 48+45.00 TO STA. 51+40.00





EXISTING NORMAL SECTION - S.R. 161
STA. 48+50.00 TO STA. 51+50.00

EXISTING TYPICAL SECTIONS
SIDE STREETS


DESIGN AGENCY
Jacobs

DESIGNER: MCK
REVIEWER: BAP 03/24/26
PROJECT ID: 109164
SHEET: P.13 | TOTAL: 618




I-71 - NORMAL SECTION

STA. 1269+00.00 TO STA. 1276+50.00




EXISTING NORMAL SECTION - IR-71

STA. 1283+00.00 TO STA. 1288+00.00

A VARIES 17.0' TO 21.25'
STA. 1283+00.00 TO STA. 1286+00.00

B VARIES 12.0' TO 10.0'
STA. 1283+00.00 TO STA. 1286+00.00

C VARIES 0.0' TO 2.0'
STA. 1283+00.00 TO STA. 1286+00.00

D VARIES 0.0' TO 9.0'
STA. 1283+00.00 TO STA. 1286+00.00

E VARIES 11.5' TO 4.5'
STA. 1283+00.00 TO STA. 1286+00.00

C SAWCUT LINE OFFSET CONSTANT 10.25' FROM ℄

F SEE PAVEMENT DETAIL SHEETS FOR CROSS SLOPE TRANSITIONS

G NJ BARRIER, TYPE D-50 FROM
STA. 1283+00.00 TO STA. 1283+40.00

## PROPOSED LEGEND

A SEE EXISTING TYPICAL SECTIONS FOR PAV'T BUILDUP WITHIN SPECIFICED STATION LIMITS
1 ITEM 442 - 1½" ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE A (447)
2 ITEM 407 - NON-TRACKING TACK COAT
3 ITEM 442 - 1¾" ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5MM, TYPE A (446)
4 ITEM 301 - 9" ASPHALT CONCRETE BASE, PG 64-22, (449) - (PLACE IN 2 EQUAL LIFTS)
5 ITEM 302 - 9" ASPHALT CONCRETE BASE, PG 64-22, (449) - (PLACE IN 2 EQUAL LIFTS)
6 ITEM 304 - 6" AGGREGATE BASE
7 ITEM 204 - SUBGRADE COMPACTION
8 ITEM 204 - PROOF ROLLING
9 ITEM 204 - SUBGRADE REPAIR/STABILIZATION
10 ITEM 442 - 2½" ASPHALT CONCRETE INTERMEDIATE COURSE, 12.5MM, TYPE A (446)
11 ITEM 254 - PAVEMENT PLANING, ASPHALT CONCRETE (1½")
12 ITEM 254 - PAVEMENT PLANING, ASPHALT CONCRETE (1½" MIN. - 5½" MAX.)
13 ITEM 605 - 6" SHALLOW PIPE UNDERDRAINS
14 ITEM 605 - 6" BASE PIPE UNDERDRAINS
15 ITEM 609 - CURB, TYPE 4-C
16 ITEM 609 - CONCRETE MEDIAN
17 ITEM 606 - GUARDRAIL, TYPE MGS
18 ITEM 606 - GUARDRAIL, TYPE MGS HALF/QUARTER POST SPACING
19 ITEM 622 - CONCRETE BARRIER, SINGLE SLOPE, TYPE B1
20 ITEM 622 - CONCRETE BARRIER, SINGLE SLOPE, TYPE C1
21 ITEM 622 - CONCRETE BARRIER, SINGLE SLOPE, TYPE D
22 ITEM 304 - 8" AGGREGATE BASE
23 ITEM 659 - SEEDING AND MULCHING
24 ITEM 601 - CONCRETE SLOPE PROTECTION
25 ITEM 253 - PAVEMENT REPAIR
26 ITEM 609 - MEDIAN, MISC.: 4" STAMPED AND COLORED CONCRETE
27 ITEM 204 - GRANULAR MATERIAL, TYPE B
28 ITEM 608 - 4" CONCRETE WALK
29 ITEM 511 - CONCRETE, MISC.: 4" CONCRETE CAP
30 ITEM 511 - CLASS Q2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPET)
31 ITEM 526 - REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=17")
32 ITEM 622 - BARRIER, MISC.: NJ BARRIER, TYPE D-50
33 ITEM 622 - BARRIER, MISC.: NJ BARRIER, TYPE B-50
34 ITEM 411 - STABILIZED CRUSHED AGGREGATE

PROPOSED TYPICAL SECTIONS
I-71


FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 1 IMPERIOUS: 66x34 (in.) DATE: 3/31/2026 TIME: 1:02:05 PM PITDW: ONDP_PDF_P-LetterTB_PWIDE_ONDP_Pwide USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCAD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL CONTENTS © 2026 JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES. ALL RIGHTS RESERVED. THIS DOCUMENT IS PROTECTED UNDER COPYRIGHT LAWS.

DESIGN AGENCY
Jacobs

DESIGNER
MCK
REVIEWER
BAP 03/24/26
PROJECT ID
109164
SHEET
P.14
TOTAL
618

NOTE:
SEE SHEET P.14 FOR PROPOSED TYPICAL SECTION LEGEND.




I-71 - NORMAL SECTION
STA. 1288+00.00 TO STA. 1296+00.00

[A] VARIES 17.0' TO 21.25'
STA. 1288+00.00 TO STA. 1291+00.00

[B] VARIES 11.5'± TO 4.5'±
STA. 1288+00.00 TO STA. 1291+00.00

[B] SAWCUT LINE OFFSET CONSTANT 10.25' FROM ℄

[C] VARIES 0.0' TO 9.0'
STA. 1288+00.00 TO STA. 1291+00.00


[D] VARIES 0.0' TO 2.0'
STA. 1288+00.00 TO STA. 1291+00.00

[F] VARIES 12.0' TO 10.0'
STA. 1288+00.00 TO STA. 1291+00.00


[F] SEE PAVEMENT DETAILS SHEETS FOR CROSS SLOPE TRANSITIONS

[G] VARIES 0.0' TO 15.5'
STA. 1288+23.20 TO STA. 1296+00.00


[H] VARIES 0.0' TO 12.0'
STA. 1293+25.00 TO STA. 1294+25.00





ACCELERATION LANE SECTION
STA. 1288+23.20 TO STA. 1288+73.12




ACCELERATION LANE SECTION
STA. 1288+73.12 TO STA. 1296+00.00




ACCELERATION LANE SECTION
STA. 1293+25.00 TO STA. 1296+00.00





I-71 - NORMAL SECTION
STA. 1296+00.00 TO STA. 1300+74.38

[A] VARIES 15.5' TO 16.0'
STA. 1296+00.00 TO STA. 1296+23.36

[B] VARIES 9.4' TO 8.0'
STA. 1296+00.00 TO STA. 1296+35.00

[C] VARIES 0.0' TO 9.0'
STA. 1296+23.36 TO STA. 1300+73.20




ACCEL. LANE SECTION
STA. 1296+23.36 TO STA. 1300+73.20

(#) SEE SHEET P.25 FOR PROPOSED PAVEMENT BUILDUP DETAILS

PROPOSED TYPICAL SECTIONS
I-71


DESIGN AGENCY
Jacobs

DESIGNER: MCK
REVIEWER: BAP 03/24/26
PROJECT ID: 109164
SHEET: P.15 TOTAL: 618

FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 2 IMPERIOUS: 66x34 (in.) DATE: 3/31/2026 TIME: 1:02:07 PM USER: CHRISTOPHER.J.LAWRENCE@JACOBS.COM WORKSPACE: OHDOT_PROJECT_STATE: OHDOT_Presta USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCLOUD WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.02.25
ELEMENT TEMPLATE LIBRARY: C:\Users\chris.lawrence1\Jacobs\Desktop\OHDOT\OHDOT_Presta.itl CELL LIB: C:\Users\chris.lawrence1\Jacobs\Desktop\OHDOT\OHDOT_CELLS.dgn

NOTE:
SEE SHEET P.14 FOR PROPOSED TYPICAL SECTION LEGEND.




## I-71 - SUPERELEVATED SECTION
STA. 1300+74.38 TO STA. 1326+50.00
STA. 1312+03.05 TO STA. 1314+15.11 (MORSE RD. BRIDGE)

A VARIES FROM 4.75' TO 4.0'
STA. 1311+00.00 TO STA. 1312+01.95

A VARIES FROM 4.0' TO 4.75'
STA. 1314+13.67 TO STA. 1315+50.00

B VARIES FROM 4.75' TO 6.7'
STA. 1311+00.00 TO STA. 1312+03.45

B VARIES FROM 6.7' TO 4.75'
STA. 1314+15.71 TO STA. 1315+50.00

C VARIES FROM 2.0' TO 4.7'
STA. 1311+00.00 TO STA. 1312+03.45

C VARIES FROM 4.7' TO 2.0'
STA. 1314+15.71 TO STA. 1315+50.00

D VARIES FROM 10.0' TO 8.0'
STA. 1304+13.48 TO STA. 1305+12.85

D VARIES FROM 8.0' TO 12.0'
STA. 1307+46.76 TO STA. 1308+45.00

D 12.0' FROM STA. 1308+45.00 TO STA. 1309+77.19

E VARIES FROM 0.0' TO 11.3'
STA. 1304+13.48 TO STA. 1309+77.19

F VARIES FROM 0.0' TO 13.7'
STA. 1309+77.19 TO STA. 1310+97.26

G VARIES FROM 12.0' TO 15.8'
STA. 1309+77.19 TO STA. 1310+97.26

G VARIES FROM 15.8' TO 15.6'
STA. 1310+97.26 TO STA. 1311+07.00

H VARIES FROM 11.3' TO 13.9'
STA. 1309+77.19 TO STA. 1311+07.00

J VARIES FROM 2.5' TO 9.1'
STA. 1309+77.19 TO STA. 1311+07.00

J VARIES FROM 15.6' TO 15.1'
STA. 1311+07.00 TO STA. 1311+41.24

K VARIES FROM 13.9' TO 14.6'
STA. 1311+07.00 TO STA. 1311+41.24

L VARIES FROM 17.0' TO 5.0'
STA. 1311+70.00 TO STA. 1311+90.14

M VARIES FROM 15.1' TO 14.9'
STA. 1311+41.24 TO STA. 1311+70.00

M VARIES FROM 14.9' TO 14.1'
STA. 1311+70.00 TO STA. 1311+90.14

N VARIES FROM 14.6' TO 15.5'
STA. 1311+41.24 TO STA. 1311+90.14

O VARIES FROM 9.1' TO 8.7'
STA. 1313+97.61 TO STA. 1314+16.20


P VARIES FROM 3.7' TO 4.1'
STA. 1313+97.61 TO STA. 1314+16.20

Q VARIES FROM 8.7' TO 8.0'
STA. 1314+16.20 TO STA. 1314+88.42


R VARIES FROM 4.1' TO 9.0'
STA. 1314+16.20 TO STA. 1316+63.48

S VARIES FROM 10.0' TO 10.7'
STA. 1311+87.18 TO STA. 1312+13.24


T SEE PAVEMENT DETAIL SHEETS FOR CROSS SLOPE TRANSITIONS





### ACCELERATION LANE SECTION
STA. 1304+13.48 TO STA. 1309+77.19





### GORE SECTION
STA. 1313+97.61 TO STA. 1314+16.20





### ACCELERATION LANE SECTION
STA. 1309+77.19 TO STA. 1311+07.00





### GORE SECTION
STA. 1314+16.20 TO STA. 1317+89.49





### ACCELERATION LANE SECTION
STA. 1311+07.00 TO STA. 1311+41.24





### ACCELERATION LANE SECTION
STA. 1311+41.24 TO STA. 1311+90.14




### CURBED SECTION
STA. 1310+00.00 TO STA. 1312+13.24
STA. 1314+29.01 TO STA. 1315+00.00




### ACCELERATION LANE SECTION
STA. 1325+90.28 TO STA. 1326+00.00




### MILL & RESURFACE SECTION
STA. 1326+00.00 TO STA. 1326+50.00

* 0.04 OR RATE OF SUPER IF GREATER

(#) SEE SHEET P.25 FOR PROPOSED PAVEMENT BUILDUP DETAILS


PROPOSED TYPICAL SECTIONS
I-71

FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 3 IMPERIOUS: 66x34 (in.) DATE: 3/31/2026 TIME: 1:03:07 PM XREFDWG: DWGREF_PDF_P_v.dwg PENTBL: DWGREF_Penbl USER: Chris.Lawrence@jacobs.com WORKSPACE: DWGOTOLXD WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. THIS FILE MAY NOT BE REPRODUCED, MODIFIED, OR DISTRIBUTED EXCEPT AS SPECIFIED IN WRITING BY BENTLEY SYSTEMS, INCORPORATED.

DESIGN AGENCY
Jacobs
DESIGNER
MCK
REVIEWER
BAP 03/24/26
PROJECT ID
109164
SHEET P.16 TOTAL 618


NOTE:
SEE SHEET P.14 FOR PROPOSED TYPICAL SECTION LEGEND.




I-71 - SUPERELEVATED SECTION
STA. 1326+50.00 TO STA. 1332+85.00

[A] VARIES FROM 12.0' TO 8.2'
STA. 1330+00.00 TO STA. 1331+90.00

[B] VARIES FROM 8.2' TO 6.3'
STA. 1331+90.00 TO STA. 1332+85.00




I-71 - NORMAL SECTION
STA. 1332+85.00 TO STA. 1337+45.00

[A] VARIES 21.25' TO 19.4'
STA. 1336+00.00 TO STA. 1337+45.00

[B] VARIES 10.0' TO 10.7'
STA. 1336+00.00 TO STA. 1337+45.00

[C] VARIES 2.0' TO 1.3'
STA. 1336+00.00 TO STA. 1337+45.00

[D] VARIES 9.0' TO 5.7'
STA. 1336+00.00 TO STA. 1337+45.00

[E] VARIES 4.75' TO 6.8'
STA. 1336+00.00 TO STA. 1337+45.00


[E] SAWCUT LINE OFFSET CONSTANT 10.25' FROM ℄

[F] VARIES FROM 6.3' TO 0.0'
STA. 1332+85.00 TO STA. 1336+00.00


[G] VARIES FROM 18.0' TO 6.0'
STA. 1333+59.80 TO STA. 1334+59.80

[H] SEE PAVEMENT DETAIL SHEETS FOR CROSS SLOPE TRANSITIONS


[I] VARIES FROM 8.0' TO 8.8'
STA. 1335+50.00 TO STA. 1336+00.00





FULL DEPTH SECTION
STA. 1333+30.00 TO STA. 1333+59.80





SHOULDER SECTION
STA. 1333+59.80 TO STA. 1337+45.00




SHOULDER SECTION
STA. 1336+00.00 TO STA. 1337+45.00




ACCELERATION LANE SECTION
STA. 1330+00.00 TO STA. 1331+90.00




ACCELERATION LANE SECTION
STA. 1331+90.00 TO STA. 1332+85.00

* 0.04 OR RATE OF SUPER IF GREATER

(#) SEE SHEET P.25 FOR PROPOSED PAVEMENT BUILDUP DETAILS

PROPOSED TYPICAL SECTIONS
I-71


DESIGN AGENCY
Jacobs

DESIGNER
MCK
REVIEWER
BAP 03/24/26
PROJECT ID
109164
SHEET P.17
TOTAL 618

FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 4 IMPERIOUS: 66x34 (in.) DATE: 3/31/2026 TIME: 10:08 AM USER: CHRISTOPHER_PAUL.LEAR File: C:\Users\christopher.lear\Jacobs\Desktop\Working Files\FRA-71-19.10 Typical Sections Proposed.dgn WORKSPACE: C:\Users\christopher.lear\Jacobs\Desktop\Working Files\OpenRoads Standards\OpenRoads Standards.cwspace WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25

NOTE:
SEE SHEET P.14 FOR PROPOSED TYPICAL SECTION LEGEND.




I-71 - NORMAL SECTION
STA. 1337+45.00 TO STA. 1340+00.00

[A] VARIES FROM 10.0' TO 11.4'
STA. 1338+25.51 TO STA. 1340+00.00

[B] VARIES FROM 10.7' TO 12.0'
STA. 1337+45.00 TO STA. 1340+00.00

[C] VARIES FROM 1.3' TO 0.0'
STA. 1337+45.00 TO STA. 1340+00.00

[D] VARIES FROM 5.7' TO 0.0'
STA. 1337+45.00 TO STA. 1340+00.00

[E] VARIES FROM 6.8' TO 10.0'
STA. 1337+45.00 TO STA. 1340+00.00

[F] SAWCUT LINE OFFSET CONSTANT 10.25' FROM ℄

[F] VARIES FROM 4.75' TO 8.3'
STA. 1338+00.00 TO STA. 1340+00.00

[G] VARIES FROM 9.0' TO 3.9'
STA. 1338+00.00 TO STA. 1340+00.00

[H] VARIES FROM 2.0' TO 0.9'
STA. 1338+00.00 TO STA. 1340+00.00


[I] VARIES FROM 10.0' TO 11.1'
STA. 1338+00.00 TO STA. 1340+00.00

[J] VARIES FROM 9.0'± TO 10.6'±
STA. 1338+00.00 TO STA. 1340+00.00

[K] SEE PAVEMENT DETAIL SHEETS FOR CROSS SLOPE TRANSITIONS

[L] VARIES FROM 19.4' TO 16.0'
STA. 1336+00.00 TO STA. 1340+00.00

[M] VARIES FROM 21.25' TO 18.5'
STA. 1338+00.00 TO STA. 1340+00.00




I-71 - NORMAL SECTION
STA. 1340+00.00 TO STA. 1341+50.00

[A] VARIES FROM 18.5' TO 16.5'
STA. 1340+00.00 TO STA. 1341+50.00

[B] VARIES FROM 8.3' TO 11.0'
STA. 1340+00.00 TO STA. 1341+50.00


[B] SAWCUT LINE OFFSET CONSTANT 10.25' FROM ℄

[C] VARIES FROM 3.9' TO 0.0'
STA. 1340+00.00 TO STA. 1341+50.00

[D] VARIES FROM 0.9' TO 0.0'
STA. 1340+00.00 TO STA. 1341+50.00

[E] VARIES FROM 11.1' TO 12.0'
STA. 1340+00.00 TO STA. 1341+50.00

[F] SEE PAVEMENT DETAIL SHEETS FOR CROSS SLOPE TRANSITIONS




I-71 - NORMAL SECTION
STA. 1405+50.00 TO STA. 1407+37.00
STA. 1425+37.50 TO STA. 1428+00.00

[A] VARIES FROM 18.0' TO 20.0'
STA. 1405+50.00 TO STA. 1407+37.00

[A] VARIES FROM 20.0' TO 19.0'
STA. 1426+00.00 TO STA. 1428+00.00

[B] VARIES FROM 18.0' TO 7.6'
STA. 1405+50.00 TO STA. 1407+37.00

[B] VARIES FROM 7.6' TO 16.4'
STA. 1426+00.00 TO STA. 1428+00.00

[C] VARIES FROM 0.0' TO 9.0'
STA. 1405+50.00 TO STA. 1407+37.00

[C] VARIES FROM 9.0' TO 0.0'
STA. 1426+00.00 TO STA. 1428+00.00

[D] VARIES FROM 0.0' TO 2.0'
STA. 1405+50.00 TO STA. 1407+37.00

[D] VARIES FROM 2.0' TO 0.0'
STA. 1426+00.00 TO STA. 1428+00.00

[E] VARIES FROM 12.0' TO 10.0'
STA. 1405+50.00 TO STA. 1407+37.00

[E] VARIES FROM 10.0' TO 12.0'
STA. 1426+00.00 TO STA. 1428+00.00

[F] SEE PAVEMENT DETAIL SHEETS FOR CROSS SLOPE TRANSITIONS

(#) SEE SHEET P.25 FOR PROPOSED PAVEMENT BUILDUP DETAILS

PROPOSED TYPICAL SECTIONS
I-71


FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 5 IMPERIOUS: 66x34 (in.) DATE: 1/31/2026 TIME: 1:03:09 PM XREFDWG: DWGPT_PSF_P-LAYOUT_PAVTBL.DWGPT_Pavtbl USER: Chris.Lawrence@jacobs.com WORKSPACE: OHDOTCAD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPLIANCE WITH THE BENTLEY LICENSE AGREEMENT PROHIBITED UNAUTHORIZED REPRODUCTION, DISTRIBUTION AND DISCLOSURE.

DESIGN AGENCY
Jacobs

DESIGNER
MCK
REVIEWER
BAP 03/24/26
PROJECT ID
109164
SHEET P.18 TOTAL 618

NOTE:
SEE SHEET P.14 FOR PROPOSED TYPICAL SECTION LEGEND.




I-71 - NORMAL SECTION
STA. 1407+37.00 TO STA. 1425+37.50
STA. 1415+09.00 TO STA. 1417+01.00 (S.R. 161 BRIDGE)

A VARIES FROM 10.8' TO 10.0'
STA. 1407+37.00 TO STA. 1408+00.00

A VARIES FROM 10.0' TO 12.0'
STA. 1411+14.04 TO STA. 1411+64.04

A VARIES FROM 12.6' TO 10.0'
STA. 1417+68.95 TO STA. 1418+00.81

B VARIES FROM 18.0' TO 14.0'
STA. 1421+00.00 TO STA. 1423+96.07

C VARIES FROM 16.6' TO 12.6'
STA. 1421+00.00 TO STA. 1423+96.07


D VARIES FROM 11.7' TO 10.0'
STA. 1407+37.00 TO STA. 1407+80.64

E VARIES FROM 0.0' TO 13.7'
STA. 1413+14.29 TO STA. 1414+14.04


F VARIES FROM 12.0' TO 12.6'
STA. 1413+14.29 TO STA. 1414+24.04

G VARIES FROM 17.0' TO 5.0'
STA. 1414+90.00 TO STA. 1415+09.04


G 5.0' FROM STA. 1417+00.95 TO STA. 1417+49.95





PULLOFF SECTION
STA. 1413+14.29 TO STA. 1414+24.04





PULLOFF SECTION
STA. 1414+24.04 TO STA. 1414+59.04





BARRIER SECTION
STA. 1414+59.04 TO STA. 1415+09.04
STA. 1417+00.95 TO STA. 1417+49.95





CURB SECTION
STA. 1417+49.95 TO STA. 1417+68.95





GORE SECTION
STA. 1424+35.70 TO STA. 1425+37.50





CURB SECTION
STA. 1414+41.04 TO STA. 1414+60.04




BARRIER SECTION
STA. 1414+60.04 TO STA. 1415+09.04
STA. 1417+00.95 TO STA. 1417+49.95




GORE SECTION
STA. 1425+09.50 TO STA. 1425+37.50




I-71 - NORMAL SECTION
STA. 1442+00.00 TO STA. 1447+00.00

(#) SEE SHEET P.25 FOR PROPOSED PAVEMENT BUILDUP DETAILS

PROPOSED TYPICAL SECTIONS
I-71


DESIGN AGENCY
Jacobs

DESIGNER
MCK
REVIEWER
BAP 03/24/26
PROJECT ID
109164
SHEET P.19 TOTAL 618

FRA-71-19.10


MODEL: Proposed Typical Sections - Sheet 6 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 1:03:19 PM JOTDW: DWGP_PDF_P-LetterTB_PENTBL: DWGP_Penlist USER: Chris.Lawrence@jacobs.com WORKSPACE: DWGOTCX01 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Ohio\109164_I-71 Widening Phase 1\Design\Roadway\Typical Sections\Proposed Typical Sections - Sheet 6.dgn

NOTE:
SEE SHEET P.14 FOR PROPOSED TYPICAL SECTION LEGEND.





I-71 - SUPERELEVATED SECTION

STA. 1113+00.00 TO STA. 1113+28.70 (LEFT)
STA. 1113+03.00 TO STA. 1113+28.70 (RIGHT)
(HIAWATHA PARK DRIVE BRIDGE: STA. 1113+28.70 TO STA. 1115+44.85)
STA. 1115+44.85 TO STA. 1115+73.00 (LEFT)
STA. 1115+44.85 TO STA. 1115+70.00 (RIGHT)




I-71 - NORMAL SECTION

STA. 1255+73.00 TO STA. 1256+21.72 (RIGHT)
STA. 1256+00.00 TO STA. 1256+21.72 (LEFT)
(COOKE ROAD BRIDGE: STA. 1256+21.72 TO STA. 1258+46.27)
STA. 1258+46.27 TO STA. 1258+67.00 (RIGHT)
STA. 1258+46.27 TO STA. 1258+94.00 (LEFT)




FULL DEPTH SECTION

STA. 1256+00.00 TO STA. 1256+21.72
STA. 1258+46.27 TO STA. 1258+94.00

A VARIES FROM 9.2' TO 9.8'
STA. 1255+86.40 TO STA. 1256+00.00

B VARIES FROM 5.6' TO 5.4'
STA. 1255+86.40 TO STA. 1256+00.00

C VARIES FROM 11.4' TO 11.6'
STA. 1255+86.40 TO STA. 1256+00.00

D VARIES FROM 11.9' TO 12.8'
STA. 1255+73.00 TO STA. 1256+16.83

D VARIES FROM 12.8' TO 12.1'
STA. 1258+41.88 TO STA. 1258+67.00

E VARIES FROM 5.1' TO 4.2'
STA. 1255+73.00 TO STA. 1256+16.83

E VARIES FROM 4.2' TO 4.9'
STA. 1258+41.88 TO STA. 1258+67.00

F VARIES FROM 10.5' TO 10.7'
STA. 1255+73.00 TO STA. 1255+99.38

F VARIES FROM 12.0' TO 10.3'
STA. 1258+23.90 TO STA. 1258+67.00

G VARIES FROM 9.8' TO 11.5'
STA. 1256+00.00 TO STA. 1256+44.41

G VARIES FROM 10.7' TO 10.1'
STA. 1258+68.21 TO STA. 1258+94.00

H VARIES FROM 5.4' TO 4.6'
STA. 1256+00.00 TO STA. 1256+26.46

H VARIES FROM 4.6' TO 5.7'
STA. 1258+50.54 TO STA. 1258+94.00

I VARIES FROM 11.6' TO 12.4'
STA. 1256+00.00 TO STA. 1256+26.46

I VARIES FROM 12.4' TO 11.3'
STA. 1258+50.54 TO STA. 1258+94.00

* 0.04 OR RATE OF SUPER IF GREATER

(#) SEE SHEET P.25 FOR PROPOSED PAVEMENT BUILDUP DETAILS

PROPOSED TYPICAL SECTIONS
I-71


DESIGN AGENCY
Jacobs


DESIGNER
MCK
REVIEWER
BAP 03/24/26
PROJECT ID
109164
SHEET P.20 TOTAL 618

FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 7 IMPERIOUS: 66x34 (in.) DATE: 3/31/2026 TIME: 10:21:13 AM JOTDW: ONDOT_PDF_P_v4.ctb PENTBL: ONDOT_Pen.tbl USER: Chris.Lawwood@jacobs.com WORKSPACE: OHDOTCAD1 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Columbus\Ohio Rail Connect\Roadway\Sheets\Typical Sections\FRA-71-19.10.dgn


NOTE:
SEE SHEET P.14 FOR PROPOSED TYPICAL SECTION LEGEND.




GORE SECTION

RAMP B: STA. 3321+32.65 TO STA. 3324+14.23
RAMP C: STA. 4298+81.04 TO STA. 4301+60.79




CURBED SECTION

RAMP B: STA. 3319+50.00 TO STA. 3321+32.65

SUPERELEVATED SECTION: MORSE RD. RAMPS B & C

MORSE RD. RAMP B: STA. 3318+00.00 TO STA. 3325+90.28

[A] VARIES FROM 3.0' TO 4.0'
STA. 3319+25.00 TO STA. 3319+50.00

[B] VARIES FROM 16.0' TO 12.0'
STA. 3324+14.23 TO STA. 3325+90.28

[C] VARIES FROM 8.2' TO 6.0'
STA. 3318+00.00 TO STA. 3318+56.06


[C] VARIES FROM 6.0' TO 8.0'
STA. 3324+65.45 TO STA. 3325+90.28

MORSE RD. RAMP C: STA. 4297+06.58 TO STA. 4305+00.00

[A] VARIES FROM 3.0' TO 3.5'
STA. 4304+50.00 TO STA. 4305+00.00

[B] VARIES FROM 12.0' TO 16.0'
STA. 4297+06.58 TO STA. 4298+81.04

[C] 8.0' FROM STA. 4297+14.95 TO STA. 4305+00.00





SUPERELEVATED SECTION: MORSE RD. RAMP D

STA. 5300+73.20 TO STA. 5307+00.00

[A] VARIES FROM 8.0' TO 6.0'
STA. 5300+73.20 TO STA. 5301+23.21


[A] VARIES FROM 6.0' TO 8.3'
STA. 5308+40.00 TO STA. 5309+00.00

[B] SEE PAVEMENT DETAIL SHEETS FOR GRADE BREAK DETAILS WITHIN THE GORE AREA.




GORE SECTION


STA. 5300+73.20 TO STA. 5303+84.94




SUPERELEVATED SECTION: MORSE RD. RAMP D


STA. 5307+00.00 TO STA. 5310+00.00

[A] VARIES FROM 6.0' TO 8.4'
STA. 5309+35.00 TO STA. 5310+00.00




MILL & RESURFACE RAMP SECTION

MORSE RD, RAMP B - STA. 3314+54.15 TO STA. 3318+00.00
MORSE RD, RAMP C - STA. 4305+00.00 TO STA. 4311+61.13




MILL & RESURFACE RAMP SECTION

MORSE RD, RAMP D - STA. 5310+00.00 TO STA. 5312+74.96

* 0.04 OR RATE OF SUPER IF GREATER

(#) SEE SHEET P.25 FOR PROPOSED PAVEMENT BUILDUP DETAILS

PROPOSED TYPICAL SECTIONS
MORSE ROAD RAMPS


DESIGN AGENCY
Jacobs


DESIGNER: MCK
REVIEWER: BAP 03/24/26
PROJECT ID: 109164
SHEET: P.21 TOTAL: 618

FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 8 REFERSETS: 66x34 (in.) DATE: 3/31/2026 TIME: 10:21:28 AM XREFDWG: DWGREF_PDF_P-LAYOUT_PXHTBL: DWGREF_PXHTBL: USER: Chris.Lawrence@jacobs.com WORKSPACE: OHDOTCAD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\Projects\Morse Road Interchange\Roadway\Typical Sections\Proposed Typical Sections.dgn

NOTE:
SEE SHEET P.14 FOR PROPOSED TYPICAL SECTION LEGEND.




SHOULDER SECTION
STA. 6317+89.49 TO STA. 6320+93.86

SUPERELEVATED SECTION: SINCLAIR RD. RAMP E
STA. 6317+89.49 TO STA. 6324+28.39

A VARIES FROM 8.0' TO 6.0'
STA. 6320+30.83 TO STA. 6320+93.86

B VARIES FROM 6.0' TO 3.0'
STA. 6323+63.40 TO STA. 6324+13.40

B 3.0' FROM STA. 6324+13.40 TO STA. 6324+28.39

C 0.0' FROM STA. 6317+89.49 TO STA. 6320+30.83

C VARIES FROM 0.0' TO 2.0'
STA. 6320+30.83 TO STA. 6322+30.83


C VARIES FROM 2.0' TO 0.0'
STA. 6323+63.40 TO STA. 6324+13.40

C 0.0' FROM STA. 6324+13.40 TO STA. 6324+28.39


D SEE PAVEMENT DETAIL SHEETS FOR GRADE BREAK DETAILS WITHIN THE GORE AREA

F 3.0' FROM STA. 6323+50.93 TO STA. 6323+53.35


F VARIES FROM 3.0' TO 2.0'
STA. 6323+53.35 TO STA. 6324+08.97





GORE SECTION
STA. 6317+89.49 TO STA. 6320+97.75





TRAFFIC ISLAND SECTION
STA. 6323+50.93 TO STA. 6324+28.39




MILL & RESURFACE TWO-WAY RAMP SECTION
SINCLAIR RD, RAMP A - STA. 2319+50.00 TO STA. 2321+25.00
SINCLAIR RD, RAMP E - STA. 6326+03.32 TO STA. 6324+28.39




CURBED SECTION
STA. 2321+12.50 TO STA. 2322+40.00

SUPERELEVATED SECTION: SINCLAIR RD. RAMP A
STA. 2321+12.50 TO STA. 2326+57.90

A VARIES FROM 1.0' TO 1.7'
STA. 2322+19.63 TO STA. 2322+40.00

B VARIES FROM 1.7' TO 10.0'
STA. 2322+40.00 TO STA. 2325+00.00


C 24.0' FROM STA. 2321+12.50 TO STA. 2323+57.90

C VARIES FROM 24.0' TO 16.0'
STA. 2323+57.90 TO STA. 2325+33.93


D 1.0' FROM STA. 2322+09.50 TO STA. 2322+19.63

D VARIES FROM 1.0' TO 4.0'
STA. 2322+19.63 TO STA. 2322+88.90


E VARIES FROM 20.0' TO 12.8'
STA. 2325+58.53 TO STA. 2326+57.90




TRAFFIC ISLAND SECTION
STA. 2321+12.50 TO STA. 2322+09.50




GORE SECTION
STA. 2325+58.53 TO STA. 2326+57.90




SUPERELEVATED SECTION: SINCLAIR RD. RAMP A
STA. 2326+57.90 TO STA. 2333+59.80

A VARIES FROM 16.0' TO 12.0'
STA. 2330+47.42 TO STA. 2333+59.80

B VARIES FROM 12.8' TO 0.0'
STA. 2326+57.90 TO STA. 2330+47.42

* 0.04 OR RATE OF SUPER IF GREATER

(#) SEE SHEET P.25 FOR PROPOSED PAVEMENT BUILDUP DETAILS

PROPOSED TYPICAL SECTIONS
SINCLAIR ROAD RAMPS


DESIGN AGENCY
Jacobs

DESIGNER: MCK
REVIEWER: BAP 03/24/26
PROJECT ID: 109164
SHEET: P.22 TOTAL: 618

FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 9 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 1:03:31 PM USERNAME: cmlawrence DESIGN: ORIGIN_PRT_P_v.dwg PRINTED BY: Chris Lawrence@jacobs.com WORKSPACE: OHDOTCAD WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.02.25
ACTIVE: Z:\Projects\Sinclair Road Ramps\Roadway\Typical Sections\Sheet 9 - Proposed Typical Sections.dgn

NOTE:
SEE SHEET P.14 FOR PROPOSED TYPICAL SECTION LEGEND.




I-71 - APPROACH SLAB
SUPERELEVATED SECTION

STA. 1312+02.91 TO STA. 1312+32.79 (MORSE RD BRIDGE)
STA. 1313+84.83 TO STA. 1314+14.97 (MORSE RD BRIDGE)

A VARIES FROM 14.1' TO 12.7'
STA. 1311+90.14 TO STA. 1312+19.48

A VARIES FROM 9.1' TO 9.1'
STA. 1313+68.26 TO STA. 1313+97.61

B VARIES FROM 15.6' TO 16.2'
STA. 1311+92.22 TO STA. 1312+21.45

B VARIES FROM 19.1' TO 19.7'
STA. 1313+70.03 TO STA. 1313+99.45

C VARIES FROM 4.0' TO 4.7'
STA. 1312+01.34 TO STA. 1312+31.13


C VARIES FROM 4.8' TO 4.1'
STA. 1313+82.76 TO STA. 1314+12.81

D VARIES FROM 6.7' TO 6.0'
STA. 1312+03.45 TO STA. 1312+33+.48

D VARIES FROM 6.0' TO 6.8'
STA. 1313+85.69 TO STA. 1314+15.71

E VARIES FROM 10.7' TO 11.4'
STA. 1312+13.24 TO STA. 1312+43.76

E VARIES FROM 10.9' TO 10.0'
STA. 1313+98.49 TO STA. 1314+29.01




I-71 - APPROACH SLAB

STA. 1415+09.04 TO STA. 1415+39.04 (SR 161 BRIDGE)
STA. 1416+70.95 TO STA. 1417+00.95 (SR 161 BRIDGE)

* 0.04 OR RATE OF SUPER IF GREATER

(#) SEE SHEET P.25 FOR PROPOSED PAVEMENT BUILDUP DETAILS

PROPOSED TYPICAL SECTIONS
APPROACH SLABS


FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 23 (MARKER25 46x44 in.) DATE: 3/27/2026 7:44E: 7:23:13 PM JEFFREY.CHADY_PW.SM USER: Chris.Lawrence1@jacobs.com WORKSPACE: ORIGITOUCH WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\Projects\Transportation\Fra-71-19.10\Roadway\Typical Sections\Proposed Typical Sections.dgn

DESIGN AGENCY
Jacobs

DESIGNER
MCK
REVIEWER
BAP 03/24/26
PROJECT ID
109164
SHEET P.23 TOTAL 618

NOTE:
SEE SHEET P.14 FOR PROPOSED TYPICAL SECTION LEGEND.





NORMAL SECTION - S.R. 161
STA. 48+56.00 TO STA. 51+43.00

A VARIES FROM 8.0' TO 7.4'
STA. 50+75.00 TO STA. 51+43.00


B VARIES FROM 43.5' TO 44.6'
STA. 50+75.00 TO STA. 51+43.00

C VARIES FROM 44.5' TO 43.0'
STA. 48+56.00 TO STA. 49+25.00


D VARIES FROM 7.5' TO 9.0'
STA. 50+75.00 TO STA. 51+43.00




EXISTING SHOULDER SECTION
STA. 48+56.00 TO STA. 48+75.00





EXISTING SHOULDER SECTION
STA. 51+11.21 TO STA. 51+43.00





NORMAL SECTION - MORSE RD.
STA. 48+45.00 TO STA. 51+40.00

A FROM STA. 49+15.00 TO STA. 50+78.00


B 10.0' FROM STA. 51+14.17 TO STA. 51+40.00




SIDEWALK SECTION
STA. 48+45.00 TO STA. 48+86.02
STA. 51+14.17 TO STA. 51+40.00




SIDEWALK SECTION
STA. 48+45.00 TO STA. 48+64.00
STA. 50+96.17 TO STA. 51+40.00




NORMAL SECTION - S.R. 161
STA. 46+18.00 TO STA. 48+56.00
STA. 51+43.00 TO STA. 53+62.00


A VARIES FROM 7.4' TO 5.3'
STA. 51+43.00 TO STA. 52+67.01

A VARIES FROM 5.3' TO 4.2'
STA. 52+67.01 TO STA. 53+62.00


B VARIES FROM 44.6' TO 47.0'
STA. 51+43.00 TO STA. 53+62.00

C VARIES FROM 47.5' TO 44.5'
STA. 47+19.00 TO STA. 48+56.00

D VARIES FROM 4.5' TO 7.5'
STA. 47+19.00 TO STA. 48+56.00




EXISTING SHOULDER SECTION
STA. 51+43.00 TO STA. 52+87.00




EXISTING SHOULDER SECTION
STA. 47+19.00 TO STA. 48+56.00

(#) SEE SHEET P.25 FOR PROPOSED PAVEMENT BUILDUP DETAILS

PROPOSED TYPICAL SECTIONS
SR 161


DESIGN AGENCY
Jacobs

DESIGNER: MCK
REVIEWER: BAP 03/24/26
PROJECT ID: 109164
SHEET: P.24 TOTAL: 618


FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 11 PAPERSIZE: 66x44 in | DATE: 3/17/2026 7:44:11 PM BY: PETERS, CHRISTOPHER J. (CPETERS) FILENAME: C:\Users\cpeters\ODOT\Jacobs\Projects - Documents\Active\109164 - SR 161 Roundabout\Roadway\Typical Sections\Typical Sections.dgn
ACTIVE: Proposed Typical Sections - Sheet 11 | REFERENCES: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTOPHER J. (CPETERS) WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25


NOTE:
SEE SHEET 14 FOR PROPOSED TYPICAL SECTION LEGEND.





SHOULDER EDGE
STEP DETAIL





CURBED EDGE
STEP DETAIL





CURBED EDGE STEP
DETAIL WITH GUARDRAIL





SINGLE SLOPE, TYPE B1 EDGE
STEP DETAIL





FULL DEPTH PAVEMENT - GREATER THAN OR EQUAL TO 8' WIDTH
BUILDUP DETAIL





FULL DEPTH PAVEMENT - WIDENING LESS THAN 8' WIDTH
BUILDUP DETAIL





MEDIAN BARRIER REPLACEMENT DETAIL
SUPERELEVATION SECTION




SINGLE SLOPE, TYPE D EDGE
STEP DETAIL





NJ BARRIER, TYPE D-50 EDGE
STEP DETAIL




NOTES:

1. NO. 8 DEFORMED STEEL BARS, 12" LONG @ 4' CENTERS. OMIT DOWELS WHEN TOP IS CONSTRUCTED INTEGRAL WITH THE BASE.
2. 1" RADIUS OR 3/4" CHAMFER
3. PERMISSIBLE 10" RADIUS
4. PERMISSIBLE 1" RADIUS
5. RACEWAY: THE CONTRACTOR SHALL ENSURE THAT THE ELECTRICAL RACEWAY IS CLEAR OF INTERNAL OBSTRUCTIONS. COST OF THE 4" PVC RACWAY FOR LIGHTING SHALL BE INCLUDED IN THE UNIT COST PER FOOT FOR ITEM 622 - BARRIER MISC.: NJ BARRIER, TYPE D-50

ITEM 622 - BARRIER MISC.: NJ BARRIER, TYPE D-50
DETAIL




NOTES:

1. NO. 8 DEFORMED STEEL BARS, 12" LONG @ 4' CENTERS. OMIT DOWELS WHEN TOP IS CONSTRUCTED INTEGRAL WITH THE BASE.
2. 1" RADIUS OR 3/4" CHAMFER
3. PERMISSIBLE 10" RADIUS
4. PERMISSIBLE 1" RADIUS
5. RACEWAY: THE CONTRACTOR SHALL ENSURE THAT THE ELECTRICAL RACEWAY IS CLEAR OF INTERNAL OBSTRUCTIONS. COST OF THE 4" PVC RACWAY FOR LIGHTING SHALL BE INCLUDED IN THE UNIT COST PER FOOT FOR ITEM 622 - BARRIER MISC.: NJ BARRIER, TYPE B-50

ITEM 622 - BARRIER MISC.: NJ BARRIER, TYPE B-50
DETAIL


PROPOSED TYPICAL SECTIONS
DETAILS

FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 12 PAPERSIZE: 66x44 in | DATE: 3/31/2026 7:46:13 PM BY:ERIC.CHADY_PW | 2-plot_PENTBL: CHADY_PW.ctb | USER: Chris.Lawrence1@jacobs.com WORKSPACE: D:\ROUTE\71\FRA-71-19.10\Roadway\Typical Sections\Sheet 12.dgn | WORKSET: 109164 | PRODUCT: OpenRoadDesigner 24.00.02.25
ALL INFORMATION CONTAINED HEREIN IS THE PROPERTY OF JACOBS AND SHALL NOT BE REPRODUCED, COPIED, OR USED IN WHOLE OR IN PART FOR ANY PURPOSE WITHOUT THE WRITTEN PERMISSION OF JACOBS.

DESIGN AGENCY
Jacobs


DESIGNED: MCK
REVIEWED: BAP 03/24/26
PROJECT ID: 109164
SHEET: P.25 TOTAL: 618




Standard tall barrier connection

ELEVATION


## NJ, B-50 TO SS, C1 TRANSITION




Standard tall barrier connection

ELEVATION

## NJ, D-50 TO SS, B1 TRANSITION





A-A
Types B-50




C-C
Type D-50

NJ SHAPE SECTIONS

See Plan Insert sheets for specific NJ Shape Concrete barrier details.




B-B
Types B1 & C1

SINGLE SLOPE SECTIONS

See SCD RM-4.3 and RM-4.5 for specific Single Slope concrete barrier details.

## NOTES

GENERAL: This Insert details the Barrier Transition, to connect existing NJ Concrete Barrier (safety shape) To a new run of Single Slope Concrete Barrier at locations shown on the plans. For NJ barrier shape and other details see the respective plan insert sheets. For Single Slope barrier details, see SCD RM-4.3 (RM-4.5 for Type D).

ADJACENT CONCRETE BARRIER RUNS: Remove any tapered end sections, impact attenuators, or other guardrail hardware from existing barrier end. The barrier to barrier transition is not intended to be used at transition sections (those shown on SCD RM-4.4), inlets, or on Type C or C1 Barrier. If proposed adjacent single slope barrier is Type A or A1, the Barrier Transiton should contain horizontal reinforcing steel similar to that required in the respective single slope barrier. Reinforcement is not shown and should be detailed separately. The adjacent single slope end should be Terminated with a reinforced End Anchor as detailed on The SCDs.

BARRIER FACE TRANSITION: To prevent vehicle snagging, a smooth transition from the safety shape face To the single slope face is made over a 20' length. The actual shape of the transition is dependent on both the adjacent NJ barrier and the single slope barrier Types, as detailed on the plans. The contractor and Engineer will agree on a construction method to ensure a smooth barrier face.

MATERIALS: Materials are same for those shown on RM-4.3 and RM-4.5, except that cast-in-place is the only acceptable method. Edges may be chamfered or radiused as shown on those drawings.

CONCRETE BASE: Construct base as shown on the NJ shape insert sheets, including the methods detailing the footing joint, Permissible Construction Joint (PCJ), and Doweling requirements. The width of the base matches the existing NJ barrier.

JOINTS: Construct joints as shown on respective barrier drawings.

RACEWAYS: When specified, place raceway(s) to match raceway elevation in adjoining segments. Place to obtain maximum concrete cover.

METRIC UNITS: Refer to respective barrier drawings or inserts for metric dimensions.

PAYMENT: This Barrier Transiton shall include all material and labor needed to construct this 20' section, including any raceways, reinforcing steel, dowels and other necessary incidentals. Payment shall be made at the unit price for Item 622 - Barrier Transition, Each.

# PROPOSED TYPICAL SECTIONS
# BARRIER DETAILS

DESIGN AGENCY
Jacobs

DESIGNER: MCK
REVIEWER: BAP 03/24/26
PROJECT ID: 109164
SHEET: P.26 TOTAL: 618

FRA-71-19.10

MODEL: Proposed Typical Sections - Sheet 13 PAPERSIZE: 66x44 in LAST: 7/17/2025 7:46:13 PM EDITED: CHADS.PSC_2 plot by: PENTEL CHADS.PSC_2 on disk: USER: Chris.Lawrence1@jacobs.com WORKSPACE: D:\ROOT\OUO WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Transportation\Fraser\FRA-71-19.10\Roadway\Design\Typical Sections\Barrier Details.dgn

**ROUNDING**

THE ROUNDING AT SLOPE BREAKPOINTS SHOWN ON THE TYPICAL SECTIONS APPLIES TO ALL CROSS-SECTIONS, EVEN THOUGH OTHERWISE SHOWN.

**UTILITIES**

LISTED BELOW ARE ALL UTILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS TOGETHER WITH THEIR RESPECTIVE OWNERS:

ELECTRIC:
AEP OHIO (DISTRIBUTION)
ATTEN: ROBERT MATTHEWS
700 MORRISON RD.
GAHANNA, OHIO 43230
rematthews@aep.com
(740) 647-2080

ELECTRIC:
AEP (TRANSMISSION)
ATTEN: MICHAEL CARR
8600 SMITHS MILL ROAD
NEW ALBANY, OHIO 43054
mdcarr@aep.com
(380) 205-5072

ELECTRIC:
CITY OF COLUMBUS DEPARTMENT OF UTILITIES
DIVISION OF POWER
3500 INDIANOLA AVE.
COLUMBUS, OHIO 43230
(614) 645-7294

GAS:
COLUMBIA GAS OF OHIO
ATTEN: ROB CALDWELL
3550 JOHNNY APPLESEED CT.
COLUMBUS, OHIO 43231
rcaldwell@nisource.com
(614) 818-2104

OIL:
MARATHON PIPELINE LLC
ATTEN: LANDON MORRIS
1900 WEST AVENUE H
GRIFFITH, IN 46319
lrmorris@marathonpetroleum.com
(419) 957-7792

WATER:
CITY OF COLUMBUS DEPARTMENT OF UTILITIES
DIVISION OF WATER
910 DUBLIN RD.
COLUMBUS, OHIO 43215
(614) 645-7788

SANITARY SEWER:
CITY OF COLUMBUS DEPARTMENT OF UTILITIES
DIVISION OF SEWERAGE & DRAINAGE
1250 FAIRWOOD AVE.
COLUMBUS, OHIO 43206
(614) 645-7102

TELECOMMUNICATIONS:
TELEPHONE/FIBER OPTIC:
AT&T (SBC)
ATTEN: ERIC EMORY SR.
111 N. 4TH ST. RM 802
COLUMBUS, OHIO 43215
G01553@att.com
(614) 397-8096

TELEPHONE/FIBER OPTIC:
AT&T TRANSMISSION
ATTEN: WILLIAM TAGGART
8372 E. BROAD ST.
REYNOLDSBURG, OHIO 43068
WT2462@att.com
(614) 370-5414

**UTILITIES (CON'T)**

TELEPHONE/FIBER OPTIC:
AT&T (TRANSMISSION) - MCG UTILITIES
ATTEN: JAMES SCHNEIDER
450 W. WILSON BRIDGE RD., SUITE 180
WORTHINGTON, OHIO 43085
james.schneider@mcgfiber.com
(440) 525-4322

TELEPHONE/CABLE:
BREEZELINE (FORMERLY WOW)
ATTEN: JEREMY BORRESON
3675 CORPORATE DRIVE
COLUMBUS, OHIO 43231
jborreson@breezeline.com

FIBER OPTIC:
COLUMBUS FIBERNET
ATTEN: MATT BLACKSTONE
1600 WALCUTT RD.
COLUMBUS, OHIO 43228
(614) 921-8524

FIBER OPTIC:
CROWN CASTLE
ATTEN: JON TARNOWSKI
2 EASTON OVAL - SUITE 425
COLUMBUS, OHIO 43219
(585) 445-5813

FIBER OPTIC:
EVERSTREAM SOLUTIONS
ATTEN: SCOTT LANCIA
240 N. 5TH ST., SUITE 168
COLUMBUS, OHIO 43215
slancia@everstream.net
(380) 204-5465

CABLE:
CHARTER COMMUNICATIONS (SPECTRUM/TIME WARNER)
ATTEN: JOSEPH VLOCK
3760 INTERCHANGE RD.
COLUMBUS, OHIO 43204
joseph.vlock@charter.com
(614) 402-1979

TELEPHONE:
LUMEN (LEVEL 3 COMMUNICATIONS/CENTURY LINK)
250 W. OLD WILSON BRIDGE RD, SUITE 130
WORTHINGTON, OHIO 43085
(614) 324-4444

TELEPHONE:
MCI (VERIZON)
ATTEN: JOHN DEERE
757 COMMERCE CT.
LEWIS CENTER, OH 43035
(614) 809-8866

COMMUNICATIONS:
CITY OF COLUMBUS DEPARTMENT OF UTILITIES
SUPPORT SERVICES DIVISION
ATTEN: JOHN GREMBOWSKI
4211 GROVES ROAD
COLUMBUS, OHIO 43232
(614) 645-7344

TRAFFIC:
CITY OF COLUMBUS (TRAFFIC SIGNALS)
ATTEN: BRAD HEGWOOD
1820 E. 17TH AVE.
COLUMBUS, OHIO 43219
bdhegwood@columbus.gov
(614) 560-0839

ITS - OHIO DEPARTMENT OF TRANSPORTATION:
ODOT CENTRAL ITS
ATTEN: PAUL BECK
1606 W. BROAD ST.
COLUMBUS, OHIO 43223
(614) 387-0695

**UTILITIES (CON'T)**

THE LOCATION OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE AS OBTAINED FROM THE OWNERS AS REQUIRED BY SECTION 153.64 O.R.C.

**SURVEYING PARAMETERS**

PRIMARY PROJECT CONTROL MONUMENTS GOVERN ALL POSITIONING ON ODOT PROJECTS. SEE SHEET 3 OF THE PLANS FOR A TABLE CONTAINING PROJECT CONTROL INFORMATION.

USE THE FOLLOWING PROJECT CONTROL, VERTICAL POSITIONING, AND HORIZONTAL POSITIONING PARAMETERS FOR ALL SURVEYING:

PROJECT CONTROL

POSITIONING METHOD: STATIC GNSS AND DIFFERENTIAL LEVELING
MONUMENT TYPE: 12 TYPE A, 19 TYPE B

VERTICAL POSITIONING

ORTHOMETRIC HEIGHT DATUM: NAVD 88
GEOID: 18

HORIZONTAL POSITIONING

REFERENCE FRAME: NAD83 (2011 ADJ, 2010.0)
ELLIPSOID: GRS 80

OHIO COUNTY COORDINATE SYSTEM: FRANKLIN
FRANKLIN LDP PROJECTION PARAMETERS:
PROJECTION: TRANSVERSE MERCATOR
CENTRAL LATITUDE: N 38°24'00"
CENTRAL LONGITUDE: W 276°54'00"
FALSE NORTHING: 0 METERS
FALSE EASTING: 50,000 METERS
PROJECTION SCALE FACTOR: 1.000037

*THE LOW DISTORTION PROJECTION (LDP) IS A LOCAL COUNTY PROJECTION DEVELOPED BY O.D.O.T. THE DISTORTION BETWEEN GROUND AND GRID IS SO MINIMAL THAT THEREIS NO NEED FOR A SCALE FACTOR TO ADJUST BETWEEN GRID AND GROUND COORDINATES. CONTACT THE DISTRICT SURVEY DEPARTMENT FOR FURTHER INFORMATION OR QUESTIONS.

UNITS ARE IN U.S. SURVEY FEET. USE THE FOLLOWING CONVERSION FACTOR: 1 METER = 3.280833333 U.S. SURVEY FEET.

USE THE POSITIONING METHODS AND MONUMENT TYPE USED IN THE ORIGINAL SURVEY TO RESTORE ALL MONUMENTS RELATED TO PRIMARY PROJECT CONTROL THAT ARE DAMAGED OR DESTROYED BY CONSTRUCTION ACTIVITIES. RESTORE THE DAMAGED OR DESTROYED MONUMENTS IN ACCORDANCE WITH C&MS 623.

BASIS OF BEARINGS:

BEARINGS ARE BASED ON GRID NORTH OF THE O.D.O.T. LOW DISTORTION PROJECTION FRANKLIN COUNTY USE THE POSITIONING METHODS AND MONUMENT TYPE USED IN THE ORIGINAL SURVEY TO RESTORE ALL MONUMENTS RELATED TO PRIMARY PROJECT CONTROL THAT ARE DAMAGED OR DESTROYED BY CONSTRUCTION ACTIVITIES. RESTORE THE DAMAGED OR DESTROYED MONUMENTS IN ACCORDANCE WITH C&MS 623.

USE THE POSITIONING METHODS AND MONUMENT TYPE USED IN THE ORIGINAL SURVEY TO RESTORE ALL MONUMENTS RELATED TO PRIMARY PROJECT CONTROL THAT ARE DAMAGED OR DESTROYED BY CONSTRUCTION ACTIVITIES. RESTORE THE DAMAGED OR DESTROYED MONUMENTS IN ACCORDANCE WITH C&MS 623.

UNITS ARE IN U.S. SURVEY FEET.

**WORK LIMITS**

THE WORK LIMITS SHOWN ON THESE PLANS ARE FOR PHYSICAL CONSTRUCTION ONLY. PROVIDE THE INSTALLATION AND OPERATION OF ALL WORK ZONE TRAFFIC CONTROL AND WORK ZONE TRAFFIC CONTROL DEVICES REQUIRED BY THESE PLANS WHETHER INSIDE OR OUTSIDE THESE WORK LIMITS.

**ROUNDING**

THE ROUNDING AT SLOPE BREAKPOINTS SHOWN ON THE TYPICAL SECTIONS APPLIES TO ALL CROSS-SECTIONS, EVEN THOUGH OTHERWISE SHOWN.

**CLEARING AND GRUBBING**

ALTHOUGH THERE ARE NO TREES OR STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE LIMITS OF THE PROJECT, A LUMP SUM QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR ITEM 201, CLEARING AND GRUBBING. ALL PROVISIONS AS SET FORTH IN THE SPECIFICATIONS UNDER THIS ITEM ARE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 201, CLEARING AND GRUBBING.

**SEEDING AND MULCHING**

THE FOLLOWING QUANTITIES ARE PROVIDED TO PROMOTE GROWTH AND CARE OF PERMANENT SEEDED AREAS:

659, SOIL ANALYSIS TEST ____ EACH
659, TOPSOIL ____ CU. YD.
659, SEEDING AND MULCHING ____ SQ. YD.
659, REPAIR SEEDING AND MULCHING ____ SQ. YD.
659, INTER-SEEDING ____ SQ. YD.
659, COMMERCIAL FERTILIZER ____ TON
659, LIME ____ ACRES
659, WATER ____ M. GAL.
659, MOWING ____ M. SQ.FT.

SEEDING AND MULCHING SHALL BE APPLIED TO ALL AREAS OF EXPOSED SOIL BETWEEN THE RIGHT-OF-WAY LINES, AND WITHIN THE CONSTRUCTION LIMITS FOR AREAS OUTSIDE THE RIGHT-OF-WAY LINES COVERED BY WORK AGREEMENT OR SLOPE EASEMENT. QUANTITY CALCULATIONS FOR SEEDING AND MULCHING ARE BASED ON THESE LIMITS.

**PROTECTION OF RIGHT-OF-WAY LANDSCAPING**

PRIOR TO BEGINNING WORK, THE CONTRACTOR, THE PROJECT ENGINEER, AND A REPRESENTATIVE OF THE MAINTAINING AGENCY WILL REVIEW AND RECORD ALL LANDSCAPING ITEMS WITHIN THE RIGHT-OF-WAY (BOTH WITHIN AND OUTSIDE THE CONSTRUCTION LIMITS). A RECORD OF THIS REVIEW WILL BE KEPT IN THE PROJECT ENGINEER'S FILES. PRIOR TO FINAL ACCEPTANCE, A FINAL REVIEW OF LANDSCAPING ITEMS WILL BE MADE.

CONSTRICT ALL ACTIVITIES, EQUIPMENT STORAGE, AND STAGING TO WITHIN THE CONSTRUCTION LIMITS. UNLESS OTHERWISE IDENTIFIED IN THE PLANS OR PROPOSAL, THE CONSTRUCTION LIMITS ARE IDENTIFIED AS 30 FEET FROM THE EDGE OF PAVEMENT.

SUBMIT A WRITTEN REQUEST TO THE PROJECT ENGINEER TO USE ANY AREA OUTSIDE THESE LIMITS. THE DOCUMENT SUBMITTED MUST CLEARLY IDENTIFY THE AREA AND EXPLAIN THE PROPOSED USE AND RESTORATION OF THE AREA. USE OF THESE AREAS FOR DISPOSAL OF WASTE MATERIAL AND CONSTRUCTION DEBRIS, EXCAVATION OF BORROW MATERIAL AND PLACEMENT OF PORTABLE PLANTS IS PROHIBITED. THE REQUEST MUST BE APPROVED, IN WRITING, BEFORE THE CONTRACTOR HAS PERMISSION TO USE THE AREA.

ANY ITEMS DAMAGED BEYOND THE CONSTRUCTION LIMITS, AS DEFINED ABOVE, WILL BE REPLACED IN KIND OR AS APPROVED BY THE PROJECT ENGINEER AT THE CONTRACTORS EXPENSE.

# GENERAL NOTES

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER MCK 03/23/26
PROJECT ID 109164
SHEET P.27 TOTAL 618

FRA-71-19.10

MODEL: General Notes - GN001 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 7:23:52 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-uls-va-pw.bentley.com:jacobs-uls-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Roadway\Sheets\109164_GN001.dgn

**BENCHING OF FOUNDATION SLOPES**

ALTHOUGH CROSS-SECTIONS INDICATE SPECIFIC DIMENSIONS FOR PROPOSED BENCHING OF THE EMBANKMENT FOUNDATIONS IN CERTAIN AREAS, NO WAIVER OF THE SPECIFICATIONS IS INTENDED. BENCH ALL OTHER SLOPED EMBANKMENT AREAS AS SET FORTH IN SECTION 203.05 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS (C&MS). NO ADDITIONAL PAYMENT WILL BE MADE FOR BENCHING REQUIRED UNDER THE PROVISIONS OF SECTION 203.05.

**CONNECTION BETWEEN EXISTING AND PROPOSED GUARDRAIL**

WHEN IT IS NECESSARY TO SPLICE PROPOSED GUARDRAIL TO EXISTING GUARDRAIL, ONLY THE EXISTING GUARDRAIL SHALL BE CUT, DRILLED, OR PUNCHED. THE CONNECTION SHALL BE MADE USING A W-BEAM, BEAM SPLICE AS SHOWN IN AASHTO M 180, EXCEPT THE BEAM WASHERS ARE NOT TO BE USED. PAYMENT SHALL BE INCLUDED IN THE CONTRACT PRICE FOR THE RESPECTIVE GUARDRAIL ITEMS.

**ITEM 606 - ANCHOR ASSEMBLY, MGS TYPE E**

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING ANY OF THE MASH 2016 TYPE E TANGENTIAL END TREATMENTS FOR TYPE MGS GUARDRAIL AS LISTED UNDER "PRODUCTS ACCEPTED FOR NEW INSTALLATIONS" ON THE ROADWAY APPROVED PRODUCTS LIST POSTED ON ROADWAY ENGINEERING'S WEB PAGE. INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS. REFER TO THE POSTED SHOP DRAWINGS FOR THE MOST CURRENT APPROVED PRODUCT MODELS.

REFER TO THE MANUFACTURER'S INSTRUCTIONS REGARDING THE INSTALLATION OF, AND THE GRADING AROUND THE FOUNDATION TUBES AND GROUND STRUT. THE TOP OF ANY FOUNDATION TUBE SHOULD BE LESS THAN 4 INCHES ABOVE THE GROUND. ON-SITE GRADING IS REQUIRED IF THE TOP OF THE FOUNDATION TUBES OR TOP OF THE GROUND STRUT DOES PROJECT MORE THAN 4 INCHES ABOVE THE GROUND LINE. THE PLACEMENT OF THE FOUNDATION TUBES SHOULD BE AN APPROPRIATE DEPTH BELOW THE LEVEL LINE IN ORDER TO MAINTAIN THE FINISHED GUARDRAIL HEIGHT OF 31 INCHES FROM THE EDGE OF THE SHOULDER.

THE FACE OF THE TYPE E IMPACT HEAD SHALL BE COVERED WITH SOLID FLUORESCENT YELLOW REBOUNDABLE RETROREFLECTIVE SHEETING, PER CMS 730.191.

WHEN THE FACE OF THE ADJACENT (ATTACHED) GUARDRAIL IS LESS THAN 4' OFFSET FROM THE PROPOSED EDGE LINE, AND PERMITTING SITE CONDITIONS EXIST: THE PROPOSED TYPE E ANCHOR ASSEMBLY SHALL BE INSTALLED AT A CONSISTENT FLARE RATE THROUGH THE FULL LENGTH OF THE SYSTEM. THE FLARE RATE SHALL BE A MAXIMUM OF 25:1 (RESULTING IN A 2' OFFSET). THE INSTALLATION SHALL BE IN ACCORDANCE WITH THE SHOP DRAWINGS, PRODUCT INSTALLATION MANUAL/GUIDANCE, AND AS DIRECTED BY THE ENGINEER.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID FOR ITEM 606, ANCHOR ASSEMBLY, MGS TYPE E, EACH, AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT A COMPLETE AND FUNCTIONAL ANCHOR ASSEMBLY SYSTEM, INCLUDING ALL RELATED TRANSITIONS, REFLECTIVE SHEETING, HARDWARE, GRADING, EMBANKMENT AND EXCAVATION NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER.

**MEDIAN AND/OR CURBING ON APPROACH SLABS**

WITHIN THE LIMITS OF THE APPROACH SLAB, TRANSITION THE SHAPE OF THE MEDIAN AND/OR CURBING ON APPROACH SLABS FROM THE STANDARD SECTION ON THE APPROACHES TO THE SECTION USED ON THE BRIDGE.

**POST CONSTRUCTION STORM WATER TREATMENT**

THIS PLAN UTILIZES STRUCTURAL BEST MANAGEMENT PRACTICES (BMP'S) FOR POST CONSTRUCTION STORM WATER TREATMENT.

**VEGETATED FILTER STRIP**

THIS PLAN UTILIZES VEGETATED FILTER STRIP(S) FOR POST CONSTRUCTION STORM WATER TREATMENT. PLACE EITHER ITEM 660 SODDING OR ITEM 659 SEEDING AND MULCHING WITH A 4-INCH LIFT OF TOPSOIL AND ITEM 670, SLOPE EROSION PROTECTION TO ALL DISTURBED AREAS DESIGNATED AS VEGETATED FILTER STRIPS, THE EDGE OF SHOULDER, AND THE FORESLOPE AS SPECIFIED IN THE PLANS.

**REVIEW OF DRAINAGE FACILITIES**

PRIOR TO THE START OF WORK AND AGAIN BEFORE FINAL ACCEPTANCE, PERFORM AN INSPECTION WITH REPRESENTATIVES OF THE DEPARTMENT, CONTRACTOR AND LOCALS OF ALL EXISTING DRAINAGE FACILITIES THAT ARE TO REMAIN IN SERVICE WHICH MAY BE AFFECTED BY THE WORK. THE CONDITION OF THE EXISTING CONDUITS AND THEIR APPURTENANCES IS DETERMINED FROM FIELD OBSERVATIONS. RECORDS OF THE INSPECTION ARE MAINTAINED BY THE DEPARTMENT.

CONFIRM ALL EXISTING SEWERS INSPECTED INITIALLY BY THE ABOVE-MENTIONED PARTIES ARE MAINTAINED AND LEFT IN A CONDITION COMPARABLE TO THAT DETERMINED BY THE ORIGINAL INSPECTION. THE CONTRACTOR IS RESPONSIBLE TO CORRECT ANY CHANGE IN THE CONDITION RESULTING FROM THEIR OPERATIONS AS DIRECTED AND APPROVED BY THE ENGINEER.

PAYMENT FOR ALL OPERATIONS DESCRIBED ABOVE IS INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT 611 CONDUIT ITEMS.

**EXISTING SUBSURFACE DRAINAGE**

PROVIDE UNOBSTRUCTED OUTLETS FOR ALL EXISTING UNDERDRAINS OR AGGREGATE DRAINS ENCOUNTERED DURING CONSTRUCTION.

PROVIDE AN OUTLET PER STANDARD CONSTRUCTION DRAWING DM-1.1 FOR ALL UNDERDRAINS THAT OUTLET TO A SLOPE. UNDERDRAINS THAT CAN BE CONNECTED TO THE NEW OR EXISTING UNDERDRAINS AT THE END OF THE PROJECT LIMITS AS WELL AS ALL NECESSARY BENDS OR BRANCHES REQUIRED FOR CONNECTION ARE INCLUDED IN THE BASIS OF PAYMENT FOR UNCLASSIFIED PIPE UNDERDRAINS.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR THE WORK NOTED ABOVE:

ITEM 601, TIED CONCRETE BLOCK MAT, TYPE 1 ____ SY
ITEM 605, AGGREGATE DRAINS ____ FT
ITEM 611, ____" CONDUIT, TYPE F ____ FT
ITEM 611, PRECAST REINFORCED CONCRETE OUTLET ____ EACH
ITEM 605, ____" UNCLASSIFIED PIPE UNDERDRAINS ____ FT

**PAVEMENT RESTORATION FOR PIPE INSTALLATIONS AND/OR REMOVALS**

THE FOLLOWING QUANTITY HAS BEEN PROVIDED FOR PAVEMENT

RESTORATION FOLLOWING INSTALLATION AND/OR REMOVAL OF PIPES.
ITEM 301 - ASPHALT CONCRETE BASE, PG64-22 ____ CU. YDS.

THE ABOVE QUANTITY IS BASED ON A 301 THICKNESS OF ___ INCHES AND A PAVEMENT RESTORATION WIDTH THAT INCLUDES THE TRENCH WIDTH PLUS TWO FEET ON EACH SIDE OF THE TRENCH.

PROVIDE ANY MATERIALS USED OUTSIDE THE LIMITS STATED ABOVE AT NO ADDITIONAL COST.

**PAVEMENT RESTORATION FOR DRAINAGE STRUCTURE INSTALLATIONS**

THE FOLLOWING QUANTITY IS PROVIDED FOR PAVEMENT RESTORATION FOLLOWING INSTALLATION OF ITEM 611, DRAINAGE STRUCTURES.

ITEM 301, ASPHALT CONCRETE BASE, PG64-22 _____ CU. YDS.

THE ABOVE QUANTITY IS BASED ON A 301 THICKNESS OF ____ INCHES AND A WIDTH OF TWO FEET AROUND THE PERIMETER OF THE DRAINAGE STRUCTURE.

PROVIDE ANY MATERIALS USED OUTSIDE THE LIMITS STATED ABOVE AT NO ADDITIONAL COST.

**CROSSINGS AND CONNECTIONS TO EXISTING PIPES AND UTILITIES**

WHERE PLANS PROVIDE FOR A PROPOSED CONDUIT TO BE CONNECTED TO, OR CROSS OVER OR UNDER AN EXISTING SEWER OR UNDERGROUND UTILITY, LOCATE THE EXISTING PIPES OR UTILITIES BOTH AS TO LINE AND GRADE BEFORE STARTING TO LAY THE PROPOSED CONDUIT.

IF IT IS DETERMINED THAT THE ELEVATION OF THE EXISTING CONDUIT, OR EXISTING APPURTENANCE TO BE CONNECTED, DIFFERS FROM THE PLAN ELEVATION OR RESULTS IN A CHANGE IN THE PLAN CONDUIT SLOPE, NOTIFY THE ENGINEER BEFORE STARTING CONSTRUCTION OF ANY PORTION OF THE PROPOSED CONDUIT WHICH WILL BE AFFECTED BY THE VARIANCE IN THE EXISTING ELEVATIONS.

IF IT IS DETERMINED THAT THE PROPOSED CONDUIT WILL INTERSECT AN EXISTING SEWER OR UNDERGROUND UTILITY IF CONSTRUCTED AS SHOWN ON THE PLAN, NOTIFY THE ENGINEER BEFORE STARTING CONSTRUCTION OF ANY PORTION OF THE PROPOSED CONDUIT WHICH WOULD BE AFFECTED BY THE INTERFERENCE WITH AN EXISTING FACILITY.

PAYMENT FOR ALL THE OPERATIONS DESCRIBED ABOVE IS INCLUDED IN THE CONTRACT PRICE FOR THE PERTINENT 611 CONDUIT ITEM.

**ITEM SPECIAL - FILL AND PLUG EXISTING CONDUIT**

THIS ITEM CONSISTS OF THE CONSTRUCTION OF BULKHEADS IN AN EXISTING ____ INCH DIAMETER CONDUIT AND FILLING THE AREA SEALED OFF WITH ITEM 613, SAND OR OTHER MATERIAL APPROVED BY THE ENGINEER.

LOCATE THE BULKHEADS AT THE LIMITS OF THE AREA TO BE FILLED, AS INDICATED ON THE PLANS. THE BULKHEADS CONSIST OF BRICK OR CONCRETE MASONRY WITH A MINIMUM THICKNESS OF 12 INCHES.

PUMP THE FILL MATERIAL INTO PLACE OR BY OTHER MEANS APPROVED BY THE ENGINEER, SO THAT AFTER SETTLEMENT, AT LEAST 90 PERCENT OF THE CROSS-SECTIONAL AREA OF THE CONDUIT, FOR ITS ENTIRE LENGTH IS FILLED. THE LENGTH OF FILLED AND PLUGGED CONDUIT TO BE PAID FOR IS THE ACTUAL NUMBER OF FEET (MEASURED ALONG THE CENTERLINE OF EACH CONDUIT FROM OUTER FACE TO OUTER FACE OF BULKHEADS) FILLED AND PLUGGED AS DESCRIBED ABOVE.

IN LIEU OF FILLING AND PLUGGING THE EXISTING CONDUIT, THE PIPE MAY BE CRUSHED AND BACKFILLED PER 203, OR IT MAY BE REMOVED. THE LENGTH, MEASURED AS PROVIDED ABOVE, WILL BE PAID FOR AT THE CONTRACT PRICE PER FOOT FOR, ITEM SPECIAL, FILL AND PLUG EXISTING CONDUIT.

**PART-WIDTH CONSTRUCTION**

BECAUSE OF THE NECESSITY TO BUILD THIS PROJECT UNDER TRAFFIC AND TO CONSTRUCT THE FULL PAVEMENT WIDTH IN STAGES, EXERCISE CARE TO PREVENT THE CONSTRUCTION OF A BUTT JOINT IN THE BASE COURSES. LAP LONGITUDINAL JOINTS AS SHOWN ON STANDARD CONSTRUCTION DRAWING BP-3.1.

**ITEM 204 - PROOF ROLLING**

THE FOLLOWING QUANTITY IS PROVIDED IN THE GENERAL SUMMARY TO ADDRESS LOCATIONS REQUIRING PROOF ROLLING. SEE TYPICAL SECTION SHEETS FOR ADDITIONAL INFORMATION.

ITEM 204 - PROOF ROLLING __ HOUR

**ITEM 204 - SUBGRADE COMPACTION AND PROOF ROLLING**

CONSTRUCT THE SUBGRADE AS FOLLOWS AND IN THE FOLLOWING SEQUENCE:

1. SHAPE THE SUBGRADE TO WITHIN 0.2 FEET OF THE PLAN SUBGRADE ELEVATION.

2. EXCAVATE AND REPLACE UNSUITABLE SUBGRADE BEFORE PROOF ROLLING. UNSUITABLE SUBGRADE INCLUDES UNSUITABLE SOIL (A-4B, A-2-5, A-5, A-7-5, AND SOIL WITH A LIQUID LIMIT GREATER THAN 65) AND ANY COAL, SHALE, OR ROCK WHICH NEEDS TO BE REMOVED ACCORDING TO SECTION 204.05 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS (C&MS). IF THERE IS UNSUITABLE SUBGRADE IN A SHALLOW FILL LOCATION, EXCAVATE AND REPLACE THE UNSUITABLE SUBGRADE BEFORE CONSTRUCTING THE SHALLOW FILL AND SHAPING THE SUBGRADE.

3. COMPACT THE SUBGRADE ACCORDING TO C&MS 204.03.

4. THE ENGINEER WILL IDENTIFY THE ACTUAL LIMITS OF EXCAVATION FOR UNSTABLE SUBGRADE BASED ON THE PROOF ROLLING RESULTS AND VISUAL OBSERVATIONS.

   PROOF ROLL THE COMPACTED SUBGRADE ACCORDING TO C&MS 204.06.

5. EXCAVATE UNSTABLE SUBGRADE AS DIRECTED BY THE ENGINEER AND STABILIZE BY REPLACING WITH THE SPECIFIED MATERIALS ACCORDING TO C&MS 204.07. EXCAVATIONS WILL EXTEND 18 INCHES BEYOND THE EDGE OF THE SURFACE OF THE PAVEMENT, PAVED SHOULDERS, OR PAVED MEDIANS.

6. PROOF ROLL THE STABILIZED AREAS ACCORDING TO C&MS 204.06 TO VERIFY STABILITY.

7. FINE GRADE THE SUBGRADE TO THE SPECIFIED GRADE.

THE QUANTITIES FOR EXCAVATING THE UNSUITABLE SUBGRADE AND UNSTABLE SUBGRADE ARE BOTH PAID UNDER ITEM 204, EXCAVATION OF SUBGRADE.

THE FOLLOWING CONTINGENCY QUANTITIES HAVE BEEN PROVIDED FOR USE, AS DIRECTED BY THE ENGINEER, TO REMOVE AND REPLACE UNSUITABLE/UNSTABLE SUBGRADE AS DESCRIBED ABOVE:

ITEM 204, EXCAVATION OF SUBGRADE ___ CU. YD.
ITEM 204, GRANULAR MATERIAL, TYPE B ___ CU. YD.
ITEM 204, GEOGRID ___SQ. YD.

GENERAL NOTES

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER MCK 03/23/26
PROJECT ID 109164
SHEET P.28 TOTAL 618

FRA-71-19.10

MODEL: General Notes - GN002 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 7:23:58 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A201000 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Roadway\Sheets\109164_GN001.dgn

**AIRWAY/HIGHWAY CLEARANCE FOR AIRPORTS AND HELIPORTS**

THIS PROJECT HAS BEEN IDENTIFIED AS BEING WITHIN THE INFLUENCE AREA OF A PUBLIC USE AIRPORT OR HELIPORT. NO TEMPORARY STRUCTURES OR CONSTRUCTION EQUIPMENT AT MAXIMUM OPERATING HEIGHT SHALL EXCEED A HEIGHT OF 190 FT. IF ANY TEMPORARY STRUCTURES OR CONSTRUCTION EQUIPMENT WILL EXCEED THIS HEIGHT, FURTHER COORDINATION WITH THE FEDERAL AVIATION ADMINISTRATION (FAA), AND ODOT OFFICE OF AVIATION, WILL BE NECESSARY PRIOR TO ERECTING SUCH TEMPORARY STRUCTURES OR OPERATING SUCH EQUIPMENT ON THE PROJECT. THE CONTRACTOR WILL BE REQUIRED TO SUBMIT FORM 7460-1 TO THE FAA. NOTIFY THE ODOT OFFICE OF AVIATION WHEN SUBMITTING FAA FORM 7460-1.

NO TEMPORARY STRUCTURES OR CONSTRUCTION EQUIPMENT SHALL EXCEED THE PERMISSIBLE HEIGHT, UNTIL A COPY OF THE FAA APPROVAL AND THE ODOT OFFICE OF AVIATION PERMIT HAS BEEN FURNISHED TO THE PROJECT ENGINEER.

FEDERAL AVIATION ADMINISTRATION
SOUTHWEST REGIONAL OFFICE
OBSTRUCTION EVALUATION GROUP
10101 HILLWOOD PARKWAY
FORT WORTH, TX 76177
FAX: (817) 222-5920
HTTP://CEAAA.FAA.GOV

OHIO DEPARTMENT OF TRANSPORTATION
OFFICE OF AVIATION
2829 WEST DUBLIN-GRANVILLE ROAD
COLUMBUS, OHIO 43235
OHIO.AIRPORT.PROTECTION@DOT.OHIO.GOV

**ITEM SPECIAL - MISCELLANEOUS METAL**

EXISTING CASTINGS MAY PROVE TO BE UNSUITABLE FOR REUSE, AS DETERMINED BY THE ENGINEER. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE THE CASTINGS OF THE REQUIRED TYPE, SIZE AND STRENGTH (HEAVY OR LIGHT DUTY) FOR THE PARTICULAR STRUCTURE IN QUESTION. ALL MATERIAL SHALL MEET ITEM 611 OF THE SPECIFICATIONS AND SHALL HAVE THE PRIOR APPROVAL OF THE ENGINEER.

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AS DIRECTED BY THE ENGINEER.

SPECIAL, MISCELLANEOUS METAL _____ POUNDS

THE CONTRACTOR IS CAUTIONED TO USE EXTREME CARE IN THE REMOVAL, STORAGE AND REPLACEMENT OF ALL EXISTING CASTINGS. CASTINGS DAMAGED BY THE NEGLIGENCE OF THE CONTRACTOR, AS DETERMINED BY THE ENGINEER, SHALL BE REPLACED WITH THE PROPER NEW CASTINGS AT THE EXPENSE OF THE CONTRACTOR.

**ITEM 511 - CONCRETE, MISC.: 4" CONCRETE CAP**

THIS ITEM SHALL CONSIST OF THE CONSTRUCTION OF A 4" CONCRETE CAP IN ACCORDANCE WITH THE LOCATIONS SHOWN ON THE PLAN SHEETS AND TYPICAL SECTIONS. THE CAP SHALL BE CONSTRUCTED OF CONCRETE MIXED AND PLACED IN ACCORDANCE WITH ITEMS 499 AND 511 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS. CLASS C CONCRETE SHALL BE USED. TRANSVERSE IMPRESSED CONTRACTION JOINTS SHALL BE CONSTRUCTED AT 20 FOOT INTERVALS. INCLUDED IN THE COST OF THIS ITEM SHALL BE THE SUPPLY AND PLACEMENT OF ITEM 516, 3/4" MINIMUM PREFORMED EXPANSION JOINT FILLER. THE ABOVE WORK INCLUDING LABOR, MATERIALS AND CONSTRUCTION SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE BID FOR ITEM 511 - CONCRETE, MISC.: 4" CONCRETE CAP.

**ITEM 609 - MEDIAN, MISC.: 4" STAMPED AND COLORED CONCRETE**

PART 1 – GENERAL

1.1 RELATED DOCUMENTS
- A. DRAWINGS

1.2 SUMMARY
- A. THIS SECTION INCLUDES: ALL EXTERIOR SPECIALTY CONCRETE PAVING REQUIRED OR SHOWN ON THE ROADWAY PLAN, INCLUDING, BUT NOT LIMITED TO, THE FOLLOWING:
  1. COLORED AND TEXTURED CONCRETE.
- B. KEEP FIELD RECORDS OF TIME AND DATE OF PLACING, CURING, AND REMOVAL OF CONCRETE IN EACH PORTION OF THE WORK.

1.3 REFERENCES
- A. CITY OF COLUMBUS (COC): CONSTRUCTION AND MATERIAL SPECIFICATIONS, 2026 EDITION.
- B. ASTM C171-92 SHEET MATERIALS FOR CURING CONCRETE.
- C. ASTM D1751-83 (1991) PREFORMED EXPANSION JOINT FILLER FOR CONCRETE PAVING AND STRUCTURAL CONSTRUCTION (NON-EXTRUDING AND RESILIENT BITUMINOUS TYPES).

1.4 SUBMITTALS
- A. PRODUCT DATA: SUBMIT FOR COLOR ADMIXTURE. SUBMIT COLOR CHIPS NOT LESS THAN 2" × 4" FOR PRELIMINARY SELECTION FROM MANUFACTURER'S FULL RANGE.
- B. DESIGN DATA, TEST REPORTS: CONCRETE MIXES DESIGN AND TEST REPORTS AS PER CITY OF COLUMBUS STANDARDS.
- C. INSTALLER UNDER QUALITY ASSURANCE BELOW: APPROVAL OF LICENSED BOMANITE INSTALLER BY COLOR ADDITIVE MANUFACTURER OR APPROVED EQUAL.
- D. SUBMIT MANUFACTURER'S INSTALLATION, FINISHING, PROTECTION, AND MAINTENANCE INSTRUCTIONS.

1.5 QUALITY ASSURANCE
- A. BASIC SPECIFICATION: PERFORM ALL WORK OF THIS SECTION ACCORDING TO COC ITEM – RIGID PAVEMENT.
- B. COLORED CONCRETE INSTALLER: LICENSED BOMANITE CONTRACTOR OR APPROVED EQUAL WITH NO LESS THAN 5 YEARS SUCCESSFUL EXPERIENCE WITH INSTALLATION OF WORK OF THE TYPE REQUIRED BY THIS PROJECT.
- C. MOCK-UP: PROVIDE MINIMUM 24 INCH SQUARE MOCK-UP OF EACH TYPE OF COLORED AND TEXTURED CONCRETE PAVED AREA.
  1. MOCK-UP TO HAVE JOINT PATTERN SIMILAR TO THAT REQUIRED BY ACTUAL PAVING.
  2. TEXTURE AND COLOR TO BE REPRESENTATIVE OF PERMANENT PAVING.
  3. OWNER'S REPRESENTATIVE'S APPROVAL REQUIRED BEFORE PLACING PERMANENT COLORED PAVING.
  4. REPEAT PROCESS UNTIL MOCK-UP IS APPROVED BY OWNER'S REPRESENTATIVE.
- D. MANUFACTURER'S REPRESENTATIVE: MANUFACTURER'S REPRESENTATIVE TO BE PRESENT PRIOR TO AND AT BEGINNING OF INSTALLATION OF COLORED CONCRETE PAVING WORK, INCLUDING MOCK-UP, TO ASSURE PROPER, INSTRUCTION MIXES INSTALLATION, AND CURING PROCEDURES. IN ADDITION, MANUFACTURER'S REPRESENTATIVE TO BE PRESENT AT SUFFICIENT INTERVALS DURING PROGRESS OF WORK TO ASSURE PROPER USE OF THEIR MATERIALS.

PART 2 – PRODUCTS

2.1 AGGREGATE BASE
- A. COC ITEM #304.

2.2 CONCRETE
- A. CONCRETE:
  1. AGGREGATE: LIMESTONE (COLOR TO MATCH APPROVED SAMPLE).
  2. AIR CONTENT: 5% ± 1% ENTRAINED AIR.
  3. STRENGTH: 4000 PSI, MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS WITH WATER REDUCER AND AIR ENTRAINMENT.
  4. CEMENT CONTENT: 600 LBS PER CUBIC YARD MINIMUM.
- B. COLOR ADMIXTURE: INTEGRAL COLOR BY BOMANITE CORPORATION OR APPROVED EQUAL. COLOR: MORSE ROAD BLEND.
- C. BOMANITE COLOR HARDENER: DRY SHAKE MATERIAL BY BOMANITE CORPORATION OR APPROVED EQUAL. COLOR AND FINISH TO MATCH SAMPLE APPROVED BY OWNER'S REPRESENTATIVE. COLOR: SAND, CH-00214-60 AND COQUINA, CH-00068-60.
- D. BOMANITE RELEASE AGENT: DRY BLEND OF POWDER AND PIGMENTS FOR USE IN THE IMPRINTING PROCESS TO ALLOW A CLEAN RELEASE FROM THE IMPRINTING TOOLS. COLOR: SAND RELEASE AGENT CH-000214-60.
- E. BOMANITE COLORWASH SYSTEM IN SHALE GRAY, FOR ACCENTING PURPOSES.

2.3 FORMWORK
- A. SIDEWALK AND MEDIANS: APPLY TO ALL CITY OF COLUMBUS STANDARDS FOR CONCRETE WORK.

2.4 ACCESSORIES
- A. CURING MATERIALS: INTEGRAL COLORED CONCRETE AREAS:
  1. LIQUID COMPOUNDS: V-SEAL BY TARA DISTRIBUTIONS GROUP OR APPROVED EQUAL.
  2. SHEET MATERIALS: "ORANGE LABEL SISALKRAFT" BY FORTAFIBER CORPORATION OR EQUAL MATERIAL: A SHEET MATERIAL CONFORMING TO ASTM C 171 FOR SURFACES RECEIVING WATER REPELLENT COATING. WATERPROOFING, OR OTHER MORTAT-SET MATERIALS.
- B. HIGH GLOSS SEALER COMPOUND: UCLID, SUPER DIAMOND CLEAR, V-SEAL 102 DPS BY TARA DISTRIBUTIONS GROUP, OR APPROVED EQUAL.
- C. EXPANSION JOINTS:
  1. FILLER: MEET OR EXCEED REQUIREMENTS OF ASTM D 1751, WIDTH AS NOTED UNDER CONCRETE JOINT SEALANTS OR AS SHOWN ON DRAWINGS.
  2. JOINT CAP: TWO-PIECE VINYL DEVICE WITH UPPER 1/2 INCH REMOVABLE AFTER CURING PERIOD: WIDTH CORRESPONDING TO JOINT FILLER; PRODUCTS BY GREENSTRECK PLASTIC PRODUCTS. VINYLES CORPORATION, OR VALCON METAL PRODUCTS, OR APPROVED EQUAL .
  3. SEALANT:
     - a. AS SPECIFIED FOR COLORED CONCRETE AREAS.

PART 3 – EXECUTION

3.1 PLACING
- A. PLACE CONCRETE FOR FULL THICKNESS IN ONE OPERATION WITHOUT CHANGE IN PROPORTIONS; SCREED TO PROPER ELEVATIONS: FINISH AND CURE AS SPECIFIED. DUSTING OF SURFACES WITH CEMENT IS PROHIBITED.
- B. CONSTRUCT CONCRETE PAVING ON COMPACTED BASE ACCURATELY FORMED FOR REQUIRED SLAB THICKNESS AND BASE.
- C. CONSTRUCTION: UNLESS OTHERWISE SHOWN. PROVIDE THE FOLLOWING:
  1. SIDEWALKS.
  2. MEDIANS.

3.2 JOINTS
- A. LOCATION: LOCATE AS SHOWN ON DRAWINGS. IN ABSENCE OF INFORMATION ON DRAWINGS, PROVIDE JOINTS AS SPECIFIED.
- B. CONTRACTION JOINTS: SAWED OR FORMED WITHIN 24 HOURS OF CONCRETE PLACEMENT.
  1. SLABS:
     - a. SPACE 30 TIMES THE THICKNESS IN BOTH DIRECTIONS.
     - b. GRID OF CONTROL JOINTS TO BE APPROXIMATELY SQUARE WITH LONGEST SIDE TO BE NOT LONGER THAN 1-1/2 TIMES THE SHORTEST SIDE. I.E. 4 FOOT WIDE SIDEWALK - SPACE JOINTS 4 FEET TO 6 FEET MAXIMUM OR WHERE SPECIFICALLY SHOWN.
     - c. MINIMUM DEPTH OF JOINT: 1/4 SLAB THICKNESS.
- C. CONSTRUCTION JOINTS: PROVIDE FORMED EDGE COLD JOINT WHERE SHOWN OR REQUIRED WITH TOOLED EDGE. CONSTRUCTION JOINTS NOT TO OCCUR CLOSER THAN CONTRACTION JOINT SPACING. PROVIDE 1/2" X 18" DOWEL BAR AT 24" O.C.
- D. EXPANSION JOINTS: FORMED BEFORE CONCRETE PLACEMENT. PROVIDE AT BUILDING WALLS AND WHERE SPECIFICALLY SHOWN ON PLAN.
  1. JOINT: FULL DEPTH OF SLAB OR CURB: 1/2 -INCH JOINT FILLER WITH 3/8-INCH - FILLED WITH SEALANT. PROVIDE REMOVABLE JOINT CAP FOR ALL SLABS; SET TOP OF CAP TO FINISH ELEVATIONS.
- E. SEALANT: ALL EXPANSION, CONTRACTION AND CONSTRUCTION JOINTS TO BE CAULKED. COLORED SEALANTS SPECIFIED ABOVE TO BE APPLIED PRIOR TO APPLICATION OF WATER REPELLENT / CHLORIDE PROTECTOR AND SPECIAL SEALER COAT. COLOR TO BE DETERMINED BY OWNER'S REPRESENTATIVE.

3.3 FINISHING
- A. TOLERANCES:
  1. CLASS 'B', 1/4 -INCH IN 10 FEET, OR BETTER (11.92.2).
  2. PORTIONS OF SLABS TO RECEIVE ADDITIONAL PAVING MATERIALS TO BE CLASS 3/32 C 5/32, 57/64 -INCH IN 2 FEET, OR BETTER (11.9.3).
- B. PAVING: STAMPED COLORED CONCRETE
  1. SIDEWALK: BOMANITE PATTERN. ASHLAR SLATE, TOOL, A- INDIVIDUAL STONE VARY IN SIZE FROM 9" BY 9" TO 15" BY 14-1/2" OR APPROVED EQUAL.
  2. MEDIAN: BOMANITE PATTERN, RUNNING BOND BELGIAN BLOCK 14-1/2" INDIVIDUAL STONE VARY IN SIZE FROM 5 -1/2" BY 6 -1/2" TO 5 -1/2" BY 10-1/2" OR APPROVED EQUAL.

3.4 CURING AND SEALING
- A. SHEET CURING (COLORED CONCRETE FINISH): PROVIDE SHEET MATERIALS MEETING REQUIREMENTS OF ASTM C 171 FOR CURING CONCRETE ON THOSE PORTIONS OF SLABS SCHEDULED OR SHOWN TO RECEIVE WATER REPELLANT TREATMENT OF ADDITIONAL MORTAR-SET PAVING MATERIALS. DO NOT USE LIQUID CURING OR SEALING COMPOUNDS.
  1. COVER SLABS WITH IMPERVIOUS MEMBRANE SHEET APPLIED AS SOON AS THE CONCRETE HAS SET SUFFICIENTLY HARD TO PERMIT APPLICATION WITHOUT MARRING THE SURFACE. SHEET MATERIAL SHALL FORM EFFECTIVE SEAL, WHICH WILL PREVENT EVAPORATION OF MOISTURE FROM CONCRETE FOR FULL CURING PERIOD.
     - a. LAP EDGES 4 INCHES
     - b. WEIGHT WITH SAND OR OTHER SUITABLE MATERIALS TO MAINTAIN PLACEMENT.
  2. IF LIQUID CURING COMPOUND IS APPLIED, THROUGH ERROR, THE TRADE CONTRACTOR MAY BE REQUIRED TO REMOVE COMPOUNDS TO THE SATISFACTION OF THE OWNER'S REPRESENTATIVE.
     - a. COLORED CONCRETE AREAS TO BE CLEANED BY EXTRACTION SYSTEM PRIOR TO APPLICATION OF SEALERS AND AFTER PROPER CURE PERIOD.

GENERAL NOTES

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER MCK 03/23/26
PROJECT ID 109164
SHEET P.29 TOTAL 618

FRA-71-19.10

MODEL: General Notes - GN003 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 7:24:00 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A201000 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Roadway\Sheets\109164_GN001.dgn

***DIVISION OF POWER***

*THE DIVISION OF POWER (DOP) MAY HAVE UNDERGROUND OR OVERHEAD PRIMARY POWER, SECONDARY POWER, CONDUIT SYSTEMS AND STREET LIGHTING AT THIS WORK LOCATION. THE CONTRACTOR IS HEREBY REQUIRED TO CONTACT OUPS AT 811 OR 1-800-362-2764 FORTY-EIGHT HOURS PRIOR TO CONDUCTING ANY ACTIVITY WITHIN THE CONSTRUCTION AREA.*

*ANY REQUIRED RELOCATION, SUPPORT, PROTECTION, OR ANY OTHER ACTIVITY CONCERNED WITH THE CITY'S ELECTRICAL FACILITIES IN THE CONSTRUCTION AREA IS TO BE PERFORMED BY THE CONTRACTOR UNDER THE DIRECTION OF DOP PERSONNEL AND AT THE EXPENSE OF THE PROJECT. DOP SHALL MAKE ALL FINAL CONNECTIONS TO DOP'S EXISTING ELECTRICAL SYSTEM AT THE EXPENSE OF THE PROJECT. THE CONTRACTOR SHALL USE MATERIAL AND MAKE REPAIRS TO A CITY OF COLUMBUS STREET LIGHTING SYSTEM BY FOLLOWING DOP'S "MATERIAL AND INSTALLATION SPECIFICATIONS" (MIS) AND THE CITY OF COLUMBUS "CONSTRUCTION AND MATERIAL SPECIFICATIONS" (CMSC). ANY NEW OR RE-INSTALLED UNDERGROUND STREETLIGHT SYSTEM SHALL REQUIRE TESTING AS REFERRED TO IN SECTION 1001.18 OF THE CMSC MANUAL. THE CONTRACTOR SHALL CONFORM TO DOP'S EXISTING STREET LIGHTING LOCKOUT/TAGOUT (LOTO) PROCEDURE, MIS-01, COPIES OF WHICH ARE AVAILABLE FROM DOP.*

*IF ANY ELECTRIC FACILITY BELONGING TO DOP IS DAMAGED IN ANY MANNER BY THE CONTRACTOR, ITS AGENTS, SERVANTS, OR EMPLOYEES, AND REQUIRES EMERGENCY REPAIRS, THE DOP DISPATCH OFFICE SHOULD BE CONTACTED IMMEDIATELY AT (614) 645-7627. DOP SHALL MAKE ALL NECESSARY REPAIRS, AND THE EXPENSE OF SUCH REPAIRS AND OTHER RELATED COSTS SHALL BE PAID BY THE CONTRACTOR TO THE DIVISION OF POWER, CITY OF COLUMBUS, OHIO.*

***RECREATION AND PARKS***

*IF THIS PROJECT IMPACTS THE CITY OF COLUMBUS PARKS AND THEREFORE REQUIRES COORDINATION WITH DEPARTMENTS NON PARK USE POLICY (NPUP). THE NPUP REQUIRES THAT AN MOU BE IN PLACE PRIOR TO WORK WITHIN A CITY PARK AND ON SITE DURING CONSTRUCTION. PLEASE CONTACT MOHN, TINA M. TMMOHN@COLUMBUS.GOV TO COORDINATE EFFORTS.*

*ENTRY INTO A CITY PARK OR PARKLAND FOR CONSTRUCTION OR ANY OTHER NON-DESIGN USE IS PROHIBITED UNLESS A MOU/NPUP IS IN PLACE. UNLESS SPECIFIC PERMISSIONS ARE GRANTED BY CRPD ACCESS TO, FROM, ON, OVER, UNDER, THOUGH, ACROSS OR OTHER RELATED NON-PARK OR NON-TRAIL USE OF THE TRAIL CORRIDOR/PARKLAND IS NOT GRANTED OR IMPLIED.*

***PERMITS***

*WHEN EXCAVATING WITHIN COLUMBUS PUBLIC RIGHT OF WAY LIMITS, THE CONTRACTOR SHALL OBTAIN AN EXCAVATION PERMIT FROM CITY OF COLUMBUS, DEPARTMENT OF PUBLIC SERVICE- PERMIT OFFICE BETWEEN THE HOURS OF 7:30 AM AND 4:00 PM MONDAY THROUGH FRIDAY. PHONE (614) 645-7497; FAX: (614) 645-1876; EMAIL: colspermits@columbus.gov*

***FLOODPLAIN***

*FEMA FIRM MAP LIST:*
*39049C0176K*
*39049C0178K*
*39049C0186K*
*39049C0188K*
*39049C0326K*

***REFERENCE LOCATION SIGNS***

*THE LOCATION OF REFERENCE LOCATION SIGNS ON THE PLANS ARE APPROXIMATE AND A MORE PRECISE LOCATION WILL BE PROVIDED BY THE DEPARTMENT. THE CONTRACTOR SHALL NOTIFY THE ENGINEER AT LEAST 30 DAYS IN ADVANCE OF THE PLANNED DATE OF REFERENCE LOCATION SIGN INSTALLATION. THE ENGINEER WILL CONTACT THE OFFICE OF TECHNICAL SERVICES WHICH WILL LOCATE THE LONGITUDINAL POSITION OF REFERENCE LOCATION SIGNS BY MEANS OF A PAINT MARK ON THE PAVEMENT EDGE. ALTERNATE MARKS WILL NOT BE PROVIDED ON DIVIDED HIGHWAYS AND THE CONTRACTOR SHALL SET REFERENCE LOCATION SIGNS FOR THE OPPOSITE ROADWAY ACROSS FROM THE PROVIDED MARK. DELINEATORS WHOSE NORMAL POSITION FALLS WITHIN 50 FEET OF A REFERENCE LOCATION SIGN SHALL BE OMITTED.*

***INLET, NO. 3B50, AS PER PLAN***

*THIS WORK SHALL CONSIST OF CONSTRUCTING INLETS IN THE TYPE D50 CAPPED BARRIER AS SHOWN IN THE PLANS. THESE INLETS SHALL BE CONSTRUCTED PER ITEM 611 OF THE CMS, EXCEPT THAT THE INSIDE WINDOW SHALL BE PERMANENTLY SEALED USING A STEEL PLATE, CONCRETE, OR OTHER SUITABLE MEANS SATISFACTORY TO THE ENGINEER TO PREVENT INFILTRATION OF THE GRANULAR FILL MATERIAL. COST FOR THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR ITEM 611, INLET, NO. 3B50, AS PER PLAN.*

***INLET, NO. 3 FOR SINGLE SLOPE BARRIER, TYPE B1, AS PER PLAN***

*THIS WORK SHALL CONSIST OF CONSTRUCTING INLETS IN THE SINGLE SLOPE, TYPE B1 CAPPED BARRIER AS SHOWN IN THE PLANS. THESE INLETS SHALL BE CONSTRUCTED PER ITEM 611 OF THE CMS AND ODOT SCD "I-3B, 3B1", EXCEPT THAT THE INSIDE WINDOW SHALL BE PERMANENTLY SEALED USING A STEEL PLATE, CONCRETE, OR OTHER SUITABLE MEANS SATISFACTORY TO THE ENGINEER TO PREVENT INFILTRATION OF THE GRANULAR FILL MATERIAL. COST FOR THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR ITEM 611, INLET, NO. 3 FOR SINGLE SLOPE BARRIER, TYPE B1, AS PER PLAN.*

***INLET RECONSTRUCTED TO GRADE, AS PER PLAN***

*THIS WORK SHALL CONSIST OF RECONSTRUCTING EXISTING JERSEY BARRIER INLETS PER CMS 611 AND RESTORING THEM BACK TO GRADE WITH A SINGLE SLOPE, TYPE B1 INLET TOP CASTING AND BARRIER CONFIGURATION. THESE INLETS CASTING TOPS AND SINGLE SLOPE BARRIER CONFIGURATIONS SHALL BE CONSTRUCTED PER ODOT SCD "I-3B, 3B1", EXCEPT THAT THE INSIDE WINDOW SHALL BE PERMANENTLY SEALED USING A STEEL PLATE, CONCRETE, OR OTHER SUITABLE MEANS SATISFACTORY TO THE ENGINEER TO PREVENT INFILTRATION OF THE GRANULAR FILL MATERIAL. COST FOR THIS WORK SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR ITEM 611, INLET RECONSTRUCTED TO GRADE, AS PER PLAN*

GENERAL NOTES

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER MCK 03/23/26
PROJECT ID 109164
SHEET P.30 TOTAL 618

FRA-71-19.10

MODEL: General Notes - GN004 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 7:24:01 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Roadway\Sheets\109164_GN001.dgn

**ITEM 614, MAINTAINING TRAFFIC (AT ALL TIMES)**

UNLESS NOTED OTHERWISE, A MINIMUM OF 3 LANE(S) OF TRAFFIC SHALL BE MAINTAINED AT ALL TIMES IN EACH DIRECTION BY USE OF THE EXISTING PAVEMENT, THE COMPLETED PAVEMENT, AND ITEM 615 PAVEMENT FOR MAINTAINING TRAFFIC.

**LANES OPEN DURING HOLIDAYS OR SPECIAL EVENTS**

NO WORK SHALL BE PERFORMED AND ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR SPECIAL EVENTS:

NEW YEAR'S (OBSERVED)
MEMORIAL DAY
FOURTH OF JULY (OBSERVED)
THE OHIO STATE FAIR
OHIO STATE FOOTBALL HOME GAMES
LABOR DAY
ALL AMERICAN QUARTERHORSE CONGRESS
GENERAL/REGULAR ELECTION DAY (NOV)
THANKSGIVING
CHRISTMAS (OBSERVED)

THE PERIOD OF TIME THAT THE LANES ARE TO BE OPEN DEPENDS ON THE DAY OF THE WEEK ON WHICH THE HOLIDAY OR SPECIAL EVENT FALLS. THE FOLLOWING SCHEDULE SHALL BE USED TO DETERMINE THIS PERIOD:

| DAY OF HOLIDAY OR SPECIAL EVENT | TIME ALL LANES MUST BE OPEN TO TRAFFIC |
|---|---|
| SUNDAY | 12:00N FRIDAY THROUGH 6:00 AM MONDAY |
| MONDAY | 12:00N FRIDAY THROUGH 6:00 AM TUESDAY |
| TUESDAY | 12:00N MONDAY THROUGH 6:00 AM WEDNESDAY |
| TUESDAY | (GEN./REG. ELECTION) 5:00 AM TUESDAY THROUGH 12:00 AM WEDNESDAY |
| WEDNESDAY | 12:00N TUESDAY THROUGH 6:00 AM THURSDAY |
| THURSDAY | 12:00N WEDNESDAY THROUGH 6:00 AM FRIDAY |
| THURSDAY | (THANKSGIVING ONLY) 6:00 AM WEDNESDAY THROUGH 6:00 AM MONDAY |
| FRIDAY | 12:00N THURSDAY THROUGH 6:00 AM MONDAY |
| SATURDAY | 12:00N FRIDAY THROUGH 6:00 AM MONDAY |

DURING THE SAME PERIODS, MAINTAIN PEDESTRIAN ACCESS IF PEDESTRIAN ACCESS WAS PRESENT PRIOR TO CONSTRUCTION.

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS,
THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE PER THE LANE

**LANE CLOSURE/REDUCTION REQUIRED**

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF UTILIZATION OF MAINTENANCE OF TRAFFIC DEVICES SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

**NOTICE OF CLOSURE SIGN**

NOTICE OF CLOSURE SIGNS (W20-H13) SHALL BE ERECTED BY THE CONTRACTOR PRIOR TO THE SCHEDULED ROAD OR RAMP CLOSURE IN ACCORDANCE WITH THE NOTICE OF CLOSURE TIME TABLE BELOW. [AT THE APPROVAL OF THE ENGINEER, PORTABLE CHANGEABLE MESSAGE SIGNS MAY BE USED IN LIEU OF THE STANDARD FLAT SHEET SIGN FOR CLOSURE DURATIONS OF LESS THAN 1 WEEK.]

THE SIGNS SHALL BE ERECTED ON THE RIGHT-HAND SIDE OF THE ROAD/RAMP FACING TRAFFIC. THEY SHALL BE PLACED SO AS NOT TO INTERFERE WITH THE VISIBILITY OF ANY OTHER TRAFFIC CONTROL SIGNS. ON ROADWAYS, THEY SHOULD BE ERECTED AT OR NEAR THE POINT OF CLOSURE. THE SIGNS MAY BE ERECTED ANYWHERE ON RAMPS AS LONG AS THEY ARE VISIBLE TO THE MOTORISTS USING THE RAMP. ON ENTRANCE RAMPS, THE SIGN SHALL BE ERECTED WELL IN ADVANCE OF THE MERGE AREA TO AVOID DISTRACTING MOTORISTS.

NOTICE OF CLOSURE SIGN TIME TABLE

| ITEM | DURATION OF CLOSURE | SIGN DISPLAYED TO PUBLIC |
|---|---|---|
| RAMP & | >=2 WEEKS | 14 CALENDAR DAYS PRIOR TO CLOSURE |
| ROAD | > 12 HOURS & < 2 WEEKS | 7 CALENDAR DAYS PRIOR TO CLOSURE |
| CLOSURES | <= 12 HOURS | 2 BUSINESS DAYS PRIOR TO CLOSURE |

THE SIGN SHALL DISPLAY THE DATE OF THE CLOSURE IN MMM-DD FORMAT AND THE NUMBER OF DAYS OF THE CLOSURE. THE LAST LINE OF THE W20-H13 SIGN LISTS A PHONE NUMBER WHICH A MOTORIST MAY CALL FOR ADDITIONAL INFORMATION. THIS IS TO BE A SPECIFIC OFFICE WITHIN THE DISTRICT RATHER THAN THE GENERAL SWITCHBOARD NUMBER.

**ESTIMATED QUANTITIES**

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR USE AS DETERMINED BY THE ENGINEER FOR THE MAINTENANCE OF TRAFFIC.

ITEM 410, TRAFFIC COMPACTED SURFACE, TYPE A OR B _____ CU. YD.
ITEM 410, TRAFFIC COMPACTED SURFACE, TYPE C _____ CU. YD.
ITEM 614, ASPHALT CONCRETE FOR MAINTAINING TRAFFIC _____ CU. YD.
ITEM 616, WATER

**ROAD CLOSED SIGN**

THE CONTRACTOR SHALL PROVIDE, ERECT AND MAINTAIN STANDARD 48 X 30 INCH ROAD CLOSED SIGNS, SIGN SUPPORTS, BARRICADES AND LIGHTS, AS DETAILED IN SCD MT-101.60 AT THE LOCATIONS SHOWN IN THE PLANS DURING PERIODS IN WHICH THE AFFECTED ROADS ARE CLOSED TO TRAFFIC.

**SIGNS AND BARRICADES**

THE CONTRACTOR SHALL PROVIDE, ERECT AND MAINTAIN SIGNS AND SIGN SUPPORTS, AS DETAILED IN THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES, AND TYPE III BARRICADES OF THE TYPE AND LOCATION AS SHOWN IN THE PLANS.

**ITEM 614, MAINTAINING TRAFFIC** CONT'D

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH C&MS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

**DRUM REQUIREMENTS**

IN ADDITION TO THE REQUIREMENTS OF THE PLANS, SPECIFICATION AND PROPOSAL, DRUMS FURNISHED BY THE CONTRACTOR SHALL BE NEW AND UNUSED AT THE TIME OF ARRIVAL ON THE PROJECT. ANY DRUMS BROUGHT ON THE PROJECT, WHICH HAVE PREVIOUSLY BEEN USED ELSEWHERE, WILL NOT BE ACCEPTED.

PAYMENT FOR DRUMS SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR MAINTAINING TRAFFIC UNLESS SEPARATELY ITEMIZED.

**PERMITTED LANE CLOSURE SCHEDULE (PLCS)**

LANE CLOSURE(S) SHALL CONFORM TO THE PLCS. PUBLISHED PLCS INFORMATION CAN BE FOUND ON THE ODOT WEBSITE. LANE CLOSURE(S) SHALL NOT BE PERMITTED ON THE FOLLOWING HIGHWAYS WHEN AN APPLICABLE SCHEDULE IS NOT PUBLISHED: INTERSTATES (FUNCTIONAL CLASSIFICATION 1), OTHER FREEWAYS AND EXPRESSWAYS (FUNCTIONAL CLASSIFICATION 2), MULTILANE MAINLINE RAMPS, AND MULTILANE SYSTEM RAMPS.

THE MONTHLY PUBLISHED SCHEDULES REQUIRED TO BE USED, FOR EACH PLCS SEGMENT WITHIN THE PROJECT AREA, ARE THOSE THAT COMPRISE THE CONSECUTIVE 12-MONTH PERIOD BEGINNING 15 MONTHS PRIOR TO THE MONTH AND YEAR OF SALE AND ENDING 4 MONTHS PRIOR TO THE MONTH AND YEAR OF SALE. THESE SAME 12 MONTHS APPLY FOR THE LIFE OF THE PROJECT AND SHALL BE APPLIED TO EACH RESPECTIVE MONTH OF CONSTRUCTION (MONTH OF LANE CLOSURE(S) SHALL MATCH MONTH OF PLCS USED). LANE CLOSURE(S) IN PLACE FOR MULTIPLE MONTHS SHALL ALWAYS COMPLY WITH THE CURRENT RESPECTIVE PLCS MONTH.

(FOR EXAMPLE: IF THE SALE DATE FOR THE PROJECT WAS MARCH OF 2021, THE MONTHLY PUBLISHED SCHEDULES FOR EACH APPLICABLE PLCS SEGMENT WOULD BE DECEMBER 2019 TO NOVEMBER 2020. IF THIS WAS A THREE-YEAR PROJECT, YEAR THREE WOULD STILL BE USING THE DECEMBER 2019 TO NOVEMBER 2020 MONTHLY SCHEDULES. IF THE PROJECT DESIRED TO CLOSE TWO LANES IN JUNE 2021, REFERENCE WOULD BE MADE TO THE JUNE 2020 SCHEDULE(S) FOR THE RESPECTIVE PLCS SEGMENT(S). IF THE SAME TWO LANES WERE DESIRED TO BE CLOSED AGAIN IN JULY 2021, REFERENCE WOULD BE MADE TO THE JULY 2020 SCHEDULE(S) FOR THE RESPECTIVE PLCS SEGMENT(S).)

MORE RESTRICTIVE CHANGES TO THE ALLOWABLE LANE CLOSURE HOURS ARE AT THE DISCRETION OF THE ENGINEER IN ORDER TO COMPLY WITH THE TRAFFIC MANAGEMENT IN WORK ZONES POLICY (21-008(P)) AND STANDARD PROCEDURE (123-001(SP)).

**PERMITTED LANE CLOSURE SCHEDULE (PLCS)** CONT'D

LESS RESTRICTIVE CHANGES TO THE ALLOWABLE LANE CLOSURE HOURS ARE SUBJECT TO THE TRAFFIC MANAGEMENT IN WORK ZONES POLICY (21-008(P)) AND STANDARD PROCEDURE (123-001(SP)) AND SHALL NOT BE IMPLEMENTED UNTIL, AND UNLESS, APPROVED BY THE PROPER ODOT AUTHORITY. [EXISTING MOT EXCEPTIONS THAT HAVE ALREADY BEEN APPROVED IN ACCORDANCE TO THE TRAFFIC MANAGEMENT IN WORK ZONES POLICY AND STANDARD PROCEDURE ARE DETAILED IN THE APPROVED MAINTENANCE OF TRAFFIC (MOT) POLICY EXCEPTION(S) PLAN NOTE.]

EXCEPT AS DIRECTED IN THE FIRST PARAGRAPH OF THIS PLAN NOTE, ALLOWABLE LANE CLOSURE HOURS FOR FACILITIES AND/OR LANE CLOSURE SCENARIOS NOT COVERED BY THE PLCS, IF ANY, SHALL BE AS SPECIFIED ELSEWHERE IN THE PLANS.

**DUST CONTROL**

THE CONTRACTOR SHALL FURNISH AND APPLY WATER FOR DUST CONTROL AS DIRECTED BY THE ENGINEER. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED FOR DUST CONTROL PURPOSES:

ITEM 616, WATER _____ M. GAL.

**WORK ZONE MARKINGS AND SIGNS**

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AT LOCATIONS IDENTIFIED BY THE ENGINEER FOR WORK ZONE PAVEMENT MARKINGS AND SIGNS PER THE REQUIREMENTS OF C&MS 614.04 AND 614.11.

**ITEM 622, PORTABLE BARRIER, 50", AS PER PLAN**

THIS WORK SHALL CONSIST OF FURNISHING, MAINTAINING, AND SUBSEQUENTLY REMOVING A 50-INCH PORTABLE BARRIER AT THE LOCATIONS SHOWN ON THE PLANS. FOR DETAILS, SEE SCD RM-4.1.

PORTABLE STEEL BARRIER IS AN APPROVED ALTERNATIVE TO PORTABLE CONCRETE BARRIER. FOR INFORMATION ON APPROVED VENDORS, SEE THE APPROVED PRODUCTS LIST MAINTAINED BY THE OFFICE OF ROADWAY ENGINEERING.

PORTABLE BARRIER, 32 INCHES HIGH WITH AN 18-INCH MINIMUM HEIGHT GLARE SCREEN MAY BE USED AT THE OPTION OF THE CONTRACTOR. THE GLARE SCREEN SHALL BE CONSTRUCTED USING ONE OF THE SCREENS PROVIDED ON THE APPROVED LIST, AVAILABLE ON THE OFFICE OF ROADWAY ENGINEERING WEBSITE.

PADDLE OR INTERMITTENT TYPE GLARE SCREENS SHALL BE DESIGNED USING A 20 DEGREE CUT-OFF ANGLE BASED ON TANGENT ALIGNMENT. THAT SPACING SHALL BE USED THROUGHOUT THE BARRIER LENGTH WITHOUT REGARD TO BARRIER CURVATURE.

THE GLARE SCREEN SYSTEM SHALL BE SECURELY FASTENED TO THE 32-INCH PORTABLE BARRIER USING THE HARDWARE AND PROCEDURES SPECIFIED BY THE MANUFACTURER.

FOR DIRECTIONS ON HOW TO INSTALL THE GLARE SCREEN AND THE BARRIER, SEE THE MANUFACTURER'S INSTRUCTIONS.

PAYMENT SHALL INCLUDE ALL LABOR, MATERIAL, AND EQUIPMENT NECESSARY TO PERFORM THE WORK AND SHALL BE PAID FOR AT THE CONTRACT PRICE PER FOOT FOR ITEM 622, PORTABLE BARRIER, 50", AS PER PLAN.

MAINTENANCE OF TRAFFIC - GENERAL NOTES

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.31 TOTAL 618

FRA-71-19.10

MODEL: Sheet 1 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:54:13 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MN001.dgn

***ITEM 614, REPLACEMENT SIGN***

*FLAT SHEET SIGNS FURNISHED BY THE CONTRACTOR IN ACCORDANCE WITH THE REQUIREMENTS OF THE PLANS, SPECIFICATIONS AND PROPOSAL WHICH BECOME DAMAGED BY TRAFFIC FOR REASONS BEYOND THE CONTROL OF THE CONTRACTOR SHALL BE REPLACED IN KIND WHEN ORDERED BY THE ENGINEER. REPLACEMENT SIGNS SHALL BE NEW. OTHER MATERIALS MAY BE IN USED, BUT GOOD, CONDITION SUBJECT TO APPROVAL BY THE ENGINEER.*

*PAYMENT FOR THE NEW SIGNS SHALL BE MADE AT THE CONTRACT PRICE PER EACH FOR ITEM 614, REPLACEMENT SIGN, AND SHALL INCLUDE THE COST OF REMOVING AND DISPOSING OF DAMAGED SIGNS, HARDWARE AND SUPPORTS, AND PROVIDING THE NECESSARY REPLACEMENT HARDWARE, SUPPORTS, ETC.*

*AN ESTIMATED QUANTITY OF _____ EACH HAS BEEN PROVIDED IN THE GENERAL SUMMARY.*

***ITEM 614, REPLACEMENT DRUM***

*DRUMS FURNISHED BY THE CONTRACTOR IN ACCORDANCE WITH THE REQUIREMENTS OF THE PLANS, SPECIFICATIONS AND PROPOSAL WHICH BECOME DAMAGED BY TRAFFIC FOR REASONS BEYOND THE CONTROL OF THE CONTRACTOR SHALL BE REPLACED IN KIND WHEN ORDERED BY THE ENGINEER. REPLACEMENT DRUMS SHALL BE NEW.*

*PAYMENT FOR THE NEW DRUMS SHALL BE MADE AT THE CONTRACT PRICE PER EACH FOR ITEM 614, REPLACEMENT DRUM, AND SHALL INCLUDE THE COST OF REMOVING AND DISPOSING OF THE DAMAGED DRUM, AND PROVIDING AND MAINTAINING THE REPLACEMENT DRUM IN ACCORDANCE WITH THE CONTRACT REQUIREMENTS FOR THE ORIGINAL DRUM.*

*AN ESTIMATED QUANTITY OF _____ EACH HAS BEEN PROVIDED IN THE GENERAL SUMMARY.*

***WORK ZONE SPEED ZONES (WZSZS)***

*THE FOLLOWING WORK ZONE SPEED ZONE (WZSZ) SPEED LIMIT REVISION(S) HAVE BEEN APPROVED FOR USE ON THIS PROJECT WHEN WORK ZONE CONDITIONS AND FACTORS ARE MET AS DESCRIBED BELOW:*

*WZSZ REVISION NUMBER(S) COUNTY-ROUTE-SECTION(S) DIRECTION(S)*
*WZ-*
*WZ-*
*WZ-*

*POTENTIAL WZSZ LOCATIONS SHALL HAVE AN ORIGINAL (PRE-CONSTRUCTION) POSTED SPEED LIMIT OF 55 MPH OR GREATER, A QUALIFYING WORK ZONE CONDITION OF AT LEAST 0.5 MILE IN LENGTH, AN EXPECTED WORK DURATION OF AT LEAST THREE HOURS, AND A WORK ZONE CONDITION IN PLACE THAT REDUCES THE EXISTING FUNCTIONALITY OF THE TRAVEL LANES OR SHOULDERS (I.E., LANE CLOSURE, LANE SHIFT, CROSSOVER, CONTRAFLOW AND/OR SHOULDER CLOSURE). THE LENGTH OF THE WORK ZONE CONDITION IS MEASURED FROM THE BEGINNING OF THE TAPER FOR THE SUBJECT WORK ZONE CONDITION IMPACTING THE TRAVEL LANES AND/OR SHOULDER TO THE END OF THE DOWNSTREAM TAPER, WHERE DRIVERS ARE RETURNED TO TYPICAL ALIGNMENT. AN EXPECTED WORK DURATION OF AT LEAST THREE HOURS IS REQUIRED TO BALANCE THE ADDITIONAL EXPOSURE CREATED BY INSTALLING AND REMOVING WZSZ SIGNING WITH THE TIME NEEDED TO COMPLETE THE WORK.*

***WORK ZONES SPEED ZONES (WZSZS)** CONT'D*

*IF THE WORK ZONE MEETS THESE MINIMUM CRITERIA, IT SHALL BE ANALYZED FURTHER USING TABLE 1 BELOW TO DETERMINE IF AND WHEN IT QUALIFIES FOR A SPEED LIMIT REDUCTION. DEPENDING ON THE ORIGINAL POSTED SPEED LIMIT, THE TYPE OF TEMPORARY TRAFFIC CONTROL USED, AND WHETHER OR NOT WORKERS ARE PRESENT, A WARRANTED WZSZ WILL VARY IN THE APPROVED SPEED LIMIT TO BE POSTED OVER TIME.*

*C&MS ITEM 614, PARAGRAPH 614.02(B), INDICATES THAT TWO DIRECTIONS OF A DIVIDED HIGHWAY ARE CONSIDERED SEPARATE HIGHWAY SECTIONS. THEREFORE, IF THE WORK ON A MULTI-LANE DIVIDED HIGHWAY IS LIMITED TO ONLY ONE DIRECTION, A SPEED LIMIT REDUCTION IN THE DIRECTION OF THE WORK DOES NOT AUTOMATICALLY CONSTITUTE A SPEED LIMIT REDUCTION IN THE OPPOSITE DIRECTION. EACH DIRECTION SHALL BE ANALYZED INDEPENDENTLY FROM EACH OTHER.*

*ALL WZSZS FLUCTUATE BETWEEN TWO APPROVED REDUCED SPEED LIMITS OR BETWEEN AN APPROVED REDUCED SPEED LIMIT AND THE ORIGINAL POSTED SPEED LIMIT. ONLY ONE OF TWO SIGNING STRATEGIES SHALL BE USED TO IMPLEMENT A WZSZ.*

*[WZSZS USING DSL SIGN ASSEMBLIES SHALL BE IN ACCORDANCE WITH THIS NOTE, APPROVED LIST, SUPPLEMENTAL SPECIFICATIONS (SS) 808 AND 908, AND TRAFFIC SCD MT-104.10.]*

*[WZSZS USING TEMPORARY FLAT SHEET SPEED LIMIT SIGNS SHALL BE IN ACCORDANCE WITH THIS NOTE AND SCD MT-104.10. ADDITIONALLY PAYMENT MAY BE REMOVED, OR A DISINCENTIVE APPLIED, FOR WZSZS USING TEMPORARY FLAT SHEET SPEED LIMIT SIGNS THE SAME AS DESCRIBED IN THE MOST RECENT PUBLICATION OF SS 808 IN REGARDS TO WZSZS USING DSL SIGN ASSEMBLIES (SEE SS 808.06 PARAGRAPHS 4 THROUGH 7, INCLUDING TABLE 1).]*

*ONLY ONE WARRANTED SPEED LIMIT APPLIES AT ANY ONE TIME; SPEED LIMIT REDUCTIONS ARE NOT CUMULATIVE. WZSZS SHALL NOT BE USED FOR MOVING/MOBILE ACTIVITIES, AS DEFINED IN OMUTCD PART 6.*

*WHEN LOOKING UP THE WARRANTED WORK ZONE SPEED LIMITS, ALWAYS USE THE ORIGINAL, PRECONSTRUCTION, POSTED SPEED LIMIT. DO NOT USE A PRIOR OR CURRENT WORK ZONE SPEED LIMIT AS A LOOK UP VALUE IN THE TABLE. POSITIVE PROTECTION IS GENERALLY REGARDED AS PORTABLE BARRIER OR OTHER RIGID BARRIER IN USE ALONG THE WORK AREA WITHIN THE SUBJECT WARRANTED WORK ZONE CONDITION. WITHOUT POSITIVE PROTECTION IS GENERALLY REGARDED AS USING DRUMS, CONES, SHADOW VEHICLE, ETC., ALONG THE WORK AREA WITHIN THE SUBJECT WARRANTED WORK ZONE CONDITION. WORKERS ARE CONSIDERED AS BEING PRESENT WHEN ON-SITE, WORKING WITHIN THE SUBJECT WARRANTED WORK ZONE CONDITION. WHEN THE WORK ZONE CONDITION REDUCING THE EXISTING FUNCTIONALITY OF THE TRAVEL LANES OR SHOULDERS IS REMOVED, THE SPEED LIMIT DISPLAYED SHALL RETURN TO THE ORIGINAL POSTED SPEED LIMIT.*

***WORK ZONES SPEED ZONES (WZSZS)** CONT'D*

*TABLE 1: WARRANTED WORK ZONE SPEED LIMITS (MPH)*
*FOR WORK ZONES ON HIGH-SPEED (55 MPH OR GREATER) MULTI-LANE HIGHWAYS*

| ORIGINAL POSTED SPEED LIMIT | WITH POSITIVE PROTECTION WORKERS PRESENT | WITHOUT POSITIVE PROTECTION WORKERS NOT PRESENT | WORKERS PRESENT | WORKERS NOT PRESENT |
|---|---|---|---|---|
| 70 | 60 | 65 | 55 | 65 |
| 65 | 55 | 60 | 50 | 60 |
| 60 | 55 | 60 | 50 | 60 |
| 55 | 50 | 55 | 45 | 55 |

*THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY.*

*[ITEM 614, WORK ZONE SPEED LIMIT SIGN*
*_____ EACH]*
*[ITEM 808, DIGITAL SPEED LIMIT (DSL) SIGN ASSEMBLY*
*_____ SIGN MNTH]*
*[ASSUMING _____ DSL SIGN ASSEMBLY(IES) FOR*
*_____ MONTH(S)]*

***WORK ZONE INCREASED PENALTIES SIGN (R11-H5A)***

*R11-H5A-48 SIGNS SHALL BE FURNISHED, ERECTED, AND MAINTAINED IN GOOD CONDITION AND/OR REPLACED AS NECESSARY AND SUBSEQUENTLY REMOVED BY THE CONTRACTOR. SIGNS SHALL BE MOUNTED AT THE APPROPRIATE OFFSETS AND ELEVATIONS AS PRESCRIBED BY THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. THEY SHALL BE MAINTAINED ON SUPPORTS MEETING CURRENT SAFETY CRITERIA.*

*THE SIGNS MAY BE ERECTED OR UNCOVERED NO MORE THAN FOUR HOURS BEFORE THE ACTUAL START OF WORK. THE SIGNS SHALL BE REMOVED OR COVERED NO LATER THAN FOUR HOURS FOLLOWING RESTORATION OF ALL LANES TO TRAFFIC WITH NO RESTRICTIONS, OR SOONER AS DIRECTED BY THE ENGINEER. TEMPORARY SIGN COVERING AND UNCOVERING DUE TO TEMPORARY LANE RESTORATIONS SHALL BE GUIDED BY THE FOUR-HOUR LIMITATIONS STATED ABOVE. SUCH LANE RESTORATIONS SHOULD BE EXPECTED TO REMAIN IN EFFECT FOR 30 OR MORE CONSECUTIVE CALENDAR DAYS, SUCH AS DURING WINTER SHUT-DOWNS.*

*(THE SIGNS ON THE MAINLINE SHALL BE DUAL MOUNTED UNLESS NOT PHYSICALLY POSSIBLE. THE FIRST SIGN SHALL BE PLACED BETWEEN THE ROAD WORK AHEAD (W20-1) SIGN AND THE NEXT SIGN IN THE SEQUENCE. SIGNS SHALL BE ERECTED ON EACH ENTRANCE RAMP AND EVERY 2 MILES THROUGH THE CONSTRUCTION WORK LIMITS. SIGNS ON THE MAINLINE SHALL BE R11-H5A-48. SIGNS USED ON THE RAMPS SHALL BE R11-H5A-24. R11-H5A-24 SIGNS MAY BE USED IN THE MEDIAN IN LIEU OF R11-H5A-48 SIGNS IF IT IS NOT PHYSICALLY POSSIBLE TO PROVIDE R11-H5A-48 SIGNS IN THE MEDIAN.)*

*THE R11-H5A-48 SIGNS SHALL BE MOUNTED ON 2 NO. 3 POSTS WHEN LOCATED WITHIN CLEAR ZONES.*

*THE CONTRACTOR MAY USE SIGNS AND SUPPORTS IN USED, BUT GOOD, CONDITION PROVIDED THE SIGNS MEET CURRENT ODOT SPECIFICATIONS.*

***WORK ZONE INCREASED PENALTIES SIGN (R11-H5A)** CONT'D*

*WORK ZONE INCREASED PENALTIES SIGNS AND SUPPORTS WILL BE MEASURED AS THE NUMBER OF SIGN INSTALLATIONS, INCLUDING THE SIGN AND NECESSARY SUPPORTS. IF A SIGN AND SUPPORT COMBINATION IS REMOVED AND REERECTED AT ANOTHER LOCATION AS DIRECTED BY THE ENGINEER, IT SHALL BE CONSIDERED ANOTHER UNIT.*

*PAYMENT FOR ACCEPTED QUANTITIES, COMPLETE, IN PLACE WILL BE MADE AT THE CONTRACT UNIT PRICE. PAYMENT SHALL BE FULL COMPENSATION FOR ALL MATERIALS, LABOR, INCIDENTALS AND EQUIPMENT FOR FURNISHING, ERECTING, MAINTAINING, COVERING DURING SUSPENSION OF WORK, AND REMOVAL OF THE SIGN AND SUPPORT.*

*ITEM 614, WORK ZONE INCREASED PENALTIES SIGN____ EACH WORK ZONE INCREASED PENALTIES SIGNS WILL BE PLACED AT THE LOCATIONS SHOWN IN THE PLANS.*

***FLOODLIGHTING***

*FLOODLIGHTING OF THE WORK SITE FOR OPERATIONS CONDUCTED DURING NIGHTTIME PERIODS SHALL BE ACCOMPLISHED SO THAT THE LIGHTS DO NOT CAUSE GLARE TO THE DRIVERS ON THE ROADWAY. TO ENSURE THE ADEQUACY OF THE FLOODLIGHT PLACEMENT, THE CONTRACTOR AND THE ENGINEER SHALL DRIVE THROUGH THE WORK SITE EACH NIGHT WHEN THE LIGHTING IS IN PLACE AND OPERATIVE PRIOR TO COMMENCING ANY WORK. IF GLARE IS DETECTED, THE LIGHT PLACEMENT AND SHIELDING SHALL BE ADJUSTED TO THE SATISFACTION OF THE ENGINEER BEFORE WORK PROCEEDS.*

*PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC.*

***ITEM 614, WORK ZONE IMPACT ATTENUATOR FOR 24" WIDE HAZARDS (UNIDIRECTIONAL OR BIDIRECTIONAL)***

*THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING A NON-GATING IMPACT ATTENUATOR. FURNISH AN IMPACT ATTENUATOR FROM THE OFFICE OF ROADWAY ENGINEERING'S APPROVED LIST FOR WORK ZONE IMPACT ATTENUATORS, FROM THE ROADWAY STANDARDS APPROVED PRODUCTS WEB PAGE.*

*INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.*

*THE CONTRACTOR SHALL REPAIR OR REPLACE A DAMAGED UNIT WITHIN 24 HOURS OF A DAMAGING IMPACT.*

*WHEN BIDIRECTIONAL DESIGNS ARE SPECIFIED, THE CONTRACTOR SHALL SUPPLY APPROPRIATE TRANSITIONS.*

*WHEN GATING IMPACT ATTENUATORS ARE DESIRED, THE CONTRACTOR SHALL SUBMIT DOCUMENTATION TO THE ENGINEER FOR ACCEPTANCE.*

*THE COST FOR THE ADDITIONAL BARRIER REQUIRED FOR A GATING IMPACT ATTENUATOR SHALL BE INCLUDED IN THE COST OF THE GATING IMPACT ATTENUATOR.*

*PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT AND MAINTAIN A COMPLETE AND FUNCTIONAL IMPACT ATTENUATOR SYSTEM, INCLUDING ALL RELATED BACKUPS, TRANSITIONS, LEVELING PADS, HARDWARE AND GRADING, NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER.*

# MAINTENANCE OF TRAFFIC - GENERAL NOTES

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.32 TOTAL 618

FRA-71-19.10

MODEL: Sheet 2 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:54:19 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-EngineeringMOT\Sheets\109164_MN001.dgn

***APPROVED MAINTENANCE OF TRAFFIC (MOT) POLICY EXCEPTION(S)***

*PORTIONS OF THE MOT PLANS AS DESCRIBED BELOW HAVE APPROVED MOT EXCEPTION(S) PER TRAFFIC MANAGEMENT IN WORK ZONES POLICY (21-008(P)) AND STANDARD PROCEDURE (123-001(SP)).*

*APPROVED MOT EXCEPTION(S) INCLUDE:*
*PHASE 3A - MAINTAIN THREE (3) SOUTHBOUND LANES AT SR 161 EXTENDING TO THE SOUTH.*

*A MAINTENANCE OF TRAFFIC MEETING SHALL BE HELD A MINIMUM OF [_30_] CALENDAR DAYS PRIOR TO IMPLEMENTATION OF EACH APPROVED MOT EXCEPTION. THIS MEETING SHALL INCLUDE THE DISTRICT WORK ZONE TRAFFIC MANAGER AS WELL AS THE CONTRACTOR, WORKSITE TRAFFIC SUPERVISOR (WTS) AND ANY SUBCONTRACTORS INVOLVED WITH TEMPORARY TRAFFIC CONTROL.*

*IN ADDITION TO ANY NOTIFICATIONS REQUIRED IN OTHER NOTES, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER AT LEAST 3 BUSINESS DAYS IN ADVANCE OF IMPLEMENTATION OF THE APPROVED MOT EXCEPTION(S) REFERENCED ABOVE SO THAT THE PROJECT ENGINEER CAN SEND EMAIL NOTIFICATION TO THE OFFICE OF ROADWAY ENGINEERING, STATEWIDE TMC, DWZTM AND SPECIAL HAULING PERMITS AT LEAST 2 BUSINESS DAYS IN ADVANCE OF THE IMPLEMENTATION OF THE APPROVED MOT EXCEPTION(S) REFERENCED ABOVE. REFERENCE "EXCEPTION REQUEST APPROVAL DATED [__/__/____] FOR PID 109164" IN THE NOTIFICATION AND OTHER CORRESPONDENCE.*

*ANY CHANGES TO THE MOT THAT IMPACT THE PREVIOUSLY APPROVED MOT EXCEPTION(S) LISTED ABOVE SHALL BE APPROVED IN WRITING BY THE MOT EXCEPTION COMMITTEE (MOTEC). IN THE EVENT THAT SUCH CHANGES ARE PROPOSED, THE REQUEST SHALL BE COORDINATED THROUGH THE DISTRICT WORK ZONE TRAFFIC MANAGER (DWZTM) A MINIMUM OF 30 CALENDAR DAYS PRIOR TO THE DESIRED IMPLEMENTATION DATE. IF THE DISTRICT AGREES WITH THE PROPOSED CHANGES THE DWZTM SHALL SEEK APPROVAL FROM THE MOTEC. IN THE EVENT THE PROPOSED CHANGES ARE APPROVED IN WRITING, THE CLOSURES ARE STILL SUBJECT TO NOTIFICATION REQUIREMENTS WITHIN THIS NOTE PRIOR TO IMPLEMENTATION.*

***ITEM 614, WORK ZONE CROSSOVER LIGHTING SYSTEM***

*THIS WORK SHALL CONSIST OF FURNISHING, ERECTING, OPERATING, MAINTAINING AND REMOVING A WORK ZONE LIGHTING SYSTEM FOR A SINGLE CROSSOVER, OR OVERLAPPING A PAIR OF CROSSOVERS. THE SYSTEM SHALL BE AS SHOWN ON TRAFFIC SCD MT-100.00. THE CONTRACTOR SHALL ARRANGE FOR AND PAY FOR POWER. ALL MATERIALS AND CONSTRUCTION SHALL COMPLY WITH APPLICABLE PORTIONS OF 625 AND 725 EXCEPT: THE PERFORMANCE TEST OF 625.19F, AND CERTIFIED DRAWING REQUIREMENT OF 625.06, ARE WAIVED AND USED MATERIALS IN GOOD CONDITION ARE ACCEPTABLE.*

*POLES WHICH ARE NOT PROTECTED BY GUARDRAIL OR PORTABLE BARRIER SHALL BE LOCATED OUTSIDE THE CLEAR ZONE, AND SHOULD BE LOCATED AT LEAST 30 FEET (PREFERABLY 40 FEET) FROM THE EDGE OF PAVEMENT WHEN POSSIBLE. ADDITIONAL POLE LINES, CABLES AND APPURTENANCES NECESSARY TO FURNISH POWER TO THE LIGHTING SYSTEM SHALL BE INCLUDED IN THIS ITEM. SERVICE POLES SHALL BE POSITIONED WITH THE SAME CONSTRAINTS AS THE LIGHTING POLES AS A MINIMUM.*

*PAYMENT WILL BE MADE AT THE UNIT PRICE PER EACH FOR ITEM 614, WORK ZONE CROSSOVER LIGHTING SYSTEM THROUGHOUT ALL PHASES OF WORK WHEN THE CROSSOVER ROADWAYS ARE USED.*

***ITEM 614, PORTABLE CHANGEABLE MESSAGE SIGNS, AS PER PLAN***

*THE CONTRACTOR SHALL FURNISH, INSTALL, MAINTAIN AND REMOVE, WHEN NO LONGER NEEDED, A CHANGEABLE MESSAGE SIGN. THE SIGN SHALL BE OF A TYPE SHOWN ON A LIST OF APPROVED PCMS UNITS AVAILABLE ON THE OFFICE OF MATERIALS MANAGEMENT WEB PAGE. THE LIST CONTAINS CLASS A AND B UNITS WITH MINIMUM LEGIBILITY DISTANCES OF 800 FEET AND 650 FEET, RESPECTIVELY.*

*EACH SIGN SHALL BE TRAILER-MOUNTED AND EQUIPPED WITH A FUNCTIONAL DIMMING MECHANISM, TO DIM THE SIGN DURING DARKNESS, AND A TAMPER AND VANDAL PROOF ENCLOSURE. EACH SIGN SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE ON-SITE PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT. THE SIGN SHALL ALSO BE CAPABLE OF BEING POWERED BY AN ELECTRICAL SERVICE DROP FROM A LOCAL UTILITY COMPANY. THE PCMS SHALL BE DELINEATED IN ACCORDANCE WITH C&MS 614.03.*

*THE PROBABLE PCMS LOCATIONS AND WORK LIMITS FOR THOSE LOCATIONS ARE SHOWN IN THE MAINTENANCE OF TRAFFIC PLAN. PLACEMENT, OPERATION, MAINTENANCE AND ALL ACTIVATION OF THE SIGNS BY THE CONTRACTOR SHALL BE AS DIRECTED BY THE ENGINEER. THE PCMS SHALL BE LOCATED IN A HIGHLY VISIBLE POSITION YET PROTECTED FROM TRAFFIC. THE CONTRACTOR SHALL, AT THE DIRECTION OF THE ENGINEER, RELOCATE THE PCMS TO IMPROVE VISIBILITY OR ACCOMMODATE CHANGED CONDITIONS. WHEN NOT IN USE, THE PCMS SHALL BE TURNED OFF. ADDITIONALLY, WHEN NOT IN USE FOR EXTENDED PERIODS OF TIME, THE PCMS SHALL BE TURNED AWAY FROM ALL TRAFFIC.*

*THE ENGINEER SHALL BE PROVIDED ACCESS TO EACH SIGN UNIT AND SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE ODOT PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT, AND TO REVISE SIGN MESSAGES, IF NECESSARY.*

*(THE CONTRACTOR SHALL IMPLEMENT A SYSTEM WHEREBY CHANGEABLE MESSAGES WILL BE IMPLEMENTED WITHIN _____ HOURS FOLLOWING TELEPHONE NOTIFICATION FROM THE PROJECT ENGINEER TO A DESIGNATED PHONE.)*

*ALL MESSAGES TO BE DISPLAYED ON THE SIGN WILL BE PROVIDED BY THE ENGINEER. A LIST OF ALL REQUIRED PRE-PROGRAMMED MESSAGES WILL BE GIVEN TO THE CONTRACTOR AT THE PROJECT PRECONSTRUCTION CONFERENCE. THE SIGN SHALL HAVE THE CAPABILITY TO STORE UP TO 99 MESSAGES. MESSAGE MEMORY OR PRE-PROGRAMMED DISPLAYS SHALL NOT BE LOST AS A RESULT OF POWER FAILURES TO THE ON-BOARD COMPUTER. THE SIGN LEGEND SHALL BE CAPABLE OF BEING CHANGED IN THE FIELD. THREE-LINE PRESENTATION FORMATS WITH UP TO SIX MESSAGE PHASES SHALL BE SUPPORTED. PCMS FORMAT SHALL PERMIT THE COMPLETE MESSAGE FOR EACH PHASE TO BE READ AT LEAST TWICE.*

*THE PCMS SHALL CONTAIN AN ACCURATE CLOCK AND PROGRAMMING LOGIC WHICH WILL ALLOW THE SIGN TO BE ACTIVATED, DEACTIVATED OR MESSAGES CHANGED AUTOMATICALLY AT DIFFERENT TIMES OF THE DAY FOR DIFFERENT DAYS OF THE WEEK.*

*(THE PCMS SHALL CONTAIN A CELLULAR TELEPHONE DATA LINK WHICH WILL (IN ACTIVE CELLULAR PHONE AREAS) ALLOW REMOTE SIGN ACTIVATION, MESSAGE CHANGES, MESSAGE ADDITIONS AND REVISIONS TO TIME OF DAY PROGRAMS. THE SYSTEM SHALL ALSO PERMIT VERIFICATION OF CURRENT AND PROGRAMMED MESSAGES. ONE REMOTE DATA INPUT DEVICE (LAPTOP COMPUTER PLUS MODEM OR EQUIVALENT) SHALL BE FURNISHED FOR USE BY THE DISTRICT TRAFFIC ENGINEER, OR EQUIVALENT, AND SHALL BE INSURED AGAINST THEFT.) THE*

***ITEM 614, PORTABLE CHANGEABLE MESSAGE SIGNS, AS PER PLAN** CONT'D*

*PCMS UNIT SHALL BE MAINTAINED IN GOOD WORKING ORDER BY THE CONTRACTOR IN ACCORDANCE WITH THE PROVISIONS OF C&MS 614.07. THE CONTRACTOR SHALL, PRIOR TO ACTIVATING THE UNIT, MAKE ARRANGEMENTS, WITH AN AUTHORIZED SERVICE AGENT FOR THE PCMS, TO ASSURE PROMPT SERVICE IN THE EVENT OF FAILURE. ANY FAILURE SHALL NOT RESULT IN THE SIGN BEING OUT OF SERVICE FOR MORE THAN 12 HOURS, INCLUDING WEEKENDS. FAILURE TO COMPLY MAY RESULT IN AN ORDER TO STOP WORK AND OPEN ALL TRAFFIC LANES AND/OR IN THE DEPARTMENT TAKING APPROPRIATE ACTION TO SAFELY CONTROL TRAFFIC. THE ENTIRE COST TO CONTROL TRAFFIC, ACCRUED BY THE DEPARTMENT DUE TO THE CONTRACTOR'S NONCOMPLIANCE, WILL BE DEDUCTED FROM MONEYS DUE, OR TO BECOME DUE THE CONTRACTOR ON HIS CONTRACT.*

*THE CONTRACTOR SHALL BE RESPONSIBLE FOR 24-HOUR-PER-DAY OPERATION AND MAINTENANCE OF THESE SIGNS ON THE PROJECT FOR THE DURATION OF THE PHASES WHEN THE PLAN REQUIRES THEIR USE.*

*PAYMENT FOR THE ABOVE DESCRIBED ITEM SHALL BE AT THE CONTRACT UNIT PRICE. PAYMENT SHALL INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, FUELS, LUBRICATING OILS, SOFTWARE, HARDWARE AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK.*

*ITEM 614, PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN _____ SIGN MONTH ASSUMING _____ PCMS SIGN(S) FOR _____ MONTH(S)*

***WORKSITE TRAFFIC SUPERVISOR***

*SUBJECT TO APPROVAL OF THE ENGINEER, THE CONTRACTOR SHALL EMPLOY AND IDENTIFY (SOMEONE OTHER THAN THE SUPERINTENDENT) A PREQUALIFIED WORKSITE TRAFFIC SUPERVISOR (WTS) BEFORE STARTING WORK IN THE FIELD. THE WTS SHALL BE TRAINED IN ACCORDANCE WITH CMS 614.03, SHALL HAVE SUCCESSFULLY COMPLETED ODOT ADMINISTERED WTS TESTING (AND RE-TESTING WHEN APPLICABLE) AND BE LISTED ON THE ODOT PREQUALIFIED WTS ROSTER. PREQUALIFICATION EXPIRES EVERY 5 YEARS. RE-TESTING SHALL BE SUCCESSFULLY REPEATED EVERY 5 YEARS TO REMAIN PREQUALIFIED.*

*THE NAME OF THE PREQUALIFIED WTS AND RELATED 24-HOUR CONTACT INFORMATION SHALL BE PROVIDED TO THE ENGINEER AT THE PRECONSTRUCTION CONFERENCE. IF THE DESIGNATED WTS WILL NOT BE AVAILABLE FULL TIME (24/7), THE CONTRACTOR MAY DESIGNATE AN ALTERNATE (SECONDARY) WTS TO BE AVAILABLE WHEN THE PRIMARY IS OFF DUTY; HOWEVER, THE PRIMARY WTS SHALL REMAIN THE POINT OF CONTACT AT ALL TIMES. ANY ALTERNATE (SECONDARY) WTS IS SUBJECT TO THE SAME TRAINING, PREQUALIFICATION AND OTHER REQUIREMENTS OUTLINED WITHIN THIS PLAN NOTE. AT ALL TIMES THE ENGINEER, OR ENGINEER'S REPRESENTATIVES, MUST BE INFORMED OF WHO THE PRIMARY WTS (AND SECONDARY WTS, IF APPLICABLE) IS AT THE CURRENT TIME.*

*THE WTS POSITION HAS THE PRIMARY RESPONSIBILITY OF IMPLEMENTING THE TRAFFIC MANAGEMENT PLAN (TMP), MONITORING THE SAFETY AND MOBILITY OF THE ENTIRE WORK ZONE, AND CORRECTING TEMPORARY TRAFFIC CONTROL (TTC) DEFICIENCIES FOR THE ENTIRE WORK ZONE. THE WTS, AND ALTERNATE WTS WHEN ON DUTY, SHALL HAVE SUFFICIENT AUTHORITY TO EFFECTIVELY CARRY OUT THE IDENTIFIED WTS RESPONSIBILITIES AND DUTIES.*

*THE DUTIES OF THE WTS ARE AS FOLLOWS:*

*1. BE AVAILABLE ON A 24-HOUR PER DAY BASIS.*

***WORKSITE TRAFFIC SUPERVISOR** CONT'D*

*2. BE ON SITE FOR ALL EMERGENCY TTC NEEDS WITHIN ONE HOUR OF NOTIFICATION BY POLICE OR PROJECT STAFF, AND EFFECT CORRECTIVE MEASURES IMMEDIATELY ON EXISTING WORK ZONE TTC DEVICES.*

*3. ATTEND PRECONSTRUCTION MEETING AND ALL PROJECT MEETINGS WHERE TTC MANAGEMENT IS DISCUSSED.*

*4. BE AVAILABLE ON SITE FOR OTHER MEETINGS OR DISCUSSIONS WITH THE ENGINEER UPON REQUEST.*

*5. BE AWARE OF ALL EXISTING AND PROPOSED TTC OPERATIONS OF THE CONTRACTOR, SUBCONTRACTORS AND SUPPLIERS, AND ENSURE COORDINATION OCCURS BETWEEN THEM TO ELIMINATE CONFLICTING TEMPORARY AND/OR PERMANENT TRAFFIC CONTROL.*

*6. COORDINATE PROJECT ACTIVITIES WITH ALL LAW ENFORCEMENT OFFICERS (LEOS). THE WTS SHALL ALSO BE THE MAIN CONTACT PERSON WITH THE LEOS WHILE LEOS ARE ON THE PROJECT.*

*7. COORDINATE AND FACILITATE MEETINGS WITH ODOT PERSONNEL, LEOS AND OTHER APPLICABLE ENTITIES BEFORE EACH PLAN PHASE SWITCH TO DISCUSS THE WORK ZONE TTC FOR IMPLEMENTING THE PHASE SWITCH. SUBMIT A WRITTEN DETAIL OF MOT OPERATIONS AND SCHEDULE OF EVENTS TO IMPLEMENT THE SWITCH BETWEEN PHASE PLANS TO THE ENGINEER 5 CALENDAR DAYS PRIOR TO THIS MEETING.*

*8. BE PRESENT, ON SITE FOR, AND INVOLVED WITH, EACH TTC SET UP/TAKE DOWN AND EACH PHASE CHANGE IN ACCORDANCE WITH CMS 614.03.*

*9. ON A CONTINUAL BASIS ENSURE THAT THE TTC ZONE AND ALL RELATED DEVICES ARE INSTALLED, MAINTAINED AND REMOVED IN COMPLIANCE WITH THE CONTRACT DOCUMENTS.*

*10. ON A CONTINUAL BASIS FACILITATE CORRECTIVE ACTION(S) NECESSARY TO BRING DEFICIENT TTC ZONES AND ALL RELATED DEVICES INTO COMPLIANCE WITH CONTRACT DOCUMENTS IN THE TIMEFRAME DETERMINED BY THE ENGINEER.*

*11. INSPECT, EVALUATE, PROPOSE NECESSARY MODIFICATIONS TO, AND DOCUMENT THE EFFECTIVENESS OF, THE TTC DEVICES AND TRAFFIC OPERATIONS ON A DAILY BASIS (7 DAYS A WEEK). IN ADDITION, PERFORM ONE WEEKLY NIGHT INSPECTION OF THE WORK ZONE SETUP FOR DAYTIME WORK OPERATIONS; AND ONE DAYTIME INSPECTION PER WEEK FOR NIGHTTIME PROJECTS. THIS SHALL INCLUDE (BUT NOT BE LIMITED TO) DOCUMENTATION ON THE FOLLOWING PROJECT EVENTS:*

*A. INITIAL TTC SETUP (DAY AND NIGHT REVIEW).*

*B. DAILY TTC SETUP AND REMOVAL.*

*C. WHEN CONSTRUCTION STAGING CAUSES A CHANGE IN THE TTC SETUP.*

*D. CRASH OCCURRENCES WITHIN THE CONSTRUCTION AREA AND WITHIN THE INFLUENCE AREA(S) APPROACHING THE WORK ZONE.*

*E. REMOVAL OF TTC DEVICES AT THE END OF A PHASE OR PROJECT.*

*F. ALL OTHER EMERGENCY TTC NEEDS.*

*12. COMPLETE THE DEPARTMENT APPROVED (CA-D-8) WITHIN GOFORMZ AFTER EACH INSPECTION AS REQUIRED IN # 11 AND SUBMIT IT TO THE ENGINEER BY THE END OF THE WORKDAY IN WHICH THE INSPECTION OCCURRED. THE CA-D-8 INCLUDES A*

# MAINTENANCE OF TRAFFIC - GENERAL NOTES

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.33 TOTAL 618

FRA-71-19.10

MODEL: Sheet 3 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:54:21 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MN001.dgn

***WORKSITE TRAFFIC SUPERVISOR** CONT'D*

*CHECKLIST OF ALL TTC MAINTENANCE ITEMS TO BE REVIEWED. CONTACT GOFORMZ.HELP@DOT.OHIO.GOV TO OBTAIN A USER ACCOUNT. ANY DEFICIENCIES OBSERVED SHALL BE NOTED ON THE CA-D-8, ALONG WITH RECOMMENDED OR COMPLETED CORRECTIVE ACTIONS AND THE DATES BY WHICH SUCH CORRECTIONS WERE, OR WILL BE, COMPLETED. A COPY OF THE CURRENT CA-D-8 DOCUMENT CAN BE FOUND ON THE OFFICE OF CONSTRUCTION ADMINISTRATION'S INSPECTION FORMS WEBSITE.*

*13. HAVE COPIES OF THE CONTRACT DOCUMENTS AVAILABLE AT ALL TIMES ON THE PROJECT.*

*THE DEPARTMENT WILL DEDUCT:*

*A. THE PRORATED DAILY AMOUNT OF ITEM 614 MAINTAINING TRAFFIC FOR ANY DAY IN WHICH THE WTS FAILS TO PERFORM THE DUTIES SET FORTH ABOVE. THE PRORATED DAILY AMOUNT WILL BE EQUAL TO THE ORIGINAL BID AMOUNT FOR ITEM 614 MAINTAINING TRAFFIC DIVIDED BY THE DIFFERENCE BETWEEN THE ORIGINAL COMPLETION DATE AND THE FIRST DAY OF WORK, IN CALENDAR DAYS.*

*B. 1% OF THE ORIGINAL BID AMOUNT FOR ITEM 614 MAINTAINING TRAFFIC FOR ANY DAY THAT A FAILURE TO PERFORM WTS DUTIES REOCCURS OR A TTC ISSUE IS IDENTIFIED IN THE FIELD AND IS NOT CORRECTED IN THE GIVEN TIMEFRAME PER THE ENGINEER. DEDUCTION B SHALL NOT APPLY TO SITUATIONS COVERED BY DEDUCTION C.*

*C. 1% OF THE ORIGINAL BID AMOUNT FOR ITEM 614 MAINTAINING TRAFFIC FOR ANY DAY THAT A LANE OR RAMP IS BLOCKED (FULLY OR PARTIALLY) WITHOUT TTC, AS DETERMINED BY THE ENGINEER. THIS DEDUCTION SHALL BE IN ADDITION TO ANY OTHER DISINCENTIVES ESTABLISHED FOR UNAUTHORIZED LANE USE.*

*FOR DAYS IN WHICH MORE THAN ONE DEDUCTION LISTED ABOVE OCCUR, THE HIGHEST DEDUCTION AMOUNT WILL APPLY.*

*IF THREE OR MORE TOTAL DAYS RESULT IN ISSUES DESCRIBED IN DEDUCTION B OR C ABOVE, THE PRIMARY WTS (AND ANY ALTERNATE WTS, IF APPLICABLE) SHALL BE IMMEDIATELY REMOVED FROM THE WORK IN ACCORDANCE WITH C&MS 108.05. UPON REMOVAL THE ENGINEER SHALL NOTIFY ODOT CENTRAL OFFICE (WTSPREQUALIFICATION@DOT.OHIO.GOV) TO REGISTER A REMOVAL AT THE PROJECT LEVEL AGAINST THE STATEWIDE PREQUALIFICATION FOR THE PRIMARY WTS (AND ALTERNATE WTS, IF APPLICABLE). ACCUMULATION OF THREE PROJECT LEVEL REMOVALS (FROM ANY PROJECTS STATEWIDE) SHALL CAUSE STATEWIDE DISQUALIFICATION FOR ANY FORMERLY PREQUALIFIED WTS. A WTS (AND ALTERNATE WTS, IF APPLICABLE) MAY BE IMMEDIATELY AND CONCURRENTLY REMOVED FROM THE WORK AT THE PROJECT LEVEL IN ACCORDANCE WITH C&MS 108.05 AND DISQUALIFIED STATEWIDE FROM THE ODOT PREQUALIFIED WTS ROSTER (REGARDLESS OF THE NUMBER OF PROJECT LEVEL REMOVALS), AS WELL AS BEING SUBJECT TO OTHER POTENTIAL CONSEQUENCES, IN CASES OF FALSIFIED, DISHONEST OR OTHERWISE UNETHICAL ACTIVITY OR DOCUMENTATION.*

*PAYMENT FOR THE ABOVE REQUIREMENTS, RESPONSIBILITIES AND DUTIES SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614, MAINTAINING TRAFFIC.*

***TRAFFIC INCIDENT MANAGEMENT (TIM) DURING MOT***

*OHIO TIM IS OHIO'S TRAFFIC INCIDENT MANAGEMENT PROGRAM WHICH IS COMMITTED TO MAINTAINING THE SAFE AND EFFECTIVE FLOW OF TRAFFIC DURING EMERGENCIES AS TO PREVENT FURTHER DAMAGE, INJURY OR UNDUE DELAY OF THE MOTORING PUBLIC. IN ADDITION TO COMPLYING WITH THE PROVISION OF OMUTCD CHAPTER 6O, CONTROL OF TRAFFIC THROUGH TRAFFIC INCIDENT MANAGEMENT AREAS, THE CONTRACTOR SHALL ACTIVELY PARTICIPATE IN TIM PLANNING AND IMPLEMENTATION AS OUTLINED BELOW.*

1. *SUPERINTENDENT SHALL IDENTIFY THE INDIVIDUAL PERSONS ON THE PROJECT WHO WILL, OR MAY NEED TO, PERFORM THE DUTIES HEREIN. AT A MINIMUM, INCLUDE THE SUPERINTENDENT, FOREMEN AND SUPERVISORS (OR EQUIVALENT) AS WELL AS THE WORKSITE TRAFFIC SUPERVISOR (WTS; IF APPLICABLE TO THE PROJECT). THESE INDIVIDUALLY IDENTIFIED PERSONS SHALL COLLECTIVELY BE KNOWN AS CONTRACTOR TRAFFIC INCIDENT MANAGEMENT (TIM) CONTACTS. NOTIFY THE PROJECT ENGINEER OF THE CONTRACTOR TIM CONTACTS (ALONG WITH CONTACT INFORMATION FOR EACH) AT OR BEFORE THE PRECONSTRUCTION MEETING.*

2. *SUPERINTENDENT SHALL NOTIFY THE ENGINEER IMMEDIATELY IF ANY CONTRACTOR TIM CONTACT IS ADDED, REMOVED OR THE CONTACT INFORMATION CHANGES OVER THE COURSE OF THE PROJECT.*

3. *PRIOR THE FIRST DAY OF WORK IN THE FIELD, EACH CONTRACTOR TIM CONTACT ON THE PROJECT SHALL HAVE ATTENDED AND SUCCESSFULLY COMPLETED OHIO TIM TRAINING PROVIDED BY THE DEPARTMENT OR DESIGNEE. TRAINING INFORMATION CAN BE FOUND AT WWW.OHIOTIM.COM.*

4. *SUPERINTENDENT, AT A MINIMUM, SHALL ATTEND AND ACTIVELY PARTICIPATE IN A DEPARTMENT SCHEDULED TIM MEETING BEFORE CONSTRUCTION WORK BEGINS AND BEFORE EACH PHASE CHANGE. THESE MEETINGS WILL RESULT IN A DEPARTMENT ISSUED PROJECT SPECIFIC TRAFFIC INCIDENT MANAGEMENT PLAN (TIMP). AT THE TIM MEETINGS THE ATTENDING CONTRACTOR TIM CONTACTS SHALL:*

   *A. COLLABORATE WITH ODOT AND SAFETY FORCES;*

   *B. SHARE PROJECT SPECIFIC DETAILS THAT IMPACT TIM RESPONDERS; AND*

   *C. RECOMMEND WAYS TO INCORPORATE NECESSARY EMERGENCY ACCESS AND OTHER TIM ELEMENTS FOR TIM RESPONDERS GIVEN PROJECT SPECIFIC WORK BEING COMPLETED AND PROJECT SPECIFIC PHASING.*

5. *CONTRACTOR TIM CONTACTS SHALL IMPLEMENT COMPONENTS OF THE RESULTING TIMP (SUCH AS APPROVED EMERGENCY INGRESS/EGRESS POINTS, ETC.), AS DIRECTED BY THE ENGINEER IN ACCORDANCE WITH 109.05.*

6. *CONTRACTOR TIM CONTACTS SHALL PERFORM, AT A MINIMUM, THE FOLLOWING FUNCTIONS WHEN AN INCIDENT/CRASH OCCURS:*

   *A. IF OBSERVED OR PRESENT WHEN OCCURS, CALL 911 AND THEN NOTIFY THE TRAFFIC MANAGEMENT CENTER (TMC) TO PROVIDE THE FOLLOWING:*

***TRAFFIC INCIDENT MANAGEMENT (TIM) DURING MOT** CONT'D*

*I. LOCATION, INCLUDING MILEPOST NUMBER AND DIRECTION OF TRAVEL*

*II. NUMBER AND TYPE OF VEHICLES INVOLVED, IF KNOWN*

*III. ESTIMATED EXTENT OF DAMAGE OR INJURY, IF KNOWN*

*IV. ESTIMATED NUMBER OF PATIENTS INVOLVED, IF KNOWN*

*V. ANY POTENTIAL HAZARDOUS CONDITIONS, IF KNOWN*

*VI. THE PLACARD NUMBER ON ANY HAZARDOUS MATERIALS PLACARD FROM A SAFE DISTANCE, IF APPLICABLE AND VISIBLE*

*B. FOLLOWING AN INCIDENT/CRASH:*

*I. INITIATE TRAFFIC MANAGEMENT/PROVIDE TEMPORARY TRAFFIC CONTROL AS INDICATED IN THE TIMP, AS DIRECTED BY THE ENGINEER IN ACCORDANCE WITH 109.05.*

*II. RECOMMEND ROADWAY REPAIR NEEDS.*

*III. PROVIDE REPAIR RESOURCES AND INITIATE REPAIRS, AS DIRECTED BY THE ENGINEER IN ACCORDANCE WITH 109.05.*

*IV. ATTEND AND PARTICIPATE IN AN AFTER ACTION REVIEW (AAR).*

*ALL COSTS, UNLESS OTHERWISE SPECIFIED, RESULTING FROM THE ABOVE REQUIREMENTS SHALL BE CONSIDERED TO BE INCLUDED IN THE LUMP SUM PRICE FOR ITEM 614, MAINTAINING TRAFFIC. FAILURE TO PERFORM THE REQUIREMENTS OF THIS PLAN NOTE WILL RESULT IN A DAILY FINE OF 2% OF ITEM 614, MAINTAINING TRAFFIC AND MAY RESULT IN ONE OR MORE CONTRACTOR TIM CONTACTS BEING REMOVED FROM THE LIST OF OHIO TIM TRAINED INDIVIDUALS (AT THE SOLE DISCRETION OF THE OHIO TIM EXECUTIVE COMMITTEE). IN THE EVENT AN INDIVIDUAL IS REMOVED FROM THE OHIO TIM TRAINED LIST, THE INDIVIDUAL WILL BE REMOVED FROM CONTRACTOR TIM CONTACT RESPONSIBILITIES ON ALL PROJECTS.*

*ITEM 614, WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN*

*WORK ZONE RAISED PAVEMENT MARKERS, AS PER PLAN, AND THEIR INSTALLATION SHALL CONFORM TO C&MS 614 OR C&MS 621 AS SPECIFIED HEREIN.*

*RAISED PAVEMENT MARKERS IN USE DURING THE SNOW-PLOWING SEASON SHALL CONFORM TO 621.*

*RAISED PAVEMENT MARKERS IN USE DURING THE NON-SNOW-PLOW SEASON SHALL CONFORM TO EITHER 614 OR TO 621.*

*THE SNOW-PLOWING SEASON SHALL RUN FROM OCTOBER 15TH THROUGH APRIL 1ST.*

*IF PROJECT DELAYS, NOT THE FAULT OF ODOT, CAUSE THE WORK TO EXTEND INTO THE SNOW-PLOWING SEASON, THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACING WORK ZONE RAISED PAVEMENT MARKERS (WZRPMS) CONFORMING TO C&MS 614, WITH RAISED PAVEMENT*

***ITEM 614, WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN** CONT'D*

*MARKERS CONFORMING TO 621, AS DETERMINED BY THE ENGINEER, AT THE CONTRACTOR'S EXPENSE.*

*THIS ITEM SHALL INCLUDE PURCHASE, INSTALLATION AND REMOVAL OF ITEM 614 WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN, INCLUDING FILLING OF ANY DEPRESSIONS CREATED IN THE PAVEMENT AS PER C&MS 621.08.*

*RESURFACING OF THE TRANSITION AREAS SHALL BE PERFORMED AT THE TIME THAT THE SURFACE COURSE IS BEING APPLIED TO THE ENTIRE PROJECT. PRIOR TO APPLICATION OF THE SURFACE COURSE ON THE PROJECT, THE EXISTING PAVEMENT WITHIN THE TRANSITION AREA SHALL BE REMOVED TO A DEPTH NECESSARY TO REACH THE LEVEL OF THE INTERMEDIATE COURSE OF THE PAVEMENT, AS DETERMINED BY THE ENGINEER.*

*THE FOLLOWING BID ITEMS SHOULD BE INCLUDED IN THE PLANS:*

*ITEM 254 PAVEMENT PLANING, ASPHALT CONCRETE _____ SQUARE YARDS*

*ITEM 614 WORK ZONE RAISED PAVEMENT MARKER, AS PER PLAN _____ EACH*

*PAYMENT FOR RESURFACING WITHIN THE TRANSITION AREA SHALL BE PAID FOR UNDER THE APPROPRIATE BID ITEMS FOR THE WORK REQUIRED, AS PROVIDED FOR IN THE PLANS.*

***ITEM 614, WORK ZONE RAISED PAVEMENT MARKERS ON PERMANENT CONCRETE SURFACES***

*RAISED PAVEMENT MARKERS IN WORK ZONES, INSTALLED ON PERMANENT CONCRETE SURFACES, SHALL BE ITEM 614 WORK ZONE RAISED PAVEMENT MARKERS. WZRPMS ARE INTENDED FOR USE ONLY DURING THE NON-SNOW-PLOWING SEASON. WZRPMS SHALL NOT BE PROVIDED DURING THE SNOW-PLOWING SEASON.*

*THE SNOW-PLOWING SEASON SHALL RUN FROM OCTOBER 15TH THROUGH APRIL 1ST.*

*WHERE A TEMPORARY ALIGNMENT WILL REMAIN IN USE THROUGH THE WINTER, THE WZRPMS SHALL BE REMOVED PRIOR TO THE BEGINNING OF THE SNOW-PLOWING SEASON AND REPLACED APPROXIMATELY APRIL 1, OR AS OTHERWISE DETERMINED BY THE ENGINEER.*

*THIS ITEM SHALL INCLUDE PURCHASE, INSTALLATION AND REMOVAL OF ITEM 614 WORK ZONE RAISED PAVEMENT MARKERS.*

*AN ESTIMATED QUANTITY OF _____ EACH OF ITEM 614 WORK ZONE RAISED PAVEMENT MARKER HAS BEEN PROVIDED AND CARRIED TO THE GENERAL SUMMARY.*

MAINTENANCE OF TRAFFIC - GENERAL NOTES

DESIGN AGENCY

Jacobs

DESIGNER SRH

REVIEWER BAP 03/20/26

PROJECT ID 109164

SHEET P.34 TOTAL 618

FRA-71-19.10

MODEL: Sheet 4 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:54:22 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MN001.dgn

***DELINEATION OF PORTABLE AND PERMANENT BARRIER***

*BARRIER REFLECTORS AND OBJECT MARKERS SHALL BE INSTALLED ON ALL PORTABLE BARRIER (PB) USED FOR TRAFFIC CONTROL; AND, ON PERMANENT CONCRETE BARRIER (INCLUDING BRIDGE PARAPETS) LOCATED WITHIN 5 FEET OF THE EDGE OF THE ADJACENT TRAVEL LANE.*

*BARRIER REFLECTORS SHALL CONFORM TO C&MS 626, EXCEPT THAT THE SPACING SHALL BE AS PER TRAFFIC SCD MT-101.70. OBJECT MARKERS AND THEIR INSTALLATION SHALL CONFORM TO C&MS 614.03 AND SCD MT-101.70. WHEN THE PB OR PERMANENT BARRIER (INCLUDING BRIDGE PARAPETS) CONTAINS GLARE SCREEN, ONE SET OF THREE VERTICAL STRIPES OF SHEETING SHALL BE CONSIDERED EQUIVALENT TO AN OBJECT MARKER, ONE-WAY.*

*[INCREASED BARRIER DELINEATION, AS SPECIFIED HEREIN, SHALL BE INSTALLED ON ALL PB AND PERMANENT CONCRETE BARRIER LOCATED WITHIN 5 FEET OF THE EDGE OF THE TRAVELED LANE UNDER EITHER OF THE FOLLOWING CONDITIONS: ALONG TAPERS AND TRANSITION AREAS; OR ALONG CURVES (OUTSIDE ONLY) WITH DEGREE OF CURVATURE GREATER THAN OR EQUAL TO 3 DEGREES.]*

*[THE INCREASED BARRIER DELINEATION SHALL CONSIST OF EITHER DELINEATION PANELS OR THE TRIPLE STACKING OF WORK ZONE BARRIER REFLECTORS.]*

*[DELINEATION PANELS SHALL CONSIST OF PANELS OF DELINEATION, APPROXIMATELY 34 INCHES LONG AND 6 INCHES WIDE AND SHALL BE "CRIMPED." PANELS SHALL BE INSTALLED AND SPACED PER TRAFFIC SCD MT-101.70.]*

*[TRIPLE-STACKED BARRIER REFLECTORS SHALL CONSIST OF ALIGNING THREE BARRIER REFLECTORS VERTICALLY, AT LOCATIONS WHERE A SINGLE BARRIER REFLECTOR WOULD BE OTHERWISE ATTACHED. THERE SHALL BE NO OPEN SPACE BETWEEN THE ADJACENT BARRIER REFLECTORS. THE TRIPLE-STACKED BARRIER REFLECTORS SHALL CONFORM TO C&MS 626, EXCEPT THAT THEY SHALL BE SPACED AND ALIGNED PER TRAFFIC SCD MT-101.70.]*

*THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE PLANS AND CARRIED TO THE GENERAL SUMMARY:*

*ITEM 614, BARRIER REFLECTOR, TYPE 1 (ONE-WAY OR BI-DIRECTIONAL) _____ EACH*

*ITEM 614, OBJECT MARKER, _____-WAY _____ EACH*

*[ITEM 614, INCREASED BARRIER DELINEATION _____FEET]*

*PAYMENT SHALL BE FULL COMPENSATION FOR ALL MATERIAL, LABOR, INCIDENTALS AND EQUIPMENT NECESSARY FOR FURNISHING, INSTALLING, MAINTAINING AND REMOVING EACH OF THE ABOVE ITEMS.*

*[ALONG RUNS OF INCREASED BARRIER DELINEATION WHERE THIS ITEM IS PROVIDED, THE QUANTITY SHALL BE MEASURED AS THE ENTIRE LENGTH OF THE RUN OF INCREASED BARRIER DELINEATION, INCLUDING THE SPACES BETWEEN THE INDIVIDUAL DELINEATION PANELS OR STACKS OF BARRIER REFLECTORS.]*

***DELINEATION OF TEMPORARY AND PERMANENT GUARDRAIL***

*BARRIER REFLECTORS SHALL BE INSTALLED ON ALL TEMPORARY GUARDRAIL USED FOR TRAFFIC CONTROL; AND, ON ALL PERMANENT GUARDRAIL LOCATED WITHIN 5 FEET OF THE EDGE OF THE ADJACENT TRAVEL LANE. BARRIER REFLECTORS SHALL CONFORM TO C&MS 626 AND THE SPACING SHALL BE APPROXIMATELY 50 FEET.*

*[OBJECT MARKERS SHALL BE INSTALLED ON ALL TEMPORARY AND PERMANENT GUARDRAIL LOCATED WITHIN 5 FEET OF THE EDGE OF THE ADJACENT TRAVEL LANE. GUARDRAIL-MOUNTING OF OBJECT MARKERS SHALL BE MADE BY INSTALLING THE OBJECT MARKERS ON THE EXTENSION BLOCKS RATHER THAN DIRECTLY ONTO THE GUARDRAIL ITSELF. OBJECT MARKERS SHALL CONFORM TO C&MS 614.03 AND THE SPACING SHALL BE APPROXIMATELY 50 FEET WITH A 25 FOOT OFFSET FROM THE BARRIER REFLECTORS.]*

*THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE PLANS AND CARRIED TO THE GENERAL SUMMARY:*

*ITEM 614, BARRIER REFLECTOR, TYPE (2, 3, 4, OR 5) (ONE-WAY OR BIDIRECTIONAL) _____ EACH*

*[ITEM 614, OBJECT MARKER, _____-WAY _____ EACH]*

*PAYMENT SHALL BE FULL COMPENSATION FOR ALL MATERIAL, LABOR, INCIDENTALS AND EQUIPMENT NECESSARY FOR FURNISHING, INSTALLING, MAINTAINING AND REMOVING THE ABOVE ITEM(S).*

***ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE DURING CONSTRUCTION OPERATIONS***

*USE OF LAW ENFORCEMENT OFFICERS (LEOS) BY CONTRACTORS OTHER THAN THE USES SPECIFIED BELOW SHALL NOT BE PERMITTED AT PROJECT COST NOR TIME COMPENSATION. LEOS SHOULD NOT BE USED WHERE THE OMUTCD INTENDS THAT FLAGGERS BE USED.*

*IN ADDITION TO THE REQUIREMENTS OF C&MS 614 AND THE OMUTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHALL BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS:*

- *DURING THE ENTIRE ADVANCE PREPARATION AND CLOSURE SEQUENCE WHERE COMPLETE BLOCKAGE OF TRAFFIC IS REQUIRED.*
- *DURING A TRAFFIC SIGNAL INSTALLATION WHEN IMPACTING THE NORMAL FUNCTION OF THE SIGNAL OR THE FLOW OF TRAFFIC, OR WHEN TRAFFIC NEEDS TO BE DIRECTED THROUGH AN ENERGIZED TRAFFIC SIGNAL CONTRARY TO THE SIGNAL DISPLAY (E.G., DIRECTING MOTORISTS THROUGH A RED LIGHT).*
- *DURING PERIODS WHERE TRAFFIC NEEDS TO BE DIRECTED CONTRARY TO A TRAFFIC CONTROL DEVICE (FLAGGER, SIGN [E.G. STOP SIGN, STREET OR HIGHWAY SIGNS, ETC.], SIGNAL OR OTHER DEVICE USED TO REGULATE, WARN OR GUIDE TRAFFIC). TRAFFIC IN THIS INSTANCE INCLUDES VEHICULAR, PEDESTRIAN AND/OR SHARED USE PATH USERS.*

*IN ADDITION TO THE REQUIREMENT OF C&MS 614 AND THE OMUTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHOULD BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS AS APPROVED BY THE ENGINEER:*

***ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE DURING CONSTRUCTION OPERATIONS** CONT'D*

- *FOR LANE CLOSURES THAT MEET ALL OF THE CRITERIA LISTED BELOW: DURING INITIAL SET-UP PERIODS, TEAR DOWN PERIODS, SUBSTANTIAL SHIFTS OF A CLOSURE POINT OR WHEN NEW LANE CLOSURE ARRANGEMENTS ARE INITIATED FOR LONG-TERM LANE CLOSURES/SHIFTS (FOR THE FIRST AND LAST DAY OF MAJOR CHANGES IN TRAFFIC CONTROL SETUP).*

  - *CRITERIA*
    - *ON A MULTI-LANE DIVIDED INTERSTATE, OTHER FREEWAY OR EXPRESSWAY; AND,*
    - *AN AUTHORIZED SPEED LIMIT OF 45 MPH OR GREATER THAT IS IN EFFECT AT THE TIME OF THE OPERATION; AND,*
    - *AADT OF 50,000 (OR AADT OF 30,000 WITH 25% OR HIGHER PERCENT TRUCKS)*

*IN GENERAL, LEOS SHOULD BE POSITIONED IN ADVANCE OF AND ON THE SAME SIDE AS THE LANE RESTRICTION (OR AT THE POINT OF ROAD CLOSURE), AND TO MANUALLY CONTROL TRAFFIC MOVEMENTS THROUGH SIGNALIZED INTERSECTIONS AND/OR IN CONTRARY TO OTHER TRAFFIC CONTROL DEVICES IN WORK ZONES.*

*LEOS SHOULD NOT FORGO THEIR TRAFFIC CONTROL RESPONSIBILITIES TO APPREHEND MOTORISTS FOR ROUTINE TRAFFIC VIOLATIONS. HOWEVER, IF A MOTORIST'S ACTIONS ARE CONSIDERED TO BE RECKLESS, THEN PURSUIT OF THE MOTORIST IS APPROPRIATE.*

*THE LEOS WORK AT THE DIRECTION OF THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR SECURING THE SERVICES OF THE LEOS WITH THE APPROPRIATE AGENCIES AND COMMUNICATING THE INTENTIONS OF THE PLANS WITH RESPECT TO DUTIES OF THE LEOS. THE ENGINEER SHALL HAVE FINAL CONTROL OVER THE LEOS' DUTIES AND PLACEMENT, AND WILL RESOLVE ANY ISSUES THAT MAY ARISE BETWEEN THE TWO PARTIES.*

*ENSURE PROVIDED LEOS HAVE BEEN TRAINED APPROPRIATE TO THE JOB DECISIONS THEY ARE REQUIRED TO MAKE WHILE ON THE PROJECT, IN ACCORDANCE WITH C&MS 614.03.THE LEO SHALL REPORT IN TO THE CONTRACTOR PRIOR TO THE START OF THE SHIFT, IN ORDER TO RECEIVE INSTRUCTIONS REGARDING SPECIFIC WORK ASSIGNMENTS DURING HIS/HER SHIFT. THE LEO IS EXPECTED TO STAY AT THE PROJECT SITE FOR THE ENTIRE DURATION OF HIS/HER SHIFT. THE LEO SHALL REPORT TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT. SHOULD IT BE NECESSARY TO LEAVE THE PROJECT SITE, THE LEO SHALL NOTIFY THE ENGINEER. THE CONTRACTOR SHALL PROVIDE THE LEO WITH A TWO-WAY COMMUNICATION DEVICE THAT SHALL BE RETURNED TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT.*

*LEOS (WITH PATROL CAR) REQUIRED BY THE TRAFFIC MAINTENANCE TASKS ABOVE SHALL BE PAID FOR ON A UNIT PRICE (HOURLY) BASIS UNDER ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY.*

***ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE DURING CONSTRUCTION OPERATIONS** CONT'D*

*ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE____ HOURS*

*THE HOURS PAID SHALL INCLUDE ANY MINIMUM SHOW-UP TIME REQUIRED BY THE LAW ENFORCEMENT AGENCY INVOLVED. ANY ADDITIONAL COSTS (ADMINISTRATIVE OR OTHERWISE) INCURRED BY THE CONTRACTOR TO OBTAIN THE SERVICES OF AN LEO ARE INCLUDED WITH THE BID UNIT PRICE FOR ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE.*

# MAINTENANCE OF TRAFFIC - GENERAL NOTES

DESIGN AGENCY

Jacobs

| | |
|---|---|
| DESIGNER | SRH |
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.35 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet 5 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:54:24 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MN001.dgn

THE MAINTENANCE OF TRAFFIC (MOT) PLAN COMBINES PART WIDTH CONSTRUCTION WITH CONTRAFLOW. EXCEPT AS NOTED, MAINTAIN A MINIMUM OF THREE (3) LANES IN EACH DIRECTION THROUGHOUT THE PROJECT.

**SEQUENCE OF WORK**

**WEEKEND CLOSURE PERIOD**
AT VARIOUS STEPS THROUGHOUT THE PROJECT, WORK MUST BE COMPLETED DURING A WEEKEND LANE CLOSURE PERIOD. EACH WEEKEND LANE CLOSURE PERIOD BEGINS ON FRIDAY AT 9 PM AND ENDS ON MONDAY AT 5 AM. SUBMIT A REQUEST FOR A WEEKEND LANE CLOSURE PERIOD 15 DAYS IN ADVANCE OF THE CLOSURE DATE. ALL WEEKEND LANE CLOSURES MUST BE APPROVED IN WRITING.

**PHASES 1A & 1B**
WITH A SERIES OF 8 WEEKEND LANE CLOSURES, COMPLETE THE BRIDGE REHABILIATION WORK AT THE I-71 MAINLINE CROSSING OVER COOKE ROAD. COMPLETE EACH STEP WITHIN ONE WEEKEND LANE CLOSURE PERIOD.

PRIOR TO THE FIRST WEEKEND CLOSURE, UTILIZE SCD MT-95.30 (PER THE PLCS) FOR SINGLE NIGHTTIME LANE CLOSURES TO COMPLETE THE PAVEMENT FOR MAINTAINING TRAFFIC.

PHASE 1A STEP 1: REPLACE THE APPROACH SLAB ALONG THE SOUTHBOUND INSIDE LANES

PHASE 1A STEP 2: REPLACE THE APPROACH SLAB ALONG THE SOUTHBOUND OUTSIDE LANES

PHASE 1A STEP 3: INSTALL THE BRIDGE DECK OVERLAY ALONG THE SOUTHBOUND INSIDE LANES

PHASE 1A STEP 4: INSTALL THE BRIDGE DECK OVERLAY ALONG THE SOUTHBOUND OUTSIDE LANES

PHASE 1B STEP 1: REPLACE THE APPROACH SLAB ALONG THE NORTHBOUND INSIDE LANES

PHASE 1B STEP 2: REPLACE THE APPROACH SLAB ALONG THE NORTHBOUND OUTSIDE LANES

PHASE 1B STEP 3: INSTALL THE BRIDGE DECK OVERLAY ALONG THE NORTHBOUND INSIDE LANES

PHASE 1B STEP 4: INSTALL THE BRIDGE DECK OVERLAY ALONG THE NORTHBOUND OUTSIDE LANES

**PHASE 2**
SHIFT EXISTING LANES OF TRAFFIC TO THE OUTSIDE SHOULDER AT EACH CROSSOVER LOCATION
INSTALL THE TEMPORARY CROSSOVERS

ADDITIONAL WORK TO BE COMPLETED PRIOR TO THE COMPLETION OF PHASE 2:
- WATERLINE RELOCATION AT SR 161
- TEMPORARY LIGHTING
- RELOCATE THE CITY OF COLUMBUS CTSS 144 STRAND FIBER OPTIC CABLE ACROSS I-71 AT SR 161

**PHASE 3A**
PHASE 3A STEP 1: DURING A WEEKEND LANE CLOSURE PERIOD, INSTALL PROPOSED DRAINAGE CONDUIT ACROSS THE I-71 SOUTHBOUND LANES AND THE I-71 SOUTHBOUND EXIT RAMP TO SINCLAIR RD.

PHASE 3A STEP 2: DURING A WEEKEND LANE CLOSURE PERIOD, INSTALL PROPOSED DRAINAGE CONDUIT ACROSS I-71 SOUTHBOUND LANES AND THE I-71 SB ENTRANCE RAMP FROM MORSE RD.

PHASE 3A STEP 3: WITH TRAFFIC IN THE PHASE 3A POSITION, AND WITH DETOUR IN PLACE, CLOSE MORSE ROAD AND SR 161 FOR BRIDGE DEMOLITION ACTIVITES. REMOVE EXISTING PIERS AND INSTALL TEMPORARY SIDEWALK WITHIN THE PHASE LIMITS PRIOR TO REOPENING. DO NOT CLOSE MORSE ROAD AND SR 161 SIMULTANEOUSLY.

COMPLETE THE I-71 SOUTHBOUND INSIDE LANES ALONG THE NEW STRUCTURES AND CONNECTING PAVEMENT AT THE MAINLINE CROSSINGS OVER MORSE ROAD AND SR 161.

**PHASE 3B**
FOR THE TRANSITION FROM PHASE 3A STEP 3 TO 3B STEP 1:

1. SCHEDULE THE TRANSITION TO OCCUR DURING A WEEKEND LANE CLOSURE PERIOD.
2. CLOSE THE PHASE 3A INSIDE SOUTHBOUND LANE AT MORSE ROAD PER SCD MT-95.30 WHILE MAINTAINING THE SOUTHBOUND CONTRAFLOW LANE AND THE PHASE 3A OUTSIDE SOUTHBOUND LANE.
3. COMPLETE THE REMAINING SOUTHBOUND VARIABLE DEPTH MILLING AND INTERMEDIATE ASPHALT PAVING ALONG THE PHASE 3B STEP 1 TRAFFIC LANES.
4. CLOSE THE I-71 SOUTHBOUND ENTRANCE RAMP FROM MORSE RD.
5. REMOVE THE INSIDE LANE CLOSURE AND SHIFT THE PHASE 3A INSIDE LANE TO THE PHASE 3B INSIDE LANE POSITION. CLOSE THE OUTSIDE PHASE 3B LANE PER SCD MT-95.30. REMOVE/COVER CONFLICTING DEVICES. CONTINUE TO MAINTAIN THE SOUTHBOUND CONTRAFLOW LANE.
6. COMPLETE THE REMAINING VARIABLE DEPTH MILLING/INTERMEDIATE ASPHALT PAVING AND PHASE 3B STEP 1 TEMPORARY TRAFFIC CONTROL DEVICES.
7. REMOVE THE LANE CLOSURE AND RAMP CLOSURE. BEGIN PHASE 3B STEP 1 WORK ACTIVITIES.

**SEQUENCE OF WORK** CONT'D

PHASE 3B STEP 1: WITH TRAFFIC IN THE PHASE 3B POSITION, AND WITH DETOUR IN PLACE, CLOSE MORSE ROAD AND SR 161 FOR BRIDGE DEMOLITION ACTIVITES. REMOVE EXISTING PIERS AND INSTALL TEMPORARY SIDEWALK WITHIN THE PHASE LIMITS PRIOR TO REOPENING. DO NOT CLOSE MORSE ROAD AND SR 161 SIMULTANEOUSLY.

CONSTRUCT THE I-71 SOUTHBOUND OUTSIDE LANES ALONG THE NEW STRUCTURES AND CONNECTING PAVEMENT AT THE MAINLINE CROSSINGS OVER MORSE ROAD AND SR 161.

COMPLETE THE I-71 SOUTHBOUND EXIT RAMP TO SINCLAIR RD AND THE I-71 SOUTHBOUND ENTRANCE RAMP FROM MORSE RD.

PHASE 3B STEP 2: RE-OPEN THE I-71 SOUTHBOUND EXIT RAMP TO SINCLAIR RD AND THE I-71 SOUTHBOUND ENTRANCE RAMP FROM MORSE RD. COMPLETE THE I-71 SOUTHBOUND OUTSIDE LANES ALONG THE NEW STRUCTURES AND CONNECTING PAVEMENT AT THE MAINLINE CROSSINGS OVER MORSE ROAD AND SR 161.

BY THE END OF PHASE 3B STEP 2, COMPLETE THE PROPOSED ITS IMPROVEMENTS AND ABANDON THE EXISTING ITS INFRASTRUCTURE IN THE MEDIAN BARRIER.

**PHASE 4A**
REMOVE THE SOUTHBOUND CONTRAFLOW LANE AND INSTALL THE NORTHBOUND CONTRAFLOW LANE.

WITH TRAFFIC IN PHASE 4A POSITION, AND WITH DETOUR IN PLACE, CLOSE MORSE ROAD AND SR 161 FOR BRIDGE DEMOLITION ACTIVITES. REMOVE EXISTING PIERS AND INSTALL TEMPORARY SIDEWALK WITHIN THE PHASE LIMITS PRIOR TO REOPENING. DO NOT CLOSE MORSE RD AND SR 161 SIMULTANEOUSLY.

COMPLETE THE I-71 NORTHBOUND INSIDE LANES ALONG THE NEW STRUCTURES AND CONNECTING PAVEMENT AT THE MAINLINE CROSSINGS OVER MORSE ROAD AND SR 161

**PHASE 4B**
FOR TRANSITION FROM PHASE 4A TO 4B STEP 1:

1. SCHEDULE THE TRANSITION TO OCCUR DURING A WEEKEND LANE CLOSURE PERIOD.
2. CLOSE THE PHASE 4A INSIDE NORTHBOUND LANE PER SCD MT-95.30 WHILE MAINTAINING THE NORTHBOUND CONTRAFLOW LANE AND THE PHASE 4A OUTSIDE NORTHBOUND LANE.
3. COMPLETE THE REMAINING NORTHBOUND VARIABLE DEPTH MILLING AND INTERMEDIATE ASPHALT PAVING ALONG THE NORTHBOUND PHASE 4B STEP 1 TRAFFIC LANES.
4. CLOSE THE I-71 NORTHBOUND ENTRANCE RAMP FROM COOKE RD.
5. REMOVE THE INSIDE LANE CLOSURE AND SHIFT THE PHASE 4A INSIDE LANE TO THE PHASE 4B INSIDE LANE POSITION. CLOSE THE OUTSIDE PHASE 4B LANE PER SCD MT-95.30. REMOVE/COVER CONFLICTING DEVICES. CONTINUE TO MAINTAIN THE NORTHBOUND CONTRAFLOW LANE. MAINTAIN ACCESS TO THE I-71 NORTHBOUND EXIT RAMP TO SR 161 PER SCD MT-98.20.
6. COMPLETE THE REMAINING NORTHBOUND VARIABLE DEPTH MILLING/ INTERMEDIATE ASPHALT PAVING AND PHASE 4B TEMPORARY TRAFFIC CONTROL DEVICES.
7. REMOVE THE LANE CLOSURE AND RAMP CLOSURE. BEGIN PHASE 4B STEP 1 WORK ACTIVITIES.

PHASE 4B STEP 1: WITH TRAFFIC IN THE PHASE 4B POSITION, AND WITH DETOUR IN PLACE, CLOSE MORSE ROAD AND SR 161 FOR BRIDGE DEMOLITION ACTIVITES. REMOVE EXISTING PIERS AND INSTALL TEMPORARY SIDEWALK WITHIN THE PHASE LIMIT PRIOR TO REOPENING. DO NOT CLOSE MORSE ROAD AND SR 161 SIMULTANEOUSLY.

CONSTRUCT THE I-71 NORTHBOUND OUTSIDE LANES ALONG THE NEW STRUCTURES AND CONNECTING PAVEMENT AT THE MAINLINE CROSSINGS OVER MORSE ROAD AND SR 161.

COMPLETE THE I-71 NORTHBOUND EXIT RAMP TO MORSE ROAD AND THE I-71 NORTHBOUND ENTRANCE RAMP FROM MORSE ROAD.

PHASE 4B STEP 2: REOPEN THE I-71 NORTHBOUND EXIT AND ENTRANCE RAMPS AT MORSE ROAD.

COMPLETE THE I-71 NORTHBOUND OUTSIDE LANES ALONG THE NEW STRUCTURES AND CONNECTING PAVEMENT AT THE CROSSINGS OVER MORSE ROAD AND SR 161.

UPON COMPLETION OF PHASE 4B STEP 2, REMOVE THE NORTHBOUND CONTRAFLOW LANE AND SHIFT TRAFFIC TO FINAL CONFIGURATION.

INSTALL MOT DEVICES PER PHASE 2 AT THE CROSSOVER LOCATIONS AND RESTORE THE CROSSOVERS TO THE ORIGINAL CONFIGURATION.

**PHASE 5**
NOTE: PHASES 5, 6, AND 7 HAVE BEEN ASSIGNED PHASE LABELS FOR REFERENCE PURPOSES ONLY. THE I-71 BRIDGE REHABILIATION WORK AT 2ND AVENUE, 17TH AVENUE, AND HIAWATHA PARK DRIVE IS NOT REQUIRED TO BE COMPLETED IN A PARTICULAR ORDER. INCLUDE THE PROPOSED SEQUENCE OF WORK IN THE PROJECT SCHEDULE FOR ENGINEER'S APPROVAL.

WITH A SERIES OF 4 WEEKEND LANE CLOSURE PERIODS, COMPLETE THE BRIDGE REHABILIATION WORK AT THE I-71 MAINLINE CROSSING OVER 2ND AVENUE. COMPLETE EACH STEP WITHIN ONE WEEKEND LANE CLOSURE PERIOD.

**SEQUENCE OF WORK** CONT'D

PHASE 5A STEP 1: INSTALL THE BRIDGE DECK OVERLAY ALONG THE NORTHBOUND INSIDE LANES

PHASE 5A STEP 2: INSTALL THE BRIDGE DECK OVERLAY ALONG THE NORTHBOUND OUTSIDE LANES

PHASE 5B STEP 1: INSTALL THE BRIDGE DECK OVERLAY ALONG THE SOUTHGBOUND INSIDE LANES

PHASE 5B STEP 2: INSTALL THE BRIDGE DECK OVERLAY ALONG THE SOUTHBOUND OUTSIDE LANES

**PHASE 6**
WITH A SERIES OF 4 WEEKEND LANE CLOSURE PERIODS, COMPLETE THE BRIDGE REHABILIATION WORK AT THE I-71 MAINLINE CROSSING OVER 17TH AVENUE. COMPLETE EACH STEP WITHIN ONE WEEKEND LANE CLOSURE PERIOD.

PHASE 6A STEP 1: INSTALL THE BRIDGE DECK OVERLAY ALONG THE NORTHBOUND INSIDE LANES

PHASE 6A STEP 2: INSTALL THE BRIDGE DECK OVERLAY ALONG THE NORTHBOUND OUTSIDE LANES

PHASE 6B STEP 1: INSTALL THE BRIDGE DECK OVERLAY ALONG THE SOUTHGBOUND INSIDE LANES

PHASE 6B STEP 2: INSTALL THE BRIDGE DECK OVERLAY ALONG THE SOUTHBOUND OUTSIDE LANES

**PHASES 7A & 7B**
WITH A SERIES OF 8 WEEKEND LANE CLOSURE PERIODS, COMPLETE THE BRIDGE REHABILIATION WORK AT THE I-71 MAINLINE CROSSING OVER HIAWATHA PARK DR. COMPLETE EACH STEP WITHIN ONE WEEKEND LANE CLOSURE PERIOD.

PHASE 7A STEP 1: REPLACE THE APPROACH SLAB ALONG THE NORTHBOUND INSIDE LANES

PHASE 7A STEP 2: REPLACE THE APPROACH SLAB ALONG THE NORTHBOUND OUTSIDE LANES

PHASE 7A STEP 3: INSTALL THE BRIDGE DECK OVERLAY ALONG THE NORTHBOUND INSIDE LANES

PHASE 7A STEP 4: INSTALL THE BRIDGE DECK OVERLAY ALONG THE NORTHBOUND OUTSIDE LANES

PHASE 7B STEP 1: REPLACE THE APPROACH SLAB ALONG THE SOUTHBOUND INSIDE LANES

PHASE 7B STEP 2: REPLACE THE APPROACH SLAB ALONG THE SOUTHBOUND OUTSIDE LANES

PHASE 7B STEP 3: INSTALL THE BRIDGE DECK OVERLAY ALONG THE SOUTHBOUND INSIDE LANES

PHASE 7B STEP 4: INSTALL THE BRIDGE DECK OVERLAY ALONG THE SOUTHBOUND OUTSIDE LANES

**PHASE 8**
UPON COMPLETION OF PHASES 1 THROUGH 7, COMPLETE ALL REMAINING WORK ITEMS, INCLUDING THE SURFACE STREET WORK ALONG MORSE RD AND SR 161.

REMOVE TEMPORARY LIGHTING.

COMPLETE ALL PUNCH LIST ITEMS

# MAINTENANCE OF TRAFFIC - GENERAL NOTES

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.36 TOTAL 618

FRA-71-19.10

MODEL: Sheet 6 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:54:25 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MN001.dgn

A

MORSE ROAD
(60"x18")
DETOUR
M4-9R-30
(MOD)

B

MORSE ROAD
(48"x18")
DETOUR
M4-9R-30

C

MORSE ROAD
(48"x18")
DETOUR
M4-9S-30

D

RAMP WILL BE CLOSED FOR DAYS
INFO:
W20-H13-60
(SIGN TO BE ERECTED 7 DAYS IN ADVANCE OF CLOSURE)

E

END DETOUR
M4-8a-24

F

R11-2 ROAD CLOSED
R11-2 ROAD CLOSED

TYPE III BARRICADES PER MT-101.60

HIGH STREET
INDIANOLA AVENUE
SINCLAIR ROAD
HUNTLEY RO
BUSCH BLVD.
COOKE ROAD
COOKE ROAD
MORSE ROAD
MORSE ROAD
23
71
161

NOT TO SCALE

LEGEND:

XX ROAD CLOSURE

MORSE RD. DETOUR DIRECTION OF TRAFFIC

TYPE III BARRICADE

# MAINTENANCE OF TRAFFIC - DETOUR MAP
## PHASE 3A STEP 1 - MORSE RD./SINCLAIR RD. SB EXIT RAMP CLOSURE

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.37 | TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:54:37 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MD001.dgn

A

DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-3-21

B

DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

C

DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

D

DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

E

END DETOUR
M4-8a-24

F

R11-2 ROAD CLOSED
R11-2 ROAD CLOSED

TYPE III BARRICADES PER MT-101.60

G

I-71 SOUTH RAMP CLOSED FOLLOW DETOUR

SPECIAL (48" x 48")

H

DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

I

ROAD CLOSED
R11-2-48

DETOUR
M4-10R-48

J


RAMP WILL BE CLOSED FOR DAYS
INFO:

W20-H13-60
(SIGN TO BE ERECTED 7 DAYS IN ADVANCE OF CLOSURE)

1

NORTH 71 SOUTH

EXISTING SIGN TO REMAIN




# MAINTENANCE OF TRAFFIC - DETOUR MAP
## PHASE 3A STEP 2 - MORSE RD. SB ENTRANCE RAMP CLOSURE

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.38 TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:54:52 AM PLTDRV: OHDOT_PDF_Ex.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MD002.dgn

A
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-3-21

B
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

C
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

D
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

E
END DETOUR
M4-8a-24

F
ROAD CLOSED
R11-2-48
DETOUR
M4-10R-48
MOUNTED ON TYPE III BARRICADE

G
MORSE ROAD
(60"x18")
DETOUR
M4-9R-30
(MOD)

H
EXIT CLOSED
E5-2a-48

I
NOT USED

J
MORSE ROAD
(48"x18")
DETOUR
M4-9R-30

K
DETOUR M4-8-24
MORSE ROAD
(48"x18")
DETOUR
M4-9S-30

L
DETOUR M4-8-24
MORSE ROAD
(48"x18")
M5-1-21

M
I-71 SOUTH
RAMP
CLOSED
FOLLOW DETOUR
SPECIAL
(48" x 48")

N
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

O
NOT USED

P
R11-2 ROAD CLOSED
R11-2 ROAD CLOSED
TYPE III BARRICADES PER MT-101.60

Q
RAMP WILL BE CLOSED
FOR DAYS
INFO:
W20-H13-60
(SIGN TO BE ERECTED 7 DAYS IN ADVANCE OF CLOSURE)

1
NORTH INTERSTATE 71 SOUTH

2
EXIT 116
Morse Rd
Sinclair Rd
CLOSED
OVERLAY WITH W20-H-15a

3
EXIT 116
Morse Rd
Sinclair Rd
CLOSED
OVERLAY WITH W20-H-15a

4
Morse Rd CLOSED
Cooke Rd 1 3/4
N Broadway 2 3/4
OVERLAY WITH W20-H-15a

5
EXIT 116
Sinclair Rd
Morse Rd
EXIT CLOSED
W20-H-15

6
EXIT 115
Cooke Rd
1/4 MILE
EXIT 116
Morse Rd
Sinclair Rd
EXIT CLOSED
W20-H-15
COVER ARROW WITH BLANK OVERLAY

7
INTERSTATE 71 SOUTH
Cincinnati
CLOSED
OVERLAY WITH W20-H-15a

8
SOUTH
INTERSTATE 71
CLOSED
OVERLAY WITH W20-H-15a

HIGH STREET

INDIANOLA AVENUE

INDIANOLA AVENUE

SINCLAIR ROAD

HUNTLEY ROA

BUSCH BLVD.

COOKE ROAD

COOKE ROAD

MORSE ROAD

23

71

161

NOT TO SCALE

LEGEND:
- XX ROAD CLOSURE
- IR-71 SB DETOUR DIRECTION OF TRAFFIC
- MORSE RD. DETOUR DIRECTION OF TRAFFIC
- TYPE III BARRICADE

# MAINTENANCE OF TRAFFIC - DETOUR MAP
## PHASE 3B STEP 1 - MORSE RD. EXIT AND ENTRANCE CLOSURE

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.39 TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:55:08 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MD003.dgn

# MAINTENANCE OF TRAFFIC - DETOUR MAP
## PHASE 4B STEP 1 - MORSE RD. EXIT AND ENTRANCE CLOSURE

**A**
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-3-21

**B**
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

**C**
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

**D**
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

**E**
END DETOUR
M4-8a-24

**F**
ROAD CLOSED
R11-2-48
DETOUR
M4-10L-48
MOUNTED ON TYPE III BARRICADE

**G**
MORSE ROAD (60"x18")
DETOUR
M4-9R-30 (MOD)

**H**
EXIT CLOSED
E5-2a-48

**I**
MORSE ROAD (48"x18")
DETOUR
M4-9R-30

**J**
DETOUR M4-8-24
MORSE ROAD (48"x18")
DETOUR
M4-9S-30

**K**
DETOUR M4-8-24
MORSE ROAD (48"x18")
M5-1-21

**R**
MORSE ROAD
NORTHBOUND EXIT
CLOSED
FOLLOW DETOUR
SPECIAL (48" x 48")

**P**
R11-2 ROAD CLOSED
R11-2 ROAD CLOSED
TYPE III BARRICADES PER MT-101.60

**L**
I-71 NORTH
RAMP
CLOSED
FOLLOW DETOUR
SPECIAL (48" x 48")

**M**
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

**N**
MORSE ROAD (48"x18")
DETOUR
M4-9L-30

**O**
RAMP WILL BE
CLOSED
FOR DAYS
INFO:
W20-H13-60
(SIGN TO BE ERECTED 7 DAYS IN ADVANCE OF CLOSURE)

**1**
INTERSTATE 71 NORTH
Cleveland
CLOSED
OVERLAY WITH W20-H-15a


**2**
Cooke Rd 1/4
Morse Rd CLOSED
161 3 1/4
OVERLAY WITH W20-H-15a

**3**
EXIT 116
Morse Rd
Sinclair Rd
CLOSED
OVERLAY WITH W20-H-15a
EXIT 115
Cooke Rd

**4**
Morse Rd CLOSED
161 2 1/4
670 4
OVERLAY WITH W20-H-15a

**5**
EXIT 116
Morse Rd
Sinclair Rd
EXIT CLOSED
W20-H-15
COVER ARROW WITH BLANK OVERLAY

**6**
N Broadway 1/4
Cooke Rd 1 1/4
Morse Rd CLOSED




NOT TO SCALE

LEGEND:
- XX ROAD CLOSURE
- IR-71 NB DETOUR DIRECTION OF TRAFFIC
- MORSE RD. DETOUR DIRECTION OF TRAFFIC
- TYPE III BARRICADE

DESIGN AGENCY: Jacobs

| | |
|---|---|
| DESIGNER | SRH |
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.40 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:55:25 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\MOT\Sheets\109164_MD004.dgn

# MAINTENANCE OF TRAFFIC - DETOUR MAP
## PHASE 5B STEPS 1 & 2 - 5TH AVENUE TO I-71 SB ENTRANCE RAMP CLOSURE

**A**
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-3-21

**B**
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

**C**
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

**D**
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

**E**
END DETOUR
M4-8a-24

**F**
ROAD CLOSED
R11-2-48
DETOUR
M4-10R-48
MOUNTED ON TYPE III BARRICADE


**G**
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

**H**
I-71 SOUTHBOUND RAMP CLOSED FOLLOW DETOUR
SPECIAL (48" x 48")

**I**
RAMP WILL BE CLOSED FOR DAYS
INFO:
W20-H13-60
(SIGN TO BE ERECTED 7 DAYS IN ADVANCE OF CLOSURE)

**J**
R11-2 ROAD CLOSED
R11-2 ROAD CLOSED
TYPE III BARRICADES PER MT-101.60

**1**
INTERSTATE 71 SOUTH
Cincinnati
EXISTING SIGN TO REMAIN




NOT TO SCALE

LEGEND:
- XX ROAD CLOSURE
- → IR-71 SB DETOUR DIRECTION OF TRAFFIC
- TYPE III BARRICADE

DESIGN AGENCY: Jacobs

| | |
|---|---|
| DESIGNER | SRH |
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.41 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:55:40 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MD005.dgn

A

DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-3-21

B

DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

C

DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

D

DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

E

DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71

M6-1-21

F

END DETOUR
M4-8a-24

G

ROAD CLOSED
R11-2-48
DETOUR
M4-10L-48
MOUNTED ON TYPE III BARRICADE

H

I-71
NORTHBOUND
RAMP CLOSED
FOLLOW DETOUR

SPECIAL
(48" x 48")

I

RAMP WILL BE CLOSED
FOR DAYS
INFO:

W20-H13-60
(SIGN TO BE ERECTED 7 DAYS IN ADVANCE OF CLOSURE)

J


R11-2 ROAD CLOSED
R11-2 ROAD CLOSED

TYPE III BARRICADES PER MT-101.60

1

INTERSTATE 71 NORTH
Cleveland

EXISTING SIGN TO REMAIN




NOT TO SCALE

LEGEND:

XX ROAD CLOSURE

IR-71 NB DETOUR DIRECTION OF TRAFFIC

TYPE III BARRICADE

# MAINTENANCE OF TRAFFIC - DETOUR MAP
## PHASE 6A STEP 2 - NORTHBOUND 11TH AVE. ENTRANCE RAMP CLOSURE

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.42 TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:55:56 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MD006.dgn

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:56:11 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MD007.dgn

FRA-71-19.10

A
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-3-21

B
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

C
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

D
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

E
END DETOUR
M4-8a-24

F
ROAD CLOSED
R11-2-48
DETOUR
M4-10L-48
MOUNTED ON TYPE III BARRICADE


G
I-71 NORTHBOUND RAMP CLOSED FOLLOW DETOUR
SPECIAL (48" x 48")

H
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

I
RAMP WILL BE CLOSED FOR DAYS
INFO:
W20-H13-60
(SIGN TO BE ERECTED 7 DAYS IN ADVANCE OF CLOSURE)

J
R11-2 ROAD CLOSED
R11-2 ROAD CLOSED
TYPE III BARRICADES PER MT-101.60

1
INTERSTATE 71 NORTH
Cleveland
EXISTING SIGN TO REMAIN




NOT TO SCALE

LEGEND:
- XX ROAD CLOSURE
- IR-71 NB DETOUR DIRECTION OF TRAFFIC
- TYPE III BARRICADE

# MAINTENANCE OF TRAFFIC - DETOUR MAP
## PHASE 7A STEPS 1/3 & 2/4 - NORTHBOUND 17TH AVE. ENTRANCE CLOSURE

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.43 TOTAL 618

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:56:28 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MD008.dgn

FRA-71-19.10

**A**

DETOUR M4-8-24
SOUTH M3-3-24
INTERSTATE 71 M1-1-24-2
M6-3-21

**B**

DETOUR M4-8-24
SOUTH M3-3-24
INTERSTATE 71 M1-1-24-2
M5-1-21

**C**

DETOUR M4-8-24
SOUTH M3-3-24
INTERSTATE 71 M1-1-24-2
M6-1-21

**D**

DETOUR M4-8-24
SOUTH M3-3-24
INTERSTATE 71 M1-1-24-2
M5-1-21

**E**

END DETOUR
*M4-8a-24*

**F**

ROAD CLOSED
*R11-2-48*

DETOUR
*M4-10R-48*
*MOUNTED ON TYPE III BARRICADE*

**G**

I-71 SOUTHBOUND RAMP CLOSED FOLLOW DETOUR
*SPECIAL (48" x 48")*

**H**

DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

**I**


RAMP WILL BE CLOSED FOR DAYS
INFO:
*W20-H13-60*
*(SIGN TO BE ERECTED 7 DAYS IN ADVANCE OF CLOSURE)*

**J**

R11-2 ROAD CLOSED
R11-2 ROAD CLOSED
*TYPE III BARRICADES PER MT-101.60*

**1**

INTERSTATE 71 SOUTH
Cincinnati
*EXISTING SIGN TO REMAIN*




NOT TO SCALE


*LEGEND:*


- XX — *ROAD CLOSURE*
- → — *IR-71 SB DETOUR DIRECTION OF TRAFFIC*
- *TYPE III BARRICADE*


# MAINTENANCE OF TRAFFIC - DETOUR MAP
## PHASE 7B STEPS 1/3 & 2/4 - SOUTHBOUND HUDSON ST. ENTRANCE RAMP CLOSURE

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.44 TOTAL 618







## PORTABLE CHANGEABLE MESSAGE SIGNS (PCMS):

| MESSAGE 1 | | MESSAGE 2 | |
|---|---|---|---|
| MORSE RD CLOSED AT I-71 | FOLLOW DETOUR | MORSE RD CLOSED AT I-71 | 10 PM (DATE) TO 5AM (DATE) |
| (2 SEC) | (2 SEC) | (2 SEC) | (2 SEC) |
| DURING ROAD CLOSURE PERIOD | | FOR SEVEN (7) DAYS IN ADVANCE OF ROAD CLOSURE PERIOD | |

## NOTES:

PROVIDE PORTABLE CHANGEABLE MESSAGE SIGNS AT "PCMS" LOCATIONS SEVEN (7) DAYS PRIOR TO CLOSURE DATE.

NOT TO SCALE

## LEGEND:

- XX — ROAD CLOSURE
- MORSE RD. WB AND I-71 SB DETOUR DIRECTION OF TRAFFIC
- MORSE RD. EB AND I-71 NB DETOUR DIRECTION OF TRAFFIC
- PORTABLE CHANGEABLE MESSAGE SIGN
- TYPE III BARRICADES PER SCD MT-101.60

# MAINTENANCE OF TRAFFIC - DETOUR MAP
# MORSE ROAD BRIDGE CLOSURE

DESIGN AGENCY: Jacobs

DESIGNER: SRH


REVIEWER: BAP 03/20/26

PROJECT ID: 109164

SHEET P.45 | TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:56:43 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MD009.dgn




MAINTENANCE OF TRAFFIC - DETOUR MAP
SR 161 BRIDGE CLOSURE DETOUR

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.46 | TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:57:00 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MD010.dgn

# MAINTENANCE OF TRAFFIC - DETOUR MAP
# SR 161 BRIDGE CLOSURE WESTBOUND DETOUR

A
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-3-21

B
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21


C
DETOUR M4-8-24
NORTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

D
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-3-21

E
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M5-1-21

F
DETOUR M4-8-24
SOUTH M3-1-24
INTERSTATE 71 M1-1-24-2
M6-1-21

G
END DETOUR
M4-8a-24





DESIGN AGENCY
Jacobs


DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.47 TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:57:16 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V400-Engineering\MOT\Sheets\109164_MD011.dgn




*TYPE III BARRICADES PER MT-101.60*




*E5-2a-48*

*MESSAGES FOR PORTABLE CHANGEABLE MESSAGE SIGNS:*

| P1 | | P2 | | P3 | |
|---|---|---|---|---|---|
| I-71 NB CLOSED AT I-670 | USE SR-315 | I-71 NB CLOSED AT I-670 | USE I-270 | I-71 NB CLOSED AT I-670 | 10 PM FRI TO 5AM MON |
| (2 SEC) | (2 SEC) | (2 SEC) | (2 SEC) | (2 SEC) | (2 SEC) |

*NOTES:*

*PORTABLE CHANGEABLE MESSAGE SIGNS AT LOCATIONS WITH (P3) SHALL BE PLACED SEVEN (7) DAYS PROIR TO CLOSURE.*
*ON THE DAY OF THE CLOSURE, USE MESSAGES ON PORTABLE CHANGEABLE MESSAGE SIGNS (P1) & (P2) AS SHOWN.*




*NOT TO SCALE*

*LEGEND:*

- XX — *ROAD CLOSURE*
- — *PORTABLE CHANGEABLE MESSAGE SIGN*
- H — *TYPE III BARRICADE*

MAINTENANCE OF TRAFFIC - DETOUR MAP
BRIDGE NO. FRA-0071-18.750B OVERLAY - I-670 TO I-71 NB RAMP CLOSURE

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.48 | TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:57:33 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MD012.dgn

A

*Type A Warning Light*




*W20-1-48*

B




*R11-H5a*

C





*W3-H5b*

D




*Digital Speed Limit (DSL) Sign Assembly*

E




*W4-2L-48 STEPS 1 & 3*

*OR*

*W4-2R-48 STEPS 2 & 4*

F


*Type A Warning Light*





*W20-5-48 STEPS 1 & 3*

*OR*

*Type A Warning Light*




*W20-5-48 STEPS 2 & 4*




*NOT TO SCALE*

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
## I-71 NORTHBOUND - PHASE 1B STEPS 1/3 & 2/4

FRA-71-19.10

DESIGN AGENCY: Jacobs

DESIGNER: SRH

REVIEWER: BAP 03/20/26

PROJECT ID: 109164

SHEET: P.49 | TOTAL: 618

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:57:48 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM001.dgn

A

*Type A Warning Light*




*W20-1-48*

B




*R11-H5a*

C




*R4-H5a-36*

D





*R4-9-36*

E




*W3-H5b*

F




*W24-1bR-48*

G




*Digital Speed Limit (DSL) Sign Assembly*




NOT TO SCALE

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 NORTHBOUND - PHASE 2(SOUTH OF MORSE RD)

DESIGN AGENCY

Jacobs

| | |
|---|---|
| DESIGNER | SRH |
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.50 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:58:04 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM002.dgn

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 NORTHBOUND - PHASE 3A STEP 3 & PHASE 3B

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.51 | TOTAL 618

FRA-71-19.10

NOT TO SCALE

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:58:19 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\MOT\Sheets\109164_MM003.dgn

A

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

B

WORK ZONE
SPEEDING
FINES DOUBLED
CAUSE DEATH OR INJURY
FINE/JAIL

*R11-H5a*

C

TRUCKS USE RIGHT LANE

*R4-5R*

D

VARIABLE SPEED LIMIT AHEAD

*W3-H5b*

E

*Type A Warning Light*

*W9-3a-48*

1/2 MILE

*W16-3aP-30*

F

*Type A Warning Light*

*W9-3a-48*

1 MILE

*W16-3aP-30*

G

MORSE ROAD
SR 161
KEEP RIGHT

H

INTERSTATE 71 NORTH
ALL LANES

I

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

1 MILE

*W16-3aP-30*

J

*Type A Warning Light*

*W9-3a-48*

2 MILES

*W16-3aP-30*


K

*Type A Warning Light*

*W9-3a-48*

3 MILES

*W16-3aP-30*




NOT TO SCALE

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 NORTHBOUND - PHASES 4A & 4B


FRA-71-19.10

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.52 TOTAL 618

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:58:36 AM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM004.dgn

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 NORTHBOUND - PHASE 5A STEP 1




| | |
|---|---|
| DESIGN AGENCY | Jacobs |
| DESIGNER | SRH |
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.53 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: MM006 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:58:51 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM005.dgn

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 NORTHBOUND - PHASE 5A STEP 2




DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26


PROJECT ID
109164


SHEET P.54 | TOTAL 618

FRA-71-19.10


MODEL: MM006 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:59:06 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM006.dgn

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 NORTHBOUND - PHASE 6A STEPS 1 & 2




NOT TO SCALE

| | |
|---|---|
| DESIGN AGENCY | Jacobs |
| DESIGNER | SRH |
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.55 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:59:21 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\MOT\Sheets\109164_MM007.dgn

A

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

B

WORK ZONE
SPEEDING
FINES DOUBLED
CAUSE DEATH OR INJURY
FINE/JAIL

*R11-H5a*

C

VARIABLE SPEED LIMIT AHEAD

*W3-H5b*

D

WORK ZONE
SPEED LIMIT
YY

*Digital Speed Limit (DSL) Sign Assembly*

E

OR

*W4-2L-48*
*STEPS 1 & 3*

*W4-2R-48*
*STEPS 2 & 4*

F

*Type A Warning Light*

LEFT LANE CLOSED AHEAD


*W20-5-48*
*STEPS 1 & 3*

OR

*Type A Warning Light*

RIGHT LANE CLOSED AHEAD

*W20-5-48*
*STEPS 2 & 4*




NOT TO SCALE

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 NORTHBOUND - PHASE 7A STEPS 1/3 & 2/4

FRA-71-19.10

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.56 | TOTAL 618

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:59:40 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM008.dgn

A

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

B

WORK ZONE
SPEEDING
FINES DOUBLED
CAUSE DEATH OR INJURY
FINE/JAIL

*R11-H5a*

C

TRUCKS USE LEFT 2 LANES

*R4-H5a-36*

D

STAY IN LANE

*R4-9-36*

E

VARIABLE SPEED LIMIT AHEAD

*W3-H5b*


F

*W24-1bR-48*

G

*WORK ZONE*
*SPEED LIMIT*
*YY*

*Digital Speed Limit (DSL) Sign Assembly*




NOT TO SCALE

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 NORTHBOUND - PHASE 2(NORTH OF SR 161)

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.57 | TOTAL 618

FRA-71-19.10


MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:33:10 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\MOT\Sheets\109164_MM009.dgn

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:00:11 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM101.dgn

FRA-71-19.10

A

*Type A Warning Light*




*W20-1-48*

B




*R11-H5a*

C





*W3-H5b*

D




*Digital Speed Limit (DSL) Sign Assembly*

E




*OR*

*W4-2L-48*
*STEPS 1 & 3*

*W4-2R-48*
*STEPS 2 & 4*


F

*Type A Warning Light*





*OR*

*Type A Warning Light*




*W20-5-48*
*STEPS 1 & 3*

*W20-5-48*
*STEPS 2 & 4*




NOT TO SCALE

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 SOUTHBOUND - PHASE 1A STEPS 1/3 & 2/4

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.58 | TOTAL 618

A

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

B

WORK ZONE
SPEEDING
FINES DOUBLED
CAUSE DEATH OR INJURY
FINE/JAIL

*R11-H5a*

C

TRUCKS USE LEFT 2 LANES

*R4-H5a-36*

D

STAY IN LANE

*R4-9-36*

E

VARIABLE SPEED LIMIT AHEAD

*W3-H5b*


F

*W24-1bR-48*

G

*WORK ZONE*
*SPEED LIMIT*
*YY*

*Digital Speed Limit (DSL) Sign Assembly*




NOT TO SCALE

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 SOUTHBOUND - PHASE 2(SOUTH OF MORSE RD)

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.59 | TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:00:26 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6AA20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\40D-Engineering\MOT\Sheets\109164_MM102.dgn

A

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

B

WORK ZONE
SPEEDING
FINES DOUBLED
CAUSE DEATH OR INJURY
FINE/JAIL

*R11-H5a*

C

TRUCKS USE RIGHT LANE

*R4-5R*

D

*Type A Warning Light*

*W9-3a-48*

1/2 MILE

*W16-3aP-30*

E

*Type A Warning Light*

*W9-3a-48*

1 MILE

*W16-3aP-30*

F

MORSE ROAD
SR 161
KEEP RIGHT

G

71 SOUTH
ALL LANES

H

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

1 MILE

*W16-3aP-30*

I

*Type A Warning Light*

*W9-3a-48*

2 MILES

*W16-3aP-30*


J

*Type A Warning Light*

*W9-3a-48*

3 MILES

*W16-3aP-30*




NOT TO SCALE

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 SOUTHBOUND - PHASE 3A STEP 3 & PHASE 3B

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.60 TOTAL 618

FRA-71-19.10


MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:00:45 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM103.dgn

A

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

B

WORK ZONE
SPEEDING
FINES DOUBLED
CAUSE DEATH OR INJURY
FINE/JAIL

*R11-H5a*

C

TRUCKS USE LEFT 2 LANES

*R4-H5aL*

D

STAY IN LANE

*R4-9-36*

E

VARIABLE SPEED LIMIT AHEAD

*W3-H5b*

71

270

HUNTLEY ROAD

SCHROCK ROAD

KARL ROAD

71

A

B

660'

C

A

B

1200'

A

B

1320'

*BEGIN ADVANCE WARNING SIGNAGE AT STA. 1481+00*

E

D

*PHASE 4A/4B WORK ZONE. SEE MOT PHASE 4A/4B PLAN SHEETS.*

N

*NOT TO SCALE*

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
## I-71 SOUTHBOUND - PHASES 4A & 4B

DESIGN AGENCY

Jacobs

| | |
|---|---|
| DESIGNER | SRH |
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.61 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:01:08 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\MOT\Sheets\109164_MM104.dgn

A

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

B

WORK ZONE
SPEEDING
FINES DOUBLED
CAUSE DEATH OR INJURY
FINE/JAIL

*R11-H5a*

C

*Type A Warning Light*

LEFT LANE CLOSED AHEAD

*W20-5-48*

D

VARIABLE SPEED LIMIT AHEAD

*W3-H5b*

E

*W4-2L-48*

F

WORK ZONE
SPEED LIMIT
YY

*Digital Speed Limit (DSL) Sign Assembly*




NOT TO SCALE

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
## I-71 SOUTHBOUND - PHASE 5B STEP 1

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.62 | TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:01:31 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM105.dgn

A

*Type A Warning Light*




*W20-1-48*

B




*R11-H5a*

C




*R4-H5aL*

D





*R4-9-36*

E





*W3-H5b*

F



*W24-1bL-48*
*INSIDE SHOULDER ONLY*




NOT TO SCALE

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 SOUTHBOUND - PHASE 5B STEP 2

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.63 | TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:02:14 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM106.dgn

A

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

B

WORK ZONE
SPEEDING
FINES DOUBLED
CAUSE DEATH OR INJURY
FINE/JAIL

*R11-H5a*

C

VARIABLE SPEED LIMIT AHEAD

*W3-H5b*

D

*WORK ZONE*
*SPEED LIMIT*
*YY*

*Digital Speed Limit (DSL) Sign Assembly*

E

*OR*

*W4-2L-48*
*STEP 1*

*W4-2R-48*
*STEP 2*

F

*Type A Warning Light*

LEFT LANE CLOSED AHEAD


*W20-5-48*
*STEP 1*

*OR*

*Type A Warning Light*

RIGHT LANE CLOSED AHEAD

*W20-5-48*
*STEP 2*




*NOT TO SCALE*

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 SOUTHBOUND - PHASE 6B STEPS 1 & 2

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.64 | TOTAL 618

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:02:30 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM107.dgn

A

*Type A Warning Light*




*W20-1-48*

B




*R11-H5a*

C





*W3-H5b*

D




*Digital Speed Limit (DSL) Sign Assembly*

E




*OR*

*W4-2L-48 STEPS 1 & 3*

*W4-2R-48 STEPS 2 & 4*


F

*Type A Warning Light*





*OR*

*Type A Warning Light*




*W20-5-48 STEPS 1 & 3*

*W20-5-48 STEPS 2 & 4*




*NOT TO SCALE*

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN I-71 NORTHBOUND - PHASE 7B STEPS 1/3 & 2/4

FRA-71-19.10


MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:03:27 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM108.dgn


DESIGN AGENCY: Jacobs

DESIGNER: SRH

REVIEWER: BAP 03/20/26

PROJECT ID: 109164

SHEET: P.65 TOTAL: 618

A

*Type A Warning Light*




*W20-1-48*

B




*R11-H5a*

C




*W3-H5b*

D




*Digital Speed Limit (DSL) Sign Assembly*

E




*W4-2R-48*

F

*Type A Warning Light*




*W20-5-48*




*NOT TO SCALE*

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
# I-71 SOUTHBOUND - PHASE 3A STEP 2

DESIGN AGENCY

Jacobs

| | |
|---|---|
| DESIGNER | SRH |
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.66 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:04:30 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM109.dgn

A

*Type A Warning Light*

ROAD WORK AHEAD

*W20-1-48*

B

WORK ZONE
SPEEDING
FINES DOUBLED
CAUSE DEATH OR INJURY
FINE/JAIL

*R11-H5a*

C

TRUCKS USE LEFT 2 LANES

*R4-H5a-36*

D

STAY IN LANE

*R4-9-36*

E

VARIABLE SPEED LIMIT AHEAD

*W3-H5b*

F

*W24-1bR-48*

G

*WORK ZONE*
*SPEED LIMIT*
*YY*

*Digital Speed Limit (DSL) Sign Assembly*




*NOT TO SCALE*

# MAINTENANCE OF TRAFFIC - ADVANCE WARNING SIGN PLAN
## I-71 SOUTHBOUND - PHASE 2(NORTH OF SR161)

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164


SHEET P.67 | TOTAL 618


FRA-71-19.10


MODEL: Untitled Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:04:46 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\MOT\Sheets\109164_MM110.dgn

FRA-71-19.10

MODEL: Phase 2A - Plan 2 PAPERSIZE: ISO A0 (1189.0 mm x 841.0 mm) DATE: 3/31/2026 TIME: 11:05:14 AM PSTDRV: DWGPT_PDF_V1.pltCfg PENTBL: DWGPT_Print.ctb USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL USERS ARE RESPONSIBLE FOR ENSURING THAT THE MOST CURRENT VERSION OF THIS FILE IS USED. THIS FILE IS PROVIDED AS AN ELECTRONIC REPRODUCTION FOR CONVENIENCE AND INFORMATIONAL PURPOSES ONLY.




TYPICAL SECTION - PHASE 1A STEPS 1 & 3
STA. 1244+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND


- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 1A STEPS 1 & 3
# STA. 1232+00.00 TO STA. 1249+00.00

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.68 TOTAL 618




*NOTES*
1. UTILIZE SCD MT-95.30 FOR SINGLE NIGHTTIME LANE LANE CLOSURES PER THE PERMITED LANE CLOSURE SCHEDULE TO INSTALL PAVEMENT FOR MAINTAINING TRAFFIC.
2. REPLACE APPROACH SLABS (AND SLEEPER SLAB/ASPHALT PAVEMENT) IN STEP 1.
3. INSTALL SDC OVERLAY IN STEP 3.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 1A STEPS 1 & 3
# STA. 1249+00.00 TO STA. 1266+00.00


DESIGN AGENCY
Jacobs

DESIGNED SRH
REVIEWED BAP 03/20/26
PROJECT ID 109164
SHEET P.69 TOTAL 618

FRA-71-19.10

MODEL: Phase 2A - Plan | PAPERSIZE: ISO A1 | DATE: 3/31/2026 TIME: 11:05:35 AM | FSTDIV: CMDOT_PDF_V | LAYER_FSTYPE: CMDOT_Plan.tbl | USER: Chris.Lawrence1@jacobs.com | WORKSPACE: CMDOTCIVIL02 | WORKSET: 109164 | PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE: C:\Projects\109164\Roadway\Design\Phase 2A\Plan\FRA-71-19.10_MOT_Phase 2A_Plan.dgn | REFS: C:\Projects\109164\Roadway\Design\Phase 2A\Plan\FRA-71-19.10_MOT_Phase 2A_Plan.dgn




TYPICAL SECTION - PHASE 1A STEPS 1 & 3
STA. 1275+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 1A STEPS 1 & 3
# STA. 1266+00.00 TO STA. 1283+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.70 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1A - Plan # PAPERSIZE: ANSI-B (in.) DATE: 3/31/2026 TIME: 11:03:11 AM PLTDRV: CTBDRV_PDF_V1.ctb PENTBL: CTBDRV_PMS.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOT1X02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE: P:\Projects\Fra\71\109164\Roadway\Design\Phase 1A\MOT\MOT_Phase 1A.dgn REFERENCES: P:\Projects\Fra\71\109164\Roadway\Design\Phase 1A\MOT\MOT_Phase 1A.dgn




NOTE: SEE SHEET P.58 FOR PHASE 1A ADVANCED SIGNING PLAN

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 1A STEPS 1 & 3
# STA. 1283+00.00 TO STA. 1300+00.00

DESIGN AGENCY
Jacobs


DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT NO: 109164
SHEET: P.71 TOTAL: 618


FRA-71-19.10

MODEL: Phase 2A - Plan | PAPERSIZE: ISO A1 | DATE: 3/31/2026 TIME: 11:03:23 AM | XSTORY: ON|OFF | XREF_FI: LAYER: ON|OFF|FREEZE | XREF_PAVE: LAYER: ON|OFF|FREEZE | XREF_PAVE_CHKOUT: LAYER: ON|OFF|FREEZE | XREF_PAVE_CHKOUT_PDF_FI

FRA-71-19.10

MODEL: Phase 2A - Plan 2 PAPERSIZE: ISO A1 (841.0 x 594.1) DATE: 3/31/2026 TIME: 11:05:49 AM FSTORY: OHDOT_ITSP_V1.pltcfg FSTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCIVIL3D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




TYPICAL SECTION - PHASE 3A STEP 3
STA. 1240+50 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 1A STEPS 2 & 4
## STA. 1232+00.00 TO STA. 1249+00.00


DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.72 TOTAL 618




NOTES:
1. REPLACE APPROACH SLABS (AND SLEEPER SLAB/ASPHALT PAVEMENT) IN STEP 2.
2. INSTALL SDC OVERLAY IN STEP 4.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 1A STEPS 2 & 4
# STA. 1249+00.00 TO STA. 1266+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.73 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1A - Plan 3 PAPERSIZE: ISO A3 (+) DATE: 3/31/2026 TIME: 11:05:54 AM FITDWG: ON DEPT_PDF_FI: off DEPT_PDF_FI: off DEPT_PDF_FI: off




TYPICAL SECTION - PHASE 1A STEPS 2 & 4
STA. 1276+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 1A STEPS 2 & 4
# STA. 1266+00.00 TO STA. 1283+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.74 TOTAL: 618

FRA-71-19.10

MODEL: Phase 2A - Plan # PAPERSIZE: ISO A3 (in) | DATE: 3/31/2026 TIME: 11:05:59 AM FSTORY: CHSOT_ITSP_1+1#SB_FSHTEL: CHSOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHSOTTCMD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Ohio\Columbus\Highway\109164 - FRA-71-19.10 Cooke Rd Interchange\Design\Roadway\Plan Sheets\Phase 2A\FRA-71-19.10 - Phase 2A - Plan # 1.dgn




TYPICAL SECTION - PHASE 1A STEPS 2 & 4
STA. 1285+00 IR-71

NOTE: SEE SHEET P.58 FOR PHASE 1A ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 1A STEPS 2 & 4
# STA. 1283+00.00 TO STA. 1300+00.00

FRA-71-19.10

MODEL: Phase 2A - Plan | PAPERSIZE: ISO A3 (in) | DATE: 3/31/2026 TIME: 12:39:23 PM | FILEDIR: C:\MDOT_CHDOT_PDF_Fi-ahSQ_FEWTEL_CHDOT_Plan.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCLIO2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE: Phase 2A - Plan | REFERENCES: ISO A3 (in) | DATE: 3/31/2026 TIME: 12:39:23 PM | FILEDIR: C:\MDOT_CHDOT_PDF_Fi-ahSQ_FEWTEL_CHDOT_Plan.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCLIO2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25

DESIGN AGENCY: Jacobs
DESIGNED: SRH
REVIEWED: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.75 TOTAL: 618




TYPICAL SECTION - PHASE 1B STEPS 1 & 3
STA. 1221+00 IR-71

NOTE: SEE SHEET P.49 FOR PHASE 1B NB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 1B STEPS 1 & 3
# STA. 1215+00.00 TO STA. 1232+00.00

FRA-71-19.10

MODEL: Phase 1A - Plan | PAPERSIZE: ANSI-D | DATE: 3/31/2026 TIME: 11:06:15 AM | FSTDIV: OHDOT_ITSP_V1.prfdg | FSTITEL: OHDOT_Pen.tbl | USER: Chris.Lawrence1@jacobs.com | WORKSPACE: OHDOTCAD2 | WORKSET: 109164 | PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\109164\Highway\Roadway\Plans\MOT\Phase 1\FRA-71-19.10_MOT_Phase 1B Steps 1 & 3.dgn

DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.76 TOTAL: 618




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 1B STEPS 1 & 3
# STA. 1232+00.00 TO STA. 1249+00.00

FRA-71-19.10

MODEL: Phase 1A - Plan 2 PAPERSIZE: 864.00x1 DATE: 3/31/2026 TIME: 11:06:35 AM FSTORY: CHDOT_PDF_V-1.dmdg FSTITEL: CHDOT_Pln.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\FRA\71\109164\Highway\Roadway\Design\Phase 1\Phase 1B\Steps 1 & 3\Plan\FRA-71-19.10_MOT_Phase 1B_Steps 1 & 3.dgn

DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.77 TOTAL 618




TYPICAL SECTION - PHASE 1B STEPS 1 & 3
STA. 1255+50 IR-71

NOTE: APPROACH SLABS AND FULL DEPTH ASPHALT TO BE REPLACED DURING STEP 1. SDC OVERLAY TO BE INSTALLED DURING STEP 3.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 1B STEPS 1 & 3
# STA. 1249+00.00 TO STA. 1266+00.00


FRA-71-19.10


MODEL: Phase 1A - Plan 3 PAPERSIZE: ISO A3 (L) DATE: 3/31/2026 TIME: 11:06:21 AM FSTDIV: CMDOT_PDF_V1.pltcfg FSTBL: CMDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CMDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\FRA\71\109164\Civil\Roadway\MOT\Phase 1\FRA-71-19.10_MOT_Phase 1B_Steps 1 & 3.dgn


DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.78 TOTAL 618

FRA-71-19.10
MODEL: Phase 1A - Plan • PAPERSIZE: ISO A1 (in) | DATE: 3/31/2026 TIME: 11:00:23 AM FSTDIV: CHSDT_ITP_U-1.dgnlib FSTITEL: CHSDT_Pln.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHSDTCIVD WORKSET: DISTAR PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE: Phase 1A - Plan • PAPERSIZE: ISO A1 (in) | DATE: 3/31/2026 TIME: 11:00:23 AM FSTDIV: CHSDT_ITP_U-1.dgnlib FSTITEL: CHSDT_Pln.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHSDTCIVD WORKSET: DISTAR PRODUCT: OpenRoadsDesigner 24.00.02.25




TYPICAL SECTION - PHASE 1B STEPS 1 & 3
STA. 1275+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND


- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 1B STEPS 1 & 3
# STA. 1266+00.00 TO STA. 1283+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.79 TOTAL: 618




TYPICAL SECTION - PHASE 1B STEPS 2 & 4
STA. 1221+00 IR-71

NOTE: SEE SHEET P.49 FOR PHASE 1B NB ADVANCED SIGNING PLAN

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 1B STEPS 2 & 4
# STA. 1215+00.00 TO STA. 1232+00.00

FRA-71-19.10


MODEL: Phase 1A - Plan | PAPERSIZE: ANSI A4 (in) | DATE: 3/31/2026 TIME: 11:06:55 AM FSTORY: CHDOT_ITSP_V1.prtSTB; FSTBL: CHDOT_Print.stb USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCIVD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\Projects\FRA\71\109164\Design\Roadway\Plans\MOT\FRA-71-19.10_MOT_Phase 1B Steps 2 & 4.dgn


DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.80 TOTAL: 618




TYPICAL SECTION - PHASE 1B STEPS 2 & 4
STA. 1247+50 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 1B STEPS 2 & 4
# STA. 1232+00.00 TO STA. 1249+00.00

FRA-71-19.10


MODEL: Phase 1A - Plan 2 PAPERSIZE: ISO A3 (L) DATE: 3/31/2026 TIME: 11:06:45 AM FSTDIR: CHDOT_PDF_V1-pltcfg FSTFIL: CHDOT_Pen.stb USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25



DESIGN AGENCY
Jacobs


DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.81 TOTAL 618




NOTE: APPROACH SLABS AND FULL DEPTH ASPHALT TO BE REPLACED DURING STEP 2. SDC OVERLAY TO BE INSTALLED DURING STEP 4.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 1B STEPS 2 & 4
## STA. 1249+00.00 TO STA. 1266+00.00

DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P-82
TOTAL: 618

FRA-71-19.10

MODEL: Phase 2A - Plan | PAPERSIZE: ISO A3 (ID) | DATE: 3/31/2026 TIME: 11:06:41 AM | FILTER: ON|OFF_ON|OFF_ON | LAYER: ON|OFF_ON|OFF_ON|OFF_




NOTE: SEE SHEET P.50 FOR PHASE 2 NB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 2
# STA. 1248+00.00 TO STA. 1265+00.00

DESIGN AGENCY
Jacobs

DESIGNER
SRH


REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.83 TOTAL 618


FRA-71-19.10

MODEL: Phase 2 Sheet 1 PAPERSIZE: ISO A3 DATE: 3/31/2026 TIME: 11:06:57 AM USER: CHRISTOPHER_H LAYER: PAVEMENTMARKING,PAVEMENTMARKING_TEMP,PAVEMENTMARKING_TEMP_TEXT,PAVEMENTMARKING_TEXT,PAVEMENTMARKING_TEXT_TEMP




CURVE DATA - 1
Δ = 04°27'52" LT
Dc = 01°00'00"
R = 5,729.58'
T = 223.33'
L = 446.44'
E = 4.35'

CURVE DATA - 2
Δ = 05°21'39" RT
Dc = 01°00'00"
R = 5,729.58'
T = 268.23'
L = 536.08'
E = 6.28'




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

MAINTENANCE OF TRAFFIC - PHASE 2
STA. 1265+00.00 TO STA. 1282+00.00

FRA-71-19.10


MODEL: Phase 2 Sheet 2 PAYPRDES: 66x34.0in | DATE: 3/31/2026 TIME: 11:07:03 AM FCDW: CHDOT_PDF_V-14PSB_PSTBL: CHDOT_Print.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCAD2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\109164\Roadway\Traffic\Work Zone\FRA-71-19.10_MOT_PH2_Sht2.dgn


DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.84 TOTAL 618

MODEL: Phase 2 Sheet 3 PAPERSIZE: ANSI A4 (in) DATE: 3/31/2026 TIME: 11:07:54 AM PLTDRV: CHIDOT_PDF_V-1.pltdg PLTBTBL: CHIDOT_Print.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHIDOTCLI02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Fra\71\109164\Highway\Traffic\Maintenance of Traffic\Phase 2\FRA-71-19.10 MOT Phase 2 Sheet 3.dgn

W1-H16-36
STA. 1287+11
STA. 1288+11
STA. 1289+11
STA. 1290+11
A

Cooke Rd
N Broadway
Weber Rd
1¼
1¼
1¼
TO REMAIN

350' SHIFT TAPER
+61
+11

WORK ZONE SPEED LIMIT AHEAD
Digital Speed Limit (DSL) Sign Assembly STA. 1295+11

WORK ZONE EDGE LINE
WORK ZONE CHANNELIZING LINE
MATCH PAVEMENT MARKINGS FROM PHASE 1
SEE TRAFFIC CONTROL PLANS PAVEMENT MARKINGS DETAILS

MATCH LINE STA. 1282+00
1282
1283
1284
1285
1286
1287
1288
1289
1290
1291
1292
1293
1294
1295
1296
1297
1298
12

IR 71 SB
℄ CONST. I-71
IR 71 NB
+11
+11
18'± 12'± 12'±
+00
+00
+00
+00

71 NB TO MORSE RD
4298
42
℄ CONST. MORSE RD RAMP C


Morse Rd
2
¼
4
TO REMAIN

Morse Rd
Sinclair Rd
TO REMAIN
EXIT 116

NOTE: SEE SHEET P.59 FOR PHASE 2 SB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT





TYPICAL SECTION - PHASE 2
STA. 1285+00 IR-71


HORIZONTAL SCALE IN FEET
0 15 30 60

MAINTENANCE OF TRAFFIC - PHASE 2
STA. 1282+00.00 TO 1299+00.00

DESIGN AGENCY
Jacobs
DESIGNER
SRH
REVIEWER
BAP 03/20/26
PROJECT ID
109164
SHEET P.85
TOTAL 618


W1-H16-36
STA. 1426+30
STA. 1427+30
STA. 1428+30
STA. 1429+30
STA. 1430+30
STA. 1431+30
EXIT 117
TO REMAIN
EXIT 117
Dublin-Granville Rd
EXIT ONLY
TO REMAIN
EXIT 116
Sinclair Rd
1 MILE
TO REMAIN
℄ CONST. SR 161 RAMP C
71 SB TO S.R. 161
520' SHIFT TAPER
MATCH EXISTING PAVEMENT MARKINGS
WORK ZONE CHANNELIZING LINE
IR 71 SB
℄ CONST. I-71
IR 71 NB
MATCH EXISTING PAVEMENT MARKINGS STA. 1423+30
TO BEHLMAN
MATCH EXISTING PAVEMENT MARKINGS
WORK ZONE EDGE LINE
S.R. 161 TO 71 NB
℄ CONST. SR 161 RAMP D
WORK ZONE CHANNELIZING LINE
WORK ZONE EDGE LINE
MATCH LINE STA. 1433+00
1086' SHIFT TAPER
200' SHIFT TAPER
W24-1(48)-48
STA. 1417+00
Digital Speed Limit (DSL) Sign Assembly
STA. 1421+30
W20-1-48
R11-1(48)-24
℄ CONST. S.R. 161
℄ IR-71
EX WE
EX LL
EX YE
12'±
15'±
17.8'±
TYPICAL SECTION - PHASE 2
STA. 1423+00 IR-71
NOTE: SEE SHEET P.57 FOR PHASE 2 NB ADVANCED SIGNING PLAN.
DRUM SPACING CHART
TANGENT 120' c/c
TAPER 60' c/c
RAMP DELINEATION 20' c/c
LEGEND
PHASE WORK ZONE
DRUMS
PORTABLE BARRIER
TEMPORARY PAVEMENT
IMPACT ATTENUATOR
DIRECTION OF TRAVEL
TYPE III BARRICADE
TEMPORARY SIGN SUPPORT
HORIZONTAL SCALE IN FEET
0 15 30 60
MAINTENANCE OF TRAFFIC - PHASE 2
STA. 1416+00.00 TO STA. 1433+00.00
DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.86
TOTAL 618
FRA-71-19.10




TYPICAL SECTION - PHASE 2
STA. 1444+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

MAINTENANCE OF TRAFFIC - PHASE 2
STA. 1433+00.00 TO STA.1450+00.00

FRA-71-19.10

MODEL: Phase 2 Sheet1 PAINTBOOTS: RGB.48 | DATE: 3/31/2026 TIME: 11:03:10 AM FSTORY: CHDOT_ITSP_V1.prf FSTYLE: CHDOT_Print.stb USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: C:\Users\chris.lawrence1\Jacobs\Desktop\Projects\FRA-71-19.10\Design\Roadway\Plan Sheets\FRA-71-19.10 MOT Phase 2.dgn


DESIGN AGENCY
Jacobs


DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.87 TOTAL 618




TYPICAL SECTION - PHASE 2
STA. 1454+00 IR-71

NOTE: SEE SHEET P.67 FOR PHASE 2 SB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 2
# STA. 1450+00.00 TO STA.1467+00.00

FRA-71-19.10

MODEL: Phase 2 Sheet1 PAPERSIZE: ANSI A4 (in) DATE: 3/31/2026 TIME: 11:07:11 AM FILTERS: ON/OFF_ITEM_IN LAYER_FILTERS: ON/OFF_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CH2OPTC02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO BENTLEY SYSTEMS LICENSE AGREEMENT. PROHIBITED ELECTRONIC REDISTRIBUTION AND/OR MODIFICATION.

DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.88 TOTAL 618







TYPICAL SECTION - PHASE 3A STEP 1
STA. 1316+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 1
# STA. 1310+00.00 TO STA. 1327+00.00

FRA-71-19.10

MODEL: Phase 3A Step 1 - Sheet 1 MARKER: 66x48 (in) UNIT: 37/120IN TIME: 1:15:07 PM PITSIRI ORNDIT .PSI_A.ctb PENTBL ORNDIT .PEN ISE USER: Chris.Lawrence@jacobs.com WORKSPACE: ONDOTCVDS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\109164\Highway\Roadway\Sheets\FRA-71-19.10_MOT_Phase 3A Step 1 - Sheet 1.dgn

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.89 TOTAL: 618




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60'c/c |
| RAMP DELINEATION | 20'c/c |

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 1
# STA. 1327+00.00 TO STA. 1344+00.00

DESIGN AGENCY
Jacobs

DESIGNER
SRH


REVIEWER
BAP 03/20/26


PROJECT ID
109164

SHEET P.90 TOTAL 618

FRA-71-19.10

MODEL: Phase 3A Step 1 - Sheet 2 WARNING: 66x48 (in.) DATE: 3/31/2026 TIME: 1:51:13 PM PITSRV ORHDOT.PSF_F.ctb FNTBL ORHDOT.fnt USER: Chris.Lawrence@jacobs.com WORKSPACE: OHDOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\109164\Highway\Plan and Profile\Phase 3A\Phase 3A Step 1\FRA-71-19.10_MOT_Phase 3A Step 1 - Sheet 2.dgn




TYPICAL SECTION - PHASE 3A STEP 1
STA. 1352+00 IR-71

NOTE: INSTALL THE OUTSIDE LANE CLOSURE PER SCD MT-95.30 USING A 780' MERGE TAPER FROM STA. 1369+40 TO 1377+20. INCORPORATE A WORK ZONE SPEED ZONE STARTING NORTH OF STA. 1377+20 USING DIGITAL SPEED LIMIT(DSL) SIGN ASSEMBLIES PER SCD MT-104.10.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'-c/c |
| TAPER | 60'-c/c |
| RAMP DELINEATION | 20'-c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 1
# STA. 1344+00.00 TO STA. 1361+00.00


FRA-71-19.10


MODEL: Phase 3A Step 1 - Sheet 9 MARKER: 66x48 (in) UNIT: 37/12ISO TIME: 1:15:14 PM PITSMY ON:DOT .PSF_P.ptelg PENTBL ON:DOT .Pen.tbl USER: Chris.Lawrence@jacobs.com WORKINGS: ON:DOT/CVDS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\109164\Highway\Traffic\Maintenance of Traffic\Phase 3A\Step 1\FRA-71-19.10_MOT_Phase 3A Step 1 - Sheet 9.dgn

DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.91
TOTAL: 618


W1-H16-36
STA. 1304+43
STA. 1305+43
STA. 1306+43
A
905' SHIFT TAPER
19:1 PCB TAPER
RAMP CLOSED SEE SHEET P.38 FOR DETOUR PLAN
MORSE RD TO 71 SB CLOSED
MATCH EXISTING PAVEMENT MARKINGS STA. 1290+45
℄ CONST. MORSE RAMP D
IMPACT ATTENUATOR PER SDC MT-101.75
MATCH LINE STA. 1307+00
845' SHIFT TAPER
71 NB TO MORSE RD
℄ CONST. MORSE RAMP C
Morse Rd
Sinclair Rd
EXIT 116
TO REMAIN
TO REMOVE
TO REMAIN
TO REMAIN
TO REMAIN


W1-H16-36
STA. 1307+43
STA. 1308+43
STA. 1309+43
STA. 1310+43
STA. 1311+43
STA. 1312+43
℄ CONST. SINCLAIR
℄ CONST. SINCLAIR RAMP A
RAMP CLOSED SEE SHEET P.38 FOR DETOUR PLAN
℄ CONST. MORSE RAMP D
MORSE RD TO 71 SB CLOSED
MATCH EXISTING PAVEMENT MARKINGS STA. 1315+42
WORK ZONE EDGE LINE
WORK ZONE CHANNELIZING LINE
SINCLAIR RD TO 71 SB CLOSED
℄ CONST. SINCLAIR RAMP E
71 SB TO SINCLAIR RD
W24.1a(-48 STA. 1322+43
MATCH LINE STA. 1307+00
MATCH LINE STA. 1324+00
845' SHIFT TAPER
℄ CONST. MORSE RD
MORSE RD TO 71 NB
℄ CONST. MORSE RAMP B
℄ CONST. MORSE RAMP C
71 NB TO MORSE RD
SOUTH Cincinnati TO REMAIN
NORTH Cleveland LEFT ONLY TO REMAIN
SOUTH Sinclair Rd RIGHT ONLY TO REMAIN
NORTH Cleveland TO REMAIN
NORTH Cleveland TO REMAIN
TO REMAIN
TO REMAIN




TYPICAL SECTION - PHASE 3A STEP 2
STA. 1337+50 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

**LEGEND**

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 2
# STA. 1324+00.00 TO STA. 1341+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.94 TOTAL: 618

FRA-71-19.10

MODEL: Phase 3A Step 2 - Sheet 9 MARKERS 66x44 (in.) DATE: 3/11/2026 TIME: 1:21:16 PM PLOTBY: CHRISTOPHER JAY, P.E. (PE/ME) CHRISTOPHER.JAY@JACOBS.COM WORKSPACE: CHRISTOPHER JAY, P.E. (PE/ME) CHRISTOPHER.JAY@JACOBS.COM WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL CONTENTS © 2026 JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES. THIS DRAWING AND ITS CONTENTS ARE THE PROPERTY OF JACOBS AND SHALL NOT BE REPRODUCED OR PUBLISHED WITHOUT THE EXPRESS WRITTEN CONSENT OF JACOBS.




TYPICAL SECTION - PHASE 3A STEP 2
STA. 1344+00 IR-71

NOTE: SEE SHEET P.66 FOR PHASE 3A STEP 2 SB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

MAINTENANCE OF TRAFFIC - PHASE 3A STEP 2
STA. 1341+00.00 TO STA. 1358+00.00

DESIGN AGENCY
Jacobs

DESIGNER
SRH


REVIEWER
BAP 03/20/26

PROJECT ID
109164


SHEET P.55 TOTAL 618

FRA-71-19.10

MODEL: Phase 3A Step 2 - Sheet 4 MARKERS: 66x48 (in.) DATE: 3/11/2026 TIME: 1:15:16 PM PLOTBY: CHRISTOPHER JAMES PAYNEL CHKDPT: Pen-tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CHKDOTCVDS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE: I:\Projects\Columbus\Fra-71\Design\Roadway\Phase 3\Phase 3A\Step 2\Sheets\Fra-71-Ph3A-Step2-Sht4.dgn




*CURVE DATA - 1*
*Δ = 01°49'36" RT*
*Dc = 00°29'00"*
*R = 11,854.31'*
*T = 188.98'*
*L = 377.93'*
*E = 1.51'*




*TYPICAL SECTION - PHASE 3A STEP 3*
*STA. 1261+00 IR-71*

*NOTE: SEE SHEET P.51 FOR PHASE 3A ADVANCED SIGNING PLAN.*

| DRUM SPACING CHART | |
|---|---|
| *TANGENT* | *120' c/c* |
| *TAPER* | *60' c/c* |
| *RAMP DELINEATION* | *20' c/c* |

*LEGEND*

- *PHASE WORK ZONE*
- *DRUMS*
- *PORTABLE BARRIER*
- *TEMPORARY PAVEMENT*
- *IMPACT ATTENUATOR*
- *DIRECTION OF TRAVEL*
- *TYPE III BARRICADE*
- *TEMPORARY SIGN SUPPORT*

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
# STA. 1249+00.00 TO STA. 1266+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.96 TOTAL: 618

FRA-71-19.10

MODEL: Phase 3A - Plan 3 PAPERSIZE: ISO A3 (L) DATE: 3/31/2026 TIME: 12:51:12 PM FILENAME: C:\TEMP_CHEOPT_PDF_P-Lot50_TEMP\TEL_CHEOPT_Plan.tbl USER: Chris.Lawmaster@jacobs.com WORKSPACE: CHEOPTCAD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE: C:\Users\chris.lawmaster\Jacobs\Desktop\Projects\109164_FRA-71-19.10\Cad\Sheets\Phase 3\Phase 3A\Plan 3\Phase 3A - Plan 3.dgn





CURVE DATA - 1
Δ = 01°48'36" LT
Dc = 00°29'00"
R = 11,854.31'
T = 187.26'
L = 374.48'
E = 1.48'

CURVE DATA - 2
Δ = 05°27'00" RT
Dc = 01°00'00"
R = 5,729.58'
T = 272.71'
L = 545.01'
E = 6.49'

CURVE DATA - 3
P.I. = STA. 9271+17.95
Δ = 06°09'08" RT
Dc = 01°50'00"
R = 3,125.23'
T = 167.95'
L = 335.58'
E = 4.51'

CURVE DATA - 4
P.I. = STA. 9274+53.53
Δ = 06°09'08" LT
Dc = 01°50'00"
R = 3,125.23'
T = 167.95'
L = 335.58'
E = 4.51'




TYPICAL SECTION - PHASE 3A STEP 3
STA. 1276+50 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
# STA. 1266+00.00 TO STA. 1283+00.00

FRA-71-19.10


MODEL: Phase 3A - Plan # PAVEMENT MARKING # SHEET: 3/31/2026 TIME: 12:53:57 PM FILTOW: CHRIST_PDF_U: pdf58_PENTBL: CHRIST_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTTC02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Indiana\109164\Roadway\Design\Microstation\Plan Sheets\Phase 3A\Phase 3A Step 3\FRA-71-19.10 Phase 3A Step 3 MOT.dgn

DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P-97
TOTAL 618


FRA-71-19.10

MODEL: Phase 3A - Plan 5 PAREDES: RM140.rvt DATE: 3/31/2026A TIME: 12:51:58 PM FITDW: DWDT_PDF_V1.pltCB_FITDTEL: DWDT_Print.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWDOTCLOD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE: Phase 3A - Plan 5 PAREDES: RM140.rvt DATE: 3/31/2026A TIME: 12:51:58 PM FITDW: DWDT_PDF_V1.pltCB_FITDTEL: DWDT_Print.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWDOTCLOD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25

W1-H16-36
STA. 1283+00
STA. 1284+00
STA. 1285+00
STA. 1286+00
STA. 1287+00
STA. 1288+00
STA. 1289+00
STA. 1290+00
STA. 1291+00
STA. 1292+00




CURVE DATA - 1
Δ = 04°41'40" RT
Dc = 01°30'00"
R = 3,819.72'
T = 156.57'
L = 312.97'
E = 3.21'




NOTE:
COMPLETE REMAINING VARIABLE DEPTH MILLING AND INTERMEDIATE COURSE WHILE TRANSITIONING FROM PHASE 3A TO PHASE 3B STEP 1. SEE SEQUENCE OF OPERATIONS FOR DETAILS.


| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT
- VARIABLE DEPTH MILLING DURING PHASE TRANSITION

HORIZONTAL SCALE IN FEET
0 15 30 60

MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
STA. 1283+00.00 TO STA. 1300+00.00

DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.98 TOTAL 618




*CURVE DATA - 1*
Δ = 04°41'40" RT
Dc = 01°30'00"
R = 3,819.72'
T = 156.57'
L = 312.97'
E = 3.21'

*CURVE DATA - 2*
Δ = 16°24'56" RT
Dc = 03°00'00"
R = 1,909.86'
T = 275.48'
L = 547.19'
E = 19.77'

*CURVE DATA - 3*
Δ = 04°06'55" LT
Dc = 00°45'00"
R = 7,639.44'
T = 274.47'
L = 548.70'
E = 4.93'




*TYPICAL SECTION - PHASE 3A STEP 3*
*STA. 1306+00 IR-71*

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
# STA. 1300+00.00 TO STA. 1317+00.00

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.99 TOTAL 618

FRA-71-19.10

MODEL: Phase 3A - Plan.dgn PREFACES: 4to14.dgn | DATE: 3/31/2026 TIME: 12:55:59 PM PSTDRV: CHROT_PDF_V1.prtSS PSTBL: CHROT_Print.stb USER: Chris.Lawmaster@jacobs.com WORKSPACE: CHROTT0202 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




FRA-71-19.10

MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
STA. 1317+00.00 TO STA. 1334+00.00

HORIZONTAL SCALE IN FEET
0 15 30 60


DESIGN AGENCY
Jacobs


DESIGNED SRH
REVIEWED BAP 03/20/26
PROJECT ID 109164
SHEET P.100 TOTAL 618

MODEL: Phase 3A - Plan | PAPERSIZE: ANSI-A4 | DATE: 3/31/2026 TIME: 12:20:55 PM | FCDIR: C:\MDOT_CHDOT_PDF_V1-pe\dgn_FCNTRL\ | CHDOT_Plot.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: C:\MDOT\CHDOT\ WORKSET: 109164_PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DRAWINGS ARE THE PROPERTY OF THE CONNECTICUT DEPARTMENT OF TRANSPORTATION. THEY ARE NOT TO BE USED FOR ANY PURPOSE WHATSOEVER WITHOUT THE WRITTEN PERMISSION OF THE CONNECTICUT DEPARTMENT OF TRANSPORTATION.

FRA-71-19.10

MODEL: Phase 3A - Place 3 PAVEMENT - 09x14.dgn | DATE: 3/31/2026 TIME: 12:53:03 PM | PLTDRV: CHDOT_PDF_V1.ctb|S_PSHTBL: CHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALIGNMENT: Phase 3A - Place 3 PAVEMENT - 09x14.dgn | DATE: 3/31/2026 TIME: 12:53:03 PM | PLTDRV: CHDOT_PDF_V1.ctb|S_PSHTBL: CHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




TYPICAL SECTION - PHASE 3A STEP 3
STA. 1339+00 IR-71

NOTE:
COMPLETE REMAINING VARIABLE DEPTH MILLING AND INTERMEDIATE COURSE WHILE TRANSITIONING FROM PHASE 3A TO PHASE 3B STEP 1. SEE SEQUENCE OF OPERATIONS FOR DETAILS.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT
- VARIABLE DEPTH MILLING DURING PHASE TRANSITION

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
# STA. 1334+00.00 TO STA. 1351+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.101 TOTAL: 618

FRA-71-19.10

MODEL: Phase 3A - Phase 3 PAPERSIZE: ANSI-B (in.) DATE: 3/31/2026 TIME: 12:33:33 PM PSTORM: CHKDP_PSP_V-Lane.tbl PSHTBL: CHKDP_Pmt.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHKDOTC102 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE XREFS: C:\Projects\Fra-71-19.10\Design\Roadway\Phase 3\Phase 3A\Step 3\Fra-71-19.10_Phase 3A_Step 3_Plan.dgn




TYPICAL SECTION - PHASE 3A STEP 3
STA. 1352+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND


- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60

MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
STA. 1351+00.00 TO STA. 1368+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.102 TOTAL: 618




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

**LEGEND**

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
# STA. 1368+00.00 TO STA. 1385+00.00

FRA-71-19.10


MODEL: Phase 3A - Plan 10 MARKERS: 66x34.0=1 DATE: 3/31/2026 TIME: 12:15:04 PM STORY: OHIOT; PSF_1-24x36_PENTEL OHIOT; Plot Bill: USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHIOTSIG02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\109164\Highway\Roadway\Maintenance of Traffic\Phase 3\Phase 3A\Step 3\FRA-71-19.10_MOT_Phase 3A_Step 3.dgn

DESIGN AGENCY
Jacobs

| DESIGNER | SRH |
|---|---|
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.103 |
| TOTAL | 618 |




*CURVE DATA - 1*
*Δ = 02°26'25" LT*
*Dc = 00°29'00"*
*R = 11,854.31'*
*T = 252.48'*
*L = 504.88'*
*E = 2.69'*




*TYPICAL SECTION - PHASE 3A STEP 3*
*STA. 1387+00 IR-71*

| DRUM SPACING CHART | |
|---|---|
| *TANGENT* | *120' c/c* |
| *TAPER* | *60' c/c* |
| *RAMP DELINEATION* | *20' c/c* |

*LEGEND*

- *PHASE WORK ZONE*
- *DRUMS*
- *PORTABLE BARRIER*
- *TEMPORARY PAVEMENT*
- *IMPACT ATTENUATOR*
- *DIRECTION OF TRAVEL*
- *TYPE III BARRICADE*
- *TEMPORARY SIGN SUPPORT*

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
# STA. 1385+00.00 TO STA. 1402+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.104 TOTAL: 618

FRA-71-19.10

MODEL: Phase 3A - Plan 11 MARKERS: 66x34.0+1 DATE: 3/31/2026 TIME: 12:15:05 PM SYSTEM: CHXDT_PSF_1-24NB_PENTBL_CHXDT_Plot.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHXDTSUS2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL INFORMATION. NOT FOR REDISTRIBUTION. LICENSED TO JACOBS.




HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
# STA. 1402+00.00 TO STA. 1419+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.105 TOTAL: 618

FRA-71-19.10


MODEL: Phase 3A - Plan 12 MARKERS: 66x34.0+1 DATE: 3/31/2026 TIME: 12:15:04 PM USER: CHRIST, JOSE J. (JJC6) PENTEL: CHRIST_PEN.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTOJJC6 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACCESS TO THIS DRAWING IS RESTRICTED TO AUTHORIZED USERS. ANY UNAUTHORIZED ACCESS, USE, OR DISTRIBUTION IS STRICTLY PROHIBITED.


19:1 PCB TAPER
EXIT 117
Dublin-Granville Rd
EXIT ONLY
TO REMAIN
EXIT 116
Sinclair Rd
Worthington
2 MILE
TO REMAIN
EXIT 117
TO REMAIN
WORK ZONE CHANNELIZING LINE
TEMP ALIGNMENT
END TEMP ALIGNMENT
STA. 4431+80.98, 7.95' LT (RAMP C)
BEGIN TEMP ALIGNMENT
STA. 1422+38.24, 51.50' LT (I-71)
WORK ZONE EDGE LINE
WORK ZONE LANE LINE
MATCH EXISTING PAVEMENT MARKINGS STA. 4421+19
71.58 TO S.R. 161
IR 71 SB
IR 71 NB
℄ CONST. I-71
℄ CONST. SR 161 RAMP C
℄ CONST. SR 161 RAMP D
S.R. 161 TO 71 NB
MATCH LINE STA. 1419+00
MATCH LINE STA. 1436+00
TO REMAIN
200' SHIFT TAPER
1086' SHIFT TAPER
225' SHIFT TAPER
STA. 1434+48
STA. 1434+00
STA. 4421+00
STA. 4419+66.66, 0.00' LT (RAMP C)
STA. 4421+58.75, 1.90' LT (RAMP C)
STA. 4423+27.62, 5.14' LT (RAMP C)
STA. 4425+58.52, 7.14' LT (RAMP C)
IR 71 SB
IR 71 NB
S.R. 161 TO 71 NB
S.R. 161
WORK ZONE EDGE LINE
WORK ZONE LANE LINE
WORK ZONE CHANNELIZING LINE
TEMP ALIGNMENT
MAINTAIN TRAFFIC PATTERN
MAINTAIN TRAFFIC PATTERN
ROAD CLOSED
R11-2-48
SPEED LIMIT
R2-1-60
SPEED LIMIT
R2-1-60
WORK ZONE EDGE LINE
WORK ZONE EDGE LINE
WORK ZONE EDGE LINE




CURVE DATA - 1
P.I. = STA. 9442+81.27
Δ = 04°48'36" LT
Dc = 01°50'00"
R = 3,125.23'
T = 131.26'
L = 262.37'
E = 2.76'

CURVE DATA - 2
P.I. = STA. 9446+33.27
Δ = 08°05'09" RT
Dc = 01°50'00"
R = 3,125.23'
T = 220.89'
L = 441.04'
E = 7.8'



TYPICAL SECTION - PHASE 3A STEP 3
STA. 1452+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
## STA. 1436+00.00 TO STA. 1453+00.00

DESIGN AGENCY
Jacobs

DESIGNER
SRH


REVIEWER
BAP 03/20/26


PROJECT ID
109164

SHEET P.107 TOTAL 618

FRA-71-19.10

MODEL: Phase 3A - Plan 14 MARKERS: 66x34.0=1 DATE: 3/31/2026 TIME: 12:31:21 PM SYSTEM: CHSOFT_PSF_C-249GB_PENTEL CHSOFT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHSOFTSVR2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: I:\Projects\Columbus\Interstate\FRA-71-19.10\Design\Roadway\Plan Sheets\Phase 3A\Phase 3A Plan 14.dgn




TYPICAL SECTION - PHASE 3A STEP 3
STA. 1469+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
# STA. 1453+00.00 TO STA. 1470+00.00


FRA-71-19.10


MODEL: Phase 3A - Plan 15 MARKERS: 66x34.0=1 DATE: 3/31/2026 TIME: 12:31:19 PM SYSTEM: CHRISTI_PSE_I-LARGE_PRINTER_CHRISTI_Plan.ctb USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTIS420 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\109164\Highway\Roadway\Design\Phase 3\Phase 3A\Step 3\Plan\FRA-71-19.10 MOT Phase 3A Step 3.dgn

DESIGN AGENCY
Jacobs
DESIGNER
SRH
REVIEWER
BAP 03/20/26
PROJECT ID
109164
SHEET P.108
TOTAL 618

FRA-71-19.10

MODEL: Phase 3A - Plan 16 MARKERS: 66x34.8in | DATE: 3/31/2026 TIME: 12:31:14 PM SYSTEM: CHRISTI_PSR_E-LARGE_PRINTER, CHRISTI_Plan Set USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTIS420 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




TYPICAL SECTION - PHASE 3A STEP 3
STA. 1475+00 IR-71

NOTE: SEE SHEET P.60 FOR PHASE 3A SB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 3A STEP 3
# STA. 1470+00.00 TO STA. 1487+00.00


DESIGN AGENCY
Jacobs


DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.109 TOTAL 618




TYPICAL SECTION - PHASE 3B STEP 1
STA. 1261+00 IR-71

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS
2. SEE SHEET P.51 FOR PHASE 3B ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1249+00.00 TO STA. 1266+00.00

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.110 TOTAL 618

FRA-71-19.10

MODEL: Phase 3B - Plan 3 PAPERSIZE: ANSI A4 (in) DATE: 3/31/2026 TIME: 11:08:45 AM PITDW: CHDOT_PDF_V-Letter.tbl PENTBL: CHDOT_Print.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCIVD2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE: C:\Projects\109164\Roadway\Design\Phase 3\FRA-71-19.10 Phase 3B Step 1 Plan.dgn
REFERENCE: C:\Projects\109164\Roadway\Design\Phase 3\FRA-71-19.10 Phase 3B Step 1 Plan.dgn

FRA-71-19.10
MODEL: Phase 3B - Plan 4 PAPERSIZE: ANSI A4 (H) DATE: 3/31/2026 TIME: 11:08:05 AM PITDW: CHDOT_PDF_V-1.dmp$ PITBTBL: CHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
DGN: C:\Projects\CHDOT\109164\Civil\Roadway\Plans\FRA-71-19.10_MOT_Phase 3B - Plan 4.dgn

W1-H16-36
STA. 1282+00
STA. 1283+00
A

EXIT 116
Cooke Rd
TO REMAIN

EXIT 114
E North St
Broadway
TO REMAIN

SEE PHASE 3A FOR I-71 SB PAVEMENT MARKING DETAILS

EXIT 113
GRAY HORSE BURIAL GROUNDS
TO REMAIN

SOUTH
71
TO REMAIN

1463' SHIFT TAPER

18:1 PCB TAPER

MATCH EXISTING PAVEMENT MARKINGS FROM PHASE 3A AT STA. 1278+00

WORK ZONE EDGE LINE

WORK ZONE CHANNELIZING LINE

71 SB TO COOKE RD

IR 71 SB

℄ CONST. I-71

IR 71 NB

COOKE RD TO 71 NB

SEE PHASE 3A STEP 3 FOR CROSSOVER DETAILS

MATCH LINE STA. 1266+00

MATCH LINE STA. 1283+00


1266 1267 1268 1269 1270 1271 1272 1273 1274 1275 1276 1277 1278 1279 1280 1281 1282 1283

+50 +70 +37 +41

11' 11' 5'1' 2'

NOS R11-2-48

CURVE DATA - 1
Δ = 04°26'48" LT
Dc = 01°00'00"
R = 5,729.58'
T = 222.44'
L = 444.66'
E = 4.32'




TYPICAL SECTION - PHASE 3B STEP 1
STA. 1276+50 IR-71

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
STA. 1266+00.00 TO STA. 1283+00.00

DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.111 TOTAL 618

FRA-71-19.10

MODEL: Phase 3B - Plan 1 PAPERSIZE: 864.00 x 1 DATE: 3/31/2026 TIME: 11:08:3 AM PSTDRV: CHDOT_PDF_V-1.ctb PSTBL: CHDOT_Print.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCAD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25

XREFS: Phase 3B - Plan 1 PATH: C:\Projects\109164\Roadway\Design\Phase 3\FRA-71-19.10 Maintenance of Traffic - Phase 3B Step 1.dgn

W1-H16-36

STA. 1284+00
STA. 1285+00
STA. 1286+00
STA. 1287+00
STA. 1288+00
STA. 1289+00
STA. 1290+00
STA. 1291+00
STA. 1292+00
STA. 1293+00
STA. 1294+00
STA. 1295+00
STA. 1296+00

Ⓐ

1463' SHIFT TAPER

Cooke Rd
No Exit Roadway
Weber Rd
TO REMAIN

WORK ZONE EDGE LINE

SPEED LIMIT 55

PCMS

Distance Speed Limit (DSL) Sign Assembly
STA. 1288+50

+73
56.2' LT.

+50

+00
38.2' LT.

WORK ZONE CHANNELIZING LINE

IR 71 SB

MATCH LINE STA. 1283+00

MATCH LINE STA. 1300+00

1284 1285 1286 1287 1288 1289 1290 1291 1292 1293 1294 1295 1296 1297 1298 1299

11' 11' 2.5' 8.5' 3'

℄ CONST. I-71

IR 71 NB

4298 4299 71 NB TO MORSE RD

℄ CONST.
MORSE RD RAMP C

℄ IR-71

WZ YE WZ WE WZ CH WZ YE WZ WE WZ YE WZ LL WZ LL WZ OL WZ WE

2.5' 11' 11' 8.5' 12.5' 11' 6' 11' 11' 11' 11'

6.7'± 2' 2' 3'

WORK ZONE
CONSTRUCTED IN PHASE 3A

TYPICAL SECTION - PHASE 3B STEP 1
STA. 1296+00 IR-71

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND


- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1283+00.00 TO STA. 1300+00.00

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.112 TOTAL 618







| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

**LEGEND**

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1300+00.00 TO STA. 1317+00.00

DESIGN AGENCY
Jacobs

DESIGNED SRH
REVIEWED BAP 03/20/26
PROJECT ID 109164
SHEET P.113 TOTAL 618

FRA-71-19.10

MODEL: Phase 3B - Plan PREFIXES: RM-FA-SU-I DATE: 3/31/2026 TIME: 1:05:58 PM USERNAME: CHRISTOPHER.PAT.LEWIS DESIGN_PREF_FILE: DESIGN_PrefLib.dgnlib PENTBL: DESIGN_PenTab USER: ChrisLewis4321@gmail.com WORKSPACE: CHDOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USAGE IS GOVERNED BY THE OPEN DESIGN ALLIANCE MEMBER AGREEMENT OR OTHER APPLICABLE LICENSE AGREEMENT.




NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET: 0, 15, 30, 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1317+00.00 TO STA. 1334+00.00

DESIGN AGENCY: Jacobs


DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.114
TOTAL: 618

FRA-71-19.10

MODEL: Phase 3B - Plan 7 PAPERSIZE: ANSI A4 (in) DATE: 3/31/2026 TIME: 1:08:03 PM USERNAME: CHRISTOPHER.PAPE_FHWA@DOT.GOV DGN: Z:\Projects\FRA-71-19.10\Design\Roadway\Maintenance of Traffic\Phase 3B\Step 1\FRA-71-19.10_MOT_Phase3B_Step1.dgn




CURVE DATA - 1
Δ = 02°10'37" LT
Dc = 00°29'00"
R = 11,854.31'
T = 225.23'
L = 450.40'
E = 2.14'




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1334+00.00 TO STA. 1351+00.00


DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.115 TOTAL 618

FRA-71-19.10

MODEL: Phase 3B - Phase 3B PAVEMENT MARKING.dgn | DATE: 3/31/2026 TIME: 11:08:55 AM | PLTDRV: CHDOT_PDF_V1.pltdrv PLTBTBL: CHDOT_Plot.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCE02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USAGE IS GOVERNED BY THE AGREEMENT FOR USE OF BENTLEY SYSTEMS SOFTWARE. Powered by ProjectWise Server 2022 Update 8.00




TYPICAL SECTION - PHASE 3B STEP 1
STA. 1352+00 IR-71

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1351+00.00 TO STA. 1368+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.116 TOTAL: 618

FRA-71-19.10

MODEL: Phase 3B - Plan PREPARED: 06x24.0 x 1 DATE: 3/31/2026 TIME: 11:08:56 AM FILENAME: P:\109164\Design\Roadway\Plans\Maintenance of Traffic\Phase 3B\109164_MOT_Phase3B_Step1.dgn USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOT2020 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




TYPICAL SECTION - PHASE 3B STEP 1
STA. 1376+00 IR-71

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1368+00.00 TO STA. 1385+00.00

DESIGN AGENCY
Jacobs


DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.117 TOTAL 618

FRA-71-19.10

MODEL: Phase 3B - Plan 10 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 11:08:57 AM USER: CHRIST, PSP, E-mail: PENTEL CHRIST, Pen tool: USER, Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTOL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: I:\Projects\Columbus\Interstate\FRA-71\19.10\Roadway\Plans\Maintenance of Traffic\Phase 3\FRA-71-19.10_MOT_Phase 3B_Step 1.dgn




*CURVE DATA - 1*
*Δ = 02°42'33" RT*
*Dc = 00°29'00"*
*R = 11,854.31'*
*T = 280.32'*
*L = 560.53'*
*E = 3.31'*




*TYPICAL SECTION - PHASE 3B STEP 1*
*STA. 1387+00 IR-71*

*NOTE:*
*1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS*

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*
- *PHASE WORK ZONE*
- *DRUMS*
- *PORTABLE BARRIER*
- *TEMPORARY PAVEMENT*
- *IMPACT ATTENUATOR*
- *DIRECTION OF TRAVEL*
- *TYPE III BARRICADE*
- *TEMPORARY SIGN SUPPORT*

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1385+00.00 TO STA. 1402+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.118 TOTAL: 618

FRA-71-19.10

MODEL: Phase 3B - Plan 11 REFRESH: 04/24/26 DATE: 3/31/2026 TIME: 11:08:54 AM USER: CHROY, PDF: C:\JHSB_PENTEL CHROY_Plan.ctb USER: Chris.Lawrence1@jacobs.com WORKPACK: CHROY0426 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED AND ITS LICENSORS. PROTECTED IN THE U.S. AND INTERNATIONAL COPYRIGHT CONVENTIONS. PATENTS PENDING IN VARIOUS JURISDICTIONS.




CURVE DATA - 2
Δ = 02°42'33" LT
Dc = 00°29'00"
R = 11,854.31'
T = 280.32'
L = 560.54'
E = 3.31'




TYPICAL SECTION - PHASE 3B STEP 1
STA. 1412+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60'c/c |
| RAMP DELINEATION | 20'c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CINTROL DETAILS

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1402+00.00 TO STA. 1419+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.119 TOTAL: 618

FRA-71-19.10

MODEL: Phase 3B - Plan 12 REFRESH: 03/19/2026 DATE: 3/31/2026 TIME: 11:08:59 AM USER: CHRIST, JOE_C PENTEL: CHRIST_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKPACK: CHRISTOJ02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL INFORMATION. Last Edited by




TYPICAL SECTION - PHASE 3B STEP 1
STA. 1435+00 IR-71

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1419+00.00 TO STA. 1436+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.120 TOTAL: 618

FRA-71-19.10

MODEL: Phase 3B - Plan 13 REFRESHED: 04/24/26 DATE: 3/31/2026 TIME: 11:09:55 AM SYCOM1 CHRDT_PDF_C-24SQL PENTBL CHRDT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRDTDS4D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT (C) 2026 BENTLEY SYSTEMS, INCORPORATED. THIS FILE CONTAINS UNPUBLISHED PROPRIETARY INFORMATION.




NOTE:
1. SEE PHASE 3A STEP FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1436+00.00 TO STA. 1453+00.00

DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.121 TOTAL 618

FRA-71-19.10

MODEL: Phase 3B - Plan 14 MAPSHEET: 66x34 (in.) DATE: 3/31/2026 TIME: 11:09:04 AM USER: DWDT_PW_E-J-HALB_PENTEL DWDT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWDOTSHEET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. THIS FILE IS PROTECTED BY COPYRIGHT LAWS AND INTERNATIONAL TREATIES. UNAUTHORIZED REPRODUCTION, DISTRIBUTION, OR USE IS PROHIBITED.




TYPICAL SECTION - PHASE 3A STEP 3
STA. 1469+00 IR-71

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1453+00.00 TO STA. 1470+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.122 TOTAL: 618

FRA-71-19.10

MODEL: Phase 3B - Plan 15 MAPFOLDER: E:\e3d\Jobs\ SAVED: 3/31/2026 7:56:11 AM BY:CHRIS.CHRIST_PW: U:\e3d\$_PENTEL.CHRIST_PW.txt USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTOUD2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 JACOBS ENGINEERING GROUP INC. THIS DRAWING AND ITS CONTENTS ARE THE PROPERTY OF JACOBS AND SHALL NOT BE REPRODUCED OR PUBLISHED WITHOUT THE PRIOR WRITTEN CONSENT OF JACOBS.




TYPICAL SECTION - PHASE 3A STEP 3
STA. 1475+00 IR-71

NOTE:
1. SEE PHASE 3A STEP 3 FOR NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS
2. SEE SHEET P.60 FOR PHASE 3B ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 1
# STA. 1470+00.00 TO STA. 1487+00.00

FRA-71-19.10


MODEL: Phase 3B - Plan 1b PAPERSIZE: 66x34.0in | DATE: 3/31/2026 TIME: 11:09:04 AM SYCOM1 CMSDT_PW_E-J-HSR_PENTBL: CMSDT_Print.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CMSDTSUS2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE PATH: P:\Projects\Ohio\Columbus\FRA-71-19.10\Design\Roadway\Plan Sheets\Phase 3\Phase 3B\FRA-71-19.10 Phase 3B Plan 1b.dgn


DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.123 TOTAL 618




CURVE DATA - 1
Δ = 04°06'55" LT
Dc = 00°30'00"
R = 11,459.00'
T = 411.70'
L = 823.04'
E = 7.39'

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 2
# STA. 1283+00.00 TO STA. 1300+00.00


FRA-71-19.10


MODEL: Phase 3B - Plan 5 PAPERSIZE: ISO A3 (ID: ) DATE: 3/31/2026 TIME: 11:09:13 AM PSTDRV: CHDOT_PDF_V-Lam5g PSTBL: CHDOT_Print.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTC02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE: P:\Projects\FRA\FRA-71-19.10\Design\Roadway\Plan Sheets\Phase 3B\FRA-71-19.10 Phase 3B Plan 5.dgn


DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.124 TOTAL 618

FRA-71-19.10

MODEL: Phase 3B - Plan | PAPERSIZE: ANSI A4 (in) | DATE: 3/31/2026 TIME: 11:09:28 AM | FCDW: CHDOT_PDF_V-1.ctb | PSTBL: CHDOT_Print.ctb | USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO BENTLEY SUBSCRIPTION AGREEMENT PROHIBITED ANY UNAUTHORIZED REPRODUCTION, DISTRIBUTION OR PUBLICATION.







TYPICAL SECTION - PHASE 3B STEP 2
STA. 1306+00 IR-71

CURVE DATA - 1
Δ = 04°06'55" LT
Dc = 00°30'00"
R = 11,459.00'
T = 411.70'
L = 823.04'
E = 7.39'

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |


LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 2
# STA. 1300+00.00 TO STA. 1317+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.125 TOTAL: 618




*CURVE DATA - 1*
Δ = 32°04'18" LT
Dc = 19°45'00"
R = 290.11'
T = 83.38'
L = 162.39'
E = 11.75'

*SPIRAL DATA - 2*
Ls = 200.00'
Θs = 19°45'00"
LT = 134.17'
ST = 67.43'
x = 193.71'
y = 45.34'
k = 99.61'
p = 5.72'
C = 198.95'
C.B. = N47°48'43"E

*CURVE DATA - 3*
Δ = 01°04'09" RT
Dc = 00°45'00"
R = 7,639.44'
T = 71.28'
L = 142.56'
E = .33'

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET: 0, 15, 30, 60


# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 2
# STA. 1317+00.00 TO STA. 1334+00.00

FRA-71-19.10


MODEL: Phase 3B - Plan | PAPERSIZE: ANSI-D | DATE: 3/31/2026 7:56:41 AM | FITDWG: ORIENT_FOR_FITDWG_TRUE | FITDWG: ORIENT_FOR_FITDWG_FALSE | PENTBL: ORIENT_FOR_PLT.tbl | PENTBL: ORIENT_FOR_PLT.tbl | USER: Chris.Lawrence1@jacobs.com | WORKSPACE: CHIDOT1202 | WORKSET: 109164 | PRODUCT: OpenRoadsDesigner 24.00.02.25


DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.126 TOTAL: 618




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

**LEGEND**

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 3B STEP 2
## STA. 1334+00.00 TO STA. 1351+00.00


FRA-71-19.10


MODEL: Phase 3B - Plan B PAPERSIZE: ANSI A4 (in) DATE: 3/31/2026 TIME: 11:09:39 AM PITDIR: C:\MDOT_CHDOT_PDF_Fix\MDOT_CHDOT_Plots\ SAVE: Chris.Lawrence1@jacobs.com WORKSPACE: C:\MDOT\CHDOT\02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE PROJECT: C:\MDOT\CHDOT\02 PROJECTS\109164 - FRA-71-19.10 PHASE 3B\109164 - Maintenance of Traffic - Phase 3B.dgnlib


DESIGN AGENCY: Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.127 TOTAL: 618

FRA-71-19.10
MODEL: Phase 3A - Plan 14 MARKERS: 66x34.0=1 DATE: 3/31/2026 TIME: 11:09:43 AM PLTDRV: DWG.PLT PLTPEN: DWG.PLT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CHDOT15v02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\109164\Highway\Roadway\Maintenance and Protection of Traffic\Phase 3A\FRA-71-19.10 Phase 3A Plan 14.dgn




*NOTES:*
1. *AT THE DEPARTMENT'S DISCETION, THE CONTRAFLOW LANE MAY BE CLOSED FOR REASONS SUCH AS, BUT NOT LIMITED TO, AN EMERGENCY OR WEATHER EVENT. WHEN DIRECTED, CLOSE THE CONTRAFLOW LANE AS SHOWN.*
2. *INSTAL ADVANCE WARNING SIGNS FOR LANE CLOSURE PER SCD MT-95.30.*
3. *THE INTENT OF THIS DRAWING IS TO SHOW ONLY THOSE DEVICES NEEDED TO CLOSE THE CONTRAFLOW LANE. PHASE 3A/3B TRAFFIC CONTROL DEVICES NOT SHOWN FOR CLARITY.*


| *DRUM SPACING CHART* | |
|---|---|
| *TANGENT* | *120' c/c* |
| *TAPER* | *60' c/c* |
| *RAMP DELINEATION* | *20' c/c* |

*LEGEND*
- *PHASE WORK ZONE*
- *DRUMS*
- *PORTABLE BARRIER*
- *TEMPORARY PAVEMENT*
- *IMPACT ATTENUATOR*
- *DIRECTION OF TRAVEL*
- *TYPE III BARRICADE*
- *TEMPORARY SIGN SUPPORT*

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 3A/3B CONTRAFLOW LANE CLOSURE STA. 1436+00.00 TO STA. 1453+00.00

DESIGN AGENCY
Jacobs
DESIGNER
SRH
REVIEWER
BAP 03/20/26
PROJECT ID
109164
SHEET P.128 TOTAL 618




*NOTES:*
1. *AT THE DEPARTMENT'S DISCETION, THE CONTRAFLOW LANE MAY BE CLOSED FOR REASONS SUCH AS, BUT NOT LIMITED TO, AN EMERGENCY OR WEATHER EVENT. WHEN DIRECTED, CLOSE THE CONTRAFLOW LANE AS SHOWN.*
2. *INSTAL ADVANCE WARNING SIGNS FOR LANE CLOSURE PER SCD MT-95.30.*
3. *THE INTENT OF THIS DRAWING IS TO SHOW ONLY THOSE DEVICES NEEDED TO CLOSE THE CONTRAFLOW LANE. PHASE 3A/3B TRAFFIC CONTROL DEVICES NOT SHOWN FOR CLARITY.*

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 3A/3B CONTRAFLOW LANE CLOSURE
## STA. 1453+00.00 TO STA. 1470+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.129 | TOTAL: 618

FRA-71-19.10


MODEL: Phase 3A - Plan 15 MARKED: 6x3.5 in | DATE: 3/31/2026 TIME: 11:09:44 AM BY/DBY: DHOFF, PM: JF-LHSB, PENTBL: DHOFF, Pen Set USER: Chris.Lawrence@jacobs.com WORKSPACE: OHDOT/OHD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.12.25
FILENAME: K:\HNTB\Projects\Ohio\FRA\71\109164\Roadway\Traffic\Sheets\109164_TMP_MOT_PHASE_3A_3B_CONTRAFLOW_LANE_CLOSURE.dgn




NOTE: SEE SHEET P.52 FOR PHASE 4A ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4A
# STA. 1249+00.00 TO STA. 1266+00.00

FRA-71-19.10


MODEL: Phase 1A - Plan 3 PAPERSIZE: ISO A3 (+) DATE: 3/31/2026 TIME: 11:10:03 AM FILTERS: CHKDT_PDF_V1.prtbl, FSTITEL: CHKDT_Pmt.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHKDTCL002 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE: Phase 1A - Plan 3 PAPERSIZE: ISO A3 (+) DATE: 3/31/2026 TIME: 11:10:03 AM FILTERS: CHKDT_PDF_V1.prtbl, FSTITEL: CHKDT_Pmt.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHKDTCL002 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25

DESIGN AGENCY
Jacobs

| | |
|---|---|
| DESIGNER | SRH |
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.130 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Phase 1A - Plan # PAVEMENTS - RM-4A-0-1 DATE: 3/31/2026A TIME: 11:03:08 AM FSTORY: CHRDT_PDF_U=1.pltSB_FSHTEL: CHRDT_PHA.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRDTFL002 WORKSET: DEFAULT PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. THIS FILE IS LICENSED TO BE USED ONLY IN CONNECTION WITH BENTLEY PRODUCTS.




# MAINTENANCE OF TRAFFIC - PHASE 4A
# STA. 1266+00.00 TO STA. 1283+00.00

DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.131 TOTAL 618




NOTE:
COMPLETE REMAINING VARIABLE DEPTH MILLING AND INTERMEDIATE COURSE WHILE TRANSITIONING FROM PHASE 4A TO PHASE 4B STEP 1. SEE SEQUENCE OF OPERATIONS FOR DETAILS.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT
- VARIABLE DEPTH MILLING DURING PHASE TRANSITION


HORIZONTAL SCALE IN FEET: 0, 15, 30, 60


MAINTENANCE OF TRAFFIC - PHASE 4A
STA. 1283+00.00 TO STA. 1300+00.00


FRA-71-19.10

MODEL: Phase 3A - Plan | RWP/RDS: 06x14.0x1 | DATE: 3/31/2026 TIME: 11:03:09 AM FSTDIR: OHDOT_PDF_V1-pltSB_FSTBL.DWGT_Print.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCAD2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE: P:\Projects\FRA\71\109164\Roadway\Design\Phase 4A\MOT\FRA-71-19.10_MOT_Phase 4A.dgn

DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.132 | TOTAL: 618


MAINTENANCE OF TRAFFIC - PHASE 4A
STA. 1300+00.00 TO STA. 1317+00.00
HORIZONTAL SCALE IN FEET
0 15 30 60
MATCH LINE STA. 1300+00
MATCH LINE STA. 1317+00
260' SHIFT TAPER
250' SHIFT TAPER
200' SHIFT TAPER
600' MERGE TAPER
WORK ZONE CHANNELIZING LINE
WORK ZONE EDGE LINE
WORK ZONE LANE LINE
WORK ZONE DOTTED LINE
IR 71 SB
IR 71 NB
℄ CONST. I-71
MORSE RD TO 71 SB
71 NB TO MORSE RD
MORSE RD TO 71 NB
℄ CONST. MORSE RD RAMP D
℄ CONST. MORSE RD RAMP C
℄ CONST. MORSE RD RAMP B
℄ CONST. MORSE RD
℄ CONST. SINCLAIR
SEE TRAFFIC CONTROL PLAN
SEE PHASE 3A FOR PAVEMENT MARKING DETAILS
MATCH EXISTING PAVEMENT MARKINGS STA. 5312+51
MATCH PHASE 3A PAVEMENT MARKING STA. 1309+00
MATCH PHASE 3A PAVEMENT MARKING STA. 1317+00
TO REMAIN
TO BE REMOVED
W20.1-48
W3-4SH-48
W4-4SH-24
W4-4SH-48
41.25'
W20.1-48 SIDE WORK AHEAD
W20.1-48 ROAD WORK AHEAD
W3-4SH-48 ROAD WORK AHEAD
W4-4SH-24 LEFT LANE ENDS MERGE RIGHT
W4-4SH-48 LEFT LANE ENDS MERGE RIGHT
W3-4SH-48 ROAD WORK AHEAD
W20.1-48 SIDE WORK AHEAD
EXIT 116
WRONG WAY
DO NOT ENTER
SOUTH Cincinnati 71
NORTH Cleveland 71
LEFT ONLY
NORTH Cleveland 71
NORTH Cleveland 71
South Sinclair Rd
RIGHT ONLY
TO REMAIN
TO REMAIN
TO REMAIN


Sinclair Rd
Morse Rd
TO REMAIN
SEE TRAFFIC CONTROL PLAN
MATCH EXISTING PAVEMENT MARKINGS STA. 2321+25
WORK ZONE CHANNELIZING LINE
144' SHIFT TAPER
494' SHIFT TAPER
200' SHIFT TAPER
50' SHIFT TAPER
71 SB TO SINCLAIR RD
SINCLAIR RD TO 71 SB
MORSE RD TO 71 NB
WORK ZONE EDGE LINE
WORK ZONE CHANNELIZING LINE
WORK ZONE LANE LINE
WORK ZONE DOTTED LINE
℄ CONST. SINCLAIR RAMP E
℄ CONST. SINCLAIR RAMP A
℄ CONST. MORSE RD RAMP B
℄ CONST. I-71
IR 71 SB
IR 71 NB
MATCH LINE STA. 1317+00
MATCH LINE STA. 1334+00
SEE PHASE 3A FOR PAVEMENT MARKINGS DETAILS
SEE NOTE
MATCH PHASE 3A PAVEMENT MARKINGS STA. 1333+00
EXIT 116 30 MPH
RAMP 30 MPH
EXIT 116 Morse Rd Sinclair Rd
EXIT 115 Cooke Rd 1¼ MILE
W3-3R30-48 STA. 1315+50
W20.1-48
R11-H5A-24
R11-H5A-24
W20.1-48
W3-3R30-48 STA. 1315+50
TO REMAIN
DO NOT ENTER
ONE WAY
NON-DIVERGING CRASH CUSHION
W2-2-36
W2-2-36
W2-2-36




NOTE:
COMPLETE REMAINING VARIABLE DEPTH MILLING AND INTERMEDIATE COURSE WHILE TRANSITIONING FROM PHASE 4A TO PHASE 4B STEP 1. SEE SEQUENCE OF OPERATIONS FOR DETALS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT
- VARIABLE DEPTH MILLING DURING PHASE TRANSITION

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4A
# STA. 1334+00.00 TO STA. 1351+00.00


FRA-71-19.10



MODEL: Phase 3A - Phase 4A PROPOSED - 60x144 in | DATE: 3/31/2026 7:56:1 11:03:13 AM | FOTOM: CHDOT_ITP_V1.pmtg | PSMTEL: CHDOT_PM.tbl | USER: Chris.Lawrence1@jacobs.com | WORKSPACE: CHDOTCIVIL02 | WORKSET: 109164 | PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: C:\Users\chris.lawrence1\Jacobs\Documents - FRA-071-19.10 Phase 4A Traffic Control Plans\Working\Phase 4A\FRA-071-19.10 Phase 4A MOT.dgn


DESIGN AGENCY: Jacobs
DESIGNED: SRH
REVIEWED: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.135 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1A - Plan PAPERSIZE: ANSI A4 (in) DATE: 3/31/2026 TIME: 11:03:14 AM FSTORM: CHKDP_PDF_V-1.dmp$_FSTITEL: CHKDP_Plot.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHKDOTLXD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE: H:\Projects\FRA\FRA-71-19.10\Design\Roadway\Phase 1\Maintenance of Traffic\Phase 4A\FRA-71-19.10_MOT_Phase 4A.dgn




TYPICAL SECTION - PHASE 4A
STA. 1352+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND


- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4A
# STA. 1351+00.00 TO STA. 1368+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.136 TOTAL: 618




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4A
# STA. 1368+00.00 TO STA. 1385+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.137 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1A - Plan 10 MARKINGS: 66x34.0in | DATE: 3/31/2026 TIME: 11:10:15 AM BY/DBY: DHOFF, PM: JF-JHM, PENTRL: DHOFF, Plot Set: USER: Chris.Lawrence@jacobs.com WORKPACE: DHOFF0145 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.12.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL INFORMATION. THIS WORK MAY NOT BE COPIED, MODIFIED, OR DISTRIBUTED WITHOUT PRIOR WRITTEN AUTHORIZATION FROM BENTLEY.





FRA-71-19.10

MAINTENANCE OF TRAFFIC - PHASE 4A
STA. 1385+00.00 TO STA. 1402+00.00

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.138 TOTAL 618

MODEL: Phase 3A - Plan 11 MARKINGS: 66x34 (H=) DATE: 3/31/2026 TIME: 11:10:14 AM BY/DRY: DHOFF, PSF, D-J-HSB, PENTEL DHOFF, Pen Set USER: Chris.Lawrence@jacobs.com WORKSPACE: DHOFFD4D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.12.25
ACTIVE FILE: P:\109164\Highway\Roadway\Design\Phase 4A\Plan Sheets\FRA-71-19.10 MOT Phase 4A.dgn







NOTE:
COMPLETE REMAINING VARIABLE DEPTH MILLING AND INTERMEDIATE COURSE WHILE TRANSITIONING FROM PHASE 4A TO PHASE 4B STEP 1. SEE SEQUENCE OF OPERATIONS FOR DETAILS.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT
- VARIABLE DEPTH MILLING DURING PHASE TRANSITION

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4A
# STA. 1402+00.00 TO STA. 1419+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.139 TOTAL: 618

FRA-71-19.10

BENTLEY SYSTEMS, INC. | Plot: 12 PAPERSIZE: 66x34.0in | DATE: 3/31/2026 TIME: 12:58:19 PM USER: CHOUDT_PW | C:\JACOBS_PROJECTS\...\CHOUDT_PW.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHOUDT0420 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




TYPICAL SECTION - PHASE 4A
STA. 1430+00 IR-71

NOTE:
COMPLETE REMAINING VARIABLE DEPTH MILLING AND INTERMEDIATE COURSE WHILE TRANSITIONING FROM PHASE 4A TO PHASE 4B STEP 1. SEE SEQUENCE OF OPERATIONS FOR DETAILS.

*SPIRAL DATA - 1*
*Ls = 200.00'*
*Gs = 07°20'00"*
*LT = 133.45'*
*ST = 66.77'*
*x = 199.67'*
*y = 8.52'*
*k = 99.95'*
*p = 2.13'*
*C = 199.85'*
*C.B. = N33°13'59"E*

*CURVE DATA - 2*
*Δ = 13°39'41" LT*
*Dc = 07°20'00"*
*R = 781.31'*
*T = 93.59'*
*L = 186.29'*
*E = 5.59'*

*SPIRAL DATA - 3*
*Ls = 200.00'*
*Gs = 07°20'00"*
*LT = 133.45'*
*ST = 66.77'*
*x = 199.13'*
*y = 17.03'*
*k = 99.95'*
*p = 2.13'*
*C = 199.85'*
*C.B. = N09°47'36"E*

*CURVE DATA - 4*
*Δ = 04°47'08" RT*
*Dc = 00°45'00"*
*R = 7,639.00'*
*T = 319.2'*
*L = 638.02'*
*E = 6.67'*

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT
- VARIABLE DEPTH MILLING DURING PHASE TRANSITION

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4A
# STA. 1419+00.00 TO STA. 1436+00.00

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.140 TOTAL 618


FRA-71-19.10


MODEL: Phase 3A - Plan 13 MARKINGS: 6in,4in,1 DATE: 3/31/2026 TIME: 12:39:07 PM USER: CHRIST, JOSE J. (JJ4GJ6, PENTEL, CHRIST, JOSE J.) File Name: USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTOJ42 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACCESS TO THIS DRAWING IS RESTRICTED TO AUTHORIZED USERS. ANY USE OF THIS DRAWING FOR PURPOSES OTHER THAN THOSE AUTHORIZED BY THE OWNER IS PROHIBITED.

FRA-71-19.10

MODEL: Phase 1A - Plan 14 MARKERS: 66x34.0+1 DATE: 3/31/2026 TIME: 11:10:19 AM FSTORY: DWGFT_PSF_C-LHSB_PENTBL: DWGFT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: DWGFT0U02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.12.25

FILE NAME: P:\Projects\Ohio\Columbus\FRA-71-19.10\Design\Roadway\Plan\Phase 4A\FRA-71-19.10_Phase 4A_Plan 14.dgn




*CURVE DATA - 1*
*P.I. = STA. 9443+28.14*
*Δ = 08°44'00" RT*
*Dc = 01°50'00"*
*R = 3,125.23'*
*T = 238.65'*
*L = 476.37'*
*E = 9.1'*

*CURVE DATA - 2*
*P.I. = STA. 9447+06.22*
*Δ = 05°08'36" LT*
*Dc = 01°50'00"*
*R = 3,125.23'*
*T = 140.36'*
*L = 280.54'*
*E = 3.15'*


| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET: 0, 15, 30, 60

# MAINTENANCE OF TRAFFIC - PHASE 4A
# STA. 1436+00.00 TO STA. 1453+00.00

DESIGN AGENCY: Jacobs
DESIGNED: SRH
REVIEWED: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.141 TOTAL: 618




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

**LEGEND**

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4A
# STA. 1453+00.00 TO STA. 1470+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.142 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1A - Plan 15 MARKERS: 66x34-6in-1 DATE: 3/31/2026 TIME: 11:10:21 AM PLOTBY: CHRISTOPHER J LANG, PE/PS, CHRISTOPHER.LANG@JACOBS.COM WORKSPACE: CHRISTOLKO2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
PLOTSCALE: 1.000 FILE: C:\Users\christopher.lang\Jacobs\Desktop\Working Files\FRA-71-19.10 Maintenance of Traffic - Phase 4A.dgn




TYPICAL SECTION - PHASE 4A
STA. 1475+00 IR-71

NOTE: SEE SHEET P.61 FOR PHASE 4A ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4A
# STA. 1470+00.00 TO STA. 1487+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.143 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1A - Plan 1A MARKERS: 66x34.0in | DATE: 3/31/2026 TIME: 12:39:44 PM STORM: ONEOT_PSF_C.shtdg PRINTED: ONEOT_Plan.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: ONEOTSHEET WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. THIS DRAWING AND ITS CONTENTS ARE THE PROPERTY OF JACOBS AND SHALL NOT BE REPRODUCED, PUBLISHED, OR USED IN ANY WAY WITHOUT THE EXPRESS WRITTEN PERMISSION OF JACOBS.




TYPICAL SECTION - PHASE 4B STEP 1
STA. 1260+00 IR-71

NOTES:
1. SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS
2. SEE SHEET P.52 FOR PHASE 4B NB ADVANCED SIGNING PLAN
3. SEE PHASE 4A FOR I-71 NORTHBOUND TEMPORARY PAVEMENT MARKING DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1249+00.00 TO STA. 1266+00.00

FRA-71-19.10

MODEL: Phase 1B - Plan 3 PAPERSIZE: ISO-A3 (ro) DATE: 3/31/2026 TIME: 11:03:18 AM FILENAME: C:\OOT_CHDOT_PDF_Files\FRA-71-19.10_109164_P1MTB1_CHDOT_Plan.dgn USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTCE02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE: Phase 1B - Plan 3 REFERENCES: C:\OOT_CHDOT_PDF_Files\FRA-71-19.10_109164_P1MTB1_CHDOT_Plan.dgn C:\OOT_CHDOT_PDF_Files\FRA-71-19.10_109164_P1MTB1_CHDOT_Plan.dgn

DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.144 TOTAL 618




TYPICAL SECTION - PHASE 4B STEP 1
STA. 1276+50 IR-71

NOTE:
SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1266+00.00 TO STA. 1283+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.145 TOTAL: 618

FRA-71-19.10


MODEL: Phase 1B - Plan • PAPERSIZE: ISO A1 (L) • DATE: 3/31/2026 TIME: 11:10:43 AM • FILTER: ON|OFF_ITEM_LY-URSB_PSHTEL: ON|OFF_Print Edit: USER: Chris.Lawrence1@jacobs.com WORKSPACE: ON|OFF|D:\02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE DGN: P:\Projects\Transportation\Roadway\109164_FRA-71-19.10\Design\Roadway\Plan Sheets\MOT\MOT_Phase 1B - Plan.dgn


FRA-71-19.10

MODEL: Phase 1B - Plan 5 PAPERSIZE: 36x24 in | DATE: 3/31/2026 TIME: 11:56:48 PM SYSTEM: CHDOT_PW | PLOTBY: CHDOT_PW.bit USER: ChrisLawrence1@jacobs.com WORKSPACE: CHDOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25

DATA: C:\Projects\109164\Roadway\Design\Phase 1\Maintenance of Traffic\Phase 1B\Plan 5\FRA-71-19.10 MOT Phase 1B Plan 5.dgn

W1-H16-36
STA. 1283+50
STA. 1284+50
STA. 1285+50
A




CURVE DATA - 1
Δ = 02°33'04" LT
Dc = 00°29'00"
R = 11,854.39'
T = 263.97'
L = 527.85'
E = 2.94'

CURVE DATA - 2
Δ = 02°33'04" RT
Dc = 00°29'00"
R = 11,854.39'
T = 263.97'
L = 527.85'
E = 2.94'

NOTE:
SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |


LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1283+00.00 TO STA. 1300+00.00

DESIGN AGENCY
Jacobs

DESIGNER
SRH
REVIEWER
BAP 03/20/26
PROJECT ID
109164
SHEET
P.146
TOTAL
618







NOTE:
SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
STA. 1300+00.00 TO STA. 1317+00.00

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.147 TOTAL 618

FRA-71-19.10

MODEL: Phase 1B - Plan # PAYPERIOD: 06/24 (+) | DATE: 3/31/2026 TIME: 1:10:15 PM | FILENAME: C:\PROJECTS\FRA-71-19.10\Design\Roadway\Phase 1B\Maintenance of Traffic\Phase 4B\FRA-71-19.10 MOT Phase 4B Step 1.dgn | USER: ChrisLawrence1@jacobs.com | WORKSPACE: c:\projects\fra-71-19.10\design\roadway\phase 1b\maintenance of traffic\phase 4b\ | WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




TYPICAL SECTION - PHASE 4B STEP 1
STA. 1318+50 IR-71

NOTE:
SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTOL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1317+00.00 TO STA. 1334+00.00

DESIGN AGENCY
Jacobs


DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.148 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1B - Plan 7 PAYPERIOD: 4to14 DATE: 3/31/2026 TIME: 1:10:57 PM USERNAME: CHRISTOPHER.PAYNE@JACOBS.COM DESIGN FILE: C:\Users\christopher.payne\Jacobs\Desktop\Projects\FRA-71-19.10\Design\Phase 1B\Plan 7\Maintenance of Traffic - Phase 4B Step 1.dgn WORKSPACE: CHRISTOPHER_PAYNE_CONNECT_Default WORKSET: 109164 PRODUCT: OpenRoadDesigner 24.00.02.25

FRA-71-19.10

MODEL: Phase 1B - Plan B PAPERIZE: ANSI-A4 (-) DATE: 3/31/2026 TIME: 11:10:57 AM FILTER: CHKDT_PDF_V = pass$ PENTBL: CHKDT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHKDTT1202 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACCESS: Project Team - Internal PROJECTWISE FOLDER: I:\FRA-71\19.10\Traffic\Maintenance of Traffic\Phase 4\Phase 4B\Step 1\Sheets\MOT-Phase 4B Step 1.dgn




NOTE:
SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTOL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1334+00.00 TO STA. 1351+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.149 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1B - Plan PAPERSIZE: ANSI-A4 | DATE: 3/31/2026 TIME: 11:10:48 AM FSTORY: CHKDT_PDF_V-Lan5B_FSHTEL: CHKDT_Print Edit USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHKDTTC02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE: P:\Projects\Fra\109164\Highway\Design\Roadway\Phase 1\Phase 1B\FRA-71-19.10 - Phase 1B - Sheet 1.dgn




TYPICAL SECTION - PHASE 4B STEP 1
STA. 1352+00 IR-71

NOTE:
SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTOL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1351+00.00 TO STA. 1368+00.00


DESIGN AGENCY
Jacobs


DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.150 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1B - Plan 1B PAPERSIZE: 66x34.0in | DATE: 3/31/2026 TIME: 11:18:49 AM BYCOM: CHRISTY, PSK, E | eFILE: PENTEL CHRISTY, Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTY.dgn WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL INFORMATION. UNAUTHORIZED USE IS PROHIBITED.

*W1-H16-36*
STA. 1369+00
STA. 1370+00
STA. 1371+00
STA. 1372+00
STA. 1373+00
(A)




NOTE:
SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTOL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |


LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1368+00.00 TO STA. 1385+00.00

DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.151 TOTAL 618

FRA-71-19.10
MODEL: Phase 1B - Plan 11 PAPERSIZE: 66x34.0in | DATE: 3/17/2026 TIME: 11:10:56 AM EDITED: CHHOY, PW: 0 LEVEL: PENTEL: CHHOY, Pen Set USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHHOYSS402 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE: Phase 1B - Plan 11 REFERENCES: Phase 1B - Plan 11 Phase 1B - Plan 11 Phase 1B - Plan 11 







NOTE:
SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTOL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1402+00.00 TO STA. 1419+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.153 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1B - Plan 12 REFRESH: 04/24/25 DATE: 3/31/2026 TIME: 11:10:51 AM USER: DWORT, PW_ID: p4h6j, PENTEL: DWORT, Pen list: USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWORT-DGN-02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO BENTLEY SYSTEMS LICENSE AGREEMENT. PROPRIETARY AND CONFIDENTIAL INFORMATION. Adobe PDF Library 17.0.0




*NOTE:*
*SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTOL DETAILS*

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

**LEGEND**

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET: 0, 15, 30, 60


# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1419+00.00 TO STA. 1436+00.00


DESIGN AGENCY: Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.154 | TOTAL: 618

FRA-71-19.10

MODEL: Phase 1B - Plan | 3 IMPERIOUS: 66x34.0in | DATE: 3/31/2026 TIME: 11:10:53 AM SYSTEM: DWG?, PW_E | 64bit, PENTEL: DWG?, Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWG?DWG\02 WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.02.25
ACTIVE FILE: P:\Projects\Columbus and Ohio\Columbus\Columbus Freeway Projects\109164 - FRA-71-19.10 Maintenance of Traffic\Design\Roadway\Plan Sheets\MOT_Phase 4B Step 1.dgn




TYPICAL SECTION - PHASE 4B STEP 1
STA. 1449+00 IR-71

NOTE:
SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTOL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1436+00.00 TO STA. 1453+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.155 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1B - Plan 14 MAPSHEET: 66x34 (in) DATE: 3/31/2026 TIME: 11:35:54 AM SYCOM1: CHKDT: PSF_E-24NB_PENTBL: CHKDT: Pen tbl USER: Chris.Lawrence1@jacobs.com WORKPACK: CHKDTSUI2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
DO NOT MODIFY THIS DRAWING. ANY MODIFICATIONS MADE TO THIS DRAWING WILL NOT BE REFLECTED IN THE OFFICIAL RECORD. Approved drawings are available on ODOT's ProjectWise.




TYPICAL SECTION - PHASE 4B STEP 1
STA. 1469+00 IR-71

NOTE:
SEE PHASE 4A FOR I-71 NORTHBOUND AND SOUTHBOUND TEMPORARY TRAFFIC CONTOL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
STA. 1453+00.00 TO STA. 1470+00.00

FRA-71-19.10

MODEL: Phase 1B - Plan 15 MAPSHEET: 66x34 (in) DATE: 3/31/2026 TIME: 11:10:55 AM EDITOR: CHRIST, PSK, D CAMUS, PENTEL CHRIST, Pen Set USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTOUD2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\109164\Highway\Roadway\Sheets\Phase 1\Phase 1B\Plan 15\FRA-71-19.10_MOT_Phase 1B_Plan 15.dgn


DESIGN AGENCY
Jacobs


DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.156 TOTAL 618




TYPICAL SECTION - PHASE 4B STEP 1
STA. 1475+00 IR-71

*NOTES:*

1. SEE PHASE 4A FOR I-71 NORTHBOUND AND SOUTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS
2. SEE SHEET P.61 FOR PHASE 4B ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 1
# STA. 1470+00.00 TO STA. 1487+00.00


DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.157 TOTAL 618

FRA-71-19.10

MODEL: Phase 1B - Plan 1B MAPSHEET: 66x34 (in) DATE: 3/31/2026 TIME: 11:10:54 AM SYSTEM: CHROT_PW_E-64\dgn_PENTBL: CHROT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHROTS1x02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\109164\Engineering\Roadway\Traffic\Phase 1\Phase 1B\Sheets\FRA-71-19.10_MOT_Phase 1B_Plan 1B.dgn




*NOTES:*

1. SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS
2. SEE PHASE 4B STEP 1 FOR ADDITIONAL I-71 NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

*CURVE DATA - 1*
*Δ = 09°05'03" RT*
*Dc = 01°15'00"*
*R = 4,583.66'*
*T = 364.14'*
*L = 726.74'*
*E = 14.44'*

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 2
# STA. 1283+00.00 TO STA. 1300+00.00

FRA-71-19.10


MODEL: Phase 1B - Plan 5 PAPERSIZE: ANSI A4 (in) DATE: 3/31/2026 TIME: 11:11:11 AM FILENAME: CHKDGT_PDF_V-Letter_PSHTEL.CHKDGT_Plan.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHKDGTCLIO2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE: P:\FRA\71\FRA-71-19.10\Roadway\Traffic\Phase 1\FRA-71-19.10 MOT Phase 1B Step 2.dgn


DESIGN AGENCY
Jacobs
DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.158 TOTAL 618




TYPICAL SECTION - PHASE 4B STEP 2
STA. 1306+00 IR-71

*NOTES:*

1. SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS
2. SEE PHASE 4B STEP 1 FOR ADDITIONAL I-71 NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 2
# STA. 1300+00.00 TO STA. 1317+00.00

FRA-71-19.10

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.159 TOTAL 618

MODEL: Phase 1B - Plan | PAPERSIZE: ANSI-D | DATE: 3/31/2026 TIME: 11:11:16 AM | FCDW: CHRISTOPHER_H | e-SEAL: PSYFEL CHRISTOPHER HUGH | Plot Set: USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTOPHER HUGH WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ELECTRONIC FILE AGREEMENT APPLIES | PROPRIETARY AND CONFIDENTIAL | Copyright © Bentley Systems, Incorporated




*NOTES:*

1. SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS
2. SEE PHASE 4B STEP 1 FOR ADDITIONAL I-71 NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET: 0, 15, 30, 60


# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 2
# STA. 1317+00.00 TO STA. 1334+00.00


FRA-71-19.10


DESIGN AGENCY: Jacobs
DESIGNED: SRH
REVIEWED: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.160 TOTAL: 618



MODEL: Phase 1B - Plan 7 PAPERSIZE: ANSI A4 (in) DATE: 3/31/2026 TIME: 11:11:17 AM FCDW: CHDOT_PDF_V1.pltcfg PSTBL: CHDOT_Plot.ctb USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHDOTC02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




TYPICAL SECTION - PHASE 4B STEP 2
STA. 1338+00 IR-71

NOTES:

1. SEE PHASE 4A FOR I-71 SOUTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS
2. SEE PHASE 4B STEP 1 FOR ADDITIONAL I-71 NORTHBOUND TEMPORARY TRAFFIC CONTROL DETAILS

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4B STEP 2
# STA. 1334+00.00 TO STA. 1351+00.00

FRA-71-19.10


MODEL: Phase 1B - Plan B PAPERSIZE: ANSI A4 (in.) DATE: 3/31/2026 TIME: 11:11:19 AM FILENAME: C:\USERS\CLAWRENCE\DESKTOP\FRA-71-19.10_PHASE 4B STEP 2_PLAN B_CLAWRENCE.DGN WORKSPACE: C:\USERS\CLAWRENCE\APPDATA\LOCAL\BENTLEY\OPENROADS CONNECT EDITION\WORKSPACES\DEFAULT.CWS


DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.161 TOTAL: 618




NOTES:
1. AT THE DEPARTMENT'S DISCRETION, THE CONTRAFLOW LANE MAY BE CLOSED FOR REASONS SUCH AS, BUT NOT LIMITED TO, AN EMERGENCY OR WEATHER EVENT. WHEN DIRECTED, CLOSE THE CONTRAFLOW LANE AS SHOWN.
2. INSTALL ADVANCE WARNING SIGNS FOR LANE CLOSURE PER SCD MT-95.30.
3. THE INTENT OF THIS DRAWING IS TO SHOW ONLY THOSE DEVICES NEEDED TO CLOSE THE CONTRAFLOW LANE. PHASE 4A/4B TRAFFIC CONTROL DEVICES NOT SHOWN FOR CLARITY

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 4A/4B CONTRAFLOW LANE CLOSURE
# STA. 1249+00.00 TO STA. 1266+00.00

FRA-71-19.10



MODEL: Phase 1A - Plan | PAPERSIZE: ISO A1 | DATE: 3/31/2026 TIME: 11:11:11 AM | FCDW: CMDOT_PDF_V-LatSQ_FIXTEL.CMDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CMDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ELEMENTS: Plan Sheet Graphics | Area Fill | Dynamic Fill | Text | Text Nodes | Dimensions | Multi-line Text | Tables | Markups | Civil Cells


DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26

PROJECT ID
109164




*NOTES:*
*1. AT THE DEPARTMENT'S DISCRETION, THE CONTRAFLOW LANE MAY BE CLOSED FOR REASONS SUCH AS, BUT NOT LIMITED TO, AN EMERGENCY OR WEATHER EVENT. WHEN DIRECTED, CLOSE THE CONTRAFLOW LANE AS SHOWN.*
*2. INSTALL ADVANCE WARNING SIGNS FOR LANE CLOSURE PER SCD MT-95.30.*
*3. THE INTENT OF THIS DRAWING IS TO SHOW ONLY THOSE DEVICES NEEDED TO CLOSE THE CONTRAFLOW LANE. PHASE 4A/4B TRAFFIC CONTROL DEVICES NOT SHOWN FOR CLARITY*

| *DRUM SPACING CHART* | |
|---|---|
| *TANGENT* | *120' c/c* |
| *TAPER* | *60' c/c* |
| *RAMP DELINEATION* | *20' c/c* |

*LEGEND*

- *PHASE WORK ZONE*
- *DRUMS*
- *PORTABLE BARRIER*
- *TEMPORARY PAVEMENT*
- *IMPACT ATTENUATOR*
- *DIRECTION OF TRAVEL*
- *TYPE III BARRICADE*
- *TEMPORARY SIGN SUPPORT*

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 4A/4B CONTRAFLOW LANE CLOSURE
# STA. 1266+00.00 TO STA. 1283+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.163 TOTAL: 618

FRA-71-19.10

MODEL: Phase 1A - Plan # PAYSHEETS: 66x34 (in) | DATE: 3/31/2026 TIME: 11:11:17 AM FSTORY: CHSOT_PSP_1A.pltcfg PSTBL: CHSOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHSOTCIVD2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\Projects\Columbus\FRA-71-19.10\Design\Roadway\Plans\Maintenance of Traffic\Phase 4A-4B\MOT_Phase 4A-4B_Contraflow Lane Closure.dgn




TYPICAL SECTION - PHASE 5A STEP 1
STA. 969+00 IR-71 NB

NOTE: SEE SHEET P.53 FOR PHASE 5A STEP 1 NB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 80' c/c |
| TAPER | 55' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


MAINTENANCE OF TRAFFIC - PHASE 5A STEP 1
STA. 953+50.00 TO STA. 970+50.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.164 TOTAL: 618

FRA-71-19.10

MODEL: CLV_OTI_NB | Plot: 1 PAPERSIZE: 66x34 in | DATE: 3/12/2026 TIME: 11:11:56 AM | USER: CMOOT_PKD | LAYER: CMOOT_PKD_5-phase_PENTEL CMOOT_Pencil | USER: Chris.Lawrence3@jacobs.com WORKSPACE: CHIDOTSVA2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. THIS DRAWING AND ITS CONTENTS ARE THE PROPERTY OF JACOBS AND SHALL NOT BE REPRODUCED OR PUBLISHED WITHOUT THE PRIOR WRITTEN PERMISSION OF JACOBS.


71 SB TO SPRING ST
670 WB TO JACK GIBBS BLVD
670 WB TO SPRING ST
670 WB TO 71 SB
71 SB TO SPRING ST
IR 670 EB
℄ I-71 SB
IR 71 SB
℄ I-71 NB
IR 71 NB
SPRING ST TO 71 NB
SPRING ST TO 670 EB
℄ I-670 RAMP V7
℄ I-670 RAMP X4
670 EB TO 71 NB
MATCH LINE STA. 970+50
MATCH LINE STA. 987+50
WORK ZONE CHANNELIZING LINE
WORK ZONE EDGE LINE
JACK GIBBS BLVD
550' SHIFT TAPER
WORK AHEAD
WORK ZONE AHEAD
WORK ZONE AHEAD
WORK ZONE






MAINTENANCE OF TRAFFIC - PHASE 5A STEP 1
STA. 987+50.00 TO STA. 1004+50.00

FRA-71-19.10


MODEL: CLV_OT1_MB Plan 3 PAYFIXED: 66x34 in | DATE: 3/12/2026 TIME: 11:12:33 AM | FILEIN: C:\PROJECTS\FRA-71-19.10\ROADWAY\SHEETS\FRA-71-19.10_MOT_PH5A_PENTEL.DWG | PLOTTED: C:\PROJECTS\FRA-71-19.10\ROADWAY\PLOTS\FRA-71-19.10_MOT_PH5A_PENTEL.DWG | PLOT_PH5A | USER: Chris.Lawrence@jacobs.com WORKSPACE: CHIDOTSEXCI WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25


DESIGN AGENCY
Jacobs
DESIGNER
SRH
REVIEWER
BAP 03/20/26
PROJECT ID
109164
SHEET P.166
TOTAL 618




*CURVE DATA - 2*
*Δ = 01°45'11" RT*
*Dc = 02°17'31"*
*R = 2,500.00'*
*T = 38.25'*
*L = 76.49'*
*E = .29'*

*CURVE DATA - 3*
*Δ = 03°15'47" LT*
*Dc = 00°47'26"*
*R = 7,246.91'*
*T = 206.42'*
*L = 412.73'*
*E = 2.94'*

*CURVE DATA - 4*
*Δ = 03°15'47" RT*
*Dc = 00°47'26"*
*R = 7,246.91'*
*T = 206.42'*
*L = 412.73'*
*E = 2.94'*

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 80' c/c |
| TAPER | 55' c/c |
| RAMP DELINEATION | 20' c/c |

*LEGEND*
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 5A STEP 1
# STA. 1004+50.00 TO STA. 1021+50.00

FRA-71-19.10

DESIGN AGENCY
Jacobs


DESIGNER
SRH


REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.167 TOTAL 618

MODEL: CU_071_NB - Plan # 3WFDSEE1 08/4/19 | DATE: 3/31/2026 TIME: 11:23:33 AM | SYSTEM: DWG97_PKE_5 | xPHB_PENTBL: DWG97_PKE.ctb | USER: Chris.Lawrence@jacobs.com | WORKSPACE: D:\WORKSPACE\ | WORKSET: 109164 | PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. THIS FILE AND ITS CONTENTS ARE PROPRIETARY TO BENTLEY SYSTEMS, INCORPORATED.




NOTE: SEE SHEET P.54 FOR PHASE 5A STEP 2 NB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 80' c/c |
| TAPER | 55' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 5A STEP 2
## STA. 970+50.00 TO STA. 987+50.00

FRA-71-19.10

DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.168 TOTAL: 618

MODEL: CLV_OT1_MB Plan: 3 PAPERSIZE: 66x34 in | DATE: 3/12/2026 TIME: 11:23:17 AM USERN: DMOOT_PRD FILENAME: C:\DOT_Projects\FRA\71\FRA-71-19.10\Design\Roadway\Sheets\FRA-71-19.10_MOT_Phase 5A Step 2.dgn PENTBL: DMOOT_Pen.tbl CLIENT: ODOT_PRD_V1.pltcfg USERNAME: Shannon.Hamilton@jacobs.com WORKSPACE: OHDOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




TYPICAL SECTION - PHASE 5A STEP 2
STA. 1002+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 80' c/c |
| TAPER | 55' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


MAINTENANCE OF TRAFFIC - PHASE 5A STEP 2
STA. 987+50.00 TO STA. 1004+50.00


DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.169 TOTAL 618

FRA-71-19.10

MODEL: CLV_OT1_NB - Plan 2 PAPERSIZE: 66x34 in | DATE: 3/12/2026 TIME: 11:55:58 PM | PCTBW: GROUT_PW_F-SHEAL_PATTEL: GROUT_Pen.tbl USER: Chris.Sizemore@jacobs.com WORKSPACE: CHOOUTCIVD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.03.25
DATA FILE PATH: P:\109164\Design\Roadway\Alignments\Alignments_Phase 5\Alignments_Phase 5A\Alignments_Phase 5A Step 2\Alignments_Phase 5A Step 2.dgn




TYPICAL SECTION - PHASE 5A STEP 2
STA. 1010+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 80' c/c |
| TAPER | 55' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 5A STEP 2
# STA. 1004+50.00 TO STA. 1021+50.00


DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.170 TOTAL 618

FRA-71-19.10

MODEL: CU_071_NB Plan 3 PAPERSIZE: ISO A1 (841 x 594) DATE: 3/12/2026 TIME: 11:12:24 AM SYSTEM: ONDOT_PID_V1.xPWB PENTBL: ONDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: D:\WORKSPACE\ CHRISTOVAS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE PLAN REFERENCES: PLAN REFERENCE:CU_071_NB_Plan 3 PLAN REFERENCE:CU_071_NB_Plan 4 PLAN REFERENCE:CU_071_NB_Plan 5A Step 1 PLAN REFERENCE:CU_071_NB_Plan 5A Step 2




TYPICAL SECTION - PHASE 5B STEP 1
STA. 996+00 IR-71

CURVE DATA - 1
Δ = 03°20'14" LT
Dc = 01°50'00"
R = 3,125.22'
T = 91.04'
L = 182.03'
E = 1.33'

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 5B STEP 1
# STA. 987+50.00 TO STA. 1004+50.00

FRA-71-19.10

DESIGN AGENCY: Jacobs
DESIGNED: SRH
REVIEWED: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.171
TOTAL: 618

MODEL: C:\DT_MB - Plan 3 PAPERSIZE: 66x34 in | DATE: 3/12/2026 TIME: 11:23:37 AM | FILENAME: C:\DOT_PKG_1-pl\MB_PENTBL: C:\DOT_Pkg\1-pl\MB_Pen.tbl | USER: Chris.Lawrence@jacobs.com WORKSPACE: C:\HIGHWAY_DESIGN_WORKSPACE\ WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




TYPICAL SECTION - PHASE 5B STEP 1
STA. 1017+00 IR-71

| CURVE DATA - 1 | CURVE DATA - 2 | CURVE DATA - 3 | CURVE DATA - 4 |
|---|---|---|---|
| Δ = 03°20'14" LT | Δ = 03°24'24" RT | Δ = 04°41'12" RT | Δ = 04°41'12" LT |
| Dc = 01°50'00" | Dc = 01°50'00" | Dc = 01°46'55" | Dc = 01°46'55" |
| R = 3,125.22' | R = 3,125.22' | R = 3,215.22' | R = 3,215.22' |
| T = 91.04' | T = 92.93' | T = 131.57' | T = 131.57' |
| L = 182.03' | L = 185.81' | L = 262.99' | L = 262.99' |
| E = 1.33' | E = 1.38' | E = 2.69' | E = 2.69' |

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 5B STEP 1
# STA. 1004+50.00 TO STA. 1021+50.00


DESIGN AGENCY
Jacobs

DESIGNED SRH
REVIEWED BAP 03/20/26
PROJECT ID 109164
SHEET P.172 TOTAL 618

FRA-71-19.10

MODEL: CLV_071_MB - Plan # 3WP03601 (664.84 ft) | DATE: 3/17/2026 TIME: 11:23:42 AM | SYSTEM: DWG97_PKT_H | APHQ6 | PENTBL: DWG97_Pen.tbl | USR: Chris.Lawrence@jacobs.com WORKSPACE: DWG97DEVKIT WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL. THIS FILE IS PROTECTED BY COPYRIGHT AND TRADE SECRET LAW.




TYPICAL SECTION - PHASE 5B STEP 1
STA. 1027+50 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

**LEGEND**

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 5B STEP 1
# STA. 1021+50.00 TO STA. 1038+50.00


DESIGN AGENCY
Jacobs


DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.173 TOTAL: 618

FRA-71-19.10

MODEL: CLV_DT1_MB Plan:5 XREFSIZE: 66x34 in | DATE: 3/12/2026 TIME: 11:23:43 AM SYSTEM: ON DGN: DGN_PRE_5 xPHA: PENTBL: ON DGN: DGN_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CHDOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadDesigner 24.00.02.25
DO NOT USE PRINTED COPIES OF ELECTRONIC FILES | ALL PRINTED COPIES ARE UNCONTROLLED | FOR CURRENT INFORMATION, REFER TO ODOT'S MANUAL OF ELECTRONIC PROJECT DELIVERY


MATCH LINE STA. 1038+50
1039
1040
1041
1042
1043
1044
1045
1046
1047
1048
1049
1050
1051
1052
1053
1054
1055
IR 71 SB
℄ CONST. I-71
IR 71 NB
11TH AVE. TO 71 SB
71 SB TO 11TH AVE
11TH AVE TO 71 NB
71 NB TO 11TH AVE
CLEVELAND AVE.
11th Ave
EXIT ONLY
EXIT 110B
EXIT 110
EXIT 109B
EXIT 109
TO REMAIN
TO REMAIN
TO REMAIN




TYPICAL SECTION - PHASE 5B STEP 2
STA. 996+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

**LEGEND**

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 5B STEP 2
# STA. 987+50.00 TO STA. 1004+50.00

DESIGN AGENCY: Jacobs

| | |
|---|---|
| DESIGNER | SRH |
| REVIEWER | BAP 03/20/26 |
| PROJECT ID | 109164 |
| SHEET | P.175 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: CLV_OTI_MB Plot: 1:1 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 11:13:59 AM EDITING CHKOPT_PSF_1=Locks PENTBL: CHKOPT_PSF_1=Locks PENTBL: CHKOPT_PSF_1=Locks USER: Chris.Lawrence@jacobs.com WORKSPACE: CHKOPTDGN02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE PLAN REFERENCE ATTACHMENTS: PLAN SET: E:\CADD\Projects\109164\Design\Roadway\Sheets\Maintenance of Traffic\FRA-71-19.10_MOT_Phase 5B Step 2.dgn




NOTE: SEE SHEET P.63 FOR PHASE 5B STEP 2 5B ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 5 STEP 2
# STA. 1004+50.00 TO STA. 1021+50.00


DESIGN AGENCY
Jacobs


DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.176 TOTAL 618

FRA-71-19.10

MODEL: CLV_071_MI - Plan 4.1 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 11:13:05 AM XREFRV: CHKOPT_PSF_1=1.pltcfg, PENTBL: CHKOPT_PSF_1=1.pltcfg, PENTBL: CHKOPT_PSF_1=1.pltcfg, PENTBL


SEE NOTE
40'
780' MERGE TAPER WITH DRUMS
+80
11TH AVE TO 71 SB
11TH AVE.
71 SB TO 11TH AVE
IR 71 SB
℄ CONST. I-71
IR 71 NB
71 NB TO 11TH AVE
11TH AVE TO 71 NB
MATCH LINE STA. 1064+00
47
1048
1049
1050
1051
1052
1053
1054
1055
1056
1057
1058
1059
1060
1061
1062
1063
EXIT 110 B
Convention Center
Nationwide Arena
Cost Science Center
TO REMAIN
EXIT 109 B
5th Ave
Spring St
TO REMAIN
EXIT 110 B
11th Ave
TO REMAIN
EXIT 110 A
Fifth Ave
½ MILE
TO REMAIN
EXIT 109 A
670
Airport
Dayton
3 MILES
TO REMAIN
EXIT 110B
TO REMAIN
EXIT 110B
11th Ave
ONLY
TO REMAIN
EXIT 110B
TO REMAIN
EXIT 111
Ohio History
Center
TO REMAIN
EXIT 111
11th Ave
Hudson St
Weber Rd
TO REMAIN
WB 71
NORTH
TO REMAIN
WB 71
SOUTH
TO REMAIN
WB 71
TO REMAIN
WB 71
TO REMAIN
WB 71




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'-c/c |
| TAPER | 60'-c/c |
| RAMP DELINEATION | 20'-c/c |

**LEGEND**

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 6A STEP 1
# STA. 1064+00.00 TO STA. 1081+00.00


DESIGN AGENCY
Jacobs

DESIGNED SRH
REVIEWED BAP 03/20/26
PROJECT ID 109164
SHEET P.178 TOTAL 618

FRA-71-19.10

MODEL: CU_071 - Plan 2 PAPERSIZE: ISO A3 (+) DATE: 3/31/2026 TIME: 11:13:24 AM FSTORY: CHSOT_PDF_U-LARGE_FSTITEL: CHSOT_Plan.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHSOTCIVD2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\FRA\71\109164\Design\Roadway\Plans\FRA-71-19.10_MOT_Phase 2 Step 1.dgn




TYPICAL SECTION - PHASE 6A STEP 1
STA. 1089+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 6A STEP 1
# STA. 1081+00.00 TO STA. 1098+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.179 TOTAL: 618

FRA-71-19.10

MODEL: CU_071 - Plan | PAINTSIZE: 36x24in | DATE: 3/31/2026 TIME: 11:13:15 AM FITDIM: ONEOFF_PDF_FI-LatSQ_FITSTYL: ONEOFF_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHICOTTLV02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: C:\Projects\Fra-71-19.10\Design\Roadway\Plans\Maintenance of Traffic\Phase 6A\FRA-71-19.10_MOT_PHASE 6A STEP 1.dgn




TYPICAL SECTION - PHASE 6A STEP 2
STA. 1061+00 IR-71

NOTE: SEE SHEET P.5S FOR PHASE 6A STEP 2 NB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 6A STEP 2
# STA. 1047+00.00 TO STA. 1064+00.00

DESIGN AGENCY
Jacobs


DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.180 TOTAL: 618


FRA-71-19.10


MODEL: CU_071 - Plan | RWYMODEL: FRA-71-19.10 | DATE: 3/31/2026 TIME: 11:13:43 AM FEATURE_ON:OFF_OFF_P-LAYER_PSHTEL_ON:OFF_OFF_P-LAYER_PSHTEL_ON:OFF | USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCIVIL3D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Ohio\FRA\71-19.10\Design\Roadway\Plan and Profile\Maintenance of Traffic\Phase 6A\FRA-71-19.10_MOT_PH6A_STEP2.dgn

FRA-71-19.10

MODEL: CU_071 - Plot 2 PAPERSIZE: ISO A1 (841.0 x 594.0 mm) DATE: 3/31/2026 TIME: 11:13:49 AM FSTORY: CHSOT_PDF_U-LARGE_PENTBL: CHSOT_Pen.ctb USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHSOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL. THIS FILE IS PROTECTED BY COPYRIGHT LAW AND INTERNATIONAL TREATIES. UNAUTHORIZED REPRODUCTION AND DISTRIBUTION OF THIS FILE, OR ANY PORTION OF IT, MAY RESULT IN SEVERE CIVIL AND CRIMINAL PENALTIES, AND WILL BE PROSECUTED TO THE MAXIMUM EXTENT POSSIBLE UNDER THE LAW.


W1-H16-36
STA. 1073+50
STA. 1074+50
STA. 1075+50
STA. 1076+50
MATCH LINE STA. 1064+00
MATCH LINE STA. 1081+00
IR 71 SB
℄ CONST. I-71
IR 71 NB
17TH AVE TO 71 SB
71 NB TO 17TH AVE
71 SB TO 17TH AVE
17TH AVE TO 71 NB
17TH AVE.
11th Ave
51th Ave
TO REMAIN
19:1 PCB TAPER
WORK ZONE CHANNELIZING LINE
WORK ZONE EDGE LINE
DRUMS AT 20' C/C
IMPACT ATTENUATOR PER SCD MT-101.75
MATCH EXISTING PAVEMENT MARKINGS STA. 1070+50
400' SHIFT TAPER
490' SHIFT TAPER
+91 28.5' RT.
+88 28.5' RT.
Hudson St
EXIT 112
17th Ave
EXIT 111
EXIT 111
TO REMAIN
TO REMAIN
TO REMAIN




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 6A STEP 2
# STA. 1081+00.00 TO STA. 1098+00.00

DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.182
TOTAL: 618

FRA-71-19.10

MODEL: CU_071 - Plan | PAYSHEETS: 60x24 in | SHEET: 3/31/2026 TIME: 11:11:55 AM FSTORY: CHSOT_PDF_U = pltSB_FSHTEL: CHSOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHSOTTEXAS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE: P:\Projects\Fra\71\109164\Design\Roadway\Plan\Sheets\FRA-71-19.10_MOT_P182_MAINTENANCE OF TRAFFIC - PHASE 6A STEP 2 STA. 1081+00.00 TO STA. 1098+00.00.dgn




TYPICAL SECTION - PHASE 6B STEP 1
STA. 1068+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

MAINTENANCE OF TRAFFIC - PHASE 6B STEP 1
STA. 1067+00.00 TO 1084+00.00

DESIGN AGENCY
Jacobs

DESIGNER
SRH

REVIEWER
BAP 03/20/26


PROJECT ID
109164


SHEET
P.183

TOTAL
618

FRA-71-19.10

MODEL: Phase 6B Step 1 - Sheet 1 MARKER: 66x48 (in.) DATE: 3/17/2026 TIME: 11:14:13 AM PLOTBY: CHHOFF PSF: 24 plotSg PENTBL: CHHOFF_Penn50 USER: Chris.Lawrence@jacobs.com WORKSPACE: CHHOFF/CAD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
K:\Projects\109164-ProjectDevelopment\Roadway\Design\Traffic\Phase 6\Phase 6B\Step 1\FRA-71-19.10 MOT Phase 6B Step 1.dgn




TYPICAL SECTION - PHASE 6B STEP 1
STA. 1102+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 6B STEP 1
# STA. 1084+00.00 TO STA. 1101+00.00

DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.184
TOTAL: 618

FRA-71-19.10

MODEL: Phase 6B Step 1 - Sheet 2 MARKER: 66x48 (in.) UNIT: 3/1/2026 TIME: 11:14:17 AM PITSPA ON/OFF: ZPP_P_1.shtg PENTBL ON/OFF: Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: ON/OFF/CKVD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE PROJECT: Projects\Active\FRA\71\FRA-71-19.10 Phase 6B\Design\Roadway\Plan\FRA-71-19.10 Phase 6B Step 1.dgn




TYPICAL SECTION - PHASE 6B STEP 1
STA. 1105+00 IR-71

NOTE: SEE SHEET P.64 FOR PHASE 6B STEP 1 SB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 6B STEP 1
# STA. 1101+00.00 TO STA. 1118+00.00


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.185 TOTAL: 618

FRA-71-19.10

MODEL: Phase 6B Step 1 - Sheet 9 MAINFILE: 66x48.tbl DATE: 3/11/2026 TIME: 11:14:18 AM PLTDRV: DWGDIF.PSF_P-A.pltcfg PENTBL: DWGDIF_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: ONDOTCKAS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. THIS FILE IS PROVIDED BY BENTLEY AS AN ACCOMMODATION AND CONTAINS NO WARRANTIES.




TYPICAL SECTION - PHASE 6B STEP 2
STA. 1072+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


MAINTENANCE OF TRAFFIC - PHASE 6B STEP 2
STA. 1067+00.00 TO STA. 1084+00.00

FRA-71-19.10

MODEL: Phase 6B Step 2 - Sheet 1 MARKER: 66x44 (in.) DATE: 3/11/2026 TIME: 11:14:53 AM PETERS DROOPT_ZPP_F.ipmlg PENTEL DROOPT_Pen.ctb USER: Chris.Lawrence@jacobs.com WORKSPACE: DROOTCK65 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE: P:\Projects\Ohio\Franklin\FRA-71-19.10\Design\Roadway\Plan Sheets\FRA-71-19.10 MOT Phase 6B Step 2.dgn

DESIGN AGENCY
Jacobs
DESIGNER
SRH
REVIEWER
BAP 03/20/26
PROJECT ID
109164
SHEET P.186 TOTAL 618




TYPICAL SECTION - PHASE 6B STEP 2
STA. 1086+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 6B STEP 2
# STA. 1084+00.00 TO STA. 1101+00.00

DESIGN AGENCY: Jacobs
DESIGNED: SRH
REVIEWED: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.187
TOTAL: 618

FRA-71-19.10

MODEL: Phase 6B Step 2 - Sheet 7 MARKER: 66x48 (in.) DATE: 3/17/2026 TIME: 11:14:37 AM PETERS CHRISTOPHER PLOTTED BY: CHRISTOPHER.PETERS@JACOBS.COM WORKSPACE: CHRISTOPHER.PETERS@JACOBS.COM WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\109164\Highway\Design\Roadway\Sheets\FRA-71-19.10_MOT_Phase 6B Step 2 - Sheet 7.dgn




TYPICAL SECTION - PHASE 6B STEP 2
STA. 1105+00 IR-71

NOTE: SEE SHEET P.64 FOR PHASE 6B STEP 2 SB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 6B STEP 2
## STA. 1101+00.00 TO STA. 1118+00.00

DESIGN AGENCY
Jacobs


DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.188 TOTAL: 618


FRA-71-19.10

MODEL: Phase 6B Step 2 - Sheet 9 MARKER: 66x48 (in.) DATE: 3/11/2026 TIME: 11:14:38 AM PEN/DRV: CMYOPT.CPP_FY.ctb/fig PENTBL: CMYOPT_Pen.tbl USER: CHris.Lawrence@jacobs.com WORKSPACE: CMYOPT/CMYOPT WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\Projects\FRA\71\109164\Design\Roadway\Traffic\Phase 6B\Step 2\Sheet 9 - Phase 6B Step 2.dgn

FRA-71-19.10

MODEL: Phase 7A Step 1 - Sheet 1 MARKER: 66x48 (in.) DATE: 3/11/2026 TIME: 3:29:03 PM PLTDRV: DWG.PC (LaserJet PCL6) PLOTTED: DWG.PC (LaserJet 1018) CivilLawrence1@jacobs.com WORKSPACE: C:\ROOT\SUD WORKSET: 109164 PRODUCT: OpenRoad Designer 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 JACOBS SOLUTIONS INC. THIS DRAWING IS THE PROPRIETARY PROPERTY OF JACOBS AND IS NOT TO BE USED FOR ANY PURPOSE OTHER THAN THE SPECIFIC PROJECT FOR WHICH IT WAS PREPARED. NO OTHER USE, REPRODUCTION, OR DISCLOSURE IS AUTHORIZED WITHOUT THE PRIOR WRITTEN CONSENT OF JACOBS.




NOTE: SEE SHEET P.56 FOR PHASE 7A STEPS 1 AND 3 NB ADVANCED SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND


- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 7A STEPS 1 & 3
## STA. 1072+50.00 TO STA. 1089+50.00

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.189 TOTAL 618




| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 7A STEPS 1 & 3
# STA. 1089+50.00 TO STA. 1106+50.00


DESIGN AGENCY
Jacobs


DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.190 TOTAL: 618

FRA-71-19.10

MODEL: Phase 7A Step 1 - Sheet 2 MARKER: 66x48 (in.) UNIT: 317/2503 TIME: 11:15:55 AM PTOPR ONDOT .PSF_P.config PENTBL ONDOT .Pen.tbl USER: CHris.Lawrence@jacobs.com WORKSPACE: ONDOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Fra\71\109164\Design\Roadway\Plans\Maintenance of Traffic\Phase 7A\Phase 7A Step 1 - Sheet 2.dgn


W1-H16-36
STA. 1106+77
STA. 1107+77
STA. 1108+77
STA. 1109+77
STA. 1110+77
STA. 1111+77
STA. 1112+77
A
MATCH LINE STA. 1106+50
1107
1108
1109
1110
1111
1112
1113
1114
1115
1116
1117
1118
1119
1120
1121
1122
1123
TRAFFIC ATTENUATOR PER SCD MT-101.75
19:1 PCB TAPER
WORK ZONE EDGE LINE
WORK ZONE CHANNELIZING LINE
19:1 PCB TAPER
+03 29.5' RT.
33.5'
12'
17'±
SEE NOTES
+70 29.5' RT.
19:1 PCB TAPER
70'
1023' SHIFT TAPER
698' SHIFT TAPER
+00
+68
168'
MATCH EXISTING PAVEMENT MARKINGS STA. 1125+68
℄ CONST. I-71
IR 71 SB
IR 71 NB
HAMPTON PARK DR.
TO REMAIN
SOUTH
71
EXIT 99 B
German Village
SOUTH
TO REMAIN
TO REMAIN
TO REMAIN




TYPICAL SECTION - PHASE 7A STEPS 2 AND 4
STA. 1102+00 IR-71

NOTE: SEE SHEET P.56 FOR PHASE 7A STEPS 2 AND 4 ADVANCE WARNING SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 7A STEPS 2 & 4
# STA. 1089+50.00 TO STA. 1106+50.00

FRA-71-19.10

MODEL: Phase 7A Step 2 - Sheet 2 MARKER: 66x48 (in.) DATE: 3/31/2026 TIME: 11:15:13 AM PTDWN ONDOT_CPD_F.ctb FILENAME: ONDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: ONDOTCivil3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25

DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.192
TOTAL: 618




TYPICAL SECTION - PHASE 7A STEPS 2 AND 4
STA. 1121+50 IR-71

NOTES:
1. REPLACE APPROACH SLABS IN STEP 2.
2. INSTALL SDC OVERLAY IN STEP 4.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 7A STEPS 2 & 4
# STA. 1106+50.00 TO STA. 1123+50.00

FRA-71-19.10


MODEL: Phase 7A Step 2 - Sheet 9 MARKER: 66x48 (in.) DATE: 3/11/2026 TIME: 11:15:18 AM PTDWG GROUP: CPP_F.ctb[Pg PENTBL GROUP: Pen-USE USER: Chris.Lawrence@jacobs.com WORKSPACE: 0HDOTCVS0 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\Projects\Iowa DOT\Maintenance of Traffic\Phase 7A\Sheets\FRA-71-19.10 Phase 7A Step 2 - Sheet 9.dgn


DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.193 TOTAL: 618




TYPICAL SECTION - PHASE 7B STEPS 1 AND 3
STA. 1114+50 IR-71

NOTES:
1. REPLACE APPROACH SLABS IN STEP 1.
2. INSTALL SDC OVERLAY IN STEP 3.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'-c/c |
| TAPER | 60'-c/c |
| RAMP DELINEATION | 20'-c/c |

LEGEND
- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


MAINTENANCE OF TRAFFIC - PHASE 7B STEPS 1 & 3
STA. 1103+00.00 TO STA. 1120+00.00

DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.194 TOTAL: 618

FRA-71-19.10

MODEL: Phase 5 Step 1 - Sheet 1 IMPERIOUS: 66x34 (in.) DATE: 3/17/2026 TIME: 11:55:46 AM PLOTBY: CHRISTOPHER.JOY.JP-LEGAL PENTBL: CHRIST_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHRISTOS43 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: P:\109164\Roadway\Plan Sheets\Maintenance of Traffic\Phase 7B\FRA-71-19.10 MOT Phase 7B Steps 1 & 3.dgn




TYPICAL SECTION - PHASE 7B STEPS 1 AND 3
STA. 1124+50 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 7B STEPS 1 & 3
# STA. 1120+00.00 TO STA. 1137+00.00

DESIGN AGENCY: Jacobs
DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.195
TOTAL: 618

FRA-71-19.10

MODEL: Phase 5 Steps 1 - Sheet 2 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:25:46 PM PITDRV_CHDOT_PDF_P-Letter.tbl PITPEN_CHDOT_PDF_P-Letter.tbl PITTBL: CHDOT_Pencil 100% Chris.Lawrence@jacobs.com WORKSPACE: CHDOTCIVIL3D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. Copyright (c) 2026 by Bentley Systems, Incorporated or one of its direct or indirect wholly owned subsidiaries. This model and drawing is the property of Bentley Systems, Incorporated or one of its direct or indirect wholly owned subsidiaries and is protected by copyright and trade secret laws.







TYPICAL SECTION - PHASE 7B STEPS 1 AND 3
STA. 1140+00 IR-71

NOTE: SEE SHEET P.65 FOR PHASE 7B STEPS 1 AND 3 SB ADVANCE WARNING SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120'c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 7B STEPS 1 & 3
# STA. 1137+00.00 TO STA. 1154+00.00


DESIGN AGENCY
Jacobs


DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.196 TOTAL: 618

FRA-71-19.10

MODEL: Phase 5 Steps 1 - Sheet 3 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 11:15:54 AM PITDAY: ONDOT_PSI_E-ARCH_PENTBL: ONDOT_PSI_E-ARCH_PITDAY: ONDOT_PSI_E-ARCH_PENTBL: ONDOT_PSI_E-ARCH_PLOTSTYLE: Full color USER: ChrisLawrence1@jacobs.com WORKSPACE: ONDOTSIGS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE: Phase 5 Steps 1 - Sheet 3 REFERENCES: C:\Users\ChrisLawrence1\Jacobs\Ohio DOT - Documents\Projects\FRA-71-19.10\Design\Roadway\Signing\FRA-71-19.10_MOT_Phase 5 Steps 1 - Sheet 3.dgn


W1-H16-36
STA. 1116+30
STA. 1117+30
STA. 1118+30
STA. 1119+30
A
MATCH EXISTING PAVEMENT MARKINGS STA. 1104+91
509' SHIFT TAPER
530' SHIFT TAPER
WORK ZONE CHANNELIZING LINE
WORK ZONE EDGE LINE
TO REMAIN
TO REMOVE
SEE NOTES
+72 29.0' LT.
+00 29.0' LT.
HIAWATHA PARK DR.
SOUTH 71
IR 71 SB
IR 71 NB
℄ CONST. I-71
MATCH LINE STA. 1120+00
19:1 PCB TAPER
03
1104
1105
1106
1107
1108
1109
1110
1111
1112
1113
1114
1115
1116
1117
1118
1119
NBX 7.4" 10.5"
2'
12'
Radius 5'
Radius 10'
Radius 20'
Radius 30'
Radius 40'
Radius 50'
Radius 60'
Radius 70'
Radius 80'
Radius 90'
Radius 100'
Radius 110'
Radius 120'
Radius 130'
Radius 140'
Radius 150'
Radius 160'
Radius 170'
Radius 180'
Radius 190'
Radius 200'
Radius 210'
Radius 220'
Radius 230'
Radius 240'
Radius 250'
Radius 260'
Radius 270'
Radius 280'
Radius 290'
Radius 300'
Radius 310'
Radius 320'
Radius 330'
Radius 340'
Radius 350'
Radius 360'
Radius 370'
Radius 380'
Radius 390'
Radius 400'
Radius 410'
Radius 420'
Radius 430'
Radius 440'
Radius 450'
Radius 460'
Radius 470'
Radius 480'
Radius 490'
Radius 500'
Radius 510'
Radius 520'
Radius 530'
Radius 540'
Radius 550'
Radius 560'
Radius 570'
Radius 580'
Radius 590'
Radius 600'
Radius 610'
Radius 620'
Radius 630'
Radius 640'
Radius 650'
Radius 660'
Radius 670'
Radius 680'
Radius 690'
Radius 700'
Radius 710'
Radius 720'
Radius 730'
Radius 740'
Radius 750'
Radius 760'
Radius 770'
Radius 780'
Radius 790'
Radius 800'
Radius 810'
Radius 820'
Radius 830'
Radius 840'
Radius 850'
Radius 860'
Radius 870'
Radius 880'
Radius 890'
Radius 900'
Radius 910'
Radius 920'
Radius 930'
Radius 940'
Radius 950'
Radius 960'
Radius 970'
Radius 980'
Radius 990'
Radius 1000'
Radius 1010'
Radius 1020'
Radius 1030'
Radius 1040'
Radius 1050'
Radius 1060'
Radius 1070'
Radius 1080'
Radius 1090'
Radius 1100'
Radius 1110'
Radius 1120'
Radius 1130'
Radius 1140'
Radius 1150'
Radius 1160'
Radius 1170'
Radius 1180'
Radius 1190'
Radius 1200'
Radius 1210'
Radius 1220'
Radius 1230'
Radius 1240'
Radius 1250'
Radius 1260'
Radius 1270'
Radius 1280'
Radius 1290'
Radius 1300'
Radius 1310'
Radius 1320'
Radius 1330'
Radius 1340'
Radius 1350'
Radius 1360'
Radius 1370'
Radius 1380'
Radius 1390'
Radius 1400'
Radius 1410'
Radius 1420'
Radius 1430'
Radius 1440'
Radius 1450'
Radius 1460'
Radius 1470'
Radius 1480'
Radius 1490'
Radius 1500'
Radius 1510'
Radius 1520'
Radius 1530'
Radius 1540'
Radius 1550'
Radius 1560'
Radius 1570'
Radius 1580'
Radius 1590'
Radius 1600'
Radius 1610'
Radius 1620'
Radius 1630'
Radius 1640'
Radius 1650'
Radius 1660'
Radius 1670'
Radius 1680'
Radius 1690'
Radius 1700'
Radius 1710'
Radius 1720'
Radius 1730'
Radius 1740'
Radius 1750'
Radius 1760'
Radius 1770'
Radius 1780'
Radius 1790'
Radius 1800'
Radius 1810'
Radius 1820'
Radius 1830'
Radius 1840'
Radius 1850'
Radius 1860'
Radius 1870'
Radius 1880'
Radius 1890'
Radius 1900'
Radius 1910'
Radius 1920'
Radius 1930'
Radius 1940'
Radius 1950'
Radius 1960'
Radius 1970'
Radius 1980'
Radius 1990'
Radius 2000'
Radius 2010'
Radius 2020'
Radius 2030'
Radius 2040'
Radius 2050'
Radius 2060'
Radius 2070'
Radius 2080'
Radius 2090'
Radius 2100'
Radius 2110'
Radius 2120'
Radius 2130'
Radius 2140'
Radius 2150'
Radius 2160'
Radius 2170'
Radius 2180'
Radius 2190'
Radius 2200'
Radius 2210'
Radius 2220'
Radius 2230'
Radius 2240'
Radius 2250'
Radius 2260'
Radius 2270'
Radius 2280'
Radius 2290'
Radius 2300'
Radius 2310'
Radius 2320'
Radius 2330'
Radius 2340'
Radius 2350'
Radius 2360'
Radius 2370'
Radius 2380'
Radius 2390'
Radius 2400'
Radius 2410'
Radius 2420'
Radius 2430'
Radius 2440'
Radius 2450'
Radius 2460'
Radius 2470'
Radius 2480'
Radius 2490'
Radius 2500'
Radius 2510'
Radius 2520'
Radius 2530'
Radius 2540'
Radius 2550'
Radius 2560'
Radius 2570'
Radius 2580'
Radius 2590'
Radius 2600'
Radius 2610'
Radius 2620'
Radius 2630'
Radius 2640'
Radius 2650'
Radius 2660'
Radius 2670'
Radius 2680'
Radius 2690'
Radius 2700'
Radius 2710'
Radius 2720'
Radius 2730'
Radius 2740'
Radius 2750'
Radius 2760'
Radius 2770'
Radius 2780'
Radius 2790'
Radius 2800'
Radius 2810'
Radius 2820'
Radius 2830'
Radius 2840'
Radius 2850'
Radius 2860'
Radius 2870'
Radius 2880'
Radius 2890'
Radius 2900'
Radius 2910'
Radius 2920'
Radius 2930'
Radius 2940'
Radius 2950'
Radius 2960'
Radius 2970'
Radius 2980'
Radius 2990'
Radius 3000'
Radius 3010'
Radius 3020'
Radius 3030'
Radius 3040'
Radius 3050'
Radius 3060'
Radius 3070'
Radius 3080'
Radius 3090'
Radius 3100'
Radius 3110'
Radius 3120'
Radius 3130'
Radius 3140'
Radius 3150'
Radius 3160'
Radius 3170'
Radius 3180'
Radius 3190'
Radius 3200'
Radius 3210'
Radius 3220'
Radius 3230'
Radius 3240'
Radius 3250'
Radius 3260'
Radius 3270'
Radius 3280'
Radius 3290'
Radius 3300'
Radius 3310'
Radius 3320'
Radius 3330'
Radius 3340'
Radius 3350'
Radius 3360'
Radius 3370'
Radius 3380'
Radius 3390'
Radius 3400'
Radius 3410'
Radius 3420'
Radius 3430'
Radius 3440'
Radius 3450'
Radius 3460'
Radius 3470'
Radius 3480'
Radius 3490'
Radius 3500'
Radius 3510'
Radius 3520'
Radius 3530'
Radius 3540'
Radius 3550'
Radius 3560'
Radius 3570'
Radius 3580'
Radius 3590'
Radius 3600'
Radius 3610'
Radius 3620'
Radius 3630'
Radius 3640'
Radius 3650'
Radius 3660'
Radius 3670'
Radius 3680'
Radius 3690'
Radius 3700'
Radius 3710'
Radius 3720'
Radius 3730'
Radius 3740'
Radius 3750'
Radius 3760'
Radius 3770'
Radius 3780'
Radius 3790'
Radius 3800'
Radius 3810'
Radius 3820'
Radius 3830'
Radius 3840'
Radius 3850'
Radius 3860'
Radius 3870'
Radius 3880'
Radius 3890'
Radius 3900'
Radius 3910'
Radius 3920'
Radius 3930'
Radius 3940'
Radius 3950'
Radius 3960'
Radius 3970'
Radius 3980'
Radius 3990'
Radius 4000'
Radius 4010'
Radius 4020'
Radius 4030'
Radius 4040'
Radius 4050'
Radius 4060'
Radius 4070'
Radius 4080'
Radius 4090'
Radius 4100'
Radius 4110'
Radius 4120'
Radius 4130'
Radius 4140'
Radius 4150'
Radius 4160'
Radius 4170'
Radius 4180'
Radius 4190'
Radius 4200'
Radius 4210'
Radius 4220'
Radius 4230'
Radius 4240'
Radius 4250'
Radius 4260'
Radius 4270'
Radius 4280'
Radius 4290'
Radius 4300'
Radius 4310'
Radius 4320'
Radius 4330'
Radius 4340'
Radius 4350'
Radius 4360'
Radius 4370'
Radius 4380'
Radius 4390'
Radius 4400'
Radius 4410'
Radius 4420'
Radius 4430'
Radius 4440'
Radius 4450'
Radius 4460'
Radius 4470'
Radius 4480'
Radius 4490'
Radius 4500'
Radius 4510'
Radius 4520'
Radius 4530'
Radius 4540'
Radius 4550'
Radius 4560'
Radius 4570'
Radius 4580'
Radius 4590'
Radius 4600'
Radius 4610'
Radius 4620'
Radius 4630'
Radius 4640'
Radius 4650'
Radius 4660'
Radius 4670'
Radius 4680'
Radius 4690'
Radius 4700'
Radius 4710'
Radius 4720'
Radius 4730'
Radius 4740'
Radius 4750'
Radius 4760'
Radius 4770'
Radius 4780'
Radius 4790'
Radius 4800'
Radius 4810'
Radius 4820'
Radius 4830'
Radius 4840'
Radius 4850'
Radius 4860'
Radius 4870'
Radius 4880'
Radius 4890'
Radius 4900'
Radius 4910'
Radius 4920'
Radius 4930'
Radius 4940'
Radius 4950'
Radius 4960'
Radius 4970'
Radius 4980'
Radius 4990'
Radius 5000'
Radius 5010'
Radius 5020'
Radius 5030'
Radius 5040'
Radius 5050'
Radius 5060'
Radius 5070'
Radius 5080'
Radius 5090'
Radius 5100'
Radius 5110'
Radius 5120'
Radius 5130'
Radius 5140'
Radius 5150'
Radius 5160'
Radius 5170'
Radius 5180'
Radius 5190'
Radius 5200'
Radius 5210'
Radius 5220'
Radius 5230'
Radius 5240'
Radius 5250'
Radius 5260'
Radius 5270'
Radius 5280'
Radius 5290'
Radius 5300'
Radius 5310'
Radius 5320'
Radius 5330'
Radius 5340'
Radius 5350'
Radius 5360'
Radius 5370'
Radius 5380'
Radius 5390'
Radius 5400'
Radius 5410'
Radius 5420'
Radius 5430'
Radius 5440'
Radius 5450'
Radius 5460'
Radius 5470'
Radius 5480'
Radius 5490'
Radius 5500'
Radius 5510'
Radius 5520'
Radius 5530'
Radius 5540'
Radius 5550'
Radius 5560'
Radius 5570'
Radius 5580'
Radius 5590'
Radius 5600'
Radius 5610'
Radius 5620'
Radius 5630'
Radius 5640'
Radius 5650'
Radius 5660'
Radius 5670'
Radius 5680'
Radius 5690'
Radius 5700'
Radius 5710'
Radius 5720'
Radius 5730'
Radius 5740'
Radius 5750'
Radius 5760'
Radius 5770'
Radius 5780'
Radius 5790'
Radius 5800'
Radius 5810'
Radius 5820'
Radius 5830'
Radius 5840'
Radius 5850'
Radius 5860'
Radius 5870'
Radius 5880'
Radius 5890'
Radius 5900'
Radius 5910'
Radius 5920'
Radius 5930'
Radius 5940'
Radius 5950'
Radius 5960'
Radius 5970'
Radius 5980'
Radius 5990'
Radius 6000'
Radius 6010'
Radius 6020'
Radius 6030'
Radius 6040'
Radius 6050'
Radius 6060'
Radius 6070'
Radius 6080'
Radius 6090'
Radius 6100'
Radius 6110'
Radius 6120'
Radius 6130'
Radius 6140'
Radius 6150'
Radius 6160'
Radius 6170'
Radius 6180'
Radius 6190'
Radius 6200'
Radius 6210'
Radius 6220'
Radius 6230'
Radius 6240'
Radius 6250'
Radius 6260'
Radius 6270'
Radius 6280'
Radius 6290'
Radius 6300'
Radius 6310'
Radius 6320'
Radius 6330'
Radius 6340'
Radius 6350'
Radius 6360'
Radius 6370'
Radius 6380'
Radius 6390'
Radius 6400'
Radius 6410'
Radius 6420'
Radius 6430'
Radius 6440'
Radius 6450'
Radius 6460'
Radius 6470'
Radius 6480'
Radius 6490'
Radius 6500'
Radius 6510'
Radius 6520'
Radius 6530'
Radius 6540'
Radius 6550'
Radius 6560'
Radius 6570'
Radius 6580'
Radius 6590'
Radius 6600'
Radius 6610'
Radius 6620'
Radius 6630'
Radius 6640'
Radius 6650'
Radius 6660'
Radius 6670'
Radius 6680'
Radius 6690'
Radius 6700'
Radius 6710'
Radius 6720'
Radius 6730'
Radius 6740'
Radius 6750'
Radius 6760'
Radius 6770'
Radius 6780'
Radius 6790'
Radius 6800'
Radius 6810'
Radius 6820'
Radius 6830'
Radius 6840'
Radius 6850'
Radius 6860'
Radius 6870'
Radius 6880'
Radius 6890'
Radius 6900'
Radius 6910'
Radius 6920'
Radius 6930'
Radius 6940'
Radius 6950'
Radius 6960'
Radius 6970'
Radius 6980'
Radius 6990'
Radius 7000'
Radius 7010'
Radius 7020'
Radius 7030'
Radius 7040'
Radius 7050'
Radius 7060'
Radius 7070'
Radius 7080'
Radius 7090'
Radius 7100'
Radius 7110'
Radius 7120'
Radius 7130'
Radius 7140'
Radius 7150'
Radius 7160'
Radius 7170'
Radius 7180'
Radius 7190'
Radius 7200'
Radius 7210'
Radius 7220'
Radius 7230'
Radius 7240'
Radius 7250'
Radius 7260'
Radius 7270'
Radius 7280'
Radius 7290'
Radius 7300'
Radius 7310'
Radius 7320'
Radius 7330'
Radius 7340'
Radius 7350'
Radius 7360'
Radius 7370'
Radius 7380'
Radius 7390'
Radius 7400'
Radius 7410'
Radius 7420'
Radius 7430'
Radius 7440'
Radius 7450'
Radius 7460'
Radius 7470'
Radius 7480'
Radius 7490'
Radius 7500'
Radius 7510'
Radius 7520'
Radius 7530'
Radius 7540'
Radius 7550'
Radius 7560'
Radius 7570'
Radius 7580'
Radius 7590'
Radius 7600'
Radius 7610'
Radius 7620'
Radius 7630'
Radius 7640'
Radius 7650'
Radius 7660'
Radius 7670'
Radius 7680'
Radius 7690'
Radius 7700'
Radius 7710'
Radius 7720'
Radius 7730'
Radius 7740'
Radius 7750'
Radius 7760'
Radius 7770'
Radius 7780'
Radius 7790'
Radius 7800'
Radius 7810'
Radius 7820'
Radius 7830'
Radius 7840'
Radius 7850'
Radius 7860'
Radius 7870'
Radius 7880'
Radius 7890'
Radius 7900'
Radius 7910'
Radius 7920'
Radius 7930'
Radius 7940'
Radius 7950'
Radius 7960'
Radius 7970'
Radius 7980'
Radius 7990'
Radius 8000'
Radius 8010'
Radius 8020'
Radius 8030'
Radius 8040'
Radius 8050'
Radius 8060'
Radius 8070'
Radius 8080'
Radius 8090'
Radius 8100'
Radius 8110'
Radius 8120'
Radius 8130'
Radius 8140'
Radius 8150'
Radius 8160'
Radius 8170'
Radius 8180'
Radius 8190'
Radius 8200'
Radius 8210'
Radius 8220'
Radius 8230'
Radius 8240'
Radius 8250'
Radius 8260'
Radius 8270'
Radius 8280'
Radius 8290'
Radius 8300'
Radius 8310'
Radius 8320'
Radius 8330'
Radius 8340'
Radius 8350'
Radius 8360'
Radius 8370'
Radius 8380'
Radius 8390'
Radius 8400'
Radius 8410'
Radius 8420'
Radius 8430'
Radius 8440'
Radius 8450'
Radius 8460'
Radius 8470'
Radius 8480'
Radius 8490'
Radius 8500'
Radius 8510'
Radius 8520'
Radius 8530'
Radius 8540'
Radius 8550'
Radius 8560'
Radius 8570'
Radius 8580'
Radius 8590'
Radius 8600'
Radius 8610'
Radius 8620'
Radius 8630'
Radius 8640'
Radius 8650'
Radius 8660'
Radius 8670'
Radius 8680'
Radius 8690'
Radius 8700'
Radius 8710'
Radius 8720'
Radius 8730'
Radius 8740'
Radius 8750'
Radius 8760'
Radius 8770'
Radius 8780'
Radius 8790'
Radius 8800'
Radius 8810'
Radius 8820'
Radius 8830'
Radius 8840'
Radius 8850'
Radius 8860'
Radius 8870'
Radius 8880'
Radius 8890'
Radius 8900'
Radius 8910'
Radius 8920'
Radius 8930'
Radius 8940'
Radius 8950'
Radius 8960'
Radius 8970'
Radius 8980'
Radius 8990'
Radius 9000'
Radius 9010'
Radius 9020'
Radius 9030'
Radius 9040'
Radius 9050'
Radius 9060'
Radius 9070'
Radius 9080'
Radius 9090'
Radius 9100'
Radius 9110'
Radius 9120'
Radius 9130'
Radius 9140'
Radius 9150'
Radius 9160'
Radius 9170'
Radius 9180'
Radius 9190'
Radius 9200'
Radius 9210'
Radius 9220'
Radius 9230'
Radius 9240'
Radius 9250'
Radius 9260'
Radius 9270'
Radius 9280'
Radius 9290'
Radius 9300'
Radius 9310'
Radius 9320'
Radius 9330'
Radius 9340'
Radius 9350'
Radius 9360'
Radius 9370'
Radius 9380'
Radius 9390'
Radius 9400'
Radius 9410'
Radius 9420'
Radius 9430'
Radius 9440'
Radius 9450'
Radius 9460'
Radius 9470'
Radius 9480'
Radius 9490'
Radius 9500'
Radius 9510'
Radius 9520'
Radius 9530'
Radius 9540'
Radius 9550'
Radius 9560'
Radius 9570'
Radius 9580'
Radius 9590'
Radius 9600'
Radius 9610'
Radius 9620'
Radius 9630'
Radius 9640'
Radius 9650'
Radius 9660'
Radius 9670'
Radius 9680'
Radius 9690'
Radius 9700'
Radius 9710'
Radius 9720'
Radius 9730'
Radius 9740'
Radius 9750'
Radius 9760'
Radius 9770'
Radius 9780'
Radius 9790'
Radius 9800'
Radius 9810'
Radius 9820'
Radius 9830'
Radius 9840'
Radius 9850'
Radius 9860'
Radius 9870'
Radius 9880'
Radius 9890'
Radius 9900'
Radius 9910'
Radius 9920'
Radius 9930'
Radius 9940'
Radius 9950'
Radius 9960'
Radius 9970'
Radius 9980'
Radius 9990'
Radius 10000'
Radius 10010'
Radius 10020'
Radius 10030'
Radius 10040'
Radius 10050'
Radius 10060'
Radius 10070'
Radius 10080'
Radius 10090'
Radius 10100'
Radius 10110'
Radius 10120'
Radius 10130'
Radius 10140'
Radius 10150'
Radius 10160'
Radius 10170'
Radius 10180'
Radius 10190'
Radius 10200'
Radius 10210'
Radius 10220'
Radius 10230'
Radius 10240'
Radius 10250'
Radius 10260'
Radius 10270'
Radius 10280'
Radius 10290'
Radius 10300'
Radius 10310'
Radius 10320'
Radius 10330'
Radius 10340'
Radius 10350'
Radius 10360'
Radius 10370'
Radius 10380'
Radius 10390'
Radius 10400'
Radius 10410'
Radius 10420'
Radius 10430'
Radius 10440'
Radius 10450'
Radius 10460'
Radius 10470'
Radius 10480'
Radius 10490'
Radius 10500'
Radius 10510'
Radius 10520'
Radius 10530'
Radius 10540'
Radius 10550'
Radius 10560'
Radius 10570'
Radius 10580'
Radius 10590'
Radius 10600'
Radius 10610'
Radius 10620'
Radius 10630'
Radius 10640'
Radius 10650'
Radius 10660'
Radius 10670'
Radius 10680'
Radius 10690'
Radius 10700'
Radius 10710'
Radius 10720'
Radius 10730'
Radius 10740'
Radius 10750'
Radius 10760'
Radius 10770'
Radius 10780'
Radius 10790'
Radius 10800'
Radius 10810'
Radius 10820'
Radius 10830'
Radius 10840'
Radius 10850'
Radius 10860'
Radius 10870'
Radius 10880'
Radius 10890'
Radius 10900'
Radius 10910'
Radius 10920'
Radius 10930'
Radius 10940'
Radius 10950'
Radius 10960'
Radius 10970'
Radius 10980'
Radius 10990'
Radius 11000'
Radius 11010'
Radius 11020'
Radius 11030'
Radius 11040'
Radius 11050'
Radius 11060'
Radius 11070'
Radius 11080'
Radius 11090'
Radius 11100'
Radius 11110'
Radius 11120'
Radius 11130'
Radius 11140'
Radius 11150'
Radius 11160'
Radius 11170'
Radius 11180'
Radius 11190'
Radius 11200'
Radius 11210'
Radius 11220'
Radius 11230'
Radius 11240'
Radius 11250'
Radius 11260'
Radius 11270'
Radius 11280'
Radius 11290'
Radius 11300'
Radius 11310'
Radius 11320'
Radius 11330'
Radius 11340'
Radius 11350'
Radius 11360'
Radius 11370'
Radius 11380'
Radius 11390'
Radius 11400'
Radius 11410'
Radius 11420'
Radius 11430'
Radius 11440'
Radius 11450'
Radius 11460'
Radius 11470'
Radius 11480'
Radius 11490'
Radius 11500'
Radius 11510'
Radius 11520'
Radius 11530'
Radius 11540'
Radius 11550'
Radius 11560'
Radius 11570'
Radius 11580'
Radius 11590'
Radius 11600'
Radius 11610'
Radius 11620'
Radius 11630'
Radius 11640'
Radius 11650'
Radius 11660'
Radius 11670'
Radius 11680'
Radius 11690'
Radius 11700'
Radius 11710'
Radius 11720'
Radius 11730'
Radius 11740'
Radius 11750'
Radius 11760'
Radius 11770'
Radius 11780'
Radius 11790'
Radius 11800'
Radius 11810'
Radius 11820'
Radius 11830'
Radius 11840'
Radius 11850'
Radius 11860'
Radius 11870'
Radius 11880'
Radius 11890'
Radius 11900'
Radius 11910'
Radius 11920'
Radius 11930'
Radius 11940'
Radius 11950'
Radius 11960'
Radius 11970'
Radius 11980'
Radius 11990'
Radius 12000'
Radius 12010'
Radius 12020'
Radius 12030'
Radius 12040'
Radius 12050'
Radius 12060'
Radius 12070'
Radius 12080'
Radius 12090'
Radius 12100'
Radius 12110'
Radius 12120'
Radius 12130'
Radius 12140'
Radius 12150'
Radius 12160'
Radius 12170'
Radius 12180'
Radius 12190'
Radius 12200'
Radius 12210'
Radius 12220'
Radius 12230'
Radius 12240'
Radius 12250'
Radius 12260'
Radius 12270'
Radius 12280'
Radius 12290'
Radius 12300'
Radius 12310'
Radius 12320'
Radius 12330'
Radius 12340'
Radius 12350'
Radius 12360'
Radius 12370'
Radius 12380'
Radius 12390'
Radius 12400'
Radius 12410'
Radius 12420'
Radius 12430'
Radius 12440'
Radius 12450'
Radius 12460'
Radius 12470'
Radius 12480'
Radius 12490'
Radius 12500'
Radius 12510'
Radius 12520'
Radius 12530'
Radius 12540'
Radius 12550'
Radius 12560'
Radius 12570'
Radius 12580'
Radius 12590'
Radius 12600'
Radius 12610'
Radius 12620'
Radius 12630'
Radius 12640'
Radius 12650'
Radius 12660'
Radius 12670'
Radius 12680'
Radius 12690'
Radius 12700'
Radius 12710'
Radius 12720'
Radius 12730'
Radius 12740'
Radius 12750'
Radius 12760'
Radius 12770'
Radius 12780'
Radius 12790'
Radius 12800'
Radius 12810'
Radius 12820'
Radius 12830'
Radius 12840'
Radius 12850'
Radius 12860'
Radius 12870'
Radius 12880'
Radius 12890'
Radius 12900'
Radius 12910'
Radius 12920'
Radius 12930'
Radius 12940'
Radius 12950'
Radius 12960'
Radius 12970'
Radius 12980'
Radius 12990'
Radius 13000'
Radius 13010'
Radius 13020'
Radius 13030'
Radius 13040'
Radius 13050'
Radius 13060'
Radius 13070'
Radius 13080'
Radius 13090'
Radius 13100'
Radius 13110'
Radius 13120'
Radius 13130'
Radius 13140'
Radius 13150'
Radius 13160'
Radius 13170'
Radius 13180'
Radius 13190'
Radius 13200'
Radius 13210'
Radius 13220'
Radius 13230'
Radius 13240'
Radius 13250'
Radius 13260'
Radius 13270'
Radius 13280'
Radius 13290'
Radius 13300'
Radius 13310'
Radius 13320'
Radius 13330'
Radius 13340'
Radius 13350'
Radius 13360'
Radius 13370'
Radius 13380'
Radius 13390'
Radius 13400'
Radius 13410'
Radius 13420'
Radius 13430'
Radius 13440'
Radius 13450'
Radius 13460'
Radius 13470'
Radius 13480'
Radius 13490'
Radius 13500'
Radius 13510'
Radius 13520'
Radius 13530'
Radius 13540'
Radius 13550'
Radius 13560'
Radius 13570'
Radius 13580'
Radius 13590'
Radius 13600'
Radius 13610'
Radius 13620'
Radius 13630'
Radius 13640'
Radius 13650'
Radius 13660'
Radius 13670'
Radius 13680'
Radius 13690'
Radius 13700'
Radius 13710'
Radius 13720'
Radius 13730'
Radius 13740'
Radius 13750'
Radius 13760'
Radius 13770'
Radius 13780'
Radius 13790'
Radius 13800'
Radius 13810'
Radius 13820'
Radius 13830'
Radius 13840'
Radius 13850'
Radius 13860'
Radius 13870'
Radius 13880'
Radius 13890'
Radius 13900'
Radius 13910'
Radius 13920'
Radius 13930'
Radius 13940'
Radius 13950'
Radius 13960'
Radius 13970'
Radius 13980'
Radius 13990'
Radius 14000'
Radius 14010'
Radius 14020'
Radius 14030'
Radius 14040'
Radius 14050'
Radius 14060'
Radius 14070'
Radius 14080'
Radius 14090'
Radius 14100'
Radius 14110'
Radius 14120'
Radius 14130'
Radius 14140'
Radius 14150'
Radius 14160'
Radius 14170'
Radius 14180'
Radius 14190'
Radius 14200'
Radius 14210'
Radius 14220'
Radius 14230'
Radius 14240'
Radius 14250'
Radius 14260'
Radius 14270'
Radius 14280'
Radius 14290'
Radius 14300'
Radius 14310'
Radius 14320'
Radius 14330'
Radius 14340'
Radius 14350'
Radius 14360'
Radius 14370'
Radius 14380'
Radius 14390'
Radius 14400'
Radius 14410'
Radius 14420'
Radius 14430'
Radius 14440'
Radius 14450'
Radius 14460'
Radius 14470'
Radius 14480'
Radius 14490'
Radius 14500'
Radius 14510'
Radius 14520'
Radius 14530'
Radius 14540'
Radius 14550'
Radius 14560'
Radius 14570'
Radius 14580'
Radius 14590'
Radius 14600'
Radius 14610'
Radius 14620'
Radius 14630'
Radius 14640'
Radius 14650'
Radius 14660'
Radius 14670'
Radius 14680'
Radius 14690'
Radius 14700'
Radius 14710'
Radius 14720'
Radius 14730'
Radius 14740'
Radius 14750'
Radius 14760'
Radius 14770'
Radius 14780'
Radius 14790'
Radius 14800'
Radius 14810'
Radius 14820'
Radius 14830'
Radius 14840'
Radius 14850'
Radius 14860'
Radius 14870'
Radius 14880'
Radius 14890'
Radius 14900'
Radius 14910'
Radius 14920'
Radius 14930'
Radius 14940'
Radius 14950'
Radius 14960'
Radius 14970'
Radius 14980'
Radius 14990'
Radius 15000'
Radius 15010'
Radius 15020'
Radius 15030'
Radius 15040'
Radius 15050'
Radius 15060'
Radius 15070'
Radius 15080'
Radius 15090'
Radius 15100'
Radius 15110'
Radius 15120'
Radius 15130'
Radius 15140'
Radius 15150'
Radius 15160'
Radius 15170'
Radius 15180'
Radius 15190'
Radius 15200'
Radius 15210'
Radius 15220'
Radius 15230'
Radius 15240'
Radius 15250'
Radius 15260'
Radius 15270'
Radius 15280'
Radius 15290'
Radius 15300'
Radius 15310'
Radius 15320'
Radius 15330'
Radius 15340'
Radius 15350'
Radius 15360'
Radius 15370'
Radius 15380'
Radius 15390'
Radius 15400'
Radius 15410'
Radius 15420'
Radius 15430'
Radius 15440'
Radius 15450'
Radius 15460'
Radius 15470'
Radius 15480'
Radius 15490'
Radius 15500'
Radius 15510'
Radius 15520'
Radius 15530'
Radius 15540'
Radius 15550'
Radius 15560'
Radius 15570'
Radius 15580'
Radius 15590'
Radius 15600'
Radius 15610'
Radius 15620'
Radius 15630'
Radius 15640'
Radius 15650'
Radius 15660'
Radius 15670'
Radius 15680'
Radius 15690'
Radius 15700'
Radius 15710'
Radius 15720'
Radius 15730'
Radius 15740'
Radius 15750'
Radius 15760'
Radius 15770'
Radius 15780'
Radius 15790'
Radius 15800'
Radius 15810'
Radius 15820'
Radius 15830'
Radius 15840'
Radius 15850'
Radius 15860'
Radius 15870'
Radius 15880'
Radius 15890'
Radius 15900'
Radius 15910'
Radius 15920'
Radius 15930'
Radius 15940'
Radius 15950'
Radius 15960'
Radius 15970'
Radius 15980'
Radius 15990'
Radius 16000'
Radius 16010'
Radius 16020'
Radius 16030'
Radius 16040'
Radius 16050'
Radius 16060'
Radius 16070'
Radius 16080'
Radius 16090'
Radius 16100'
Radius 16110'
Radius 16120'
Radius 16130'
Radius 16140'
Radius 16150'
Radius 16160'
Radius 16170'
Radius 16180'
Radius 16190'
Radius 16200'
Radius 16210'
Radius 16220'
Radius 16230'
Radius 16240'
Radius 16250'
Radius 16260'
Radius 16270'
Radius 16280'
Radius 16290'
Radius 16300'
Radius 16310'
Radius 16320'
Radius 16330'
Radius 16340'
Radius 16350'
Radius 16360'
Radius 16370'
Radius 16380'
Radius 16390'
Radius 16400'
Radius 16410'
Radius 16420'
Radius 16430'
Radius 16440'
Radius 16450'
Radius 16460'
Radius 16470'
Radius 16480'
Radius 16490'
Radius 16500'
Radius 16510'
Radius 16520'
Radius 16530'
Radius 16540'
Radius 16550'
Radius 16560'
Radius 16570'
Radius 16580'
Radius 16590'
Radius 16600'
Radius 16610'
Radius 16620'
Radius 16630'
Radius 16640'
Radius 16650'
Radius 16660'
Radius 16670'
Radius 16680'
Radius 16690'
Radius 16700'
Radius 16710'
Radius 16720'
Radius 16730'
Radius 16740'
Radius 16750'
Radius 16760'
Radius 16770'
Radius 16780'
Radius 16790'
Radius 16800'
Radius 16810'
Radius 16820'
Radius 16830'
Radius 16840'
Radius 16850'
Radius 16860'
Radius 16870'
Radius 16880'
Radius 16890'
Radius 16900'
Radius 16910'
Radius 16920'
Radius 16930'
Radius 16940'
Radius 16950'
Radius 16960'
Radius 16970'
Radius 16980'
Radius 16990'
Radius 17000'
Radius 17010'
Radius 17020'
Radius 17030'
Radius 17040'
Radius 17050'
Radius 17060'
Radius 17070'
Radius 17080'
Radius 17090'
Radius 17100'
Radius 17110'
Radius 17120'
Radius 17130'
Radius 17140'
Radius 17150'
Radius 17160'
Radius 17170'
Radius 17180'
Radius 17190'
Radius 17200'
Radius 17210'
Radius 17220'
Radius 17230'
Radius 17240'
Radius 17250'
Radius 17260'
Radius 17270'
Radius 17280'
Radius 17290'
Radius 17300'
Radius 17310'
Radius 17320'
Radius 17330'
Radius 17340'
Radius 17350'
Radius 17360'
Radius 17370'
Radius 17380'
Radius 17390'
Radius 17400'
Radius 17410'
Radius 17420'
Radius 17430'
Radius 17440'
Radius 17450'
Radius 17460'
Radius 17470'
Radius 17480'
Radius 17490'
Radius 17500'
Radius 17510'
Radius 17520'
Radius 17530'
Radius 17540'
Radius 17550'
Radius 17560'
Radius 17570'
Radius 17580'
Radius 17590'
Radius 17600'
Radius 17610'
Radius 17620'
Radius 17630'
Radius 17640'
Radius 17650'
Radius 17660'
Radius 17670'
Radius 17680'
Radius 17690'
Radius 17700'
Radius 17710'
Radius 17720'
Radius 17730'
Radius 17740'
Radius 17750'
Radius 17760'
Radius 17770'
Radius 17780'
Radius 17790'
Radius 17800'
Radius 17810'
Radius 17820'
Radius 17830'
Radius 17840'
Radius 17850'
Radius 17860'
Radius 17870'
Radius 17880'
Radius 17890'
Radius 17900'
Radius 17910'
Radius 17920'
Radius 17930'
Radius 17940'
Radius 17950'
Radius 17960'
Radius 17970'
Radius 17980'
Radius 17990'
Radius 18000'
Radius 18010'
Radius 18020'
Radius 18030'
Radius 18040'
Radius 18050'
Radius 18060'
Radius 18070'
Radius 18080'
Radius 18090'
Radius 18100'
Radius 18110'
Radius 18120'
Radius 18130'
Radius 18140'
Radius 18150'
Radius 18160'
Radius 18170'
Radius 18180'
Radius 18190'
Radius 18200'
Radius 18210'
Radius 18220'
Radius 18230'
Radius 18240'
Radius 18250'
Radius 18260'
Radius 18270'
Radius 18280'
Radius 18290'
Radius 18300'
Radius 18310'
Radius 18320'
Radius 18330'
Radius 18340'
Radius 18350'
Radius 18360'
Radius 18370'
Radius 18380'
Radius 18390'
Radius 18400'
Radius 18410'
Radius 18420'
Radius 18430'
Radius 18440'
Radius 18450'
Radius 18460'
Radius 18470'
Radius 18480'
Radius 18490'
Radius 18500'
Radius 18510'
Radius 18520'
Radius 18530'
Radius 18540'
Radius 18550'
Radius 18560'
Radius 18570'
Radius 18580'
Radius 18590'
Radius 18600'
Radius 18610'
Radius 18620'
Radius 18630'
Radius 18640'
Radius 18650'
Radius 18660'
Radius 18670'
Radius 18680'
Radius 18690'
Radius 18700'
Radius 18710'
Radius 18720'
Radius 18730'
Radius 18740'
Radius 18750'
Radius 18760'
Radius 18770'
Radius 18780'
Radius 18790'
Radius 18800'
Radius 18810'
Radius 18820'
Radius 18830'
Radius 18840'
Radius 18850'
Radius 18860'
Radius 18870'
Radius 18880'
Radius 18890'
Radius 18900'
Radius 18910'
Radius 18920'
Radius 18930'
Radius 18940'
Radius 18950'
Radius 18960'
Radius 18970'
Radius 18980'
Radius 18990'
Radius 19000'
Radius 19010'
Radius 19020'
Radius 19030'
Radius 19040'
Radius 19050'
Radius 19060'
Radius 19070'
Radius 19080'
Radius 19090'
Radius 19100'
Radius 19110'
Radius 19120'
Radius 19130'
Radius 19140'
Radius 19150'
Radius 19160'
Radius 19170'
Radius 19180'
Radius 19190'
Radius 19200'
Radius 19210'
Radius 19220'
Radius 19230'
Radius 19240'
Radius 19250'
Radius 19260'
Radius 19270'
Radius 19280'
Radius 19290'
Radius 19300'
Radius 19310'
Radius 19320'
Radius 19330'
Radius 19340'
Radius 19350'
Radius 19360'
Radius 19370'
Radius 19380'
Radius 19390'
Radius 19400'
Radius 19410'
Radius 19420'
Radius 19430'
Radius 19440'
Radius 19450'
Radius 19460'
Radius 19470'
Radius 19480'
Radius 19490'
Radius 19500'
Radius 19510'
Radius 19520'
Radius 19530'
Radius 19540'
Radius 19550'
Radius 19560'
Radius 19570'
Radius 19580'
Radius 19590'
Radius 19600'
Radius 19610'
Radius 19620'
Radius 19630'
Radius 19




TYPICAL SECTION - PHASE 7B STEPS 2 AND 4
STA. 1123+00 IR-71

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60 c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT


HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 7B STEPS 2 & 4
# STA. 1120+00.00 TO STA. 1137+00.00

FRA-71-19.10

MODEL: CU_I71 | Plan: 2 PHASE7B STEP2 AND 4.dgn | DATE: 3/31/2026 TIME: 1:33:19 PM | USER: CROOT_PW | Path: C:\Users\croot_pw\Desktop\Projects\109164 PHASE 7B\Design\Roadway\MOT\PHASE 7B STEP 2 AND 4.dgn
ELEMENTS FROM REFERENCE FILES: Plan: P:\109164 PHASE 7B\Design\Roadway\MOT\PHASE 7B STEP 2 AND 4.dgn | Level: All | Color: All | Font: All | Dimension: All | Text: All | Multi-line Text: All | Point: All | Cell: All | Line Style: All | Line Weight: All

DESIGN AGENCY
Jacobs
DESIGNER
SRH
REVIEWER
BAP 03/20/26
PROJECT ID
109164
SHEET P.198 TOTAL 618




TYPICAL SECTION - PHASE 7B STEPS 2 AND 4
STA. 1138+00 IR-71

NOTE: SEE SHEET P.65 FOR PHASE 7B STEPS 2 AND 4 SB ADVANCE WARNING SIGNING PLAN.

| DRUM SPACING CHART | |
|---|---|
| TANGENT | 120' c/c |
| TAPER | 60' c/c |
| RAMP DELINEATION | 20' c/c |

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 7B STEPS 2 & 4
# STA. 1137+00.00 TO STA. 1154+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.199 TOTAL: 618

FRA-71-19.10

MODEL: C0 / P3 | Plan 3 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 11:16:16 AM PLTDRV: DHDOT_PDF_V1.drv PLTSTYL: DHDOT_Plot.ctb USER: ChrisLawrence3@jacobs.com WORKSPACE: DHDOTCAD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DRAWINGS ARE THE PROPERTY OF THE OHIO DEPARTMENT OF TRANSPORTATION. THEY ARE NOT TO BE USED FOR ANY PURPOSE WITHOUT THE WRITTEN PERMISSION OF THE OHIO DEPARTMENT OF TRANSPORTATION.




*NOTES:*
*1. CONTRACTOR MAY CLOSE LEFT TURN LANES AS SHOWN DURING NON-PEAK HOURS ONLY WITH WRITTEN PERMISSION FROM THE ENGINEER.*
*2. COVER ALL CONFLICTING SIGNS.*
*3. SEE TRAFFIC CONTROL PLAN FOR EXISTING SIGNS.*
*4. PROVIDE A 14 DAY ADVANCE NOTICE TO THE CITY OF COLUMBUS TO COORDINATE TEMPORARY ADJUSTMENTS TO THE EXISTING TRAFFIC SIGNAL TIMING.*

*LEGEND*

- *PHASE WORK ZONE*
- *DRUMS*
- *PORTABLE BARRIER*
- *TEMPORARY PAVEMENT*
- *IMPACT ATTENUATOR*
- *DIRECTION OF TRAVEL*
- *TYPE III BARRICADE*
- *TEMPORARY SIGN SUPPORT*

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 8B STEP 1
# SR 161 OUTSIDE RECONSTRUCTION

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.200 TOTAL: 618

FRA-71-19.10

MODEL: 161 Phase 1 Sheet 1 PAYPSHEET: 66x34 IN | DATE: 3/12/2026 TIME: 11:14:33 AM | USER: CKirk | FILEPATH: C:\PROJECTS\FRA-71-19.10\CADD\MAINTENANCE OF TRAFFIC\MOT_PHS 1\MOT_PHS1B_STEP01_CMOT.dgn | USER: CKirk.bakerwood@jacobs.com WORKSPACE: CHDOTCIVIL WORKSET: DEV14 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BY JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES. THE INFORMATION CONTAINED HEREIN IS THE PROPRIETARY AND CONFIDENTIAL INFORMATION OF JACOBS OR ITS CLIENT AND MAY NOT BE USED, DISCLOSED OR REPRODUCED WITHOUT THE PRIOR WRITTEN AUTHORIZATION OF JACOBS OR ITS CLIENT.




FRA-71-19.10

MODEL: 161 Phase 1 Sheet 2 PAPERSIZE: 66x34 IN | DATE: 3/12/2026 TIME: 11:16:39 AM | FILTERV: ON OFF_PRE_14.pltcfg PENTBL: ON OFF_Pen.ctb USER: Chris.Isaiewicz@jacobs.com WORKSPACE: CHIDOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25


ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL INFORMATION. NOT FOR REPRODUCTION OR DISTRIBUTION.

HORIZONTAL SCALE IN FEET
0 15 30 60

MAINTENANCE OF TRAFFIC - PHASE 8B STEP 1
SR 161 OUTSIDE RECONSTRUCTION

DESIGN AGENCY
Jacobs

DESIGNER SRH
REVIEWER BAP 03/20/26
PROJECT ID 109164
SHEET P.201 TOTAL 618




NOTES:
1. CONTRACTOR MAY CLOSE LEFT TURN LANES AS SHOWN DURING NON-PEAK HOURS ONLY WITH WRITTEN PERMISSION FROM THE ENGINEER.
2. COVER ALL CONFLICTING SIGNS.
3. SEE TRAFFIC CONTROL PLAN FOR EXISTING SIGNS.
4. PROVIDE A 14 DAY ADVANCE NOTICE TO THE CITY OF COLUMBUS TO COORDINATE TEMPORARY ADJUSTMENTS TO THE EXISTING TRAFFIC SIGNAL TIMING.

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 8B STEP 1
# SR 161 OUTSIDE RECONSTRUCTION

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.202 TOTAL: 618

FRA-71-19.10

MODEL: 161 Phase 1 Sheet 1 XREFSDEC 6kx14 in 1 DATE: 3/12/2026 TIME: 11:14:44 AM SYSTEM: DHOOT_PRF_1-pltcfg PENTBL: DHOOT_Pen1st USER: Chris.Isaenhood@jacobs.com WORKSPACE: DHOOTSTAD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\109164\Highway\Roadway\Plans\MOT\161 Phase 1 Sheet 1.dgn




NOTES:
1. CONTRACTOR MAY CLOSE LEFT TURN LANES AS SHOWN DURING NON-PEAK HOURS ONLY WITH WRITTEN PERMISSION FROM THE ENGINEER.
2. COVER ALL CONFLICTING SIGNS.
3. SEE TRAFFIC CONTROL PLAN FOR EXISTING SIGNS.
4. PROVIDE A 14 DAY ADVANCE NOTICE TO THE CITY OF COLUMBUS TO COORDINATE TEMPORARY ADJUSTMENTS TO THE EXISTING TRAFFIC SIGNAL TIMING.

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 8B STEP 2
# SR 161 INSIDE RECONSTRUCTION

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.203 TOTAL: 618

FRA-71-19.10

MODEL: 161 Phase 2 Sheet 1 PAYFILE01 DGN 8 file 1 DATE: 3/12/2026 TIME: 11:16:45 AM USER: CHOOT_PID: 54 pPAGE PENTBL: CHOOT_Pen.tbl USER: Chris.Isaenko@jacobs.com WORKSPACE: CHOOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL INFORMATION CONTAINED HEREIN IS PROPRIETARY AND CONFIDENTIAL AND IS THE PROPERTY OF JACOBS AND/OR ITS CLIENT. ANY UNAUTHORIZED USE, DISCLOSURE, REPRODUCTION, OR DISTRIBUTION IS PROHIBITED.




NOTES:
1. CONTRACTOR MAY CLOSE LEFT TURN LANES AS SHOWN DURING NON-PEAK HOURS ONLY WITH WRITTEN PERMISSION FROM THE ENGINEER.
2. COVER ALL CONFLICTING SIGNS.
3. SEE TRAFFIC CONTROL PLAN FOR EXISTING SIGNS.
4. PROVIDE A 14 DAY ADVANCE NOTICE TO THE CITY OF COLUMBUS TO COORDINATE TEMPORARY ADJUSTMENTS TO THE EXISTING TRAFFIC SIGNAL TIMING.

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 8B STEP 2
# SR 161 INSIDE RECONSTRUCTION

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.204 TOTAL: 618

FRA-71-19.10

MODEL: 161 Phase 2 Sheet 2 (MAYERS) 66x34 in | DATE: 3/12/2026 TIME: 11:16:59 AM | FILTER: ON:OFF_PRE_14 xPHASE_ENTITIES: ON:OFF_Pre14 USER: Chris.Isaenhood@jacobs.com WORKSPACE: CHIDOTDist2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DRAWINGS ARE THE PROPERTY OF THE DEPARTMENT AND MAY NOT BE REPRODUCED OR USED WITHOUT THE DEPARTMENT'S PERMISSION




*NOTES:*
*1. CONTRACTOR MAY CLOSE LEFT TURN LANES AS SHOWN DURING NON-PEAK HOURS ONLY WITH WRITTEN PERMISSION FROM THE ENGINEER.*
*2. COVER ALL CONFLICTING SIGNS.*
*3. SEE TRAFFIC CONTROL PLAN FOR EXISTING SIGNS.*
*4. PROVIDE A 14 DAY ADVANCE NOTICE TO THE CITY OF COLUMBUS TO COORDINATE TEMPORARY ADJUSTMENTS TO THE EXISTING TRAFFIC SIGNAL TIMING.*

*LEGEND*

- *PHASE WORK ZONE*
- *DRUMS*
- *PORTABLE BARRIER*
- *TEMPORARY PAVEMENT*
- *IMPACT ATTENUATOR*
- *DIRECTION OF TRAVEL*
- *TYPE III BARRICADE*
- *TEMPORARY SIGN SUPPORT*

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 8B STEP 2
# SR 161 INSIDE RECONSTRUCTION

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.205 TOTAL: 618

FRA-71-19.10

MODEL: 161 Phase 2 Sheet 3 XREFMODEL: 66x34 in. DATE: 3/12/2026 TIME: 11:14:51 AM XREFs: DATUM: DATUM_PRE_14.dgnlib XREFBL: DATUM_PRE_14.dgn DGN: DATUM_PRE_14.dgn USER: Chris.Isaenko@jacobs.com WORKSPACE: CHIDOTCIVIL3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DRAWINGS ARE THE PROPERTY OF THE DEPARTMENT AND MAY NOT BE REPRODUCED OR USED WITHOUT THE PERMISSION OF THE DEPARTMENT





FRA-71-19.10

MAINTENANCE OF TRAFFIC - PHASE 1
SR 161 WATERLINE RELOCATION

DESIGN AGENCY
Jacobs

DESIGNED: SRH
REVIEWED: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.206 TOTAL: 618

MODEL: 161 Phase 3 | SHEET: 661x419 in | DATE: 3/12/2026 TIME: 11:16:53 AM | USER: DHOUT_PID_14.pltcfg | PENTBL: DHOUT_PID_14.ctb | USER: DNickbarnes4@jacobs.com WORKSPACE: DHOUT(Civil) WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: C:\Users\dnickbarnes4\Jacobs\Documents - FRA-71-19.10 Waterline Relocation\Working\Phase 3\161 Phase 3.dgn




NOTES:
1. COVER ALL CONFLICTING SIGNS.
2. SEE TRAFFIC CONTROL PLAN FOR EXISTING SIGNS.

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60

# MAINTENANCE OF TRAFFIC - PHASE 1
# SR 161 WATERLINE RELOCATION

DESIGN AGENCY
Jacobs

DESIGNER
SRH


REVIEWER
BAP 03/20/26

PROJECT ID
109164

SHEET P.207 TOTAL 618

FRA-71-19.10

MODEL: 161 Phase 2 SHEET: 66x34 in. DATE: 3/12/2026 TIME: 11:16:57 AM SYSTEM: OHDOT_PID_24.dgnlib ENTITY: OHDOT_PID_24 USER: Chris.Isaenko@jacobs.com WORKSPACE: CHDOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: C:\Users\Chris.Isaenko\Jacobs\Desktop\Projects\109164 - FRA-71-19.10 SR 161 Waterline Relocation\Design\Roadway\Traffic\Maintenance of Traffic.dgn




NOTES:
1. INSTALL LANE CLOSURE DURING NON PEAK HOURS ONLY WITH WRITTEN APPROVAL FROM THE ENGINEER.
2. MAINTAIN AT LEAST ONE SIDEWALK AT ALL TIMES. DIVERT PEDESTRIAN TRAFFIC TO OPPOSITE SIDE OF THE ROAD WHILE CLOSED.
3. COVER ALL CONFLICTING SIGNS.
4. SEE TRAFFIC CONTROL PLAN FOR EXISTING SIGNS.
5. PROVIDE A 14 DAY ADVANCE NOTICE TO THE CITY OF COLUMBUS TO COORDINATE TEMPORARY ADJUSTMENTS TO THE EXISTING TRAFFIC SIGNAL TIMING.
6. PROVIDE PCB DIRECTLY BEHIND THE SIDEWALK, FOR PHASES 3 AND 4.

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 8A STEP 1
# MORSE ROAD OUTSIDE RECONSTRUCTION

DESIGN AGENCY
Jacobs

DESIGNED: SRH
REVIEWED: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.208 TOTAL: 618

FRA-71-19.10

MODEL: Morse Phase 1 - Sheet 1 PAPERSIZE: 66x34 (in.) DATE: 3/17/2026 TIME: 11:16:54 AM PLOTBY: DHOOT_PW PLOTSTYLE: DHOOT_PW.ctb USER: ChrisLawrence1@jacobs.com WORKSPACE: DHOOTD4D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\109164\Design\Roadway\Morse Phase 1\Sheet 1.dgn




NOTES:
1. INSTALL LANE CLOSURE DURING NON PEAK HOURS ONLY WITH WRITTEN APPROVAL FROM THE ENGINEER.
2. MAINTAIN AT LEAST ONE SIDEWALK AT ALL TIMES. DIVERT PEDESTRIAN TRAFFIC TO OPPOSITE SIDE OF THE ROAD WHILE CLOSED.
3. COVER ALL CONFLICTING SIGNS.
4. SEE TRAFFIC CONTROL PLAN FOR EXISTING SIGNS.
5. PROVIDE A 14 DAY ADVANCE NOTICE TO THE CITY OF COLUMBUS TO COORDINATE TEMPORARY ADJUSTMENTS TO THE EXISTING TRAFFIC SIGNAL TIMING.

LEGEND

- PHASE WORK ZONE
- DRUMS
- PORTABLE BARRIER
- TEMPORARY PAVEMENT
- IMPACT ATTENUATOR
- DIRECTION OF TRAVEL
- TYPE III BARRICADE
- TEMPORARY SIGN SUPPORT

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 8A STEP 1
# MORSE ROAD OUTSIDE RECONSTRUCTION


DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.209 TOTAL: 618

FRA-71-19.10

MODEL: Morse Phase 1 - Sheet 2 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 11:17:04 AM USER: CHRIS PORTAL: C:\HOST_dm.dat USER: ChrisLawrence1@jacobs.com WORKSPACE: C:\HOST\OUO WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: C:\Users\chrislawrence1\Jacobs\Desktop\Morse Phase 1 - Sheet 2.dgn


INDIANOLA AVE.
PORT WILLIAM ST.
€ CONST. MORSE RD
€ SINCLAIR RD
INDIANOLA AVE.
W20.5-36
STA. 40+00
Type A
Warning Light
W20.5-36
STA. 46+00
Type A
Warning Light
R3-2-30
STA. 48+75
SEE NOTE 1
M4-8-24
M3-1-24
M1-1-24-2
M6-3-21
STA. 48+67
R3-2-30
STA. 49+67
R3-2-30
STA. 51+25
R3-2-30
STA. 51+35
DRUMS AT 20' C/C (TYP)
M6-3-21
STA. 51+45
M1-1-24-2
M3-1-24
M4-8-24
DETOUR
NORTH
71
IR 71 SB
IR 71 NB
€ CONST. I-71
€ CONST. MORSE RD RAMP B
MORSE RD TO 71 NB
200' MERGE TAPER WITH 20' DRUM SPACING
FLASHING ARROW BOARD
MATCH LINE STA. 54+00
€ CONST. MORSE RD RAMP C
71 NB TO MORSE RD
€ CONST. MORSE RD RAMP D
MORSE RD TO 71 SB
42
43
44
45
46
47
48
49
50
51
52
53
5313
5312
5311
5310
5309
4312
4311
4310
4309
3318
3317
3316
3315
3314
1442
1446
1448
1450
1452
1454
1456
1458
1460
1462
1464
1466
1468
1470
1472
1474
1476
1478
1480
1482
1484
1486
1488
1490
1492
1494
1496
1498
1500
1502
1504
1506
1508
1510
1512
1514
1516
1518
1520
1522
1524
1526
1528
1530
1532
1534
1536
1538
1540
1542
1544
1546
1548
1550
1552
1554
1556
1558
1560
1562
1564
1566
1568
1570
1572
1574
1576
1578
1580
1582
1584
1586
1588
1590
1592
1594
1596
1598
1600
1602
1604
1606
1608
1610
1612
1614
1616
1618
1620
1622
1624
1626
1628
1630
1632
1634
1636
1638
1640
1642
1644
1646
1648
1650
1652
1654
1656
1658
1660
1662
1664
1666
1668
1670
1672
1674
1676
1678
1680
1682
1684
1686
1688
1690
1692
1694
1696
1698
1700
1702
1704
1706
1708
1710
1712
1714
1716
1718
1720
1722
1724
1726
1728
1730
1732
1734
1736
1738
1740
1742
1744
1746
1748
1750
1752
1754
1756
1758
1760
1762
1764
1766
1768
1770
1772
1774
1776
1778
1780
1782
1784
1786
1788
1790
1792
1794
1796
1798
1800
1802
1804
1806
1808
1810
1812
1814
1816
1818
1820
1822
1824
1826
1828
1830
1832
1834
1836
1838
1840
1842
1844
1846
1848
1850
1852
1854
1856
1858
1860
1862
1864
1866
1868
1870
1872
1874
1876
1878
1880
1882
1884
1886
1888
1890
1892
1894
1896
1898
1900
1902
1904
1906
1908
1910
1912
1914
1916
1918
1920
1922
1924
1926
1928
1930
1932
1934
1936
1938
1940
1942
1944
1946
1948
1950
1952
1954
1956
1958
1960
1962
1964
1966
1968
1970
1972
1974
1976
1978
1980
1982
1984
1986
1988
1990
1992
1994
1996
1998
2000
2002
2004
2006
2008
2010
2012
2014
2016
2018
2020
2022
2024
2026
2028
2030
2032
2034
2036
2038
2040
2042
2044
2046
2048
2050
2052
2054
2056
2058
2060
2062
2064
2066
2068
2070
2072
2074
2076
2078
2080
2082
2084
2086
2088
2090
2092
2094
2096
2098
2100
2102
2104
2106
2108
2110
2112
2114
2116
2118
2120
2122
2124
2126
2128
2130
2132
2134
2136
2138
2140
2142
2144
2146
2148
2150
2152
2154
2156
2158
2160
2162
2164
2166
2168
2170
2172
2174
2176
2178
2180
2182
2184
2186
2188
2190
2192
2194
2196
2198
2200
2202
2204
2206
2208
2210
2212
2214
2216
2218
2220
2222
2224
2226
2228
2230
2232
2234
2236
2238
2240
2242
2244
2246
2248
2250
2252
2254
2256
2258
2260
2262
2264
2266
2268
2270
2272
2274
2276
2278
2280
2282
2284
2286
2288
2290
2292
2294
2296
2298
2300
2302
2304
2306
2308
2310
2312
2314
2316
2318
2320
2322
2324
2326
2328
2330
2332
2334
2336
2338
2340
2342
2344
2346
2348
2350
2352
2354
2356
2358
2360
2362
2364
2366
2368
2370
2372
2374
2376
2378
2380
2382
2384
2386
2388
2390
2392
2394
2396
2398
2400
2402
2404
2406
2408
2410
2412
2414
2416
2418
2420
2422
2424
2426
2428
2430
2432
2434
2436
2438
2440
2442
2444
2446
2448
2450
2452
2454
2456
2458
2460
2462
2464
2466
2468
2470
2472
2474
2476
2478
2480
2482
2484
2486
2488
2490
2492
2494
2496
2498
2500
2502
2504
2506
2508
2510
2512
2514
2516
2518
2520
2522
2524
2526
2528
2530
2532
2534
2536
2538
2540
2542
2544
2546
2548
2550
2552
2554
2556
2558
2560
2562
2564
2566
2568
2570
2572
2574
2576
2578
2580
2582
2584
2586
2588
2590
2592
2594
2596
2598
2600
2602
2604
2606
2608
2610
2612
2614
2616
2618
2620
2622
2624
2626
2628
2630
2632
2634
2636
2638
2640
2642
2644
2646
2648
2650
2652
2654
2656
2658
2660
2662
2664
2666
2668
2670
2672
2674
2676
2678
2680
2682
2684
2686
2688
2690
2692
2694
2696
2698
2700
2702
2704
2706
2708
2710
2712
2714
2716
2718
2720
2722
2724
2726
2728
2730
2732
2734
2736
2738
2740
2742
2744
2746
2748
2750
2752
2754
2756
2758
2760
2762
2764
2766
2768
2770
2772
2774
2776
2778
2780
2782
2784
2786
2788
2790
2792
2794
2796
2798
2800
2802
2804
2806
2808
2810
2812
2814
2816
2818
2820
2822
2824
2826
2828
2830
2832
2834
2836
2838
2840
2842
2844
2846
2848
2850
2852
2854
2856
2858
2860
2862
2864
2866
2868
2870
2872
2874
2876
2878
2880
2882
2884
2886
2888
2890
2892
2894
2896
2898
2900
2902
2904
2906
2908
2910
2912
2914
2916
2918
2920
2922
2924
2926
2928
2930
2932
2934
2936
2938
2940
2942
2944
2946
2948
2950
2952
2954
2956
2958
2960
2962
2964
2966
2968
2970
2972
2974
2976
2978
2980
2982
2984
2986
2988
2990
2992
2994
2996
2998
3000
3002
3004
3006
3008
3010
3012
3014
3016
3018
3020
3022
3024
3026
3028
3030
3032
3034
3036
3038
3040
3042
3044
3046
3048
3050
3052
3054
3056
3058
3060
3062
3064
3066
3068
3070
3072
3074
3076
3078
3080
3082
3084
3086
3088
3090
3092
3094
3096
3098
3100
3102
3104
3106
3108
3110
3112
3114
3116
3118
3120
3122
3124
3126
3128
3130
3132
3134
3136
3138
3140
3142
3144
3146
3148
3150
3152
3154
3156
3158
3160
3162
3164
3166
3168
3170
3172
3174
3176
3178
3180
3182
3184
3186
3188
3190
3192
3194
3196
3198
3200
3202
3204
3206
3208
3210
3212
3214
3216
3218
3220
3222
3224
3226
3228
3230
3232
3234
3236
3238
3240
3242
3244
3246
3248
3250
3252
3254
3256
3258
3260
3262
3264
3266
3268
3270
3272
3274
3276
3278
3280
3282
3284
3286
3288
3290
3292
3294
3296
3298
3300
3302
3304
3306
3308
3310
3312
3314
3316
3318
3320
3322
3324
3326
3328
3330
3332
3334
3336
3338
3340
3342
3344
3346
3348
3350
3352
3354
3356
3358
3360
3362
3364
3366
3368
3370
3372
3374
3376
3378
3380
3382
3384
3386
3388
3390
3392
3394
3396
3398
3400
3402
3404
3406
3408
3410
3412
3414
3416
3418
3420
3422
3424
3426
3428
3430
3432
3434
3436
3438
3440
3442
3444
3446
3448
3450
3452
3454
3456
3458
3460
3462
3464
3466
3468
3470
3472
3474
3476
3478
3480
3482
3484
3486
3488
3490
3492
3494
3496
3498
3500
3502
3504
3506
3508
3510
3512
3514
3516
3518
3520
3522
3524
3526
3528
3530
3532
3534
3536
3538
3540
3542
3544
3546
3548
3550
3552
3554
3556
3558
3560
3562
3564
3566
3568
3570
3572
3574
3576
3578
3580
3582
3584
3586
3588
3590
3592
3594
3596
3598
3600
3602
3604
3606
3608
3610
3612
3614
3616
3618
3620
3622
3624
3626
3628
3630
3632
3634
3636
3638
3640
3642
3644
3646
3648
3650
3652
3654
3656
3658
3660
3662
3664
3666
3668
3670
3672
3674
3676
3678
3680
3682
3684
3686
3688
3690
3692
3694
3696
3698
3700
3702
3704
3706
3708
3710
3712
3714
3716
3718
3720
3722
3724
3726
3728
3730
3732
3734
3736
3738
3740
3742
3744
3746
3748
3750
3752
3754
3756
3758
3760
3762
3764
3766
3768
3770
3772
3774
3776
3778
3780
3782
3784
3786
3788
3790
3792
3794
3796
3798
3800
3802
3804
3806
3808
3810
3812
3814
3816
3818
3820
3822
3824
3826
3828
3830
3832
3834
3836
3838
3840
3842
3844
3846
3848
3850
3852
3854
3856
3858
3860
3862
3864
3866
3868
3870
3872
3874
3876
3878
3880
3882
3884
3886
3888
3890
3892
3894
3896
3898
3900
3902
3904
3906
3908
3910
3912
3914
3916
3918
3920
3922
3924
3926
3928
3930
3932
3934
3936
3938
3940
3942
3944
3946
3948
3950
3952
3954
3956
3958
3960
3962
3964
3966
3968
3970
3972
3974
3976
3978
3980
3982
3984
3986
3988
3990
3992
3994
3996
3998
4000
4002
4004
4006
4008
4010
4012
4014
4016
4018
4020
4022
4024
4026
4028
4030
4032
4034
4036
4038
4040
4042
4044
4046
4048
4050
4052
4054
4056
4058
4060
4062
4064
4066
4068
4070
4072
4074
4076
4078
4080
4082
4084
4086
4088
4090
4092
4094
4096
4098
4100
4102
4104
4106
4108
4110
4112
4114
4116
4118
4120
4122
4124
4126
4128
4130
4132
4134
4136
4138
4140
4142
4144
4146
4148
4150
4152
4154
4156
4158
4160
4162
4164
4166
4168
4170
4172
4174
4176
4178
4180
4182
4184
4186
4188
4190
4192
4194
4196
4198
4200
4202
4204
4206
4208
4210
4212
4214
4216
4218
4220
4222
4224
4226
4228
4230
4232
4234
4236
4238
4240
4242
4244
4246
4248
4250
4252
4254
4256
4258
4260
4262
4264
4266
4268
4270
4272
4274
4276
4278
4280
4282
4284
4286
4288
4290
4292
4294
4296
4298
4300
4302
4304
4306
4308
4310
4312
4314
4316
4318
4320
4322
4324
4326
4328
4330
4332
4334
4336
4338
4340
4342
4344
4346
4348
4350
4352
4354
4356
4358
4360
4362
4364
4366
4368
4370
4372
4374
4376
4378
4380
4382
4384
4386
4388
4390
4392
4394
4396
4398
4400
4402
4404
4406
4408
4410
4412
4414
4416
4418
4420
4422
4424
4426
4428
4430
4432
4434
4436
4438
4440
4442
4444
4446
4448
4450
4452
4454
4456
4458
4460
4462
4464
4466
4468
4470
4472
4474
4476
4478
4480
4482
4484
4486
4488
4490
4492
4494
4496
4498
4500
4502
4504
4506
4508
4510
4512
4514
4516
4518
4520
4522
4524
4526
4528
4530
4532
4534
4536
4538
4540
4542
4544
4546
4548
4550
4552
4554
4556
4558
4560
4562
4564
4566
4568
4570
4572
4574
4576
4578
4580
4582
4584
4586
4588
4590
4592
4594
4596
4598
4600
4602
4604
4606
4608
4610
4612
4614
4616
4618
4620
4622
4624
4626
4628
4630
4632
4634
4636
4638
4640
4642
4644
4646
4648
4650
4652
4654
4656
4658
4660
4662
4664
4666
4668
4670
4672
4674
4676
4678
4680
4682
4684
4686
4688
4690
4692
4694
4696
4698
4700
4702
4704
4706
4708
4710
4712
4714
4716
4718
4720
4722
4724
4726
4728
4730
4732
4734
4736
4738
4740
4742
4744
4746
4748
4750
4752
4754
4756
4758
4760
4762
4764
4766
4768
4770
4772
4774
4776
4778
4780
4782
4784
4786
4788
4790
4792
4794
4796
4798
4800
4802
4804
4806
4808
4810
4812
4814
4816
4818
4820
4822
4824
4826
4828
4830
4832
4834
4836
4838
4840
4842
4844
4846
4848
4850
4852
4854
4856
4858
4860
4862
4864
4866
4868
4870
4872
4874
4876
4878
4880
4882
4884
4886
4888
4890
4892
4894
4896
4898
4900
4902
4904
4906
4908
4910
4912
4914
4916
4918
4920
4922
4924
4926
4928
4930
4932
4934
4936
4938
4940
4942
4944
4946
4948
4950
4952
4954
4956
4958
4960
4962
4964
4966
4968
4970
4972
4974
4976
4978
4980
4982
4984
4986
4988
4990
4992
4994
4996
4998
5000
5002
5004
5006
5008
5010
5012
5014
5016
5018
5020
5022
5024
5026
5028
5030
5032
5034
5036
5038
5040
5042
5044
5046
5048
5050
5052
5054
5056
5058
5060
5062
5064
5066
5068
5070
5072
5074
5076
5078
5080
5082
5084
5086
5088
5090
5092
5094
5096
5098
5100
5102
5104
5106
5108
5110
5112
5114
5116
5118
5120
5122
5124
5126
5128
5130
5132
5134
5136
5138
5140
5142
5144
5146
5148
5150
5152
5154
5156
5158
5160
5162
5164
5166
5168
5170
5172
5174
5176
5178
5180
5182
5184
5186
5188
5190
5192
5194
5196
5198
5200
5202
5204
5206
5208
5210
5212
5214
5216
5218
5220
5222
5224
5226
5228
5230
5232
5234
5236
5238
5240
5242
5244
5246
5248
5250
5252
5254
5256
5258
5260
5262
5264
5266
5268
5270
5272
5274
5276
5278
5280
5282
5284
5286
5288
5290
5292
5294
5296
5298
5300
5302
5304
5306
5308
5310
5312
5314
5316
5318
5320
5322
5324
5326
5328
5330
5332
5334
5336
5338
5340
5342
5344
5346
5348
5350
5352
5354
5356
5358
5360
5362
5364
5366
5368
5370
5372
5374
5376
5378
5380
5382
5384
5386
5388
5390
5392
5394
5396
5398
5400
5402
5404
5406
5408
5410
5412
5414
5416
5418
5420
5422
5424
5426
5428
5430
5432
5434
5436
5438
5440
5442
5444
5446
5448
5450
5452
5454
5456
5458
5460
5462
5464
5466
5468
5470
5472
5474
5476
5478
5480
5482
5484
5486
5488
5490
5492
5494
5496
5498
5500
5502
5504
5506
5508
5510
5512
5514
5516
5518
5520
5522
5524
5526
5528
5530
5532
5534
5536
5538
5540
5542
5544
5546
5548
5550
5552
5554
5556
5558
5560
5562
5564
5566
5568
5570
5572
5574
5576
5578
5580
5582
5584
5586
5588
5590
5592
5594
5596
5598
5600
5602
5604
5606
5608
5610
5612
5614
5616
5618
5620
5622
5624
5626
5628
5630
5632
5634
5636
5638
5640
5642
5644
5646
5648
5650
5652
5654
5656
5658
5660
5662
5664
5666
5668
5670
5672
5674
5676
5678
5680
5682
5684
5686
5688
5690
5692
5694
5696
5698
5700
5702
5704
5706
5708
5710
5712
5714
5716
5718
5720
5722
5724
5726
5728
5730
5732
5734
5736
5738
5740
5742
5744
5746
5748
5750
5752
5754
5756
5758
5760
5762
5764
5766
5768
5770
5772
5774
5776
5778
5780
5782
5784
5786
5788
5790
5792
5794
5796
5798
5800
5802
5804
5806
5808
5810
5812
5814
5816
5818
5820
5822
5824
5826
5828
5830
5832
5834
5836
5838
5840
5842
5844
5846
5848
5850
5852
5854
5856
5858
5860
5862
5864
5866
5868
5870
5872
5874
5876
5878
5880
5882
5884
5886
5888
5890
5892
5894
5896
5898
5900
5902
5904
5906
5908
5910
5912
5914
5916
5918
5920
5922
5924
5926
5928
5930
5932
5934
5936
5938
5940
5942
5944
5946
5948
5950
5952
5954
5956
5958
5960
5962
5964
5966
5968
5970
5972
5974
5976
5978
5980
5982
5984
5986
5988
5990
5992
5994
5996
5998
6000
6002
6004
6006
6008
6010
6012
6014
6016
6018
6020
6022
6024
6026
6028
6030
6032
6034
6036
6038
6040
6042
6044
6046
6048
6050
6052
6054
6056
6058
6060
6062
6064
6066
6068
6070
6072
6074
6076
6078
6080
6082
6084
6086
6088
6090
6092
6094
6096
6098
6100
6102
6104
6106
6108
6110
6112
6114
6116
6118
6120
6122
6124
6126
6128
6130
6132
6134
6136
6138
6140
6142
6144
6146
6148
6150
6152
6154
6156
6158
6160
6162
6164
6166
6168
6170
6172
6174
6176
6178
6180
6182
6184
6186
6188
6190
6192
6194
6196
6198
6200
6202
6204
6206
6208
6210
6212
6214
6216
6218
6220
6222
6224
6226
6228
6230
6232
6234
6236
6238
6240
6242
6244
6246
6248
6250
6252
6254
6256
6258
6260
6262
6264
6266
6268
6270
6272
6274
6276
6278
6280
6282
6284
6286
6288
6290
6292
6294
6296
6298
6300
6302
6304
6306
6308
6310
6312
6314
6316
6318
6320
6322
6324
6326
6328
6330
6332
6334
6336
6338
6340
6342
6344
6346
6348
6350
6352
6354
6356
6358
6360
6362
6364
6366
6368
6370
6372
6374
6376
6378
6380
6382
6384
6386
6388
6390
6392
6394
6396
6398
6400
6402
6404
6406
6408
6410
6412
6414
6416
6418
6420
6422
6424
6426
6428
6430
6432
6434
6436
6438
6440
6442
6444
6446
6448
6450
6452
6454
6456
6458
6460
6462
6464
6466
6468
6470
6472
6474
6476
6478
6480
6482
6484
6486
6488
6490
6492
6494
6496
6498
6500
6502
6504
6506
6508
6510
6512
6514
6516
6518
6520
6522
6524
6526
6528
6530
6532
6534
6536
6538
6540
6542
6544
6546
6548
6550
6552
6554
6556
6558
6560
6562
6564
6566
6568
6570
6572
6574
6576
6578
6580
6582
6584
6586
6588
6590
6592
6594
6596
6598
6600
6602
6604
6606
6608
6610
6612
6614
6616
6618
6620
6622
6624
6626
6628
6630
6632
6634
6636
6638
6640
6642
6644
6646
6648
6650
6652
6654
6656
6658
6660
6662
6664
6666
6668
6670
6672
6674
6676
6678
6680
6682
6684
6686
6688
6690
6692
6694
6696
6698
6700
6702
6704
6706
6708
6710
6712
6714
6716
6718
6720
6722
6724
6726
6728
6730
6732
6734
6736
6738
6740
6742
6744
6746
6748
6750
6752
6754
6756
6758
6760
6762
6764
6766
6768
6770
6772
6774
6776
6778
6780
6782
6784
6786
6788
6790
6792
6794
6796
6798
6800
6802
6804
6806
6808
6810
6812
6814
6816
6818
6820
6822
6824
6826
6828
6830
6832
6834
6836
6838
6840
6842
6844
6846
6848
6850
6852
6854
6856
6858
6860
6862
6864
6866
6868
6870
6872
6874
6876
6878
6880
6882
6884
6886
6888
6890
6892
6894
6896
6898
6900
6902
6904
6906
6908
6910
6912
6914
6916
6918
6920
6922
6924
6926
6928
6930
6932
6934
6936
6938
6940
6942
6944
6946
6948
6950
6952
6954
6956
6958
6960
6962
6964
6966
6968
6970
6972
6974
6976
6978
6980
6982
6984
6986
6988
6990
6992
6994
6996
6998
7000
7002
7004
7006
7008
7010
7012
7014
7016
7018
7020
7022
7024
7026
7028
7030
7032
7034
7036
7038
7040
7042
7044
7046
7048
7050
7052
7054
7056
7058
7060
7062
7064
7066
7068
7070
7072
7074
7076
7078
7080
7082
7084
7086
7088
7090
7092
7094
7096
7098
7100
7102
7104
7106
7108
7110
7112
7114
7116
7118
7120
7122
7124
7126
7128
7130
7132
7134
7136
7138
7140
7142
7144
7146
7148
7150
7152
7154
7156
7158
7160
7162
7164
7166
7168
7170
7172
7174
7176
7178
7180
7182
7184
7186
7188
7190
7192
7194
7196
7198
7200
7202
7204
7206
7208
7210
7212
7214
7216
7218
7220
7222
7224
7226
7228
7230
7232
7234
7236
7238
7240
7242
7244
7246
7248
7250
7252
7254
7256
7258
7260
7262
7264
7266
7268
7270
7272
7274
7276
7278
7280
7282
7284
7286
7288
7290
7292
7294
7296
7298
7300
7302
7304
7306
7308
7310
7312
7314
7316
7318
7320
7322
7324
7326
7328
7330
7332
7334
7336
7338
7340
7342
7344
7346
7348
7350
7352
7354
7356
7358
7360
7362
7364
7366
7368
7370
7372
7374
7376
7378
7380
7382
7384
7386
7388
7390
7392
7394
7396
7398
7400
7402
7404
7406
7408
7410
7412
7414
7416
7418
7420
7422
7424
7426
7428
7430
7432
7434
7436
7438
7440
7442
7444
7446
7448
7450
7452
7454
7456
7458
7460
7462
7464
7466
7468
7470
7472
7474
7476
7478
7480
7482
7484
7486
7488
7490
7492
7494
7496
7498
7500
7502
7504
7506
7508
7510
7512
7514
7516
7518
7520
7522
7524
7526
7528
7530
7532
7534
7536
7538
7540
7542
7544
7546
7548
7550
7552
7554
7556
7558
7560
7562
7564
7566
7568
7570
7572
7574
7576
7578
7580
7582
7584
7586
7588
7590
7592
7594
7596
7598
7600
7602
7604
7606
7608
7610
7612
7614
7616
7618
7620
7622
7624
7626
7628
7630
7632
7634
7636
7638
7640
7642
7644
7646
7648
7650
7652
7654
7656
7658
7660
7662
7664
7666
7668
7670
7672
7674
7676
7678
7680
7682
7684
7686
7688
7690
7692
7694
7696
7698
7700
7702
7704
7706
7708
7710
7712
7714
7716
7718
7720
7722
7724
7726
7728
7730
7732
7734
7736
7738
7740
7742
7744
7746
7748
7750
7752
7754
7756
7758
7760
7762
7764
7766
7768
7770
7772
7774
7776
7778
7780
7782
7784
7786
7788
7790
7792
7794
7796
7798
7800
7802
7804
7806
7808
7810
7812
7814
7816
7818
7820
7822
7824
7826
7828
7830
7832
7834
7836
7838
7840
7842
7844
7846
7848
7850
7852
7854
7856
7858
7860
7862
7864
7866
7868
7870
7872
7874
7876
7878
7880
7882
7884
7886
7888
7890
7892
7894
7896
7898
7900
7902
7904
7906
7908
7910
7912
7914
7916
7918
7920
7922
7924
7926
7928
7930
7932
7934
7936
7938
7940
7942
7944
7946
7948
7950
7952
7954
7956
7958
7960
7962
7964
7966
7968
7970
7972
7974
7976
7978
7980
7982
7984
7986
7988
7990
7992
7994
7996
7998
8000
8002
8004
8006
8008
8010
8012
8014
8016
8018
8020
8022
8024
8026
8028
8030
8032
8034
8036
8038
8040
8042
8044
8046
8048
8050
8052
8054
8056
8058
8060
8062
8064
8066
8068
8070
8072
8074
8076
8078
8080
8082
8084
8086
8088
8090
8092
8094
8096
8098
8100
8102
8104
8106
8108
8110
8112
8114
8116
8118
8120
8122
8124
8126
8128
8130
8132
8134
8136
8138
8140
8142
8144
8146
8148
8150
8152
8154
8156
8158
8160
8162
8164
8166
8168
8170
8172
8174
8176
8178
8180
8182
8184
8186
8188
8190
8192
8194
8196
8198
8200
8202
8204
8206
8208
8210
8212
8214
8216
8218
8220
8222
8224
8226
8228
8230
8232
8234
8236
8238
8240
8242
8244
8246
8248
8250
8252
8254
8256
8258
8260
8262
8264
8266
8268
8270
8272
8274
8276
8278
8280
8282
8284
8286
8288
8290
8292
8294
8296
8298
8300
8302
8304
8306
8308
8310
8312
8314
8316
8318
8320
8322
8324
8326
8328
8330
8332
8334
8336
8338
8340
8342
8344
8346
8348
8350
8352
8354
8356
8358
8360
8362
8364
8366
8368
8370
8372
8374
8376
8378
8380
8382
8384
8386
8388
8390
8392
8394
8396
8398
8400
8402
8404
8406
8408
8410
8412
8414
8416
8418
8420
8422
8424
8426
8428
8430
8432
8434
8436
8438
8440
8442
8444
8446
8448
8450
8452
8454
8456
8458
8460
8462
8464
8466
8468
8470
8472
8474
8476
8478
8480
8482
8484
8486
8488
8490
8492
8494
8496
8498
8500
8502
8504
8506
8508
8510
8512
8514
8516
8518
8520
8522
8524
8526
8528
8530
8532
8534
8536
8538
8540
8542
8544
8546
8548
8550
8552
8554
8556
8558
8560
8562
8564
8566
8568
8570
8572
8574
8576
8578
8580
8582
8584
8586
8588
8590
8592
8594
8596
8598
8600
8602
8604
8606
8608
8610
8612
8614
8616
8618
8620
8622
8624
8626
8628
8630
8632
8634
8636
8638
8640
8642
8644
8646
8648
8650
8652
8654
8656
8658
8660
8662
8664
8666
8668
8670
8672
8674
8676
8678
8680
8682
8684
8686
8688
8690
8692
8694
8696
8698
8700
8702
8704
8706
8708
8710
8712
8714
8716
8718
8720
8722
8724
8726
8728
8730
8732
8734
8736
8738
8740
8742
8744
8746
8748
8750
8752
8754
8756
8758
8760
8762
8764
8766
8768
8770
8772
8774
8776
8778
8780
8782
8784
8786
8788
8790
8792
8794
8796
8798
8800
8802
8804
8806
8808
8810
8812
8814
8816
8818
8820
8822
8824
8826
8828
8830
8832
8834
8836
8838
8840
8842
8844
8846
8848
8850
8852
8854
8856
8858
8860
8862
8864
8866
8868
8870
8872
8874
8876
8878
8880
8882
8884
8886
8888
8890
8892
8894
8896
8898
8900
8902
8904
8906
8908
8910
8912
8914
8916
8918
8920
8922
8924
8926
8928
8930
8932
8934
8936
8938
8940
8942
8944
8946
8948
8950
8952
8954
8956
8958
8960
8962
8964
8966
8968
8970
8972
8974
8976
8978
8980
8982
8984
8986
8988
8990
8992
8994
8996
8998
9000
9002
9004
9006
9008
9010
9012
9014
9016
9018
9020
9022
9024
9026
9028
9030
9032
9034
9036
9038
9040
9042
9044
9046
9048
9050
9052
9054
9056
9058
9060
9062
9064
9066
9068
9070
9072
9074
9076
9078
9080
9082
9084
9086
9088
9090
9092
9094
9096
9098
9100
9102
9104
9106
9108
9110
9112
9114
9116
9118
9120
9122
9124
9126
9128
9130
9132
9134
9136
9138
9140
9142
9144
9146
9148
9150
9152
9154
9156
9158
9160
9162
9164
9166
9168
9170
9172
9174
9176
9178
9180
9182
9184
9186
9188
9190
9192
9194
9196
9198
9200
9202
9204
9206
9208
9210
9212
9214
9216
9218
9220
9222
9224
9226
9228
9230
9232
9234
9236
9238
9240
9242
9244
9246
9248
9250
9252
9254
9256
9258
9260
9262
9264
9266
9268
9270
9272
9274
9276
9278
9280
9282
9284
9286
9288
9290
9292
9294
9296
9298
9300
9302
9304
9306
9308
9310
9312
9314
9316
9318
9320
9322
9324
9326
9328
9330
9332
9334
9336
9338
9340
9342
9344
9346
9348
9350
9352
9354
9356
9358
9360
9362
9364
9366
9368
9370
9372
9374
9376
9378
9380
9382
9384
9386
9388
9390
9392
9394
9396
9398
9400
9402
9404
9406
9408
9410
9412
9414
9416
9418
9420
9422
9424
9426
9428
9430
9432
9434
9436
9438
9440
9442
9444
9446
9448
9450
9452
9454
9456
9458
9460
9462
9464
9466
9468
9470
9472
9474
9476
9478
9480
9482
9484
9486
9488
9490
9492
9494
9496
9498
9500
9502
9504
9506
9508
9510
9512
9514
9516
9518
9520
9522
9524
9526
9528
9530
9532
9534
9536
9538
9540
9542
9544
9546
9548
9550
9552
9554
9556
9558
9560
9562
9564
9566
9568
9570
9572
9574
9576
9578
9580
9582
9584
9586
9588
9590
9592
9594
9596
9598
9600
9602
9604
9606
9608
9610
9612
9614
9616
9618
9620
9622
9624
9626
9628
9630
9632
9634
9636
9638
9640
9642
9644
9646
9648
9650
9652
9654
9656
9658
9660
9662
9664
9666
9668
9670
9672
9674
9676
9678
9680
9682
9684
9686
9688
9690
9692
9694
9696
9698
9700
9702
9704
9706
9708
9710
9712
9714
9716
9718
9720
9722
9724
9726
9728
9730
9732
9734
9736
9738
9740
9742
9744
9746
9748
9750
9752
9754
9756
9758
9760
9762
9764
9766
9768
9770
9772
9774
9776
9778
9780
9782
9784
9786
9788
9790
9792
9794
9796
9798
9800
9802
9804
9806
9808
9810
9812
9814
9816
9818
9820
9822
9824
9826
9828
9830
9832
9834
9836
9838
9840
9842
9844
9846
9848
9850
9852
9854
9856
9858
9860
9862
9864
9866
9868
9870
9872
9874
9876
9878
9880
9882
9884
9886
9888
9890
9892
9894
9896
9898
9900
9902
9904
9906
9908
9910
9912
9914
9916
9918
9920
9922
9924
9926
9928
9930
9932
9934
9936
9938
9940
9942
9944
9946
9948
9950
9952
9954
9956
9958
9960
9962
9964
9966
9968
9970
9972
9974
9976
9978
9980
9982
9984
9986
9988
9990
9992
9994
9996
9998
10000
10002
10004
10006
10008
10010
10012
10014
10016
10018
10020
10022
10024
10026
10028
10030
10032
10034
10036
10038
10040
10042
10044
10046
10048
10050
10052
10054
10056
10058
10060
10062
10064
10066
10068
10070
10072
10074
10076
10078
10080
10082
10084
10086
10088
10090
10092
10094
10096
10098
10100
10102
10104
10106
10108
10110
10112
10114
10116
10118
10120
10122
10124
10126
10128
10130
10132
10134
10136
10138
10140
10142
10144
10146
10148
10150
10152
10154
10156
10158
10160
10162
10164
10166
10168
10170
10172
10174
10176
10178
10180
10182
10184
10186
10188
10190
10192
10194
10196
10198
10200
10202
10204
10206
10208
10210
10212
10214
10216
10218
10220
10222
10224
10226
10228
10230
10232
10234
10236
10238
10240
10242
10244
10246
10248
10250
10252
10254
10256
10258
10260
10262
10264
10266
10268
10270
10272
10274
10276
10278
10280
10282
10284
10286
10288
10290
10292
10294
10296
10298
10300
10302
10304
10306
10308
10310
10312
10314
10316
10318
10320
10322
10324
10326
10328
10330
10332
10334
10336
10338
10340
10342
10344
10346
10348
10350
10352
10354
10356
10358
10360
10362
10364
10366
10368
10370
10372
10374
10376
10378
10380
10382
10384
10386
10388
10390
10392
10394
10396
10398
10400
10402
10404
10406
10408
10410
10412
10414
10416
10418
10420
10422
10424
10426
10428
10430
10432
10434
10436
10438
10440
10442
10444
10446
10448
10450
10452
10454
10456
10458
10460
10462
10464
10466
10468
10470
10472
10474
10476
10478
10480
10482
10484
10486
10488
10490
10492
10494
10496
10498
10500
10502
10504
10506
10508
10510
10512
10514
10516
10518
10520
10522
10524
10526
10528
10530
10532
10534
10536
10538
10540
10542
10544
10546
10548
10550
10552
10554
10556
10558
10560
10562
10564
10566
10568
10570
10572
10574
10576
10578
10580
10582
10584
10586
10588
10590
10592
10594
10596
10598
10600
10602
10604
10606
10608
10610
10612
10614
10616
10618
10620
10622
10624
10626
10628
10630
10632
10634
10636
10638
10640
10642
10644
10646
10648
10650
10652
10654
10656
10658
10660
10662
10664
10666
10668
10670
10672
10674
10676
10678
10680
10682
10684
10686
10688
10690
10692
10694
10696
10698
10700
10702
10704
10706
10708
10710
10712
10714
10716
10718
10720
10722
10724
10726
10728
10730
10732
10734
10736
10738
10740
10742
10744
10746
10748
10750
10752
10754
10756
10758
10760
10762
10764
10766
10768
10770
10772
10774
10776
10778
10780
10782
10784
10786
10788
10790
10792
10794
10796
10798
10800
10802
10804
10806
10808
10810
10812
10814
10816
10818
10820
10822
10824
10826
10828
10830
10832
10834
10836
10838
10840
10842
10844
10846
10848
10850
10852
10854
10856
10858
10860
10862
10864
10866
10868
10870
10872
10874
10876
10878
10880
10882
10884
10886
10888
10890
10892
10894
10896
10898
10900
10902
10904
10906
10908
10910
10912
10914
10916
10918
10920
10922
10924
10926
10928
10930
10932
10934
10936
10938
10940
10942
10944
10946
10948
10950
10952
10954
10956
10958
10960
10962
10964
10966
10968
10970
10972
10974
10976
10978
10980
10982
10984
10986
10988
10990
10992
10994
10996
10998
11000
11002
11004
11006
11008
11010
11012
11014
11016
11018
11020
11022
11024
11026
11028
11030
11032
11034
11036
11038
11040
11042
11044
11046
11048
11050
11052
11054
11056
11058
11060
11062
11064
11066
11068
11070
11072
11074
11076
11078
11080
11082
11084
11086
11088
11090
11092
11094
11096
11098
11100
11102
11104
11106
11108
11110
11112
11114
11116
11118
11120
11122
11124
11126
11128
11130
11132
11134
11136
11138
11140
11142
11144
11146
11148
11150
11152
11154
11156
11158
11160
11162
11164
11166
11168
11170
11172
11174
11176
11178
11180
11182
11184
11186
11188
11190
11192
11194
11196
11198
11200
11202
11204
11206
11208
11210
11212
11214
11216
11218
11220
11222
11224
11226
11228
11230
11232
11234
11236
11238
11240
11242
11244
11246
11248
11250
11252
11254
11256
11258
11260
11262
11264
11266
11268
11270
11272
11274
11276
11278
11280
11282
11284
11286
11288
11290
11292
11294
11296
11298
11300
11302
11304
11306
11308
11310
11312
11314
11316
11318
11320
11322
11324
11326
11328
11330
11332
11334
11336
11338
11340
11342
11344
11346
11348
11350
11352
11354
11356
11358
11360
11362
11364
11366
11368
11370
11372
11374
11376
11378
11380
11382
11384
11386
11388
11390
11392
11394
11396
11398
11400
11402
11404
11406
11408
11410
11412
11414
11416
11418
11420
11422
11424
11426
11428
11430
11432
11434
11436
11438
11440
11442
11444
11446
11448
11450
11452
11454
11456
11458
11460
11462
11464
11466
11468
11470
11472
11474
11476
11478
11480
11482
11484
11486
11488
11490
11492
11494
11496
11498
11500
11502
11504
11506
11508
11510
11512
11514
11516
11518
11520
11522
11524
11526
11528
11530
11532
11534
11536
11538
11540
11542
11544
11546
11548
11550
11552
11554
11556
11558
11560
11562
11564
11566
11568
11570
11572
11574
11576
11578
11580
11582
11584
11586
11588
11590
11592
11594
11596
11598
11600
11602
11604
11606
11608
11610
11612
11614
11616
11618
11620
11622
11624
11626
11628
11630
11632
11634
11636
11638
11640
11642
11644
11646
11648
11650
11652
11654
11656
11658
11660
11662
11664
11666
11668
11670
11672
11674
11676
11678
11680
11682
11684
11686
11688
11690
11692
11694
11696
11698
11700
11702
11704
11706
11708
11710
11712
11714
11716
11718




*NOTES:*
1. *INSTALL LANE CLOSURE DURING NON PEAK HOURS ONLY WITH WRITTEN APPROVAL FROM THE ENGINEER.*
2. *MAINTAIN AT LEAST ONE SIDEWALK AT ALL TIMES. DIVERT PEDESTRIAN SIDEWALK TO OPPOSITE SIDE OF THE ROAD WHILE CLOSED.*
3. *COVER ALL CONFLICTING SIGNS.*
4. *SEE TRAFFIC CONTROL PLAN FOR EXISTING SIGNS.*
5. *PROVIDE A 14 DAY ADVANCE NOTICE TO THE CITY OF COLUMBUS TO COORDINATE TEMPORARY ADJUSTMENTS TO THE EXISTING TRAFFIC SIGNAL TIMING.*

*LEGEND*

- *PHASE WORK ZONE*
- *DRUMS*
- *PORTABLE BARRIER*
- *TEMPORARY PAVEMENT*
- *IMPACT ATTENUATOR*
- *DIRECTION OF TRAVEL*
- *TYPE III BARRICADE*
- *TEMPORARY SIGN SUPPORT*

HORIZONTAL SCALE IN FEET
0 15 30 60


# MAINTENANCE OF TRAFFIC - PHASE 8A STEP 2
# MORSE ROAD INSIDE RECONSTRUCTION

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.211 TOTAL: 618

FRA-71-19.10

MODEL: Morse Phase 1 - Plan 2 PAPERSIZE: 66x34 in | DATE: 3/31/2026 TIME: 11:17:56 AM PITDIV: ORDOT_PDP_P-LetSq_PENTBL: ORDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTD2O WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. THIS FILE IS PROVIDED AS AN INSTRUMENT OF SERVICE AND SHALL REMAIN THE PROPERTY OF JACOBS UNLESS OTHERWISE AGREED.




*DETAIL A*
*N.T.S.*




NOTES:
1. PROVIDE WORK ZONE CROSSOVER LIGHTING SYSTEM PER SCD MT-100.00. SEE LIGHTING PLAN NOTES.
2. CAREFULLY REMOVE AND STORE EXISTING LIGHT POLES FOR RE-INSTALLATION.

HORIZONTAL SCALE IN FEET
0 10 20 40


# MAINTENANCE OF TRAFFIC - CROSSOVER DETAILS
# STA. 1439+00.00 TO STA. 1450+00.00

DESIGN AGENCY
Jacobs


DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.217 TOTAL: 618

FRA-71-19.10

MODEL: North Crossover Sheet PAPERSIZE: 48x24 in | DATE: 3/31/2026 TIME: 11:18:02 AM |FITDW_CHSDT_PDF_IT.pltcfg, FITBTBL_CHSDT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CHSDTCIV2D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: C:\Users\chris.lawrence\Jacobs\Desktop\Central\109164_FRA-71-19.10_MOT_North Crossover Sheet.dgn




*DETAIL A*
*N.T.S.*




*NOTES:*
*1. PROVIDE WORK ZONE CROSSOVER LIGHTING SYSTEM PER SCD MT-100.00. SEE LIGHTING PLAN NOTES.*
*2. CAREFULLY REMOVE AND STORE EXISTING LIGHT POLES FOR RE-INSTALLATION.*

HORIZONTAL SCALE IN FEET
0 10 20 40


# MAINTENANCE OF TRAFFIC - CROSSOVER DETAILS
# STA. 1267+00.00 TO 1278+00.00

DESIGN AGENCY
Jacobs

DESIGNER: SRH
REVIEWER: BAP 03/20/26
PROJECT ID: 109164
SHEET: P.218 TOTAL: 618

FRA-71-19.10

MODEL: South Crossover Sheet PAPERSIZE: ANSI-B (in.) DATE: 3/31/2026 TIME: 11:18:07 AM PITDRV_ONDOT_PDP_IT-pltcfg PENTBL: ONDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: OHDOTCIVIL3D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.22.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL INFORMATION.




## LEGEND

| | | |
|---|---|---|
| A.A. - ANCHOR ASSEMBLY | EX. - EXISTING | PA - PREVIOUSLY ABANDONED |
| BARR - BARRIER | GR - GUARDRAIL | TBA - TO BE ABANDONED |
| BARR, B1 - BARRIER, TYPE B1 | I.A. - IMPACT ATTENUATOR | TBR - TO BE REMOVED |
| BARR, D - BARRIER, TYPE D | NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET | TBRL - TO BE RELOCATED |
| BARR, D (MOD) - BARRIER, TYPE D MODIFIED | PAV'T - PAVEMENT | TYP - TYPICAL |
| B.T.A. - BRIDGE TERMINAL ASSEMBLY | PR. - PROPOSED | - MILL AND RESURFACING AREA |
| CONST. - CONSTRUCTION | SHLDR - SHOULDER | - CONCRETE CAP REPLACEMENT |
| CURB, 4-C - CURB, TYPE 4C | SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM4-4.4 | - VEGETATED FILTER STRIPS |
| CURB, 6 - CURB, TYPE 6 | WDNG - WIDENING | - PROPOSED LIGHT POLE |
| (**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS | ATG - ADJUST TO GRADE | - PROPOSED LIGHTING PULLBOX |
| (#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET | DND - DO NOT DISTURB | - PROPOSED ITS CABINET |
| | F&P - FILL AND PLUG | - PROPOSED ITS PULLBOX |
| | L.O.N. - LENGTH OF NEED | - PROPOSED ELECTRIC PULLBOX |
| | U.D. - UNDERDRAIN | |

HORIZONTAL SCALE IN FEET: 0, 10, 20, 40


PLAN - I-71
STA. 1109+00.00 TO STA. 1120+00.00

DESIGN AGENCY: Jacobs

DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.219 | TOTAL: 618

FRA-71-19.10

MODEL: C3F_I071 - Sheet 1 PAPERSIZE: 66x34.0 in | DATE: 3/31/2026 TIME: 2:53:59 PM PITDRV: ORIOT_PDF_V1.prtdg PITSTYL: ORIOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: ORIOTCIVIL3D WORKSET: DEFAULT PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\FRA\FRA-71-19.10\Design\Roadway\Plans\Sheets\FRA-71-19.10_I071_PLAN_1109+00_TO_1120+00.dgn




## LEGEND

| | | |
|---|---|---|
| *A.A. - ANCHOR ASSEMBLY* | *EX. - EXISTING* | *PA - PREVIOUSLY ABANDONED* |
| *BARR - BARRIER* | *GR - GUARDRAIL* | *TBA - TO BE ABANDONED* |
| *BARR, B1 - BARRIER, TYPE B1* | *I.A. - IMPACT ATTENUATOR* | *TBR - TO BE REMOVED* |
| *BARR, D - BARRIER, TYPE D* | *NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET* | *TBRL - TO BE RELOCATED* |
| *BARR, D (MOD) - BARRIER, TYPE D MODIFIED* | *PAV'T - PAVEMENT* | *TYP - TYPICAL* |
| *B.T.A. - BRIDGE TERMINAL ASSEMBLY* | *PR. - PROPOSED* | *- MILL AND RESURFACING AREA* |
| *CONST. - CONSTRUCTION* | *SHLDR - SHOULDER* | *- CONCRETE CAP REPLACEMENT* |
| *CURB, 4-C - CURB, TYPE 4C* | *SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4* | *- VEGETATED FILTER STRIPS* |
| *CURB, 6 - CURB, TYPE 6* | *WDNG - WIDENING* | *- PROPOSED LIGHT POLE* |
| *(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS* | *ATG - ADJUST TO GRADE* | *- PROPOSED LIGHTING PULLBOX* |
| *(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET* | *DND - DO NOT DISTURB* | *- PROPOSED ITS CABINET* |
| | *F&P - FILL AND PLUG* | *- PROPOSED ITS PULLBOX* |
| | *L.O.N. - LENGTH OF NEED* | *- PROPOSED ELECTRIC PULLBOX* |
| | *U.D. - UNDERDRAIN* | |

HORIZONTAL SCALE IN FEET
0 10 20 40


# PLAN - I-71
## STA. 1250+00.00 TO STA. 1261+00.00

FRA-71-19.10


MODEL: CU_071 - Sheet 2 PAPERSIZE: 66x34.0 in | DATE: 3/31/2026 TIME: 2:52:42 PM PCTBW: CMDOT_PDF_U-LARGE_PSTBL.CMDOT_PDF_U-LARGE_PSTBL.CMDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CMDOTCIVIL3D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ROUTE: Fra-71-19.10 Plan and Profile Sheets | Fra-071-19.10 Plan and Profile Sheets | Plan and Profile Sheets


DESIGN AGENCY
Jacobs

DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.220 TOTAL: 618




## LEGEND

- *A.A. - ANCHOR ASSEMBLY*
- *BARR - BARRIER*
- *BARR, B1 - BARRIER, TYPE B1*
- *BARR, D - BARRIER, TYPE D*
- *BARR, D (MOD) - BARRIER, TYPE D MODIFIED*
- *B.T.A. - BRIDGE TERMINAL ASSEMBLY*
- *CONST. - CONSTRUCTION*
- *CURB, 4-C - CURB, TYPE 4C*
- *CURB, 6 - CURB, TYPE 6*
- *(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS*
- *(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET*

- *EX. - EXISTING*
- *GR - GUARDRAIL*
- *I.A. - IMPACT ATTENUATOR*
- *NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET*
- *PAV'T - PAVEMENT*
- *PR. - PROPOSED*
- *SHLDR - SHOULDER*
- *SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4*
- *WDNG - WIDENING*
- *ATG - ADJUST TO GRADE*
- *DND - DO NOT DISTURB*
- *F&P - FILL AND PLUG*
- *L.O.N. - LENGTH OF NEED*
- *U.D. - UNDERDRAIN*

- *PA - PREVIOUSLY ABANDONED*
- *TBA - TO BE ABANDONED*
- *TBR - TO BE REMOVED*
- *TBRL - TO BE RELOCATED*
- *TYP - TYPICAL*
- *- MILL AND RESURFACING AREA*
- *- CONCRETE CAP REPLACEMENT*
- *- VEGETATED FILTER STRIPS*
- *- PROPOSED LIGHT POLE*
- *- PROPOSED LIGHTING PULLBOX*
- *- PROPOSED ITS CABINET*
- *- PROPOSED ITS PULLBOX*
- *- PROPOSED ELECTRIC PULLBOX*

HORIZONTAL SCALE IN FEET: 0, 10, 20, 40

# PLAN - I-71
# STA. 1261+00.00 TO STA. 1272+00.00

FRA-71-19.10


MODEL: CU_071 - Sheet 3 PAYREQ01 66x34 (in) SKTS: 37/1/2026 TIME: 2:53:47 PM PCTBW: CMDOT_PDF_U-LARGE_PSTBL.CTB/CMDOT_PDF_U-LARGE_PSTBL.CMDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CMDOTCLOUD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALIGNMENT NAME: I-71 NB PROFILE NAME: I-71 NB SURFACE NAME: Proposed Roadway Surface_CONCRETE



DESIGN AGENCY: Jacobs

DESIGNER: CNR

REVIEWER: MCK 03/11/26

PROJECT ID: 109164

SHEET: P.221 TOTAL: 618




## LEGEND

*A.A. - ANCHOR ASSEMBLY*
*BARR - BARRIER*
*BARR, B1 - BARRIER, TYPE B1*
*BARR, D - BARRIER, TYPE D*
*BARR, D (MOD) - BARRIER, TYPE D MODIFIED*
*B.T.A. - BRIDGE TERMINAL ASSEMBLY*
*CONST. - CONSTRUCTION*
*CURB, 4-C - CURB, TYPE 4C*
*CURB, 6 - CURB, TYPE 6*
*(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS*
*(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET*

*EX. - EXISTING*
*GR - GUARDRAIL*
*I.A. - IMPACT ATTENUATOR*
*NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET*
*PAV'T - PAVEMENT*
*PR. - PROPOSED*
*SHLDR - SHOULDER*
*SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4*
*WDNG - WIDENING*
*ATG - ADJUST TO GRADE*
*DND - DO NOT DISTURB*
*F&P - FILL AND PLUG*
*L.O.N. - LENGTH OF NEED*
*U.D. - UNDERDRAIN*

*PA - PREVIOUSLY ABANDONED*
*TBA - TO BE ABANDONED*
*TBR - TO BE REMOVED*
*TBRL - TO BE RELOCATED*
*TYP - TYPICAL*
*- MILL AND RESURFACING AREA*
*- CONCRETE CAP REPLACEMENT*
*- VEGETATED FILTER STRIPS*
*- PROPOSED LIGHT POLE*
*- PROPOSED LIGHTING PULLBOX*
*- PROPOSED ITS CABINET*
*- PROPOSED ITS PULLBOX*
*- PROPOSED ELECTRIC PULLBOX*

HORIZONTAL SCALE IN FEET
0 10 20 40


# PLAN - I-71
# STA. 1272+00.00 TO STA. 1283+00.00


DESIGN AGENCY
Jacobs
DESIGNER
CNR
REVIEWER
MCK 03/11/26
PROJECT ID
109164
SHEET
P.222
TOTAL
618

FRA-71-19.10

MODEL: CLP_071 - Sheet 4 PAYREQD1 66x34 (in) SHTS: 37/122(In TAB: 21/121 PM: PCONY, CHDOT_PDP_LP LAYER: PSHTEL, CHDOT_Pen.tbl USER: ChrisLawrence@jacobs.com WORKSPACE: CHDOTCLX02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. UNAUTHORIZED USE, MODIFICATION, OR DISTRIBUTION OF THIS PLOT IS STRICTLY PROHIBITED. PROTECTED BY COPYRIGHT AND TRADE SECRET LAWS.

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS








PROFILE - I-71
STA. 1275+00.00 TO STA. 1283+00.00

FRA-71-19.10

MODEL: 71 Profiles 1 PAPERSIZE: 34x24 in | DATE: 3/30/2026 TIME: 11:54:41 PM PITDW: DWGT_PDF_U = 4PSB, PITBTBL: DWGT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: OHIODTLEO1 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 14.00.10.25
FILE: C:\Projects\Fra\FRA-71-19.10\Roadway\Sheets\FRA-71-19.10_Profiles.dgn

DESIGN AGENCY
Jacobs
DESIGNER
CNR
REVIEWER
MCK 03/11/26
PROJECT ID
109164
SHEET
P.223
TOTAL
618




HORIZONTAL SCALE IN FEET: 0, 10, 20, 40


PLAN - I-71
STA. 1283+00.00 TO STA. 1294+00.00


DESIGN AGENCY: Jacobs
DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.224 | TOTAL: 618

FRA-71-19.10

MODEL: CU_071 - Sheet: S PAYREQD1 66x34 (in) DATE: 3/31/2026 TIME: 2:33:11 PM PLTDRV: DWG.pltcfg PENTBL: DWG.tbl USER: ChrisLawrence@jacobs.com WORKSPACE: CHCOTC1V2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\FRA\71\109164\Highway\Roadway\Plan and Profile\FRA-71-19.10_PLAN_I-71_1283+00.00 TO 1294+00.00.dgn

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS








PROFILE - I-71
STA. 1283+00.00 TO STA. 1294+00.00

FRA-71-19.10


MODEL: 71 Profiles 2 PARTIALS: 04x24 (no) DATE: 3/30/2026 TIME: 11:59:44 AM PLTSTBL: ON-OFF_PSR_LV.stb PLOTTED ON-OFF_PSR_LV DESIGN: WORKSPACE: OHDOTCIVD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 14.00.02.25
FILE: C:\Projects\109164\Roadway\Profiles\Profiles\FRA71-19.10_PROFILE-I-71-NORTHBOUND-SOUTHBOUND.dgn


DESIGN AGENCY: Jacobs
DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.225 TOTAL: 618




## LEGEND

| | | |
|---|---|---|
| *A.A. - ANCHOR ASSEMBLY* | *EX. - EXISTING* | *PA - PREVIOUSLY ABANDONED* |
| *BARR - BARRIER* | *GR - GUARDRAIL* | *TBA - TO BE ABANDONED* |
| *BARR, B1 - BARRIER, TYPE B1* | *I.A. - IMPACT ATTENUATOR* | *TBR - TO BE REMOVED* |
| *BARR, D - BARRIER, TYPE D* | *NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET* | *TBRL - TO BE RELOCATED* |
| *BARR, D (MOD) - BARRIER, TYPE D MODIFIED* | *PAV'T - PAVEMENT* | *TYP - TYPICAL* |
| *B.T.A. - BRIDGE TERMINAL ASSEMBLY* | *PR. - PROPOSED* | *- MILL AND RESURFACING AREA* |
| *CONST. - CONSTRUCTION* | *SHLDR - SHOULDER* | *- CONCRETE CAP REPLACEMENT* |
| *CURB, 4-C - CURB, TYPE 4C* | *SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4* | *- VEGETATED FILTER STRIPS* |
| *CURB, 6 - CURB, TYPE 6* | *WDNG - WIDENING* | *- PROPOSED LIGHT POLE* |
| *(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS* | *ATG - ADJUST TO GRADE* | *- PROPOSED LIGHTING PULLBOX* |
| *(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET* | *DND - DO NOT DISTURB* | *- PROPOSED ITS CABINET* |
| | *F&P - FILL AND PLUG* | *- PROPOSED ITS PULLBOX* |
| | *L.O.N. - LENGTH OF NEED* | *- PROPOSED ELECTRIC PULLBOX* |
| | *U.D. - UNDERDRAIN* | |

*CURVE DATA: I71-11*
*P.I. = STA. 1318+02.63*
*Δ = 45°31'52" RT*
*Dc = 01°30'00"*
*R = 3,819.72'*
*Ls = 250.00'*
*Θs = 01°52'30"*
*LT = 166.68'*
*ST = 83.34'*
*Lc = 2,785.41'*
*Ts = 1,728.25'*
*Es = 323.45'*
*Emax = 0.050*
*S.C. = 1303+24.38*
*C.S. = 1331+09.80*

*CURVE DATA: MORC-1*
*P.I. = STA. 4299+26.82*
*Δ = 06°36'00" RT*
*Dc = 01°30'00"*
*R = 3,819.72'*
*T = 220.24'*
*L = 440'*
*E = 6.34'*
*Emax = 0.041*

*CURVE DATA: MORC-2*
*P.I. = STA. 4303+89.72*
*Δ = 14°30'37" RT*
*Dc = 03°00'00"*
*R = 1,909.86'*
*T = 243.14'*
*L = 483.67'*
*E = 15.41'*
*Emax = 0.050*

*SPIRAL DATA: MORD-1*
*P.I. = STA. 5302+39.87*
*Ls = 250.00'*
*Θs = 00°56'15"*
*LT = 166.67'*
*ST = 83.34'*
*x = 249.99'*
*y = 1.36'*
*k = 125.00'*
*p = 0.34'*
*C = 250.00'*
*Start = Sta. 5300+73.20*
*End = Sta. 5303+23.20*
*C.B. = N04°41'06"W*

*CURVE DATA: MORD-2*
*P.I. = STA. 5304+58.68*
*Δ = 02°01'55" LT*
*Dc = 00°45'00"*
*R = 7,639.44'*
*T = 135.48'*
*L = 270.93'*
*E = 1.20'*
*Emax = 0.018*

FRA-71-19.10

MODEL: CLP_OPT1 - Sheet 6 PAVEMENT 66x34 (Ps) SHTS: 37/122(M) TIME: 2:51:13 PM PLTDRV: CMDOT_PDF_FI-LatSB_PSTBL CMDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CMDOTCLOUD WORKSET: DEFAULT PRODUCT: OpenRoadsDesigner 24.00.02.25

DESIGN AGENCY: Jacobs

DESIGNER: CNR

REVIEWER: MCK 03/11/26


PROJECT ID: 109164


SHEET: P.226 TOTAL: 618

HORIZONTAL SCALE IN FEET: 0 10 20 40

PLAN - I-71
STA. 1294+00.00 TO STA. 1305+00.00

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS








PROFILE - I-71
STA. 1294+00.00 TO STA. 1305+00.00


FRA-71-19.10



MODEL: 71 Profiles 3 PARTIDAS: 04x24 (no) DATE: 3/30/2026 TIME: 11:56:47 PM PITDW: DHDOT_PDP_LV profile_PRINTBL DHDOT_Pen.tbl USER: Chris.Lawwood@jacobs.com WORKSPACE: OHDOTCLOUD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 14.00.03.25
FILE: C:\Users\chris.lawwood\Jacobs\Documents - Ohio DOT Projects\109164 - FRA-71-19.10 - I-71 Profiles\Microstation\Sheets\Alignment\FRA-71-19.10_Profile_Sheet.dgn


DESIGN AGENCY: Jacobs
DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.227 TOTAL: 618


LEGEND
A.A. - ANCHOR ASSEMBLY
BARR - BARRIER
BARR, B1 - BARRIER, TYPE B1
BARR, D - BARRIER, TYPE D
BARR, D (MOD) - BARRIER, TYPE D MODIFIED
B.T.A. - BRIDGE TERMINAL ASSEMBLY
CONST. - CONSTRUCTION
CURB, 4-C - CURB, TYPE 4C
CURB, 6 - CURB, TYPE 6
(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS
(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET
EX. - EXISTING
GR - GUARDRAIL
I.A. - IMPACT ATTENUATOR
NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET
PAV'T - PAVEMENT
PR. - PROPOSED
SHLDR - SHOULDER
SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4
WDNG - WIDENING
ATG - ADJUST TO GRADE
DND - DO NOT DISTURB
F&P - FILL AND PLUG
L.O.N. - LENGTH OF NEED
U.D. - UNDERDRAIN
PA - PREVIOUSLY ABANDONED
TBA - TO BE ABANDONED
TBR - TO BE REMOVED
TBRL - TO BE RELOCATED
TYP - TYPICAL
- MILL AND RESURFACING AREA
- CONCRETE CAP REPLACEMENT
- VEGETATED FILTER STRIPS
- PROPOSED LIGHT POLE
- PROPOSED LIGHTING PULLBOX
- PROPOSED ITS CABINET
- PROPOSED ITS PULLBOX
- PROPOSED ELECTRIC PULLBOX
CURVE DATA: I71-11
P.I. = STA. 1318+02.63
Δ = 45°31'52" RT
Dc = 01°30'00"
R = 3,819.72'
Ls = 250.00'
Θs = 01°52'30"
LT = 166.68'
ST = 83.34'
Lc = 2,785.41'
Ts = 1,728.25'
Es = 323.45'
Emax = 0.050
S.C. = 1303+24.38
C.S. = 1331+09.80
CURVE DATA: MORD-2
P.I. = STA. 5304+58.68
Δ = 02°01'55" LT
Dc = 00°45'00"
R = 7,639.44'
T = 135.48'
L = 270.93'
E = 1.20'
Emax = 0.018
CURVE DATA: MORD-3
P.I. = STA. 5309+47.68
Δ = 09°06'08" RT
Dc = 02°59'18"
R = 1,917.34'
T = 152.62'
L = 304.6'
E = 6.06'
Emax = 0.034
CURVE DATA: MORC-2
P.I. = STA. 4303+89.72
Δ = 14°30'37" RT
Dc = 03°00'00"
R = 1,909.86'
T = 243.14'
L = 483.67'
E = 15.41'
Emax = 0.050
SPIRAL DATA: MORC-3
P.I. = STA. 4306+80.26
Ls = 150.00'
Θs = 02°15'00"
LT = 100.01'
ST = 50.01'
x = 149.94'
y = 3.93'
k = 75.00'
p = 0.49'
C = 149.99'
Start = Sta. 4306+30.25
End = Sta. 4307+80.25
C.B. = N19°23'00"E
CURVE DATA: MORC-4
P.I. = STA. 4310+54.05
Δ = 16°59'40" LT
Dc = 08°00'00"
R = 716.20'
Ls = 100.00'
Θs = 04°00'00"
LT = 66.68'
ST = 33.35'
Lc = 112.43'
Ts = 157.08'
Es = 8.54'
Emax = EXISTING
S.C. = 4309+96.97
C.S. = 4311+09.40
+76.8 (RAMP D) END RESURFACING
+00.0, (RAMP D) END SHLDR TAPER & FULL DEPTH PAV'T / BEGIN RESURFACING
+35.0, (RAMP D) BEGIN SHLDR TAPER
+24.6 (RAMP D), END FILTER STRIP AREA #2
+88.2 (RAMP D)
+45.0, END SHLDR TAPER
+46.8, BEGIN SHLDR TAPER
+12.9, END A.A. & SHLDR TAPER
+45.7 (RAMP D)
+22.7, L.O.N. (RAMP D)
+87.2, L.O.N.
+21.4
+00.0, BEGIN CURB (#)
+61.1 (RAMP C) END RESURFACING
+53.2 (RAMP B) BEGIN RESURFACING
+77.2, BEGIN PULLOFF TAPER AND SHLDR TAPER
+97.2, END SHLDR TAPER
+07.0, BEGIN BARR, TYPE D
+97.3 END PULLOFF TAPER
+41.1, END PULLOFF
+90.1, END BARR, TYPE D
+02.9, BEGIN APPROACH SLAB
+32.8, END APPROACH SLAB
+00.0, BEGIN SHLDR TAPER (LT & RT)
+87.2, BEGIN / SHLDR TAPER
+13.2, END CURB
+29.0, BEGIN CURB
+00.0, END CURB (#)
+97.6, BEGIN CURB
+16.2, END CURB
+84.8, BEGIN APPROACH SLAB
+15.0, END APPROACH SLAB
+88.4, END SHLDR TAPER
+50.0, END SHLDR TAPER (LT & RT)
POT STA. 5313+12.27 (MORSE RD RAMP D) = STA. 47+45.65 (MORSE ROAD)
POT STA. 10+00.00 (SINCLAIR RD) = STA. 47+59.17 (MORSE ROAD)
POT STA. 4312+97.35 (MORSE RD RAMP C) = STA. 52+23.79 (MORSE ROAD)
POT STA. 3313+70.07 (MORSE RD RAMP B) = STA. 52+47.99 (MORSE ROAD)
STA. 50+00.00 (MORSE RD) = STA. 1312+97.31 (I-71)
PI STA. 5309+99.66
PI STA. 5310+06.06
PI STA. 5305+84.13
PI STA. 53+08.88
MATCH LINE STA. 1305+00
MATCH LINE STA. 1316+00
MATCH LINE STA. 4305+25
MATCH LINE STA. 4315+91.91
STRUCTURE NO. FRA-71-24.46(L&R)
I-71 (SOUTHBOUND)
I-71 (NORTHBOUND)
I-71 SB PGL
I-71 NB PGL
℄ CONST. I-71
℄ CONST. RAMP D
℄ CONST. RAMP C
℄ CONST. MORSE RD
SINCLAIR RD
℄ SINCLAIR ROAD
MORSE RD
MORD-2
MORD-3
MORC-2
MORC-3
MORC-4
I71-11
D-19
D-20
D-21
D-22
D-23
D-24
D-25
D-26
D-27
D-28
D-29
A.A. TYPE E
A.A. TYPE T
B.T.A. TYPE 1
B.T.A. TYPE 2
RCP TYPE C (22' x 2.5' X 1.5')
RCP TYPE C (26' x 2.5' X 1.5')
RCP TYPE C (9' x 2.5' X 1.5')
15" TYPE C
15" TYPE B
CONST. LIMITS (TYP.)
CONCRETE LANDSCAPING BAND
BLOCK LANDSCAPING WALL
TOE OF SINGLE SLOPE BARRIER
PR. UNDERDRAIN (TYP.)
TAPER CURB HEIGHT FROM 4" TO 0" OVER 1'
FLUME - (26' X 5.5') TIED CONCRETE BLOCK MAT W/ TYPE 2 UNDERLAYMENT
PR. FENCE, TYPE 47
EX. FENCE (TBR)
U.D. OUTLET - (4' X 4') TIED CONCRETE BLOCK MAT
EX. GUARDRAIL (TBR)
EX. ELEC. (**)
EX. ODOT FIBER & ELEC. (**)
EX. ODOT FIBER (**)
EX. CTSS FIBER (**)
EX. ELEC. PULL BOX AND RISER (**)
EX. UTILITY POLE (DND)
EX. AEP POLE (DND)
EX. AEP POLE (TBRL-OTHERS)
EX. ELEC. AEP (TBRL-BY OTHERS)
EX. CH TELECOM. CHARTER (TBRL-BY OTHERS)
EX. LIGHT POLE (**) (TYP.)
EX. RAMP SIGNAL (**)
RAMP SIGNAL (**)
EX. 3" CONDUIT (**)
EX. 4" CONDUIT (**)
EX. FLASHING SIGN POLE (**)
EX. PULL BOX (**)
EX. CAMERA POLE (**)
EX. CTSS POWER (**)
EX. LIGHTING CONDUIT (**)
EX. SIGNAL CONDUIT (DND)
EX. SIGNAL CONDUIT (TBR)
EX. CONDUIT (**)
EX. CANTILEVER SIGN STRUCTURE (DND)
EX. BLOCK WALL (DND)
EX. GAS (DND)
EX. 12" SLUDGE LINE C.O.C. (CTOSS82-047) (DND)
EX. 42" RCP (FRA-1-25.33) (DND)
EX. 36" RCP (FRA-1-25.33) (DND)
EX. 30" RCP (FRA-1-25.33) (DND)
EX. 24" RCP (FRA-1-25.33)
EX. 18" RCP (DND)
EX. 15" RCP (DND)
EX. 12" RCP (DND)
EX. 60" RCP (DND)
EX. 36" RCP (DND)
EX. 30" RCP (DND)
EX. 18" RCP (DND)
EX. 15" CPP (FRA-CN-17) (DND)
EX. 12" CPP (DND)
EX. CTSS FIBER (**)
EX. 42" RCP (FRA-1-25.33) (DND)
EX. 12" RCP (DND)
EX. 15" RCP (DND)
EX. 36" RCP (DND)
EX. 21" RCP (DND)
EX. 30" RCP (DND)
EX. 18" RCP (DND)
EX. 15" RCP (DND)
EX. 12" RCP (DND)
EX. 36" RCP (DND)
EX. 60" RCP (DND)
EX. 18" RCP (DND)
EX. 15" RCP (DND)
EX. 12" RCP (DND)
EX. 36" RCP (DND)
EX. 30

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS





PROFILE - I-71
STA. 1305+00.00 TO STA. 1316+00.00

DESIGN AGENCY
Jacobs


DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.229 TOTAL: 618


FRA-71-19.10

MODEL: 71 Profile 4 PARTIDGE: 04x14 En1 DATE: 3/30/2026 TIME: 11:07:54 AM PITDIM: ON DIDT_PW_LA prEdg PWTEL: ON DIDT_Pen.tbl USER: Chris.Lawwood@jacobs.com WORKSPACE: OH DOT/CO DOT WORKSET: DISTRICT PRODUCT: OpenRoadsDesigner 14.00.02.25
FILE: C:\Projects\Fra-71-19.10\Design\Roadway\Profiles\Fra-71-19.10 Profile 4.dgn


SPIRAL DATA: SINCE-1
P.I. = STA. 6321+67.37
Ls = 200.00'
Θs = 38°00'00"
LT = 136.54'
ST = 69.59'
x = 191.38'
y = 42.85'
k = 98.55'
p = 10.88'
C = 196.12'
Start = Sta. 6320+30.83
End = Sta. 6322+30.83
C.B. = N08°00'21"E
CURVE DATA: SINCE-2
P.I. = STA. 6323+35.18
Δ = 69°22'34" LT
Dc = 38°00'00"
R = 150.78'
T = 104.36'
L = 182.57'
E = 32.59'
Emax = 0.060
CURVE DATA: I71-11
P.I. = STA. 1318+02.63
Δ = 45°31'52" RT
Dc = 01°30'00"
R = 3,819.72'
Ls = 250.00'
Θs = 01°52'30"
LT = 166.68'
ST = 83.34'
Lc = 2,785.41'
Ts = 1,728.25'
Es = 323.45'
Emax = 0.050
S.C. = 1303+24.38
C.S. = 1331+09.80
CURVE DATA: MORB-1
P.I. = STA. 3321+05.52
Δ = 29°46'27" RT
Dc = 03°00'00"
R = 1,909.86'
T = 507.71'
L = 992.47'
E = 66.33'
Emax = 0.050
CURVE DATA: SINCA-1
P.I. = STA. 2322+90.10
Δ = 27°18'30" LT
Dc = 19°45'00"
R = 290.11'
T = 70.47'
L = 138.27'
E = 8.44'
Emax = 0.058
SPIRAL DATA: SINCA-2
P.I. = STA. 2324+60.52
Ls = 300.00'
Θs = 29°37'30"
LT = 202.87'
ST = 102.62'
x = 278.97'
y = 100.29'
k = 148.67'
p = 12.80'
C = 296.45'
Start = Sta. 2323+57.90
End = Sta. 2326+57.90
C.B. = N45°58'34"E
CURVE DATA: SINCA-3
P.I. = STA. 2329+05.37
Δ = 06°10'50" RT
Dc = 01°15'00"
R = 4,583.66'
T = 247.47'
L = 494.45'
E = 6.68'
Emax = 0.028
HORIZONTAL SCALE IN FEET
0 10 20 40
PLAN - I-71
STA. 1316+00.00 TO STA. 1327+00.00
LEGEND
A.A. - ANCHOR ASSEMBLY
BARR - BARRIER
BARR, B1 - BARRIER, TYPE B1
BARR, D - BARRIER, TYPE D
BARR, D (MOD) - BARRIER, TYPE D MODIFIED
B.T.A. - BRIDGE TERMINAL ASSEMBLY
CONST. - CONSTRUCTION
CURB, 4-C - CURB, TYPE 4C
CURB, 6 - CURB, TYPE 6
(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS
(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET
EX. - EXISTING
GR - GUARDRAIL
I.A. - IMPACT ATTENUATOR
NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET
PAV'T - PAVEMENT
PR. - PROPOSED
SHLDR - SHOULDER
SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4
WDNG - WIDENING
ATG - ADJUST TO GRADE
DND - DO NOT DISTURB
F&P - FILL AND PLUG
L.O.N. - LENGTH OF NEED
U.D. - UNDERDRAIN
PA - PREVIOUSLY ABANDONED
TBA - TO BE ABANDONED
TBR - TO BE REMOVED
TBRL - TO BE RELOCATED
TYP - TYPICAL
- MILL AND RESURFACING AREA
- CONCRETE CAP REPLACEMENT
- VEGETATED FILTER STRIPS
- PROPOSED LIGHT POLE
- PROPOSED LIGHTING PULLBOX
- PROPOSED ITS CABINET
- PROPOSED ITS PULLBOX
- PROPOSED ELECTRIC PULLBOX
DESIGN AGENCY
Jacobs
DESIGNER CNR
REVIEWER MCK 03/11/26
PROJECT ID 109164
SHEET P.230
TOTAL 618
FRA-71-19.10
MODEL: CU_071 - Sheet 8 PAYRIDGE: 66x34 (in) SKITS: 37/1/2026 TIME: 23:15:54 PM PITDIR: DWDT_PDF_U LaYdSt: PSTBL: DWDT_Pen.tbl USER: ChrisJLawrence@jacobs.com WORKSPACE: DWDTFILES WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS





PROFILE - I-71
STA. 1316+00.00 TO STA. 1327+00.00

FRA-71-19.10

MODEL: 71 Profiles 5 PARTIALS: 04x24 (no) DATE: 3/30/2026 TIME: 11:59:45 PM PLTDRV: DHDOT_PSP_LV.pltcfg PSHTBL: DHDOT_Pen.tbl USER: Chris.Lawwood@jacobs.com WORKSPACE: OHDOTCLOUD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 14.00.02.25
FILE: C:\Users\chris.lawwood\Jacobs\Documents - OHDOT Cloud Workspace\Projects\109164\Roadway\Alignments\FRA-71-19.10.dgn

DESIGN AGENCY
Jacobs

DESIGNER
CNR
REVIEWER
MCK 03/11/26
PROJECT ID
109164
SHEET P.231
TOTAL 618




## LEGEND

| | |
|---|---|
| EX. - EXISTING | PA - PREVIOUSLY ABANDONED |
| GR - GUARDRAIL | TBA - TO BE ABANDONED |
| I.A. - IMPACT ATTENUATOR | TBR - TO BE REMOVED |
| NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET | TBRL - TO BE RELOCATED |
| PAV'T - PAVEMENT | TYP - TYPICAL |
| PR. - PROPOSED | - MILL AND RESURFACING AREA |
| SHLDR - SHOULDER | - CONCRETE CAP REPLACEMENT |
| SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4 | - VEGETATED FILTER STRIPS |
| WDNG - WIDENING | - PROPOSED LIGHT POLE |
| ATG - ADJUST TO GRADE | - PROPOSED LIGHTING PULLBOX |
| DND - DO NOT DISTURB | - PROPOSED ITS CABINET |
| F&P - FILL AND PLUG | - PROPOSED ITS PULLBOX |
| L.O.N. - LENGTH OF NEED | - PROPOSED ELECTRIC PULLBOX |
| U.D. - UNDERDRAIN | |

A.A. - ANCHOR ASSEMBLY
BARR - BARRIER
BARR, B1 - BARRIER, TYPE B1
BARR, D - BARRIER, TYPE D
BARR, D (MOD) - BARRIER, TYPE D MODIFIED
B.T.A. - BRIDGE TERMINAL ASSEMBLY
CONST. - CONSTRUCTION
CURB, 4-C - CURB, TYPE 4C
CURB, 6 - CURB, TYPE 6
(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS
(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET

**CURVE DATA: I71-11**
P.I. = STA. 1318+02.63
Δ = 45°31'52" RT
Dc = 01°30'00"
R = 3,819.72'
Ls = 250.00'
Θs = 01°52'30"
LT = 166.68'
ST = 83.34'
Lc = 2,785.41'
Ts = 1,728.25'
Es = 323.45'
Emax = 0.059
S.C. = 1303+24.38
C.S. = 1331+09.80

**CURVE DATA: SINCA-3**
P.I. = STA. 2329+05.37
Δ = 06°10'50" RT
Dc = 01°15'00"
R = 4,583.66'
T = 247.47'
L = 494.45'
E = 6.68'
Emax = 0.028

HORIZONTAL SCALE IN FEET: 0, 10, 20, 40


PLAN - I-71
STA. 1327+00.00 TO STA. 1338+00.00


DESIGN AGENCY: Jacobs
DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.232
TOTAL: 618

FRA-71-19.10

MODEL: CLP_I071 - Sheet: 9 PAPERSIZE: 66x34.0 in | DATE: 3/31/2026 TIME: 2:33:33 PM PSTORE: CMDOT_PDF_V1.stb|@_PSTBL: CMDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CMDOTCLOUD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Interstate\I-70\Floyd Hill\Roadway\Sheets\Plan\FRA-71-19.10_I-71 SB PGL to I-71 NB PGL.dgn

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS








PROFILE - I-71
STA. 1327+00.00 TO STA. 1338+00.00

FRA-71-19.10

MODEL: 71 Profiles & PLMTHDS | SHEET: 3/30/2026 TIME: 11:10:50 AM PITDW: DHOFF_PSP_LH_prfl.dgn PITPEN: DHOFF_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: OHIOTOLL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 14.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. ©2021 BENTLEY SYSTEMS, INCORPORATED. Bentley, MicroStation, OpenRoads and i-model are either registered or unregistered trademarks or service marks of Bentley Systems, Incorporated or one of its direct or indirect subsidiaries.

DESIGN AGENCY
Jacobs
DESIGNER
CNR
REVIEWER
MCK 03/11/26
PROJECT ID
109164
SHEET P.233
TOTAL 618




## LEGEND

A.A. - ANCHOR ASSEMBLY
BARR - BARRIER
BARR, B1 - BARRIER, TYPE B1
BARR, D - BARRIER, TYPE D
BARR, D (MOD) - BARRIER, TYPE D MODIFIED
B.T.A. - BRIDGE TERMINAL ASSEMBLY
CONST. - CONSTRUCTION
CURB, 4-C - CURB, TYPE 4C
CURB, 6 - CURB, TYPE 6
(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS
(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET

EX. - EXISTING
GR - GUARDRAIL
I.A. - IMPACT ATTENUATOR
NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET
PAV'T - PAVEMENT
PR. - PROPOSED
SHLDR - SHOULDER
SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4
WDNG - WIDENING
ATG - ADJUST TO GRADE
DND - DO NOT DISTURB
F&P - FILL AND PLUG
L.O.N. - LENGTH OF NEED
U.D. - UNDERDRAIN

PA - PREVIOUSLY ABANDONED
TBA - TO BE ABANDONED
TBR - TO BE REMOVED
TBRL - TO BE RELOCATED
TYP - TYPICAL

- MILL AND RESURFACING AREA
- CONCRETE CAP REPLACEMENT
- VEGETATED FILTER STRIPS
- PROPOSED LIGHT POLE
- PROPOSED LIGHTING PULLBOX
- PROPOSED ITS CABINET
- PROPOSED ITS PULLBOX
- PROPOSED ELECTRIC PULLBOX

CURVE DATA: I71-12
P.I. = STA. 1359+02.77
Δ = 39°33'14" LT
Dc = 01°30'00"
R = 3,819.72'
Ls = 250.00'
Θs = 01°52'30"
LT = 166.68'
ST = 83.34'
Lc = 2,386.92'
Ts = 1,498.69'
Es = 240.14'
Emax = EXISTING
S.C. = 1346+54.09
C.S. = 1370+41.01

HORIZONTAL SCALE IN FEET: 0, 10, 20, 40


PLAN - I-71
STA. 1338+00.00 TO STA. 1349+00.00


DESIGN AGENCY: Jacobs
DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.234
TOTAL: 618

FRA-71-19.10

MODEL: CLP_I071 - Sheet 10 WARNING: 66.66 IN | DATE: 2/12/2026 7:56:41 PM BY/DBY: DHOFF, PM: JJ HAN, PENTRL: DHOFF_Pen.tbl USER: ChrisLawrence@jacobs.com WORKSPACE: DHOFF/D40 WORKSET: 199164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO APPLICABLE AGREEMENT. ©2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL INFORMATION.

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS




PROFILE - I-71
STA. 1338+00.00 TO STA. 1349+00.00

FRA-71-19.10

DESIGN AGENCY
Jacobs


DESIGNER
CNR


REVIEWER
MCK 03/11/26

PROJECT ID
109164

SHEET P.235 TOTAL 618

MODEL: 71 Profiles 7 PARTIZIO: 66x34 in | DATE: 3/30/2026 TIME: 11:13:21 PM PITDW: DHDOT_PSP_LV.pltcfg PENTBL: DHDOT_Pen.tbl USER: Chris.Lawwood@jacobs.com WORKSPACE: DHDOTCLOUD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 14.00.02.25
FILE: C:\Users\chris.lawwood\Jacobs\Desktop\Projects\FRA-71-19.10\Roadway\Profiles\FRA-71-19.10 Profiles.dgn


Ex LA-R/W
EX. 15" RCP (END)
93
1394
EX. NJ BARR TO REMAIN
1395
1396
℄ CONST. I-71
1397
EX. CONDUIT (**)
1398
EX. 15" CCP (END)
5,105.06'
N02°45'02"E
1399
EX. ELEC. CONDUIT (**)
1400
1401
1402
EX. 15" CCP (END)
18'
1403
EX. CONDUIT (**)
EX. LIGHT POLE (**) (TYP.)
EX. 15" CCP (END)
EX. CONDUIT (ODOT) (**)
I-71 (SOUTHBOUND)
I-71 (NORTHBOUND)
I-71 SB PGL
MATCH LINE STA. 1404+00
POT STA. 3402+27.44 (S161 RAMP B) = STA. 1402+27.44, 91.00' LT (I-71)
EX. 4" CTSS FIBER CONDUIT (**)
3403
322.05'
N01°06'57"E
℄ RAMP B
℄ RAMP A
2403
S161A-1
MATCH LINE STA. 2404+00
POT STA. 2402+23.61 (S161 RAMP A) = STA. 1402+23.61, 66.00' RT (I-71)
EX. GUARDRAIL (DND)
EX. ODOT FIBER (**)
EX. CONDUIT (ODOT) (**)
EX. CONDUIT (ODOT) (**)
EX. CONDUIT (ODOT)




## LEGEND

| | |
|---|---|
| *A.A. - ANCHOR ASSEMBLY* | *EX. - EXISTING* |
| *BARR - BARRIER* | *GR - GUARDRAIL* |
| *BARR, B1 - BARRIER, TYPE B1* | *I.A. - IMPACT ATTENUATOR* |
| *BARR, D - BARRIER, TYPE D* | *NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET* |
| *BARR, D (MOD) - BARRIER, TYPE D MODIFIED* | *PAV'T - PAVEMENT* |
| *B.T.A. - BRIDGE TERMINAL ASSEMBLY* | *PR. - PROPOSED* |
| *CONST. - CONSTRUCTION* | *SHLDR - SHOULDER* |
| *CURB, 4-C - CURB, TYPE 4C* | *SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4* |
| *CURB, 6 - CURB, TYPE 6* | *WDNG - WIDENING* |
| *(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS* | *ATG - ADJUST TO GRADE* |
| *(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET* | *DND - DO NOT DISTURB* |
| | *F&P - FILL AND PLUG* |
| | *L.O.N. - LENGTH OF NEED* |
| | *U.D. - UNDERDRAIN* |

| | |
|---|---|
| *PA - PREVIOUSLY ABANDONED* | |
| *TBA - TO BE ABANDONED* | |
| *TBR - TO BE REMOVED* | |
| *TBRL - TO BE RELOCATED* | |
| *TYP - TYPICAL* | |
| *- MILL AND RESURFACING AREA* | |
| *- CONCRETE CAP REPLACEMENT* | |
| *- VEGETATED FILTER STRIPS* | |
| *- PROPOSED LIGHT POLE* | |
| *- PROPOSED LIGHTING PULLBOX* | |
| *- PROPOSED ITS CABINET* | |
| *- PROPOSED ITS PULLBOX* | |
| *- PROPOSED ELECTRIC PULLBOX* | |

HORIZONTAL SCALE IN FEET
0 10 20 40

# PLAN - I-71
# STA. 1404+00.00 TO STA. 1415+00.00


DESIGN AGENCY
Jacobs


DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.237 TOTAL: 618

FRA-71-19.10

MODEL: CLP_STL - Sheet: 12 PAPERSIZE: 66x44 (in.) DATE: 2/12/2026 TIME: 2:31:34 PM USER: DHOFF_PW: Z:\JHQ_PENTRL_DHOFF_Plan.ctb USER: Chris.Lawrence@jacobs.com WORKSPACE: DHOFF-5420 WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.12.25
ELECTRONIC FILE ATTRIBUTES: FRA-71-19.10 FILE NAME: Z:\JHQ\Design\Roadway\Plan and Profile\FRA-71-19.10_Plan and Profile.dgn

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS





PROFILE - I-71
STA. 1404+00.00 TO STA. 1415+00.00

FRA-71-19.10


MODEL: 71 Profiles 3 PARTIDAS: 66434 En | DATE: 3/30/2026 TIME: 11:13:10 PM PITDW: DHOFF_PW_LP-APSB_PWTEL: DHOFF_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: OHIOTOLL01 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 14.00.02.25
FILES: C:\Projects\FRA-71-19.10\Roadway\Alignments\FRA-71-19.10 Profiles 3.dgn


DESIGN AGENCY
Jacobs

DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.238 TOTAL: 618


EX. CDC CONDUIT (**)
EX. 38" X 60" RCP (FRA-161-10.83) (DND)
EX. CTSS CABINETS (**)
EX. 32" PB (**)
EX. CTSS FIBER (**)
EX. LIGHT POLE (**)
EX. CAMERA (**)
EX. CTSS FIBER (**)
EX. ELECTRIC (**)
EX. TELECOM (AT&T) (DND)
EX. ELEC. (**) (PIER MOUNTED)
EX. CTSS AERIAL FIBER (**)
EX. ELEC. (**) (PIER MOUNTED)
STRUCTURE NO. FRA-71-26.46 (L&R)
EX. LIGHT POLE (**)
EX. TELECOM (AT&T) (DND)
EX. AEP POLES (DND)
EX. LIGHT POLE (**)
EX. CONDUIT (ODOT) (**)
EX. 29" X 45" RCP (FRA-161-10.83) (DND)
EX. ELEC. CONDUIT (**)
EX. 24" WATER (CTP0300_012/D.I.P.) (TBR)
EX. 24" WATER (CTP0300_012/D.I.P.) (DND)
EX. TELECOM (AT&T) (DND)
EX. ELEC. CONDUIT (**)
EX. LIGHT POLE (**)
EX. AEP POLE (TBRL-BY OTHERS)
EX. CTSS FIBER (**)
EX. OH ELEC. (AEP)
EX. OH TELECOM (VERIZON) (TBRL-BY OTHERS)
EX. ODOT FIBER (**)
EX. PULL BOX (**)
EX. CONDUIT (ODOT) (**)
EX. 3-4" CONDUIT (ODOT) (**)
EX. 48" RCP (DND)
EX. 4" CONDUIT (**)
EX. 15" CPP (DND)
EX. 15" RCP (DND)
EX. GUARDRAIL (DND)
EX. GUARDRAIL (TBR)
EX. ELEC. CONDUIT (**) (TYP.)
EX. LIGHT POLE (**) (TYP.)
EX. 4" CONDUIT (**)
EX. 2" CONDUIT (**)
EX. 3" CONDUIT (**)
EX. 1" CONDUIT (**)
EX. 2" CONDUIT (**)
EX. 1" CONDUIT (**)
EX. 2" CONDUIT (**)
EX. 3

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS








PROFILE - I-71
STA. 1415+00.00 TO STA. 1426+00.00

FRA-71-19.10


MODEL: 71 Profile 10 PAYNE2021 dw:sk3 [+/-] DATE: 3/31/2026 TIME: 2:54:09 PM PSTORE: ONDOT_PSP_LP.stb[] PSTYTBL: ONDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: OHDOTCIVD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 14.00.02.25
DGN: [Profiles and Miscellaneous Plan and Profile Sheets]FRA71-19.10_PROFILE_I-71_SOUTHBOUND_AND_NORTHBOUND_PROFILES_1415+00_TO_1426+00.dgn


DESIGN AGENCY: Jacobs
DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.240 TOTAL: 618




## LEGEND

| | | |
|---|---|---|
| *A.A. - ANCHOR ASSEMBLY* | *EX. - EXISTING* | *PA - PREVIOUSLY ABANDONED* |
| *BARR - BARRIER* | *GR - GUARDRAIL* | *TBA - TO BE ABANDONED* |
| *BARR, B1 - BARRIER, TYPE B1* | *I.A. - IMPACT ATTENUATOR* | *TBR - TO BE REMOVED* |
| *BARR, D - BARRIER, TYPE D* | *NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET* | *TBRL - TO BE RELOCATED* |
| *BARR, D (MOD) - BARRIER, TYPE D MODIFIED* | *PAV'T - PAVEMENT* | *TYP - TYPICAL* |
| *B.T.A. - BRIDGE TERMINAL ASSEMBLY* | *PR. - PROPOSED* | *- MILL AND RESURFACING AREA* |
| *CONST. - CONSTRUCTION* | *SHLDR - SHOULDER* | *- CONCRETE CAP REPLACEMENT* |
| *CURB, 4-C - CURB, TYPE 4C* | *SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4* | *- VEGETATED FILTER STRIPS* |
| *CURB, 6 - CURB, TYPE 6* | *WDNG - WIDENING* | *- PROPOSED LIGHT POLE* |
| *(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS* | *ATG - ADJUST TO GRADE* | *- PROPOSED LIGHTING PULLBOX* |
| *(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET* | *DND - DO NOT DISTURB* | *- PROPOSED ITS CABINET* |
| | *F&P - FILL AND PLUG* | *- PROPOSED ITS PULLBOX* |
| | *L.O.N. - LENGTH OF NEED* | *- PROPOSED ELECTRIC PULLBOX* |
| | *U.D. - UNDERDRAIN* | |

*CURVE DATA: I71-13*
*P.I. = STA. 1450+88.71*
*Δ = 24°44'23" RT*
*Dc = 00°28'00"*
*R = 12,277.67'*
*T = 2,692.64'*
*L = 5,301.35'*
*E = 291.8'*
*Emax = EXISTING*

*CURVE DATA: S161D-2*
*P.I. = STA. 5433+89.78*
*Δ = 05°57'16" RT*
*Dc = 00°45'00"*
*R = 7,639.44'*
*T = 397.32'*
*L = 793.92'*
*E = 10.32'*
*Emax = EXISTING*

HORIZONTAL SCALE IN FEET
0 10 20 40

# PLAN - I-71
# STA. 1426+00.00 TO STA. 1437+00.00


DESIGN AGENCY
Jacobs

DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.241 TOTAL: 618


FRA-71-19.10

MODEL: CLP_I071 - Sheet:14 WARNING: 66.66 IN | DATE: 2/12/2026 7:56:1 | 2:54:48 PM BY:CNR | DWGS: CNR.DGN | PE: | LEVEL: [PENTEL DWGS]_Pen.tbl USER: ChrisLawrence@jacobs.com WORKSPACE: CNRDOTS.ws3 WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.12.25
ALL RIGHTS RESERVED. THIS DRAWING IS THE PROPERTY OF JACOBS AND IS NOT TO BE USED, COPIED, REPRODUCED, OR MODIFIED IN ANY FORM OR MANNER WHATSOEVER WITHOUT THE PRIOR WRITTEN PERMISSION OF JACOBS.

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS




SOUTHBOUND PROFILE




NORTHBOUND PROFILE

PROFILE - I-71
STA. 1426+00.00 TO STA. 1430+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CNR


REVIEWER
MCK 03/11/26

PROJECT ID
109164

SHEET P.242 TOTAL 618

FRA-71-19.10


MODEL: 71 Profile 11 REFRESH: 04:43 PM DATE: 3/30/2026 TIME: 11:14:44 PM PITDIR: DHOFF_PW DHOFF_P-I.dgnlib, PENTBL, DHOFF_PW.ctb USER: Chris.Lawrence1@jacobs.com WORKSPACE: DHOOTOLS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\109164\Highway\Roadway\Profiles\FRA-71-19.10_PROFILE I-71 NORTHBOUND SOUTHBOUND.dgn




## LEGEND

- A.A. - ANCHOR ASSEMBLY
- BARR - BARRIER
- BARR, B1 - BARRIER, TYPE B1
- BARR, D - BARRIER, TYPE D
- BARR, D (MOD) - BARRIER, TYPE D MODIFIED
- B.T.A. - BRIDGE TERMINAL ASSEMBLY
- CONST. - CONSTRUCTION
- CURB, 4-C - CURB, TYPE 4C
- CURB, 6 - CURB, TYPE 6
- (**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS
- (#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET

- EX. - EXISTING
- GR - GUARDRAIL
- I.A. - IMPACT ATTENUATOR
- NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET
- PAV'T - PAVEMENT
- PR. - PROPOSED
- SHLDR - SHOULDER
- SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4
- WDNG - WIDENING
- ATG - ADJUST TO GRADE
- DND - DO NOT DISTURB
- F&P - FILL AND PLUG
- L.O.N. - LENGTH OF NEED
- U.D. - UNDERDRAIN

- PA - PREVIOUSLY ABANDONED
- TBA - TO BE ABANDONED
- TBR - TO BE REMOVED
- TBRL - TO BE RELOCATED
- TYP - TYPICAL

- - MILL AND RESURFACING AREA
- - CONCRETE CAP REPLACEMENT
- - VEGETATED FILTER STRIPS
- - PROPOSED LIGHT POLE
- PB - PROPOSED LIGHTING PULLBOX
- ITS - PROPOSED ITS CABINET
- ITS - PROPOSED ITS PULLBOX
- EP - PROPOSED ELECTRIC PULLBOX

*CURVE DATA: I71-13*
*P.I. = STA. 1450+88.71*
*Δ = 24°44'23" RT*
*Dc = 00°28'00"*
*R = 12,277.67'*
*T = 2,692.64'*
*L = 5,301.35'*
*E = 291.8'*
*Emax = EXISTING*

*CURVE DATA: S161D-2*
*P.I. = STA. 5433+89.78*
*Δ = 05°57'16" RT*
*Dc = 00°45'00"*
*R = 7,639.44'*
*T = 397.32'*
*L = 793.92'*
*E = 10.32'*
*Emax = EXISTING*


HORIZONTAL SCALE IN FEET: 0, 10, 20, 40

PLAN - I-71
STA. 1437+00.00 TO STA. 1448+00.00

DESIGN AGENCY: Jacobs
DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.243 TOTAL: 618

FRA-71-19.10

MODEL: CLP_DT1 - Sheet: 15 WARNER: 66-64 PM | DATE: 2/12/2026 7AM | 2:54:44 PM EST/DST | PSF: C:\HNTB_PENTRI_CMSDT_PSF_C-HNTB_PENTRI_CMSDT_Pen.tbl USER: ChrisLawrence@jacobs.com WORKSPACE: CMSDTDS4D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.12.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. THIS FILE IS PROTECTED UNDER INTERNATIONAL AND LOCAL COPYRIGHT LAWS.




## LEGEND

| | | |
|---|---|---|
| *A.A. - ANCHOR ASSEMBLY* | *EX - EXISTING* | *PA - PREVIOUSLY ABANDONED* |
| *BARR - BARRIER* | *GR - GUARDRAIL* | *TBA - TO BE ABANDONED* |
| *BARR, B1 - BARRIER, TYPE B1* | *I.A. - IMPACT ATTENUATOR* | *TBR - TO BE REMOVED* |
| *BARR, D - BARRIER, TYPE D* | *NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET* | *TBRL - TO BE RELOCATED* |
| *BARR, D (MOD) - BARRIER, TYPE D MODIFIED* | *PAV'T - PAVEMENT* | *TYP - TYPICAL* |
| *B.T.A. - BRIDGE TERMINAL ASSEMBLY* | *PR - PROPOSED* | *- MILL AND RESURFACING AREA* |
| *CONST. - CONSTRUCTION* | *SHLDR - SHOULDER* | *- CONCRETE CAP REPLACEMENT* |
| *CURB, 4-C - CURB, TYPE 4C* | *SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4* | *- VEGETATED FILTER STRIPS* |
| *CURB, 6 - CURB, TYPE 6* | *WDNG - WIDENING* | *- PROPOSED LIGHT POLE* |
| *(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS* | *ATG - ADJUST TO GRADE* | *- PROPOSED LIGHTING PULLBOX* |
| *(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET* | *DND - DO NOT DISTURB* | *- PROPOSED ITS CABINET* |
| | *F&P - FILL AND PLUG* | *- PROPOSED ITS PULLBOX* |
| | *L.O.N. - LENGTH OF NEED* | *- PROPOSED ELECTRIC PULLBOX* |
| | *U.D. - UNDERDRAIN* | |

HORIZONTAL SCALE (IN FEET) 0 10 20 40


# PLAN AND PROFILE
# SINCLAIR ROAD RAMPS A & E


DESIGN AGENCY: Jacobs

DESIGNER: CNR
REVIEWER: MCK 03/11/26
PROJECT ID: 109164
SHEET: P.244 TOTAL: 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: ANSI-B (in) DATE: 3/31/2026 TIME: 2:33:41 PM USERNAME: CNR DGN: FRA-71-19.10_SHEETS_P&P_E.dgn PENTBL: CMYOPT_Pen.tbl USER: Caitlyn.Ridgeway@jacobs.com WORKSPACE: CMYOPT.XWS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




PROFILE - SINCLAIR ROAD
RAMP A


*(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS*


FRA-71-19.10

MODEL: Design A Sheet PWPBSHEET 64x24 IN | DATE: 2/20/2026 TIME: 11:18:03 PM JPOSEN | DGNSET: PDF_Full.dgnlib PENTBL: DMOOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: DMOOTCivil WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVITY: Design Plans PURPOSE: Design Plans FILE: C:\Users\CLawrence1\Desktop\109164_Sheets\109164_Sheets_Ramp A Profile.dgn

| | |
|---|---|
| DESIGN AGENCY | Jacobs |
| DESIGNER | CNR |
| REVIEWER | MCK 03/11/26 |
| PROJECT ID | 109164 |
| SHEET | P.245 |
| TOTAL | 618 |

MODEL: Morse Road Scheet (NAVIGOS) DATE: 3/30/2026 TIME: 11:18:09 PM USER: CHRISTOPHER_PUTT_(A_ohio.transmod@jacobs.com) WORKSPACE: (SHEETS.DGN) WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.00.25
ALL RIGHTS RESERVED. THIS DRAWING IS THE PROPERTY OF JACOBS AND IS NOT TO BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT IS SUPPLIED.




(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS

PROFILE - MORSE ROAD
RAMPS B & C


DESIGN AGENCY
Jacobs


DESIGNER
CNR

REVIEWER
MCK 03/11/26

PROJECT ID
109164

SHEET P.246 TOTAL 618




PROFILE - MORSE ROAD RAMP D
& SINCLAIR ROAD RAMP E

(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING AND ITS PLANS

DESIGN AGENCY
Jacobs

DESIGNER
CNR


REVIEWER
MCK 03/11/26


PROJECT ID
109164


SHEET P.247 TOTAL 618


FRA-71-19.10


MODEL: Morse D and Sinclair E Sheet PAPERSIZE: 60x34 in | DATE: 3/4/2026 TIME: 11:18:14 PM PITDRV: DHDOT_ORP_D_pltcfg_FITPTBL: DHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCivil3D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Morse and Sinclair Ramps\Design\Roadway\Plans\Profiles\FRA-71-19.10 Morse and Sinclair Ramp Profiles.dgn





















CROSS SECTIONS - I-71
STA. 1282+50.00 TO STA. 1287+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CGL


REVIEWER
MCK 02/19/26


PROJECT ID
109164


| Sheet Totals | | | SHEET | TOTAL |
|---|---|---|---|---|
| Seeding | Cut | Fill | P.248 | 618 |


FRA-71-19.10


MODEL: CU_071 - 1282+50.00 [Sheet] PAPERSIZE: 66x44 (in) DATE: 2/27/2026 TIME: 11:18:47 PM SYSTEM: CH0OT_PW_2 • config PANTEL: CH0OT_Pen.ctb USER: Chris.Lawrence3@jacobs.com WORKSPACE: CH0OTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. Unauthorized use or distribution prohibited. This file is the property of the Ohio Department of Transportation and is not to be changed without permission.





















CROSS SECTIONS - I-71
STA. 1287+50.00 TO STA. 1291+50.00

DESIGN AGENCY
Jacobs

DESIGNER
CGL

REVIEWER
MCK 02/19/26

PROJECT ID
109164


| Sheet Totals | | | |
|---|---|---|---|
| Seeding | Cut | Fill | SHEET |
| | | | P.249 |


TOTAL
618


FRA-71-19.10


MODEL: CU_ST1 - 1287+50.00 [Sheet] PAPERSIZE: 66x44 (in) DATE: 2/27/2026 TIME: 11:20:01 PM STORY: ONDOT_PW_F+ pltcfg: FINITEL ONDOT_Pen.ctb USER: Chris.Lawrence1@jacobs.com WORKSPACE: ONDOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PATENT PENDING. DELETE OR MANIPULATE COPYRIGHT NOTICES IS PROHIBITED.


MODEL: CLV_RTI - 1292+00.00 [Sheet] PAPERSIZE: 66x44 (in.) DATE: 3/27/2026 TIME: 11:15:03 PM USER: CHOOT_PW X-refs: PAVING: CHOOT_Pav.dgn LEVEL: CHOOT_Pav.dgn LEVEL: Cross Sections.dgn WORKSPACE: CHOOTCVLS WORKSET: 109164 PRODUCT: OpenRoadDesigner 24.00.02.25
ALL RIGHTS RESERVED. Use of this software is subject to the terms of the Bentley Subscription Services Agreement (SSA) or other applicable license agreement. This software may contain proprietary and confidential information of Bentley Systems, Incorporated and may not be disclosed to third parties without the express written permission of Bentley Systems, Incorporated.





















# CROSS SECTIONS - I-71
# STA. 1292+00.00 TO STA. 1295+50.00

DESIGN AGENCY
Jacobs


DESIGNER
CGL


REVIEWER
MCK 02/19/26


PROJECT ID
109164


| Sheet Totals | | | |
|---|---|---|---|
| Seeding | Cut | Fill | SHEET |
| | | | P.250 |


TOTAL
618





















CROSS SECTIONS - I-71
STA. 1296+00.00 TO STA. 1299+47.33


DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | |
|---|---|---|---|
| Seeding | Cut | Fill | SHEET P.251 / TOTAL 618 |


FRA-71-19.10


MODEL: CU_071 - 1296+00.00 [Sheet] PAPHSER 66x44 (in) | DATE: 2/27/2026 7h45 | 11:23:06 PM SYDNEY, CHOOSE_PSF_F+.ctb| PENTBL: CHOOSE_Pen.tbl| USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHOOSTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. Copyright (c) 2026 Bentley Systems, Incorporated. Unauthorized use, distribution or duplication is prohibited and may result in severe penalties.





















CROSS SECTIONS - I-71
STA. 1299+91.33 TO STA. 1303+24.38


DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | | P.252 | 618 |


FRA-71-19.10


MODEL: CU_ATT - 1299+91.33 Sheet( INPROGRESS 66x44 in.) DATE: 3/3/2026 TIME: 11:23:11 PM SYSTEM: CH0OT_PW_1 config: PENTEL CH0OT_Pen.ctb USER: Chris.Lawrence@dot.ohio.gov WORKSPACE: CH0OTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DATA SHOWN IS FOR INFORMATIONAL PURPOSES ONLY AND IS NOT INTENDED TO BE USED FOR CONSTRUCTION, BIDDING OR PERMITTING PURPOSES.

















CROSS SECTIONS - I-71
STA. 1303+81.85 TO STA. 1307+46.76


DESIGN AGENCY
Jacobs

DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164

| Sheet Totals | | | | | |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | SHEET | TOTAL |
| | | | P.253 | 618 |

FRA-71-19.10

MODEL: CU_ATT - 1303+81.85 [Sheet] PAPERSIZE: 66x44 (in) DATE: 2/27/2026 TIME: 11:24:18 PM STORM: ONDOT_PSH_F+.ctb SETTING: ONDOT_PSH_F+.stng PENTBL: ONDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: ONDOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. Unpublished work. Autodesk, Inc. and its licensors. This file is licensed and subject to the Autodesk Privacy Statement at autodesk.com/privacy.




CROSS SECTIONS - I-71
STA. 1308+00.00 TO STA. 1311+00.00

DESIGN AGENCY
Jacobs


DESIGNER
CGL
REVIEWER
MCK 02/19/26
PROJECT ID
109164


| Sheet Totals | | | | | |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | SHEET | TOTAL | |
| | | | P.254 | 618 | |


FRA-71-19.10


MODEL: CU_071 - 19&I-670 [Sheet] PAPERSIZE: 66x44 (in.) DATE: 3/30/2026 TIME: 11:25:13 PM STORM: ONDOT_PSF_F+.ctb SCALE: Print Scale=1:1 USER: Dhn.Lawrence@jacobs.com WORKSPACE: ONDOTCAD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL USE SUBJECT TO LIMITATIONS IN LICENSE AGREEMENT. USE OF THIS DRAWING FOR ANY PURPOSE OTHER THAN THE SPECIFIC PROJECT FOR WHICH IT WAS PREPARED IS PROHIBITED.


MODEL: C3F_RTI - 1311+50.00 | Sheet: PAPERSPACE - 66x44 (in) | DATE: 3/27/2026 TIME: 11:26:17 PM | STORE: ONDOT_PW_F:\dot\g PENTRE, ONDOT_Pw.ctb | USER: Chris.Lawrence@dot.ohio.gov | WORKSPACE: ONDOTCIVIL3 | WORKSET: 109164 | PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DATA CONTAINED HEREIN IS FOR INFORMATIONAL PURPOSES ONLY AND MAY NOT BE SUITABLE FOR OTHER USES. THE ACCURACY OF THIS DATA IS NOT GUARANTEED. USE AT YOUR OWN RISK.













CROSS SECTIONS - I-71
STA. 1311+50.00 TO STA. 1314+29.01

DESIGN AGENCY
Jacobs


DESIGNER
CGL


REVIEWER
MCK 02/19/26


PROJECT ID
109164


| Sheet Totals | | | |
|---|---|---|---|
| Seeding | Cut | Fill | SHEET TOTAL |
| | | | P.255 618 |


MODEL: CLF_RTI - 1314+50.00 | SHEET: PAPERSIZE_66x44 (in) | DATE: 3/27/2026 7:48:11 PM | STORY: CHOOSY_PSR_F | config: PENTEL CHOOSY_Pen.ctb | USER: Chris.Lawrence@jacobs.com | WORKSPACE: CHOOSY.dc5 | WORKSET: 109164 | PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE OF THIS DESIGN IS SUBJECT TO THE TERMS AND RESTRICTIONS OF THE AGREEMENT UNDER WHICH IT WAS DISTRIBUTED. Copyright Jacobs













CROSS SECTIONS - I-71
STA. 1314+50.00 TO STA. 1317+50.00


DESIGN AGENCY
Jacobs

DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | SHEET | TOTAL |
|---|---|---|---|---|
| Seeding | Cut | Fill | P.256 | 618 |

MODEL: C:\PT1 - 1317+89.49 (Sheet) INPROGRS 64x44 (in) DATE: 1/27/2026 TIME: 11:28:13 PM SYSTEM: ONDOT_PW_F+ config: PENTEL ONDOT_Pen.ctb USER: Chris.Lawrence@jacobs.com WORKSPACE: ONDOTCIVIL9 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACCESS: Use of this software is governed by the Bentley Subscription Services Agreement (SSA) and you are authorized to use this software only if you are subscribed to it.


| | |
|---|---|
| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |





| | |
|---|---|
| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |





| | |
|---|---|
| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |





| | |
|---|---|
| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |





| | |
|---|---|
| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |





| | |
|---|---|
| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |




| | |
|---|---|
| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |




| | |
|---|---|
| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |






CROSS SECTIONS - I-71
STA. 1317+89.49 TO STA. 1321+22.50


DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | | |
|---|---|---|---|---|
| Seeding | Cut | Fill | SHEET | TOTAL |
| | | | P.257 | 618 |





















CROSS SECTIONS - I-71
STA. 1321+50.00 TO STA. 1325+70.39


| | | | |
|---|---|---|---|
| Sheet Totals | | | |
| Seeding | Cut | Fill | |
| | | | |


SHEET P.258
TOTAL 618


DESIGN AGENCY: Jacobs
DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT ID: 109164


FRA-71-19.10


MODEL: CU_ATT - 1321-50.00 | SHEET: PAPERSIZE: 66x44 (in) | DATE: 3/27/2026 TIME: 11:29:09 PM SYSTEM: CHXDOT_PW_F+ config: PENTEL: CHXDOT_Pen.ctb USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHXDOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. Unpublished - Rights reserved under the Copyright Laws of the United States and International Copyright Laws.





















CROSS SECTIONS - I-71
STA. 1325+90.28 TO STA. 1330+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CGL

REVIEWER
MCK 02/19/26


PROJECT ID
109164


| Sheet Totals | | | |
|---|---|---|---|
| Seeding | Cut | Fill | SHEET P.259 |
| | | | TOTAL 618 |

FRA-71-19.10

MODEL: CU_ATT - 1325+90.28 Sheet] PAPERSIZE: 66x44 (in) DATE: 2/27/2026 TIME: 11:30:20 PM STORM: ONDOT_PSI_F+.ctb PENTBL: ONDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: ONDOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. Unpublished work. Autodesk, Inc. Protected by U.S. and international copyright laws. Pursuant to Autodesk Privacy Statement and Policy.

MODEL: CU_ATT - 11Dx36 sht | Sheet: PAPERSPACE - 66x44 (in) | DATE: 3/27/2025 TIME: 11:31:27 PM | STORY: ONEOFF_PW | F-plot: PENTEL ONEOFF_Pen.ctb | USER: Chris.Lawrence@jacobs.com | WORKSPACE: ONEOFFCVS | WORKSET: 109164 | PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DATA CONTAINED HEREIN ARE PROPRIETARY AND CONFIDENTIAL TO JACOBS ENGINEERING GROUP INC.









CROSS SECTIONS - I-71
STA. 1330+02.45 TO STA. 1333+30.00


DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | | Fill | P.260 | 618 |





















CROSS SECTIONS - I-71
STA. 1333+59.80 TO STA. 1336+50.00

DESIGN AGENCY
Jacobs

DESIGNER
CGL

REVIEWER
MCK 02/19/26


PROJECT ID
109164


Sheet Totals

| Seeding | Cut | Fill | SHEET | TOTAL |
|---|---|---|---|---|
| | | | P.261 | 618 |

FRA-71-19.10

MODEL: CU_ATT - 1333+59.80 [Sheet] PAPERSIZE: 66x44 (in) DATE: 3/27/2026 TIME: 11:33:17 PM STORM: ONDOT_PSF_F+.ctb(g) PENTBL: ONDOT_Pen.tbl USER: Chris.Lawrence3@jacobs.com WORKSPACE: ONDOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DATA CONTAINED HEREIN IS PROPRIETARY AND CONFIDENTIAL. USE OF THIS DATA IS RESTRICTED TO AUTHORIZED PURPOSES ONLY.




# CROSS SECTIONS - I-71
# STA. 1337+00.00 TO STA. 1340+50.00

DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164

| Sheet Totals | | | |
|---|---|---|---|
| Seeding | Cut | Fill | SHEET: P.262 |
| | | | TOTAL: 618 |

FRA-71-19.10

MODEL: CLF_RTI - 1317+00.00 [Sheet] PAPERSIZE: 66x44 (in.) DATE: 2/27/2026 TIME: 11:18:44 PM SYSTEM: CH007F_PW-1 config: PENTEL CH007F_Pen.ctb USER: Chris.Lawrence3@jacobs.com WORKSPACE: CH007STCVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL. Powered by MicroStation CONNECT Edition


FRA-71-19.10
MODEL: CU_OT1 - 1341-00.00 | Sheet: PAPER2ER - 66x44 (in) | DATE: 2/20/2026 | TIME: 11:14:44 PM | STORY: CHOOSE_PSR_1 | config: PAVING_CHOOSE_Sheet3D_USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHOOSTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. Unauthorized use or distribution prohibited. This software and related materials are the property of Bentley Systems, Incorporated or its subsidiaries.






CROSS SECTIONS - I-71
STA. 1341+00.00 TO STA. 1342+00.00


DESIGN AGENCY
Jacobs
DESIGNER
CGL
REVIEWER
MCK 02/19/26
PROJECT ID
109164


| Sheet Totals | | | SHEET | TOTAL |
|---|---|---|---|---|
| Seeding | Cut | Fill | P.263 | 618 |













CROSS SECTIONS - I-71
STA. 1405+00.00 TO STA. 1407+80.64

DESIGN AGENCY
Jacobs

DESIGNER
CGL


REVIEWER
MCK 02/19/26


PROJECT ID
109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | | Fill | P.264 | 618 |


FRA-71-19.10


MODEL: CU_OT1 - 1405-0630 [Sheet] PAPERSIZE: 66x44 (in.) DATE: 3/3/2026 TIME: 11:16:04 PM STORY: CHOOT_PSF_F+ pltcfg: FINITEL CHOOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CHOOTSTVDS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE: P:\Projects\FRA\71\109164\Highway\Roadway\Sheets\FRA-71-19.10_CROSS SECTIONS - I-71 STA. 1405+00.00 TO STA. 1407+80.64.dgn













CROSS SECTIONS - I-71
STA. 1408+00.00 TO STA. 1411+64.04

DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT ID: 109164


| Sheet Totals | | | |
|---|---|---|---|
| Seeding | Cut | Fill | SHEET TOTAL |
| | | | P.265 618 |


FRA-71-19.10


MODEL: CU_071 - 1408-0630 [Sheet] PAPERSIZE: 66x44 (in.) DATE: 2/27/2026 TIME: 11:16:43 PM USER: CHOOT_PW X-refs: PAVING: CHOOT_Pav.dgn LEVEL: CHOOT_PW_F-Lighting FEATURE: CHOOT_Pav.dgn USER: Dirk.Lawrence1@jacobs.com WORKSPACE: CHOOTCVDS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. This model and drawing are for design purposes only and may not be used for construction unless specifically noted.


MODEL: CLV_OT1 - 1412+00.00 [Sheet] PAPERSPACE 44x34 (in.) DATE: 3/27/2025 TIME: 11:36:23 PM SYSTEM: CHROOT_PW_F+ config: PENTEL CHROOT_Pen.ctb USER: Chris.Lawrence3@jacobs.com WORKSPACE: CHROOT\CVLS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2025 BENTLEY SYSTEMS, INCORPORATED. This model and drawing are for design purposes only and are not to be used for construction unless specifically noted.






CROSS SECTIONS - I-71
STA. 1412+00.00 TO STA. 1414+00.00


DESIGN AGENCY
Jacobs


DESIGNER
CGL
REVIEWER
MCK 02/19/26
PROJECT ID
109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | | Fill | P.266 | 618 |


MODEL: CLV_OT1 - 1414+14.04 [Sheet] PAPERSIZE: 66x44 (in.) DATE: 2/27/2026 TIME: 11:16:03 PM SYSTEM: CHXOT_PW_1 [chxg] PENTBL: CHXOT_Pen.ctb USER: Chris.Lawrence3@jacobs.com WORKPACE: CHXOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. Use of this software is governed by the Bentley Software Subscription Services Agreement (SSSA) found at https://www.bentley.com/sssa






CROSS SECTIONS - I-71
STA. 1414+14.04 TO STA. 1417+00.00


DESIGN AGENCY
Jacobs


DESIGNED: CGL
REVIEWED: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | | P.267 | 618 |


MODEL: CU_OT1 - 1417+60.00 | Sheet: PAPER2ER - 66x44 (in) | DATE: 3/27/2026 7:14:13 PM | STORY: CHOOT_PSF_F | config: FINITEL: CHOOT_Pen.ctb | USER: Chris.Lawrence3@jacobs.com | WORKSPACE: CHOOTCVDS | WORKSET: 109164 | PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. This model is for exclusive use on the specified project and may not be distributed, copied or disclosed to third parties without the consent of Bentley Systems, Incorporated.





CROSS SECTIONS - I-71
STA. 1417+60.00 TO STA. 1419+00.00

DESIGN AGENCY
Jacobs


DESIGNER
CGL


REVIEWER
MCK 02/19/26


PROJECT ID
109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | | Fill | P.268 | 618 |


MODEL: CU_071 - 1419+50.00 | SHEET: PAPERSIZE 66x44 in | DATE: 3/20/2026 7:14:11 PM | STORY: CHOOT_PSY_F | config: PENTEL CHOOT_Pen.ctb USER: Chris.Lawrence3@jacobs.com WORKSPACE: CHOOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PATENT PENDING. UNAUTHORIZED REPRODUCTION OR DISTRIBUTION PROHIBITED. DAMAGES AND PENALTIES MAY BE IMPOSED.














CROSS SECTIONS - I-71
STA. 1419+50.00 TO STA. 1422+50.00


DESIGN AGENCY
Jacobs


DESIGNER
CGL
REVIEWER
MCK 02/19/26
PROJECT #
109164


| Sheet Totals | | | | | |
|---|---|---|---|---|---|
| Seeding | Cut | | Fill | SHEET | TOTAL |
| | | | | P.269 | 618 |













CROSS SECTIONS - I-71
STA. 1423+00.00 TO STA. 1425+09.51


| | |
|---|---|
| DESIGN AGENCY | Jacobs |
| DESIGNER | CGL |
| REVIEWER | MCK 02/19/26 |
| PROJECT ID | 109164 |


| Sheet Totals | | | | |
|---|---|---|---|---|
| Seeding | Cut | Fill | SHEET | TOTAL |
| | | | P.270 | 618 |

FRA-71-19.10

MODEL: CU_ATT - 141-0630 [Sheet] PAPERSIZE: 66x44 (in.) DATE: 3/30/2026 TIME: 11:38:18 PM STORM: ONDOT_PSF_F+.ctb/g PENTBL: ONDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: ONDOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. THIS FILE IS PROTECTED BY COPYRIGHT LAWS AND INTERNATIONAL TREATIES. UNAUTHORIZED REPRODUCTION, DISPLAY, MODIFICATION OR DISTRIBUTION OF THIS FILE MAY RESULT IN SEVERE CIVIL AND CRIMINAL PENALTIES AND WILL BE PROSECUTED TO THE MAXIMUM EXTENT POSSIBLE UNDER THE LAW.

MODEL: CU_071 - 1425+37.50 [Sheet] PAPERSPACE 66x44 (in.) DATE: 3/20/2026 TIME: 11:39:15 PM SYSTEM: CH0OSY_PW_F+ config: PENTEL CH0OSY_Pen.ctb USER: Chris.Lawrence1@jacobs.com WORKSPACE: CH0OSY1V03 WORKSET: 109164 PRODUCT: OpenRoadDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. THIS FILE IS PROTECTED UNDER U.S. AND INTERNATIONAL COPYRIGHT LAWS.




# CROSS SECTIONS - I-71
# STA. 1425+37.50 TO STA. 1428+50.00

DESIGN AGENCY
Jacobs


DESIGNER
CGL


REVIEWER
MCK 02/19/26


PROJECT ID
109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | | P.271 | 618 |


# CROSS SECTIONS - SINCLAIR ROAD RAMP A
# STA. 2321+00.00 TO STA. 2323+89.58





















FRA-71-19.10

MODEL: BU_ROADWAYS_2321+00.00 | Sheet: PWTRSEC 66x34 in | DATE: 2/20/2026 TIME: 11:46:29 PM PLTDRV: DWG.PDF_FV.xfrm$ PENTBL: DWG.PT | User Id: CGIEB | Chris.Lawrence3@jacobs.com WORKSPACE: CHDOT(TEAM) WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.02.25
ACTIVE FILE PATH: C:\Projects\FRA-71-19.10\Roadway\Alignments\FRA-71-19.10_Alignments.dgn


DESIGN AGENCY
Jacobs


| DESIGNER | |
|---|---|
| CGL | |
| REVIEWER | |
| MCK 02/19/26 | |
| PROJECT # | |
| 109164 | |


| Sheet Totals | | | | | |
|---|---|---|---|---|---|
| Seeding | Cut | | Fill | SHEET | TOTAL |
| | | | | P.272 | 618 |


MODEL: BLF_ROADWAY - 2324+50.00 [Sheet] PAPERSIZE: 66x34 IN | DATE: 2/20/2026 TIME: 11:43:04 PM PLTDRV: DWG2PDF_PSF_FX.dPlt@ PENTBL: DWG2PDF_PNT.tbl USER: ChrisLawrence1@jacobs.com WORKSPACE: CHDOTDEV02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE PROJECT: C:\Projects\FRA-71-19.10\Roadway\Corridors\FRA-71-19.10_Ramp A.dgn


FRA-71-19.10

















# CROSS SECTIONS - SINCLAIR ROAD RAMP A
# STA. 2324+50.00 TO STA. 2327+62.28

DESIGN AGENCY
Jacobs


DESIGNER
CGL


REVIEWER
MCK 02/19/26


PROJECT #
109164


| Sheet Totals | | | SHEET | TOTAL |
|---|---|---|---|---|
| Seeding | Cut | Fill | P.273 | 618 |


MODEL: BLF_ROADCLASS - 2328+00.00 [Sheet] PAPERSIZE: ISO (A1) UNITS: 2/20/2026 TIME: 11:43:15 PM PLOTBY: DROOT_PW_F1.dwg PENTBL: DROOT_PW.ctb USER: ChrisLawrence3@jacobs.com WORKSPACE: CHDOTCIVIL3D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. THIS FILE IS PROVIDED "AS IS" WITH NO WARRANTIES WHATSOEVER.













CROSS SECTIONS - SINCLAIR ROAD RAMP A
STA. 2328+00.00 TO STA. 2331+15.97

DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | SHEET | TOTAL |
|---|---|---|---|---|
| Seeding | Cut | Fill | P.274 | 618 |


MODEL: BIF_ROADWAY - 2331+52.35 [Sheet] PAPERSIZE: ISO A1 (841 x 594mm) DATE: 2/20/2026 TIME: 11:44:23 PM PLTDRV: DWGOUT_PSP_FX.ctb PENTBL: DWGOUT_PSP_FX.ctb USER: ChrisLawrence3@outlook.com WORKSPACE: CHDOTDEVSS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVITY: 0 FILE: C:\Users\ChrisLawrence3\Jacobs\CHDOT Devs - Documents\Projects\FRA-71-19.10\Roadway\Sheets\FRA-71-19.10_Sheets.dgn


FRA-71-19.10


# CROSS SECTIONS - SINCLAIR ROAD RAMP A
# STA. 2331+52.35 TO STA. 2333+59.80














DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | | P.275 | 618 |


# CROSS SECTIONS - MORSE ROAD RAMP B
# STA. 3317+50.00 TO STA. 3320+00.00













DESIGN AGENCY
Jacobs

DESIGNER
CGL


REVIEWER
MCK 02/19/26


PROJECT #
109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | | P.276 | 618 |


FRA-71-19.10


MODEL: BU_ROADWAY - 3317+50.00 Sheet: PAPERSIZE: 66x44 (in.) DATE: 7/7/2025 TIME: 8:11:16 AM PITDRY: DWDY_PW_2-LANE_PENTEL_DWDY_PW.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CMDOT5x02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DATA CONTAINED HEREIN IS PROPRIETARY AND CONFIDENTIAL PER CDOT POLICY DIRECTIVE 1210.0 AND SHALL NOT BE DISCLOSED OUTSIDE OF CDOT WITHOUT PRIOR WRITTEN CONSENT.













CROSS SECTIONS - MORSE ROAD RAMP B
STA. 3320+50.00 TO STA. 3323+50.00


FRA-71-19.10


DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | SHEET | TOTAL |
|---|---|---|---|---|
| Seeding | Cut | Fill | P.277 | 618 |


MODEL: BU_XRORDER - 3320+50.00 [Sheet: PAPERSPACE - 66x44 in.] DATE: 7/7/2025 7:46:11:24 AM BY:CHRIS.LAWRENCE1@JACOBS.COM WORKSPACE: CROSSTOOLS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: C:\Users\chris.lawrence1\Jacobs\Desktop\Morse Road Ramp B\Morse Road Ramp B Cross Sections.dgn





CROSS SECTIONS - MORSE ROAD RAMP B
STA. 3324+00.00 TO STA. 3325+90.28


DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | | Fill | P.278 | 618 |


FRA-71-19.10


MODEL: BLF_ROADWAY - 3324+00.00 [Sheet] PAPERSIZE: 66x44 (in.) DATE: 7/7/2025 TIME: 8:18:46 AM PITDIR: DWGS\P_PSF_F-J.dwg, PENTBL: DWGS\P_PEN.TBL USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWGS\DGN WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2025 BY JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES. THIS DRAWING IS THE PROPERTY OF JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES AND IS NOT TO BE USED, COPIED, REPRODUCED, OR DISCLOSED IN ANY MANNER WITHOUT THE PRIOR WRITTEN PERMISSION OF JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES.













# CROSS SECTIONS - MORSE ROAD RAMP C
# STA. 4297+06.58 TO STA. 4299+50.00


| | | | |
|---|---|---|---|
| DESIGN AGENCY | Jacobs | | |
| DESIGNER | CGL | | |
| REVIEWER | MCK 02/19/26 | | |
| PROJECT ID | 109164 | | |
| Sheet Totals | | | |
| Seeding | Cut | Fill | |
| | | | |
| SHEET | P.279 | TOTAL | 618 |

FRA-71-19.10


MODEL: C:_MODELS\C-4297+06.58 (Sheet) INPERSPECT 64x64 (ex), DATE: 7/17/2025 7:44:1 8:29:44 AM, PITDRY: ON/OFF, PSF: C:\.pltcfg, PENTBL: ON/OFF, PW: 0.00, USER: Chris.Lawrence1@jacobs.com WORKSPACE: ON/OFF/OUT2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT (c) 2024 BENTLEY SYSTEMS, INCORPORATED. PATENTS PENDING. Bentley Confidential Information

MODEL: CU_MAINSEC - 450x560@0.5(Sheet) INPERSON 64x44 (in) DATE: 7/17/2025 7:46:13 AM EDITED ON/OFF: ON PC_F-LAYER: PENTBL ON/OFF: ON USER: Chris.Lawrence1@jacobs.com WORKSPACE: ON/OFF:OFF WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\280\Projects\109164\Design\Roadway\Sheets\FRA-71-19.10_CROSS SECTIONS - MORSE ROAD RAMP C STA. 4300+00.00 TO STA. 4302+00.00.dgn


| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
|---|---|
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |





PGL 889.38
STA. 4301+46.58
XGL 888.75




PGL 889.24
STA. 4301+00.00
XGL 888.42





PGL 888.95
STA. 4300+50.00
XGL 888.11





PGL 888.61
STA. 4300+00.00
XGL 887.79

| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
|---|---|
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |





PGL 889.37
STA. 4302+00.00
XGL 888.99

| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
|---|---|
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |





PGL 889.40
STA. 4301+80.13
XGL 888.93

| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
|---|---|
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |




PGL 889.39
STA. 4301+60.86
XGL 888.80

| Cut Area (SF): 0 | Cut Vol. (CY): 0 |
|---|---|
| Fill Area (SF): 0 | Fill Vol. (CY): 0 |
| Seed Width (FT): | Seed Area (SY): |





PGL 889.39
STA. 4301+58.12
XGL 888.78


# CROSS SECTIONS - MORSE ROAD RAMP C STA. 4300+00.00 TO STA. 4302+00.00


DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | |
|---|---|---|---|
| Seeding | Cut | Fill | SHEET: P.280 |
| | | | TOTAL: 618 |













CROSS SECTIONS - MORSE ROAD RAMP C
STA. 4302+60.86 TO STA. 4305+50.00

FRA-71-19.10

DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | | P.281 | 618 |


MODEL: C:\P_MODELS\C-4302-4686.DGN [Sheet] PAPERSIZE: 66x44 (in.) DATE: 7/7/2025 7:44:1 8:23:5 AM PTDRIVE: DWGPT_PW_2-pltcfg PENTBL: DWGPT_PW.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWGPTDGN2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. UNAUTHORIZED USE, MODIFICATION, OR DISTRIBUTION OF THIS FILE IS PROHIBITED.


MODEL: BLF_ROADWAY - 5300+73.20 Sheet: XSAMPLE01 - 66x34 (in) LAST: 2/17/2026 7:46:11:53 PM PLTDEV: DWGDEF_PSF_FY.ctb|fg PENTBL: DWGDEF_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CHDOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DATA CONTAINED HEREIN IS PROPRIETARY AND CONFIDENTIAL TO JACOBS AND SHALL NOT BE REPRODUCED, USED OR DISCLOSED TO ANY PERSON OR ENTITY WITHOUT THE EXPRESS WRITTEN PERMISSION OF JACOBS.


CROSS SECTIONS - MORSE ROAD RAMP D
STA. 5300+73.20 TO STA. 5303+50.00


















DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | SHEET | TOTAL |
|---|---|---|---|---|
| Seeding | Cut | Fill | P.282 | 618 |


MODEL: BLF_MODELS - 5303+82.83 [Sheet] (MARKER: 66x8 [Arr] UNIT: 2/2/2025 TIME: 11:53:17 PM PLTDEV: DWGDEF_PSF_2-1.stb[g PENTBL: DWGDEF_Penn.ctb USER: Chris.Lawrence@jacobs.com WORKSPACE: CHDOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2025 BENTLEY SYSTEMS, INCORPORATED. PATENT PENDING. PROTECTED BY U.S. AND INTERNATIONAL LAW. e-mail: Bentley Systems, Incorporated 685 Stockton Drive Exton, PA 19341 USA














# CROSS SECTIONS - MORSE ROAD RAMP D
# STA. 5303+82.83 TO STA. 5305+94.13


DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT ID: 109164


| Sheet Totals | | | |
|---|---|---|---|
| Seeding | Cut | Fill | |
| | | | |


SHEET: P.283
TOTAL: 618














CROSS SECTIONS - MORSE ROAD RAMP D
STA. 5306+50.00 TO STA. 5309+00.00


FRA-71-19.10

| Sheet Totals | | | | |
|---|---|---|---|---|
| Seeding | Cut | Fill | SHEET | TOTAL |
| | | | P.284 | 618 |


DESIGN AGENCY
Jacobs
DESIGNER
CGL
REVIEWER
MCK 02/19/26
PROJECT #
109164

MODEL: BU_ROADWAY - 5306+50.00 [Sheet] WARNING: 66x34 [in] UNIT: 1/300'[US] TIME: 11:54:14 PM PLTDRV: DWGDRV_PSF_FX.pltcfg PENTBL: DWGDT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CHDOTCIVD3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ACTIVE FILE PATH: C:\Users\chris.lawrence\Jacobs\Morse Road Ramp D - Documents\Roadway\Cross Sections\FRA-71-19.10 - Morse Road Ramp D - Cross Sections.dgn





| | | | |
|---|---|---|---|
| Cut Area (SF): | 0 | Cut Vol. (CY): | 0 |
| Fill Area (SF): | 0 | Fill Vol. (CY): | 0 |
| Seed Width (FT): | | Seed Area (SY): | |




| | | | |
|---|---|---|---|
| Cut Area (SF): | 0 | Cut Vol. (CY): | 0 |
| Fill Area (SF): | 0 | Fill Vol. (CY): | 0 |
| Seed Width (FT): | | Seed Area (SY): | |




| | | | |
|---|---|---|---|
| Cut Area (SF): | 0 | Cut Vol. (CY): | 0 |
| Fill Area (SF): | 0 | Fill Vol. (CY): | 0 |
| Seed Width (FT): | | Seed Area (SY): | |

CROSS SECTIONS - MORSE ROAD RAMP D
STA. 5309+35.00 TO STA. 5310+50.00

DESIGN AGENCY
Jacobs

DESIGNER
CGL


REVIEWER
MCK 02/19/26


PROJECT ID
109164


| Sheet Totals | | | | | |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | SHEET | TOTAL |
| | | | P.285 | 618 |


FRA-71-19.10


MODEL: BLY_ANDREWS - 5309+35.00 [Sheet] PAYNTER 66x34 (in) | DATE: 2/19/2026 7:46:11.516 AM PITDEV: DHROOT_PSF_2-1.stg PAYNE, DHROOT_Pitt-SE USER: Chris.Lawrence@jacobs.com WORKSPACE: CHDOTCIVD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO BENTLEY SYSTEMS LICENSE AGREEMENT. PRINTED COPIES ARE UNCONTROLLED.









CROSS SECTIONS - SINCLAIR ROAD RAMP E
STA. 6317+89.49 TO STA. 6320+30.83

DESIGN AGENCY
Jacobs

DESIGNER
CGL

REVIEWER
MCK 02/19/26


PROJECT #
109164


| Sheet Totals | | | SHEET | TOTAL |
|---|---|---|---|---|
| Seeding | Cut | Fill | P.286 | 618 |


FRA-71-19.10


MODEL: BLF_ROADCARE 6317+89.49 (Sheet: PAVEMENT 6&14 Int) DATE: 2/20/2026 TIME: 11:15:14 PM PSTDRV: DROOT_PSF_14 xRefs PENTBL: DROOT_Pen.tbl USER: ChrisLlewellyn@jacobs.com WORKSPACE: DROOT\DGN WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS.


MODEL: BU_ROADWAY | ROADWAY | 0.05+93.86 | Sheet | PAPERSIZE: 66x34 in | DATE: 12/02/2026 | TIME: 11:54:34 PM | PSTBY: DPOOT_PW | F: \drive | PSTYPE: DPOOT_PW.ctb | USER: ChrisLawrence@jacobs.com | WORKSPACE: DPOOTDVG | WORKSET: 109164 | PRODUCT: OpenRoadsDesigner 24.00.00.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 JACOBS SOLUTIONS INC. THESE DRAWINGS ARE THE PROPERTY OF JACOBS SOLUTIONS INC. AND ARE NOT TO BE USED IN WHOLE OR IN PART WITHOUT THE WRITTEN PERMISSION OF JACOBS SOLUTIONS INC.


















CROSS SECTIONS - SINCLAIR ROAD RAMP E
STA. 6320+93.86 TO STA. 6323+50.93


DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | | P.287 | 618 |




FRA-71-19.10

MODEL: BU_ROADCARE 6323+63.40 [Sheet: PAVEMENT 6&14 Hor] DATE: 1/30/2026 TIME: 11:57:14 PM PSTDRV: DROOT_PSF_14.dat| PENTBL: DROOT_PNT.tbl USER: ChrisLlewellyn@jacobs.com WORKSPACE: DROOT(SVN) WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. FILE NAME: 109164-FRA-71-19.10-CROSS SECTIONS - SINCLAIR ROAD RAMP E STA. 6323+63.40 TO STA. 6324+50.00.dgn

CROSS SECTIONS - SINCLAIR ROAD RAMP E
STA. 6323+63.40 TO STA. 6324+50.00


DESIGN AGENCY
Jacobs


DESIGNER
CGL

REVIEWER
MCK 02/19/26

PROJECT ID
109164

| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | | P.288 | 618 |




## LEGEND

A.A. - ANCHOR ASSEMBLY
BARR - BARRIER
BARR, B1 - BARRIER, TYPE B1
BARR, D - BARRIER, TYPE D
BARR, D (MOD) - BARRIER, TYPE D MODIFIED
B.T.A. - BRIDGE TERMINAL ASSEMBLY
CONST. - CONSTRUCTION
CURB, 4-C - CURB, TYPE 4C
CURB, 6 - CURB, TYPE 6
(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS
(#) - TAPER CURB HEIGHT FROM 0 TO 4-INCHES OVER 10-FEET

EX. - EXISTING
GR - GUARDRAIL
I.A. - IMPACT ATTENUATOR
NJSS - NEW JERSEY TO SINGLE SLOPE BARRIER TRANSITION - SEE PLAN INSERT SHEET
PAVT - PAVEMENT
PR - PROPOSED
SHLDR - SHOULDER
SST, RM 4.4 - SIGN SUPPORT TRANSITION PER RM-4.4
WDNG - WIDENING
ATG - ADJUST TO GRADE
DND - DO NOT DISTURB
F&P - FILL AND PLUG
L.O.N. - LENGTH OF NEED
U.D. - UNDERDRAIN

PA - PREVIOUSLY ABANDONED
TBA - TO BE ABANDONED
TBR - TO BE REMOVED
TBRL - TO BE RELOCATED
TYP - TYPICAL

- MILL AND RESURFACING AREA
- CONCRETE CAP REPLACEMENT
- VEGETATED FILTER STRIPS
- PROPOSED LIGHT POLE
- PROPOSED ITS CABINET
- PROPOSED ITS PULLBOX
- PROPOSED ELECTRIC PULLBOX

HORIZONTAL SCALE IN FEET
0 10 20 40


# PLAN AND PROFILE MORSE ROAD


DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/11/26
PROJECT ID 109164
SHEET P.289 TOTAL 618

FRA-71-19.10

MODEL: CU_MORSE Date: 04/09/2026 08:44:04 | USER: JSTOLZENBERG | STATE: NJ | PLOTTED: 3/31/2026 7:48:15 PM | PLOTBY: CHRISTOPHER JAMES | PW: 109164 | CTB: ChrisLawrence@jacobs.com WORKSPACE: CHRISTOVAD WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES. THIS DRAWING AND ITS CONTENTS ARE THE PROPERTY OF JACOBS AND SHALL NOT BE REPRODUCED, PUBLISHED, OR USED IN ANY WAY WITHOUT THE PRIOR WRITTEN PERMISSION OF JACOBS.




HORIZONTAL SCALE IN FEET
0 10 20 40


# PLAN AND PROFILE SR 161


DESIGN AGENCY
Jacobs


DESIGNER CNR
REVIEWER MCK 03/11/26
PROJECT ID 109164
SHEET P.290 TOTAL 618


FRA-71-19.10


MODEL: CU=.5#3 - Sheet: PAVEMENT, RM-4.4 (1) | DATE: 3/31/2026 TIME: 3:15:32 PM | FLOW: DWGS_PDF_FLAT_PLAN_PENTEL.DWGSET_PKG.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWGS\TEXT.dwt | WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.35
ACTIVE CONFIGURATION: Default | ACTIVE DESIGN MODEL: FRA-71-19.10.dgn | PLOT STYLE TABLE: Pentel_Color.ctb | PLOTTED BY: Christopher Lawrence | PLOTTED ON: 3/31/2026 3:15:32 PM





















CROSS SECTIONS - SR 161
STA. 47+00.00 TO STA. 50+00.00


DESIGN AGENCY
Jacobs


DESIGNER: CGL
REVIEWER: MCK 02/19/26
PROJECT #: 109164


| Sheet Totals | | | | |
|---|---|---|---|---|
| Seeding | Cut | Fill | SHEET | TOTAL |
| | | | P.291 | 618 |


FRA-71-19.10


MODEL: CLF_SR71_47+00.dgn[Sheet] (REFERENCE: 60x24 in) DATE: 1/30/2026 TIME: 11:59:17 PM PITDWY: DWDP_PDF_in.pltcfg PRNTBL DWDP_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWDOTCIVIL2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS

















CROSS SECTIONS - SR 161
STA. 50+50.00 TO STA. 53+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CGL


REVIEWER
MCK 02/19/26

PROJECT ID
109164

| Sheet Totals | | | | SHEET | TOTAL |
|---|---|---|---|---|---|
| Seeding | Cut | Fill | | P.292 | 618 |

FRA-71-19.10

MODEL: C:\P_SR161_50+50.00\Sheet] [REFFILES: 66x34 in.] DATE: 2/11/2026 TIME: 12:08:47 AM EDITOR: DHOOT_CAD_ID: p-dhoot PENTBL: DHOOT_Print.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\Projects\109164\Highway\Roadway\Plans\Sheets\SR161_50+50.00 TO 53+00.00.dgn




- MILL AND RESURFACING AREA

NOTE: ELEVATIONS ARE SHOWN AT 25' INTERVALS

HORIZONTAL SCALE IN FEET
0 10 20 40

PAVEMENT DETAILS - I-71
STA. 1281+00.00 TO STA. 1292+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CGL


REVIEWER
MCK 02/04/26

PROJECT ID
109164

SHEET P.293 TOTAL 618

FRA-71-19.10

MODEL: CU_071 - Sheet 1 PAYPERIOD: 04x24 (to) 5 DATE: 3/31/2026 TIME: 11:16:44 AM PLTDEV: DWG?C_PSF_(Landg_PENTRL.DWG)?_Pen.tbl USER: ChrisLawrence1@jacobs.com WORKSPACE: CHDOT5142 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: E:\Projects\Jacobs\Ohio\Ohio Turnpike and Infrastructure Commission\109164 - Ohio Turnpike Roadway Improvements\Engineering\Roadway\Plan Sheets\FRA-71-19.10.dgn




HORIZONTAL SCALE IN FEET
0 10 20 40


# PAVEMENT DETAILS - I-71
# STA. 1292+00.00 TO STA. 1303+00.00

DESIGN AGENCY
Jacobs

DESIGNER: CGL
REVIEWER: MCK 02/04/26
PROJECT ID: 109164
SHEET: P.294
TOTAL: 618

FRA-71-19.10


MODEL: CU_071 - Sheet 2 PAYREQST: 66a34 Fri 3 SAVE: 3/31/2026 TIME: 11:16:44 AM USER: CHRISTOPHER.CHRIST_PSF_CJ-HALL PENTEL CHRIST_PSF_CJ-HALL PENTEL CHRIST_PenTel USER: ChrisLawrence1@jacobs.com WORKSPACE: CHRISTOPHER.CHRIST_PSF_CJ-HALL PENTEL CHRIST_PenTel WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DATA CONTAINED HEREIN IS PROPRIETARY AND CONFIDENTIAL. USE OF THIS DATA IS SUBJECT TO THE TERMS AND CONDITIONS OF THE AGREEMENT UNDER WHICH IT WAS PROVIDED. COPYRIGHT 2026




FRA-71-19.10

MODEL: C5F_071 - Sheet 3 PAVEMENT; 66x34 (in.); DATE: 3/31/2026 TIME: 11:16 AM BY/DIR: DIRDY, PDF, [--Unit]; PENTEL DIRDY, Pen Set: USER; Chris.Lawrence1@jacobs.com WORKSPACE: DIRDY/DIR/2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25

| | |
|---|---|
| DESIGN AGENCY | Jacobs |
| DESIGNER | CGL |
| REVIEWER | MCK 02/04/26 |
| PROJECT ID | 109164 |
| SHEET | P.295 |
| TOTAL | 618 |




HORIZONTAL SCALE IN FEET
0 10 20 40


# PAVEMENT DETAILS - I-71
# STA. 1314+50.00 TO STA. 1325+00.00

DESIGN AGENCY
Jacobs

DESIGNED: CGL
REVIEWED: MCK 02/04/26
PROJECT ID: 109164
SHEET: P.296 TOTAL: 618

FRA-71-19.10

MODEL: CU_071 - Sheet 4 PAYMENT: 6ka3-Fe1 DATE: 3/31/2026 TIME: 11:15:44 AM SYSTEM: ONDOT_PDF_2 LAYER: PENTRL ONDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: ONDOTS42 WORKSET: 109164 PRODUCT: CivilRadiodesigner 24.00.02.25
ACCESS AND USE OF THIS DRAWING IS SUBJECT TO THE TERMS AND CONDITIONS SET FORTH IN THE ENGINEER'S SEAL AND NOTICE AGREEMENT AT THE BEGINNING OF THE PLAN SET.




- MILL AND RESURFACING AREA

*NOTE: ELEVATIONS ARE SHOWN AT 25' INTERVALS*

HORIZONTAL SCALE IN FEET
0 10 20 40


# PAVEMENT DETAILS - I-71
## STA. 1325+00.00 TO STA. 1336+00.00

DESIGN AGENCY
Jacobs

| | |
|---|---|
| DESIGNER | CGL |
| REVIEWER | MCK 02/04/26 |
| PROJECT ID | 109164 |
| SHEET | P.297 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: CU_071 - Sheet 5 PAYMENT: 6kA34-Fri 3 DATE: 3/7/2026 TIME: 11:15:4 AM PLTDRV: DWDT_PS-F_LinkN_PENTBL: DWDT_PenTbl USER: ChrisLawrence@jacobs.com WORKPACKET: DWDTDT042 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL INFORMATION. UNAUTHORIZED REPRODUCTION, DISTRIBUTION OR DISCLOSURE PROHIBITED.




▨ - MILL AND RESURFACING AREA

NOTE: ELEVATIONS ARE SHOWN AT 25' INTERVALS

HORIZONTAL SCALE IN FEET
0 10 20 40


PAVEMENT DETAILS - I-71
STA. 1336+00.00 TO STA. 1347+00.00

DESIGN AGENCY
Jacobs

DESIGNER: CGL
REVIEWER: MCK 02/04/26
PROJECT ID: 109164
SHEET: P.298 TOTAL: 618

FRA-71-19.10

MODEL: CU_071 - Sheet 6 PAVEMENT 66x34 (v.) DATE: 3/31/2026 TIME: 11:11:54 AM USER: CHRIS CHROST, PE# 27-24426, PENTEL CHROST, PE# 88 USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHROST0142 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL. THIS FILE IS PROTECTED BY COPYRIGHT LAWS AND INTERNATIONAL TREATIES.




HORIZONTAL SCALE IN FEET
0 10 20 40


PAVEMENT DETAILS - I-71
STA. 1400+00.00 TO STA. 1411+00.00

DESIGN AGENCY
Jacobs

DESIGNER: CGL
REVIEWER: MCK 02/04/26
PROJECT ID: 109164
SHEET: P.299 TOTAL: 618

FRA-71-19.10

MODEL: CU_071 - Sheet 7 PAPERSIZE: 66x34.0in | DATE: 3/31/2026 TIME: 11:15:59 AM BYDIR: ONDOT_PSF_I-Unit_PENTBL: ONDOT_PenSet USER: ChrisLawrence1@jacobs.com WORKSPACE: ONDOTSUS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Fra\FRA-71-19.10\Roadway\Design\Sheets\FRA-71-19.10_Sheet 7.dgn




HORIZONTAL SCALE IN FEET
0 10 20 40


# PAVEMENT DETAILS - I-71
# STA. 1411+00.00 TO STA. 1422+00.00

FRA-71-19.10

MODEL: CU_071 - Sheet II PAYSHEET: 66x34 (in.) DATE: 3/31/2026 TIME: 11:10:00 AM SYSTEM: OHDOT_PSF_I-LHSA_PENTRU_OHDOT_Plan.ctb USER: ChrisLawrence1@jacobs.com WORKSPACE: OHDOTSHEETS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
DATA REFERENCE FILE(S): C:\Projects\OHDOT\109164\Design\Roadway\Plan Production\Pavement Plan\Pavement Plan.dgn

DESIGN AGENCY
Jacobs

DESIGNER: CGL
REVIEWER: MCK 02/04/26
PROJECT ID: 109164
SHEET: P.300 TOTAL: 618




HORIZONTAL SCALE IN FEET
0 10 20 40


# PAVEMENT DETAILS - I-71
# STA. 1422+00.00 TO STA. 1433+00.00

DESIGN AGENCY
Jacobs

DESIGNER: CGL
REVIEWER: MCK 02/04/26
PROJECT ID: 109164
SHEET: P.301 TOTAL: 618


FRA-71-19.10


MODEL: CU_071 - Sheet 9 PAYMENT: 6&4+0+1 DATE: 3/31/2026 TIME: 11:10:04 AM USER: CHRIS.GROOT_PSF_FJ-HNTB_PENTEL.GROOT_PenTel USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHOOTS142 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DATA IN THIS PLAN SET IS PROVIDED FOR INFORMATIONAL PURPOSES ONLY. THE STATE OF OHIO AND ITS REPRESENTATIVES MAKE NO WARRANTY, EXPRESSED OR IMPLIED, AS TO THE ACCURACY OF THE DATA CONTAINED HEREIN.




| DRAINAGE PIPES DETAILS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| REF NO. | CFN | LENGTH | SIZE | TYPE | SLOPE | START STRUCT. REF NO. | START INVERT ELEV. | STOP STRUCT. REF NO. | STOP INVERT ELEV. | DISPOSITION |
| P-1 | | 11.0 ft | 15" | TYPE B | 1.64 % | D-1 | 873.07 ft | D-2 | 872.89 ft | PROPOSED (REMOVE EXISTING) |
| P-2 | | 8.0 ft | 18" | TYPE B | 0.39 % | D-2 | 872.89 ft | CONC. COLLAR | ±872.86 ft | PROPOSED (REMOVE EXISTING) |
| P-3 | | 91.0 ft | 18" | EX. CONC | 0.39 % | CONC. COLLAR | ±872.86 ft | D-3 | ±872.50 ft | DO NOT DISTURB |
| P-4 | | 13.0 ft | 15" | EX. CONC | 3.31 % | D-4 | ±875.87 ft | D-5 | ±875.44 ft | DO NOT DISTURB |
| P-5 | | 90.0 ft | 15" | EX. CONC | 1.68 % | D-5 | ±875.44 ft | D-6 | ±873.93 ft | DO NOT DISTURB |

| DRAINAGE STRUCTURES DETAILS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| REF NO. | ALIGNMENT NAME | STATION | OFFSET | SIDE | TYPE | GRATE/RIM ELEV. | INVERT ELEV. | CONNECTED PIPES | DISPOSITION |
| D-1 | ℄ CONST. I-71 | 1272+85.00 | 6.75 ft | RT | I-3B50, APP | 877.32 ft | 873.07 ft | (OUT) P-1 E 873.07 | PROPOSED (REMOVE EXISTING) |
| D-2 | ℄ CONST. I-71 | 1272+85.00 | 6.75 ft | LT | I-3B50, APP | 877.24 ft | 872.89 ft | (IN) P-1 E 872.89, (OUT) P-2 E 872.89 | PROPOSED (REMOVE EXISTING) |
| D-3 | ℄ CONST. I-71 | 1272+84.98 | 104.20 ft | LT | EX. HW | N/A | ±872.50 ft | (OUT) P-3 E ±872.5 | DO NOT DISTURB |
| D-4 | ℄ CONST. I-71 | 1280+84.50 | 7.11 ft | RT | EX. I-3B | ±879.92 ft | ±875.87 ft | (OUT) P-4 E ±875.87 | DO NOT DISTURB |
| D-5 | ℄ CONST. I-71 | 1280+84.34 | 6.91 ft | LT | EX. I-3B | ±879.84 ft | ±875.44 ft | (IN) P-4 E ±875.44, (OUT) P-5 E ±875.44 | DO NOT DISTURB |
| D-6 | ℄ CONST. I-71 | 1280+84.77 | 96.09 ft | LT | EX. HW | N/A | ±873.93 ft | (OUT) P-5 E ±873.93 | DO NOT DISTURB |




HORIZONTAL SCALE IN FEET
0 25 50 100


# DRAINAGE DETAILS
STA. 1270+50.00 TO STA. 1283+00.00

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/05/26
PROJECT ID 109164
SHEET P.302 TOTAL 618


FRA-71-19.10


MODEL: Drainage Plan - Sheet 1 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:12:23 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Drainage\Sheets\109164_DP001.dgn





| DRAINAGE PIPES DETAILS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| REF NO. | CFN | LENGTH | SIZE | TYPE | SLOPE | START STRUCT. REF NO. | START INVERT ELEV. | STOP STRUCT. REF NO. | STOP INVERT ELEV. | DISPOSITION |
| P-6 | | 13.0 ft | 15" | EX. CONC | 0.42 % | D-7 | ±876.04 ft | D-8 | ±875.99 ft | DO NOT DISTURB |
| P-7 | | 90.0 ft | 18" | EX. CONC | 0.96 % | D-8 | ±875.99 ft | D-9 | ±875.12 ft | DO NOT DISTURB |
| P-8 | | 13.0 ft | 15" | EX. CONC | 0.46 % | D-10 | ±878.31 ft | D-11 | ±878.25 ft | DO NOT DISTURB |
| P-9 | | 90.0 ft | 15" | EX. CONC | 0.40 % | D-11 | ±878.25 ft | D-12 | ±877.89 ft | DO NOT DISTURB |
| P-10 | | 13.0 ft | 15" | EX. CONC | 0.42 % | D-13 | ±880.64 ft | D-14 | ±880.59 ft | DO NOT DISTURB |
| P-11 | | 98.0 ft | 18" | EX. CONC | 0.94 % | D-14 | ±880.59 ft | D-15 | ±879.67 ft | DO NOT DISTURB |

| DRAINAGE STRUCTURES DETAILS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| REF NO. | ALIGNMENT NAME | STATION | OFFSET | SIDE | TYPE | GRATE/RIM ELEV. | INVERT ELEV. | CONNECTED PIPES | DISPOSITION |
| D-7 | ℄ CONST. I-71 | 1283+85.61 | 7.20 ft | RT | EX. I-3B | ±880.79 ft | ±876.04 ft | (OUT) P-6 E ±876.04 | DO NOT DISTURB |
| D-8 | ℄ CONST. I-71 | 1283+85.08 | 6.75 ft | LT | I-3B1, RTG | 881.03 ft | ±875.99 ft | (IN) P-6 E ±875.99, (OUT) P-7 E ±875.99 | RECONSTRUCT TO GRADE |
| D-9 | ℄ CONST. I-71 | 1283+85.67 | 95.64 ft | LT | EX. HW | N/A | ±875.12 ft | (IN) P-7 E ±875.12 | DO NOT DISTURB |
| D-10 | ℄ CONST. I-71 | 1291+34.72 | 6.75 ft | RT | I-3B1, RTG | 883.58 ft | ±878.31 ft | (OUT) P-8 E ±878.31 | RECONSTRUCT TO GRADE |
| D-11 | ℄ CONST. I-71 | 1291+34.32 | 6.75 ft | LT | I-3B1, RTG | 883.60 ft | ±878.25 ft | (IN) P-8 E ±878.25, (OUT) P-9 E ±878.25 | RECONSTRUCT TO GRADE |
| D-12 | ℄ CONST. I-71 | 1291+34.98 | 96.36 ft | LT | EX. HW | N/A | ±877.89 ft | (IN) P-9 E ±877.89 | DO NOT DISTURB |
| D-13 | ℄ CONST. I-71 | 1295+37.33 | 6.75 ft | RT | I-3B1, RTG | 884.93 ft | ±880.64 ft | (OUT) P-10 E ±880.64 | RECONSTRUCT TO GRADE |
| D-14 | ℄ CONST. I-71 | 1295+36.64 | 6.75 ft | LT | I-3B1, RTG | 884.85 ft | ±880.59 ft | (IN) P-10 E ±880.59, (OUT) P-11 E ±880.59 | RECONSTRUCT TO GRADE |
| D-15 | ℄ CONST. I-71 | 1295+38.15 | 103.70 ft | LT | EX. HW | N/A | ±879.67 ft | (IN) P-11 E ±879.67 | DO NOT DISTURB |




HORIZONTAL SCALE IN FEET
0 25 50 100


# DRAINAGE DETAILS
## STA. 1283+00.00 TO STA. 1295+50.00

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/05/26
PROJECT ID 109164
SHEET P.303 TOTAL 618


FRA-71-19.10

MODEL: Drainage Plan - Sheet 2 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:12:29 AM PLTDRV: OHDOT_PDF_Ex.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\40D-Engineering\Drainage\Sheets\109164_DP001.dgn




| DRAINAGE PIPES DETAILS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| REF NO. | CFN | LENGTH | SIZE | TYPE | SLOPE | START STRUCT. REF NO. | START INVERT ELEV. | STOP STRUCT. REF NO. | STOP INVERT ELEV. | DISPOSITION |
| P-12 | | 13.0 ft | 15" | TYPE B | 4.54 % | D-16 | 887.25 ft | D-17 | 886.66 ft | PROPOSED |
| P-13 | | 121.0 ft | 18" | TYPE B | 0.50 % | D-17 | 886.41 ft | D-18 | 885.81 ft | PROPOSED |

| DRAINAGE STRUCTURES DETAILS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| REF NO. | ALIGNMENT NAME | STATION | OFFSET | SIDE | TYPE | GRATE/RIM ELEV. | INVERT ELEV. | CONNECTED PIPES | DISPOSITION |
| D-16 | ℄ CONST. I-71 | 1302+75.00 | 6.75 ft | RT | I-3B1, APP | 893.49 ft | 887.25 ft | (OUT) P-12 E 887.25 | PROPOSED |
| D-17 | ℄ CONST. I-71 | 1302+75.00 | 6.75 ft | LT | I-3B1, APP | 890.92 ft | 886.41 ft | (IN) P-12 E 886.66, (OUT) P-13 E 886.41 | PROPOSED |
| D-18 | ℄ CONST. I-71 | 1302+75.00 | 126.56 ft | LT | HW-2.1 | N/A | 885.81 ft | (IN) P-13 E 885.81 | PROPOSED |




HORIZONTAL SCALE IN FEET
0 25 50 100


# DRAINAGE DETAILS
# STA. 1295+50.00 TO STA. 1308+00.00

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/05/26
PROJECT ID 109164
SHEET P.304 TOTAL 618


FRA-71-19.10


MODEL: Drainage Plan - Sheet 3 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:12:30 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Drainage\Sheets\109164_DP001.dgn






| DRAINAGE STRUCTURES DETAILS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| REF NO. | ALIGNMENT NAME | STATION | OFFSET | SIDE | TYPE | GRATE/RIM ELEV. | INVERT ELEV. | CONNECTED PIPES | DISPOSITION |
| D-19 | ℄ CONST. I-71 | 1308+51.58 | 6.75 ft | RT | I-3B1, APP | 900.39 ft | 896.14 ft | (OUT) P-14 S 896.14 | PROPOSED |
| D-20 | ℄ CONST. I-71 | 1309+35.18 | 6.75 ft | LT | I-3B1, APP | 897.11 ft | 886.44 ft | (IN) P-14 S 892.86, (OUT) P-15 E 886.44 | PROPOSED |
| D-21 | ℄ CONST. RAMP D | 5309+62.38 | 34.52 ft | RT | EX. CB-2-2B | ±872.76 ft | ±868.51 ft | (IN) P-18 W ±868.56, (IN) P-17 E ±868.58, (OUT) P-19 S ±868.51 | DO NOT DISTURB |
| D-22 | ℄ CONST. RAMP D | 5309+61.86 | 26.31 ft | LT | EX. CB-2-2B | ±873.46 ft | ±869.61 ft | (OUT) P-18 W ±869.61 | DO NOT DISTURB |
| D-23 | ℄ CONST. I-71 | 1311+38.23 | 129.37 ft | LT | MH-3 | 888.50 ft | ±865.40 ft | (IN) P-19 S ±865.40 | RECONSTRUCT TO GRADE |
| D-24 | ℄ CONST. I-71 | 1310+16.00 | 65.17 ft | RT | CB-3 | 899.52 ft | 895.27 ft | (OUT) P-20 W 895.27 | PROPOSED |
| D-25 | ℄ CONST. I-71 | 1310+16.00 | 98.00 ft | RT | HW-2.1 | N/A | 895.12 ft | (IN) P-20 W 895.12 | PROPOSED |
| D-26 | ℄ CONST. I-71 | 1311+31.47 | 83.25 ft | LT | I-3D | 902.11 ft | 897.71 ft | (OUT) P-21 E 897.71 | PROPOSED |
| D-27 | ℄ CONST. I-71 | 1311+29.71 | 113.44 ft | LT | HW-2.1 | N/A | 896.02 ft | (IN) P-21 E 896.02 | PROPOSED |
| D-28 | ℄ CONST. I-71 | 1314+84.00 | 65.17 ft | RT | CB-3 | 900.34 ft | 896.09 ft | (OUT) P-22 W 896.09 | PROPOSED |
| D-29 | ℄ CONST. I-71 | 1314+84.00 | 80.00 ft | RT | HW-2.1 | N/A | 895.99 ft | (IN) P-22 W 895.99 | PROPOSED |
| D-30 | ℄ CONST. I-71 | 1318+35.00 | 6.75 ft | RT | I-3B1, APP | 899.44 ft | 893.19 ft | (OUT) P-23 E 893.19 | PROPOSED (REMOVE EXISTING) |
| D-31 | ℄ CONST. I-71 | 1318+34.70 | 6.75 ft | LT | I-3B1, APP | 895.00 ft | 890.75 ft | (IN) P-23 E 892.00, (OUT) P-24 S 890.75 | PROPOSED (REMOVE EXISTING) |
| D-32 | ℄ CONST. I-71 | 1320+35.32 | 9.79 ft | LT | MH-3 | 893.18 ft | 889.23 ft | (IN) P-24 S 889.23, (OUT) P-25 SW 889.23 | PROPOSED (REMOVE EXISTING) |


| DRAINAGE PIPES DETAILS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| REF NO. | CFN | LENGTH | SIZE | TYPE | SLOPE | START STRUCT. REF NO. | START INVERT ELEV. | STOP STRUCT. REF NO. | STOP INVERT ELEV. | DISPOSITION |
| P-14 | | 85.0 ft | 15" | TYPE B | 3.86 % | D-19 | 896.14 ft | D-20 | 892.86 ft | PROPOSED |
| P-15 | | 10.0 ft | 15" | TYPE B | 3.00 % | D-20 | 886.44 ft | CONC. COLLAR | ±886.14 ft | PROPOSED |
| P-16 | | 118.0 ft | 15" | EX. CONC | 3.00 % | CONC. COLLAR | ±886.14 ft | BEND | ±883.60 ft | EXISTING |
| P-17 | | 27.0 ft | 15" | EX. CONC | 51.93 % | BEND | ±883.60 ft | D-21 | ±868.58 ft | DO NOT DISTURB |
| P-18 | | 61.0 ft | 18" | EX. CONC | 1.72 % | D-22 | ±869.61 ft | D-21 | ±868.56 ft | DO NOT DISTURB |
| P-19 | | 214.0 ft | 18" | EX. CONC | 1.45 % | D-21 | ±868.51 ft | D-23 | ±865.40 ft | DO NOT DISTURB |
| P-20 | | 31.0 ft | 15" | TYPE C | 0.50 % | D-24 | 895.27 ft | D-25 | 895.12 ft | PROPOSED |
| P-21 | | 30.0 ft | 15" | TYPE C | 5.65 % | D-26 | 897.71 ft | D-27 | 896.02 ft | PROPOSED |
| P-22 | | 14.0 ft | 15" | TYPE C | 0.70 % | D-28 | 896.09 ft | D-29 | 895.99 ft | PROPOSED |
| P-23 | | 12.0 ft | 15" | TYPE B | 9.92 % | D-30 | 893.19 ft | D-31 | 892.00 ft | PROPOSED (REMOVE EXISTING) |
| P-24 | | 201.0 ft | 15" | TYPE B | 0.76 % | D-31 | 890.75 ft | D-32 | 889.23 ft | PROPOSED (REMOVE EXISTING) |
| P-25 | | 151.0 ft | 15" | TYPE B | 0.76 % | D-32 | 889.23 ft | D-34 | 888.08 ft | PROPOSED (REMOVE EXISTING) |




HORIZONTAL SCALE IN FEET
0 25 50 100


# DRAINAGE DETAILS
## STA. 1308+00.00 TO STA. 1320+50.00

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/05/26
PROJECT ID 109164
SHEET P.305 TOTAL 618


FRA-71-19.10


MODEL: Drainage Plan - Sheet 4 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:12:31 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Drainage\Sheets\109164_DP001.dgn






| DRAINAGE STRUCTURES DETAILS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| REF NO. | ALIGNMENT NAME | STATION | OFFSET | SIDE | TYPE | GRATE/RIM ELEV. | INVERT ELEV. | CONNECTED PIPES | DISPOSITION |
| D-33 | ℄ CONST. I-71 | 1321+86.00 | 6.75 ft | RT | I-3B1, APP | 895.35 ft | 889.10 ft | (OUT) P-26 SE 889.10 | PROPOSED (REMOVE EXISTING) |
| D-34 | ℄ CONST. I-71 | 1321+86.00 | 6.75 ft | LT | I-3B1, APP | 891.33 ft | 884.20 ft | (IN) P-26 SE 888.08, (IN) P-25 SW 888.08, (OUT) P-27 W 884.20 | PROPOSED (REMOVE EXISTING) |
| D-35 | ℄ CONST. RAMP E | 6322+03.71 | 78.19 ft | LT | EX. CB | ±887.23 ft | ±882.33 ft | (OUT) P-29 W ±882.33 | DO NOT DISTURB |
| D-36 | ℄ CONST. RAMP E | 6321+89.84 | 45.03 ft | LT | CB-8 | 885.22 ft | 881.73 ft | (IN) P-29 W ±882.06, (OUT) P-30 W 881.73 | PROPOSED |
| D-37 | ℄ CONST. RAMP E | 6321+85.42 | 28.19 ft | RT | MH-3 | 892.74 ft | ±880.66 ft | (IN) P-28 SE ±883.14, (IN) P-30 W 881.16, (OUT) P-31 S ±880.66 | RECONSTRUCT TO GRADE |
| D-38 | ℄ CONST. I-71 | 1322+87.86 | 124.36 ft | LT | EX. CB | ±884.37 ft | ±876.87 ft | (IN) P-31 S ±878.02, (IN) P-37 NE ±877.86, (OUT) P-40A E ±876.87 | DO NOT DISTURB |
| D-39 | ℄ CONST. I-71 | 1323+87.03 | 6.75 ft | RT | I-3B1, APP | 893.47 ft | 886.11 ft | (OUT) P-32 SE 886.11 | PROPOSED (REMOVE EXISTING) |
| D-40 | ℄ CONST. I-71 | 1323+86.81 | 6.75 ft | LT | I-3B1, APP | 889.77 ft | 885.22 ft | (IN) P-32 SE 885.22, (IN) P-33 NE 885.47, (OUT) P-35 SE 885.22 | PROPOSED (REMOVE EXISTING) |
| D-41 | ℄ CONST. I-71 | 1324+56.25 | 6.75 ft | LT | I-3B1, APP | 889.65 ft | 885.75 ft | (IN) P-34 NE 885.90, (OUT) P-33 NE 885.75 | PROPOSED |
| D-42 | ℄ CONST. I-71 | 1324+86.35 | 6.75 ft | RT | I-3B1, APP | 893.23 ft | 887.03 ft | (OUT) P-34 NE 887.03 | PROPOSED |
| D-43 | ℄ CONST. RAMP A | 2323+74.66 | 34.14 ft | RT | MH-3 | 892.23 ft | 878.95 ft | (IN) P-36 SE 882.85, (IN) P-38 N 879.05, (OUT) P-37 NE 878.95 | RECONSTRUCT TO GRADE |
| D-44 | ℄ CONST. RAMP A | 2324+65.38 | 30.74 ft | LT | CB-8 | 884.50 ft | 881.93 ft | (OUT) P-39 SW 881.93 | PROPOSED |
| D-47 | ℄ CONST. RAMP A | 2320+57.48 | 9.80 ft | LT | EX. MH | ±888.75 ft | ±875.55 ft | (IN) P-40B E ±875.55, (IN) P-43 S ±880.95, (OUT) P-44 E ±875.55 | DO NOT DISTURB |
| D-48 | ℄ CONST. RAMP A | 2319+84.50 | 4.07 ft | LT | EX. MH | ±887.17 ft | ±875.33 ft | (IN) P-44 E ±875.33 | DO NOT DISTURB |

| DRAINAGE PIPES DETAILS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| REF NO. | CFN | LENGTH | SIZE | TYPE | SLOPE | START STRUCT. REF NO. | START INVERT ELEV. | STOP STRUCT. REF NO. | STOP INVERT ELEV. | DISPOSITION |
| P-25 | | 151.0 ft | 15" | TYPE B | 0.76 % | D-32 | 889.23 ft | D-34 | 888.08 ft | PROPOSED (REMOVE EXISTING) |
| P-26 | | 12.0 ft | 15" | TYPE B | 8.50 % | D-33 | 889.10 ft | D-34 | 888.08 ft | PROPOSED (REMOVE EXISTING) |
| P-27 | | 8.0 ft | 18" | TYPE B | 1.20 % | D-34 | 884.20 ft | CONC. COLLAR | ±884.10 ft | PROPOSED (REMOVE EXISTING) |
| P-28 | | 80.0 ft | 18" | EX. CONC | 1.20 % | CONC. COLLAR | ±884.10 ft | D-37 | ±883.14 ft | DO NOT DISTURB |
| P-29 | | 34.0 ft | 8" | EX. CONC | 0.80 % | D-35 | ±882.33 ft | D-36 | ±882.06 ft | DO NOT DISTURB |
| P-30 | | 73.0 ft | 15" | TYPE B | 0.78 % | D-36 | 881.73 ft | D-37 | 881.16 ft | PROPOSED (REMOVE EXISTING) |
| P-31 | | 110.0 ft | 18" | EX. CONC | 2.40 % | D-37 | ±880.66 ft | D-38 | ±878.02 ft | DO NOT DISTURB |
| P-32 | | 12.0 ft | 15" | TYPE B | 7.42 % | D-39 | 886.11 ft | D-40 | 885.22 ft | PROPOSED (REMOVE EXISTING) |
| P-33 | | 70.0 ft | 15" | TYPE B | 0.40 % | D-41 | 885.75 ft | D-40 | 885.47 ft | PROPOSED |
| P-34 | | 32.0 ft | 15" | TYPE B | 3.53 % | D-42 | 887.03 ft | D-41 | 885.90 ft | PROPOSED |
| P-35 | | 8.0 ft | 15" | TYPE B | 2.10 % | D-40 | 885.22 ft | CONC. COLLAR | ±885.05 ft | PROPOSED (REMOVE EXISTING) |
| P-36 | | 105.0 ft | 15" | EX. CONC | 2.10 % | CONC. COLLAR | ±885.05 ft | D-43 | ±882.85 ft | DO NOT DISTURB |
| P-37 | | 101.0 ft | 21" | EX. CONC | 1.08 % | D-43 | ±878.95 ft | D-38 | ±877.86 ft | DO NOT DISTURB |
| P-38 | | 99.00 ft | 21" | EX. CONC | 2.57 % | CONC. COLLAR | ±881.60 ft | D-43 | ±879.05 ft | DO NOT DISTURB |
| P-39 | | 13.0 ft | 21" | TYPE C | 2.57% | D-44 | 881.93 ft | CONC. COLLAR | ±881.60 ft | PROPOSED (REMOVE EXISTING) |
| P-40 | | 292.0 ft | 36" | EX. CONC | 0.45 % | D-38 | 876.87 ft | D-47 | 875.55 ft | REMOVE BLIND TAP CONNECTION |
| P-41 | | 8.0 ft | 36" | TYPE C | 0.45 % | CONC. COLLAR | ±876.47 ft | CONC. COLLAR | ±876.43 ft | PROPOSED (PIPE REPAIR) |
| P-44 | | 73.0 ft | 36" | EX. CONC | 0.30 % | D-47 | ±875.55 ft | D-48 | ±875.33 ft | DO NOT DISTURB |




HORIZONTAL SCALE IN FEET
0 25 50 100


DRAINAGE DETAILS
STA. 1320+50.00 TO STA. 1325+50.00

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/05/26
PROJECT ID 109164
SHEET P.306 TOTAL 618


FRA-71-19.10


MODEL: Drainage Plan - Sheet 5 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:12:33 AM PLTDRV: OHDOT_PDF_Ex.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Drainage\Sheets\109164_DP001.dgn





| DRAINAGE PIPES DETAILS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| REF NO. | CFN | LENGTH | SIZE | TYPE | SLOPE | START STRUCT. REF NO. | START INVERT ELEV. | STOP STRUCT. REF NO. | STOP INVERT ELEV. | DISPOSITION |
| P-45 | | 47.0 ft | 15" | TYPE B | 2.64 % | D-49 | 887.65 ft | D-50 | 886.41 ft | PROPOSED |
| P-46 | | 124.0 ft | 18" | TYPE B | 0.50 % | D-50 | 886.16 ft | D-51 | 885.54 ft | PROPOSED |
| P-47 | | 12.00 ft | 15" | TYPE B | 4.50 % | D-52 | 890.61 ft | D-53 | 890.07 ft | PROPOSED (REMOVE EXISTING) |
| P-48 | | 106.0 ft | 15" | EX. CONC | 1.86 % | D-53 | ±890.07 ft | D-54 | ±888.10 ft | DO NOT DISTURB |
| P-49 | | 294.0 ft | 15" | TYPE B | 0.80 % | D-55 | 895.88 ft | D-56 | 893.53 ft | PROPOSED |
| P-50 | | 12.0 ft | 15" | TYPE B | 0.42 % | D-56 | 893.02 ft | D-57 | 892.97 ft | PROPOSED (REMOVE EXISTING) |
| P-51 | | 90.0 ft | 15" | EX. CONC | 1.36 % | D-57 | ±892.97 ft | D-58 | ±891.75 ft | DO NOT DISTURB |

| DRAINAGE STRUCTURES DETAILS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| REF NO. | ALIGNMENT NAME | STATION | OFFSET | SIDE | TYPE | GRATE/RIM ELEV. | INVERT ELEV. | CONNECTED PIPES | DISPOSITION |
| D-49 | ℄ CONST. I-71 | 1326+50.00 | 6.75 ft | RT | I-3B1, APP | 893.90 ft | 887.65 ft | (OUT) P-45 NE 887.65 | PROPOSED |
| D-50 | ℄ CONST. I-71 | 1326+05.00 | 6.75 ft | LT | I-3B1, APP | 890.18 ft | 886.16 ft | (IN) P-45 NE 886.41, (OUT) P-46 SE 886.16 | PROPOSED |
| D-51 | ℄ CONST. I-71 | 1326+04.85 | 128.19 ft | LT | HW-2.1 | N/A | 885.54 ft | (IN) P-46 SE 885.54 | PROPOSED |
| D-52 | ℄ CONST. I-71 | 1331+85.58 | 6.75 ft | RT | I-3B1, APP | 897.45 ft | 890.61 ft | (OUT) P-47 SE 890.61 | PROPOSED (REMOVE EXISTING) |
| D-53 | ℄ CONST. I-71 | 1331+85.41 | 6.75 ft | LT | I-3B1, RTG | 895.68 ft | ±890.07 ft | (IN) P-47 SE 890.07, (OUT) P-48 SE ±890.07 | RECONSTRUCT TO GRADE |
| D-54 | ℄ CONST. I-71 | 1331+86.76 | 111.87 ft | LT | EX. HW | N/A | ±888.10 ft | (IN) P-48 SE ±888.10 | DO NOT DISTURB |
| D-55 | ℄ CONST. I-71 | 1337+00.00 | 6.75 ft | RT | I-3B1, APP | 900.14 ft | 895.88 ft | (OUT) P-49 NE 895.88 | PROPOSED |
| D-56 | ℄ CONST. I-71 | 1334+05.69 | 6.75 ft | RT | I-3B1, APP | 898.03 ft | 893.02 ft | (IN) P-49 NE 893.53, (OUT) P-68 SE 893.02 | PROPOSED (REMOVE EXISTING) |
| D-57 | ℄ CONST. I-71 | 1334+04.81 | 6.75 ft | LT | I-3B1, RTG | 897.88 ft | ±892.97 ft | (IN) P-68 SE 892.97, (OUT) P-51 SE ±892.97 | RECONSTRUCT TO GRADE |
| D-58 | ℄ CONST. I-71 | 1334+06.12 | 95.49 ft | LT | EX. HW | N/A | ±891.75 ft | (IN) P-51 SE ±891.75 | DO NOT DISTURB |




HORIZONTAL SCALE IN FEET
0 25 50 100


# DRAINAGE DETAILS
## STA. 1325+50.00 TO STA. 1338+00.00

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/05/26
PROJECT ID 109164
SHEET P.307 TOTAL 618


FRA-71-19.10


MODEL: Drainage Plan - Sheet 6 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:12:34 AM PLTDRV: OHDOT_PDF_Ex.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6AA20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\40D-Engineering\Drainage\Sheets\109164_DP001.dgn






| DRAINAGE PIPES DETAILS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| REF NO. | CFN | LENGTH | SIZE | TYPE | SLOPE | START STRUCT. REF NO. | START INVERT ELEV. | STOP STRUCT. REF NO. | STOP INVERT ELEV. | DISPOSITION |
| P-53 | | 30.0 ft | 15" | TYPE C | 0.85 % | D-61 | 932.27 ft | D-62 | 932.01 ft | PROPOSED |
| P-54 | | 16.0 ft | 15" | TYPE C | 1.75 % | D-63 | 932.88 ft | D-64 | 932.60 ft | PROPOSED |
| P-55 | | 16.0 ft | 15" | TYPE C | 1.75 % | D-65 | 933.01 ft | D-66 | 932.73 ft | PROPOSED |
| P-56 | | 17.0 ft | 15" | TYPE C | 2.50 % | D-67 | 933.28 ft | D-68 | 932.86 ft | PROPOSED |
| P-57 | | 8.00 ft | 15" | TYPE B | 5.40 % | D-69 | 919.34 ft | CONC. COLLAR | ±918.91 ft | PROPOSED (REMOVE EXISTING) |
| P-58 | | 63.0 ft | 15" | EX. CONC | 5.40 % | CONC. COLLAR | ±918.91 ft | D-71 | ±915.51 ft | DO NOT DISTURB |
| P-59 | | 102.0 ft | 15" | EX. CONC | 1.00 % | D-70 | ±919.43 ft | D-71 | ±918.41 ft | DO NOT DISTURB |
| P-60 | | 81.0 ft | 15" | EX. CONC | 5.40 % | D-71 | ±915.51 ft | D-72 | ±911.13 ft | DO NOT DISTURB |


| DRAINAGE STRUCTURES DETAILS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| REF NO. | ALIGNMENT NAME | STATION | OFFSET | SIDE | TYPE | GRATE/RIM ELEV. | INVERT ELEV. | CONNECTED PIPES | DISPOSITION |
| D-61 | ℄ CONST. I-71 | 1414+49.04 | 77.00 ft | LT | I-3D | 936.52 ft | 932.27 ft | (OUT) P-53 E 932.27 | PROPOSED |
| D-62 | ℄ CONST. I-71 | 1414+49.03 | 109.15 ft | LT | HW-2.1 | N/A | 932.01 ft | (IN) P-53 E 932.01 | PROPOSED |
| D-63 | ℄ CONST. I-71 | 1414+84.04 | 62.42 ft | RT | I-3D | 937.13 ft | 932.88 ft | (OUT) P-54 W 932.88 | PROPOSED |
| D-64 | ℄ CONST. I-71 | 1414+84.04 | 80.97 ft | RT | HW-2.1 | N/A | 932.60 ft | (IN) P-54 W 932.60 | PROPOSED |
| D-65 | ℄ CONST. I-71 | 1417+25.95 | 77.00 ft | LT | I-3D | 937.26 ft | 933.01 ft | (OUT) P-55 E 933.01 | PROPOSED |
| D-66 | ℄ CONST. I-71 | 1417+25.95 | 95.84 ft | LT | HW-2.1 | N/A | 932.73 ft | (IN) P-55 E 932.73 | PROPOSED |
| D-67 | ℄ CONST. I-71 | 1417+25.95 | 62.42 ft | RT | I-3D | 937.53 ft | 933.28 ft | (OUT) P-56 W 933.28 | PROPOSED |
| D-68 | ℄ CONST. I-71 | 1417+25.95 | 81.77 ft | RT | HW-2.1 | N/A | 932.86 ft | (IN) P-56 W 932.86 | PROPOSED |
| D-69 | ℄ CONST. I-71 | 1425+11.17 | 0.00 ft | ℄ | I-4B1 | 924.23 ft | 919.34 ft | (OUT) P-57 E 919.34 | PROPOSED (REMOVE EXISTING) |
| D-70 | ℄ CONST. I-71 | 1424+14.95 | 80.37 ft | LT | EX. CB | ±925.65 ft | ±919.43 ft | (OUT) P-59 S ±919.43 | DO NOT DISTURB |
| D-71 | ℄ CONST. I-71 | 1425+15.43 | 70.97 ft | LT | EX. CB | ±923.18 ft | ±915.51 ft | (IN) P-59 S ±918.41, (IN) P-58 E ±915.51, (OUT) P-60 E ±915.51 | DO NOT DISTURB |
| D-72 | ℄ CONST. I-71 | 1425+20.24 | 151.78 ft | LT | EX. HW | N/A | ±911.13 ft | (IN) P-60 E ±911.13 | DO NOT DISTURB |




HORIZONTAL SCALE IN FEET
0 25 50 100


# DRAINAGE DETAILS
## STA. 1414+00.00 TO STA. 1426+50.00

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/05/26
PROJECT ID 109164
SHEET P.308 TOTAL 618


FRA-71-19.10

MODEL: Drainage Plan - Sheet 7 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:12:36 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\40D-Engineering\Drainage\Sheets\109164_DP001.dgn




| DRAINAGE PIPES DETAILS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| REF NO. | CFN | LENGTH | SIZE | TYPE | SLOPE | START STRUCT. REF NO. | START INVERT ELEV. | STOP STRUCT. REF NO. | STOP INVERT ELEV. | DISPOSITION |
| P-61 | | 487.0 ft | 15" | EX. CONC | 0.37 % | D-73 | ±917.92 ft | CONC. COLLAR | ±916.12 ft | DO NOT DISTURB |
| P-62 | | 8.0 ft | 15" | TYPE B | 0.37 % | CONC. COLLAR | ±916.12 ft | D-74 | 916.09 ft | PROPOSED (REMOVE EXISTING) |
| P-63 | | 8.0 ft | 15" | TYPE B | 0.39 % | D-74 | 916.09 ft | CONC. COLLAR | ±916.06 ft | PROPOSED (REMOVE EXISTING) |
| P-64 | | 102.0 ft | 15" | EX. CONC | 0.39 % | CONC. COLLAR | ±916.06 ft | D-75 | ±915.66 ft | DO NOT DISTURB |

| DRAINAGE STRUCTURES DETAILS | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| REF NO. | ALIGNMENT NAME | STATION | OFFSET | SIDE | TYPE | GRATE/RIM ELEV. | INVERT ELEV. | CONNECTED PIPES | DISPOSITION |
| D-73 | ℄ CONST. I-75 | 1450+82.24 | 0.00 ft | ℄ | EX. INLET | 923.05 ft | 917.92 ft | (OUT) P-61 N 917.92 | DO NOT DISTURB |
| D-74 | ℄ CONST. I-75 | 1445+87.33 | 0.00 ft | ℄ | I-3D50 | 921.79 ft | 916.09 ft | (IN) P-62 N 916.09, (OUT) P-63 E 916.09 | PROPOSED |
| D-75 | ℄ CONST. I-75 | 1445+87.26 | 110.27 ft | LT | EX. HW | N/A | ±915.66 ft | (IN) P-64 E ±915.66 | DO NOT DISTURB |




HORIZONTAL SCALE IN FEET
0 25 50 100


# DRAINAGE DETAILS
## STA. 1445+00.00 TO STA. 1451+00.00

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/05/26
PROJECT ID 109164
SHEET P.309 TOTAL 618

FRA-71-19.10

MODEL: Drainage Plan - Sheet 8 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:12:37 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\Drainage\Sheets\109164_DP001.dgn





HORIZONTAL
SCALE IN FEET
0 10 20 40

## ESTIMATED QUANTITIES

| ITEM | QUANTITY | UNIT | DESCRIPTION |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

## EXISTING STRUCTURE

*TYPE:* ROUND CONCRETE PIPE
*SIZE:* 42"
*SKEW:* 0°
*ALIGNMENT:* TANGENT
*CFN:* 1807089




# CULVERT DETAIL
# STA. 1412+96.92

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/05/26
PROJECT ID 109164
SHEET P.310 TOTAL 618

FRA-71-19.10

MODEL: Profile Run Culvert - Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:12:59 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Drainage\Sheets\109164_DC001.dgn

**PROPOSED WORK:**

THE FOLLOWING PROPOSED WORK APPLIES AT THE LOCATION BELOW:

WALL NO. 1 - I-71 SB EXIT RAMP TO 11TH AVE.

PROPOSED WORK:

1) REMOVING A PORTION OF THE EXISTING CAST-IN-PLACE REINFORCED CONCRETE RETAINING WALL AND REGRADING.
2) REMOVING AND REPLACING A PORTION OF THE EXISTING CAST-IN-PLACE REINFORCED CONCRETE RETAINING WALL
3) 519 PATCHING
4) REMOVING AND REPLACING EXISTING WALL MOUNTED FENCING
5) CONCRETE SEALING WITH EPOXY-URETHANE

**STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS**

REFER TO THE FOLLOWING STANDARD DRAWINGS:

F-1.1 REVISED 07/19/2013

AND TO THE FOLLOWING SUPPLEMENTAL SPECIFICATION(S):

N/A

**DESIGN DATA**

CONCRETE CLASS QC1 (RETAINING WALL) - COMPRESSIVE STRENGTH 4.0 KSI

EPOXY-COATED REINFORCING STEEL - MINIMUM YIELD STRENGTH 60 KSI.

**EXISTING STRUCTURE VERIFICATION**

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK, BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO C&MS SECTIONS 102.05, 105.02 AND 513.04 FOR FURTHER INFORMATION.

**ITEM 202 - PORTIONS OF STRUCTURE REMOVED, AS PER PLAN**

THE PROVISIONS OF C&MS 202 APPLY, IN ADDITION TO THOSE LISTED HEREIN. THE ITEM SHALL INCLUDE THE ELEMENTS INDICATED IN THE PLANS AND GENERAL NOTES AND THAT ARE NOT SEPARATELY LISTED FOR PAYMENT. ITEMS TO BE REMOVED INCLUDE ALL EXISTING MATERIALS BEING REPLACED BY NEW CONSTRUCTION AND MISCELLANEOUS ITEMS THAT ARE NOT SHOWN TO BE INCORPORATED INTO THE FINAL CONSTRUCTION AND ARE DIRECTED TO BE REMOVED BY THE ENGINEER. THE DEPARTMENT WILL NOT PERMIT THE USE OF EXPLOSIVES, HEADACHE BALLS AND/OR HOE-RAMS. DO NOT BEGIN WORK UNTIL THE ENGINEER ACCEPTS THE METHOD OF REMOVAL AND THE WEIGHT OF THE HAMMER SHALL BE APPROVED BY THE ENGINEER. PERFORM ALL WORK IN A MANNER THAT WILL NOT CUT, ELONGATE OR DAMAGE EXISTING CONCRETE REINFORCEMENT TO BE PRESERVED. CHIPPING HAMMERS SHALL NOT BE HEAVIER THAN THE NOMINAL 90-POUND CLASS. PNEUMATIC HAMMERS SHALL NOT BE PLACED IN DIRECT CONTACT WITH CONCRETE REINFORCEMENT THAT IS TO BE RETAINED IN THE REBUILT STRUCTURE. SUBMIT CONSTRUCTION PLANS ACCORDING TO C&MS 501.05.

**UNDERGROUND UTILITIES**

SEE ROADWAY PLANS

**MAINTENANCE OF TRAFFIC**

SEE ROADWAY PLANS

**ITEM 201 - CLEARING AND GRUBBING**

ALTHOUGH THERE ARE NO TREES OR STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE LIMITS OF THE PROPOSED WORK, A LUMP SUM QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR ITEM 201, CLEARING AND GRUBBING. ALL PROVISIONS AS SET FORTH IN THE SPECIFICATION UNDER THIS ITEM ARE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 201, CLEARING AND GRUBBING. NO TREE REMOVAL SHALL OCCUR BETWEEN OCTOBER 1ST AND MARCH 31ST.

**ITEM 202 - FENCE REMOVED, AS PER PLAN**

THIS ITEM INCLUDES REMOVAL OF BOTH WALL MOUNTED AND NON-WALL MOUNTED FENCE INDICATED FOR REMOVAL IN THE PLANS.

**ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN**

THE PROVISIONS OF C&MS 503 APPLY, IN ADDITION TO THOSE LISTED HEREIN. THE ITEM SHALL INCLUDE EXCAVATION NECESSARY TO CONSTRUCT THE PROPOSED WORK (E.G. REMOVE POTIONS OF EXISTING WALL, ERECT FORMWORK AND POUR NEW CAST-IN-PLACE REINFORCED CONCRETE WALL). ALL EXCAVATION MUST REMAIN WITHIN THE LIMITS OF EXISTING RIGHT-OF-WAY.

TO MITIGATE THE RETAINED/BENCHED EXCAVATION HEIGHT DURING REMOVAL AND CONSTRUCTION OF THE RETAINING WALL, THE CONTRACTOR MAY CUT-BACK THE RETAINED SOIL, BUT SHALL ENSURE THE SLOPE IS STABLE AND STAYS WITHIN EXISTING RIGHT-OF-WAY DURING PROPOSED WORK.

ALL ITEMS REMOVED THAT ARE NOT TO BE REBUILT AND INCORPORATED INTO THE FINAL PERMANENT CONDITION SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFFSITE.

ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE BID FOR ITEM 503, UNCLASSIFIED EXCAVATION, AS PER PLAN.

**ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN**

THE PROVISIONS OF C&MS 503 APPLY, IN ADDITION TO THOSE LISTED HEREIN. THIS ITEM HAS BEEN ADDED TO THE PLANS FOR USE AS DESIRED/NECESSARY BY THE CONTRACTORS MEANS AND METHODS TO ENSURE THE EXISTING SLOPE IS STABLE AND REMAINS WITHIN EXISTING RIGHT-OF-WAY DURING PROPOSED WORK.

THE ITEM SHALL INCLUDE THE CONSTRUCTION OF TEMPORARY SHORING SYSTEM (E.G. DRIVEN STEEL PLATES, FORM WORK ANCHORED TO EXISTING PORTIONS OF STRUCTURE TO REMAIN, STAGED REMOVAL AND REPLACEMENT RELYING ON SOIL ARCHING , ETC.) TO CONSTRUCT THE PROPOSED WORK (E.G. REMOVE POTIONS OF EXISTING WALL, ERECT FORMWORK AND POUR NEW CAST-IN-PLACE REINFORCED CONCRETE WALL). THE ENTIRE SHORING SYSTEM MUST REMAIN WITHIN THE LIMITS OF EXISTING RIGHT-OF-WAY.

PORTIONS OF THE EXCAVATION TO PERFORM THE PROPOSED WORK (REMOVAL AND REPLACEMENT OF THE EXISTING CAST-IN-PLACE REINFORCED CONCRETE RETAINING WALL) ARE NOT ANTICIPATED TO EXCEED 7-FT.

THE CONTRACTOR SHALL BE AWARE THAT LIMITED RIGHT-OF-WAY EXISTS BEHIND THE RETAINING WALL. ADDITIONALLY, THE PRESENCE OF AN EXISTING SHALLOW FOUNDATION (THE HEEL OF THE EXISTING CAST-IN-PLACE REINFORCED CONCRETE RETAINING WALL FOOTING) AND UTILITIES WILL FURTHER RESTRICT THE ABILITY TO ERECT/EMBED A ''CONVENTIONAL DRIVEN' SHORING SYSTEM.

ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE BID FOR ITEM 503, COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN.

**BACKFILL**

FILL THE VOID CREATED BY EXCAVATING FOR THE RETAINING WITH C LOW STRENGTH MORTAR (LSM) BACKFILL, TYPE 1 PER C&MS 613.

**ITEM 510 - DOWEL HOLES, WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN**


PRIOR TO DRILLING DOWEL HOLES, LOCATE ALL EXISTING REINFORCING STEEL IN THE AREA OF THE HOLE WITH THE AID OF A REINFORCING STEEL BAR LOCATOR (PACHOMETER). IF AN EXISTING BAR IS ENCOUNTERED AT THE SAME LOCATION AS THE PROPOSED DOWEL HOLE, THEN MOVE THE DOWEL HOLE TO EITHER SIDE OF THE EXISTING BAR. DRILL DOWEL HOLES WHERE SHOWN IN THE PLANS EXCEPT AS NOTED HEREIN. INSTALL REINFORCING STEEL ACCORDING TO C&MS 510 USING NONSHRINK, NONMETALLIC GROUT CONFORMING TO C&MS 705.20.

CONTRACTOR SHALL FIELD ADJUST LOCATIONS OF DOWEL BARS AS NECESSARY TO AVOID CONFLICT. DRILL DOWEL HOLES WHERE SHOWN IN THE PLANS AND 3" CLEAR FROM EDGE OF EXISTING CONCRETE SURFACES.

ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE BID FOR ITEM 510, DOWEL HOLES, WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN.

**CONTRACTION/EXPANSION JOINTS**

CONTRACTOR SHALL PLACE CONTRACTION/EXPANSION JOINTS NOT TO EXCEED A 30-FOOT SPACING AS MEASURED ALONG THE FRONT FACE OF WALL. LOCATION OF CONTRACTION JOINTS MAY BE CHOSEN BY THE CONTRACTOR TO FACILITATE FORMING AND REINFORCING STEEL PLACEMENT.




**CONTRACTION JOINT DETAIL**

**ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN**

THIS ITEM CONSISTS OF PATCHING THE EXISTING CAST-IN-PLACE REINFORCED CONCRETE RETAINING WALL IN ACCORDANCE WITH C&MS 519.


THE ENGINEER SHALL SOUND THE EXISTING RETAINING WALL AND IDENTIFY PATCHING LIMITS ON THE WALL BY DELINEATING THE PATCHING AREA WITH ORANGE SPRAY PAINT FOR THE CONTRACTOR TO PERFORM.

ALL LABOR, MATERIALS, TOOLS, EQUIPMENT AND INCIDENTALS FOR THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE BID FOR ITEM 519, PATCHING CONCRETE STRUCTURE, AS PER PLAN, SF.

**ITEM 606 - FENCE, TYPE CLT, AS PER PLAN**

THIS ITEM CONSISTS OF CONSTRUCTING A FENCE ATOP THE RETAINING WALL. A CHAIN LINK FENCE IN ACCORDANCE WITH ODOT C&MS 607 SHALL BE MOUNTED TO THE TOP OF THE RETAINING WALL UTILIZING A BASE PLATE AND ADHESIVE ANCHORS WITH A WASHER AND NUT.

ALL LABOR, MATERIALS, TOOLS, EQUIPMENT AND INCIDENTALS FOR THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE BID FOR ITEM 607, FENCE, AS PER PLAN, FOOT.




**ABBREVIATION LEGEND**

℄ - BASELINE
BOT. - BOTTOM
CLR. - CLEAR
CONST. - CONSTRUCTION
D.N.D. - DO NOT DISTURB
E.F. - EACH FACE
EX. - EXISTING
EL. - ELEVATION
E.O.P. - EDGE OF PAVEMENT
E.O.S. - EDGE OF SHOULDER
FTG. - FOOTING
HORIZ. - HORIZONTAL
MAX. - MAXIMUM
MIN. - MINIMUM
R/W - RIGHT OF WAY
SER. - SERIES
SPA. - SPACING
STA. - STATIONING
T.B.R. - TO BE REMOVED
T.B.R.R. - TO BE REMOVED AND REPLACED
TYP. - TYPICAL

| ITEM | EXTENSION | TOTAL 01/NHS/BR | UNIT | ESTIMATED QUANTITIES DESCRIPTION |
|---|---|---|---|---|
| | | | | |
| 202 | 11201 | | LS | PORTIONS OF STRUCTURE REMOVED, AS PER PLAN |
| 202 | 75001 | | FT | FENCE REMOVED, AS PER PLAN |
| | | | | |
| 203 | 10000 | | CY | EXCAVATION |
| 203 | 20000 | | CY | EMBANKMENT |
| | | | | |
| 503 | 11101 | | LS | COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN |
| 503 | 21101 | | LS | UNCLASSIFIED EXCAVATION, AS PER PLAN |
| | | | | |
| 509 | 10000 | | LB | EPOXY COATED STEEL REINFORCEMENT |
| | | | | |
| 510 | 10001 | | EA | DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT, AS PER PLAN |
| | | | | |
| 511 | 46010 | | CY | CLASS QC1 CONCRETE, RETAINING/WINGWALL NOT INCLUDING FOOTING |
| | | | | |
| 512 | 10100 | | SY | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) |
| 512 | 33000 | | SY | TYPE 2 WATERPROOFING |
| | | | | |
| 519 | 11101 | | SF | PATCHING CONCRETE STRUCTURE, AS PER PLAN |
| | | | | |
| 607 | 23001 | | FT | FENCE, TYPE CLT, AS PER PLAN |
| | | | | |
| 613 | 41250 | | CY | LOW STRENGTH MORTAR BACKFILL (TYPE 1) |
| | | | | |


# WALL 1 GENERAL NOTES AND ESTIMATED QUANTITIES
## 11TH AVE. EXIT RAMP

DESIGN AGENCY
Jacobs


DESIGNER KPL
REVIEWER MJR 01/25/25
PROJECT ID 109164
SHEET P.311 TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 8:47:35 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\Wall_001\Sheets\109164_001_WG001.dgn




**PLAN**





**WALL ELEVATION**
*(REMOVAL & REPAIR LIMITS)*
*(FENCING NOT SHOWN FOR CLARITY)*

**NOTES:**


1. THE CONTRACTOR SHALL SEAL ALL EXPOSED CONCRETE FACES UNDER THE FINAL PERMANENT CONDITION. THIS INCLUDES SEALING EXISTING WALL FACES NOT BEING PATCHED OR REPLACED.
2. THE CONTRACTOR SHALL ENSURE EXCAVATION AND/OR TEMPORARY SHORING STAYS WITHIN EXISTING R/W. SEE SHEET 2 FOR ADDITIONAL NOTES.
3. CUT EXISTING REINFORCING STEEL FLUSH AT CUT LINE.
4. MINIMUM LAP LENGTHS:
   #5 BAR (HORIZ.): 2'-5"
5. FOR NOTES AND ABBREVIATION LEGEND, SEE SHEET 2.

**LEGEND:**


- ITEM 202 - PORTIONS OF STRUCTURE REMOVED, AS PER PLAN
- ■ - MEASURED ALONG FRONT FACE OF WALL (±)
- ◔ - DENOTES DOWEL BAR





**PARTIAL WALL ELEVATION**
*(STEM WALL REPLACEMENT)*
*(FENCING NOT SHOWN FOR CLARITY)*




**WALL SECTION A-A**




**WALL SECTION B-B**




**WALL SECTION C-C**

HORIZONTAL SCALE IN FEET
0 5 10 20

# WALL 1 PLAN AND ELEVATION
# 11TH AVE. EXIT RAMP

DESIGN AGENCY
Jacobs

DESIGNER KPL
REVIEWER MJR 01/25/25
PROJECT ID 109164
SHEET P.312 TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 8:47:54 AM PLTDRV: OHDOT_PDF_Ex.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\Wall_001\Sheets\109164_001_WP001.dgn

MODEL: General Notes - GN005 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:13:54 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR30 WIP\109164\00-Engineering\Roadway\Sheets\109164_GN001.dgn

***WATERWORK NOTES***

*THE CITY OF COLUMBUS, CONSTRUCTION AND MATERIAL SPECIFICATIONS, 2026 EDITION AND ALL REVISIONS, INCLUDING ALL SUPPLEMENTS THERETO, SHALL GOVERN ALL CONSTRUCTION ITEMS THAT ARE A PART OF THIS PLAN, UNLESS OTHERWISE NOTED.*

*ALL WATER MAIN MATERIALS AND INSTALLATIONS SHALL BE IN ACCORDANCE WITH THE CURRENT RULES AND REGULATIONS OF THE CITY OF COLUMBUS, DIVISION OF WATER. ALL CITY OF COLUMBUS, DIVISION OF WATER STANDARD DRAWINGS SHALL APPLY TO THE PROJECT, UNLESS OTHERWISE NOTED.*

*FOR ANY EMERGENCIES INVOLVING THE WATER DISTRIBUTION SYSTEM, PLEASE CONTACT THE DIVISION OF WATER DISTRIBUTION MAINTENANCE OFFICE AT 614-645-7788.*

*ALL BRASS FITTINGS ASSOCIATED WITH WATER WORK, INCLUDING REPAIRS TO THE EXISTING SYSTEM, SHALL CONFORM TO THE REVISED ALLOWABLE LEAD EXTRACTION LIMIT PER THE UPDATED NSF/ANSI 61 STANDARD. THE DIVISION OF WATER'S APPROVED MATERIALS LIST HAS BEEN UPDATED TO REFLECT THIS REQUIREMENT.*

*IT SHALL BE UNLAWFUL FOR ANY PERSON TO PERFORM ANY WORK ON CITY OF COLUMBUS WATER MAIN SYSTEMS WITHOUT FIRST SECURING LICENSE TO ENGAGE IN SUCH WORK, AS INDICATED IN COLUMBUS CITY CODE SECTION 1103.02 AND 1103.06. THIS WORK INCLUDES ANY ATTACHMENTS, ADDITIONS TO OR ALTERATIONS IN ANY CITY SERVICE PIPE OR APPURTENANCES (INCLUDING WATER SERVICE LINES AND TAPS). THIS REQUIREMENT MAY BE MET BY UTILIZATION OF A SUBCONTRACTOR WHO HOLDS A CITY OF COLUMBUS WATER CONTRACTOR LICENSE OR A COMBINED WATER/SEWER CONTRACTOR LICENSE TO PERFORM THIS WORK. UTILIZATION OF A SUBCONTRACTOR MUST MEET THE LICENSING REQUIREMENTS OF CITY OF COLUMBUS BUILDING CODE, IN PARTICULAR SECTION 4114.119 AND 4114.529.*

*NO PERSON SHALL BEGIN CONSTRUCTION OR INSTALLATION OF A PUBLIC WATER MAIN UNTIL PLANS HAVE BEEN APPROVED BY THE STATE OF OHIO ENVIRONMENTAL PROTECTION AGENCY (OEPA).*

*THE INSTALLATION OF PVC PIPING IS NOT PERMITTED IN THE "DOWNTOWN"DISTRICT COMMUNITY, AS DEFINED BY THE CITY OF COLUMBUS CODE OF ORDINANCES, CODE 3359.03. IT IS ALSO NOT PERMITTED FOR INSTALLATION ON ANY "PRIORITY 1"(HIGH TRAFFIC VOLUME) ARTERIAL STREETS, AS DEFINED BY THE COLUMBUS DEPARTMENT OF PUBLIC SERVICE PER THE FOLLOWING LINK: HTTPS://WWW.COLUMBUS.GOV/PUBLICSERVICE/SNOW-AND-ICE-CONTROL/. PVC PIPE MAY ONLY BE USED AS AN ALTERNATE FOR 6 AND 8-INCH DUCTILE IRON WATER MAINS, AND SHALL NOT BE USED FOR HYDRANT LEADS OR WATER TAPS.*

*THESE DESIGN PLANS HAVE ASSUMED DUCTILE IRON AS THE BASELINE PIPE MATERIAL FOR DESIGN. ALL FITTINGS, DEFLECTIONS, AND OTHER DESIGN ELEMENTS ARE BASED OFF OF THE DUCTILE IRON STANDARDS. IF PVC PIPING IS TO BE UTILIZED IN THE PERMITTED LOCATIONS FOR CONSTRUCTION, A FORMAL PLAN REVISION SHALL BE SUBMITTED FOR REVIEW AND APPROVAL REGARDING ANY CHANGES TO THE DESIGN PLANS.*

*ALL WATER MAINS SHALL BE CLEANED AND FLUSHED, AND ANY WATER MAIN 12-INCH AND LARGER MUST BE PROPERLY PIGGED, IN ACCORDANCE WITH SECTION 801.15 OF THE CITY OF COLUMBUS, CONSTRUCTION AND MATERIAL SPECIFICATIONS.*

*ALL WATER MAINS SHALL BE PRESSURE TESTED IN ACCORDANCE WITH SECTION 801.16 OF THE CITY OF COLUMBUS, CONSTRUCTION AND MATERIAL SPECIFICATIONS. THE CITY MAY NOT APPROVE ANY TEST LASTING LESS THAN TWO HOURS, REGARDLESS OF THE AMOUNT OF LEAKAGE.*

*ALL WATER MAINS SHALL BE DISINFECTED IN ACCORDANCE WITH SECTION 801.17 OF THE CITY OF COLUMBUS, CONSTRUCTION AND MATERIAL SPECIFICATIONS. SPECIAL ATTENTION IS DIRECTED TO APPLICABLE SECTIONS OF A.W.W.A. C-651. WHEN THE WATER MAINS ARE READY FOR DISINFECTION, THE INSPECTOR SHALL SUBMIT A WRITTEN REQUEST FOR CHLORINATION OF THE MAINS THAT NEED DISINFECTED, THREE (3) SETS OF "AS-BUILT"PLANS (FULL SIZE SHEETS ONLY), THE AS-BUILT SURVEY COORDINATES, WATER SERVICE REPORTS AND A PRESSURE TEST TO THE CITY OF COLUMBUS, DIVISION OF WATER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COSTS ASSOCIATED WITH THE DISINFECTION OF ALL WATER MAINS CONSTRUCTED UNDER THIS PLAN.*

*THE CONTRACTOR SHALL PROVIDE CHLORINATION TAPS AND BLOWOFFS AS PER THE REQUIREMENTS OF SECTION 801.17 OF THE CITY OF COLUMBUS, CONSTRUCTION AND MATERIAL SPECIFICATIONS. IN ADDITION TO THE BLOWOFF LOCATIONS NOTED IN 801.17, THE CONTRACTOR SHALL ALSO INSTALL BLOWOFFS AT EVERY 1,100 LINEAR FEET OF THE WATER MAIN INSTALLED FOR SAMPLING.*

*ANY SECTION OF WATER MAIN THAT IS LONGER THAN 20 FEET IN LENGTH SHALL BE CHLORINATED. HAND SWABBING METHODS WILL ONLY BE PERMITTED FOR SECTIONS LESS THAN OR EQUAL TO 20 FEET IN LENGTH. USE UNSCENTED HOUSEHOLD BLEACH FOR HAND SWABBING OF PIPE AND FITTINGS. PLEASE NOTE THAT CUT-IN-TEES, SLEEVES, AND ANY OTHER REQUIRED FITTINGS OR PIPING SHALL BE TAKEN INTO ACCOUNT AND ARE INCLUDED IN THE TOTAL LENGTH OF THE SECTION (CUT TO CUT).*

*ONLY ONE CONNECTION TO AN EXISTING WATER MAIN IS PERMITTED BEFORE DISINFECTION OF A NEW WATER MAIN HAS BEEN COMPLETED. ALL OTHER CONNECTIONS MUST BE MADE AFTER THE MAIN HAS BEEN DISINFECTED.*

*MAINTAIN EIGHTEEN (18) INCHES VERTICAL AND TEN (10) FEET HORIZONTAL SEPARATION BETWEEN ANY SANITARY OR STORM SEWER PIPING AND ALL PROPOSED WATER MAINS.*

*WHEN CROSSING THE EXISTING WATER MAIN, AND LOW STRENGTH MORTAR (ITEM 613) IS TO BE USED AS BACKFILL, THE CONTRACTOR SHALL PROVIDE SIZE NO. 57 CRUSHED CARBONATE STONE (CCS) 1 FOOT BELOW TO 1 FOOT ABOVE THE EXISTING WATER MAIN.*

*IF DURING EXCAVATION, THE POLYETHYLENE ENCASEMENT ON THE EXISTING WATER MAIN BECOMES DAMAGED, THE CONTRACTOR SHALL REPAIR THE POLYETHYLENE ENCASEMENT PER MANUFACTURER'S SPECIFICATIONS AND DOW STANDARD DRAWINGS L-1003 AND L-1004, AT THEIR OWN EXPENSE. ENSURE THAT THE ENTIRE EXPOSED AREA IS COVERED WITH NEW POLYETHYLENE ENCASEMENT AND SECURELY TAPED, PRIOR TO BACKFILLING.*

*CONTRACTOR SHALL ADHERE TO THE REQUIREMENTS OF THE OHIO ADMINISTRATIVE CODE CHAPTER 3745-83-02 WATER DISRUPTION OF SERVICE RULE. EXCAVATE PITS SUFFICIENTLY BELOW THE AREA TO BE CONNECTED TO IN ORDER TO MAINTAIN WATER LEVELS BELOW THE WATER MAIN. IF WATER FROM THE PIT ENTERS THE EXISTING MAIN, CONTACT DIVISION OF WATER IMMEDIATELY. ENSURE THAT SUFFICIENTLY SIZED PUMPS ARE UTILIZED TO REMOVE WATER FROM THE TRENCH AND BACKUP PUMPS ARE KEPT ON SITE FOR REDUNDANCY.*

*"ITEM SPECIAL SURVEY COORDINATES"SHALL INCLUDE ALL MATERIAL, EQUIPMENT, AND LABOR NECESSARY TO OBTAIN HORIZONTAL AND VERTICAL (NORTHING, EASTING, AND CENTERLINE OF PIPE ELEVATION) SURVEY COORDINATES FOR THE WATER MAIN IMPROVEMENTS. THE SURVEY COORDINATES SHALL BE OBTAINED FOR THE COMPLETED WATER MAIN CONSTRUCTION AND SHALL INCLUDE ALL VALVES, TEES, CROSSES, BENDS, HORIZONTAL DEFLECTIONS, PLUGS, REDUCERS, TAPPING SLEEVES, FIRE HYDRANTS, AIR RELEASES, CURB STOPS, TRACER WIRE BOXES, AND CASING PIPE TERMINI. ADDITIONAL SURVEY COORDINATES ARE REQUIRED ON THE WATER MAIN EVERY 200 FEET WHERE NO FITTING OR OTHER WATER MAIN STRUCTURE IS BEING INSTALLED WITHIN THAT LENGTH OF THE IMPROVEMENT.*

*ALL SURVEY COORDINATES SHALL BE REFERENCED TO THE APPLICABLE COUNTY ENGINEER'S MONUMENTS, AND SHALL BE BASED ON THE NORTH AMERICAN DATUM OF 1983 (NAD 83) WITH THE (NSRS2011) ADJUSTMENT, WITH FURTHER REFERENCE MADE TO THE OHIO STATE PLANE SOUTH COORDINATE SYSTEM (GRID), SOUTH ZONE, WITH ELEVATIONS BASED ON NAVD 88 DATUM. ALL COORDINATES (NORTHING, EASTING, AND CENTERLINE OF PIPE ELEVATION) SHALL BE REFERENCED TO THE NEAREST HUNDREDTH (N XXXXXX.XX, E XXXXXX.XX, C/L ELEV. XXX.XX). ALL SURVEY COORDINATES SHALL BE ACCURATE TO WITHIN 1.0 FOOT HORIZONTAL AND A TENTH OF A FOOT (0.10) OR LESS VERTICAL.*

*THE COORDINATES SHALL BE DOCUMENTED TO THE ENGINEER IN DIGITAL SPREADSHEET FORM AND SHALL INCLUDE THE APPLICABLE ITEM, STATION, NORTHING, EASTING, AND CENTERLINE OF PIPE ELEVATION. COORDINATES SHALL BE SUBMITTED TO THE ENGINEER ON A BI-WEEKLY BASIS. COORDINATES SHALL ALSO BE REQUIRED TO BE SUBMITTED TO THE DIVISION OF WATER AS PART OF THE REQUEST FOR CHLORINATION.*

*LUMP SUM PAYMENT IS FULL COMPENSATION FOR ALL WORK INVOLVED IN OBTAINING AND DOCUMENTING THE SURVEY COORDINATES AS DESCRIBED IN THIS SPECIFICATION.*

*ALL WATER MAIN VALVE BOXES, WATER TAP BOXES, TEST STATIONS, PITOMETER TAP STRUCTURES, METER PIT COVERS, AND OTHER SURFACE UTILITY STRUCTURES WITHIN THE DISTURBED AREA SHALL BE ADJUSTED TO GRADE. ANY OF THESE STRUCTURES LOCATED WITHIN PAVEMENT, DRIVEWAYS, OR OTHER TRAVELED AREAS, WHETHER EXISTING OR PROPOSED, SHALL BE EQUIPPED WITH A TRAFFIC RATED, HEAVY DUTY VALVE BOX AND/OR COVER IN ACCORDANCE WITH THE STANDARD DRAWINGS. EXISTING WATER TAP BOXES TO REMAIN THAT ARE ENCOUNTERED WITHIN THE PROJECT LIMITS SHALL BE CLEANED OUT, CENTERED OVER THE CURB STOP, AND ADJUSTED TO THE PROPOSED GRADE.*

*RISER RINGS WILL NOT BE PERMITTED ON ANY NEWLY INSTALLED VALVE BOXES TO BRING VALVES TO FINAL GRADE. THE CONTRACTOR SHALL ENSURE THAT THE BOXES ARE INSTALLED AT THE CORRECT GRADE FOR FINAL PAVING OPERATIONS AND THAT THEIR PAVING CONTRACTOR INSTALLS PAVEMENT CORRECTLY AT LIDS DURING PAVING OPERATIONS. VALVE LIDS ARE NOT PERMITTED TO SET ABOVE FINAL GRADE AND SHALL BE A MAXIMUM OF ¼"BELOW FINAL GRADE*

*WHERE NEW CONDUIT IS PROPOSED TO CROSS AN EXISTING OR PROPOSED WATER MAIN OR WATER TAP/SERVICE LINE, A MINIMUM OF 12-INCHES OF VERTICAL CLEARANCE SHALL BE MAINTAINED BETWEEN THE CONDUIT AND THE WATER MAIN OR TAP/SERVICE LINE. A MINIMUM OF 3-FEET OF HORIZONTAL CLEARANCE (OUT TO OUT) IS REQUIRED AT LOCATIONS WHERE THE CONDUIT IS PARALLEL TO THE WATER MAIN AND AT LOCATIONS OF WATER MAIN THRUST BLOCKS.*

*A MINIMUM OF 3 FEET OF HORIZONTAL CLEARANCE (OUT TO OUT) SHALL BE MAINTAINED BETWEEN ALL EXISTING WATER MAINS AND FOUNDATIONS FOR POLES, PULL BOXES, PUSH BUTTON PEDESTALS, AND ANY OTHER MISCELLANEOUS ELECTRICAL STRUCTURE*

*A MINIMUM OF 4 FEET OF COVER IS REQUIRED PRIOR TO PRESSURE TESTING ANY WATER MAIN. A SUFFICIENT AMOUNT OF BACKFILL SHALL BE INSTALLED TO PROVIDE THE ADEQUATE RESTRAINT IN AREAS WHERE REQUIRED.*

*THE PROPOSED WATER MAIN SHALL BE LOCATED A MINIMUM DISTANCE OF TWENTY (20) FEET AWAY FROM ANY EXISTING OR PROPOSED STRUCTURE, OVERHANG OR FOOTER.*

*ALL VALVE BOXES AND WATER TAP BOXES SHALL BE LOCATED WITHIN THE EASEMENT AREA.*

*DURING CONSTRUCTION, THE CONTRACTOR SHALL USE EXTREME CAUTION NOT TO DAMAGE THE EXISTING 24 INCH WATER MAIN DUE TO MINIMAL COVER.*

*WHERE INDICATED ON THE PLANS, THE EXISTING WATER MAIN SHALL BE ABANDONED; AND ANY EXISTING WATER SERVICE LINES OFF THIS MAIN SHALL BE TRANSFERRED TO THE NEW WATER MAIN. PRIOR TO ABANDONMENT OF THE EXISTING WATER MAIN, THE PROPOSED WATER MAIN SHALL BE PIGGED (IF REQUIRED), TESTED, CHLORINATED AND PUT IN SERVICE AND THEN THE EXISTING WATER SERVICE LINES SHALL BE TRANSFERRED. THE CONTRACTOR SHALL MAINTAIN WATER SERVICE TO ALL PROPERTIES DURING CONSTRUCTION OF THE NEW WATER MAIN AND SHALL NOTIFY ALL CUSTOMERS AFFECTED BY THE TRANSFER OF WATER SERVICE LINES. TO ENSURE THAT ALL EXISTING WATER SERVICE LINES ARE TRANSFERRED TO THE NEW MAIN, NO WATER MAIN SHALL BE ABANDONED UNTIL THE NEW WATER MAIN HAS BEEN PUT IN SERVICE; ALL AFFECTED WATER SERVICE LINES HAVE BEEN TRANSFERRED; AND THE EXISTING WATER MAIN TO BE ABANDONED HAS BEEN SHUT DOWN FOR 24 HOURS. ALL VISIBLE VALVE BOXES, FIRE HYDRANTS, AND WATER TAP BOXES ON THE WATER MAIN TO BE ABANDONED, WHICH WILL NO LONGER BE IN SERVICE, SHALL BE REMOVED. ALL WATER MAINS TO BE ABANDONED SHALL BE MADE WATER TIGHT. THE REQUIRED SURFACE RESTORATION SHALL BE PAID FOR UNDER THE APPROPRIATE BID ITEM(S).*

*THE CONTRACTOR SHALL COORDINATE HIS WORK SUCH THAT NO WATER CUSTOMER WILL HAVE THEIR SERVICE DISRUPTED MORE THAN TWO (2) TIMES THROUGHOUT THE DURATION OF THIS PROJECT.*

*THE CONTRACTOR IS REQUIRED TO SUBMIT A SEQUENCE OF CONSTRUCTION TO THE CITY AT THE PRECONSTRUCTION CONFERENCE. THIS SEQUENCE OF CONSTRUCTION SHOULD ALSO DETAIL THE CONTRACTOR'S PLANS FOR TESTING AND CHLORINATION OF THE NEW MAINS, INCLUDING THE SOURCE OF THE WATER AND LOCATION OF TEMPORARY CHLORINATION AND BLOW-OFF TAPS. THE CITY SHALL HAVE THE RIGHT TO APPROVE, REJECT OR MODIFY THE CONSTRUCTION SEQUENCE TO ENSURE THAT THE INTERRUPTIONS ARE HELD TO A MINIMUM. NOTE: THE CITY MAY TAKE UP TO 10 WORKING DAYS TO RESPOND TO THIS SUBMITTAL.*

WATER WORK NOTES

DESIGN AGENCY
Jacobs


DESIGNER
SRH

REVIEWER
MCK 03/23/26


PROJECT ID
109164

SHEET P.313 | TOTAL 618

FRA-71-19.10




| WATERLINE SURVEY COORDINATE DATA | | | | | | | |
|---|---|---|---|---|---|---|---|
| S.R. 161 | | | | | | | |
| PROPOSED | | | AS-BUILT | | | | |
| REF # | ITEM | STATION | AS-BUILT STATION | OFFSET | NORTHING | EASTING | ℄ ELEV. |
| 1 | CUT & CONNECT TO EX. 24" WL W/ INSERTING VALVE | 48+66.52 | | | | | |
| 2 | 45° HORIZONTAL BEND | 48+76.52 | | | | | |
| 3 | 45° HORIZONTAL BEND | 49+00.00 | | | | | |
| 4 | 45° HORIZONTAL BEND | 51+00.00 | | | | | |
| 5 | 45° HORIZONTAL BEND | 51+23.42 | | | | | |
| 6 | CUT & CONNECT TO EX. 24" WL W/ INSERTING VALVE | 51+33.42 | | | | | |




| STATION | 9+00 | 10+00 | 11+00 | 12+00 | 13+00 |
|---|---|---|---|---|---|
| EX GROUND | 914.72 | 914.76 | 915.49 | 915.84 | 915.61 |
| ℄ OF PIPE | 904.46± | 907.54 | 907.62 | 907.71 | 906.69± |
| CUT | 9.26± | 6.22 | 6.87 | 7.13 | 7.92± |

*NOTES:*

*1. CONNECTIONS TO EXISTING WATER LINE ARE SHOWN FOR BIDDING PURPOSES ONLY AND ARE BASED ON AVAILABLE RECORD DOCUMENTATION. CONTRACTOR SHALL FIELD LOCATE EXISTING WATER LINE AND SHALL SUBMIT, FOR REVIEW AND APPROVAL, A REVISED RELOCATION PLAN BASED ON EXISTING CONDITIONS, INCLUDING EXISTING JOINTS LOCATIONS. SUBMITTAL SHALL ALSO INCLUDE ALL SUPPORTING CALCULATIONS FOR RESTRAINED JOINT LOCATIONS AND LENGTHS.*

HORIZONTAL SCALE IN FEET
0 10 20 40

# WATERLINE RELOCATION PLAN
# SR 161

DESIGN AGENCY
Jacobs

DESIGNER MCK
REVIEWER BAP 03/05/26
PROJECT ID 109164
SHEET P.314 TOTAL 618

FRA-71-19.10

MODEL: CLP_WL161 - Plan 1 [Sheet] PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:14:20 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCtv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Utilities\Sheets\109164_UP001.dgn

| ITEM | ITEM EXT | GRAND TOTAL | UNIT | DESCRIPTION |
|---|---|---|---|---|
| | | | | **NOISE BARRIERS** |
| SPECIAL | 60610900 | LS | | SPECIAL - NOISE BARRIER (REFLECTIVE TYPE BARRIER PANELS WITH STRUCTURAL THICKNESS = 4½") |
| | | | | |

**NOISE BARRIER WALL DATA**

| SHAFT NO. | NOISE BARRIER STATION | POST TYPE | TOP OF BARRIER ELEVATION | BOTTOM OF BARRIER ELEVATION | BARRIER HEIGHT (FT.) | POST SPACING (FT.) | GAP (IN.) | PLATE THICKNESS (IN.) | SHAFT LENGTH (FT.) | TOP OF SHAFT ELEVATION | TIP OF SHAFT ELEVATION |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 142 | 10+12.00 | A | 884.00 | 872.00 | 12.00 | 8 | 2.1875 | 1.125 | 8 | 871.72 | 863.72 |
| 143 | 10+20.00 | A | 884.00 | 872.00 | 12.00 | 8 | 2.1875 | 1.125 | 8 | 871.72 | 863.72 |
| 144 | 10+28.00 | A | 884.00 | 871.50 | 12.50 | 8 | 2.1875 | 1.125 | 8 | 871.22 | 863.22 |
| 145 | 10+36.00 | A | 884.00 | 871.00 | 13.00 | 8 | 2.1875 | 1.125 | 8 | 870.72 | 862.72 |
| 146 | 10+44.00 | A | 884.00 | 871.00 | 13.00 | 8 | 2.1875 | 1.125 | 8 | 870.72 | 862.72 |
| 147 | 10+52.00 | A | 884.00 | 870.50 | 13.50 | 8 | 2.1875 | 1.125 | 8 | 870.22 | 862.22 |
| 148 | 10+60.00 | A | 884.00 | 870.00 | 14.00 | 8 | 2.1875 | 1.125 | 8 | 869.72 | 861.72 |
| 149 | 10+68.00 | A | 884.00 | 869.50 | 14.50 | 8 | 2.1875 | 1.125 | 8 | 869.22 | 861.22 |
| 150 | 10+76.00 | A | 884.00 | 869.00 | 15.00 | 8 | 2.1875 | 1.125 | 8 | 868.72 | 860.72 |
| 151 | 10+84.00 | A | 884.00 | 868.50 | 15.50 | 8 | 2.1875 | 1.125 | 8 | 868.22 | 860.22 |
| 152 | 10+92.00 | A | 884.00 | 868.00 | 16.00 | 8 | 2.1875 | 1.125 | 8 | 867.72 | 859.72 |
| 153 | 11+00.00 | A | 884.00 | 867.00 | 17.00 | 8 | 2.1875 | 1.125 | 8 | 866.72 | 858.72 |
| 154 | 11+08.00 | A | 884.00 | 866.00 | 18.00 | 8 | 2.1875 | 1.125 | 8 | 865.72 | 857.72 |
| 155 | 11+16.00 | A | 884.00 | 865.00 | 19.00 | 8 | 2.1875 | 1.125 | 8 | 864.72 | 856.72 |
| 156 | 11+24.00 | A | 884.00 | 864.00 | 20.00 | 8 | 2.1875 | 1.125 | 8 | 863.72 | 855.72 |
| 157 | 11+32.00 | A | 883.00 | 863.00 | 20.00 | 8 | 2.1875 | 1.125 | 8 | 862.72 | 854.72 |
| 158 | 11+40.00 | A | 881.50 | 861.50 | 20.00 | 8 | 2.1875 | 1.125 | 8 | 861.22 | 853.22 |
| 159 | 11+48.00 | B | 880.00 | 860.00 | 20.00 | 8 | 1.8750 | 0.875 | 8 | 859.77 | 851.77 |

***NOISE BARRIER WALL SCHEDULE***

***PROPOSED WORK:***

*THIS TASK INVOLVES EXTENSION OF EXISTING NOISE BARRIER WALL AND REPLACEMENT OF EXISTING NOISE BARRIER PANELS WITH FULL-HEIGHT NOISE BARRIER PANELS AT SOUTH OF W. COOKE ROAD IN FRANKLIN COUNTY.*

***ITEM 606 - NOISE BARRIER (REFLECTIVE TYPE BARRIER WALLS WITH STRUCTURAL THICKNESS = 4 ½")***

*THIS WORK CONSISTS OF THE FOLLOWING PROPOSED WORK:*

1) *REMOVE AND REPLACEM EXISTING NOISE BARRIER PANELS AND POSTS INCLUDING NEW FOUNDATIONS. CUT EXISTING ANCHOR BOLT FLUSH AT TOP OF SHAFT AND GRIND SMOOTH.*
2) *REMOVE EXISTING NOISE BARRIER FOUNDATIONS IF IN CONFLICT WITH PROPOSED WORK OR AS DIRECTED BY THE ENGINEER. BACKFILL VOIDS IN ACCORDANCE WITH C&MS 202.*
3) *EXTENSION/CONSTRUCTION OF NOISE BARRIER WALL NORTH OF EXISTING END OF WALL.*

*ALL LABOR, MATERIALS, EQUIPMENT, TOOLS AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK AS DETAILED IN THE PLANS AND STANDARD DRAWING NBS-1-09 SHALL BE INCLUDED IN THE CONTRACT BID PRICE FOR ITEM 606, SPECIAL - NOISE BARRIER (REFLECTIVE TYPE BARRIER PANELS WITH STRUCTURAL THICKNESS = 4 1/2").*


# NOISE BARRIER (WALL 9) GENERAL NOTES AND ESTIMATED QUANTITIES SOUTH OF W. COOKE RD.

DESIGN AGENCY
Jacobs

DESIGNER MAN
REVIEWER MJR 01/25/25
PROJECT ID 109164
SHEET P.315 TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 8:48:59 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19101-71 HSR\30 WIP\109164\400-Engineering\Structures\Wall_009\Sheets\109164_009_WQ001.dgn




***PLAN VIEW (WALL 9)***

**NOTES:**

1) REMOVE EXISTING NOISE BARRIER FOUNDATIONS IF IN CONFLICT WITH PROPOSED WORK OR AS DIRECTED BY THE ENGINEER.




***PROFILE ALONG ℄ NOISE BARRIER WALL 9***

***LEGEND:***

SHAFT XXX - *PROPOSED DRILLED SHAFT FOUNDATION*

- *REMOVE AND REPLACE EXISTING NOISE BARRIER PANELS. PAYMENT INCLUDED WITH NOISE BARRIER (REFLECTIVE TYPE BARRIER PANELS WITH STRUCTURAL THICKNESS = 4 1/2"), LUMP SUM.*

HORIZONTAL SCALE IN FEET
0 5 10 20


# NOISE BARRIER (WALL 9) PLAN AND ELEVATION SOUTH OF W. COOKE RD.

DESIGN AGENCY
Jacobs


DESIGNER MAN
REVIEWER RLC 05/10/24
PROJECT ID 109164
SHEET P.316 TOTAL 618

FRA-71-19.10


MODEL: CLP_WALL009 - Plan 1 [Sheet] PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 8:49:36 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\Wall_009\Sheets\109164_009_WP001.dgn




**TYPICAL NOISE BARRIER ELEVATION**
**(N.T.S.)**




**A** **SECTION**
**TYPICAL WALL SECTION (N.T.S.)**




**B** **SECTION**
**TYPICAL WALL SECTION (N.T.S.)**

***NOTES & LEGEND:***

1. *REFER TO NOISE BARRIER SPECIFICATIONS AND STANDARD DRAWING NBS-1-09.*
2. *DRAINAGE REQUIREMENTS SHALL CONFORM TO STD. DWG. NBS-1-09.*
3. *PANELS SHALL MATCH THE EXISTING WALL AESTHETIC TO THE SATISFACTION OF THE ENGINEER. REFER TO NBS-1-09 FOR ADDITIONAL REQUIREMENTS.*

▪ = *SEE PLAN AND PROFILE OF WALL FOR NOISE BARRIER PANELS HEIGHT AND SPACINGS.*

◔ = $3\frac{5}{16}$" *MAX. TYP. GAP (POST A) BETWEEN BOTTOM OF POST & TOP OF DRILLED SHAFT*
= $2\frac{3}{4}$" *MAX. TYP. GAP (POST B) BETWEEN BOTTOM OF POST & TOP OF DRILLED SHAFT*


# NOISE BARRIER (WALL 9) DETAILS SOUTH OF W. COOKE RD.

DESIGN AGENCY
Jacobs

| | |
|---|---|
| DESIGNER | MAN |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SHEET | P.317 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 8:49:55 AM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\Wall_009\Sheets\109164_009_WD001.dgn




| PAVEMENT MARKING LEGEND | |
|---|---|
| XX | PROPOSED PAVEMENT MARKINGS, ITEM 642 |
| XX | PROPOSED PAVEMENT MARKINGS, ITEM 646 |
| XX | EXISTING PAVEMENT MARKINGS (TO REMAIN) |
| | RAISED PAVEMENT MARKERS- INSTALL PER STD. CONST. DWGS TC-65.10 AND TC-65.11 |

| INTERSTATE LINE SPECIFICATIONS (ODOT) | | |
|---|---|---|
| ITEM 644 | ITEM 646 | |
| WE | WE | EDGE LINE, 6" WHITE |
| YE | YE | EDGE LINE, 6" YELLOW |
| LL | LL | LANE LINE, 6" WHITE |
| CH | CH | CHANNELIZING LINE, 12" WHITE |
| CM | CM | CHEVRON MARKING, 24" WHITE |
| LA | LA | LANE ARROW |
| WD | WD | WORD ON PAVEMENT |
| DL6 | DL6 | DOTTED LINE, 6" WHITE (3' LINE / 9' GAP) |

| SR 161 LINE SPECIFICATIONS (CITY OF COLUMBUS) | |
|---|---|
| ITEM 642 | |
| WE | EDGE LINE, 6" WHITE |
| YE | EDGE LINE, 4" YELLOW |
| LL | LANE LINE, 6" WHITE |
| DY | CENTER LINE, 4" SOLID DOUBLE YELLOW |
| CH | CHANNELIZING LINE, 12" WHITE |
| SL | STOP LINE, 24" WHITE |
| XW | CROSSWALK LINE, 12" WHITE |
| YT | TRANSVERSE / DIAGONAL LINE, 24" YELLOW |
| WT | TRANSVERSE / DIAGONAL LINE, 24" WHITE |
| LA | LANE ARROW |
| WD | WORD ON PAVEMENT |

| SIGN LEGEND | |
|---|---|
| | PROPOSED SIGN |
| | EXISTING SIGN TO BE REMOVED |
| | EXISTING SIGN TO REMAIN |

HORIZONTAL SCALE IN FEET: 0, 10, 20, 40


# TRAFFIC CONTROL PLAN - I-71
# BEGIN WORK TO STA. 991+00.00

DESIGN AGENCY: Jacobs

DESIGNER: CNR
REVIEWER: MCK 03/16/26
PROJECT ID: 109164
SHEET: P.318 | TOTAL: 618

FRA-71-19.10

MODEL: CLP_071 - Sheet 1 PAPERSIZE: 66x34.0in | DATE: 3/31/2026 TIME: 11:16:04 AM BY/DBY: CHADEY, PSP, JJ-cadd, PENTRL: CHADEY_PSP_JJ-cadd_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHADEY5420 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\109164\Highway\Roadway\Plans\Sheets\TCP\FRA-71-19.10_TCP_Sheet 1.dgn




HORIZONTAL SCALE IN FEET
0 10 20 40


TRAFFIC CONTROL PLAN - I-71
STA. 991+00.00 TO STA. 1002+00.00

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/16/26
PROJECT ID 109164
SHEET P.319 TOTAL 618

FRA-71-19.10

MODEL: CLP_OT1 - Sheet 2 PAPERSIZE: 66x34.0 in | DATE: 3/31/2026 TIME: 11:16:13 AM BYDIR: DWGOT_PSF_I-71HOL PENTBL: DWGOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: DWGOTS\42 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: C:\Users\chris.lawrence\Jacobs\Desktop\Projects\109164 - FRA-71-19.10 HOL\Sheets\109164_TCP_I-71_STA_991+00_TO_STA_1002+00.dgn




HORIZONTAL SCALE IN FEET
0 10 20 40


# TRAFFIC CONTROL PLAN - I-71
# STA. 1002+00.00 TO STA. 1013+00.00

DESIGN AGENCY
Jacobs

DESIGNER: CNR
REVIEWER: MCK 03/16/26
PROJECT ID: 109164
SHEET: P.320
TOTAL: 618

FRA-71-19.10

MODEL: C3F_DT1 - Sheet: 3 PAPERSIZE: 66x34.0 in SAVED: 3/17/2026 TIME: 11:16:14 AM BYDIR: ONDOT_PSF_E-I-MGB_PENTBL: ONDOT_PW.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: ONDOTDGN2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: N:\Projects\109164\Roadway\Traffic\Sheets\FRA-71-19.10_TRAFFIC CONTROL PLAN - I-71 STA. 1002+00.00 TO STA. 1013+00.00.dgn




HORIZONTAL SCALE IN FEET
0 10 20 40


TRAFFIC CONTROL PLAN - I-71
STA. 1013+00.00 TO STA. 1024+00.00

DESIGN AGENCY
Jacobs

DESIGNED CNR
REVIEWED MCK 03/16/26
PROJECT ID 109164
SHEET P.321 TOTAL 618

FRA-71-19.10

MODEL: CLP_071 - Sheet 4 PAPERSIZE: 66x34.0 in | DATE: 3/31/2026 TIME: 11:16:13 AM PLTDRV: DWG2PC_PSF_[-color]_PENTBL: DWG2PC_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: DWGTOLVZ WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: I:\Projects\Ohio\Columbus\Franklin\FRA-71-19.10\Design\Roadway\Plan\Sheets\FRA-71-19.10_TCP_004.dgn




HORIZONTAL SCALE IN FEET
0 10 20 40


# TRAFFIC CONTROL PLAN - I-71
# STA. 1059+00.00 TO STA. 1070+00.00

DESIGN AGENCY
Jacobs

DESIGNER: CNR
REVIEWER: MCK 03/16/26
PROJECT ID: 109164
SHEET: P.322
TOTAL: 618

FRA-71-19.10

MODEL: CU_071 - Sheet: 5 PAPERSIZE: 66x34.0 in | DATE: 3/31/2026 TIME: 11:16:14 AM BYDIR: DWOOT_PSF: 17-cmb_PENTBL: DWOOT_PenSet USER: Chris.Lawrence@jacobs.com WORKSPACE: DWOOT0142 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DESIGNS, DRAWINGS AND SPECIFICATIONS CONTAINED IN THIS PLAN ARE THE PROPRIETARY PROPERTY OF JACOBS AND SHALL NOT BE USED IN WHOLE OR IN PART FOR ANY PURPOSE WITHOUT THE WRITTEN PERMISSION OF JACOBS.




HORIZONTAL SCALE IN FEET
0 10 20 40

# TRAFFIC CONTROL PLAN - I-71
# STA. 1070+00.00 TO STA. 1081+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CNR

REVIEWER
MCK 03/16/26


PROJECT ID
109164

SHEET
P.323

TOTAL
618

FRA-71-19.10

MODEL: CU_071 - Sheet 6 PAPERSIZE: 66x34.0 in | DATE: 3/17/2026 TIME: 11:16:17 AM BY/DBY: DHOOT; PSF: [--Unit]; PENTBL: DHOOT_PSF; File Unit: USER: Chris.Lawmon1@jacobs.com WORKSPACE: DHOOT01423 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DRAWINGS ARE THE PROPERTY OF THE CONSULTANT AND MAY NOT BE USED WITHOUT THEIR WRITTEN CONSENT. ©2026 Jacobs




HORIZONTAL SCALE IN FEET
0 10 20 40

TRAFFIC CONTROL PLAN - I-71
STA. 1081+00.00 TO STA. 1092+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CNR

REVIEWER
MCK 03/16/26


PROJECT ID
109164

SHEET
P.324

TOTAL
618

FRA-71-19.10

MODEL: CU_071 - Sheet 7 PAPERSIZE: 66x34.0 in | DATE: 3/31/2026 TIME: 11:16:14 AM BYDIR: ONDOT_PSF_I-71HOL PENTBL: ONDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: ONDOTDIST2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE NAME: P:\109164\Highway\Roadway\Design\Traffic\Sheets\FRA-71-19.10_TCP_I-71_STA_1081+00_TO_1092+00.dgn




HORIZONTAL SCALE IN FEET
0 10 20 40

TRAFFIC CONTROL PLAN - I-71
STA. 1092+00.00 TO STA. 1103+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CNR


REVIEWER
MCK 03/16/26

PROJECT ID
109164

SHEET P.325 | TOTAL 618

FRA-71-19.10

MODEL: CU_071 - Sheet 8 PAPERSIZE: 66x34.0 in | DATE: 3/17/2026 TIME: 11:16:19 AM PLTDRV: CHDOT_PSF_11.stb| PLTBL: CHDOT_Pen.tbl USER: Chris.Lawmon@jacobs.com WORKSPACE: CHDOT042 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: I:\Projects\109164\Design\Roadway\Sheets\109164_TRAFFIC CONTROL PLAN - I-71 STA 1092+00 TO STA 1103+00.dgn




HORIZONTAL SCALE IN FEET
0 10 20 40

TRAFFIC CONTROL PLAN - I-71
STA. 1103+00.00 TO STA. 1114+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CNR


REVIEWER
MCK 03/16/26

PROJECT ID
109164

SHEET P.326 | TOTAL 618

FRA-71-19.10

MODEL: CU_071 - Sheet: 9 PAPERSIZE: 66x34.0 in | DATE: 3/17/2026 TIME: 11:16:24 AM USERPROFILE: CMOOT PSF: I-71HOL PENTBL: CMOOT_PW.tbl USER: Chris.Lawmon1@jacobs.com WORKSPACE: CMOOT0143 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\Ohio\FRA-71-19.10\Design\Roadway\Plan Sheets\Traffic Control\FRA-71-19.10_TCP_009.dgn




FRA-71-19.10

MODEL: CU_071 - Sheet: SS WARNINGS: 66x44 Dia | DATE: 2/11/2026 7:44:11 AM | PLOTTED: GROOT, JOY - J-shelf, ENTIRE CHOOT, Pen:68 USER: Chris.Lawrence@jacobs.com WORKSPACE: OHDOTCVG3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.00.25

FILE: C:\Users\chris.lawrence\Jacobs\Documents\CADD\109164 - I-71 Corridor Study\Roadway\Plan Production\109164_071_SS.dgn

HORIZONTAL SCALE IN FEET
0 10 20 40

TRAFFIC CONTROL PLAN - I-71
STA. 1114+00.00 TO STA. 1125+00.00

DESIGN AGENCY
Jacobs


DESIGNER
CNR

REVIEWER
MCK 03/16/26

PROJECT ID
109164

SHEET
P.327

TOTAL
618




HORIZONTAL SCALE IN FEET
0 10 20 40

TRAFFIC CONTROL PLAN - I-71
STA. 1125+00.00 TO STA. 1136+00.00


DESIGN AGENCY
Jacobs

DESIGNED CNR
REVIEWED MCK 03/16/26
PROJECT ID 109164
SHEET P.328 TOTAL 618

FRA-71-19.10

MODEL: CLP_OT1 - Sheet:11 WARNOCK 66x44 (Ex.) DATE: 2/11/2026 TIME: 11:16:17 AM PTDBY: GROOT, JOP, J-Lead, PENTRE, CHRISTOPHER Pen-tbl: USER: Chris.Lawrence@jacobs.com WORKSPACE: CHRISTCVG3 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: I:\Projects\Transportation\Columbus\FRA-71-19.10\Design\Roadway\Plan Production\Sheets\FRA-71-19.10_TCP_P328.dgn

MODEL: CLP_I071 - Sheet 12 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:23 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\256A20100 - FRA-071-19\10-I-71 HSR\10 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn




TRAFFIC CONTROL PLAN - I-71
STA. 1239+00.00 TO STA. 1250+00.00


HORIZONTAL SCALE IN FEET
0 20
10 40

| | | | | | |
|---|---|---|---|---|---|
| 689 | P.327 | 109164 | 03/16/26 | MCK | CMK |
| SHEET NO. | TOTAL SHEETS | PROJECT NO. | DATE | DESIGNED | DRAWN |

jacobs

CHECKED


MODEL: CLP_I071 - Sheet 13 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:25 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\25A20100 - FRA-071-19\10-I-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn




TRAFFIC CONTROL PLAN - I-71
STA. 1250+00.00 TO STA. 1261+00.00

HORIZONTAL SCALE IN FEET
0 20
10 40

| | | | | | |
|---|---|---|---|---|---|
| 688 | P.391 | 109164 | MCK 03/16/26 | CNK | jacobs |
| SHEET NO. | TOTAL SHEETS | PROJECT NO. | DESIGNED - KSH<br>DRAWN - MCK<br>CHECKED - CNK | QUALITY CHECK | DESIGN AGENCY |




HORIZONTAL SCALE IN FEET
0 10 20 40

# TRAFFIC CONTROL PLAN - I-71
# STA. 1261+00.00 TO STA. 1272+00.00


DESIGN AGENCY
Jacobs

DESIGNER: CNR
REVIEWER: MCK 03/16/26
PROJECT ID: 109164
SHEET: P.331
TOTAL: 618


FRA-71-19.10

MODEL: CLP_OT1 - Sheet 14 MARKERS: 66-44 Fri | DATE: 3/12/2026 TIME: 11:16:19 AM PLOTTED: 03/12/2026 7:29:07 PM | USER: Chris.Lizenby@jacobs.com WORKSPACE: C:\WORKSPACE\ CHOOSTCVGS WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.00.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 JACOBS SOLUTIONS INC. THIS FILE CONTAINS PROPRIETARY AND CONFIDENTIAL INFORMATION.


MODEL: CLP_I071 - Sheet 15 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:27 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCIVv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\25A20100 - FRA-071-19\10-I-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn


MATCH LINE STA. 1272+00
REMOVE & RE-ERECT
8
MILE
114
71
S
N
71
MILE
114
8
59'
50'
50'
17'
17'
48'
11.5'
11.5'
ADOPT A HIGHWAY
LITTER CONTROL
STATE AUTO
INSURANCE
SPEED
LIMIT
65
SOUTH
71
CAR POOL
INFO
875-POOL
I-71 (NORTHBOUND)
℄ CONST. I-71
I-71 (SOUTHBOUND)
90'
11'
11'
11

MODEL: CLP_I071 - Sheet 16 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:28 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCIVD2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\25A20100 - FRA-071-19\10-I-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn


MATCH LINE STA. 1283+00
MATCH LINE STA. 1294+00
Cooke Rd ¼
N Broadway 1¼
Weber Rd 1¾
Morse Rd ½ 2½ 4
MILE 114.8
MILE 114.8
71 SOUTH
71 NORTH
I-71 (NORTHBOUND)
℄ CONST. I-71
I-71 (SOUTHBOUND)
SPEED LIMIT 70
SPEED LIMIT 70
SPEED LIMIT 70

MODEL: CLP_I071 - Sheet 17 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:29 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCtv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\25A20100 - FRA-071-19\10-I-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn





TRAFFIC CONTROL PLAN - I-71
STA. 1294+00.00 TO STA. 1305+00.00


HORIZONTAL SCALE IN FEET
0 20
10 40

| | | | | | |
|---|---|---|---|---|---|
| SHEET NO. 488 | TOTAL SHEETS P-234 | PROJECT NO. 109164 | DESIGNED MCK 03/16/26 | DRAWN CNS | CHECKED |


jacobs

QUALITY ASSURANCE


HORIZONTAL SCALE IN FEET
0 10 20 40
TRAFFIC CONTROL PLAN - I-71
STA. 1305+00.00 TO STA. 1316+00.00
I-71 (SOUTHBOUND)
I-71 (NORTHBOUND)
℄ CONST. I-71
℄ CONST. RAMP D
℄ CONST. RAMP C
℄ CONST. RAMP B
℄ SINCLAIR ROAD
℄ MORSE ROAD
MATCH LINE STA. 1305+00
MATCH LINE STA. 1316+00
+72 (RAMP D) END PAV'T MARKINGS
+92 (RAMP D)
+51 (RAMP D)
+36 (RAMP D)
+30 (RAMP C)
+58 (RAMP C)
+80 (RAMP C)
+68 (RAMP C)
+97 (RAMP C)
+14 (RAMP C)
+84 (RAMP C)
+67 (RAMP C)
+46 (RAMP C)
+16 (RAMP C)
+00 (RAMP C)
+61 (RAMP C), END PAV'T MARKINGS
+00 (RAMP B)
+54 (RAMP B) BEGIN PAV'T MARKINGS
R=200'
R=120'
N07°20'32"W
S01°35'32"E
S88°55'24"E
N03°08'20"E
N20°08'00"E
N02°51'45"E
RAMP MORSE RD TO I-71
STOP ON RED
ONE VEHICLE PER GREEN
R10-6,24
SIX SIGNAL HEADS
W4-18-48 STA. 1308+79
REMOVE EX. POST MOUNTED SIGNS & CONCRETE MEDIAN BARRIER SIGN BRACKET STA. 1315+83
MILE 115 6
MILE 115 7
SPONSOR A HIGHWAY
EX. GROUND MOUNTED SIGN (REMAIN AND PROTECT) (BY OTHERS)
Morse Rd
Sinclair Rd
WRONG WAY
WRONG WAY
ONLY
GAS
Jacobs
DESIGNER CNR
REVIEWER MCK 03/16/26
PROJECT ID 109164
SHEET P.335
TOTAL 618
FRA-71-19.10
MODEL: CLP_OT1 - Sheet: 18 (MARKERS: 66x44 Dia.) DATE: 3/12/2026 TIME: 10:18:58 AM PTOBY: CROOT_PW J:\eng_PROJ\FRA\71\109164\Traffic\Sheets\FRA-71-19.10_TCP.dgn
ALL DRAWINGS ARE THE PROPERTY OF JACOBS AND CANNOT BE REPRODUCED OR USED WITHOUT THE EXPRESS WRITTEN CONSENT OF JACOBS. ©2026 Jacobs
PLOTTED BY: Chris.Lizenmire@gmail.com WORKSPACE: CROOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.00.25


MATCH LINE STA. 1316+00
MATCH LINE STA. 1327+00
MATCH LINE STA. 3316+00
MATCH LINE STA. 6322+50
MATCH LINE STA. 2323+00
℄ CONST. RAMP E
℄ CONST. I-71
℄ CONST. RAMP A
℄ CONST. RAMP B
I-71 (SOUTHBOUND)
I-71 (NORTHBOUND)
N20°37'29"E
+63
+93
+31 (RAMP E)
+98 (RAMP E)
+91 (RAMP E)
+22
+33 (RAMP B)
+10
+90 (RAMP A)
+34 (RAMP A)
+59 (RAMP A)
+90
STOP
RAMP
AHEAD
ONE
WAY
TRAFFIC
GREEN
WHITE
R10-7-24
STA. 6321+73
R10-7-24
STA. 6321+93
STOP
AHEAD
R10-6-24
STA. 6321+93
STOP
RAMP
AHEAD
R10-6-24
STA. 6321+73
STOP
RAMP
AHEAD
R10-6-24
STA. 2323+01 (LT)
STA. 2323+01 (RT)
WRONG
WAY
R5-1a-24
STA. 2323+42
WRONG
WAY
R5-1a-24
STA. 2323+40
WRONG
WAY
R5-1a-24
STA. 2324+45
WRONG
WAY
R5-1a-24
STA. 2324+72
WRONG
WAY
R5-1a-24
STA. 2324+72
DO NOT
ENTER
R5-1-24
STA. 2324+45
DO NOT
ENTER
R5-1-24
STA. 2324+72
ONE
WAY
R6-2-24
STA. 2324+72
ONE
WAY
R6-2-24
STA. 2324+72
FOOD
1K
1K
FOOD
1.0 MI
2.0 MI
3.3 MI
1.0 MI
2.0 MI
3.3 MI
EX. GROUND MOUNTED SIGN
(REMOVE AND RE-ERECT)
(BY OTHERS)
EX. GROUND MOUNTED SIGN
(REMOVE AND RE-ERECT)
(BY OTHERS)
EXIT
116
30
MPH
E5-51-24
STA. 2324+72
EXIT
116
E5-51-24
STA. 2324+72
RAMP
30
MPH
E13-3-48
STA. 2326+30
W1-16-48
STA. 1317+70
W1-6-48
STA. 1320+68
W1-6R-36
STA. 2322+50
W1-6R-36
STA. 2322+50
REMOVE EX. POLE MOUNTED SIGN & REERECT ON SINGLE POST & MEDIAN BARRIER SIGN BRACKET STA. 2324+74
8
MILE
115
71
N
S
71
MILE
115
8
WRONG WAY
TO I-71 N
R5-1a-48
STA. 3318+04
WRONG WAY
TO I-71 N
R5-1a-48
STA. 3318+04
CH–
CH–
WE–
YE–
LL–
WE–
LL–
YE–
WE–
LL–
YE–
LL–
CH–
CH–
DL6–
S–
R–
SL–
YE–
CH–
CH–
WE–
S–
S–
S

MODEL: CLP_I071 - Sheet 20 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:33 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCIVil2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\254A20100 - FRA-071-19\10-I-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn





TRAFFIC CONTROL PLAN - I-71
STA. 1327+00.00 TO STA. 1338+00.00

HORIZONTAL SCALE IN FEET
0 20
10 40

| | | | | | | |
|---|---|---|---|---|---|---|
| SHEET NO. 488 | TOTAL SHEETS P-337 | PROJECT NO. 109164 | DESIGNED MCK 03/16/26 | DRAWN CMK | CHECKED | QUALITY CHECK |

MODEL: CLP_I071 - Sheet 21 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:34 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCtv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\25A20100 - FRA-071-19\10-I-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn







TRAFFIC CONTROL PLAN - I-71
STA. 1338+00.00 TO STA. 1349+00.00

HORIZONTAL SCALE IN FEET
0 20
10 40

MODEL: CLP_I071 - Sheet 22 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:35 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCtv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\2SA20100 - FRA-071-19\10-I-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn





TRAFFIC CONTROL PLAN - I-71
STA. 1349+00.00 TO STA. 1360+00.00

HORIZONTAL
SCALE IN FEET
0 20
10 40

| | | | | | | |
|---|---|---|---|---|---|---|
| 688 | P.391 | 109164 | MCK 03/16/26 | CNK | jacobs | DESIGN AGENCY |
| SHEET No. | TOTAL SHEETS | PROJECT No. | DESIGNED | CHECKED | | |


FRA-71-19.10

MODEL: CLP_I071 - Sheet 23 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:36 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\25A20100 - FRA-071-19\10-I-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn




TRAFFIC CONTROL PLAN - I-71
STA. 1360+00.00 TO STA. 1371+00.00

HORIZONTAL
SCALE IN FEET
0 20
10 40




FRA-71-19.10

MODEL: CU_OT1 - Sheet:24 JMARKSON -66x44.0in | DATE: 3/11/2026 7AM | 3:16:17 AM | PITDEV: DROOT_PSF_I-71.ctb| PENTBL: DROOT_Pen.tbl USER: Chris.Lisenmeyer@jacobs.com WORKSPACE: DROOT\CIVD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.00.25
FILE: I:\Projects\109164\Highway\Roadway\Design\Plans\Traffic\FRA-71-19.10_TRAFFIC CONTROL PLAN - I-71 STA. 1371+00 TO STA. 1382+00.dgn

HORIZONTAL SCALE IN FEET
0 10 20 40

TRAFFIC CONTROL PLAN - I-71
STA. 1371+00.00 TO STA. 1382+00.00


DESIGN AGENCY
Jacobs

DESIGNER
CNR

REVIEWER
MCK 03/16/26

PROJECT ID
109164

SHEET P.341 | TOTAL 618




HORIZONTAL SCALE IN FEET
0 10 20 40

# TRAFFIC CONTROL PLAN - I-71
# STA. 1382+00.00 TO STA. 1393+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CNR

REVIEWER
MCK 03/16/26


PROJECT ID
109164

SHEET
P.342

TOTAL
618

FRA-71-19.10

MODEL: CLP_OT1 - Sheet:25 PAPERSIZE: 66.44 IN | DATE: 3/11/2026 7:44:11 | 3:16:18 AM | PLOTBY: GROOT, JOP, J-F | config: PENTBL: CHROOT: /PW: J-F | config: PENTBL: CHROOT: /PW: USER: Chris.Lizenmire@jacobs.com WORKSPACE: CHROOT/CIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.00.25
FILE: C:\Users\Chris.Lizenmire\Jacobs\Connected Data - Documents\109164 - FRA-71-19.10 - I-71 Widen Rehab Replacement\CIVIL\Sheets\FRA-71-19.10_TCP01.dgn




HORIZONTAL SCALE IN FEET
0 10 20 40

# TRAFFIC CONTROL PLAN - I-71
# STA. 1393+00.00 TO STA. 1404+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CNR

REVIEWER
MCK 03/16/26


PROJECT ID
109164

SHEET
P.343

TOTAL
618

FRA-71-19.10

MODEL: CU_071 - Sheet: 04 JMARKSON 66x44 ES | DATE: 3/11/2026 7:44:11 AM | STORY: GROUT / PVI / J-shelf& PENTEL CHOOT / Pen:68 USER: Chris.Lawrence@jacobs.com WORKSPACE: CHOOTCIVD1 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.00.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROTECTED BY U.S. AND INTERNATIONAL COPYRIGHT LAWS.




FRA-71-19.10

MODEL: CLV_OT1 - Sheet:27 /MARKERS: 66.64 Ea | USER: JSTILLINGS THAN | 3:18:48 AM 3/7/2026 | PLOT: 3:20:07 PM | F:\pwdg_EN\ENG_CHOOT_Proj\E USER: Chris.Lizenmier@jacobs.com WORKSPACE: CHOOTCIVIL WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.00.25


ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. THIS FILE IS PROVIDED "AS IS" WITH NO WARRANTIES WHATSOEVER, INCLUDING ANY WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE.

HORIZONTAL SCALE IN FEET
0 10 20 40

# TRAFFIC CONTROL PLAN - I-71
# STA. 1404+00.00 TO STA. 1415+00.00

DESIGN AGENCY
Jacobs

| | |
|---|---|
| DESIGNER | CNR |
| REVIEWER | MCK 03/16/26 |
| PROJECT ID | 109164 |
| SHEET | P.344 |
| TOTAL | 618 |




HORIZONTAL SCALE IN FEET
0 10 20 40


# TRAFFIC CONTROL PLAN - I-71
# STA. 1415+00.00 TO STA. 1426+00.00

DESIGN AGENCY
Jacobs

DESIGNER: CNR
REVIEWER: MCK 03/16/26
PROJECT ID: 109164
SHEET: P.345
TOTAL: 618

FRA-71-19.10

MODEL: CU_071 - Sheet 24 PAPERSIZE: 66.44 IN x 33.97 IN DATE: 3/12/2026 TIME: 11:18:41 AM USER: GROOT_PW J:\pw\fra_fra\Documents\FRA-71-19.10\Design\Roadway\Plan Sheets\FRA-71-19.10_TCP24.dgn
ALL DRAWINGS ARE THE PROPERTY OF THE OHIO DEPARTMENT OF TRANSPORTATION AND MAY NOT BE REPRODUCED OR USED WITHOUT THE PERMISSION OF ODOT. © 2026 ODOT
Bentley PowerGeotech CONNECT Edition 10.00.02.25 [Build 10.00.02.25] -




FRA-71-19.10

MODEL: CU_071 - Sheet:29 JWARNOCK 66.44 Ins | DATE: 2/12/2026 7AM | 11:14:42 AM | PTOBY: GROOT, JPG | Config: PENTRE, CHOOT | Pen-tbl: USER: Chris.Lizenner@jacobs.com WORKSPACE: CHOOTCVG5 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.00.25

ELEMENTS: Horizontal Alignment, Vertical Alignment, Profile, Superelevation, Template, Corridor, Terrain Model, Feature Definition, Civil Cell, Point Group

HORIZONTAL SCALE IN FEET
0 10 20 40


TRAFFIC CONTROL PLAN - I-71
STA. 1426+00.00 TO STA. 1437+00.00

DESIGN AGENCY
Jacobs

DESIGNER CNR
REVIEWER MCK 03/16/26
PROJECT ID 109164
SHEET P.346 TOTAL 618

FRA-71-19.10


MODEL: CLP_I071 - Sheet 30 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:43 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCtv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\DSA20100 - FRA-071-19\10-I-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn




TRAFFIC CONTROL PLAN - I-71
STA. 1437+00.00 TO STA. 1448+00.00

HORIZONTAL SCALE IN FEET
0 20
10 40

| | | | | | |
|---|---|---|---|---|---|
| SHEET NO. 30 | PROJECT NO. 109164 | DESIGNED MCK | DRAWN CMK | CHECKED | QUALITY CHECK |
| TOTAL SHEETS 48 | DATE 03/16/26 | REVISION | REVISION | REVISION | REVISION |




FRA-71-19.10

MODEL: CLP_DT1 - Sheet:31 WARNINGS: 66x44 Ents | DATE: 2/11/2026 7:44:11 | 3:18:44 AM | PITSBY GROOT / PGI J-Lahaj, KENTRL CHROOT: /Pw-tld USER: Chris.Lawrence@jacobs.com WORKSPACE: CHROOT/CIVD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.00.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL INFORMATION. UNAUTHORIZED REPRODUCTION, DISTRIBUTION OR DISCLOSURE PROHIBITED.

HORIZONTAL SCALE IN FEET
0 10 20 40

# TRAFFIC CONTROL PLAN - I-71
# STA. 1448+00.00 TO STA. 1459+00.00

DESIGN AGENCY
Jacobs

DESIGNER
CNR


REVIEWER
MCK 03/16/26

PROJECT ID
109164


SHEET
P.348

TOTAL
618

MODEL: CLP_I071 - Sheet 32 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:16:45 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCtv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\16A20100 - FRA-071-19\10-I-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP001.dgn



MODEL: Sheet PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:17:02 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCivil2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\CEA20100 - FRA-071-1910-11.HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP101.dgn







TRAFFIC CONTROL PLAN
SINCLAIR ROAD RAMPS A & E

HORIZONTAL SCALE IN FEET
0 20
10 40

FRA-71-19.10

MODEL: CLP_MORSE-1 - Sheet PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 12:17:29 AM PLTDRV: OHDOT_PDF_E+ plt.cfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\10A20100 - FRA-071-19\D1-71 HSR\30 WIP\109164\400-Engineering\Traffic\Sheets\109164_TP201.dgn





| | | | | | | |
|---|---|---|---|---|---|---|
| SHEET NO. 498 TOTAL SHEETS | SHEET NO. P-351 TOTAL SHEETS | PROJECT NO. 109164 | DESIGNED MCK 03/16/26 | DRAWN CNS | CHECKED | QUALITY CHECK |

jacobs

TRAFFIC CONTROL PLAN
MORSE ROAD

HORIZONTAL SCALE IN FEET
0 20
10 40




FRA-71-19.10

MODEL: CU7_5163-1 Sheet: PAPERSIZE: 66x44 (in) DATE: 3/11/2026 TIME: 2:22:29 PM USER: CHRISTOPHER_FLANSBURG PENTEL: CHRISTOPHER_FLANSBURG.PLT.cfg DESIGNER: CHRISTOPHER_FLANSBURG EMAIL: Chris.Lawrence1@jacobs.com WORKGROUP: CHRISTOPHER_FLANSBURG WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25

HORIZONTAL
SCALE IN FEET
0 10 20 40

TRAFFIC CONTROL PLAN
SR 161

DESIGN AGENCY
Jacobs


DESIGNER
CNR

REVIEWER
MCK 03/16/26

PROJECT ID
109164

SHEET
P 352

TOTAL
618




NOTES:
1. SEQUENCE OF ACTIVITIES:
A) INSTALL TEMPORARY 48" PULL BOX AND 4" CONDUIT WITH TEMPORARY 288 STRAND SM AND 24 STRAND SM FIBER OPTIC CABLES FROM STA. 1269+15, 9' LT. TO STA. 1276+35, 9' LT.
B) WITHIN A 48 HR PERIOD, COMPLETE THE FOLLOWING ACTIVITES:
i) DE-ENERGIZE THE EXISTING LIGHTING CIRCUIT IN THE EXISTING MEDIAN BARRIER.
ii) CUT EXISTING FIBER OPTIC CABLES AT EXISTING MEDIAN PULL BOX AT STATION 1272+85 +/- . USE EXISTING PULL BOXES AT APPROX. STATIONS 1264+91 AND 1278+11 TO PULL CABLES BACK BEYOND LIMITS OF BARRIER REMOVAL.
iii) REMOVE BARRIER AND EXISTING CONDUITS FROM STA. 1269+00 TO STA. 1269+25 AND STA. 1276+25 TO STA. 1276+50.
iv) TRANSITION BARRIER CONDUITS TO UNDERGROUND AT STA. 1269+00 AND STA. 1276+50. SEE DETAIL "A" ON MAINTENANCE OF TRAFFIC CROSSOVER LAYOUT SHEET. UTILIZE TRANSITION TO INSTALL TEMPORARY 4" RIGID CONDUITS FROM EXISTING BARRIER TO TEMPORARY 48" PULL BOXES AT 1269+15, 9' LT. AND STA. 1276+35, 9' LT. PULL EXISTING FIBER TO TEMPORARY 48" PULL BOXES.
v) WITH TEMPORARY SPLICE ENCLOSURES, SPLICE EXISTING 288 STRAND, 24 STRAND, AND 48 STRAND FIBER OPTIC CABLES TO TEMPORARY 288 STRAND, 24 STRAND, AND 48 STRAND FIBER OPTIC CABLES IN EACH TEMPORARY 48" PULL BOX.

2. SEE SHEET XXXX FOR ADDITIONAL CROSSOVER DETAILS.

FOR ITS LEGEND, SEE SHEET P.355

HORIZONTAL SCALE IN FEET
0 10 20 40


# TEMPORARY ITS PLAN
# BEGIN WORK TO STA. 1272+00

DESIGN AGENCY
Jacobs

DESIGNER: BAP
REVIEWER: RF 03/20/26
PROJECT ID: 109164
SHEET: P.353 TOTAL: 618

FRA-71-19.10

MODEL: CU - ITS - Sheet 1 PAYPRINT: 06x34 (in.) DATE: 3/31/2026 TIME: 3:47:29 PM PLTDRV: DHDOT_PRF_FLAT4b_PENTBL: DHDOT_Pen.tbl USER: ChrisLawrence1@jacobs.com WORKSPACE: C:\HDOT\CAD WORKSET: DEFAULT PRODUCT: OpenRoadsDesigner 24.00.02.25
FILENAME: P:\Projects\FRA\71\19.10\Design\Roadway\Sheets\FRA-71-19.10_ITS_Sheet 1.dgn




*NOTES:*

*1. SEQUENCE OF ACTIVITIES:*

*A) INSTALL TEMPORARY 48" PULL BOX AND 4" CONDUIT WITH TEMPORARY 288 STRAND SM AND 24 STRAND SM FIBER OPTIC CABLES FROM STA. 1269+15, 9' LT. TO STA. 1276+35, 9' LT.*

*B) WITHIN A 48 HR PERIOD, COMPLETE THE FOLLOWING ACTIVITES;*

*i) DE-ENERGIZE THE EXISTING LIGHTING CIRCUIT IN THE EXISTING MEDIAN BARRIER,*

*ii) CUT EXISTING FIBER OPTIC CABLES AT EXISTING MEDIAN PULL BOX AT STATION 1272+85 +/- . USE EXISTING PULL BOXES AT APPROX. STATIONS 1264+91 AND 1278+11 TO PULL CABLES BACK BEYOND LIMITS OF BARRIER REMOVAL.*

*iii) REMOVE BARRIER AND EXISTING CONDUITS FROM STA. 1269+00 TO STA. 1269+25 AND STA. 1276+25 TO STA. 1276+50.*

*iv) TRANSITION BARRIER CONDUITS TO UNDERGROUND AT STA. 1269+00 AND STA. 1276+50. SEE DETAIL "A" ON MAINTENANCE OF TRAFFIC CROSSOVER LAYOUT SHEET. UTILIZE TRANSITION TO INSTALL TEMPORARY 4" RIGID CONDUITS FROM EXISTING BARRIER TO TEMPORARY 48" PULL BOXES AT 1269+15, 9' LT. AND STA. 1276+35, 9' LT. PULL EXISTING FIBER TO TEMPORARY 48" PULL BOXES.*

*v). WITH TEMPORARY SPLICE ENCLOSURES, SPLICE EXISTING 288 STRAND, 24 STRAND, AND 48 STRAND FIBER OPTIC CABLES TO TEMPORARY 288 STRAND, 24 STRAND, AND 48 STRAND FIBER OPTIC CABLES IN EACH TEMPORARY 48" PULL BOX.*

*2. SEE SHEET XXXX FOR ADDITIONAL CROSSOVER DETAILS.*

*FOR ITS LEGEND, SEE SHEET P.355*

HORIZONTAL SCALE IN FEET
0 10 20 40

# TEMPORARY ITS PLAN
# STA. 1272+00.00 TO END WORK

DESIGN AGENCY
Jacobs

DESIGNER: BAP
REVIEWER: RF 03/20/26
PROJECT ID: 109164
SHEET: P.354 TOTAL: 618

FRA-71-19.10

MODEL: CU - ITS - Sheet 2 PAYRIDGE: 66x34 (in) SAVED: 3/31/2026 7:04:25 PM PLOTBY: CHHOT_PW_LA-HNL PENTBL: CHHOT_Pen.tbl USER: ChrisLuemmert@jacobs.com WORKSPACE: CHHOTSTEAD WORKSET: 109164 PRODUCT: OpenRoadDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES. THIS DRAWING IS THE PROPERTY OF JACOBS AND IS NOT TO BE USED OR REPRODUCED WITHOUT PRIOR WRITTEN PERMISSION.





HORIZONTAL SCALE IN FEET
0 10 20 40

ITS PLAN - I-71
STA. 1260+00.00 TO STA. 1271+00.00

FRA-71-19.10


MODEL: CU_071 - Plot: ? PAPERIZE: 36x24 in | DATE: 3/31/2026 TIME: 12:18:11 AM PITDRV: CMDOT_PDF_U-LARGE PRINTEL: CMDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CMDOTCIVIL02 WORKSET: DRIVE PRODUCT: OpenRoadsDesigner 24.00.02.25
DATA FILES: Plan: C:\Projects\109164\Roadway\Design\Sheets\109164_FRA071901_SHEET_ITS_PLAN_001.dgn Profile: C:\Projects\109164\Roadway\Design\Sheets\109164_FRA071901_SHEET_ITS_PLAN_001.dgn


DESIGN AGENCY
Jacobs
DESIGNER
BAP
REVIEWER
RF 03/20/26
PROJECT ID
109164
SHEET P.355 TOTAL 618




FOR ITS LEGEND, SEE SHEET P.355

HORIZONTAL SCALE IN FEET
0 10 20 40

ITS PLAN - I-71
STA. 1271+00.00 TO STA. 1282+00.00

DESIGN AGENCY
Jacobs

DESIGNER
BAP


REVIEWER
RF 03/20/26

PROJECT ID
109164

SHEET P.356 TOTAL 618

FRA-71-19.10

MODEL: CU_071 - Plan PAYPAGES: 66x34 in | DATE: 3/31/2026 TIME: 10:33:03 AM FSTORY: CMDOT_PDF_U-LARGE_FSTITEL: CMDOT_Pln.dgn USER: Chris.Lawrence@jacobs.com WORKSPACE: CMDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DRAWINGS ARE INSTRUMENTS OF SERVICE AND ARE PROPERTY OF THE CDOT. REUSE OF THESE DRAWINGS FOR ANY PURPOSE OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY WERE PREPARED IS PROHIBITED.




FOR ITS LEGEND, SEE SHEET P.355

HORIZONTAL SCALE IN FEET
0 10 20 40


ITS PLAN - I-71
STA. 1282+00.00 TO STA. 1293+00.00

DESIGN AGENCY
Jacobs

DESIGNER BAP
REVIEWER RF 03/20/26
PROJECT ID 109164
SHEET P.357 TOTAL 618

FRA-71-19.10

MODEL: CU_071 - Plan | RAYFILES: RIGHT.tif | DATE: 3/31/2026 TIME: 10:31:08 AM SYSTEM: CMDOT_PW_01 | LAYER: PENTBL, CMDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CMDOTCIVIL02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DESIGNS, DRAWINGS AND SPECIFICATIONS ARE COPYRIGHTED BY JACOBS AND SHALL NOT BE REUSED WITHOUT PRIOR WRITTEN CONSENT.




FOR ITS LEGEND, SEE SHEET P.355

HORIZONTAL SCALE IN FEET
0 10 20 40

ITS PLAN - I-71
STA. 1293+00.00 TO STA. 1304+00.00

DESIGN AGENCY
Jacobs

DESIGNER
BAP


REVIEWER
RF 03/20/26

PROJECT ID
109164

SHEET P.358 | TOTAL 618

FRA-71-19.10

MODEL: CLP_ITS - Plan 10 PAPERSIZE: 66x34.0 in | DATE: 3/31/2026 TIME: 10:19:04 AM BYDRY: DHOOT, PEM_F | HALL, PENTEL DHOOT, Plan Set USER: Chris.Lawrence@jacobs.com WORKSPACE: DHOOT0402 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. PROPRIETARY AND CONFIDENTIAL INFORMATION. PROTECTED UNDER U.S. AND INTERNATIONAL COPYRIGHT AND OTHER LAWS.




FOR ITS LEGEND, SEE SHEET P.355

HORIZONTAL SCALE IN FEET
0 10 20 40


# ITS PLAN - I-71
## STA. 1304+00.00 TO STA. 1315+00.00


FRA-71-19.10

MODEL: CLF_DT1 - Plot: 11 PAPERSIZE: 66x34.0 in | DATE: 3/31/2026 TIME: 10:11:44 AM EDITOR: DWOOT, PEF, C:\JHSB_PENTRL DWOOT_Pen.ctb USER: Chris.Lawrence@jacobs.com WORKSPACE: DWOOT0420 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.12.25
ALL RIGHTS RESERVED. COPYRIGHT © 2026 BENTLEY SYSTEMS, INCORPORATED. THIS FILE IS PROTECTED UNDER U.S. AND INTERNATIONAL COPYRIGHT LAWS.

DESIGN AGENCY
Jacobs

DESIGNER BAP
REVIEWER RF 03/20/26
PROJECT ID 109164
SHEET P.359 TOTAL 618


ITS-XX
ITS PLAN
X FT - TRENCH, AS PER PLAN
TO EX. PB AT STA. 6325+39, 7' LT (SINCLAIR RAMP E)
AND THEN TO EX. RAMP FLASHING SIGN
AT STA. 6325+27, 11' LT (SINCLAIR RAMP E)
X FT - 2" CONDUIT
X FT - SIGNAL CABLE
ITS PLAN
1 EA - RMS CONTROLLER, RELOCATED, AS PER PLAN
1 EA - CONTROLLER FOUNDATION
1 EA - WORK PAD
X FT - TRENCH, AS PER PLAN
X FT - 24 STRAND SM FIBER OPTIC CABLE
X FT - (3)-#6AWG POWER SERVICE CABLES
X FT - 2" CONDUIT
X FT - ETHERNET CABLE
X FT - SIGNAL CABLE
IC-XX
INTERCONNECT
X FT - TRENCH, AS PER PLAN
X FT - 4" MULTI-CELL CONDUIT
X FT - (2) 24 STRAND SM FIBER OPTIC CABLE
X FT - ETHERNET CABLE
X FT - SIGNAL CABLE
ITS PLAN
X FT - (3) - NO. 6 AWG 600 VOLT
X FT - 2" CONDUIT
ITS PLAN
X FT - TRENCH, AS PER PLAN
X FT - 2" CONDUIT
X FT - SIGNAL CABLE
ITS PLAN
1 EA - RAMP SIGNAL WITH TRANSFORMER BASE, RELOCATED
1 EA - PEDESTAL FOUNDATION
INTERCONNECT
X FT - TRENCH, AS PER PLAN
X FT - 4" MULTI-CELL CONDUIT
X FT - 4" CONDUIT
X FT - 24 STRAND SM FIBER OPTIC CABLE
X FT - 288 STRAND SM FIBER OPTIC CABLE
PB-XX
EX. ODOT FIBER (ABANDON)
EX. PB (TBR)
EX. RAMP SIGNAL (TBRL)
EX. RMS CABINET (TBRL)
EX. SFVD POLE (RELOCATED)
EX. SFVD POLE (TBRL)
ITS PLAN
LOCATE PULL BOX, 18", ON EXISTING
CONTROLLER POWER SERVICE CONDUIT
AND INTERCEPT POWER FOR RELOCATED
CONTROLLER
ITS PLAN
1 EA - RAMP SIGNAL WITH TRANSFORMER BASE, RELOCATED
1 EA - PEDESTAL FOUNDATION
ITS PLAN
1 EA - PEDESTAL WITH TRANSFORMER BASE AND DETECTOR, RELOCATED
1 EA - PEDESTAL FOUNDATION
X FT - 4" CONDUIT
X FT - SIGNAL CABLE
INTERCONNECT
X FT - TRENCH, AS PER PLAN
X FT - 4" MULTI-CELL CONDUIT
X FT - 4" CONDUIT
X FT - 24 STRAND SM FIBER OPTIC CABLE
X FT - 288 STRAND SM FIBER OPTIC CABLE
INTERCONNECT
X FT - TRENCH, AS PER PLAN
X FT - 4" MULTI-CELL CONDUIT
X FT - 24 STRAND SM FIBER OPTIC DROP CABLE
X FT - ETHERNET CABLE
X FT - SIGNAL CABLE
EX. (2) 3" CTSS FIBER CONDUITS (DND)
EX. 2" CTSS ELECTRIC CONDUIT (DND)
EX. PB (TBR)
EX. VDS CABINET (TBR)
EX. 18" CTSS PB (DND)
EX. 32" PB (TO REMAIN)
INTERCONNECT
X FT - TRENCH, AS PER PLAN
X FT - 4" MULTI-CELL CONDUIT
X FT - 24 STRAND SM FIBER OPTIC CABLE
X FT - 24 STRAND SM FIBER OPTIC CABLE
INSTALL IN EXISTING 3" CONDUITS
REMOVE EXISTING 24 STRAND SM FIBER
EX. CTSS FIBER (TO REMAIN)
(2) 3" CONDUITS
(2) 144 STRAND FIBER OPTIC CABLES
EX. 2" CTSS ELECTRIC CONDUIT (DND)
EX. ODOT FIBER (TBR)
EX. ODOT AND CTSS FIBER (TBR)
EX. CTSS FIBER (TBR)
EX. CTSS FIBER (ABANDON)
CL CONST. SINCLAIR RAMP B
CL CONST. SINCLAIR RAMP E
CL CONST. I-71
CL CONST. MORSE RAMP B
I-71 SB ENTRANCE RAMP FROM SINCLAIR RD
I-71 SB EXIT RAMP TO SINCLAIR RD
I-71 NB ENTRANCE RAMP FROM MORSE RD
EX. I-71 SOUTHBOUND
EX. I-71 NORTHBOUND
EX. 30" COX WATER O.L. "D"
EX. 8" COX STEEL O.L. "D"
EX. 6" COX STEEL O.L. "D"
EX. 4" COX STEEL O.L. "D"
EX. 3" COX STEEL O.L. "D"
EX.COC CONDUIT O.L. "B"
EX.OHDOT CONDUIT O.L. "B"
EX.OHDOT CONDUIT O.L. "C"
EX.OHDOT CONDUIT O.L. "D"
EX.COC CONDUIT O.L. "C"
EX.COC CONDUIT O.L. "D"
Ex LA-R/W
FO
3-HO
MATCH LINE STA. 1315+00
MATCH LINE STA. 1326+00
6318
6319
6320
6321
6322
6323
6324
1316
1317
1318
1319
1320
1321
1322
1323
1324
1325
3316
3317
3318
3319
3320
3321
3322
3323
3324
3325
2322
2324
HORIZONTAL SCALE IN FEET
0
10
20
40
ITS PLAN - I-71
STA. 1315+00.00 TO STA. 1326+00.00
FOR ITS LEGEND, SEE SHEET P.355
DESIGN AGENCY
Jacobs
DESIGNER
BAP
REVIEWER
RF 03/20/26
PROJECT ID
109164
SHEET P.360
TOTAL 618
FRA-71-19.10
MODEL: CU_ITS - Plot: 12 PAPERSIZE: 66x34.0in | DATE: 3/31/2026 TIME: 10:15:24 AM BYDIR: DWGS_ITS_PLT_I-71HOL_PENTBL: DWGS_ITS_PLT_I-71HOL_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: C:\WDOTDWG\ WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DRAWINGS ARE PROPERTY OF THE OHIO DEPARTMENT OF TRANSPORTATION. ANY REUSE WITHOUT PRIOR WRITTEN CONSENT OF ODOT IS PROHIBITED AND ODOT IS NOT RESPONSIBLE FOR ANY CONVERSION OF THE DRAWINGS TO OTHER FORMATS OR INCOMPLETE DRAWINGS.




FOR ITS LEGEND, SEE SHEET P.355

HORIZONTAL SCALE IN FEET
0 10 20 40


ITS PLAN - I-71
STA. 1326+00 TO STA. 1337+00

DESIGN AGENCY
Jacobs

DESIGNER BAP
REVIEWER RF 03/20/26
PROJECT ID 109164
SHEET P.361 TOTAL 618

FRA-71-19.10

MODEL: CU_ITS - Plot: 13 PAPERSIZE: 66x34 (in.) DATE: 3/17/2026 TIME: 03:15:24 AM BYDWG: DHOOT, PM: T. LANG, PENTBL: DHOOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: DHOOTS4D WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: C:\Users\chris.lawrence\Jacobs\Desktop\Projects\FRA-71-19.10\Design\ITS\Plans\FRA-71-19.10_ITS_PLAN_1326+00_1337+00.dgn




FOR ITS LEGEND, SEE SHEET P.355

HORIZONTAL SCALE IN FEET
0 10 20 40


ITS PLAN - I-71
STA. 1337+00.00 TO STA. 1348+00.00

DESIGN AGENCY
Jacobs

DESIGNER BAP
REVIEWER RF 03/20/26
PROJECT ID 109164
SHEET P.362 TOTAL 618

FRA-71-19.10

MODEL: CU_071 - Plot: 14 PAPERSIZE: 66x34 (in.) DATE: 3/31/2026 TIME: 10:19:24 AM BYDIR: DWGS_PEM_C-LHSS_PENTBL: DWGS_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: DWGS\OD WORKSET: 109164 PRODUCT: OpenRoads Designer 24.00.12.25
FILENAME: P:\Projects\Ohio\Columbus\Columbus Area ITS Phase 2\Design\Roadway\Plans\Sheets\FRA-71-19.10.dgn




FOR ITS LEGEND, SEE SHEET P.355

HORIZONTAL SCALE IN FEET
0 10 20 40


ITS PLAN - I-71
STA. 1403+00.00 TO STA. 1414+00.00

DESIGN AGENCY
Jacobs

DESIGNER: BAP
REVIEWER: RF 03/20/26
PROJECT ID: 109164
SHEET: P.363 TOTAL: 618

FRA-71-19.10

MODEL: CU_071 - Plan 20 PAPERSIZE: 66x34.0in | DATE: 3/31/2026 TIME: 10:31:27 AM BY/DIR: DWOFF, PM: C.Lemmo@jacobs.com WORKSPACE: DWOFF0x40 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.12.25
FILE: C:\Users\c.lemmo\Jacobs\Desktop\Projects\Fra-71-19.10\Design\Roadway\Plan and Profile\Fra-71-19.10 Plan 20.dgn




NOTES:
1. IN A NEW SPLICE ENCLOSURE INSIDE THE EX. 48 PULL BOX, SPLICE THE PROPOSED 288 STRAND SM FIBER OPTIC CABLE, THE RELOCATED 288 STRAND SM FIBER OPTIC CABLE, (2) 144 STRAND SM FIBER OPTIC CABLES, (3) 144 STRAND SM FIBER OPTIC CABLES FROM THE EX. CABINET, AND THE 24 STRAND SM FIBER OPTIC CABLE FROM THE CABINET.

FOR ITS LEGEND, SEE SHEET P.355

HORIZONTAL SCALE IN FEET
0 10 20 40


# ITS PLAN - I-71
# STA. 1414+00.00 TO STA. 1425+00.00

DESIGN AGENCY
Jacobs

DESIGNER BAP
REVIEWER RF 03/20/26
PROJECT ID 109164
SHEET P.364 TOTAL 618

FRA-71-19.10

MODEL: CLF_ITS - Plan 21 PAPERSIZE: 66x34 (in) DATE: 3/31/2026 TIME: 10:31:31 AM BY/DBY: DHOOT, PM: C.J.HAIL PENTEL: DHOOT, Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: DHOOT0402 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
DGN FILE PATH: C:\Users\dhoot\Jacobs\Ohio DOT - Documents\Projects\109164 - FRA-71-19.10 ITS Design\Design\ITS PLAN.dgn




FOR ITS LEGEND, SEE SHEET P.355

HORIZONTAL SCALE IN FEET
0 10 20 40


# ITS PLAN - I-71 SR 161 RAMPS A & D

DESIGN AGENCY
Jacobs

DESIGNER: BAP
REVIEWER: RF 03/20/26
PROJECT ID: 109164
SHEET: P.365 TOTAL: 618

FRA-71-19.10

MODEL: CLF_563 - Plan 22 PAPERSIZE: 66x34 in | DATE: 3/31/2026 TIME: 03:19:38 AM BY/DBY: OHDOT_PSF (J-uhdg ENTRL OHDOT_Pen.tbl USER: Chris.Lawmon@jacobs.com WORKSPACE: OHDOTSVG5 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO BENTLEY SYSTEMS LICENSE AGREEMENT. UNAUTHORIZED REPRODUCTION, DISTRIBUTION OR DISCLOSURE PROHIBITED.




FRA-71-19.10

BLOCK: Sheet PAPERSIZE: ANSI A4 | DATE: 3/31/2026 TIME: 12:19:00 AM PITSTOP: ON|OFF_PDF_Y-profile PENTBL: ON|OFF_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: ON|OFFICE|O WORKSET: 109164 PRODUCT: OpenRoads|Designer 24.00.02.25
FILE: N:\Projects\Ohio\Columbus Area Office\Projects\Columbus Area\109164 - FRA-71-19.10 Lighting Improvements\Roadway\Lighting\Sheets\109164_LIGHTING_SCHEMATIC.dgn

LIGHTING PLAN - I-71
SCHEMATIC PLAN

DESIGN AGENCY
Jacobs

DESIGNER

REVIEWER

PROJECT ID
109164

SHEET P.366 | TOTAL 618

**GENERAL LIGHTING NOTE**

THE CONTRACTOR SHALL CONFORM TO THE NATIONAL ELECTRIC CODE, NATIONAL ELECTRICAL SAFETY CODE AND THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAY IN PRFORMING CONTRACT WORK. THE HIGHWAY LIGHTING SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE 2023 ODOT CONSTRUCTION AND MATERIALS SPECIFICATIONS. THIS DOCUMENT SHALL GOVERN ALL MATERIALS AND WORKMANSHIP INVOLVED IN THE IMPROVEMENTS SHOWN ON THES PLANS, EXCEPT AS SUCH SPECIFICATIONS ARE MODIFIED BY THE FOLLOWING SPECIFICATIONS OR BY THE CONSTRUCTION DETAILS SET FORTH HEREIN.

**GUARANTEE**

THE CONTRACTOR SHALL GUARANTEE THAT THE LIGHTING SYSTEM INSTALLED AS PART OF THIS CONTRACT SHALL OPERATE SATISFACTORILY FOR A PERIOD OF 90 DAYS FOLLOWING COMPLETION OF THE 10-DAY PERFORMANCE TEST. IN THE EVENT OF UNSATISFACTORY OPERATION, THE CONTRACTOR SHALL CORRECT FAULTY INSTALLATIONS, MAKE REPAIRS AND REPLACE DEFECTIVE PARTS WITH NEW PARTS OF EQUAL OR BETTER QUALITY. EQUIPMENT, MATERIAL AND LABOR COSTS INCURRED IN CORRECTING AN UNSATISFACTORY OPERATION SHALL BE BORNE BY THE CONTRACTOR.

CUSTOMARY MANUFACTURER'S GUARANTEES FOR THE FOREGOING ITEMS SHALL BE TURNED OVER TO THE STATE OR THE MAINTAINING AGENCY FOLLOWING ACCEPTANCE OF THE EQUIPMENT.

THE COST OF GUARANTEEING THE LIGHTING SYSTEM WILL BE INCIDENTAL TO AND INCLUDED IN THE CONTRACT UNIT PRICE OF THE VARIOUS ITEMS MAKING UP THE SYSTEM.

**PADLOCKS AND KEYS**

PADLOCKS FURNISHED SHALL BE EITHER BRASS OR BRONZE, EQUAL TO MASTER NO. 4BKA OR WILSON BOHANNAN 660A, AND SHALL BE KEYED IN ACCORDANCE WITH C&MS 631.06. PAYMENT SHALL BE INCLUDED IN THE BID FOR THE ITEM(S) BEING LOCKED.

**ITEM 625, LIGHT POLE, REMOVE AND RE-ERECT, AS PER PLAN**

THIS ITEM OF WORK SHALL CONSIST OF REMOVING, STORING, AND RE-ERECTING AN EXISTING LIGHT POLE AT THE LOCATION NOTED ON THE PLANS. TEMPORARILY RELOCATE THE POLE TO A LOCATION THAT IS OUTSIDE OF THE CLEAR ZONE AND STORE IN A MANNER TO PREVENT DAMAGE AS APPROVED BY THE ENGINEER.

THE LIGHT POLE SHALL BE CLEANED AND REPAIRED TO BRING THE POLE TO A GOOD SERVICEABLE CONDITION. THE EXISTING POLE NUMBER DECAL SHALL BE REMOVED AND REPLACED IF IT IS IN POOR CONDITION OR IF THE POLE NUMBER HAS CHANGED.

PAYMENT SHALL BE MADE AT THE UNIT PRICE BID UNDER ITEM 625, LIGHT POLE, REMOVE AND RE-ERECT, AS PER PLAN, FOR EACH POLE INSTALLED, WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIAL, AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.

**ITEM 625, LIGHTING, MISC.: REMOVAL OF UNDERPASS LIGHTING**

THIS ITEM OF WORK SHALL CONSIST OF REMOVING THE EXISTING UNDERPASS LIGHTING SYSTEM, WHICH INCLUDES THE REMOVAL OF DISCONNECT SWITCHES, CONDUITS, FITTINGS, WIRING, FIXTURES, AND ALL RELATED APPURTENANCES.

PAYMENT SHALL BE MADE AT THE UNIT PRICE BID UNDER ITEM 625, LIGHTING, MISC.: REMOVAL OF UNDERPASS LIGHTING, FOR EACH INTERCHANGE WHERE EXISTING UNDERPASS LIGHTING IS REMOVED, WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIAL, AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.

**SPECIAL, MAINTAIN EXISTING LIGHTING**

EXISTING ROADWAYS WHICH ARE TO REMAIN OPEN TO TRAFFIC DURING CONSTRUCTION OF THIS PROJECT AND WHICH ARE LIGHTED SHALL HAVE THE LIGHTING MAINTAINED AS DESCRIBED HEREIN.

BEFORE ANY WORK IS STARTED IN THE IMMEDIATE VICINITY OF THE EXISTING LIGHTING CIRCUITS, REPRESENTATIVES OF ODOT, THE MAINTAINING AGENCY AND THE CONTRACTOR SHALL MAKE A VISUAL INSPECTION OF THE EXISTING ROADWAY LIGHTING CIRCUITS TO BE MAINTAINED. DURING THIS INSPECTION, A WRITTEN RECORD OF THE CONDITION OF EXISTING LIGHTING SHALL BE MADE BY ODOT'S REPRESENTATIVE. THIS WRITTEN REPORT SHALL NOTE INDIVIDUAL LUMINAIRES WHICH ARE NOT IN WORKING ORDER, INDIVIDUAL POLES WHICH ARE NOT STANDING, AND INDIVIDUAL CIRCUITS WHICH ARE NOT IN WORKING ORDER. THE COMPLETED REPORT SHALL BE SIGNED BY THE REPRESENTATIVES OF ODOT, THE MAINTAINING AGENCY AND THE CONTRACTOR.

IF, AS A RESULT OF THIS INSPECTION, IT IS DETERMINED THAT THE CONDITION OF THE EXISTING SYSTEM IS BELOW THAT REQUIRED FOR THE SAFETY OF THE TRAVELING PUBLIC, THEN THE MAINTAINING AGENCY SHALL MAKE THE REPAIRS NECESSARY TO RETURN THE SYSTEM TO AN ACCEPTABLE CONDITION. FOLLOWING THESE REPAIRS, THE SYSTEM SHALL AGAIN BE INSPECTED AND A REPORT SHALL BE MADE AND SIGNED AS OUTLINED HEREIN.

WHEN THE EXISTING SYSTEM IS IN AN ACCEPTABLE CONDITION, IT SHALL BE TURNED OVER TO THE CONTRACTOR WHO SHALL THEN BE REQUIRED TO MAINTAIN THE EXISTING LIGHTING TO THE CONDITION OUTLINED IN THIS REPORT WITH THE EXCEPTION OF KNOCKDOWNS DUE TO TRAFFIC ACCIDENTS.

REPLACEMENT OF KNOCKED DOWNED UNITS SHALL BE DONE ONLY WHEN THE ENGINEER HAS DETERMINED THAT THE REPLACEMENT OF THE KNOCKED DOWN UNIT IS NECESSARY AND SHALL BE PAID SEPARATELY ON A UNIT BASIS.

BETTERMENTS SHALL BE COVERED IN ITEMS OF WORK PERTAINING TO THE CONSTRUCTION OF PERMANENT IMPROVEMENT.

WHEN THE SEQUENCE OF CONSTRUCTION ACTIVITIES REQUIRES, OR SHOULD THE CONTRACTOR DESIRE, THE REMOVAL OF THE EXISTING LIGHTING BEFORE THE NEW LIGHTING IS OPERATIONAL, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TEMPORARY LIGHTING OF THIS PORTION OF THE ROADWAY.

PRIOR TO INSTALLING SUCH LIGHTING, THE CONTRACTOR SHALL PREPARE AND SUBMIT FOUR SETS OF THE TEMPORARY LIGHTING PLAN TO THE ENGINEER FOR REVIEW AND APPROVAL.

THIS PLAN SHALL SHOW LOCATIONS OF POLES, LENGTHS OF BRACKET ARMS, STYLES OF LUMINAIRES, MOUNTING HEIGHTS, WIRING METHODS AND OTHER PERTINENT INFORMATION. THE TEMPORARY LIGHTING SHALL PROVIDE AN AVERAGE INITIAL INTENSITY OF 1.2 FOOTCANDLES WITH AN AVERAGE TO MINIMUM UNIFORMITY NOT TO EXCEED 3:1. MOUNTING HEIGHT OF TEMPORARY LUMINAIRES SHALL NOT BE LESS THAN 30 FEET, AND THE MINIMUM OVERHEAD CONDUCTOR CLEARANCE SHALL BE 20 FEET. TEMPORARY OVERHEAD CONSTRUCTION SHALL NOT BE LESS THAN GRADE "B" FOR STRENGTH REQUIREMENTS AS DEFINED BY THE NATIONAL ELECTRIC SAFETY CODE. WOOD POLES WITH OVERHEAD WIRING MAY BE USED. HOWEVER, TEMPORARY LIGHTING SHALL MEET FEDERAL AND STATE SAFETY CRITERIA. IF BREAKAWAY POLES ARE USED TO MEET THESE CRITERIA, THEN UNDERGROUND WIRING SHALL BE USED. RECONDITIONED OR USED MATERIALS MAY BE FURNISHED FOR TEMPORARY LIGHTING.

**SPECIAL, MAINTAIN EXISTING LIGHTING** CONT'D

ALL MATERIALS NECESSARY TO COMPLETE THE TEMPORARY LIGHTING SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR. WHEN NO LONGER NEEDED, THE TEMPORARY LIGHTING INSTALLATION SHALL BE REMOVED AND PROPERLY DISPOSED OF BY THE CONTRACTOR.

WHEN THE PROJECT BEGINS AND THE CONTRACTOR HAS TAKEN OVER MAINTENANCE OF THE EXISTING FACILITIES, THE CONTRACTOR IS RESPONSIBLE FOR ALL REQUIRED LAYOUTS AND LOCATIONS OF THE EXISTING AND PROPOSED ELECTRICAL CIRCUITS AND RELATED ITEMS WITHIN THE PROJECT LIMITS. THE CONTRACTOR SHALL LOCATE AND MARK ALL UNDERGROUND ELECTRICAL CIRCUITS (INCLUDING TRAFFIC LOOPS AND LOOP LEAD-INS) FOR THE DURATION OF THE PROJECT.

THE MAINTAINING AGENCY WILL PAY FOR ELECTRICAL ENERGY CONSUMED BY EXISTING POWER SERVICES AND BY PROPOSED PERMANENT POWER SERVICES AFTER ACCEPTANCE OF THE LIGHTING WORK. THE CONTRACTOR WILL PAY FOR ELECTRICAL ENERGY, INSTALLATION, REMOVAL AND MAINTENANCE OF ANY TEMPORARY POWER SERVICES.

THE LUMP SUM PRICE BID FOR ITEM SPECIAL "MAINTAIN EXISTING LIGHTING" SHALL INCLUDE PAYMENT FOR ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO MAINTAIN THE EXISTING LIGHTING AS SPECIFIED HEREIN.

THE UNIT PRICE BID FOR ITEM SPECIAL "REPLACEMENT OF EXISTING LIGHTING UNIT" SHALL BE FULL PAYMENT FOR THE REPLACEMENT OF AN EXISTING LIGHTING UNIT WHICH HAS BEEN KNOCKED DOWN AFTER THE AFOREMENTIONED INSPECTION AND SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO PROVIDE A REPLACEMENT FOR SUCH UNIT.

**GROUNDING AND BONDING**

THE REQUIREMENTS OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS (C&MS) AND THE HL AND TC SERIES OF STANDARD CONSTRUCTION DRAWINGS ARE MODIFIED AS FOLLOWS:

1. ALL METALLIC PARTS CONTAINING ELECTRICAL CONDUCTORS SHALL BE PERMANENTLY JOINED TO FORM AN EFFECTIVE GROUND FAULT CURRENT PATH BACK TO THE GROUNDED CONDUCTOR IN THE POWER SERVICE DISCONNECT SWITCH.
   - A. PROVIDE AN EQUIPMENT GROUNDING CONDUCTOR IN METALLIC CONDUITS (725.04) IN ADDITION TO THE CONDUCTORS SPECIFIED AND BOND THE CONDUIT TO THIS GROUNDING CONDUCTOR.
   - B. WHEN AN EQUIPMENT GROUNDING CONDUCTOR IS REQUIRED IN PLASTIC CONDUIT (725.05), THE INSTALLATION SHALL INCLUDE A SEPARATE EQUIPMENT GROUNDING CONDUCTOR IN ADDITION TO THE CONDUCTORS SPECIFIED.
   - C. METAL PULL BOX LIDS SHALL BE BONDED BY ATTACHMENT OF THE EQUIPMENT GROUNDING CONDUCTOR TO THE FRAME DIAGONAL AS PROVIDED ON SCD. HL-30.11.
   - D. IF MULTIPLE CONDUIT RUNS BEGIN AND END AT THE SAME POINTS, ONLY ONE EQUIPMENT GROUNDING CONDUCTOR IS REQUIRED.
2. CONDUITS.
   - A. THE 725.04 CONDUIT SHALL HAVE GROUNDING BUSHINGS INSTALLED AT ALL TERMINATION POINTS. THE BUSHING MATERIAL SHALL BE COMPATIBLE WITH GALVANIZED STEEL CONDUIT AND THE GROUNDING LUG MATERIAL SHALL BE COMPATIBLE FOR USE WITH COPPER WIRE. THREADED OR COMPRESSION TYPE BUSHINGS MAY BE USED.
   - B. THE 725.05 CONDUIT SHALL HAVE THE INSIDE AND OUTSIDE DIAMETERS OF THE CONDUIT DEBURRED AT ALL TERMINATION POINTS.

**GROUNDING AND BONDING**

- C. BOTH ENDS OF METALLIC CONDUIT SHALL BE BONDED TO THE EQUIPMENT GROUNDING CONDUCTOR.
- D. METALLIC CONDUIT MAY BE BONDED TO METALLIC BOXES THROUGH THE USE OF CONDUIT FITTINGS UL APPROVED FOR THIS TYPE OF CONNECTION, WITH THE BOX BONDED TO THE EQUIPMENT GROUNDING CONDUCTOR.

3. WIRE FOR GROUNDING AND BONDING.
   - A. USE INSULATED, COPPER WIRE FOR THE EQUIPMENT GROUNDING CONDUCTOR. BONDING JUMPERS IN BOXES AND ENCLOSURES MAY BE BARE OR INSULATED COPPER WIRE. WIRE SIZE SHALL BE AS FOLLOWS:
     - I. USE SAME SIZE EQUIPMENT GROUNDING CONDUCTOR AS THE DUCT CABLE OR DISTRIBUTION CABLE CIRCUIT CONDUCTORS, WITH THE MINIMUM CONDUCTOR SIZE OF #4 AWG. BONDING JUMPERS WILL BE MINIMUM SIZE #4 AWG.
     - II. THE INSULATION SHALL BE GREN OR GREEN WITH YELLOW STRIPE(S). FOR #4 AWG OR LARGER, INSULATION MAY ALSO BE BLACK WITH GREEN TAPE/LABELS INSTALLED AT ALL ACCESS POINTS.

4 . GROUND ROD.
   - A. A 3/4-INCH SCHEDULE 40 PVC CONDUIT WILL BE USED IN FOUNDATIONS AND CONCRETE WALLS FOR THE GROUNDING CONDUCTOR (GROUND WIRE) RACEWAY TO THE GROUND ROD. SHOULD METALLIC CONDUIT BE USED, BOTH ENDS OF THE CONDUIT SHALL BE BONDED TO THE GROUNDING CONDUCTOR.
   - B. THE TYPICAL GROUNDING CONDUCTOR (GROUND WIRE) SHALL BE 4 AWG INSULATED, COPPER.

5. POWER SERVICE AND DISCONNECT SWITCH.
   - A. AT THE POWER SERVICE LOCATION, THE GROUNDING CONDUCTOR (GROUND WIRE) FROM THE DISCONNECT SWITCH NEUTRAL (AC-) BAR TO THE GROUND ROD SHALL BE A CONTINUOUS, UNSPLICED CONDUCTOR. IF SPLICED, IT SHALL BE AN EXOTHERMIC WELD BUTT SPLICE.
   - B. THE SERVICE NEUTRAL (AC-) SHALL ONLY BE CONNECTED TO GROUND AT THE PRIMARY POWER SERVICE DISCONNECT SWITCH.
   - C. IF SECONDARY DISCONNECT SWITCHES ARE CONNECTED AFTER THE PRIMARY DISCONNECT SWITCH, THE NEUTRAL (AC-) SHALL ONLY BE GROUNDED AT THE PRIMARY SWITCH. EQUIPMENT GROUNDING CONDUCTORS SHALL BE BROUGHT TO THE PRIMARY SWITCH, BUT SHALL BE GROUNDED AT BOTH SECONDARY AND PRIMARY SWITCHES.

6. STRUCTURE GROUNDING

HL-50.24 SHOWS A 1/0 AWG STRANDED COPPER CABLE USED FOR STRUCTURE GROUNDING. ADDITIONALLY, THIS SAME CABLE SHALL BE INSULATED AND ANY CONNETIONS AND BARE COPPER STRANDS EXPOSED TO CONCRETE SHALL BE COVERED WITH MASTIC TO PREVENT CONTACT WITH THE CONCRETE.

7. PAYMENT - ALL MATERIALS AND WORK REQUIRED TO COMPLETE THE EFFECTIVE GROUND FAULT CURRENT PATH SYSTEM ARE INCIDENTAL TO THE CONDUCTORS INSTALLED BY CONTRACT.

**ITEM 625, DISTRIBUTION CABLE REMOVED, AS PER PLAN**

THE CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL EXISTING DISTRIBUTION CABLE THAT IS NOT TO REMAIN IN SERVICE, AS SHOWN IN THE PLANS.

EXISTING LIGHTING CONDUIT WITH CIRCUIT CABLES CALLED OUT FOR REMOVAL MAY BE ABANDONED IN PLACE, UNLESS IT CONFLICTS WITH ANY PROPOSED IMPROVEMENTS, IN WHICH CASE IT SHALL BE REMOVED. ANY CONDUIT THAT IS REQUIRED TO BE REMOVED SHALL BE INCIDENTAL TO THIS PAY ITEM.

# LIGHTING GENERAL NOTES

DESIGN AGENCY

Jacobs

DESIGNER

REVIEWER

PROJECT ID
109164

SHEET P.367 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:19:15 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19\10 I-71 HSR\30 WIP\109164400-EngineeringILighting\Sheets\109164_LN001.dgn

***625, PULL BOX CLEANED***

*THIS ITEM OF WORK SHALL CONSIST OF CLEANING AN EXISTING PULL BOX BY REMOVING ANY EXISTING CABLES NOT BEING RECONNECTED, AND DEBRIS SO THAT NEW CABLES CAN BE INSTALLED. ANY UNUSED OPENINGS SHALL BE CLOSED. DISTURBED AREAS NEAR THE PULL BOX SHALL BE CLEARED OF WEEDS OR DEBRIS AND SHALL BE FULLY RESTORED. MATERIAL REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE PROPERLY DISPOSED OF OFF OF THE PROJECT SITE.*

*PAYMENT WILL BE MADE AT THE UNIT PRICE BID UNDER C&MS ITEM 625, "PULL BOX CLEANED" FOR EACH PULL BOX CLEANED WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIALS AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.*

***625, CONDUIT CLEANED AND CABLES REMOVED***

*THIS ITEM SHALL CONSIST OF CLEANING AN EXISTING CONDUIT BY REMOVING EXISTING CABLES, MUD AND DEBRIS SO THAT NEW CABLE CAN BE INSTALLED. INCIDENTAL TO THE CLEANING IS THE INSTALLATION OF BUSHINGS AND/OR COUPLINGS ON THE ENDS OF EXISTING CONDUIT AS REQUIRED. MATERIALS REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTOR FOR PROPER DISPOSAL OFF OF THE PROJECT SITE. DISTURBED AREAS SHALL BE PROPERLY RESTORED.*

*PAYMENT WILL BE MADE AT THE UNIT PRICE BID UNDER C&MS ITEM 625, "CONDUIT CLEANED AND CABLES REMOVED" PER FOOT OF CONDUIT CLEANED WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIALS AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.*

***CONDUIT EXPANSION AND DEFLECTION***

*EXPANSION FITTINGS SHALL BE OZ TYPE AX, CROUSE HINDS TYPE XJG, OR EQUAL APPROVED BY THE ENGINEER. EACH EXPANSION FITTING SHALL PROVIDE EITHER 4 OR 8 INCHES TOTAL MOVEMENT AS SPECIFIED BY THE PLAN DETAILS AND SHALL HAVE AN EXTERNAL COPPER BONDING JUMPER, UNLESS SPECIFIED OTHERWISE BY THE PLAN DETAILS.*

*DEFLECTION COUPLINGS SHALL BE OZ TYPE DX, CROUSE HINDS TYPE XD, OR EQUAL APPROVED BY THE ENGINEER. EACH DEFLECTION COUPLING SHALL HAVE AN EXTERNAL COPPER BONDING JUMPER, UNLESS SPECIFIED OTHERWISE BY THE PLAN DETAILS. MINIMUM DEFLECTION CAPABILITY: 25 DEGREES.*

*EXPANSION AND DEFLECTION FITTINGS FULLY OR PARTIALLY EMBEDDED IN CONCRETE, SOIL, OR SIMILAR MATERIAL SHALL BE COMPLETELY WRAPPED IN A NEOPRENE SLEEVE OR SHEET OF 1/2-INCH MINIMUM THICKNESS. SECURE NEOPRENE WRAP WITH TIE-WRAPS PRIOR TO EMBEDMENT OF THE FITTING.*

***PADLOCKS AND KEYS***

*PADLOCKS FURNISHED SHALL BE EITHER BRASS OR BRONZE, EQUAL TO MASTER NO. 4BKA OR WILSON BOHANNAN 660A, AND SHALL BE KEYED IN ACCORDANCE WITH C&MS 631.06. PAYMENT SHALL BE INCLUDED IN THE BID FOR THE ITEM(S) BEING LOCKED.*

***ITEM 625, LUMINAIRE, CONVENTIONAL, SOLID STATE (LED), AS PER PLAN, 240V***

*IN ADDITION TO THE REQUIREMENTS OF THE ODOT CONSTRUCTION AND MATERIAL SPECIFICATIONS, LUMINAIRES FOR CONVENTIONAL LIGHTING UNITS SHALL BE AS FOLLOWS:*

*LUMINAIRES FOR CONVENTIONAL LIGHTING UNITS WITH ASYMMETRIC DISTRIBUTION SHALL BE:*

*AEL, ATBM-P40-XXXX-R3-3K*
*GE EVOLVE, ERL2-18C330-XXX*

*OR EQUAL AS APPROVED BY THE ENGINEER.*

*PAYMENT SHALL BE MADE AT THE UNIT PRICE BID UNDER ITEM 625, LUMINAIRE, CONVENTIONAL, SOLID STATE (LED), AS PER PLAN, 240V, FOR EACH LUMINAIRE INSTALLED, WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIAL, AND INCIDENTALS REQUIRED TO COMPLETE THIS WORK IN A SATISFACTORY AND WORKMANLIKE MANNER.*

***ITEM 625, LUMINAIRE, UNDERPASS, AS PER PLAN***

*IN ADDITION TO THE REQUIREMENTS OF ODOT'S CONSTRUCTION AND MATERIAL SPECIFICATIONS, LUMINAIRES FOR UNDERPASS LIGHTING SHALL BE AS FOLLOWS:*

*LUMINAIRES FOR UNDERPASS LIGHTING UNITS SHALL BE HOLOPHANE TUNNELPASS TNLEDMED PK1 30K MVOLT UDP DGRA SCRW (AT MORSE ROAD) AND TNLEDMED PK1 30K XVOLT UDP DGRA SCRW (AT SR 161), OR EQUAL AS APPROVED BY THE ENGINEER. WALL MOUNTED LUMINAIRES SHALL BE FURNISHED WITH AN INTEGRAL FUSE HOLDER AND 10 AMP FUSE.*

*PAYMENT SHALL BE MADE AT THE UNIT PRICE BID UNDER C&MS ITEM 625, "LUMINAIRE, UNDERPASS, AS PER PLAN" FOR EACH LUMINAIRE WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIAL, AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.*

***ITEM 625, SERVICE TO UNDERPASS LIGHTING, AS PER PLAN***

*THIS ITEM SHALL CONSIST OF PROVIDING COMPLETE ELECTRICAL SERVICE, EXCEPT FOR LUMINAIRES AND PULL BOX GROUND ROD, FOR AN UNDERPASS LIGHTING SYSTEM. THE WORK SHALL INCLUDE DISCONNECT SWITCH, CONDUITS, FITTINGS, WIRING, AND ALL INCIDENTALS NECESSARY TO PROVIDE A COMPLETE UNDERPASS LIGHTING SYSTEM, IN PLACE, TESTED AND ACCEPTED.*

*PAYMENT SHALL BE MADE AT THE UNIT BID PRICE, UNDER CMS ITEM 625, "SERVICE TO UNDERPASS LIGHTING, AS PER PLAN" FOR EACH LIGHTED UNDERPASS, WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIAL, AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.*

***ITEM 625, LIGHTING, MISC.: REMOVAL OF UNDERPASS LIGHTING***

*THIS ITEM OF WORK SHALL CONSIST OF REMOVING THE EXISTING UNDERPASS LIGHTING SYSTEM, WHICH INCLUDES THE REMOVAL OF DISCONNECT SWITCHES, CONDUITS, FITTINGS, WIRING, FIXTURES, AND ALL RELATED APPURTENANCES.*

*PAYMENT SHALL BE MADE AT THE UNIT PRICE BID UNDER ITEM 625, LIGHTING, MISC.: REMOVAL OF UNDERPASS LIGHTING, FOR EACH INTERCHANGE WHERE EXISTING UNDERPASS LIGHTING IS REMOVED, WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIAL, AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.*

***ITEM 625, LIGHT POLE FOUNDATION REMOVED, AS PER PLAN***

*THIS ITEM OF WORK SHALL CONSIST OF REMOVING THE EXISTING LIGHT POLE FOUNDATION TO A MINIMUM OF 1 FOOT BELOW FINISHED GRADE, OR REMOVING THE FOUNDATION COMPLETELY, BACKFILLING THE VOID WITH COMPACTED MATERIAL, AND RESTORING THE DISTURBED AREA TO THE SATISFACTION OF THE ENGINEER.*

*PAYMENT SHALL BE MADE AT THE UNIT PRICE BID UNDER ITEM 625, LIGHT POLE FOUNDATION REMOVED, AS PER PLAN, FOR EACH FOUNDATION REMOVED, WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIAL, AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.*

LIGHTING GENERAL NOTES

DESIGN AGENCY
Jacobs

DESIGNER


REVIEWER

PROJECT ID
109164

SHEET P.367A TOTAL 618

FRA-71-19.10

MODEL: Sheet2 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 9:09:01 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1f@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19\10 I-71 HSR\30 WIP\109164\400-Engineering\Lighting\Sheets\109164_LN001.dgn




HORIZONTAL SCALE IN FEET
0 50 100 200

LEGEND

| EXISTING | PROPOSED | |
|---|---|---|
| | | UTILITY POLE |
| | | PULL BOX / JUNCTION BOX (SIZE AS INDICATED) |
| | | CONTROL CENTER |
| | | 1-1/2" DUCT CABLE (2 CONDUCTOR, SIZE AS INDICATED) |
| | | 1-1/2" DUCT CABLE (3 CONDUCTOR, SIZE AS INDICATED) |
| | | CONDUIT (TYPE, SIZE & INSTALLATION AS INDICATED) |
| | | QUANTITY REFERENCE NUMBER |
| | | REMOVALS (ITEMS AS INDICATED) |
| | | CONVENTIONAL LIGHT POLE (SINGLE OR TWIN-ARM) |
| | | RELOCATED GROUND MOUNTED CONVENTIONAL LIGHT POLE |
| | | LIGHT TOWER, SYMMETRIC DISTRIBUTION |
| | | RELOCATED LIGHT TOWER, SYMMETRIC DISTRIBUTION |
| | | UNDERPASS LUMINAIRE |


| POWER SERVICE DESIGNATION | TYPE OF SERVICE | CONNECTED LOAD (KVA) | SERVICE ENTRANCE CONDUCTOR - AWG | ENCLOSURE RATING (AMP) | CIRCUIT NUMBER | CIRCUIT LOAD (AMPS) | CIRCUIT FUSE (AMPS) | MAINTAINING AGENCY |
|---|---|---|---|---|---|---|---|---|
| CC-5 (EXISTING) | 480V SINGLE PHASE 2 WIRE GROUNDED NEUTRAL | 32.95 | NO. 2 | 60 | J<br>K | 30.69<br>37.75 | 50<br>50 | ODOT<br>ODOT |
| CC-5 (PROPOSED) | 240V SINGLE PHASE 3 WIRE GROUNDED NEUTRAL | 11.95 | NO. 2 | 100 | J1<br>J2<br>K1<br>K2 | 12.68<br>15.19<br>10.13<br>11.81 | 20<br>20<br>20<br>20 | ODOT<br>ODOT<br>ODOT<br>ODOT |

| POWER SERVICE DESIGNATION | TYPE OF SERVICE | CONNECTED LOAD (KVA) | SERVICE ENTRANCE CONDUCTOR - AWG | ENCLOSURE RATING (AMP) | CIRCUIT NUMBER | CIRCUIT LOAD (AMPS) | CIRCUIT FUSE (AMPS) | MAINTAINING AGENCY |
|---|---|---|---|---|---|---|---|---|
| CC-1 (EXISTING) | 480V SINGLE PHASE 3 WIRE W/ GROUNDED NEUTRAL | 38.40 | NO. 2 | 100 | A<br>B | 16.0<br>64.0 | 30<br>100 | ODOT |
| CC-1 (PROPOSED) | 480V SINGLE PHASE 3 WIRE W/ GROUNDED NEUTRAL | 38.74 | NO. 2 | 200 | A<br>B | 16.71<br>64.0 | 30<br>100 | ODOT |

TYPICAL ANNOTATION

STA. XXXX+XX, XX' RT., I-71 (XX-XX)
ATXXBXX, CONVENTIONAL SOLID STATE (LED)

- STATION
- OFFSET
- ROADWAY SIDE
- ALIGNMENT REFERENCE
- CONTROLLER AND CIRCUIT NO.
- POLE NO.
- (XX) SUBSUMMARY REFERENCE NO.
- LUMINAIRE TYPE
- MOUNTING HEIGHT
- BRACKET ARM LENGTH
- BASE




LIGHTING PLAN - CIRCUIT DIAGRAM
CIRCUITS J1, J2, K1 & K2

DESIGN AGENCY
Jacobs

DESIGNER


REVIEWER

PROJECT ID
109164

SHEET P.368 | TOTAL 618

FRA-71-19.10

MODEL: CU_071 - Sheet 1 PAPERSIZE: 66x34.0 in | DATE: 7/31/2024 TIME: 12:19:12 AM PLTDRV: DWGPC_PDF_E.pltcfg PENTBL: DWGPC_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWGPC WORKSET: 109164 PRODUCT: CivilRadialDesigner 24.00.02.25
ELECTRONIC ENGINEER'S SEAL AND AUTHENTICATION APPEARS ON THE PDF COVER SHEET. ELECTRONIC SIGNATURES AND SEALS ARE NOT VALID ON ANY OTHER PDF.




LEGEND

| EXISTING | PROPOSED | |
|---|---|---|
| | | UTILITY POLE |
| | | PULL BOX / JUNCTION BOX (SIZE AS INDICATED) |
| | | CONTROL CENTER |
| | | 1-1/2" DUCT CABLE (2 CONDUCTOR, SIZE AS INDICATED) |
| | | 1-1/2" DUCT CABLE (3 CONDUCTOR, SIZE AS INDICATED) |
| | | CONDUIT (TYPE, SIZE & INSTALLATION AS INDICATED) |
| | (XX) | QUANTITY REFERENCE NUMBER |
| | | REMOVALS (ITEMS AS INDICATED) |
| | | CONVENTIONAL LIGHT POLE (SINGLE OR TWIN-ARM) |
| | | RELOCATED GROUND MOUNTED CONVENTIONAL LIGHT POLE |
| | | LIGHT TOWER, SYMMETRIC DISTRIBUTION |
| | | RELOCATED LIGHT TOWER, SYMMETRIC DISTRIBUTION |
| | | UNDERPASS LUMINAIRE |

| POWER SERVICE DESIGNATION | TYPE OF SERVICE | CONNECTED LOAD (KVA) | SERVICE ENTRANCE CONDUCTOR - AWG | ENCLOSURE RATING (AMP) | CIRCUIT NUMBER | CIRCUIT LOAD (AMPS) | CIRCUIT FUSE (AMPS) | MAINTAINING AGENCY |
|---|---|---|---|---|---|---|---|---|
| CC-4 (EXISTING) | 480V SINGLE PHASE 2 WIRE GROUNDED NEUTRAL | 28.82 | NO. 4 | 60 | I | 26.10 | 40 | ODOT |


HORIZONTAL SCALE IN FEET
0 25 50 100

# LIGHTING PLAN
## BEGIN WORK TO STA. 1284+50.00

DESIGN AGENCY
Jacobs
DESIGNER
REVIEWER
PROJECT ID
109164
SHEET P.369 TOTAL 618

FRA-71-19.10

MODEL: CU1_071 - Sheet:0 PAPERSIZE: 66x34.0 in | DATE: 7/31/2024 TIME: 2:03:03 PM | FCDIR: C:\MDOT_CMDP_1\ | pltSB_FIXTBL: CMDOT_Pen.tbl | USER: Chris.Lawrence@jacobs.com WORKSPACE: CMDOTCU01 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. THIS FILE IS LICENSED SOFTWARE PRODUCT OF BENTLEY SYSTEMS, INCORPORATED. LICENSE ID: 1000184




*NOTES:*

*1. REMOVE EXISTING CIRCUITS 5J AND 5K AS NEEDED TO INSTALL PROPOSED CIRCUITS. ABANDON REMAINING CIRCUITRY.*

*2. EXISTING CIRCUITS CONSIST OF (2) NO. 4 AWG, UNLESS NOTED OTHERWISE.*

*FOR LEGEND SEE SHEET P.369.*


HORIZONTAL SCALE IN FEET
0 25 50 100

# LIGHTING PLAN
## STA . 1284+50.00 TO STA. 1313+50.00

DESIGN AGENCY
Jacobs
DESIGNER
REVIEWER
PROJECT ID
109164
SHEET P.370 TOTAL 618

FRA-71-19.10

MODEL: CLP_OTI - Sheet 1 PAPERSIZE: 66x34 in | DATE: 7/7/2026 TIME: 12:19:55 AM PLOTBY: CHRISTI_PEAT_C LAYER: PENTEL CHRISTI_PEAT USER: Chris.Lawrence@jacobs.com WORKSPACE: C:\MICROSTATION\CHRISTI_PEAT\WORKSPACE\ WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO COMPANY INSTRUCTIONS. THIS FILE IS PROVIDED AS AN INSTRUMENT OF SERVICE AND SHALL REMAIN THE PROPERTY OF JACOBS.




*NOTES:*

*1. REMOVE EXISTING CIRCUITS 5J AND 5K AS NEEDED TO INSTALL PROPOSED CIRCUITS. ABANDON REMAINING CIRCUITRY.*

*2. EXISTING CIRCUITS CONSIST OF (2) NO. 4 AWG, UNLESS NOTED OTHERWISE.*

*FOR LEGEND SEE SHEET P.369.*

HORIZONTAL SCALE IN FEET: 0, 25, 50, 100

# LIGHTING PLAN
## STA. 1313+50.00 TO STA. 1342+50.00

DESIGN AGENCY: Jacobs

DESIGNER


REVIEWER

PROJECT ID: 109164

SHEET: P.371 | TOTAL: 618

FRA-71-19.10

MODEL: CLP_OT1 - Sheet 2 PAPERSIZE: 66x34.0 in SAVED: 3/31/2026 TIME: 11:39:55 AM BY:DEBO, ONDOT_PDF_F-LANE_PENTEL, ONDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: ONDOT5K02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25




| POWER SERVICE DESIGNATION | TYPE OF SERVICE | CONNECTED LOAD (KVA) | SERVICE ENTRANCE CONDUCTOR - AWG | ENCLOSURE RATING (AMP) | CIRCUIT NUMBER | CIRCUIT LOAD (AMPS) | CIRCUIT FUSE (AMPS) | MAINTAINING AGENCY |
|---|---|---|---|---|---|---|---|---|
| CC-6 (EXISTING) | 480V SINGLE PHASE 2 WIRE GROUNDED NEUTRAL | 9.89 | NO. 4 | 60 | L | 20.60 | 30 | ODOT |

FOR LEGEND SEE SHEET P.369.


HORIZONTAL SCALE IN FEET
0 25 50 100

# LIGHTING PLAN
## STA. 1342+50.00 TO STA. 1371+75.00

DESIGN AGENCY
Jacobs
DESIGNER
REVIEWER
PROJECT ID
109164
SHEET P.372 TOTAL 618

FRA-71-19.10

MODEL: CU_071 - Sheet 3 PAPERSIZE: 66x34.0in SAVED: 7/31/2024 TIME: 11:33:03 AM PLOTTED: 08/07/2024 PSF: FJ-HMB_PENTBL: CMDOT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CMDOTSHEET WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DRAWINGS ARE THE PROPERTY OF JACOBS AND ARE NOT TO BE USED WITHOUT THE WRITTEN PERMISSION OF JACOBS. ©2024 Jacobs




FOR LEGEND SEE SHEET P.369.

HORIZONTAL SCALE IN FEET
0 25 50 100

# LIGHTING PLAN
## STA. 1371+75.00 TO STA. 1401+00.00

DESIGN AGENCY
Jacobs

DESIGNER


REVIEWER

PROJECT ID
109164

SHEET P.373 | TOTAL 618

FRA-71-19.10

MODEL: CLV_071 - Sheet 4 PAPERSIZE: 66x34.0 in | DATE: 7/7/2026 TIME: 12:26:04 AM PLTDRV: DWG2PC.PSF | LAYER: PENTBL: DWG2PC.PENTBL USER: Chris.Lawrence1@jacobs.com WORKSPACE: DWG2TEXT2 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. THIS DRAWING AND ANY INFORMATION CONTAINED HEREIN IS THE PROPRIETARY PROPERTY OF JACOBS AND SHALL NOT BE REPRODUCED IN WHOLE OR IN PART.




HORIZONTAL SCALE IN FEET
0 25 50 100

# LIGHTING PLAN
## STA. 1401+00.00 TO STA. 1430+25.00

DESIGN AGENCY
Jacobs

DESIGNER


REVIEWER

PROJECT ID
109164

SHEET P.374 TOTAL 618

FRA-71-19.10

MODEL: CLF_DT1 - Sheet: 5 PAPERSIZE: 66x34.0 in SHTS: 37/37/2265 TIME: 12:20:04 AM BY:DAVI, DAVOT, PSF, [--Unit], PENTBL: DAVOT, PenTbl: USER: Dan.Lawrence@jacobs.com WORKSPACE: DAVOT05142 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL RIGHTS RESERVED. USE PURSUANT TO BENTLEY SYSTEMS LICENSE AGREEMENT. PROHIBITED ON UNLICENSED PRODUCTS AND WEBSITES.




| POWER SERVICE DESIGNATION | TYPE OF SERVICE | CONNECTED LOAD (KVA) | SERVICE ENTRANCE CONDUCTOR - AWG | ENCLOSURE RATING (AMP) | CIRCUIT NUMBER | CIRCUIT LOAD (AMPS) | CIRCUIT FUSE (AMPS) | MAINTAINING AGENCY |
|---|---|---|---|---|---|---|---|---|
| CC-2 (EXISTING) | 480V SINGLE PHASE 3 WIRE W/ GROUNDED NEUTRAL | 21.36 | NO. 4 | 60 | A | 44.50 | 60 | ODOT |

FOR LEGEND SEE SHEET P.369.

HORIZONTAL SCALE IN FEET
0 25 50 100

LIGHTING PLAN
STA. 1430+25.00 TO END WORK

DESIGN AGENCY
Jacobs

DESIGNER


REVIEWER

PROJECT ID
109164


SHEET P.375 TOTAL 618

FRA-71-19.10

MODEL: CU_071 - Sheet 6 PAPERSIZE: 66x34.0 in | DATE: 7/7/2026 TIME: 12:20:04 AM PLOTBY: CHADO7, PSF: 1 unit, PENTBL: CHADO7_PSF.ctb USER: Chris.Lawrence1@jacobs.com WORKSPACE: CHADO7SAD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
ALL DESIGNS AS INSTRUMENTS OF SERVICE ARE AND SHALL REMAIN THE PROPERTY OF JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES. ANY REUSE WITHOUT WRITTEN VERIFICATION OR ADAPTATION BY JACOBS ENGINEERING GROUP INC. FOR THE SPECIFIC PURPOSE INTENDED WILL BE AT USER'S SOLE RISK AND WITHOUT LIABILITY OR LEGAL EXPOSURE TO JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES. USER SHALL INDEMNIFY AND HOLD HARMLESS JACOBS ENGINEERING GROUP INC. AND/OR ITS SUBSIDIARIES FROM ALL CLAIMS, DAMAGES, LOSSES AND EXPENSES ARISING OUT OF OR RESULTING FROM USER'S REUSE OF THESE DESIGNS.




PLAN




PROFILE ALONG I-71 PROFILE GRADE LINE

*NOTES:*

*1) SEE SHEET P.377 FOR ELEVATION VIEWS.*

*2) PROVIDE 0.75" PVC-COATED (SEALTIGHT) FLEXIBLE STEEL CONDUIT FROM SPLICE BOX TO UNDERPASS LIGHTING FIXTURE*

*3) ADJUST EXISTING PULL BOXES TO GRADE SO THAT THEY ARE FLUSH WITH THE PROPOSED SHARED USE PATH.*

*4) REMOVE EXISTING UNDERPASS LIGHTING.*

*FOR LEGEND SEE SHEET P.369*

# UNDERPASS LIGHTING PLAN

FRA-071-24.46 L&R: I-71 OVER MORSE ROAD

FRA-71-19.10

DESIGN AGENCY
Jacobs


DESIGNER

REVIEWER


PROJECT ID
109164

SHEET P.376 | TOTAL 618

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:20:27 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Lighting\Sheets\109164_LE001.dgn




REAR ABUTMENT RETAINING WALL ELEVATION





FORWARD ABUTMENT ELEVATION

NOTES:


1) SEE SHEET P.376 FOR UNDERPASS LIGHTING PLAN VIEW.

2) PROVIDE 0.75 PVC-COATED (SEALTIGHT) FLEXIBLE STEEL CONDUIT FROM SPLICE BOX TO UNDERPASS LIGHTING FIXTURE.

3) FOR THE REAR ABUTMENT, MOUNT UNDERPASS LIGHT IN CENTER OF WALL COPING. FOR THE FORWARD ABUTMENT, MOUNT UNDERPASS LIGHT 12" BELOW THE PROPOSED BEAM SEAT.




RISER DETAIL




FORWARD ABUTMENT DETAIL

FOR LEGEND SEE SHEET P.368.

UNDERPASS LIGHTING ABUTMENT ELEVATIONS
FRA-071-24.46 L&R: I-71 OVER MORSE ROAD

DESIGN AGENCY
Jacobs

DESIGNER


REVIEWER

PROJECT ID
109164


SHEET P.377 TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:20:40 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Lighting\Sheets\109164_LE002.dgn




PLAN




PROFILE ALONG I-71 PROFILE GRADE LINE

NOTES:

1) SEE SHEET P.379 FOR ELEVATION VIEWS.

2) INSTALL NEW LIGHT POLE FOUNDATION ON EXISTING CONDUIT AT STA. 48+46, 63' LT. DISCONNECT POLE AND BRACKET CABLES IN EX. LIGHT POLE AT STA. 48+72, 62' LT. AND PULL CONDUCTORS BACK TO PROPOSED FOUNDATION. RELOCATE EX. LIGHT POLE TO NEW FOUNDATION.

3) INSTALL NEW LIGHT POLE FOUNDATION ON EXISTING CONDUIT AT STA. 48+46, 58' RT. DISCONNECT POLE AND BRACKET CABLES IN EX. LIGHT POLE AT STA. 48+71, 58' RT. AND PULL CONDUCTORS BACK TO PROPOSED FOUNDATION. RELOCATE EX. LIGHT POLE TO NEW FOUNDATION.

4) INSTALL NEW LIGHT POLE FOUNDATION ON EXISTING CONDUIT AT STA. 51+53, 60' LT. DISCONNECT POLE AND BRACKET CABLES IN EX. LIGHT POLE AT STA. 51+26, 60' LT. AND PULL CONDUCTORS BACK TO PROPOSED FOUNDATION. RELOCATE EX. LIGHT POLE TO NEW FOUNDATION.

5) REMOVE EXISTING UNDERPASS LIGHTING.

FOR LEGEND SEE SHEET P.369

# UNDERPASS LIGHTING PLAN
FRA-071-26.46 L&R: I-71 OVER SR-161

DESIGN AGENCY
Jacobs

DESIGNER


REVIEWER

PROJECT ID
109164


SHEET P.378 | TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:21:03 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Lighting\Sheets\109164_LE003.dgn




REAR ABUTMENT RETAINING WALL ELEVATION




FORWARD ABUTMENT RETAINING WALL ELEVATION




RISER DETAIL

NOTES:

1) SEE SHEET P.378 FOR UNDERPASS LIGHTING PLAN VIEW.

2) PROVIDE 0.75 PVC-COATED (SEALTIGHT) FLEXIBLE STEEL CONDUIT FROM SPLICE BOX TO UNDERPASS LIGHTING FIXTURE.

3) MOUNT UNDERPASS LIGHT IN CENTER OF WALL COPING.

FOR LEGEND SEE SHEET P.368.

UNDERPASS LIGHTING ABUTMENT ELEVATIONS
FRA-071-26.46 L&R: I-71 OVER SR-161

DESIGN AGENCY
Jacobs

DESIGNER

REVIEWER

PROJECT ID
109164

SHEET P.379 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:21:23 AM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Lighting\Sheets\109164_LE004.dgn

| C/C CURVE | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| CURVE # | STATION | OFFSET | SIDE | REFERENCE | RADIUS | ANGLE | LENGTH | CHORD | BEGIN STATION/OFFSET | END STATION/OFFSET |
| C-1 | 1311+67.86 | 93.5' | LT. | CL CONST. I-71 | 15.0' | 90° | 23.6' | 21.2' | 1311+68, 109' LT. | 1311+82, 87' LT. |
| C-2 | 1313+97.66 | 85.0' | LT. | CL CONST. I-71 | 15.0' | 88.6° | 23.2' | 21.0' | 1313+83, 85' LT. | 1313+98, 100' LT. |
| C-3 | 1314+49.47 | 175.0' | LT. | CL CONST. I-71 | 75.0' | 33.7° | 44.1' | 43.5' | 1314+50, 100' LT. | 1314+90, 100' LT. |
| C-4 | 1314+25.60 | 69.1' | RT. | CL CONST. I-71 | 15.0' | 87.1° | 22.8' | 20.7' | 1314+10, 70' RT. | 1314+26, 84' RT. |
| C-5 | 1315+52.39 | 182.6' | RT. | CL CONST. I-71 | 100.0' | 15.6° | 52.4 | 52.3' | 1315+50, 83' RT. | 1315+82, 87' RT. |
| C-6 | 1311+28.87 | 148.5' | RT. | CL CONST. I-71 | 65.0' | 69.3° | 78.6' | 73.9' | 1310+66, 124' RT. | 1311+30, 84' RT. |
| C-7 | 1311+93.80 | 68.9' | RT. | CL CONST. I-71 | 16.3' | 90.9° | 23.8' | 21.4' | 1311+94, 84' RT. | 1312+09, 69' RT. |
| C-8 | 48+52.68 | 106.71' | RT. | MORSE RD | 50.0' | 29.5° | 25.7' | 25.4' | 48+20, 69' RT. | 48+43, 48' RT. |
| C-9 | 48+79.68 | 137.53' | LT. | MORSE RD | 65.0' | 19.4° | 22.0' | 21.9' | 48+53, 61' LT. | 48+86, 58' LT. |
| C-10 | 51+23.43 | 121.75' | RT. | MORSE RD | 65.0' | 32.9° | 37.4' | 36.8' | 51+06, 62' RT. | 51+59, 67' RT. |
| C-11 | 51+36.15 | 122.50' | LT. | MORSE RD | 65.0' | 29.7° | 33.7' | 33.3' | 51+15, 58' LT. | 51+68, 66' LT. |
| C-12 | 1308+99.63 | 146.74' | LT. | CL CONST. I-71 | 45.0' | 60.4° | 47.4' | 45.3' | 1308+68, 116' LT. | 1309+10, 103' LT. |

NOTES:
1. THE INTENT OF THIS PROJECT IS TO CAREFULLY REMOVE AND RE-INSTALL THE EXISTING RETAINING WALL. CAREFULLY REMOVE EXISTING VERSA-LOK LANDSCAPING RETAINING WALL BLOCKS WITHIN THE FOLLOWING LIMITS AND STORE IN A MANNER TO PREVENT DAMAGE TO THE SATISFACTION OF THE ENGINEER:
   A. STA. 48+20, 69' RT. (MORSE RD) TO STA. 49+14, 57' RT. (MORSE RD)
   B. STA. 50+64, 56' RT. (MORSE RD) TO STA. 51+59, 67' RT. (MORSE RD)
   C. STA. 48+53, 62' LT. (MORSE RD) TO STA. 49+29, 60' LT. (MORSE RD)
   D. STA. 50+81, 58' LT. (MORSE RD) TO STA. 51+68, 66' LT. (MORSE RD)
2. SORT EXISTING REMOVED RETAINING BLOCKS AND UTILIZE UNDAMAGED BLOCKS TO RE-ERECT LANDSCAPING RETAINING WALL. SEE DETAIL ON SHEET XXX.
3. PROVIDE 12" (MINIMUM) TOPSOIL DEPTH BETWEEN THE PROPOSED CONCRETE EDGING AND THE PROPOSED CONSTRUCTION LIMITS.
4. DO NOT DISTURB EXISTING PLANT MATERIAL LOCATED OUTSIDE OF THE CONSTRUCTION LIMITS.
5. SEE SHEET XXX FOR PLANTING AND CONCRETE EDGING DETAILS.

STA. 1319+23, 106' LT. (I-71) CUT EXISTING CONCRETE EDGING MATCH PROPOSED CONCRETE EDGING TO EXISTING. CONNECT PROPOSED 2.5" IRRIGATION PIPE TO EXISTING

STA. 1308+67, 85' LT. (I-71) BEGIN PROPOSED EDGING. CAP PROPOSED 2.5" IRRIGATION PIPE

℄ CONST. RAMP D

STA. 48+20, 69' RT. (MORSE RD) BEGIN RE-ERECTED RETAINING WALL TOP OF WALL EL. XXX.XX

STA. 48+53, 61' LT. (MORSE RD) BEGIN RE-ERECTED RETAINING WALL TOP OF WALL EL. XXX.XX

STA. 48+43, 58' RT. (MORSE RD) END RE-ERECTED RETAINING WALL TOP OF WALL EL. XXX.XX

RE-ERECTED RETAINING WALL SEE NOTE 2

AUSTRIAN PINE TREES (18)

GREEN VASE ZELKOVA (4)

EX. CONCRETE EDGING (TO REMAIN)

C-8

STA. 48+43, 58' RT

C-9

STA. 48+86, 58' LT. (MORSE RD) END RE-ERECTED RETAINING WALL TOP OF WALL EL. XXX.XX

REMOVE EX. RETAINING WALL. SEE NOTE 1

SHRUBS TBD (45)

TREES TBD (7)

AUSTRIAN PINE TREES (14)

WINTER RED WINTERBERRY HOLLY (7)

EX. CONCRETE EDGING (TO REMAIN)

C-12

C-1

C-2

C-3

PROPOSED CONCRETE EDGING SEE NOTE 5

STA. 1310+34, 114' LT. (I-71) CUT EXISTING CONCRETE EDGING MATCH PROPOSED CONCRETE EDGING TO EXISTING. CONNECT PROPOSED 2.5" IRRIGATION PIPE TO EXISTING

WINTER RED WINTERBERRY HOLLY (9)

EX. CONCRETE EDGING (TBR)

REMOVE EX. RETAINING WALL. SEE NOTE 1

SHRUBS TBD (47)

TREES TBD (12)

STA. 1311+82, 87' LT. (I-71) END PROPOSED EDGING. CAP PROPOSED 2.5" IRRIGATION PIPE

PROPOSED RETAINING WALL SEE BRIDGE PLANS

STA. 1313+83, 85' LT. (I-71) BEGIN PROPOSED EDGING. CAP PROPOSED 2.5" IRRIGATION PIPE

EX. CONCRETE EDGING (TBR)

STA. 1314+90, 113' LT. (I-71) CUT EXISTING CONCRETE EDGING MATCH PROPOSED CONCRETE EDGING TO EXISTING. CONNECT PROPOSED 2.5" IRRIGATION PIPE TO EXISTING

PROPOSED CONCRETE EDGING SEE NOTE 5

℄ CONST. RAMP E

STA. 1312+09, 69' RT. (I-71) END PROPOSED EDGING. CAP PROPOSED 2.5" IRRIGATION PIPE

STA. 1314+10, 68' RT. (I-71) BEGIN PROPOSED EDGING. CAP PROPOSED 2.5" IRRIGATION PIPE

PROPOSED CONCRETE EDGING SEE NOTE 5

STA. 1316+00, 92' RT. (I-71) CUT EXISTING CONCRETE EDGING MATCH PROPOSED CONCRETE EDGING TO EXISTING. CONNECT PROPOSED 2.5" IRRIGATION PIPE TO EXISTING

REMOVE EX. RETAINING WALL. SEE NOTE 1

EX. CONCRETE EDGING (TBR)

C-7

C-4

C-5

C-6

REMOVE EX. RETAINING WALL. SEE NOTE 1

STA. 1310+60, 140' RT. (I-71) CUT EXISTING CONCRETE EDGING MATCH PROPOSED CONCRETE EDGING TO EXISTING. CONNECT PROPOSED 2.5" IRRIGATION PIPE TO EXISTING

EX. CONCRETE EDGING (TBR)

EX. CONCRETE EDGING (TO REMAIN)

AUSTRIAN PINE TREES (16)

WINTER RED WINTERBERRY HOLLY (38)

STA. 51+14, 58' LT. (MORSE RD) BEGIN RE-ERECTED RETAINING WALL TOP OF WALL EL. XXX.XX

RE-ERECTED RETAINING WALL SEE NOTE 2

AUSTRIAN PINE TREES (13)

TREES TBD (9)

SHRUBS TBD (59)

WINTER RED WINTERBERRY HOLLY (15)

EX. CONCRETE EDGING (TO REMAIN)

C-11

C-10

STA. 51+06, 62' RT. (MORSE RD) BEGIN RE-ERECTED RETAINING WALL TOP OF WALL EL. XXX.XX

TREES TBD (20)

RE-ERECTED RETAINING WALL SEE NOTE 2

SHRUBS TBD (59)

℄ CONST. RAMP B

STA. 51+68, 66' LT. (MORSE RD) END RE-ERECTED RETAINING WALL TOP OF WALL EL. XXX.XX

℄ CONST. RAMP C

STA. 51+59, 67' RT. (MORSE RD) END RE-ERECTED RETAINING WALL TOP OF WALL EL. XXX.XX

HORIZONTAL SCALE IN FEET
0 15 30 60

LANDSCAPING PLAN - MORSE ROAD

DESIGN AGENCY
Jacobs

DESIGNER
BAP


REVISION
XXX 03/20/26

PROJECT ID
109164

SHEET P.380 TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 66x34 in | DATE: 3/31/2026 TIME: 12:23:43 AM |XYZ|XY: CHSOFT_PDF_FI.pltcfg PENTBL: CHSOFT_Pen.tbl USER: Chris.Lawrence@jacobs.com WORKSPACE: CHSOFTCLOUD WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
FILE: C:\Projects\Morse Road\Morse Roadway\Morse Roadway.dgn REFERENCES: C:\Projects\Morse Road\Morse Roadway\Morse Roadway.dgn




TOP OF ROOT BALL TO BE 2"-3" ABOVE ADJACENT FINISH GRADE

REMOVE ROPE AND BURLAP FROM TOP ⅓ OF ROOT BALL. CUT TOP ⅓ OF WIRE BASKET FROM ROOT BALL. REMOVE ALL LABELS, TAGS OR OTHER FOREIGN MATERIALS FROM LIMBS.


SHRUB PLANTING
NOT TO SCALE




TOP OF ROOT BALL TO BE 2"-3" ABOVE ADJACENT FINISH GRADE

REMOVE ROPE AND BURLAP FROM TOP ⅓ OF ROOT BALL. CUT TOP ⅓ OF WIRE BASKET FROM ROOT BALL. REMOVE ALL LABELS, TAGS OR OTHER FOREIGN MATERIALS FROM LIMBS.


TREE PLANTING
NOT TO SCALE





TOP OF ROOT BALL TO BE 2"-3" ABOVE ADJACENT FINISH GRADE

REMOVE ROPE AND BURLAP FROM TOP ⅓ OF ROOT BALL. CUT TOP ⅓ OF WIRE BASKET FROM ROOT BALL. REMOVE ALL LABELS, TAGS OR OTHER FOREIGN MATERIALS FROM LIMBS.

EVERGREEN TREE PLANTING
NOT TO SCALE





PINNING DETAIL FOR BATTERED WALL
NOT TO SCALE




GENERAL NOTES FOR CAPPING:

1. CAPS SHALL BE ADHERED TO WALL USING VERSA-LOK CONCRETE ADHESIVE.
2. CAPS MAY BE PLACED WITH A ½" TO ¾" OVERHANG ON TOP OF WALL.
3. WHEN CUTTING CAP UNIT FOR WALL END DO NOT USE A CAP SECTION LESS THAN 6" WIDE.
4. DO NOT OVERHANG CAP AT END OF COURSE MORE THAN 1".
5. INSTALL CAPS WITH TOP OF MOLD FACING UP.

CAPPING DETAIL - PROFILE
NOT TO SCALE





CONCRETE EDGING
NOT TO SCALE





RE-ERECTED LANDSCAPING BLOCK RETAINING WALL
NOT TO SCALE

THE DETAILS AND INSTALLATION SPECIFICATION FOUND ON THIS SHEET WERE PROVIDED BY THE MANUFACTURER OF VERSA-LOK


WALL MANUFACTURER: OBERFIELD'S INC. (614) 252-0955
4033 ALUM CREEK DR., OBETZ, OH. 43207
PRODUCT: VERSA-LOK WEATHERED MOSAIC RETAINING WALL SYSTEM
SIZE: 6"X12"X16"
COLOR: FLAGSTONE BLEND



SECOND COURSE





SECOND COURSE



FIRST COURSE

90 DEGREE-OUTSIDE




FIRST COURSE

OBLIQUE ANGLE-OUTSIDE

CAPPING DETAIL - PROFILE
NOT TO SCALE


LANDSCAPING NOTES

DESIGN AGENCY
Jacobs


DESIGNER CGL
REVIEWER BRP 03/25/26
PROJECT ID 109164
SHEET P.381 TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:22:04 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Landscaping\Sheets\109164_PN001.dgn




**ABUTMENT SEALING LIMITS**
*I-71 OVER 17TH AVE.*





**ABUTMENT SEALING LIMITS**
*I-71 RAMP OVER 2ND AVE.*
*I-71 MAINLINE OVER 2ND AVE.*
*I-71 OVER HIAWATHA PARK DR.*
*I-71 OVER COOKE RD.*





**ELEVATION**


**TYPICAL WINGWALL SEALING LIMITS**
*(STRAIGHT WING ABUTMENT)*





**SECTION A-A**





**TYPICAL WINGWALL SEALING LIMITS**
*(TURNBACK WALL ON U-TYPE ABUTMENT)*




**ELEVATION**




**SECTION B-B**




**SECTION C-C**

**TYPICAL PIER SEALING LIMITS**

**WINGWALL AND ABUTMENT SEALING LIMITS**
*I-71 OVER MORSE RD.*
*I-71 OVER SR 161*

**COMMON SUBSTRUCTURE SEALING LIMITS**

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:04:52 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2506467\Sheets\109164_SFN_2506467_SM001.dgn

SFN
-

DESIGN AGENCY
Jacobs


| DESIGNER | CHECKER |
|---|---|
| KPL | ADS |

REVIEWER
MJR 01/25/25


PROJECT ID
109164

| SUBSET | TOTAL |
|---|---|
| - | - |

| SHEET | TOTAL |
|---|---|
| P. 382 | 618 |




## PLAN




## PROFILE

**LEGEND:**

▨ - LIMITS OF ITEM 202 - WEARING COURSE REMOVED & ASPHALT CONCRETE OVERLAY

**NOTES:**

1. THE CONTRACTOR SHALL USE A MINIMUM 50'-0" LONG TAPER TO ACCOUNT FOR THE RAISED PROFILE ATOP THE BRIDGE DECK AND APPROACH SLABS.

## EXISTING STRUCTURE

TYPE: 3 SPAN PRESTRESSED CONCRETE, NON-COMPOSITE BOX BEAMS SUPPORTED ON REINFORCED CONCRETE SUBSTRUCTURE UNITS

SPANS: 39'-0"± -55'-0"± -44'-6"± ALONG ℄ SUBSTRUCTURE BRGS.

ROADWAY: 42'-0"± F/F CONCRETE BARRIER

LOADING: HS 20-44 AND ALTERNATE MILITARY LOADING

WEARING SURFACE: 2½"± ASPHALT CONCRETE

SKEW: 11°35'54" ± L.F.

APPROACH SLABS: 25'-0"± LONG (AS-1-81)

ALIGNEMNT: TANGENT

CROWN: 0.0156± FT/FT

STRUCTURE FILE NUMBER: 2506467

DATE BUILT: 1995

## PROPOSED WORK

1. REMOVE AND REPLACE ASPHALT CONCRETE WEARING SURFACE AND WATERROOFING ON BRIDGE DECK AND APPROACH SLABS.
2. REPAIR CORNER OF EAST EXTERIOR PRESTRESSED CONCRETE BOX BEAM (B21-48) AT FORWARD (NORTH) ABUTMENT.
3. C&MS 519 PATCHING AND SEALING EXPOSED CONCRETE SURFACES WITH EPOXY-URETHANE.

# SITE PLAN
# BRIDGE NO. FRA-00071-18.750 B
# I-71 RAMP OVER 2ND AVE.

SFN 2506467

DESIGN AGENCY

Jacobs

| DESIGNER | CHECKER |
|---|---|
| KPL | ADS |

REVIEWER MJR 01/25/25

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 1 | 3 |

| SHEET | TOTAL |
|---|---|
| P. 383 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:06:49 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2506467\Sheets\109164_SFN2506467_SP001.dgn
Asad.Nawaz@jacobs.com
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2506467\Sheets\109164_SFN2506467_SP001.dgn

**STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS**

REFER TO THE FOLLOWING STANDARD BRIDGE DRAWING(S):

N/A

AND TO THE FOLLOWING SUPPLEMENTAL SPECIFICATIONS:

N/A

**DESIGN SPECIFICATIONS**

THIS STRUCTURE CONFORMS TO THE 9th EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020 AND THE ODOT BRIDGE DESIGN MANUAL (BDM), 2020, DATED JULY, 2025.

**EXISTING STRUCTURE VERIFICATION**

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO C&MS SECTIONS 102.05 AND 105.02. BASE CONTRACT BID PRICES UPON RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURE. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS THAT HAVE BEEN VERIFIED IN THE FIELD.

**EXISTING STRUCTURE PLANS**

CONSTRUCTION PLANS FOR THE EXISTING BRIDE ARE ON FILE AT THE DEPARTMENT OF TRANSPORTATION (ODOT), DISTRICT 6 OFFICE, 400 E. WILLIAM STREET, DELAWARE, OHIO AND ARE AVAILABLE FOR REFERENCE.

**ITEM 516 - 2" DEEP JOINT SEALER, AS PER PLAN**

UPON COMPLETION OF THE PROPOSED ASPHALT OVERLAY, THE CONTRACTOR SHALL SAW CUT ALONG THE APPROACH SLAB AND BRIDGE LIMIT AS DETAILED IN THE PLANS, AN AREA 1" WIDE BY 3" DEEP AND FILL THIS AREA WITH HOT APPLIED JOINT SEALER PER C&MS 705.04.

**ITEM 530 - SPECIAL - STRUCTURES MISC.: PATCHING CONCRETE STRUCTURE: PRESTRESSED CONCRETE BOX BEAM REPAIR**

REPAIRS SPALLS IN PRESTRESSED CONCRETE BOX BEAMS WITH CONCRETE PATCHING PER C&MS 519 WHEN THE BEAM REINFORCING AND/OR STRANDS ARE EXPOSED.

FOLLOWING REMOVAL OF DETERIORATED CONCRETE PER C&MS 519, BUT PRIOR TO THE SURFACE CLEANING SPECIFIED IN C&MS 519.04 AND WITHIN 24 HOURS OF PLACING PATCHING MATERIAL, BLAST CLEAN ALL SURFACES TO BE PATCHED INCLUDING EXPOSED REINFORCING STEEL. ACCEPTABLE METHODS INCLUDE HIGH PRESSURE WATER BLASTING WITH OR WITHOUT ABRASIVES IN THE WATER, ABRASIVE BLASTING WITH CONTAINMENT OR VACUUM ABRASIVE BLASTING.

CONFINE THE CONCRETE PATCH WITH A FIBER REINFORCED POLYMER (FRP) WRAP. SEAL ALL REPAIRS AREAS WITH AN EPOXY-URETHANE SEALER PER C&MS 512.03. THE COLOR OF THE SEALER SHALL CLOSELY MATCH THE COLOR OF THE EXISTING BEAMS. THE MATERIAL SUPPLIER SHALL VERIFY THAT THE COATING IS COMPATIBLE WITH THE INSTALLED FIBER WRAP SYSTEM.

THE FOLLOWING AREA HAS BEEN OBSERVED TO REQUIRE PATCHING:

EAST FASCIA BEAM: END OF BEAM AT FORWARD (NORTH) ABUTMENT - 4 S.F.

MEASUREMENT & PAYMENT: ALL LABOR, MATERIALS, EQUIPMENT, TOOLS AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE BID FOR ITEM 530 - SPECIAL MISC.: PATCHING CONCRETE STRUCTURE: PRESTRESSED CONCRETE BOX BEAM REPAIR.

**ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN**


ALL PROVISIONS OF C&MS 519 APPLY IN ADDITION TO THOSE LISTED HEREIN. THE CONTRACTOR SHALL PATCH EXPOSED CONCRETE SURFACES BASED ON VISUAL DETERIORATION ONLY. THE CONTRACTOR IS NOT REQUIRED TO SOUND THE ENTIRE EXPOSED CONCRETE SURFACE(S) TO DETERMINE WHICH AREAS REQUIRE PATCHING.

THE ENGINEER SHALL PERFORM A VISUAL INSPECTION OF THE EXPOSED CONCRETE SURFACE. AREAS OBSERVED TO BE DETERIORATED WILL BE DELINEATED BY THE ENGINEER BY SOUNDING THE CONCRETE. THE ENGINEER WILL SOUND AND MARK THE PATCHING LIMITS USING ORANGE SPRAY PAINT AND NOTIFY THE CONTRACTOR WHEN THIS ACTIVITY IS COMPLETE.


THE FOLLOWING QUANTITY HAS BEEN ESTIMATED BASED UPON THE OBSERVED CONDITION USING AVAILABLE IMAGERY, A 2023 INSPECTION BY THE ENGINEER AND AVAILABLE INSPECTION RECORDS.

ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN: 10 SF

THE DEPARTMENT WILL MEASURE THE QUANTITY OF REPAIRS ON A SQUARE-FOOT BASIS. THE DEPARTMENT WILL PAY FOR THE ACCEPTED QUANTITIES AT THE CONTRACT PRICE FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN. ALL LABOR, MATERIALS, EQUIPMENT, TOOLS AND INCIDENTALS NECESSARY TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN.




**TYPICAL SECTION**
(WEARING COURSE REMOVAL)




**TYPICAL SECTION**
(PROP. WEARING COURSE)

**LEGEND:**

1. ITEM 202 - WEARING COURSE REMOVED (ASPHALT CONCRETE, AVG. THICKNESS = 2½"±)
2. EX. WATERPROOFING (TO BE REMOVED) (INCLUDE W/ ITEM 202 - WEARING COURSE REMOVED FOR PAYMENT)
3. ITEM 512 - TYPE 3 WATERPROOFING
4. ITEM 407 - NON-TRACKING TACK COAT
5. ITEM 441 - 3" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG70-22M (TWO EQUAL 1½" LIFTS)

**ABBREVIATION LEGEND**

APPR. (APP.) - APPROACH
℄ - CENTERLINE
C.J. - CONSTRUCTION JOINT
CLR. - CLEARANCE
C&MS - CONSTRUCTION AND MATERIAL SPECIFICATIONS
CONST. - CONSTRUCTION
CY - CUBIC YARD
EA - EACH
EX. - EXISTING
FT - FEET
LS - LUMP SUM
LT. - LEFT
MAX. - MAXIMUM
M.E. - MATCH EXISTING
MIN. - MINIMUM
NB - NORTHBOUND
PROP. - PROPOSED
RT. - RIGHT
SB - SOUTHBOUND
STA. - STATION
SY - SQUARE YARD
SHDR. (SHD.) - SHOULDER
T/T - TOE-TO-TOE
TYP. - TYPICAL
W/ - WITH


| ITEM | EXTENSION | TOTAL 01/NHS/BR | UNIT | ESTIMATED QUANTITIES DESCRIPTION | ABUT. | PIERS | SUPER. | GEN. | SHEET NO. |
|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | |
| 202 | 23500 | 861 | SY | WEARING COURSE REMOVED | | | 634 | 227 | |
| | | | | | | | | | |
| 407 | 20000 | 104 | GAL | NON-TRACKING TACK COAT | | | 77 | 27 | |
| | | | | | | | | | |
| 441 | 50100 | 72 | CY | ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (448), PG70-22M | | | 53 | 19 | |
| | | | | | | | | | |
| 512 | 10100 | 357 | SY | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) | 18 | 149 | 190 | | |
| 512 | 33010 | 652 | SY | TYPE 3 WATERPROOFING | | | 652 | | 2/3 |
| | | | | | | | | | |
| 516 | 31011 | 82 | FT | 2" DEEP JOINT SEALER, AS PER PLAN | | | 82 | | 2/3 |
| | | | | | | | | | |
| 519 | 11101 | 10 | SF | PATCHING CONCRETE STRUCTURE, AS PER PLAN | 5 | 5 | | | 2/3 |
| | | | | | | | | | |
| 530 | 00600 | 4 | SF | SPECIAL - STRUCTURE MISC.: PATCHING CONCRETE STRUCTURE: PRESTRESSED CONCRETE BOX BEAM REPAIR | | | 2 | | 2/3 |

STRUCTURE GENERAL NOTES
BRIDGE NO. FRA-00071-18.750 B
I-71 RAMP OVER 2ND AVE.


SFN 2506467
DESIGN AGENCY Jacobs
DESIGNER KPL | CHECKER ADS
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 2 | TOTAL 3
SHEET P. 384 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:07:14 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2506467\Sheets\109164_SFN_2506467_SN001.dgn





***EXISTING TRANSVERSE SECTION***




***CONSTRUCTION***

*(REFER TO MOT PLANS FOR WEEKEND CLOSURE AND DETOUR)*




***FINAL CONDITION***

***LEGEND:***

- *LIMITS OF ITEM 202 - WEARING COURSE REMOVED & ASPHALT CONCRETE OVERLAY.*

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 2/3.*
2. *FOR NOTES AND TYPICAL WEARING COURSE SECTIONS, SEE SHEET 2/3.*
3. *PORTABLE BARRIER INCLUDED WITH ROADWAY QUANTITIES AND CARRIED TO THE GENERAL SUMMARY FOR PAYMENT.*

# STAGE CONSTRUCTION DETAILS
# BRIDGE NO. FRA-00071-18.750 B
# I-71 RAMP OVER 2ND AVE.


| | |
|---|---|
| SFN | 2506467 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | KPL |
| CHECKER | ADS |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 3 |
| TOTAL | 3 |
| SHEET | P. 385 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:07:26 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2506467\Sheets\109164_SFN_2506467_SC001.dgn




**PLAN**




**PROFILE ALONG ℄ CONST. I-71**

***LEGEND:***

- *LIMITS OF ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE (SDC) OVERLAY USING HYDRODEMOLITION, AS PER PLAN (1¾" THICK)*
- *PHASE 5A (STEP 1) 38'-5" FROM ℄ CONST. I-71 TO PHASE C.J.*
- *PHASE 5A (STEP 2) 28'-10½"± FROM PHASE C.J. TO TOE OF PARAPET*
- *PHASE 5B (STEP 1) 39'-6" FROM ℄ CONST. I-71 PHASE C.J.*
- *PHASE 5B (STEP 2) 28'-6"± FROM PHASE C.J. TO TOE OF PARAPET*

*M.E. - MATCH EXISTING (SHOWN IN ELEVATION)*

*A - PHASE C.J., I-71 NB @ BEGIN REAR APPROACH SLAB ℄ CONST. I-71 STA. 1007+73.97, 38.42'' RT.*
*B - PHASE C.J., I-71 NB @ END FWD. APPROACH SLAB ℄ CONST. I-71 STA. 1009+64.07, 38.42'' RT.*
*C - PHASE C.J., I-71 SB @ BEGIN REAR APPROACH SLAB ℄ CONST. I-71 STA. 1007+90.04, 39.50' LT.*
*D - PHASE C.J., I-71 SB @ END FWD. APPROACH SLAB ℄ CONST. I-71 STA. 1009+80.07, 39.50' LT.*

***NOTES:***

1. *FOR DESIGN TRAFFIC, SEE ROADWAY SHEETS.*

*EXISTING STRUCTURE*

*TYPE:* THREE SPAN CONTINUOUS REINFORCED CONCRETE SLAB BRIDGE SUPPORTED ON REINFORCED CONCRETE SUBSTRUCTURE

*SPANS:* 44'-1½"± - 55'-0"± - 38'-7½"± C/C SPANS

*ROADWAY:* 66'-3"± T/T PARAPETS (SOUTHBOUND)
65'-5"± T/T PARAPETS (NORTHBOUND)

*LOADING:* CF 2000 (57)

*SKEW:* 11°36'38"± L.F.

*WEARING SURFACE:* 1¼"± LATEX MODIFIED CONCRETE OVERLAY

*APPROACH SLABS:* 25' LONG (AS-1-81)

*ALIGNMENT:* TANGENT

*CROWN:* 0.016± FT/FT

*STRUCTURE FILE NUMBER:* 2507838

*DATE BUILT:* 1961 (1990 1ST GEN OVERLAY, 2010 REHAB)

*DISPOSITION:* BRIDGE PRESERVATION (SEE PROPOSED WORK BELOW)

*PROPOSED STRUCTURE*

*PROPOSED WORK:* REMOVE EXISTING 1¼" LMC OVERLAY VIA HYDRODEMOLITION (SS 848). PLACE NEW 1¾" NOMINAL SDC OVERLAY ON BRIDGE DECKS AND APPROACH SLABS TO BOTH NORTHBOUND AND SOUTHBOUND I-71 MAINLINE STRUCTURES OVER 2ND AVE. 519 PATCHING AND SEALING OF EXPOSED CONCRETE SURFACES.

*TYPE:* NO CHANGE

*SPANS:* NO CHANGE

*ROADWAY:* NO CHANGE

*LOADING:* NO CHANGE

*SKEW:* NO CHANGE

*WEARING SURFACE:* 1¾" SDC OVERLAY (NORTHBOUND & SOUTHBOUND) BRIDGE DECK & APPROACH SLABS

*APPROACH SLABS:* NO CHANGE

*ALIGNMENT:* NO CHANGE

*CROWN:* NO CHANGE

*DECK AREA:* 9072 SF (NORTHBOUND)
9168 SF (SOUTHBOUND)

*COORDINATES:* LATITUDE N39°58'52.96"
LONGITUDE W82°59'3.80"

# SITE PLAN
# BRIDGE NO. FRA-00071-18.750
# I-71 MAINLINE OVER 2ND AVE.

SFN 2507838

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| KPL | MAN |

REVIEWER MJR 01/25/25

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 1 | 4 |

| SHEET | TOTAL |
|---|---|
| P. 386 | 618 |

FRA-71-19.10

MODEL: CLP_I071 - Plan 1 [Sheet] PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:07:42 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507838_SP101.dgn

**STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS**

REFER TO THE FOLLOWING STANDARD BRIDGE DRAWING(S):

N/A

AND TO THE FOLLOWING SUPPLEMENTAL SPECIFICATIONS:

848 DATED 09/19/2024

**DESIGN SPECIFICATIONS**

THIS STRUCTURE CONFORMS TO THE 9th EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020 AND THE ODOT BRIDGE DESIGN MANUAL (BDM), 2020, DATED JULY, 2025.

**DESIGN DATA**

N/A

**DECK PROTECTION METHOD**

NEW 1¾" THICK SDC OVERLAY - LEFT (SB) AND RIGHT (NB) BRIDGE INCLUDING DECK/SLAB AND APRPOACH SLABS

**EXISTING STRUCTURE VERIFICATION**

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO C&MS SECTIONS 102.05 AND 105.02. BASE CONTRACT BID PRICES UPON RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURE. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS THAT HAVE BEEN VERIFIED IN THE FIELD.

**EXISTING STRUCTURE PLANS**

CONSTRUCTION PLANS FOR THE EXISTING BRIDE ARE ON FILE AT THE DEPARTMENT OF TRANSPORTATION (ODOT), DISTRICT 6 OFFICE, 400 E. WILLIAM STREET, DELAWARE, OHIO AND ARE AVAILABLE FOR REFERENCE.

**ITEM 516 - 2" DEEP JOINT SEALER, AS PER PLAN**

UPON COMPLETION OF THE PROPOSED OVERLAY, THE CONTRACTOR SHALL SAW CUT ALONG THE APPROACH SLAB AND BRIDGE LIMIT AS DETAILED IN THE PLANS (SEE SHEET 4), AN AREA 1" WIDE BY 2" DEEP AND FILL THIS AREA WITH HOT APPLIED JOINT SEALER PER C&MS 705.04.

**ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN**

ALL PROVISIONS OF C&MS 519 APPLY IN ADDITION TO THOSE LISTED HEREIN. THE CONTRACTOR SHALL PATCH EXPOSED CONCRETE SURFACES BASED ON VISUAL DETERIORATION ONLY. THE CONTRACTOR IS NOT REQUIRED TO SOUND THE ENTIRE EXPOSED CONCRETE SURFACES TO DETERMINE WHICH AREAS REQUIRE PATCHING.

THE ENGINEER SHALL PERFORM A VISUAL INSPECTION OF THE EXPOSED CONCRETE SURFACE. AREAS OBSERVED TO BE DETERIORATED WILL BE DELINEATED BY THE ENGINEER BY SOUNDING THE CONCRETE. THE ENGINEER WILL SOUND AND MARK THE PATCHING LIMITS USING ORANGE SPRAY PAINT AND NOTIFY THE CONTRACTOR WHEN THIS ACTIVITY IS COMPLETE.

THE FOLLOWING QUANTITY HAS BEEN ESTIMATED BASED UPON THE OBSERVED CONDITION USING AVAILABLE IMAGERY, A 2023 INSPECTION BY THE ENGINEER, AND AVAILABLE INSPECTION RECORDS.

ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN: 200 SF

THE DEPARTMENT WILL MEASURE THE QUANTITY OF REPAIRS ON A SQUARE-FOOT BASIS. THE DEPARTMENT WILL PAY FOR THE ACCEPTED QUANTITIES AT THE CONTRACT PRICE FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN. ALL LABOR, MATERIAL, EQUIPMENT, TOOLS AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN.

**ITEM 530 - SPECIAL - STRUCTURES MISC.: CLEANING OF DRAINAGE SYSTEMS**

THIS WORK CONSISTS OF THE REMOVAL OF DIRT, SAND, SOIL, PAPER, GLASS, CANS, AND OTHER DEBRIS FROM DRAINAGE SYSTEMS. EQUIPMENT MAY CONSISTS OF HAND TOOLS, MANUAL BROOMS, POWER BROOMS, AIR COMPRESSORS, WATER TANKS, WATER PUMPS WITH ASSOCIATED DELIVERY HARDWARE TO CLEAN, FLUSH, AND REMOVE DIRT AND DEBRIS FROM DRAINAGE SYSTEMS.

THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A BRIDGE CLEANING WORK PLAN INDICATING LOCATIONS OF ALL TEMPORARY BMP INSTALLED TO CAPTURE ANY WASH WATER USED IN THE CLEANING PROCESS. THE PLANS SHALL INCLUDE INSPECTION AND DOCUMENTATION OF BMP PERFORMANCE PRIOR TO WORK AND IMMEDIATELY FOLLOWING THE WORK. IMMEDIATE INSPECTION SHALL BE CONDUCTED EVERY 4 HOURS UNTIL WORK IS COMPLETE. CONTRACTOR SHALL FURNISH ALL MATERIAL, EQUIPMENT, LABOR, TOOLS AND INCIDENTALS NECESSARY TO PROPERLY REMOVE AND DISPOSE OF ALL DEBRIS AND OTHER FOREIGN MATERIAL BY POWER SWEEPING, SHOVELING, SCRAPING, ETC. FOLLOWED BY INSTALLING BMPS AS IDENTIFIED IN THE WORK PLAN FOR BRIDGE CLEANING, AND PRESSURE WASHING THE CURB LINES, SHOULDERS, SCUPPERS AND DOWNSPOUTS (IF PRESENT).

THE FOLLOWING ARE TO BE CLEANED:
1. CLEANING SCUPPERS AND DOWNSPOUTS (IF PRESENT):
A) USE SHOVEL, HAND SCRAPERS, AND OTHER TOOLS TO BREAK UP DEBRIS IN THE SCUPPERS TO THE MAXIMUM EXTENT PRACTICABLE. COLLECT LOOSE AND LARGE DEBRIS FROM THE SCUPPERS PRIOR TO INTRODUCING WATER.
B) PRESSURE WASH THE SCUPPERS AND DOWNSPOUTS FOR FINAL CLEANING.
C) ALL DIRT OR DEBRIS FROM THE CLEANING OPERATION SHALL BE REMOVED.

THE CONTRACTOR SHALL USE POTABLE WATER FOR CLEANING. DISCHARGING TO OR COLLECTING WATER FROM STREAMS IS PROHIBITED. PRESSURE WASHER WATER PRESSURE SHALL BE CAPABLE OF 1,500 PSI. CONTRACTOR SHALL NOT PRESSURE WASH NEAR EXISTING UTILITIES OR BRIDGE ITEMS CONTAINING OR COATED WITH ASBESTOS OR TANSITE. OPERATING PRESSURES SHALL BE SUFFICIENT TO REMOVE THE ACCUMULATED MATERIAL WITHOUT DAMAGE TO THE STRUCTURE. THE CONTRACTOR SHALL ENSURE THAT THE DRAINAGE SYSTEMS REMAIN CLEAN AND FREE OF ALL DEBRIS UNTIL ALL WORK UNDER THIS CONTRACT IS COMPLETE. ANY DAMAGE OR DETERIORATED SYSTEMS SHALL BE REPORTED TO THE ENGINEER.

PAYMENT FOR THE ABOVE DESCRIBED WORK SHALL BE MADE AT THE CONTRACT BID PRICE AS FOLLOWS:

ITEM 503 SPECIAL - STRUCTURE, MISC.: CLEANING OF DRAINAGE SYSTEMS (LS)

**ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN (T= 1¾")**

**ITEM 848 - SURFACE PREPARATION USING HYDRODEMOLITION, AS PER PLAN**

THIS ITEM SHALL CONFORM TO SUPPLEMENTAL SPECIFICATION (SS) 848 WITH THE FOLLOWING CONDITIONS AND REVISIONS:

A) THE FINAL SOUNDING MAY TAKE PLACE WITHIN 24 HOURS OF RAIN, AND THE DECK DOES NOT HAVE TO BE COMPLETELY DRY.

B) THE WET CURE TIME IS REDUCED FROM 72 HOURS TO 24 HOURS OR UNTIL A BEAM BREAK OF 600 PSI IS ACHIEVED, WHICHEVER IS GREATER.

C) A UNIFORM REMOVAL DEPTH OF ½" SHALL BE PERFORMED EXCEPT AS NOTED BELOW.

PORTIONS OF THE EXISTING SLAB THAT WERE RECONSTRUCTED IN 2010 AND THE EXISTING APPROACH SLABS DO NOT HAVE AN EXISTING RIGID OVERLAY AS SHOWN ON SHEET 4. THE CONTRACTOR SHALL REMOVE A NOMINAL DEPTH OF 1¾" OF CONCRETE USING HYDRODEMOLITION AND/OR HAND CHIPPING.

ALL LABOR, EQUIPMENT, TOOLS, AND INCIDENTALS TO REMOVE THE EXISTING CONCRETE SURFACE SHALL BE INCLUDED WITH ITEM 848 - SURFACE PREPARATION USING HYDRODEMOLITION, AS PER PLAN.

**ABBREVIATION LEGEND**

℄ - CENTERLINE
C&MS - CONSTRUCTION AND MATERIAL SPECIFICATIONS
CONST. - CONSTRUCTION
CY - CUBIC YARD
EX. - EXISTING
LS - LUMP SUM
LT. - LEFT
MAX. - MAXIMUM
M.E. - MATCH EXISTING
NB - NORTHBOUND
PROP. - PROPOSED
RT. - RIGHT
SB - SOUTHBOUND
SDC - SUPERPLASTICIZED DENSE CONCRETE OVERLAY
SF - SQUARE FOOT
SY - SQUARE YARD
SHDR. (SHD.) - SHOULDER
TYP. - TYPICAL


| ITEM | EXTENSION | LEFT BRIDGE | RIGHT BRIDGE | TOTAL 01/NHS/BR | UNIT | ESTIMATED QUANTITIES DESCRIPTION | ABUT. | PIERS | SUPER. | GEN. | SHEET NO. |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | |
| 512 | 10100 | 429 | 429 | 858 | SY | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) | 54 | 428 | 376 | | |
| | | | | | | | | | | | |
| 516 | 31011 | 133 | 131 | 264 | FT | 2" DEEP JOINT SEALER, AS PER PLAN | | | 264 | | 2/4 |
| | | | | | | | | | | | |
| 519 | 11101 | 100 | 100 | 200 | SF | PATCHING CONCRETE STRUCTURE, AS PER PLAN | 80 | 50 | 70 | | 2/4 |
| | | | | | | | | | | | |
| 530 | 00200 | - | - | LS | LS | SPECIAL - STRUCTURE MISC.: CLEANING OF DRAINAGE SYSTEMS | | | | | 2/4 |
| | | | | | | | | | | | |
| 848 | 10201 | 1392 | 1374 | 2766 | SY | SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN (T=1¾" AVG.) | | | 2034 | 732 | 2/4 |
| 848 | 20001 | 1392 | 1374 | 2766 | SY | SURFACE PREPARATION USING HYDRODEMOLITION, AS PER PLAN | | | 2034 | 732 | 2/4 |
| 848 | 30200 | 15 | 15 | 30 | CY | SUPERPLASTICIZED DENSE CONCRETE OVERLAY (VARIABLE THICKNESS), MATERIAL ONLY | | | 26 | 4 | |
| 848 | 50000 | 70 | 69 | 139 | SY | HAND CHIPPING | | | 139 | | |
| 848 | 50100 | - | - | LS | LS | TEST SLAB | | | | | |
| 848 | 50200 | 16 | 16 | 32 | CY | FULL-DEPTH REPAIR | | | 32 | | |
| 848 | 50320 | 1024 | 1011 | 2035 | SY | EXISTING CONCRETE OVERLAY REMOVED (1¼"± THICK) | | | 2035 | | |
| 848 | 50340 | 154 | 152 | 306 | SY | REMOVAL OF DEBONDED OR DETERIORATED EX. VARIABLE THICKNESS CONCRETE OVERLAY | | | 306 | | |

STRUCTURE GENERAL NOTES & ESTIMATED QUANTITIES
BRIDGE NO. FRA-00071-18.750
I-71 MAINLINE OVER 2ND AVE.


SFN 2507838
DESIGN AGENCY Jacobs
DESIGNER KPL | CHECKER MAN
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 2 | TOTAL 4
SHEET P. 387 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:07:55 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2507838\Sheets\109164_SFN_2507838_SN001.dgn





**EXISTING TRANSVERSE SECTION**





**PHASE 5B (STEP 1) CONSTRUCTION (LT. BRIDGE ONLY)**

**PHASE 5A (STEP 1) CONSTRUCTION (RIGHT BRIDGE ONLY)**




**PHASE 5B (STEP 2) CONSTRUCTION (LT. BRIDGE ONLY)**

**PHASE 5A (STEP 2 CONSTRUCTION (RIGHT BRIDGE ONLY)**




**PROPOSED TRANSVERSE SECTION**
*(REFER TO TRAFFIC CONTROL FOR PAVEMENT MARKINGS)*

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 2/4.
2. SEAL JOINTS IN ACCORDANCE WITH SUPPLEMENTAL SPECIFICATION 848. PER 848.32 THE COST OF SEALING SHALL BE CONSIDERED INCIDENTAL TO THE CONCRETE OVERLAY ITEM.
3. PORTABLE CONCRETE BARRIER INCLUDED WITH ROADWAY QUANTITIES.

STAGED CONSTRUCTION DETAILS
BRIDGE NO. FRA-00071-18.750
I-71 MAINLINE OVER 2ND AVE.

| | |
|---|---|
| SFN | 2507838 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | KPL |
| CHECKER | MAN |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 3 |
| TOTAL | 4 |
| SHEET | P. 388 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:08:07 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V400-Engineering\Structures\SFN_2507838\Sheets\109164_SFN_2507838_SC001.dgn




***TYPICAL OVERLAY***
*(NOT TO SCALE)*

***LEGEND:***

(1) - *ITEM 848 - EXISTING CONCRETE OVERLAY REMOVED (T=1¼"±)*

(2) - *ITEM 848 - SURFACE PREPARATION USING HYDRODEMOLITION (T=½")*

(3) - *ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION (T=1¾")*

(4) - *ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION (VARIABLE THICKNESS), MATERIAL ONLY*

(5) - *ITEM 848 - FULL DEPTH REPAIR*

(6) - *REMOVE 1¾" OF CONCRETE USING HYDRODEMILITION AND/OR HAND CHIPPING (INCLUDE FOR PAYMENT WITH ITEM 848 - SURFACE PREPARATION USING HYDRODEMOLITION)*

(A) - *EXISTING CONCRETE LMC OVERLAY (T=1¼"±)*

(B) - *EXISTING REINFORCED CONCRETE SLAB (T=2'-0¼"±)*

(C) - *EXISTING REINFORCED CONCRETE SLAB (T=2'-1½"±)*


(D) - *EXISTING REINFORCED CONCRETE APPROACH SLAB (AS-1-81, 25 FT LONG, T=1'-3"±)*

# OVERLAY DETAILS
# BRIDGE NO. FRA-00071-18.750
# I-71 MAINLINE OVER 2ND AVE.


| | |
|---|---|
| SFN | 2507838 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | KPL |
| CHECKER | MAN |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 4 |
| TOTAL | 4 |
| SHEET | P. 389 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:08:22 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507838\Sheets\109164_SFN_2507838_SS001.dgn




**PLAN**
*(BEAMS NOT SHOWN FOR CLARITY)*




**PROFILE DRAWN ABOUT ℄ CONST. I - 71**

## LEGEND:

- LIMITS OF ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE (SDC) OVERLAY USING HYDRODEMOLITION, AS PER PLAN (2" THICK)
- APPROXIMATE LIMITS OF EXISTING ASPHALT CONCRETE WEARING SURFACE ATOP SCARIFIED APPROACH SLAB PERFORMED UNDER UNKNOWN PROJECT/MAINTENANCE

M.E. - MATCH EXISTING

◔ - PHASE 6A (STEP 1) 28'-6" FROM ℄ CONST. I-71 TO PHASE C.J.
◔◔ - PHASE 6A (STEP 2) 26'-9"± FROM PHASE C.J. TO TOE OF PARAPET

◘ - PHASE 6B (STEP 1) 28'-6" FROM ℄ CONST. I-71 TO PHASE C.J.
◘◘ - PHASE 6B (STEP 2) 27'-2"± FROM PHASE C.J. TO TOE OF PARAPET

V.C. - NO CHANGE
15.5' REQUIRED MIN. VERTICAL CLEARANCE
15.4'± ACTUAL MIN. VERTICAL CLEARANCE (INVENTORY)

A - PHASE C.J., I-71 NB @ BEGIN REAR APPROACH SLAB
℄ CONST. I-71 STA. 1077+91.02, 28.50' RT.
B - PHASE C.J., I-71 NB @ END FWD. APPROACH SLAB
℄ CONST. I-71 STA. 1079+88.04, 28.50' RT.
C - PHASE C.J., I-71 SB @ BEGIN REAR APPROACH SLAB
℄ CONST. I-71 STA. 1077+92.98, 28.50' LT.
D - PHASE C.J., I-71 SB @ END FWD. APPROACH SLAB
℄ CONST. I-71 STA. 1079+90.98, 28.50' LT.

## NOTES:

1. SEE ROADWAY PLANS FOR DESING TRAFFIC.

## EXISTING STRUCTURE

TYPE: 3-SPAN, CONTINUOUS, ROLLED STEEL BEAM BRIDGE WITH NON-COMPOSITE, REINFORCED CONCRETE DECK SUPPORTED ON REINFORCED CONCRETE SUBSTRUCTURE

SPANS: 39'-0"± - 65'-0"± - 39'-0"± (W.R.T. ORIGINAL REFERENCE CHORD)

ROADWAY: 53'-5"± (SOUTHBOUND), 54'-3"± (NORTHBOUND) T/T PARAPETS

LOADING: CF 2,000 (57)

SKEW: 02°27'58"± L.F. W/ REFERENCE LINE

WEARING SURFACE: 1¾"± MICROSILICA CONCRETE OVERLAY

APPROACH SLABS: 25'-0"± LONG (AS-1-81)

ALIGNMENT: 0°30'00"± LT. CURVE

CROWN: 3/16" PER FOOT

STRUCTURE FILE NUMBER: 2507951

DATE BUILT: 1961

DISPOSITION: BRIDGE PRESERVATION (SEE PROPOSED WORK BELOW)

## PROPOSED STRUCTURE

PROPOSED WORK: REMOVE EXISTING 1¾"± THICK MICROSILICA CONCRETE OVERLAY VIA HYDRODEMOLITION (SS 848). PLACE NEW 2" NOMINAL SDC OVERLAY ON BRIDGE DECKS AND APPROACH SLABS TO BOTH NORTHBOUND AND SOUTHBOUND I-71 MAINLINE STRUCTURES OVER 17TH AVE. 519 PATCHING AND SEALING OF EXPOSED CONCRETE SURFACES.

TYPE: NO CHANGE

SPANS: NO CHANGE

ROADWAY: NO CHANGE

LOADING: NO CHANGE

SKEW: NO CHANGE

WEARING SURFACE: 2" SDC OVERLAY (NORTHBOUND & SOUTHBOUND) BRIDGE DECK & APPROACH SLABS

APPROACH SLABS: NO CHANGE

ALIGNMENT: NO CHANGE

CROWN: NO CHANGE

DECK AREA: 8400± SF (NORTHBOUND), 8157± SF (SOUTHBOUND)

COORDINATES: LATITUDE 40° 00' 1.90" N
LONGITUDE 82° 59' 4.26" W

# SITE PLAN
# BRIDGE NO. FRA-00071-20.080
# I-71 OVER 17TH AVE.

SFN 2507951

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| ADS | KPL |

REVIEWER MJR 01/25/25

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 1 | 4 |

| SHEET | TOTAL |
|---|---|
| P. 390 | 618 |

FRA-71-19.10

MODEL: CLR_I071 - Plan 1 [Sheet] PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:08:38 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A201000 - FRA-071-1910 I-71 HSR\30 WIP\109164\A00-Engineering\Structures\SFN_2507951\Sheets\109164_SFN_2507951_SP001.dgn

**STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS**

REFER TO THE FOLLOWING STANDARD BRIDGE DRAWING(S):

PCB-91 REVISED 07/17/2020

AND TO THE FOLLOWING SUPPLEMENTAL SPECIFICATIONS:

848 DATED 07/19/2024

**DESIGN SPECIFICATIONS**

THIS STRUCTURE CONFORMS TO THE 9th EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020 AND THE ODOT BRIDGE DESIGN MANUAL (BDM), 2020, DATED JULY, 2025.

**DECK PROTECTION METHOD**

NEW SDC OVERLAY, 2" THICKNESS
LEFT (SB) AND RIGHT (NB) BRIDGE DECKS
AND APPROACH SLABS

**DESIGN DATA**

N/A

**EXISTING STRUCTURE VERIFICATION**

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO C&MS SECTIONS 102.05 AND 105.02. BASE CONTRACT BID PRICES UPON RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURE. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS THAT HAVE BEEN VERIFIED IN THE FIELD.

**EXISTING STRUCTURE PLANS**

CONSTRUCTION PLANS FOR THE EXISTING BRIDGE ARE ON FILE AT THE DEPARTMENT OF TRANSPORTATION (ODOT), DISTRICT 6 OFFICE, 400 E. WILLIAM STREET, DELAWARE, OHIO AND ARE AVAILABLE FOR REFERENCE.

**ITEM 516 - ELASTOMERIC STRIP SEAL WITHOUT STEEL EXTRUSIONS, AS PER PLAN**

THIS ITEM SHALL INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, TOOLS AND INCIDENTALS NECESSARY TO REMOVE THE EXISTING STRIP SEAL GLAND AND REPLACE IN KIND. THIS ITEM INCLUDES ALL WORK NECESSARY TO CLEAN AND PREPARE THE EXISTING JOINT SURFACES (E.G. RETAINER CLIPS) FOR THE NEW STRIP SEAL. THE PROPOSED STRIP SEAL GLAND SHALL BE INSTALLED IN ONE CONTINUOUS STRIP FOR THE ENTIRE LENGTH OF THE BRIDGE JOINT.

**ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN**

ALL PROVISIONS OF C&MS 519 APPLY IN ADDITION TO THOSE LISTED HEREIN. THE CONTRACTOR SHALL PATCH EXPOSED CONCRETE SURFACES BASED ON VISUAL DETERIORATION ONLY. THE CONTRACTOR IS NOT REQUIRED TO SOUND THE ENTIRE EXPOSED CONCRETE SURFACES TO DETERMINE WHICH AREAS REQUIRE PATCHING.

THE ENGINEER SHALL PERFORM A VISUAL INSPECTION OF THE EXPOSED CONCRETE SURFACE. AREAS OBSERVED TO BE DETERIORATED WILL BE DELINEATED BY THE ENGINEER BY SOUNDING THE CONCRETE. THE ENGINEER WILL SOUND AND MARK THE PATCHING LIMITS USING ORANGE SPRAY PAINT AND NOTIFY THE CONTRACTOR WHEN THIS ACTIVITY IS COMPLETE.

THE FOLLOWING QUANTITY HAS BEEN ESTIMATED BASED UPON THE OBSERVED CONDITION USING AVAILABLE IMAGERY, A 2023 INSPECTION BY THE ENGINEER AND AVAILABLE INSPECTION RECORDS.

ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN: 310 SF.

THE DEPARTMENT WILL MEASURE THE QUANTITY OF REPAIRS ON A SQUARE-FOOT BASIS. THE DEPARTMENT WILL PAY FOR THE ACCEPTED QUANTITIES AT THE CONTRACT PRICE FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN. ALL LABOR, MATERIAL, EQUIPMENT, TOOLS AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN.

**ITEM 530 - SPECIAL - STRUCTURES MISC.: CLEANING OF DRAINAGE SYSTEMS**

THIS WORK SHALL CONSISTS OF THE REMOVAL OF DIRT, SAND, SOIL, PAPER, GLASS, CANS, AND OTHER DEBRIS FROM EXISTING DRAINAGE SYSTEMS TO REMAIN. EQUIPMENT MAY CONSISTS OF HAND TOOLS, MANUAL BROOMS, POWER BROOMS, AIR COMPRESSORS, WATER TANKS, WATER PUMPS WITH ASSOCIATED DELIVERY HARDWARE TO CLEAN, FLUSH, AND REMOVE DIRT AND DEBRIS FROM DRAINAGE SYSTEMS.

THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A BRIDGE CLEANING WORK PLAN INDICATING LOCATIONS OF ALL TEMPORARY BMP INSTALLED TO CAPTURE ANY WASH WATER USED IN THE CLEANING PROCESS. THE PLANS SHALL INCLUDE INSPECTION AND DOCUMENTATION OF BMP PERFORMANCE PRIOR TO WORK AND IMMEDIATELY FOLLOWING THE WORK. IMMEDIATE INSPECTION SHALL BE CONDUCTED EVERY 4 HOURS UNTIL WORK IS COMPLETE. CONTRACTOR SHALL FURNISH ALL MATERIAL, EQUIPMENT, LABOR, TOOLS AND INCIDENTALS NECESSARY TO PROPERLY REMOVE AND DISPOSE OF ALL DEBRIS AND OTHER FOREIGN MATERIAL BY POWER SWEEPING, SHOVELING, SCRAPING, ETC. FOLLOWED BY INSTALLING BMPS AS IDENTIFIED IN THE WORK PLAN FOR BRIDGE CLEANING, AND PRESSURE WASHING THE CURB LINES, SHOULDERS, SCUPPERS AND DOWNSPOUTS (IF PRESENT).

THE FOLLOWING ARE TO BE CLEANED:
1. CLEANING SCUPPERS AND DOWNSPOUTS (IF PRESENT):
A) USE SHOVEL, HAND SCRAPERS, AND OTHER TOOLS TO BREAK UP DEBRIS IN THE SCUPPERS TO THE MAXIMUM EXTENT PRACTICABLE. COLLECT LOOSE AND LARGE DEBRIS FROM THE SCUPPERS PRIOR TO INTRODUCING WATER.
B) PRESSURE WASH THE SCUPPERS AND DOWNSPOUTS FOR FINAL CLEANING.
C) ALL DIRT OR DEBRIS FROM THE CLEANING OPERATION SHALL BE REMOVED.

THE CONTRACTOR SHALL USE POTABLE WATER FOR CLEANING. DISCHARGING TO OR COLLECTING WATER FROM STREAMS IS PROHIBITED. PRESSURE WASHER WATER PRESSURE SHALL BE CAPABLE OF 1,500 PSI. CONTRACTOR SHALL NOT PRESSURE WASH NEAR EXISTING UTILITIES OR BRIDGE ITEMS CONTAINING OR COATED WITH ASBESTOS OR TANSITE. OPERATING PRESSURES SHALL BE SUFFICIENT TO REMOVE THE ACCUMULATED MATERIAL WITHOUT DAMAGE TO THE STRUCTURE. THE CONTRACTOR SHALL ENSURE THAT THE DRAINAGE SYSTEMS REMAIN CLEAN AND FREE OF ALL DEBRIS UNTIL ALL WORK UNDER THIS CONTRACT IS COMPLETE. ANY DAMAGE OR DETERIORATED SYSTEMS SHALL BE REPORTED TO THE ENGINEER.

PAYMENT FOR THE ABOVE DESCRIBED WORK SHALL BE MADE AT THE CONTRACT BID PRICE AS FOLLOWS:

ITEM 530 SPECIAL - STRUCTURE, MISC.: CLEANING OF DRAINAGE SYSTEMS (LS)

**ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN (2" THICK)**

THIS ITEM SHALL CONFORM TO SUPPLEMENTAL SPECIFICATION (SS) 848 WITH THE FOLLOWING CONDITIONS AND REVISIONS:

A) THE FINAL SOUNDING MAY TAKE PLACE WITHIN 24 HOURS OF RAIN, AND THE DECK DOES NOT HAVE TO BE COMPLETELY DRY.

B) THE WET CURE TIME IS REDUCED FROM 72 HOURS TO 24 HOURS OR UNTIL A BEAM BREAK OF 600 PSI IS ACHIEVED, WHICHEVER IS GREATER.

## ABBREVIATION LEGEND

APPR. - APPROACH
BOT. - BOTTOM
BRG. - BEARING
℄ - CENTERLINE
C.J. - CONSTRUCTION JOINT
CLR. - CLEARANCE
C&MS - CONSTRUCTION AND MATERIAL SPECIFICATIONS
CONST. - CONSTRUCTION
CY - CUBIC YARD
DIA. - DIAMETER
EA - EACH
E.F. - EACH FACE
EL. (ELEV.) - ELEVATION
EX. - EXISTING
F.F. - FAR FACE
FT - FEET
HMWM - HIGH MOLECULAR WEIGHT METHACRYLATE
HSR - HARD SHOULDER RUNNING
LB - POUND
LS - LUMP SUM
LT. - LEFT
MAX. - MAXIMUM
M.E. - MATCH EXISTING
MIN. - MINIMUM
NB - NORTHBOUND
N.F. - NEAR FACE
P.B. - PORTABLE BARRIER
P.E.J.F. - PREFORMED EXPANSION JOINT FILLER
PGL - PROFILE GRADE LINE
PROP. - PROPOSED
R.C. - REFERENCE CHORD
RT. - RIGHT
SB - SOUTHBOUND
SDC - SUPERPLASTICIZED DENSE CONCRETE
SER. - SERIES
STA. - STATION
SY - SQUARE YARD
SHD. - SHOULDER
T/T - TOE-TO-TOE
TYP. - TYPICAL
U.N.O. - UNLESS NOTED OTHERWISE
W.R.T. - WITH RESPECT TO
W/ - WITH
ϕ - DIAMETER


| ITEM | EXTENSION | LEFT BRIDGE | RIGHT BRIDGE | TOTAL 01/NHS/BR | UNIT | ESTIMATED QUANTITIES DESCRIPTION | ABUT. | PIERS | SUPER. | GEN. | SHEET NO. |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 512 | 10100 | 700 | 700 | 1400 | SY | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) | 340 | 460 | 600 | | |
| 516 | 01301 | 111 | 113 | 224 | SY | ELASTOMERIC STRIP SEAL WITHOUT STEEL EXTRUSIONS, AS PER PLAN | | | 224 | | 2/4 |
| 519 | 11101 | 155 | 155 | 310 | SF | PATCHING CONCRETE STRUCTURE, AS PER PLAN | 150 | 100 | 60 | | 2/4 |
| 530 | 00200 | - | - | LS | LS | SPECIAL - STRUCTURE MISC.: CLEANING OF DRAINAGE SYSTEMS | | | | | 2/4 |
| 848 | 10201 | 1173 | 1191 | 2364 | SY | SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN (2" THICK) | | | 1766 | 598 | 2/4 |
| 848 | 20000 | 1173 | 1191 | 2364 | SY | SURFACE PREPARATION USING HYDRODEMOLITION | | | 1766 | 598 | |
| 848 | 30200 | 25 | 19 | 44 | CY | SUPERPLASTICIZED DENSE CONCRETE OVERLAY (VARIABLE THICKNESS), MATERIAL ONLY | | | 39 | 5 | |
| 848 | 50000 | 88 | 90 | 178 | SY | HAND CHIPPING | | | 178 | | |
| 848 | 50100 | - | - | LS | LS | TEST SLAB | | | 615 | | |
| 848 | 50200 | 14 | 9 | 23 | CY | FULL-DEPTH REPAIR | | | 23 | | |
| 848 | 50320 | 876 | 890 | 1766 | SY | EXISTING CONCRETE OVERLAY REMOVED (1¾" THICK) | | | 1766 | | |
| 848 | 50340 | 263 | 201 | 464 | SY | REMOVAL OF DEBONDED OR DETERIORATED EXISTING VARIABLE THICKNESS CONCRETE OVERLAY | | | 464 | | |

STRUCTURE GENERAL NOTES
BRIDGE NO. FRA-00071-20.080
I-71 OVER 17TH AVE.


SFN 2507951
DESIGN AGENCY Jacobs
DESIGNER ADS | CHECKER KPL
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 2 | TOTAL 4
SHEET P. 391 | TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:08:52 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507951\Sheets\109164_SFN_2507951_SN001.dgn





## EXISTING SECTION





## PHASE 6A (STEP 1) CONSTRUCTION




## PHASE 6A (STEP 2) CONSTRUCTION




## PHASE 6B (STEP 1) CONSTRUCTION




## PHASE 6B (STEP 2) CONSTRUCTION

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 2/4.
2. FOR TYPICAL OVERLAY DETAILS, SEE SHEET 4/4.
3. SEAL JOINTS IN ACCORDANCE WITH SS 848. PER SS 848.32 THE COST OF SEALING SHALL BE CONSIDERED INCIDENTAL TO THE CONCRETE OVERLAY ITEM.
4. PORTABLE BARRIER INCLUDED WITH ROADWAY QUANTITIES.
5. REFER TO TRAFFIC CONTROL PLANS FOR PROPOSED PAVEMENT MARKINGS.

# STAGED CONSTRUCTION DETAILS
# BRIDGE NO. FRA-00071-20.080
# I-71 OVER 17TH AVE.

SFN 2507951
DESIGN AGENCY Jacobs
DESIGNER ADS | CHECKER KPL
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 3 | TOTAL 4
SHEET P. 392 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:09:05 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507951\Sheets\109164_SFN_2507951_SC001.dgn




***TYPICAL OVERLAY DETAIL***

***OVERLAY HISTORY:***

*1961 - DATE BUILT, 9"± THICK DECK, 2"± CLR. TO TOP MAT REINFORCING FROM TOP OF DECK.*

*1985 - 1ST OVERLAY, SCARIFY ¼"± DECK, PLACE 1¼"± LMC OVERLAY. ESTIMATED TO HAVE RAISED PROFILE GRADE 1"± FROM EX.*
*REMAINING CONCRETE DECK THICKNESS = 8¾"± EXLUDING OVERLAY MATERIAL*
*3"± CLR. TO TOP MAT REINFORCING FROM TOP OF FINISHED GRADE (TOP OF LMC OVERLAY).*

*1990 - REHABILITATION TO JOINT AND PARAPETS/BARRIERS.*

*2008 - 2ND OVERLAY, REMOVE 1¼"± LMC OVERLAY, REMOVE ½"± DECK, PLACE 1¾"± MICROSILICA CONCRETE OVERLAY*
*TO MATCH EXISTING PROFILE GRADE. REMAINING CONCRETE DECK THICKNESS = 8¼"± EXLUDING OVERLAY MATERIAL*
*3"± CLR. TO TOP MAT REINFORCING FROM TOP OF FINISHED GRADE (TOP OF MICROSILICA OVERLAY).*

***NOTES:***

*1. FOR ABBREVIATION LEGEND, SEE SHEET 2/4.*

***LEGEND:***

(1) - *ITEM 848 - EXISTING CONCRETE OVERLAY REMOVED (T=1¾"±)*

(2) - *ITEM 848 - SURFACE PREPARATION USING HYDRODEMOLITION (T=¼")*

(3) - *ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION (T=2")*

(4) - *ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION (VARIABLE THICKNESS), MATERIAL ONLY*

(5) - *ITEM 848 - FULL DEPTH REPAIR*

(6) - *REMOVE 2" OF CONCRETE USING HYDRODEMILITION AND/OR HAND CHIPPING (INCLUDE FOR PAYMENT WITH ITEM 848 - SURFACE PREPARATION USING HYDRODEMOLITION)*

(7) - *ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY*

(A) - *EXISTING MICROSILICA CONCRETE OVERLAY (T=1¾"±)*

(B) - *EXISTING REINFORCED CONCRETE DECK (T=8¼"±)*


(C) - *EXISTING REINFORCED CONCRETE APPROACH SLAB (AS-1-81, 25 FT LONG, T=1'-3"±)*

OVERLAY DETAIL
BRIDGE NO. FRA-00071-20.080
I-71 OVER 17TH AVE.


| | |
|---|---|
| SFN | 2507951 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ADS |
| CHECKER | KPL |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 4 |
| TOTAL | 4 |
| SHEET | P. 393 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:09:16 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6AA20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507951\Sheets\109164_SFN_2507951_SR002.dgn




**PLAN**




**PROFILE ALONG ℄ CONST. I-71**

***LEGEND:***

- *LIMITS OF ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN (T=2½")*

▪ *- PHASE 7A (STEPS 1 & 3) 29'-6" FROM ℄ CONST. I-71 TO PHASE C.J.*
▪▪ *- PHASE 7A (STEPS 2 & 4) 25'-11"± FROM PHASE C.J. TO TOE OF PARAPET*

◔ *- PHASE 7B (STEPS 1 & 3) 29'-0" FROM ℄ CONST. I-71 TO PHASE C.J.*
◔◔ *- PHASE 7B (STEPS 2 & 4) 26'-8"± FROM PHASE C.J. TO TOE OF PARAPET*

*V.C. - NO CHANGE*
*15.5' REQUIRED MINIMUM VERTICAL CLEARANCE*
*15.1' ACTUAL MINIMUM VERTICAL CLEARANCE (INVENTORY)*

*A - PHASE C.J., I-71 NB @ BEGIN REAR APPROACH SLAB*
*℄ CONST. I-71 STA. 1113+29.64, 29.50' RT.*

*B - PHASE C.J., I-71 NB @ END FWD. APPROACH SLAB*
*℄ CONST. I-71 STA. 1115+43.50, 29.50' RT.*

*C - PHASE C.J., I-71 SB @ BEGIN REAR APPROACH SLAB*
*℄ CONST. I-71 STA. 1113+29.89, 29.50' LT.*

*D - PHASE C.J., I-71 SB @ END FWD. APPROACH SLAB*
*℄ CONST. I-71 STA. 1115+46.21, 29.50' LT.*

***NOTES:***

1. *SEE ROADWAY PLANS FOR DESIGN TRAFFIC.*
2. *REMOVE AND REINSTALL EXISTING BRIDGE TERMINAL ASSEMBLIES (B.T.A.) AND APPROACH GUARDRAIL INCLUDING ALL HARDWARE AS NECESSARY TO CONSTRUCT PROPOSED APPROACH SLABS. ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO REMOVE, STORE AND REINSTALL BRIDGE TERMINAL ASSEMBLIES AND GUARDRAIL SHALL BE INCLUDED FOR PAYMENT UNDER ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN, LUMP SUM.*

## *EXISTING STRUCTURE*

*TYPE:* 4-SPAN CONTINUOUS REINFORCED CONCRETE SLAB SUPPORTED ON CAP AND COLUMN PIERS AND STUB ABUTMENTS

*SPANS:* 36'-0"± - 45'-0"± - 45'-0"± - 36'-0"± C/C BRGS. (W.R.T. ORIGINAL R.C.)

*ROADWAY:* 54'-3"± (LT.), 53'-5"± (RT.) TOE-TO-TOE PARAPETS

*LOADING:* CF 2,000 (57)

*SKEW:* NONE

*WEARING SURFACE:* 1¾"± MICROSILICA CONCRETE OVERLAY

*APPROACH SLABS:* AS-1-54, 25' LONG

*ALIGNMENT:* 02°30'00" LEFT CURVE

*CROWN:* SUPERELEVATION VARIES

*STRUCTURE FILE NUMBER:* 2507986

*DATE BUILT:* 1961

*DISPOSITION:* BRIDGE PRESERVATION (SEE PROPOSED WORK BELOW)

## *PROPOSED STRUCTURE*

*PROPOSED WORK:* REMOVE EXISTING 1¾"± THICK MICROSILICA OVERLAY USING HYDRODEMOLITION. PLACE 2½" THICK SDC OVERLAY ON SLAB. REPLACE APPROACH SLABS; INSTALL FULL-WIDTH APPROACH SLABS WITH TYPE A INSTALLATION. MODIFY BACKWALL TO ACCOMODATE PROPOSED APPROACH SLABS. REPLACE COMPRESSION SEAL W/ NEW COMPRESSION SEAL. PATCHING AND SEALING.

*TYPE:* NO CHANGE

*SPANS:* NO CHANGE

*ROADWAY:* NO CHANGE

*LOADING:* NO CHANGE

*SKEW:* NO CHANGE

*WEARING SURFACE:* 2½"± SDC OVERLAY

*APPROACH SLABS:* AS-1-15, 25' LONG & AS-2-15 (TYPE A INSTALLATION, A.P.P.)

*ALIGNMENT:* NO CHANGE

*CROWN:* NO CHANGE

*STRUCTURE FILE NUMBER:* NO CHANGE

*CROWN:* NO CHANGE

*DECK AREA:* 8879± SF (LT.), 8743± SF (RT.) TOE-TO-TOE PARAPETS

*COORDINATES:* LATITUDE 40°00'34.55" NORTH
LONGITUDE 82°59'14.48" WEST

# SITE PLAN
# BRIDGE NO. FRA-00071-20.750
# I-71 OVER HIAWATHA PARK DR.

SFN 2507986

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| KPL | KPL |

REVIEWER MJR 01/25/25

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 1 | 13 |

| SHEET | TOTAL |
|---|---|
| P. 394 | 618 |

FRA-71-19.10

MODEL: SITE PLAN PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:09:37 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SP001.dgn

**STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS**

REFER TO THE FOLLOWING STANDARD BRIDGE DRAWING(S):

| | | |
|---|---|---|
| AS-1-15 | REVISED | 01/20/2023 |
| AS-2-15 | REVISED | 01/20/2023 |
| PCB-91 | REVISED | 07/17/2020 |

AND TO THE FOLLOWING SUPPLEMENTAL SPECIFICATIONS:

848 DATED 07/19/2024

**DESIGN SPECIFICATIONS**

THIS STRUCTURE CONFORMS TO THE 9th EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020 AND THE ODOT BRIDGE DESIGN MANUAL (BDM), 2020, DATED JULY, 2025.

**DECK PROTECTION METHOD**

NEW SDC OVERLAY, 2½" THICKNESS

**DESIGN DATA**

N/A

**EXISTING STRUCTURE VERIFICATION**

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO C&MS SECTIONS 102.05 AND 105.02. BASE CONTRACT BID PRICES UPON RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURE. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS THAT HAVE BEEN VERIFIED IN THE FIELD.

**EXISTING STRUCTURE PLANS**

CONSTRUCTION PLANS FOR THE EXISTING BRIDE ARE ON FILE AT THE DEPARTMENT OF TRANSPORTATION (ODOT), DISTRICT 6 OFFICE, 400 E. WILLIAM STREET, DELAWARE, OHIO AND ARE AVAILABLE FOR REFERENCE.

**ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN**

THIS ITEM SHALL INCLUDE THE ELEMENTS INDICATED IN THE PLANS AND GENERAL NOTES AND THAT ARE NOT SEPARATELY LISTED FOR PAYMENT. ITEMS TO BE REMOVED INCLUDE ALL EXISTING MATERIALS BEING REPLACED BY NEW CONSTRUCTION AND MISCELLANEOUS ITEMS THAT ARE NOT SHOWN TO BE INCORPORATED INTO THE FINAL CONSTRUCTION AND ARE DIRECTED TO BE REMOVED BY THE ENGINEER. THIS ITEM SHALL INCLUDE THE REMOVAL AND EXCAVATION NECESSARY TO CONSTRUCT NEW FULL-WIDTH APPROACH SLABS WHERE FULL-WIDTH APPROACH SLABS DO NOT CURRENTLY EXIST.

THE USE OF EXPLOSIVES, HEADACHE BALLS AND/OR HOE-RAMS WILL NOT BE PERMITTED. THE METHOD OF REMOVAL AND THE WEIGHT OF HAMMER SHALL BE APPROVED BY THE ENGINEER. PERFORM ALL WORK IN A MANNER THAT WILL NOT CUT, ELONGATE OR DAMAGE THE EXISTING REINFORCING STEEL TO BE PRESERVED. CHIPPING HAMMERS SHALL NOT BE HEAVIER THAN THE NOMINAL 90-POUND CLASS. PNEUMATIC HAMMERS SHALL NOT BE PLACED IN DIRECT CONTACT WITH REINFORCING STEEL THAT IS TO BE RETAINED IN THE REBUILT STRUCTURE. SUBMIT CONSTRUCTION PLANS ACCORDING TO C&MS 501.01.

**ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN**

THIS ITEM SHALL CONSIST OF THE REMOVAL OF UNCLASSIFIED ITEMS (EXISTING FLEXIBLE PAVEMENT, PORTIONS OF THE EXISTING CONCRETE BASE SLAB (A.K.A. FOUNDATION) SUPPORTING THE MEDIAN BARRIER, AGGREGATE BASE, SUBGRADE, SOIL, TOPSOIL, DEBRIS, VEGETATION, ETC.) TO CONSTRUCT PROPOSED FULL-WIDTH APPROACH SLABS. THE CONTRACTOR SHALL REMOVE AND PROPERLY DISPOSE OF ALL MATERIAL OFF SITE.

ADDITIONALLY, THIS ITEM SHALL INCLUDE ANY WORK NECESSARY TO REMOVE, STORE AND REINSTALL EXISTING BRIDGE TERMINAL ASSEMBLIES AND GUARDRAIL AS NECESSARY TO CONSTRUCT THE PROPOSED APPROACH SLABS.

ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE INCLUDED FOR PAYMENT UNDER THE LUMP SUM CONTRACT BID PRICE FOR ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN.

**ITEM 516 - ARMORLESS PREFORMED JOINT SEAL, AS PER PLAN**

THIS WORK CONSIST OF REMOVING THE EXISTING COMPRESSION SEAL, AND INSTALLATION OF THE PROPOSED ARMORLESS PREFORMED JOINT SEAL IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS AND UNDER THE SUPERVISION OF THE MANUFACTURER'S DESIGNATED REPRESENTATIVE. INSTALL THE ARMORLESS PREFORMED JOINT SEAL TOE TO TOE OF EXISTING PARAPETS WITH UPTURNS INTO THE PARAPETS.

INSTALL THE JOINT IN ONE CONTINUOUS PIECE.

JOINT FACES: EX. STEEL ARMORING/EX. STEEL ARMORING
TOTAL DESIGN MOVEMENT: 1"
OPENING @ 60°F: 2"±

SELECT THE ARMORLESS PREFORMED JOINT SEAL FROM ONE OF THE MANUFACTURERS LISTED BELOW:

R.J. WATSON, INC.
11035 WALDEN AVENUE
ALDEN, NY 14004-9616
PHONE: (716) 901-7020
FAX: (716) 901-7015
-SILICOFLEX SF 225

WATSON BOWMAN ACME CORP.
95 PINEVIEW DRIVE
AMHERST, NY 14228-2121
PHONE: (716) 691-7566
FAX: (716) 691-9239
-JENEE W SERIES, 25W

D.S. BROWN COMPANY
300 EAST CHERRY STREET
NORTH BALTIMORE, OH 45872-1227
PHONE: (419) 257-3561
FAX: (419) 257-2200
- V-300

THE SEAL, ADHESIVE, AND SILICONE SEALANT ARE AN INTEGRAL JOINT SYSTEM THAT SHALL BE DESIGNED AND SUPPLIED BY THE SAME MANUFACTURER.


SET THE TOP OF THE JOINT SEAL ¾" BELOW THE ROADWAY SURFACE. IF EXISTING RETAINER BARS AND/OR JOINT SUPPORT BOLTS ARE PRESENT. THEN THE CONTRACTOR SHALL REMOVE EXISTING RETAINERS AND BOLTS THAT INTERFERE WITH THE INSTALLATION OF THE PROPOSED JOINT SEAL BY GRINDING SMOOTH.

THE CONTRACTOR SHALL SUBMIT THE JOINT SEAL INSTALLATION PROCEDURES TO THE ENGINEER AT LEAST SEVEN (7) CALENDAR DAYS BEFORE CONSTRUCTION BEGINS. THE DEPARTMENT'S ACCEPTANCE IS NOT REQUIRED.


THE DEPARTMENT WILL MEASURE THE ARMORLESS PREFORMED JOINT SEAL BY THE NUMBER OF FEET HORIZONTALLY ALONG THE JOINT CENTERLINE.

THE DEPARTMENT WILL INCLUDE THE COST OF ALL MATERIALS, LABOR, EQUIPMENT, SURFACE PREPARATION, TOOLS, THE MANUFACTURER'S REPRESENTATIVE, AND INCIDENTALS NEEDED TO COMPLETE THE WORK DESCRIBED ABOVE IN THE CONTRACT PRICE BID PER FOOT FOR ITEM 516 - ARMORLESS PREFORMED JOINT SEAL, AS PER PLAN.

**ITEM 516 - ARMORLESS PREFORMED JOINT SEAL, AS PER PLAN - CONTINUED**




***EXPANSION JOINT DETAIL***




***PARAPET SECTION***

**ITEM 516 - 2" DEEP JOINT SEALER, AS PER PLAN**

UPON COMPLETION OF THE PROPOSED APPROACH SLAB, THE CONTRACTOR SHALL SAW CUT ALONG THE APPROACH SLAB AND BRIDGE LIMIT AS DETAILED IN THE PLANS, AN AREA 1" WIDE BY 2" DEEP AND FILL THIS AREA WITH HOT APPLIED JOINT SEALER PER C&MS 705.04.

**ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN**

ALL PROVISIONS OF C&MS 519 APPLY IN ADDITION TO THOSE LISTED HEREIN. THE CONTRACTOR SHALL EXPOSED CONCRETE SURFACES BASED ON VISUAL DETERIORATION ONLY. THE CONTRACTOR IS NOT REQUIRED TO SOUND THE ENTIRE EXPOSED CONCRETE SURFACES TO DETERMINE WHICH AREAS REQUIRE PATCHING.

THE ENGINEER SHALL PERFORM A VISUAL INSPECTION OF THE EXPOSED CONCRETE SURFACE. AREAS OBSERVED TO BE DETERIORATED WILL BE DELINEATED BY THE ENGINEER BY SOUNDING THE CONCRETE. THE ENGINEER WILL SOUND AND MARK THE PATCHING LIMITS USING ORANGE SPRAY PAINT AND NOTIFY THE CONTRACTOR WHEN THIS ACTIVITY IS COMPLETE.

THE FOLLOWING QUANTITY HAS BEEN ESTIMATED BASED UPON THE OBSERVED CONDITION USING AVAILABLE IMAGERY, A 2023 INSPECTION BY THE ENGINEER AND AVAILABLE INSPECTION RECORDS.

ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN: XXX SF.

THE DEPARTMENT WILL MEASURE THE QUANTITY OF REPAIRS ON A SQUARE-FOOT BASIS. THE DEPARTMENT WILL PAY FOR THE ACCEPTED QUANTITIES AT THE CONTRACT PRICE FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN. ALL LABOR, MATERIAL, EQUIPMENT, TOOLS AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN.

**ITEM 526 - REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=15")**

**ITEM 526 - TYPE A INSTALLATION, AS PER PLAN**

PROVISIONS OF C&MS 511 & 526 APPLY IN ADDITION TO THE CONDITIONS AND/OR REVISIONS HEREIN.

TO CONFORM TO THE PERMITTED WEEKEND CLOSURE WINDOW(S) TO PERFORM THE WORK; USE CONCRETE WITH AN ACCELERATING ADMIXTURE SUCH AS SIKA RAPID-1 OR ANY APPROVED EQUIVALENT TO ACHIEVE 3,000 PSI COMPRESSIVE STRENGTH IN 6 HOURS FOR THE TYPE A INSTALLATION AND 12 HOURS FOR THE REINFORCED CONCRETE APPROACH SLAB. USE A NON-CHLORIDE ACCELERATING ADMIXTURE AND PROVIDE DOCUMENTATION THAT THE MIX WILL PROVIDE THE STRENGTH IN THE SPECIFIED TIME PER SUPPLEMENT 1126.

TRAFFIC WILL NOT BE PERMITTED ON THE FINISHED CONCRETE SURFACE UNTIL COMPLETION OF A 12 HOUR MINIMUM WET CURE AND AFTER TWO TEST BEAMS HAVE ATTAINED AN AVERAGE MODULUS OF RUPTURE OF 400 PSI.

ADDITIONALLY, A POLYMER MODIFIED EXPANSION JOINT AS DETAILED IN ODOT STANDARD CONSTRUCTION DRAWING AS-2-15 IS NOT REQUIRED.

**ITEM 530 - SPECIAL - STRUCTURES MISC.: CLEANING OF DRAINAGE SYSTEMS**

THIS WORK SHALL CONSISTS OF THE REMOVAL OF DIRT, SAND, SOIL, PAPER, GLASS, CANS, AND OTHER DEBRIS FROM DRAINAGE SYSTEMS. EQUIPMENT MAY CONSISTS OF HAND TOOLS, MANUAL BROOMS, POWER BROOMS, AIR COMPRESSORS, WATER TANKS, WATER PUMPS WITH ASSOCIATED DELIVERY HARDWARE TO CLEAN, FLUSH, AND REMOVE DIRT AND DEBRIS FROM DRAINAGE SYSTEMS.

THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A BRIDGE CLEANING WORK PLAN INDICATING LOCATIONS OF ALL TEMPORARY BMP INSTALLED TO CAPTURE ANY WASH WATER USED IN THE CLEANING PROCESS. THE PLANS SHALL INCLUDE INSPECTION AND DOCUMENTATION OF BMP PERFORMANCE PRIOR TO WORK AND IMMEDIATELY FOLLOWING THE WORK. IMMEDIATE INSPECTION SHALL BE CONDUCTED EVERY 4 HOURS UNTIL WORK IS COMPLETE. CONTRACTOR SHALL FURNISH ALL MATERIAL, EQUIPMENT, LABOR, TOOLS AND INCIDENTALS NECESSARY TO PROPERLY REMOVE AND DISPOSE OF ALL DEBRIS AND OTHER FOREIGN MATERIAL BY POWER SWEEPING, SHOVELING, SCRAPING, ETC. FOLLOWED BY INSTALLING BMPS AS IDENTIFIED IN THE WORK PLAN FOR BRIDGE CLEANING, AND PRESSURE WASHING THE CURB LINES, SHOULDERS, SCUPPERS AND DOWNSPOUTS (IF PRESENT).

THE FOLLOWING ARE TO BE CLEANED:
1. CLEANING SCUPPERS AND DOWNSPOUTS (IF PRESENT):
A) USE SHOVEL, HAND SCRAPERS, AND OTHER TOOLS TO BREAK UP DEBRIS IN THE SCUPPERS TO THE MAXIMUM EXTEND PRACTICABLE. COLLECT LOOSE AND LARGE DEBRIS FROM THE SCUPPERS PRIOR TO INTRODUCING WATER.
B) PRESSURE WASH THE SCUPPERS AND DOWNSPOUTS FOR FINAL CLEANING.
C) ALL DIRT OR DEBRIS FROM THE CLEANING OPERATION SHALL BE REMOVED.

THE CONTRACTOR SHALL USE POTABLE WATER FOR CLEANING. DISCHARGING TO OR COLLECTING WATER FROM STREAMS IS PROHIBITED. PRESSURE WASHER WATER PRESSURE SHALL BE CAPABLE OF 1,500 PSI. CONTRACTOR SHALL NOT PRESSURE WASH NEAR EXISTING UTILITIES OR BRIDGE ITEMS CONTAINING OR COATED WITH ASBESTOS OR TANSITE. OPERATING PRESSURES SHALL BE SUFFICIENT TO REMOVE THE ACCUMULATED MATERIAL WITHOUT DAMAGE TO THE STRUCTURE. THE CONTRACTOR SHALL ENSURE THAT THE DRAINAGE SYSTEMS REMAIN CLEAN AND FREE OF ALL DEBRIS UNTIL ALL WORK UNDER THIS CONTRACT IS COMPLETE. ANY DAMAGE OR DETERIORATED SYSTEMS SHALL BE REPORTED TO THE ENGINEER.

PAYMENT FOR THE ABOVE DESCRIBED WORK SHALL BE MADE AT THE CONTRACT BID PRICE AS FOLLOWS:

ITEM 530 SPECIAL - STRUCTURE, MISC.: CLEANING OF DRAINAGE SYSTEMS (LS)

**ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN (2½" THICK)**

THIS ITEM SHALL CONFORM TO SUPPLEMENTAL SPECIFICATION (SS) 848 WITH THE FOLLOWING CONDITIONS AND REVISIONS:

A) THE FINAL SOUNDING MAY TAKE PLACE WITHIN 24 HOURS OF RAIN, AND THE DECK DOES NOT HAVE TO BE COMPLETELY DRY.

B) THE WET CURE TIME IS REDUCED FROM 72 HOURS TO 24 HOURS OR UNTIL A BEAM BREAK OF 600 PSI IS ACHIEVED, WHICHEVER IS GREATER.

STRUCTURE GENERAL NOTES
BRIDGE NO. FRA-00071-20.750
I-71 OVER HIAWATHA PARK DR.

| | |
|---|---|
| SFN | 2507986 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ADS |
| CHECKER | KPL |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 2 |
| TOTAL | 13 |
| SHEET | P. 395 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:09:49 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SN001.dgn

| ITEM | EXTENSION | LEFT BRIDGE | RIGHT BRIDGE | TOTAL 01/NHS/BR | UNIT | ESTIMATED QUANTITIES DESCRIPTION | ABUT. | PIERS | SUPER. | GEN. | SHEET NO. |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | |
| 202 | 11203 | - | - | LS | LS | PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN | | | | | 2/13 |
| 202 | 22900 | 200 | 200 | 400 | SY | APPROACH SLAB REMOVED | | | | 400 | |
| | | | | | | | | | | | |
| 503 | 21301 | - | - | LS | LS | UNCLASSIFIED EXCAVATION, AS PER PLAN | | | | | 2/13 |
| | | | | | | | | | | | |
| 512 | 10100 | 709 | 695 | 1404 | SY | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) | 120 | 595 | 689 | | |
| | | | | | | | | | | | |
| 516 | 10011 | 113 | 111 | 224 | FT | ARMORLESS PREFORMED JOINT SEAL, AS PER PLAN | | | 224 | | 2/13 |
| 516 | 13200 | 150 | 150 | 300 | SF | ½" PREFORMED EXPANSION JOINT FILLER | | | 300 | | |
| 516 | 13600 | 374 | 374 | 748 | SF | 1" PREFORMED EXPANSION JOINT FILLER | | | 748 | | |
| 516 | 31001 | 109 | 107 | 216 | FT | 2" DEEP JOINT SEALER, AS PER PLAN | | | 216 | | 2/13 |
| | | | | | | | | | | | |
| 519 | 11101 | 228 | 183 | 411 | SF | PATCHING CONCRETE STRUCTURE, AS PER PLAN | 175 | 186 | 50 | | 2/13 |
| | | | | | | | | | | | |
| 526 | 25010 | 298 | 298 | 596 | SY | REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T = 15") | | | | 596 | 2/13 |
| 526 | 90011 | 107 | 108 | 215 | FT | TYPE A INSTALLATION, AS PER PLAN | | | | 215 | 2/13 |
| | | | | | | | | | | | |
| 530 | 00200 | - | - | LS | LS | SPECIAL - STRUCTURE MISC.: CLEANING OF DRAINAGE SYSTEMS | | | | | 2/13 |
| | | | | | | | | | | | |
| 848 | 10201 | 962 | 947 | 1909 | SY | SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN (2½" THICK) | | | 1909 | | 2/13 |
| 848 | 20000 | 962 | 947 | 1909 | SY | SURFACE PREPARATION USING HYDRODEMOLITION | | | 1909 | | |
| 848 | 30200 | 145 | 143 | 288 | CY | SUPERPLASTICIZED DENSE CONCRETE OVERLAY (VARIABLE THICKNESS), MATERIAL ONLY | | | 288 | | |
| 848 | 50000 | 77 | 76 | 153 | SY | HAND CHIPPING | | | 153 | | |
| 848 | 50100 | - | - | LS | LS | TEST SLAB | | | | | |
| 848 | 50200 | 11 | 10 | 21 | CY | FULL-DEPTH REPAIR | | | 21 | | |
| 848 | 50320 | 962 | 947 | 1909 | SY | EXISTING CONCRETE OVERLAY REMOVED (1¾" THICK) | | | 1909 | | |
| 848 | 50340 | 145 | 143 | 188 | SY | REMOVAL OF DEBONDED OR DETERIORATED EXISTING VARIABLE THICKNESS CONCRETE OVERLAY | | | 188 | | |

## ABBREVIATION LEGEND


A.P.P. - AS PER PLAN
APPR. (APP.) - APPROACH
BOT. (B) - BOTTOM
BRG. - BEARING
℄ - CENTERLINE
C.J. - CONSTRUCTION JOINT
CLR. - CLEARANCE
C&MS - CONSTRUCTION AND MATERIAL SPECIFICATIONS
CONST. - CONSTRUCTION
CY - CUBIC YARD
DIA. - DIAMETER
EA - EACH
E.F. - EACH FACE
EL. (ELEV.) - ELEVATION
EX. - EXISTING
F.F. - FAR FACE
FT - FEET
HMWM - HIGH MOLECULAR WEIGHT METHACRYLATE
HSR - HARD SHOULDER RUNNING
LB - POUND
LMC - LATEX MODIFIED CONCRETE
LONG. - LONGITUDINAL
LS- LUMP SUM
LT. - LEFT
MAX. - MAXIMUM
M.E. - MATCH EXISTING
MIN. - MINIMUM
NB - NORTHBOUND
N.F. - NEAR FACE
P.B. - PORTABLE BARRIER
P.E.J.F. - PREFORMED EXPANSION JOINT FILLER
PGL - PROFILE GRADE LINE
PROP. - PROPOSED
RT. - RIGHT
SB - SOUTHBOUND
SDC - SUPERPLASTICIZED DENSE CONCRETE
SER. - SERIES
STA. - STATION
SY - SQUARE YARD
SHDR. (SHD.) - SHOULDER
(T) - TOP
T/T - TOE-TO-TOE
TYP. - TYPICAL
U.N.O. - UNLESS NOTED OTHERWISE
W/ - WITH
W.R.T. - WITH RESPECT TO
ϕ - DIAMETER

BRIDGE ESTIMATED QUANTITIES
BRIDGE NO. FRA-00071-20.750
I-71 OVER HIAWATHA PARK DR.


SFN 2507986
DESIGN AGENCY Jacobs
DESIGNER ADS | CHECKER KPL
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 3 | TOTAL 13
SHEET P. 396 | TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:10:02 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SQ001.dgn





**EXISTING TRANSVERSE SECTION**
*(SCUPPERS NOT SHOWN FOR CLARITY)*





**PHASE 7A (STEPS 1 & 3) CONSTRUCTION**
*(SCUPPERS NOT SHOWN FOR CLARITY)*




**PHASE 7A (STEPS 2 & 4) CONSTRUCTION**
*(SCUPPERS NOT SHOWN FOR CLARITY)*




**PHASE 7B (STEPS 1 & 3) CONSTRUCTION**
*(SCUPPERS NOT SHOWN FOR CLARITY)*




**PHASE 7B (STEPS 2 & 4) CONSTRUCTION**
*(SCUPPERS NOT SHOWN FOR CLARITY)*

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 3/13.
2. FOR TYPICAL OVERLAY DETAILS, SEE SHEET 10/13.
3. SEAL JOINTS IN ACCORDANCE WITH SS 848.32 THE COST OF SEALING SHALL BE CONSIDERED INCIDENTAL TO THE CONCRETE OVERLAY ITEM.
4. PORTABLE BARRIER INCLUDED WITH ROADWAY QUANTITIES.
5. REFER TO TRAFFIC CONTROL PLANS FOR PROPOSED MARKINGS.

# STAGED CONSTRUCTION DETAILS
# BRIDGE NO. FRA-00071-20.750
# I-71 OVER HIAWATHA PARK DR.


| | |
|---|---|
| SFN | 2507986 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ADS |
| CHECKER | MAN |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 4 |
| TOTAL | 13 |
| SHEET | P. 397 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:10:14 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SC001.dgn
Asad.Nawaz@jacobs.com
ctures\SFN_2507986\Sheets\109164_SFN_2507986_SC001.dgn




***PLAN - REAR ABUTMENT***
*(EX. REINFORCING AND JOINT ARMOR NOT SHOWN FOR CLARITY)*




***ELEVATION - REAR ABUTMENT***
*(EX. REINFORCING NOT SHOWN FOR CLARITY)*

***LEGEND:***

- *ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN*
- *ITEM 202 - APPROACH SLAB REMOVED*

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 3/13.*
2. *ALL REMOVAL AND EXCAVATION NECESSARY TO CONSTRUCT NEW FULL-WIDTH APPROACH SLABS WHERE FULL-WIDTH APPROACH SLABS DO NOT CURRENTLY EXISTS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM BID PRICE FOR ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN.*

# REAR ABUTMENT - REMOVAL DETAILS
# BRIDGE NO. FRA-00071-20.750
# I-71 OVER HIAWATHA PARK DR.


| | |
|---|---|
| SFN | 2507986 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ADS |
| CHECKER | KPL |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 5 |
| TOTAL | 13 |
| SHEET | P. 398 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:10:32 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SV001.dgn
d:\Asad.Nawaz@jacobs.com\Documents\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SV001.dgn




**PLAN - FWD. ABUTMENT**
*(EX. REINFORCING AND JOINT ARMOR NOT SHOWN FOR CLARITY)*




**ELEVATION - FWD. ABUTMENT**
*(EX. REINFORCING NOT SHOWN FOR CLARITY)*

**LEGEND:**

- ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN
- ITEM 202 - APPROACH SLAB REMOVED

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 3/13.
2. ALL REMOVAL AND EXCAVATION NECESSARY TO CONSTRUCT NEW FULL-WIDTH APPROACH SLABS WHERE FULL-WIDTH APPROACH SLABS DO NOT CURRENTLY EXISTS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM BID PRICE FOR ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN.

# FORWARD ABUTMENT - REMOVAL DETAILS
## BRIDGE NO. FRA-00071-20.750
## I-71 OVER HIAWATHA PARK DR.


| | |
|---|---|
| SFN | 2507986 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | KPL |
| CHECKER | ADS |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 6 |
| TOTAL | 13 |
| SHEET | P. 399 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:10:51 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2507986_SV002.dgn




A/5 A/6 SECTION




B/5 B/6 SECTION




C/5 C/6 SECTION

***LEGEND:***

- ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN
- ITEM 202 - APPROACH SLAB REMOVED
- CUT EXISTING REINFORCING BAR(S) FLUSH AT THE CUT LINE

***NOTES:***


1. FOR ABBREVIATION LEGEND, SEE SHEET 3/13.
2. ALL REMOVAL AND EXCAVATION NECESSARY TO CONSTRUCT NEW FULL-WIDTH APPROACH SLABS WHERE FULL-WIDTH APPROACH SLABS DO NOT CURRENTLY EXISTS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM BID PRICE FOR ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN.

# ABUTMENT REMOVAL SECTIONS
# BRIDGE NO. FRA-00071-20.750
# I-71 OVER HIAWATHA PARK DR.

| | |
|---|---|
| SFN | 2507986 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | QTH |
| CHECKER | KPL |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 7 |
| TOTAL | 13 |
| SHEET | P. 400 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:11:09 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SV003.dgn




**PLAN - REAR ABUTMENT**

*(EXP. JT. AND JT. ARMOR NOT SHOWN FOR CLARITY)*




**ELEVATION - REAR ABUTMENT**

**NOTES:**


1. *FOR ABBREVIATION LEGEND, SEE SHEET 3/13.*
2. *FOR PROPOSED REAR APPROACH SLAB DETAILS, SEE SHEET 11/13.*

# REAR ABUTMENT DETAILS
# BRIDGE NO. FRA-00071-20.750
# I-71 OVER HIAWATHA PARK DR.


| | |
|---|---|
| SFN | 2507986 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ADS |
| CHECKER | MAN |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 8 |
| TOTAL | 13 |
| SHEET | P. 401 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:11:33 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SR001.dgn




**PLAN - FWD. ABUTMENT**
*(EXP. JT. AND JT. ARMOR NOT SHOWN FOR CLARITY)*




**ELEVATION - FWD. ABUTMENT**

**NOTES:**


1. *FOR ABBREVIATION LEGEND, SEE SHEET 3/13.*
2. *FOR PROPOSED FORWARD APPROACH SLAB DETAILS, SEE SHEET 12/13.*


# FORWAD ABUTMENT DETAILS
# BRIDGE NO. FRA-00071-20.750
# I-71 OVER HIAWATHA PARK DR.


| | |
|---|---|
| SFN | 2507986 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | KPL |
| CHECKER | ADS |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 9 |
| TOTAL | 13 |
| SHEET | P. 402 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:11:49 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SF001.dgn




***ENLARGED JOINT DETAIL***




***TYPICAL OVERLAY DETAIL***

***NOTES:***


1. *FOR ABBREVIATION LEGEND SEE SHEET 3/13.*
2. *FURNISH AMORLESS PREFORMED JOINT SEAL IN ONE CONTINUOUS PIECE. SEE SHEET 2/13 FOR ADDITIONAL NOTES.*
3. *SEAL JOINTS IN ACCORDANCE WITH SS 848. PER 848.32 THE COST OF SEALING SHALL BE CONSIDERED INCIDENTAL TO THE CONCRETE OVERLAY ITEM.*
4. *PROPOSED APPROACH SLAB SHALL OMIT REINFORCING TYING APPROACH SLAB TO EXISTING BACKWALL. IN OTHER WORDS OMIT 'D801' BARS TYPICALLY PROVIDED PER ODOT STANDARD CONSTRUCTION DRAWING AS-1-15.*

ABUTMENT & OVERAY DETAILS
BRIDGE NO. FRA-00071-20.750
I-71 OVER HIAWATHA PARK DR.

| | |
|---|---|
| SFN | 2507986 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | QTH |
| CHECKER | KPL |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 10 |
| TOTAL | 13 |
| SHEET | P. 403 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:12:03 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SR002.dgn




**PLAN**




**ELEVATION**
(LOOKING DOWNSTATION)

| APPROACH SLAB FINAL SURFACE ELEVATIONS - RIGHT (NB) | | | |
|---|---|---|---|
| POINT ID | STATION | OFFSET | SURFACE ELEV. |
| 1 | | | |
| 2 | | | |
| 3 | TO BE COMPLETED WITH STAGE 3 | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

| APPROACH SLAB FINAL SURFACE ELEVATIONS - LEFT (SB) | | | |
|---|---|---|---|
| POINT ID | STATION | OFFSET | SURFACE ELEV. |
| 9 | | | |
| 10 | | | |
| 11 | TO BE COMPLETED WITH STAGE 3 | | |
| 12 | | | |
| 13 | | | |
| 14 | | | |

| SLEEPER SLAB - TOP OF SLEEPER SLAB ELEV. - RIGHT (NB) | | | |
|---|---|---|---|
| POINT ID | STATION | OFFSET | SURFACE ELEV. |
| 15 | | | |
| 16 | | | |
| 17 | TO BE COMPLETED WITH STAGE 3 | | |
| 18 | | | |
| 19 | | | |
| 20 | | | |

| SLEEPER SLAB - TOP OF SLEEPER SLAB ELEV. - LEFT (SB) | | | |
|---|---|---|---|
| POINT ID | STATION | OFFSET | SURFACE ELEV. |
| 21 | | | |
| 22 | | | |
| 21 | TO BE COMPLETED WITH STAGE 3 | | |
| 23 | | | |
| 24 | | | |
| 25 | | | |
| 26 | | | |

**LEGEND:**

◕ - 8" MAX. (BOT.)

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 3/13.
2. SEE ODOT SCD. DWG. AS-1-15, AS-2-15 AND BP-5.1 FOR ADDITIONAL DETAILS NOT SHOWN.
3. A POLYMER MODIFIED ASPHALT EXPANSION JOINT IS NOT REQUIRED WITH THE TYPE A INSTALLATION.
4. TRIM REINFORCING BARS AS NEEDED TO PROVIDE 2" MINIMUM CLEAR COVER.
5. PROPOSED OUTSIDE EDGE OF APPROACH SLABS SHALL FOLLOW EXISTING CURB LINE. PLACE 1/2" PREFORMED EXPANSION JOINT FILLER (P.E.J.F.) ALONG THE INTERFACE OF THE PROPOSED APPROACH SLAB AND EXISTING CURB AS SHOWN IN ODOT SCD. BP-5.1 AND SEAL WITH JOINT SEALER PER C&MS 705.04.
6. THE PROPOSED ELEVATIONS PROVIDED ARE TO BE CONSIDERED APPROXIMATE. FIELD VERIFY ALL PROPOSED ELEVATIONS AT THE LOCATIONS SHOWN IN THESE PLANS. ADJUST THE PROPOSED ELEVATIONS ACCORDINGLY TO MAINTAIN THE EXISTING CROSS SLOPE AND PROFILE IN ORDER TO MATCH UP WITH THE EXISTING ROADWAY AND THE EXISTING BRIDGE ABUTMENT. NOTIFY THE ENGINEER OF THE PROPOSED ADJUSTMENTS PRIOR TO CONSTRUCTING THE PROPOSED WORK.

# REAR APPROACH SLAB DETAILS
# BRIDGE NO. FRA-00071-20.750
# I-71 OVER HIAWATHA PARK DR.


SFN 2507986
DESIGN AGENCY Jacobs
DESIGNER ADS | CHECKER KPL
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 11 | TOTAL 13
SHEET P. 404 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:12:21 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SM001.dgn




**PLAN**




**ELEVATION**
(LOOKING UPSTATION)

***LEGEND:***

◒ - 8" MAX. (BOT.)

***NOTES;***

1. FOR ABBREVIATION LEGEND, SEE SHEET 3/13.
2. SEE ODOT SCD. DWG. AS-1-15, AS-2-15 AND BP-5.1 FOR ADDITIONAL DETAILS NOT SHOWN.
3. A POLYMER MODIFIED ASPHALT EXPANSION JOINT IS NOT REQUIRED WITH THE TYPE A INSTALLATION.
4. TRIM REINFORCING BARS AS NEEDED TO PROVIDE 2" MINIMUM CLEAR COVER.
5. PROPOSED OUTSIDE EDGE OF APPROACH SLAB SHALL FOLLOW EXISTING CURB LINE. PLACE 1/2" PREFORMED EXPANSION JOINT FILLER (P.E.J.F.) ALONG THE INTERFACE OF THE PROPOSED APPROACH SLAB AND EXISTING CURB AS SHOWN IN ODOT SCD. BP-5.1 AND SEAL WITH JOINT SEALER PER C&MS 705.04.
6. THE PROPOSED ELEVATIONS PROVIDED ARE TO BE CONSIDERED APPROXIMATE. FIELD VERIFY ALL PROPOSED ELEVATIONS AT THE LOCATIONS SHOWN IN THESE PLANS. ADJUST THE PROPOSED ELEVATIONS ACCORDINGLY TO MAINTAIN THE EXISTING CROSS SLOPE AND PROFILE IN ORDER TO MATCH UP WITH THE EXISTING ROADWAY AND THE EXISTING BRIDGE ABUTMENT. NOTIFY THE ENGINEER OF THE PROPOSED ADJUSTMENTS PRIOR TO CONSTRUCTING THE PROPOSED WORK.

| APPROACH SLAB FINAL SURFACE ELEVATIONS - RIGHT (NB) | | | |
|---|---|---|---|
| POINT ID | STATION | OFFSET | SURFACE ELEV. |
| 1 | | | |
| 2 | | | |
| 3 | TO BE COMPLETED WITH STAGE 3 | | |
| 4 | | | |
| 5 | | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |

| SLEEPER SLAB - TOP OF SLEEPER SLAB ELEV. - RIGHT (NB) | | | |
|---|---|---|---|
| POINT ID | STATION | OFFSET | SURFACE ELEV. |
| 15 | | | |
| 16 | | | |
| 17 | TO BE COMPLETED WITH STAGE 3 | | |
| 18 | | | |
| 19 | | | |
| 20 | | | |

| APPROACH SLAB FINAL SURFACE ELEVATIONS - LEFT (SB) | | | |
|---|---|---|---|
| POINT ID | STATION | OFFSET | SURFACE ELEV. |
| 9 | | | |
| 10 | | | |
| 11 | TO BE COMPLETED WITH STAGE 3 | | |
| 12 | | | |
| 13 | | | |
| 14 | | | |

| SLEEPER SLAB - TOP OF SLEEPER SLAB ELEV. - LEFT (SB) | | | |
|---|---|---|---|
| POINT ID | STATION | OFFSET | SURFACE ELEV. |
| 21 | | | |
| 22 | | | |
| 23 | TO BE COMPLETED WITH STAGE 3 | | |
| 24 | | | |
| 25 | | | |
| 26 | | | |

FORWARD APPROACH SLAB DETAILS
BRIDGE NO. FRA-00071-20.750
I-71 OVER HIAWATHA PARK DR.


SFN 2507986
DESIGN AGENCY Jacobs
DESIGNER KPL | CHECKER ADS
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 12 | TOTAL 13
SHEET P. 405 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:12:39 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SM002.dgn

| MARK | NUMBER TOTAL | LENGTH | WEIGHT | TYPE | DIMENSIONS A | B | C | D | E | R | INC |
|---|---|---|---|---|---|---|---|---|---|---|---|
| **APPROACH SLABS (FOR INFORMATION ONLY)** | | | | | | | | | | | |
| AS501■ | 180 | 27'-9" | 5,225 | STR | | | | | | | |
| AS502 | 436 | 24'-6" | 11,141 | STR | | | | | | | |
| AS503■ | 180 | 25'-3" | 4,740 | STR | | | | | | | |
| AS504■ | 180 | 27'-2" | 5,100 | STR | | | | | | | |
| AS505 | 180 | 26'-0" | 4,881 | STR | | | | | | | |
| AS1001 | 374 | 25'-11" | 41,708 | 16 | 24'-6" | | | | | | |
| SUB-TOTAL | | | 72,795 | | | | | | | | |
| **SLEEPER SLABS (FOR INFORMATION ONLY)** | | | | | | | | | | | |
| SS501 | 16 | 27'-8" | 462 | STR | | | | | | | |
| SS502 | 16 | 25'-0" | 417 | STR | | | | | | | |
| SS503 | 16 | 26'-9" | 446 | STR | | | | | | | |
| SS504 | 16 | 25'-8" | 428 | STR | | | | | | | |
| SS505■ | 16 | 7'-6" | 1,729 | STR | | | | | | | |
| SUB-TOTAL | | | 3,482 | | | | | | | | |
| GRAND TOTAL | | | 76,277 | | | | | | | | |

*APPROACH SLAB AND SLEEPER SLAB REINFORCING SHOWN INCLUDES THE NUMBER/WEIGHT OF THE LEFT AND RIGHT BRIDGES FOR BOTH THE REAR AND FORWARD APPROACH SLABS.*




TYPE-16

***LEGEND:***

■ - *REINFORCING BAR UTILIZES A MECHANICAL CONNECTOR. BAR LENGTH IS MEASURED TO THE CONSTRUCTION JOINT. EXTRA BAR LENGTH AND/OR BAR END PREPARATION MAY BE NECESSARY DEPENDING UPON THE TYPE OF MECHANICAL CONNECTOR FURNISHED.*

***NOTES:***


1. *THE BAR SIZE NUMBER IS SPECIFIED ON THE PLANS IN THE BAR MARK COLUMN. THE FIRST DIGIT WHERE THREE DIGITS ARE USED, AND THE FIRST TWO DIGITS WHERE FOUR DIGITS ARE USED, INDICATES THE BAR SIZE NUMBER. FOR EXAMPLE, AN AS501 BAR IS A NO. 5 BAR. BAR DIMENSIONS SHOWN ARE OUT TO OUT UNLESS OTHERWISE NOTED. "STD" WRITTEN IN PLACE OF A DIMENSION INDICATES A STANDARD BEND AT THE END OF THE BAR.*
2. *STRAIGHT BARS ARE INDICATED BY "STR".*
3. *ALL REINFORCING STEEL SHALL BE EPOXY COATED.*
4. *ALL REINFORCING STEEL SHALL BE GRADE 60 WITH A MINIMUM YIELD STRENGTH OF 60 KSI.*

REINFORCING STEEL LIST
BRIDGE NO. FRA-00071-20.750
I-71 OVER HIAWATHA PARK DR.

SFN 2507986
DESIGN AGENCY Jacobs
DESIGNER KPL | CHECKER ADS
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 13 | TOTAL 13
SHEET P. 406 | TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:12:52 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2507986\Sheets\109164_SFN_2507986_SL001.dgn




**PLAN**

**NOTES:**

1. SEE ROADWAY PLANS FOR DESIGN TRAFFIC.
2. REMOVE AND REINSTALL EXISTING BRIDGE TERMINAL ASSEMBLIES (B.T.A.) AND APPROACH GUARDRAIL INCLUDING ALL HARDWARE AS NECESSARY TO CONSTRUCT PROPOSED APPROACH SLABS. ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO REMOVE, STORE AND REINSTALL BRIDGE TERMINAL ASSEMBLIES AND GUARDRAIL SHALL BE INCLUDED FOR PAYMENT UNDER ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN, LUMP SUM.




**PROFILE ALONG ℄ CONST. I-71**

***LEGEND:***

- ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN (2½" THICK)
- PHASE 1B (STEPS 1 & 3) 39'-0" FROM ℄ CONST. I-71 TO PHASE C.J.
- PHASE 1B (STEPS 2 & 4) 26'-8½"± FROM PHASE C.J. TO TOE OF PARAPET
- PHASE 1A (STEPS 1 & 3) 39'-0" FROM ℄ CONST. I-71 TO PHASE C.J.
- PHASE 1A (STEPS 2 & 4) 26'-3½"± FROM PHASE C.J. TO TOE OF PARAPET

V.C. - NO CHANGE
15.00' REQUIRED MINIMUM VERTICAL CLEARANCE
15.17' ACTUAL MINIMUM VERTICAL CLEARANCE (INVENTORY)

A - PHASE C.J., I-71 NB @ BEGIN REAR APPROACH SLAB
CONST. I-71 STA. 1256+07.81, 39.00' RT.

B - PHASE C.J., I-71 NB @ END FWD. APPROACH SLAB
CONST. I-71 STA. 1258+32.85, 39.00' RT.

C - PHASE C.J., I-71 SB @ BEGIN REAR APPROACH SLAB
CONST. I-71 STA. 1256+35.62, 39.00' LT.

D - PHASE C.J., I-71 NB @ END FWD. APPROACH SLAB
CONST. I-71 STA. 1258+59.69, 39.00' LT.

## EXISTING STRUCTURE

TYPE: 4-SPAN CONTINUOUS REINFORCED CONCRETE SLAB SUPPORTED ON CAP AND COLUMN PIERS AND STUB ABUTMENTS SUPPORTED ON PILES

SPANS: 38'-0"± - 47'-6"± - 47'-6"± - 38'-0"± C/C BRGS.

ROADWAY: 53'-0"± (LT.), 53'-0"± (RT.)

LOADING: CF 2,000 (57)

SKEW: 19°00'00" (LEFT FORWARD)

WEARING SURFACE: 1¾" ± MICROSILICA CONCRETE OVERLAY

APPROACH SLABS: AS-1-54, 25' LONG

ALIGNMENT: TANGENT

CROWN: 0.0156 FT./FT.

STRUCTURE FILE NUMBER: 2508133 & 2508168

DATE BUILT: 1960

DISPOSITION: BRIDGE PRESERVATION (SEE PROPOSED WORK BELOW)

## PROPOSED STRUCTURE

PROPOSED WORK: REMOVE EXISTING 1¾"± THICK MICROSILICA CONCRETE OVERLAY USING HYDRODMEOLITION. PLACE 2½" THICK SDC OVERLAY ON SLAB. REPLACE APPRACH SLABS; INSTALL FULL-WIDTH APPROACH SLABS WITH TYPE A INSTALLATION. MODIFY BACKWALL TO ACCOMODATE PROPOSED APPROACH SLABS. C&MS 519 PATCHING AND SEALING EXPOSED CONCRETE SURFACES.

TYPE: NO CHANGE

SPANS: NO CHANGE

ROADWAY: NO CHANGE

LOADING: NO CHANGE

SKEW: NO CHANGE

WEARING SURFACE: 2½" SDC OVERLAY FOR SB & 2½" SDC OVERLAY FOR NB

APPROACH SLABS: AS-1-15, 25' LONG & AS-2-15 (TYPE A INSTALLATION, A.P.P.)

ALIGNMENT: NO CHANGE

CROWN: NO CHANGE

STRUCTURE FILE NUMBER: NO CHANGE

CROWN: NO CHANGE

DECK AREA: 8752± SF (LT.), 8802± SF (RT.)

COORDINATES: LATITUDE 40°02'46.04" NORTH
LONGITUDE 82°59'50.54" WEST

# SITE PLAN
# BRIDGE NO. FRA-00071-23.460
# I-71 OVER COOKE RD.

SFN 2508133

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| KPL | ADS |

REVIEWER MJR 01/25/25

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 1 | 14 |

| SHEET | TOTAL |
|---|---|
| P. 407 | 618 |

FRA-71-19.10

MODEL: CLP_I72 - Plan 1 [Sheet] PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:13:11 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCtx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SP001.dgn

**STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS**

REFER TO THE FOLLOWING STANDARD BRIDGE DRAWING(S):

| | | |
|---|---|---|
| AS-1-15 | REVISED | 01/20/2023 |
| AS-2-15 | REVISED | 07/21/2023 |
| PCB-91 | REVISED | 07/17/2020 |

AND TO THE FOLLOWING SUPPLEMENTAL SPECIFICATIONS:

848 DATED 07/19/2024

**DESIGN SPECIFICATIONS**

THIS STRUCTURE CONFORMS TO THE 9th EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020 AND THE ODOT BRIDGE DESIGN MANUAL (BDM), 2020, DATED JULY, 2025.

**DECK PROTECTION METHOD**

NEW SDC OVERLAY, 2½" THICKNESS

**DESIGN DATA**

N/A

**EXISTING STRUCTURE VERIFICATION**

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO C&MS SECTIONS 102.05 AND 105.02. BASE CONTRACT BID PRICES UPON RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURE. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS THAT HAVE BEEN VERIFIED IN THE FIELD.

**EXISTING STRUCTURE PLANS**

CONSTRUCTION PLANS FOR THE EXISTING BRIDE ARE ON FILE AT THE DEPARTMENT OF TRANSPORTATION (ODOT), DISTRICT 6 OFFICE, 400 E. WILLIAM STREET, DELAWARE, OHIO AND ARE AVAILABLE FOR REFERENCE.

**ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN**

THIS ITEM SHALL INCLUDE THE ELEMENTS INDICATED IN THE PLANS AND GENERAL NOTES AND THAT ARE NOT SEPARATELY LISTED FOR PAYMENT. ITEMS TO BE REMOVED INCLUDE ALL EXISTING MATERIALS BEING REPLACED BY NEW CONSTRUCTION AND MISCELLANEOUS ITEMS THAT ARE NOT SHOWN TO BE INCORPORATED INTO THE FINAL CONSTRUCTION AND ARE DIRECTED TO BE REMOVED BY THE ENGINEER. THE USE OF EXPLOSIVES, HEADACHE BALLS AND/OR HOE-RAMS WILL NOT BE PERMITTED. THE METHOD OF REMOVAL AND THE WEIGHT OF HAMMER SHALL BE APPROVED BY THE ENGINEER. PERFORM ALL WORK IN A MANNER THAT WILL NOT CUT, ELONGATE OR DAMAGE THE EXISTING REINFORCING STEEL TO BE PRESERVED. CHIPPING HAMMERS SHALL NOT BE HEAVIER THAN THE NOMINAL 90-POUND CLASS. PNEUMATIC HAMMERS SHALL NOT BE PLACED IN DIRECT CONTACT WITH REINFORCING STEEL THAT IS TO BE RETAINED IN THE REBUILT STRUCTURE. SUBMIT CONSTRUCTION PLANS ACCORDING TO C&MS 501.01.

**ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN**

THIS ITEM SHALL CONSIST OF THE REMOVAL OF UNCLASSIFIED ITEMS (EXISTING FLEXIBLE PAVEMENT, PORTIONS OF THE EXISTING CONCRETE BASE SLAB (A.K.A. FOUNDATION) SUPPORTING THE MEDIAN BARRIER, AGGREGATE BASE, SUBGRADE, SOIL, TOPSOIL, DEBRIS, VEGETATION, ETC.) TO CONSTRUCT PROPOSED FULL-WIDTH APPROACH SLABS. THE CONTRACTOR SHALL REMOVE AND PROPERLY DISPOSE OF ALL MATERIAL OFF SITE.

ADDITIONALLY, THIS ITEM SHALL INCLUDE ANY WORK NECESSARY TO REMOVE, STORE AND REINSTALL EXISTING BRIDGE TERMINAL ASSEMBLIES AND GUARDRAIL AS NECESSARY TO CONSTRUCT THE PROPOSED APPROACH SLABS.

ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE INCLUDED FOR PAYMENT UNDER THE LUMP SUM CONTRACT BID PRICE FOR ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN.

**ITEM 516 - 2" DEEP JOINT SEALER, AS PER PLAN**

UPON COMPLETION OF THE PROPOSED APPROACH SLAB, THE CONTRACTOR SHALL SAW CUT ALONG THE APPROACH SLAB AND BRIDGE LIMIT AS DETAILED IN THE PLANS, AN AREA 1" WIDE BY 2" DEEP AND FILL THIS AREA WITH HOT APPLIED JOINT SEALER PER C&MS 705.04.

ADDITIONALLY THIS ITEM INCLUDES REMOVING AND CLEANING THE EXISTING SLIDING PLATE EXPANSION JOINT TO PLACE NEW HOT APPLIED JOINT SEALER PER C&MS 705.04.

REFER TO SHEET 11/14 FOR ADDITIONAL NOTES AND DETAILS.

**ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN**

ALL PROVISIONS OF C&MS 519 APPLY IN ADDITION TO THOSE LISTED HEREIN. THE CONTRACTOR SHALL EXPOSED CONCRETE SURFACES BASED ON VISUAL DETERIORATION ONLY. THE CONTRACTOR IS NOT REQUIRED TO SOUND THE ENTIRE EXPOSED CONCRETE SURFACES TO DETERMINE WHICH AREAS REQUIRE PATCHING.

THE ENGINEER SHALL PERFORM A VISUAL INSPECTION OF THE EXPOSED CONCRETE SURFACE. AREAS OBSERVED TO BE DETERIORATED WILL BE DELINEATED BY THE ENGINEER BY SOUNDING THE CONCRETE. THE ENGINEER WILL SOUND AND MARK THE PATCHING LIMITS USING ORANGE SPRAY PAINT AND NOTIFY THE CONTRACTOR WHEN THIS ACTIVITY IS COMPLETE.

THE FOLLOWING QUANTITY HAS BEEN ESTIMATED BASED UPON THE OBSERVED CONDITION USING AVAILABLE IMAGERY, A 2023 INSPECTION BY THE ENGINEER AND AVAILABLE INSPECTION RECORDS.

ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN: XXX SF.

THE DEPARTMENT WILL MEASURE THE QUANTITY OF REPAIRS ON A SQUARE-FOOT BASIS. THE DEPARTMENT WILL PAY FOR THE ACCEPTED QUANTITIES AT THE CONTRACT PRICE FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN. ALL LABOR, MATERIAL, EQUIPMENT, TOOLS AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT PRICE FOR ITEM 519 - PATCHING CONCRETE STRUCTURE, AS PER PLAN.

**ITEM 526 - REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T=15")**

**ITEM 526 - TYPE A INSTALLATION, AS PER PLAN**

PROVISIONS OF C&MS 511 & 526 APPLY IN ADDITION TO THE CONDITIONS AND/OR REVISIONS HEREIN.

TO CONFORM TO THE PERMITTED WEEKEND CLOSURE WINDOW(S) TO PERFORM THE WORK; USE CONCRETE WITH AN ACCELERATING ADMIXTURE SUCH AS SIKA RAPID-1 OR ANY APPROVED EQUIVALENT TO ACHIEVE 3,000 PSI COMPRESSIVE STRENGTH IN 6 HOURS FOR THE TYPE A INSTALLATION AND 12 HOURS FOR THE REINFORCED CONCRETE APPROACH SLAB. USE A NON-CHLORIDE ACCELERATING ADMIXTURE AND PROVIDE DOCUMENTATION THAT THE MIX WILL PROVIDE THE STRENGTH IN THE SPECIFIED TIME PER SUPPLEMENT 1126.

TRAFFIC WILL NOT BE PERMITTED ON THE FINISHED CONCRETE SURFACE UNTIL COMPLETION OF A 12 HOUR MINIMUM WET CURE AND AFTER TWO TEST BEAMS HAVE ATTAINED AN AVERAGE MODULUS OF RUPTURE OF 400 PSI.

ADDITIONALLY, A POLYMER MODIFIED EXPANSION JOINT AS DETAILED IN ODOT STANDARD CONSTRUCTION DRAWING AS-2-15 IS NOT REQUIRED.

**ITEM 530 - SPECIAL - STRUCTURES MISC.: CLEANING OF DRAINAGE SYSTEMS**

THIS WORK SHALL CONSISTS OF THE REMOVAL OF DIRT, SAND, SOIL, PAPER, GLASS, CANS, AND OTHER DEBRIS FROM DRAINAGE SYSTEMS. EQUIPMENT MAY CONSISTS OF HAND TOOLS, MANUAL BROOMS, POWER BROOMS, AIR COMPRESSORS, WATER TANKS, WATER PUMPS WITH ASSOCIATED DELIVERY HARDWARE TO CLEAN, FLUSH, AND REMOVE DIRT AND DEBRIS FROM DRAINAGE SYSTEMS.

THE CONTRACTOR SHALL SUBMIT TO THE ENGINEER A BRIDGE CLEANING WORK PLAN INDICATING LOCATIONS OF ALL TEMPORARY BMP INSTALLED TO CAPTURE ANY WASH WATER USED IN THE CLEANING PROCESS. THE PLANS SHALL INCLUDE INSPECTION AND DOCUMENTATION OF BMP PERFORMANCE PRIOR TO WORK AND IMMEDIATELY FOLLOWING THE WORK. IMMEDIATE INSPECTION SHALL BE CONDUCTED EVERY 4 HOURS UNTIL WORK IS COMPLETE. CONTRACTOR SHALL FURNISH ALL MATERIAL, EQUIPMENT, LABOR, TOOLS AND INCIDENTALS NECESSARY TO PROPERLY REMOVE AND DISPOSE OF ALL DEBRIS AND OTHER FOREIGN MATERIAL BY POWER SWEEPING, SHOVELING, SCRAPING, ETC. FOLLOWED BY INSTALLING BMPS AS IDENTIFIED IN THE WORK PLAN FOR BRIDGE CLEANING, AND PRESSURE WASHING THE CURB LINES, SHOULDERS, SCUPPERS AND DOWNSPOUTS (IF PRESENT).

THE FOLLOWING ARE TO BE CLEANED:
1. CLEANING SCUPPERS AND DOWNSPOUTS (IF PRESENT):
A) USE SHOVEL, HAND SCRAPERS, AND OTHER TOOLS TO BREAK UP DEBRIS IN THE SCUPPERS TO THE MAXIMUM EXTEND PRACTICABLE. COLLECT LOOSE AND LARGE DEBRIS FROM THE SCUPPERS PRIOR TO INTRODUCING WATER.
B) PRESSURE WASH THE SCUPPERS AND DOWNSPOUTS FOR FINAL CLEANING.
C) ALL DIRT OR DEBRIS FROM THE CLEANING OPERATION SHALL BE REMOVED.

THE CONTRACTOR SHALL USE POTABLE WATER FOR CLEANING. DISCHARGING TO OR COLLECTING WATER FROM STREAMS IS PROHIBITED. PRESSURE WASHER WATER PRESSURE SHALL BE CAPABLE OF 1,500 PSI. CONTRACTOR SHALL NOT PRESSURE WASH NEAR EXISTING UTILITIES OR BRIDGE ITEMS CONTAINING OR COATED WITH ASBESTOS OR TANSITE. OPERATING PRESSURES SHALL BE SUFFICIENT TO REMOVE THE ACCUMULATED MATERIAL WITHOUT DAMAGE TO THE STRUCTURE. THE CONTRACTOR SHALL ENSURE THAT THE DRAINAGE SYSTEMS REMAIN CLEAN AND FREE OF ALL DEBRIS UNTIL ALL WORK UNDER THIS CONTRACT IS COMPLETE. ANY DAMAGE OR DETERIORATED SYSTEMS SHALL BE REPORTED TO THE ENGINEER.

PAYMENT FOR THE ABOVE DESCRIBED WORK SHALL BE MADE AT THE CONTRACT BID PRICE AS FOLLOWS:

ITEM 503 SPECIAL - STRUCTURE, MISC.: CLEANING OF DRAINAGE SYSTEMS (LS)

**ITEM 848 - SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN (2½" THICK)**

THIS ITEM SHALL CONFORM TO SUPPLEMENTAL SPECIFICATION (SS) 848 WITH THE FOLLOWING CONDITIONS AND REVISIONS:

A) THE FINAL SOUNDING MAY TAKE PLACE WITHIN 24 HOURS OF RAIN, AND THE DECK DOES NOT HAVE TO BE COMPLETELY DRY.

B) THE WET CURE TIME IS REDUCED FROM 72 HOURS TO 24 HOURS OR UNTIL A BEAM BREAK OF 600 PSI IS ACHIEVED, WHICHEVER IS GREATER.

**ABBREVIATION LEGEND**

A.P.P. - AS PER PLAN
APPR. (APP.) - APPROACH
BOT. (B) - BOTTOM
BRG. - BEARING
℄ - CENTERLINE
C.J. - CONSTRUCTION JOINT
CLR. - CLEARANCE
C&MS - CONSTRUCTION AND MATERIAL SPECIFICATIONS
CONST. - CONSTRUCTION
CY - CUBIC YARD
DIA. - DIAMETER
EA - EACH
E.F. - EACH FACE
EL. (ELEV.) - ELEVATION
EX. - EXISTING
F.F. - FAR FACE
FT - FEET
HMWM - HIGH MOLECULAR WEIGHT METHACRYLATE
HSR - HARD SHOULDER RUNNING
LB - POUND
LMC - LATEX MODIFIED CONCRETE
LONG. - LONGITUDINAL
LS- LUMP SUM
LT. - LEFT
MAX. - MAXIMUM
M.E. - MATCH EXISTING
MIN. - MINIMUM
NB - NORTHBOUND
N.F. - NEAR FACE
P.B. - PORTABLE BARRIER
P.E.J.F. - PREFORMED EXPANSION JOINT FILLER
PGL - PROFILE GRADE LINE
PROP. - PROPOSED
RT. - RIGHT
SB - SOUTHBOUND
SDC - SUPERPLASTICIZED DENSE CONCRETE
SER. - SERIES
STA. - STATION
SY - SQUARE YARD
SHDR. (SHD.) - SHOULDER
(T) - TOP
T/T - TOE-TO-TOE
TYP. - TYPICAL
U.N.O. - UNLESS NOTED OTHERWISE
W/ - WITH
W.R.T. - WITH RESPECT TO
ϕ - DIAMETER

GENERAL NOTES
BRIDGE NO. FRA-00071-23.460
I-71 OVER COOKE RD.

SFN 2508133
DESIGN AGENCY Jacobs
DESIGNER ADS | CHECKER KPL
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 2 | TOTAL 14
SHEET P. 408 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:13:25 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SN001.dgn

| ITEM | EXTENSION | LEFT BRIDGE | RIGHT BRIDGE | TOTAL 01/NHS/BR | UNIT | ESTIMATED QUANTITIES DESCRIPTION | ABUT. | PIERS | SUPER. | GEN. | SHEET NO. |
|---|---|---|---|---|---|---|---|---|---|---|---|
| 202 | 11203 | - | - | LS | LS | PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN | | | | | 2/14 |
| 202 | 22900 | 212 | 212 | 424 | SY | APPROACH SLAB REMOVED | | | | 424 | |
| 503 | 21301 | - | - | LS | LS | UNCLASSIFIED EXCAVATION, AS PER PLAN | | | | | 2/14 |
| 512 | 10100 | 918 | 918 | 1836 | SY | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) | 142 | 1050 | 644 | | |
| 516 | 13600 | 203 | 212 | 415 | SF | 1" PREFORMED EXPANSION JOINT FILLER | | | 415 | | |
| 516 | 31001 | 113 | 113 | 226 | FT | 2" DEEP JOINT SEALER, AS PER PLAN | | | 226 | | 2/14 |
| 519 | 11101 | 559 | 559 | 1118 | SF | PATCHING CONCRETE STRUCTURE, AS PER PLAN | 100 | 318 | 700 | | 2/14 |
| 526 | 25010 | 294 | 294 | 588 | SY | REINFORCED CONCRETE APPROACH SLABS WITH QC/QA (T = 15") | | | | 588 | |
| 526 | 90011 | 112 | 112 | 224 | FT | TYPE A INSTALLATION, AS PER PLAN | | | | 224 | 2/14 |
| 530 | 00200 | - | - | LS | LS | SPECIAL - STRUCTURE MISC.: CLEANING OF DRAINAGE SYSTEMS | | | | | 2/14 |
| 848 | 10201 | 1000 | 980 | 1980 | SY | SUPERPLASTICIZED DENSE CONCRETE OVERLAY USING HYDRODEMOLITION, AS PER PLAN (2½" THICK) | | | 1980 | | 2/14 |
| 848 | 20000 | 1000 | 980 | 1980 | SY | SURFACE PREPARATION USING HYDRODEMOLITION | | | 1980 | | |
| 848 | 30200 | 22 | 22 | 44 | CY | SUPERPLASTICIZED DENSE CONCRETE OVERLAY (VARIABLE THICKNESS), MATERIAL ONLY | | | 44 | | |
| 848 | 50000 | 40 | 40 | 80 | SY | HAND CHIPPING | | | 80 | | |
| 848 | 50100 | - | - | LS | LS | TEST SLAB | | | | | |
| 848 | 50200 | 14 | 14 | 28 | CY | FULL-DEPTH REPAIR | | | 28 | | |
| 848 | 50320 | 1000 | 980 | 1980 | SY | EXISTING CONCRETE OVERLAY REMOVED (1¾" THICK) | | | 1980 | | |
| 848 | 50340 | 354 | 346 | 700 | SY | REMOVAL OF DEBONDED OR DETERIORATED EXISTING VARIABLE THICKNESS CONCRETE OVERLAY | | | 700 | | |

ESTIMATED QUANTITIES
BRIDGE NO. FRA-00071-23.460
I-71 OVER COOKE RD.

SFN 2508133

DESIGN AGENCY
Jacobs

| DESIGNER | CHECKER |
|---|---|
| ADS | KPL |

REVIEWER
MJR 01/25/25


PROJECT ID
109164

| SUBSET | TOTAL |
|---|---|
| 3 | 14 |


| SHEET | TOTAL |
|---|---|
| P. 409 | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:13:37 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SQ001.dgn




***EXISTING TRANSVERSE SECTION***




***PHASE 1A (STEPS 1& 3) CONSTRUCTION***




***PHASE 1A (STEPS 2 & 4) CONSTRUCTION***

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 2/14.*
2. *FOR TYPICAL OVERLAY DETAILS, SEE SHEET 11/14.*
3. *SEAL JOINTS IN ACCORDANCE WITH C&MS 848. PER SS 848.32 THE COST OF SEALING SHALL BE CONSIDERED INCIDENTAL TO THE CONCRETE OVERLAY ITEM.*
4. *PORTABLE BARRIER INCLUDED WITH ROADWAY QUANTITIES.*
5. *REFER TO TRAFFIC CONTROL PLANS FOR PROPOSED PAVEMENT MARKINGS.*

# STAGED CONSTRUCTION DETAILS (1 OF 2)
## BRIDGE NO. FRA-00071-23.460
## I-71 OVER COOKE RD.


| | |
|---|---|
| SFN | 2508133 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | KPL |
| CHECKER | ADS |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 4 |
| TOTAL | 14 |
| SHEET | P. 410 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet 1 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:13:49 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SC001.dgn




**PHASE 1B (STEPS 1 & 3) CONSTRUCTION**




**PHASE 1B (STEPS 2 & 4) CONSTRUCTION**




**PROPOSED TRANSVERSE SECTION**

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 2/14.
2. FOR TYPICAL OVERLAY DETAILS, SEE SHEET 11/14.
3. SEAL JOINTS IN ACCORDANCE WITH C&MS 848. PER SS 848.32 THE COST OF SEALING SHALL BE CONSIDERED INCIDENTAL TO THE CONCRETE OVERLAY ITEM.
4. PORTABLE BARRIER INCLUDED WITH ROADWAY QUANTITIES.
5. REFER TO TRAFFIC CONTROL PLANS FOR PROPOSED PAVEMENT MARKINGS.

STAGED CONSTRUCTION DETAILS (2 OF 2)
BRIDGE NO. FRA-00071-23.460
I-71 OVER COOKE RD.

SFN 2508133
DESIGN AGENCY
Jacobs
DESIGNER KPL | CHECKER ADS
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 5 | TOTAL 14
SHEET P. 411 | TOTAL 618


FRA-71-19.10

MODEL: Sheet 2 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:13:52 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SC001.dgn




***PLAN - REAR ABUTMENT***

*(EX. SLIDING PLATE EXPANSION JOINT & MEDIAN BARRIER NOT SHOWN FOR CLARITY)*




***ELEVATION - REAR ABUTMENT***

*(EX. REINFORCING NOT SHOWN FOR CLARITY)*

***LEGEND:***

- *ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN*
- *ITEM 202 - APPROACH SLAB REMOVED*

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 2/14.*
2. *ALL REMOVAL AND EXCAVATION NECESSARY TO CONSTRUCT NEW FULL-WIDTH APPROACH SLABS WHERE FULL-WIDTH APPROACH SLABS DO NOT CURRENTLY EXIST, SHALL BE INCLUDED IN THE CONTRACT LUMP SUM BID PRICE FOR ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN.*
3. *SEE SECTION C ON SHEET XX FOR SIMILAR REMOVAL DETAILS AT EXISTING MEDIAN BARRIER INCLUDING REMOVAL OF EXISTING MEDIAN BASE SLAB/FOUNDATION AS NECESSARY FOR FULL-WIDTH APPROACH SLABS.*

REMOVAL DETAILS (1 OF 3)
BRIDGE NO. FRA-00071-23.460
I-71 OVER COOKE RD.

| | |
|---|---|
| SFN | 2508133 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ADS |
| CHECKER | KPL |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 6 |
| TOTAL | 14 |
| SHEET | P. 412 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:14:06 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SV001.dgn




***PLAN - FWD. ABUTMENT***

*(EX. SLIDING PLATE EXPANSION JOINT & MEDIAN BARRIER NOT SHOWN FOR CLARITY)*




***ELEVATION - FWD. ABUTMENT***

*(EX. REINFORCING NOT SHOWN FOR CLARITY)*

***LEGEND:***

-ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN

-ITEM 202 - APPROACH SLAB REMOVED

***NOTES:***


1. FOR ABBREVIATION LEGEND, SEE SHEET 2/14.
2. ALL REMOVAL AND EXCAVATION NECESSARY TO CONSTRUCT NEW FULL-WIDTH APPROACH SLABS WHERE FULL-WIDTH APPROACH SLABS DO NOT CURRENTLY EXIST, SHALL BE INCLUDED IN THE CONTRACT LUMP SUM BID PRICE FOR ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN.
3. SEE SECTION C ON SHEET XX FOR SIMILAR REMOVAL DETAILS AT EXISTING MEDIAN BARRIER INCLUDING REMOVAL OF EXISTING MEDIAN BASE SLAB/FOUNDATION AS NECESSARY FOR FULL-WIDTH APPROACH SLABS.

# REMOVAL DETAILS (2 OF 3)
# BRIDGE NO. FRA-00071-23.460
# I-71 OVER COOKE RD.


| | |
|---|---|
| SFN | 2508133 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ADS |
| CHECKER | KPL |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 7 |
| TOTAL | 14 |
| SHEET | P. 413 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:14:21 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SV002.dgn





A/6 A/7 **SECTION**




B/6 B/7 **SECTION**




**ENLARGED DETAIL**
(EX. SLIDING PLATE EXP. JT. REMOVAL)




**EX. CURB PLATE DETAIL**

**LEGEND:**

- ITEM 202 - APPROACH SLAB REMOVED
- ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN
- CUT EXISTING REINFORCING BAR(S) FLUSH AT THE CUT LINE

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 2/14.
2. ALL REMOVAL AND EXCAVATION NECESSARY TO CONSTRUCT NEW FULL-WIDTH APPROACH SLABS WHERE APPROACH SLABS DO NOT CURRENTLY EXIST SHALL BE INCLUDED IN THE CONTRACT LUMP SUM BID PRICE FOR ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN.
3. ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO REMOVE PORTIONS OF EXISTING SLIDING PLATE EXPANSION JOINT SHALL BE INCLUDED WITH THE LINEAR FOOT CONTRACT PRICE BID FOR ITEM 202 - REMOVAL MISC.: SLIDING PLATE EXPANSION JOINT REMOVED.


REMOVAL DETAILS (3 OF 3)
BRIDGE NO. FRA-00071-23.460
I-71 OVER COOKE RD.

| | |
|---|---|
| SFN | 2508133 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | KPL |
| CHECKER | ADS |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 8 |
| TOTAL | 14 |
| SHEET | P. 414 |
| TOTAL | 618 |


FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:14:33 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SV003.dgn




***PLAN - REAR ABUTMENT***




***ELEVATION - REAR ABUTMENT***

***NOTES:***

*1. FOR ABBREVIATION LEGEND, SEE SHEET 2/14.*

***LEGEND:***


◕ *- MEASURED ALONG FRONT FACE OF BACKWALL.*


REAR ABUTMENT PLAN AND ELEVATION
BRIDGE NO. FRA-00071-23.460
I-71 OVER COOKE RD.

| | |
|---|---|
| SFN | 2508133 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ADS |
| CHECKER | KPL |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 9 |
| TOTAL | 14 |
| SHEET | P. 415 |
| TOTAL | 618 |


FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:14:45 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SR001.dgn




***PLAN - FWD. ABUTMENT***




***ELEVATION - FWD. ABUTMENT***

***NOTES:***

*1. FOR ABBREVIATION LEGEND, SEE SHEET 2/14.*

***LEGEND:***


◒ *- MEASURED ALONG FRONT FACE OF BACKWALL.*

# FORWARD ABUTMENT PLAN AND ELEVATION
## BRIDGE NO. FRA-00071-23.460
## I-71 OVER COOKE RD.


| | |
|---|---|
| SFN | 2508133 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ADS |
| CHECKER | KPL |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109164 |
| SUBSET | 10 |
| TOTAL | 14 |
| SHEET | P. 416 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:15:00 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SF001.dgn




A/9 A/10 **SECTION**




***ENLARGED JOINT DETAIL***




***TYPICAL OVERLAY DETAIL***

***NOTES:***


1. *FOR ABBREVIATION LEGEND SEE SHEET 2/14.*
2. *FURNISH AMORLESS PREFORMED JOINT SEAL IN ONE CONTINUOUS PIECE. SEE SHEET 2/14 FOR ADDITIONAL NOTES.*
3. *SEAL JOINTS IN ACCORDANCE WITH SS 848. PER 848.32 THE COST OF SEALING SHALL BE CONSIDERED INCIDENTAL TO THE CONCRETE OVERLAY ITEM.*
4. *PROPOSED APPROACH SLAB SHALL OMIT REINFORCING TYING APPROACH SLAB TO EXISTING BACKWALL. IN OTHER WORDS OMIT 'D801' BARS TYPICALLY PROVIDED PER ODOT STANDARD CONSTRUCTION DRAWING AS-1-15.*
5. *REMOVE EXISTING JOINT SEALER AND CLEAN EXISTING SURFACE. PLACE NEW JOINT SEALER PER C&MS 705.04. ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO PERFORM THIS WORK SHALL BE INCLUDED FOR PAYMENT WITH ITEM 516 - 2" DEEP JOINT SEALER, AS PER PLAN.*

# ABUTMENT SECTION AND DETAILS
## BRIDGE NO. FRA-00071-23.460
## I-71 OVER COOKE RD.


| | |
|---|---|
| SFN | 2508133 |
| DESIGN AGENCY | Jacobs |
| DESIGNER | KPL |
| CHECKER | ADS |
| REVIEWER | MJR 01/25/25 |
| PROJECT ID | 109165 |
| SUBSET | 11 |
| TOTAL | 14 |
| SHEET | P. 417 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:15:13 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SR002.dgn




***PLAN***




| SLEEPER SLAB & APPROACH SLAB TOP SURFACE ELEVATIONS | | | |
|---|---|---|---|
| POINT ID | STATION | OFFSET | SURFACE ELEV. |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | TO BE COMPLETED WITH STAGE 3 | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |
| 10 | | | |

| POINT ID | STATION | OFFSET | SURFACE ELEV. |
|---|---|---|---|
| 11 | | | |
| 12 | | | |
| 13 | | | |
| 14 | | | |
| 15 | TO BE COMPLETED WITH STAGE 3 | | |
| 16 | | | |
| 17 | | | |
| 18 | | | |
| 19 | | | |
| 20 | | | |
| 21 | | | |

| POINT ID | STATION | OFFSET | SURFACE ELEV. |
|---|---|---|---|
| 22 | | | |
| 23 | | | |
| 24 | | | |
| 25 | TO BE COMPLETED WITH STAGE 3 | | |
| 26 | | | |
| 27 | | | |
| 28 | | | |

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 2/14.*
2. *SEE ODOT SCD. DWG. AS-1-15, AS-2-15 FOR ADDITIONAL DETAILS.*
3. *A POLYMER MODIFIED ASPHALT EXPANSION JOINT IS NOT REQUIRED WITH THE TYPE A INSTALLATION.*
4. *TRIM REINFORCING BARS AS NEEDED TO PROVIDE 2" MINIMUM CLEAR COVER.*
5. *THE PROPOSED ELEVATIONS PROVIDED ARE TO BE CONSIDERED APPROXIMATE. FIELD VERIFY ALL PROPOSED ELEVATIONS AT THE LOCATIONS SHOWN IN THESE PLANS. ADJUST THE PROPOSED ELEVATIONS ACCORDINGLY TO MAINTAIN THE EXISTING CROSS SLOPE AND PROFILE IN ORDER TO MATCH UP WITH THE EXISTING ROADWAY AND THE EXISTING BRIDGE ABUTMENT. NOTIFY THE ENGINEER OF THE PROPOSED ADJUSTMENTS PRIOR TO CONSTRUCTING THE PROPOSED WORK.*

# REAR APPROACH SLAB DETAILS
# BRIDGE NO. FRA-00071-23.460
# I-71 OVER COOKE RD.


SFN 2508133
DESIGN AGENCY
Jacobs
DESIGNER ADS | CHECKER KPL
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 12 | TOTAL 14
SHEET P. 418 | TOTAL 618


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:15:29 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SM001.dgn




**PLAN**




| SLEEPER SLAB & APPROACH SLAB TOP SURFACE ELEVATIONS | | | |
|---|---|---|---|
| POINT ID | STATION | OFFSET | SURFACE ELEV. |
| 1 | | | |
| 2 | | | |
| 3 | | | |
| 4 | | | |
| 5 | TO BE COMPLETED WITH STAGE 3 | | |
| 6 | | | |
| 7 | | | |
| 8 | | | |
| 9 | | | |
| 10 | | | |

| POINT ID | STATION | OFFSET | SURFACE ELEV. |
|---|---|---|---|
| 11 | | | |
| 12 | | | |
| 13 | | | |
| 14 | | | |
| 15 | | | |
| 16 | TO BE COMPLETED WITH STAGE 3 | | |
| 17 | | | |
| 18 | | | |
| 19 | | | |
| 20 | | | |
| 21 | | | |

| POINT ID | STATION | OFFSET | SURFACE ELEV. |
|---|---|---|---|
| 22 | | | |
| 23 | | | |
| 24 | | | |
| 25 | TO BE COMPLETED WITH STAGE 3 | | |
| 26 | | | |
| 27 | | | |
| 28 | | | |

***NOTES:***

1. *FOR ABBREVIATION LEGEND, SEE SHEET 2/14.*
2. *SEE ODOT SCD. DWG. AS-1-15, AS-2-15 FOR ADDITIONAL DETAILS.*
3. *A POLYMER MODIFIED ASPHALT EXPANSION JOINT IS NOT REQUIRED WITH THE TYPE A INSTALLATION.*
4. *TRIM REINFORCING BARS AS NEEDED TO PROVIDE 2" MINIMUM CLEAR COVER.*
5. *THE PROPOSED ELEVATIONS PROVIDED ARE TO BE CONSIDERED APPROXIMATE. FIELD VERIFY ALL PROPOSED ELEVATIONS AT THE LOCATIONS SHOWN IN THESE PLANS. ADJUST THE PROPOSED ELEVATIONS ACCORDINGLY TO MAINTAIN THE EXISTING CROSS SLOPE AND PROFILE IN ORDER TO MATCH UP WITH THE EXISTING ROADWAY AND THE EXISTING BRIDGE ABUTMENT. NOTIFY THE ENGINEER OF THE PROPOSED ADJUSTMENTS PRIOR TO CONSTRUCTING THE PROPOSED WORK.*

# FORWARD APPROACH SLAB DETAILS
## BRIDGE NO. FRA-00071-23.460
## I-71 OVER COOKE RD.

SFN 2508133

DESIGN AGENCY: Jacobs

| DESIGNER | CHECKER |
|---|---|
| KPL | ADS |

REVIEWER: MJR 01/25/25

PROJECT ID: 109164

| SUBSET | TOTAL |
|---|---|
| 13 | 14 |


| SHEET | TOTAL |
|---|---|
| P. 419 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:15:44 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SM002.dgn

| MARK | NUMBER TOTAL | LENGTH | WEIGHT | TYPE | DIMENSIONS A | B | C | D | E | R | INC |
|---|---|---|---|---|---|---|---|---|---|---|---|
| **APPROACH SLABS (FOR INFORMATION ONLY)** | | | | | | | | | | | |
| AS501■ | 664 | 27'-9" | 19,218 | STR | | | | | | | |
| AS502 | 424 | 24'-6" | 10,835 | STR | | | | | | | |
| | | | | | | | | | | | |
| AS1001 | 368 | 25'-11" | 41,039 | 16 | 24'-6" | | | | | | |
| | | | | | | | | | | | |
| | | SUB-TOTAL | 71,092 | | | | | | | | |
| **SLEEPER SLABS (FOR INFORMATION ONLY)** | | | | | | | | | | | |
| SS501■ | 32 | 27'-9" | 926 | STR | | | | | | | |
| SS502 | 216 | 7'-11" | 1,784 | STR | | | | | | | |
| SS503■ | 32 | 27'-2" | 907 | STR | | | | | | | |
| | | | | | | | | | | | |
| | | SUB-TOTAL | 3,617 | | | | | | | | |
| | | GRAND TOTAL | 74,709 | | | | | | | | |

*APPROACH SLAB AND SLEEPER SLAB REINFORCING SHOWN INCLUDES THE NUMBER/WEIGHT OF THE LEFT AND RIGHT BRIDGES FOR BOTH THE REAR AND FORWARD APPROACH SLABS.*




TYPE-16

***LEGEND:***

■ - *REINFORCING BAR UTILIZES A MECHANICAL CONNECTOR. BAR LENGTH IS MEASURED TO THE CONSTRUCTION JOINT. EXTRA BAR LENGTH AND/OR BAR END PREPARATION MAY BE NECESSARY DEPENDING UPON THE TYPE OF MECHANICAL CONNECTOR FURNISHED.*

***NOTES:***

1. *THE BAR SIZE NUMBER IS SPECIFIED ON THE PLANS IN THE BAR MARK COLUMN. THE FIRST DIGIT WHERE THREE DIGITS ARE USED, AND THE FIRST TWO DIGITS WHERE FOUR DIGITS ARE USED, INDICATES THE BAR SIZE NUMBER. FOR EXAMPLE, AN AS501 BAR IS A NO. 5 BAR. BAR DIMENSIONS SHOWN ARE OUT TO OUT UNLESS OTHERWISE NOTED. "STD" WRITTEN IN PLACE OF A DIMENSION INDICATES A STANDARD BEND AT THE END OF THE BAR.*
2. *STRAIGHT BARS ARE INDICATED BY "STR".*
3. *ALL REINFORCING STEEL SHALL BE EPOXY COATED.*
4. *ALL REINFORCING STEEL SHALL BE GRADE 60 WITH A MINIMUM YIELD STRENGTH OF 60 KSI.*

REINFORCING STEEL LIST
BRIDGE NO. FRA-00071-23.460
I-71 OVER COOKE RD.


SFN 2508133
DESIGN AGENCY Jacobs
DESIGNER KPL | CHECKER ADS
REVIEWER MJR 01/25/25
PROJECT ID 109164
SUBSET 14 | TOTAL 14
SHEET P. 420 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 10:16:00 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508133\Sheets\109164_SFN_2508133_SL001.dgn

MODEL: CLP_I071 - Plan 1 [Sheet] PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:47:53 AM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Matt.Rotar@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SP001.dgn






**PLAN**
*(GIRDERS AND TEMPORARY SHORING NOT SHOWN FOR CLARITY)*

*(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS*

## BENCHMARK DATA

| | | | | | | |
|---|---|---|---|---|---|---|
| BM #1 STA. | 1308+16.86, | ELEV. | 893.69, | OFFSET | 68.87', | LT. |
| BM #2 STA. | 1315+45.86, | ELEV. | 895.50, | OFFSET | 81.43', | LT. |
| BM #3 STA. | 1323+25.21, | ELEV. | 889.52, | OFFSET | 83.11', | RT. |

## NOTES

1. EARTHWORK LIMITS SHOWN ARE APPROXIMATE. ACTUAL SLOPES SHALL CONFORM TO PLAN CROSS SECTIONS.
2. FOR ADDITIONAL BENCHMARK AND SURVEY INFORMATION, SEE ROADWAY PLANS.
3. FOR BRIDGE PROFILES, SEE SHEET 2.
4. FOR GENERAL PLAN, SEE SHEET 3.

DESIGN TRAFFIC:

2030 ADT = 134,014 2030 ADTT = 16,646
2050 ADT = 151,444 2050 ADTT = 17,746
DIRECTIONAL DISTRIBUTION = 0.53 (NB)

## LEGEND

- BORING LOCATION
- 15'-6" REQUIRED MINIMUM VERTICAL CLEARANCE
  15'-9" ACTUAL MINIMUM VERTICAL CLEARANCE (SEE SHEET 2)
- A - VARIES, 0" MIN. TO $8\frac{13}{16}$" MAX.
- B - SHOULDER VARIES, 9'-$1\frac{3}{8}$"± MIN. TO 12'-$6\frac{3}{4}$"± MAX.
- C - RAMP LANE VARIES, 16'-$1\frac{1}{2}$"± MIN. TO 19'-2"± MAX.
- D - SHOULDER VARIES, 4'-0" MIN.
- E - SHOULDER VARIES, 12'-0"± MIN.
- F - SHOULDER VARIES, 10'-0" MIN.

## EXISTING STRUCTURE

TYPE: 4-SPAN CONTINUOUS REINFORCED CONCRETE SLAB SUPPORTED ON REINFORCED CONCRETE STUB ABUTMENTS AND CAP AND COLUMN PIERS

SPANS: 38'-0"± - 47'-6"± - 47'-6"± - 38'-0"± C/C BEARINGS (W.R.T. RECORD R.C.)

ROADWAY: 53'-0"± T/T PARAPET - RIGHT (NORTHBOUND) BRIDGE VARIES, 58'-2"± TO 63'-3"± T/T PARAPET - LEFT(SOUTHBOUND)

LOADING: CF2000

SKEW: 10°15'04"± RIGHT (NORTHBOUND)
10°01'32"± LEFT (SOUTHBOUND)

WEARING SURFACE: LMC OVERLAY/MONOLITHIC CONCRETE

APPROACH SLABS: AS-1-81 (25' LONG)

ALIGNMENT: 01°30'00" RT. CURVE

CROWN: 0.05± FT/FT

STRUCTURE FILE NUMBER: 2508192 (LEFT), 2508222 (RIGHT)

DATE BUILT: 1959

DISPOSITION: TO BE REPLACED

## PROPOSED STRUCTURE

TYPE: SINGLE SPAN STEEL PLATE GIRDER (ASTM A709, GRADE 50) WITH COMPOSITE REINFORCED CONCRETE DECK SUPPORTED ON SEMI-INTEGRAL ABUTMENTS

SPANS: 150'-0" C/C BEARINGS (W.R.T. REFERENCE CHORD)

ROADWAY: 62'-2" TOE/TOE PARAPET (RIGHT BRIDGE)
78'-3" TOE/TOE PARAPET (LEFT BRIDGE)

LOADING: HL93 AND 60 PSF FUTURE WEARING SURFACE

SKEW: 10°20'00" WITH RESPECT TO REFERENCE CHORD

WEARING SURFACE: 1" MONOLITHIC CONCRETE

APPROACH SLABS: 30'-0" LONG (AS-1-15, AS-2-15) W/ TYPE C

ALIGNMENT: 01°30'00" RT. CURVE

CROWN: 0.05 FT/FT

DECK AREA: 9971 SF (RIGHT), 12,416 SF (LEFT)


STRUCTURE FILE NUMBER: TBD (LEFT), TBD (RIGHT)

COORDINATES: LATITUDE 40°03'41.11" NORTH
LONGITUDE 82°59'52.70" WEST

HORIZONTAL SCALE IN FEET
0 10 20 40

# SITE PLAN (1 OF 2)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 1 |
| TOTAL | 65 |
| SHEET | P. 421 |
| TOTAL | 618 |




***PROFILE ALONG PROFILE GRADE LINE - LEFT BRIDGE (SOUTHBOUND)***

***LEGEND:***

- *15'-6" REQUIRED MINIMUM VERTICAL CLEARANCE*
  *15'-9" ACTUAL MINIMUM VERTICAL CLEARANCE*




***PROFILE ALONG PROFILE GRADE LINE - RIGHT BRIDGE (NORTHBOUND)***

***NOTES:***

1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *FOR GENERAL PLAN, SEE SHEET 3.*

SITE PLAN (2 OF 2)
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 2 |
| TOTAL | 65 |
| SHEET | P. 422 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:55:49 AM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Matt.Rotar@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SP002.dgn


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:36:09 AM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Matt.Rotar@jacobs.com WORKSPACE: OHDOTCe02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SG001.dgn

FRA-71-19.10




**HORIZONTAL CURVE DATA**
P.I. = STA. 1317+82.27
Δ = 41°46'52" RT.
Dc = 01°30'00"
R = 3819.72'
T = 1457.89'
L = 2785.41'
E = 268.76'

## GENERAL PLAN




## GEOMETRIC LAYOUT

**NOTES:**

1. FOR TEMPORARY SHORING PLAN, SEE SHEET 17.
2. FOR STAGED CONSTRUCTION DETAILS, SEE SHEETS 7 THRU 8.
3. FOR ABBREVIATION LEGEND, SEE SHEET 5.

# GENERAL PLAN
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

SFN TBD
SFN TBD
DESIGN AGENCY Jacobs
DESIGNER MAN | CHECKER DBL
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 3 | TOTAL 65
SHEET P. 423 | TOTAL 618

**STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS**

REFER TO THE FOLLOWING STANDARD BRIDGE DRAWINGS:

| | | |
|---|---|---|
| AS-1-15 | REVISED | 1/20/2023 |
| AS-2-15 | REVISED | 7/21/2023 |
| GSD-1-19 | REVISED | 7/19/2024 |
| PCB-91 | REVISED | 7/17/2020 |
| SBR-1-20 | REVISED | 7/19/2024 |
| SBR-2-20 | REVISED | 7/19/2024 |
| SICD-1-21 | REVISED | 1/19/2024 |
| SICD-2-14 | REVISED | 1/15/2021 |

AND TO THE FOLLOWING SUPPLEMENTAL SPECIFICATION(S):

| | | |
|---|---|---|
| 800 | DATED | XX/YY/ZZZZ |
| 840 | DATED | 1/16/2026 |
| 867 | DATED | 4/15/2022 |

**DESIGN SPECIFICATIONS**

THIS STRUCTURE CONFORMS TO THE 9th EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020 AND THE ODOT BRIDGE DESIGN MANUAL, 2020, DATED JULY 2025.

**OPERATIONAL IMPORTANCE**

A LOAD MODIFIER OF 1.05 HAS BEEN ASSUMED FOR THE DESIGN OF THIS STRUCTURE IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, ARTICLE 1.3.5 AND THE ODOT BRIDGE DESIGN MANUAL.

**DESIGN LOADING**

DESIGN LOADING INCLUDES:
VEHICULAR LIVE LOAD: HL-93
FUTURE WEARING SURFACE (FWS) OF 0.060 KIPS/SQ.FT.

**DESIGN DATA**

CONCRETE CLASS QC2 - COMPRESSIVE STRENGTH 4.5 KSI (DRILLED SHAFT)

CONCRETE CLASS QC2 - COMPRESSIVE STRENGTH 4.5 KSI (SUPERSTRUCTURE)

CONCRETE CLASS QC1 - COMPRESSIVE STRENGTH 4.0 KSI (SUBSTRUCTURE)

CONCRETE REINFORCEMENT:

EPOXY COATED STEEL REINFORCEMENT - MINIMUM YIELD STRENGTH - 60-KSI

GFRP REINFORCEMENT (PARAPETS)

STRUCTURAL STEEL - ASTM A709 GRADE 50 - YIELD STRENGTH 50 KSI (GIRDERS, CONNECTION PLATES, SPLICE PLATES, CROSS FRAMES MEMBERS, BEARING STIFFENERS, LOAD PLATES, SEMI-INTEGRAL ABUTMENT PEDESTALS)

STEEL CAST-IN-PLACE (C.I.P.) REINFORCED CONCRETE PIPE PILES (C&MS 507) - ASTM A252 GRADE 3 - YIELD STRENGTH 45 KSI

**DECK PROTECTION METHOD**

EPOXY COATED REINFORCING STEEL

2½" CONCRETE COVER

**MONOLITHIC WEARING SURFACE**

A MONOLITHIC WEARING SURFACE IS ASSUMED, FOR DESIGN PURPOSES TO BE 1 INCH THICK.

**EXISTING BRIDGE PLANS**

FOR INFORMATION NOT SHOWN, EXISTING BRIDGE PLANS MAY BE INSPECTED IN THE OFFICE OF STRUCTURAL ENGINEERING IN COLUMBUS, OHIO OR AT THE DISTRICT 6 OFFICE, 400 EAST WILLIAM STREET, DELAWARE, OHIO 43015.

**MAINTENANCE OF TRAFFIC**

FOR MAINTENANCE OF TRAFFIC PLANS, SEE ROADWAY SHEETS.

**UTILITIES**

FOR UTILITY NOTES, SEE ROADWAY SHEETS.

**EXISTING STRUCTURE VERIFICATION**

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURES HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURES AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE(S) AND THE PROPOSED WORK, BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO C&MS SECTIONS 102.05, 105.02 AND 513.04 FOR FURTHER INFORMATION.

BASE CONTRACT BID PRICES UPON A RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURE. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS THAT HAVE BEEN VERIFIED IN THE FIELD.

**ASBESTOS NOTIFICATION**

AN ASBESTOS SURVEY OF THE BRIDGE WAS CONDUCTED BY A CERTIFIED ASBESTOS HAZARD EVALUATION SPECIALIST. THE SURVEY DETERMINED THAT NO ASBESTOS IS PRESENT AT THE BRIDGES.

A COPY OF THE OHIO ENVIRONMENTAL PROTECTION AGENCY (OEPA) NOTIFICATION OF DEMOLITION AND RENOVATION FORMS, PARTIALLY COMPLETED AND SIGNED BY THE BRIDGE OWNER, WILL BE PROVIDED TO THE SUCCESSFUL BIDDER. THE CONTRACTOR SHALL COMPLETE THE FORM AND SUBMIT IT TO:

OHIO EPA, CDO
50 WEST TOWN ST, SUITE 700
COLUMBUS, OHIO 43215
KELLY TOTH, APC MANAGER
(614) 728-3778
FAX: (614) 728-3898

THE CONTRACTOR SHALL PROVIDE A COPY OF THE COMPLETED FORM TO THE ENGINEER AT LEAST TEN (10) WORKING DAYS PRIOR TO THE START OF ANY DEMOLITION AND/OR REHABILITATION.

INFORMATION REQUIRED ON THE FORM SHALL INCLUDE: 1) THE CONTRACTOR NAME, ADDRESS AND CONTACT INFORMATION 2) THE SCHEDULED DATES FOR THE START AND COMPLETION OF THE BRIDGE REMOVAL AND 3) A DESCRIPTION OF THE PLANNED DEMOLITION WORK AND THE METHOD(S) TO BE USED.

THE CONTRACTOR SHALL FURNISH ALL FEES, LABOR, MATERIAL, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE AND SUBMIT THE OEPA NOTIFICATION FORM.

**ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN**

THE PROVISIONS OF C&MS 202 APPLY, IN ADDITION TO THOSE LISTED HEREIN. THIS ITEM SHALL INCLUDE THE ELEMENTS INDICATED IN THE PLANS AND GENERAL NOTES AND THAT ARE NOT SEPARATELY LISTED FOR PAYMENT. ITEMS TO BE REMOVED INCLUDE ALL EXISTING MATERIALS BEING REPLACED BY NEW CONSTRUCTION AND MISCELLANEOUS ITEMS THAT ARE NOT SHOWN TO BE INCORPORATED INTO THE FINAL CONSTRUCTION AND ARE DIRECTED TO BE REMOVED BY THE ENGINEER. THE USE OF EXPLOSIVES AND HEADACHE BALLS WILL NOT BE PERMITTED. THE METHOD OF REMOVAL AND THE WEIGHT OF HAMMER SHALL BE APPROVED BY THE ENGINEER. PERFORM ALL WORK CAREFULLY TO PROTECT PORTIONS OF SUCH SYSTEMS THAT ARE TO BE SALVAGED FOR MAINTAINING TRAFFIC.

**CUT LINE CONSTRUCTION JOINT PREPARATION:**

SAW CUT BOUNDARIES OF PROPOSED CONCRETE REMOVALS 1 INCH DEEP. REMOVE CONCRETE TO A ROUGH SURFACE.

**REMOVAL METHODS:**

THE CONTRACTOR MAY REMOVE CONCRETE BY CUTTING AND BY MEANS OF HAND OPERATED PNEUMATIC HAMMERS EMPLOYING POINTED OR BLUNTED CHISEL TYPE TOOLS. UNLESS OTHERWISE ADVISED BY THE ENGINEER, THE CONTRACTOR IS PERMITTED TO USE A HYDRAULIC HOE-RAM ONLY FOR SUBSTRUCTURE REMOVALS ONLY AFTER THE PHASED REMOVAL LIMITS OF THE SUPERSTRUCTURE ARE COMPLETE FOR THAT PHASE. THE CONTRACTOR MUST SUBMIT DEMOLITION PLAN(S) ACCORDING TO C&MS 501.05.

**EXISTING CIP PILES:**

REMOVE ALL EXISTING PILING TO A MINIMUM OF 1-FOOT BELOW THE PROPOSED BOTTOM OF FOOTING ELEVATION. FILL THE REMOVAL CAVITY ACCORDING TO C&MS 202.

**PILE DRIVING CONSTRAINTS**

REAR ABUTMENT:

PRIOR TO DRIVING PILES TO THE ULTIMATE BEARING VALUE (UBV), CONSTRUCT THE MSE WALL AND THE BRIDGE APPROACH EMBANKMENT BEHIND THE ABUTMENT UP TO THE BOTTOM OF THE FOOTING FOR A MINIMUM DISTANCE OF 200 FEET. THE CONTRACTOR MAY PRE-DRIVE PILES BEFORE CONSTRUCTING THE MSE WALL. PRE-DRIVING CONSISTS OF INSTALLING THE PILES INTO THE SOIL ONLY AS FAR AS NECESSARY SO THAT THE PILE WILL REMAIN VERTICAL DURING MSE WALL CONSTRUCTION. IF PRE-DRIVING PILES, INSTALL PILE SLEEVES AROUND PILES BEFORE CONSTRUCTING THE MSE WALL. PROVIDE AT LEAST 3-FEET OF PILE ABOVE THE TOP OF THE PILE SLEEVE TO MEET THE REQUIREMENTS OF C&MS 507.09 REGARDING SPLICES. DO NOT DRIVE PILES TO THE UBV UNTIL AFTER THE MSE WALL AND EMBANKMENT HAVE BEEN CONSTRUCTED AND A 24 CALENDAR DAY WAITING PERIOD HAS ELAPSED. THE ENGINEER MAY ADJUST THE LENGTH OF THE WAITING PERIOD BASED ON SETTLEMENT PLATFORM READINGS. AFTER THE SPECIFIED WAITING PERIOD HAS ELAPSED, DRIVE PILES TO THE UBV. IN ORDER TO REMOVE ANY NEGATIVE SKIN FRICTION THAT HAS DEVELOPED DURING THE WAITING PERIOD, DRIVE EACH PILE A DISTANCE OF AT LEAST 0.50-INCH.

IF NOT PRE-DRIVING PILES, INSTALL PILES THROUGH THE PILE SLEEVES AFTER THE REQUIRED MSE WALL AND EMBANKMENT HAVE BEEN CONSTRUCTED AND THE SPECIFIED WAITING PERIOD HAS ELAPSED.

**ITEM 507 - PREBORED HOLES, AS PER PLAN**

THE CONTRACTOR SHALL PREBORE PILE HOLES FOR ALL FORWARD ABUTMENT PILES TO A MINIMUM ELEVATION OF 869.00 FOR THE LEFT BRIDGE (PILE NO.s 69-106) AND ELEVATION 872.00 FOR THE RIGHT BRIDGE (PILE NO.s 107-136). THE DIAMETER OF THE PREBORED HOLE SHALL BE A MINIMUM 2-INCH LARGER THAN THE DIAMETER OF THE PILE. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AN OPEN HOLE.

PREBORED HOLES SHALL BE CLEAN AND FREE OF ALL DELETERIOUS MATERIALS PRIOR TO BACKFILLING OPERATIONS. BACKFILL THE CAVITY BETWEEN THE PILE AND THE PREBORED HOLE WITH GRANULAR MATERIAL CONFORMING TO C&MS 703.11, STRUCTURAL BACKFILL TYPE 2, EXCEPT 100 PERCENT OF THE MATERIAL SHALL PASS THROUGH A ¾" SIEVE. BACKFILL THE CAVITY UP TO THE BOTTOM OF FOOTING ELEVATION.

ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE PAID AT THE CONTRACT BID PRICE FOR ITEM 507 - PREBORED HOLES, AS PER PLAN.

**PILE DESIGN LOADS (ULTIMATE BEARING VALUE, UBV)**

THE ULTIMATE BEARING VALUE IS 343 KIPS PER FOOT FOR ABUTMENT PILES.

ABUTMENT PILES:
14" DIAMETER CIP PILES

REAR ABUTMENT:
ESTIMATED LENGTH = 65'-0"
ORDER LENGTH = 70'-0"

FORWARD ABUTMENT:
ESTIMATED LENGTH = 65'-0"
ORDER LENGTH = 70'-0"

PILE DRIVING: THE MAXIMUM RATED ENERGY OF THE HAMMER SHALL NOT EXCEED 47,000 FOOT-POUNDS. ENSURE THAT STRESSES IN THE PILES DURING DRIVING DO NOT EXCEED 40,500 POUNDS PER SQUARE INCH.

A MINIMUM WALL THICKNESS OF 0.375" SHALL BE USED AT ALL THE REAR ABUTMENT PILES. A MINIMUM WALL THICKNESS OF 0.250" SHALL BE USED AT THE FORWARD ABUTMENT PILES. ALL STEEL SHALL BE ASTM A252 STEEL, GRADE 3 WITH A MINIMUM YIELD STRENGTH OF 45 KSI.

**PILES DRIVEN TO FULL ESTIMATED LENGTH WITH PILE/SOIL SETUP**
**ITEM 523 - DYNAMIC LOAD TESTING, AS PER PLAN**
**ITEM 523 - RESTRIKE, AS PER PLAN**

THE ULTIMATE BEARING VALUE (UBV) LISTED ABOVE WILL BE ACHIEVED THROUGH PILE/SOIL SETUP, WHICH IS A TIME DEPENDENT INCREASE THAT OCCURS IN SOME SOILS.

NOTIFY THE ENGINEER AT LEAST 5 WORKING DAYS BEFORE DRIVING PILES SO THAT THE ENGINEER CAN NOTIFY THE DISTRICT GEOTECHNICAL ENGINEER, THE OFFICE OF CONSTRUCTION ADMINISTRATION, AND THE OFFICE OF GEOTECHNICAL ENGINEERING.

DRIVE THE FIRST TWO PILES IN EACH SUBSTRUCTURE TO THEIR FULL ESTIMATED LENGTHS, 65-FEET AT THE REAR ABUTMENT AND 65-FEET AT THE FORWARD ABUTMENT. PERFORM DYNAMIC LOAD TESTING ON BOTH PILES WHILE DRIVING. AFTER DRIVING AND TESTING THE FIRST TWO PILES, DRIVE THE REMAINING PILES IN THE SUBSTRUCTURE TO THE SAME DEPTH AS THE FIRST TWO PILES. AFTER DRIVING ALL PILES TO THE ESTIMATED LENGTH, CEASE ALL DRIVING OPERATIONS AT THE SUBSTRUCTURE FOR A PERIOD OF 7 DAYS. INCLUDE THE WAITING PERIOD AS A SEPARATE ACTIVITY IN THE PROGRESS SCHEDULE. AFTER THE WAITING PERIOD, PERFORM RESTRIKES ON BOTH OF THE FIRST TWO PILES (ONE RESTRIKE ITEM).

SUBMIT ALL TEST RESULTS TO THE ENGINEER. IF THE RESTRIKE RESULTS INDICATE THAT BOTH PILES ACHIEVED THE REQUIRED UBV, ALL PILES IN THE SUBSTRUCTURE MAY BE ACCEPTED BY THE ENGINEER.

IF THE RESTRIKE RESULTS INDICATE THAT EITHER OF THE TWO PILES DID NOT ACHIEVE THE REQUIRED UBV, IMMEDIATELY NOTIFY THE ENGINEER SO THAT THE ENGINEER CAN NOTIFY THE DISTRICT GEOTECHNICAL ENGINEER, THE OFFICE OF CONSTRUCTION ADMINISTRATION, AND THE OFFICE OF GEOTECHNICAL ENGINEERING. THE ENGINEER WILL REVIEW THE TEST RESULTS AND ESTABLISH ADDITIONAL RESTRIKE TESTING OR DRIVING CRITERIA FOR THE PILING IN THE SUBSTRUCTURE WITH THE ASSISTANCE OF THE DISTRICT GEOTECHNICAL ENGINEER, THE OFFICE OF CONSTRUCTION ADMINISTRATION, AND THE OFFICE OF GEOTECHNICAL ENGINEERING.

IF DIRECTED BY THE ENGINEER, PERFORM ADDITIONAL RESTRIKE TESTING OR DRIVE ALL PILES IN THE SUBSTRUCTURE TO THE ESTABLISHED DRIVING CRITERIA. THE DEPARTMENT WILL PAY FOR SPLICING OF THE PILES BEYOND THE ESTIMATED LENGTH PROVIDED IN THE PLANS UNDER C&MS 109.05 WITH A NEGOTIATED PRICE PER SPLICE.

THIS PLAN NOTE INCLUDES A QUANTITY OF ONE EACH ITEM 523 DYNAMIC LOAD TESTING, AS PER PLAN AND A QUANTITY OF ONE EACH ITEM 523 RESTRIKE, AS PER PLAN PER EACH SUBSTRUCTURE UNIT.

**ITEM 514 - FIELD PAINTING OF STRUCTURAL STEEL, FINISH COAT**

THE COLOR OF THE FINISH COAT SHALL BE FEDERAL COLOR NO. FS 595 17038, OSHA BLACK/ANA 515/622

**DECK PLACEMENT ASSUMPTIONS**

THE FOLLOWING ASSUMPTIONS OF CONSTRUCTION MEANS AND METHODS WERE MADE FOR THE ANALYSIS AND DESIGN OF THE SUPERSTRUCTURE. THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN OF THE FALSEWORK SUPPORT SYSTEM WITHIN THESE PARAMETERS AND WILL ASSUME RESPONSIBILITY FOR SUPERSTRUCTURE ANALYSIS FOR DEVIATION FROM THESE DESIGN ASSUMPTIONS.

AN EIGHT WHEEL FINISHING MACHINE.

| BRIDGE | CONST. PHASE | MAX. WHEEL LOAD (KIP) | MAX. RAIL-TO-RAIL WIDTH (FT.) | MAX. BRACKET OVERHANG (MEASURED ℄ FROM GIRDER) (IN.) |
|---|---|---|---|---|
| LEFT | 3A | 2.20 | 33.05 | 70 |
| LEFT | 3B | 2.33 | 46.50 | 70 |
| RIGHT | 4A | 2.20 | 32.03 | 70 |
| RIGHT | 4B | 2.20 | 32.28 | 70 |

A MINIMUM OUT-TO-OUT WHEEL SPACING AT EACH END OF THE MACHINE OF 103".

A MAXIMUM SPACING OF OVERHANG FALSEWORK BRACKETS OF 48".

**ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN**

THE DESIGN(S) SHOWN ON THE PLANS FOR TEMPORARY SUPPORT OF EXCAVATION IS ONE REPRESENTATIVE DESIGN THAT MAY BE USED TO CONSTRUCT THE PROJECT. THE CONTRACTOR MAY CONSTRUCT THE DESIGN SHOWN ON THE PLANS OR PREPARE AN ALTERNATE DESIGN TO SUPPORT THE SIDES OF EXCAVATIONS. IF CONSTRUCTING AN ALTERNATE DESIGN FOR TEMPORARY SUPPORT OF EXCAVATION, PREPARE AND PROVIDE PLANS IN ACCORDANCE WITH C&MS 501.05. THE DEPARTMENT WILL PAY FOR THE TEMPORARY SUPPORT OF EXCAVATION AT THE CONTRACT LUMP SUM PRICE FOR COFFERDAMS AND EXCAVATION BRACING. THE DEPARTMENT WILL NOT MAKE ADDITIONAL PAYMENT FOR PROVIDING AN ALTERNATE DESIGN.

REFER TO SHEET 16 FOR ADDITIONAL NOTES.

STRUCTURE GENERAL NOTES (1 OF 2)
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

SFN TBD
SFN TBD
DESIGN AGENCY Jacobs
DESIGNER MJR | CHECKER DBL
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 4 | TOTAL 65
SHEET P. 424 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:43:30 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SN001.dgn

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:43:42 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SN002.dgn

FRA-71-19.10

***ITEM 622 - PORTABLE BARRIER, 32", BRIDGE MOUNTED, AS PER PLAN***

*THE CONTRACTOR SHALL UTILIZE AN ANCHORED PORTABLE BARRIER SYSTEM WHERE SPECIFIED IN THE PLANS AND GENERAL NOTES. THE CONTRACTOR IS PERMITTED TO USE PCB-91 OR RM-4.2 SEGMENTS EXCEPT AS NOTED HEREIN. THE USE OF RM-4.2 IS NOT PERMITTED WHERE LESS THAN ONE FOOT OF EDGE DISTANCE (MEASURED FROM THE EDGE OF DECK ALONG THE REMOVAL LINE TO THE NEAREST TOE OF BARRIER) IS PROVIDED. THE CONTRACTOR SHALL UTILIZE PCB-91 OR THE EASI-SET WORLDWIDE TEMPORARY BARRIER (OR APPROVED EQUAL) WHERE LESS THAN ONE FOOT OF EDGE DISTANCE IS PROVIDED.*

*THE FOLLOWING ANCHOR REQUIREMENTS APPLY:*

| | NO. OF ANCHORS REQUIRED (EACH BARRIER SEGMENT) | |
|---|---|---|
| | EDGE DISTANCE, D < 1'-0" | EDGE DISTANCE, D >= 1'-0" |
| PCB-91 | 6 | 3 |
| RM-4.2 | NOT PERMITTED | 2 |
| EASI-SET WORLDWIDE (OR APPROVED EQUAL) | SEE MANUFACTURER RECOMMENDATIONS | SEE MANUFACTURER RECOMMENDATIONS |

*ALL LABOR, MATERIALS, TOOLS, EQUIPMENT AND INCIDENTALS TO CONSTRUCT ANCHORED PORTABLE BARRIER INCLUDING APPROVED ALTERNATES AS DESCRIBED ABOVE WILL BE PAID AT THE CONTRACT BID PRICE FOR ITEM 622 - PORTABLE BARRIER, 32", BRIDGE MOUNTED, AS PER PLAN.*

***ITEM SPECIAL - SETTLEMENT PLATFORMS***

*DESCRIPTION:*

*THIS ITEM CONSISTS OF FURNISHING, CONSTRUCTING, AND MAINTAINING SETTLEMENT PLATFORMS WITHIN THE PROPOSED REAR ABUTMENT EMBANKMENT AND/OR MSE WALL BACKFILL AND OBTAINING SETTLEMENT READINGS AS REQUIRED BY THE PLANS OR AS DIRECTED BY THE ENGINEER. AT THE OPTION AND THE EXPENSE OF THE CONTRACTOR, ADDITIONAL SETTLEMENT PLATFORMS MAY BE INSTALLED AT LOCATIONS APPROVED BY THE ENGINEER. SETTLEMENT READINGS SHALL BE TAKEN WEEKLY DURING CONSTRUCTION AND DURING THE WAITING PERIOD. THE READINGS SHALL BE PLOTTED ON GRAPH PAPER PRESENTING DEFORMATION (ON THE NEGATIVE Y-AXIS) AND FILL HEIGHT (ON THE POSITIVE Y-AXIS) VERSUS TIME (ON THE X-AXIS). IN ORDER TO CREATE THE GRAPH, USE THE SETTLEMENT PLATFORM SPREADSHEET LOCATED AT THE LINK BELOW ON THE OGE WEBSITE PUBLICATIONS AND DOCUMENTS SECTION.*

*HTTP://WWW.DOT.STATE.OH.US/GEOTECHNICAL/PAGES/SETTELMENT.ASPX*

*A COPY OF EACH CUMULATIVE PLOT SHALL BE SENT TO THE OFFICE OF GEOTECHNICAL ENGINEERING, ATTENTION: GEOTECHNICAL DESIGN COORDINATOR, AFTER EACH SETTLEMENT READING IS RECORDED.*

***MATERIALS:***

*SOUND LUMBER SUCH AS 19MMM (3/4-INCH) EXTERIOR GRADE PLYWOOD SHALL BE USED FOR THE BASE. THE PIPE SHALL BE 64MM (2-1/2-INCH) STANDARD BLACK PIPE WITH THREADED FITTINGS AS SHOWN ON THE PLANS. A STEEL PLATE 915MM X 915MM X 3.2MM (36" X 36" X 1/8") MAY BE SUBSTITUTED FOR THE LUMBER FOR THE PLATFORMS, AT THE CONTRACTOR'S OPTION.*

***CONSTRUCTION METHODS:***

*THE PLATFORM SHALL CONFORM TO THE DETAILS SHOWN ON THE PLANS. THE PLATFORM SHALL BE SET ON A LEVEL SURFACE. THE PIPE SHALL BE FIRMLY SECURED TO THE PLATFORM AND SHALL BE MAINTAINED IN A PLUMB POSITION DURING PLACEMENT OF THE EMBANKMENT AND/OR MSE WALL CONSTRUCTION. THE PIPE SHALL BE MARKED AT INTERVALS TO FACILITATE MEASUREMENT OF THE DEPTH OF FILL. THE CONTRACTOR SHALL PROTECT SETTLEMENT PLATFORMS FROM CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL STOP WORK IN ANY LOCATION WHERE THE SETTLEMENT PLATFORM HAS BEEN DISTURBED OR DAMAGED. PLATFORMS OR PIPES DAMAGED OR DISPLACED DURING CONSTRUCTION SHALL BE RESTORED TO THEIR PROPER CONDITION AT THE CONTRACTOR'S EXPENSE.*

*THE TOP OF SETTLEMENT PLATFORM PIPE SHALL BE CUT OFF ONE FOOT BELOW THE BOTTOM OF FOOTING ELEVATION OR TWO FEET BELOW THE FINISHED GROUND SURFACE, WHICHEVER IS APPLICABLE.*

***CRITERIA:***

*REMAINING SETTLEMENT (AFTER WAITING PERIOD) IS LESS THAN OR EQUAL TO 1 INCH FOR WALLS AND EMBANKMENTS.*

***WAITING PERIOD:***

*THE WAITING PERIOD SHALL NOT BE CONSIDERED TO BEGIN UNTIL ALL FILL IS CONSTRUCTED TO THE BOTTOM OF FOOTING ELEVATIONS. THE FILL SHALL CONSISTS OF THE PROPOSED MSE WALL BACKFILL OR EMBANKMENT CONSTRUCTED TO THE ENTIRE LATERAL EXTENTS OF THE PHASED CONSTRUCTION WITHIN ONE FOOT OF THE PROPOSED VERTICAL EXTENTS.*

*NO CONSTRUCTION OF STRUCTURES (INCLUDING FOUNDATIONS, LIMITED CONSTRUCTION OF PILE DRIVING SPECIFIED HEREIN, MSE WALL TOP PANELS, COPING, ETC.) OR PAVING OF ROADWAYS SHALL BEGIN UNTIL CONFIRMATION HAS BEEN RECEIVED FROM THE ENGINEER THAT THE CRITERIA TO END THE WAITING PERIOD HAVE BEEN MET.*


*IT IS ANTICIPATED THAT AFTER COMPLETION OF MSE WALL AND/OR EMBANKMENT CONSTRUCTION, A 24 CALENDAR DAY WAITING PERIOD AT THE REAR ABUTMENT (MSE WALL 1) AND A 30 CALENDAR DAY WAITING PERIOD AT THE FORWARD ABUTMENT WILL BE REQUIRED BEFORE THE SETTLEMENT RATE THRESHOLD IS ACHIEVED.*

***METHOD OF MEASUREMENT**:*

*THE NUMBER OF SETTLEMENT PLATFORMS TO BE PAID FOR SHALL BE THE ACTUAL NUMBER OF SETTLEMENT PLATFORMS COMPLETED, MAINTAINED, AND ACCEPTED BY THE ENGINEER.*

***BASIS OF PAYMENT:***

*PAYMENT SHALL BE MADE AT THE CONTRACT UNIT PRICE EACH FOR ITEM SPECIAL - SETTLEMENT PLATFORMS WHICH IS COMPENSATION FOR CONSTRUCTING, MAINTAINING, AND MONITORING THE SETTLEMENT PLATFORMS INCLUDING FURNISHING ALL LABOR, MATERIAL, EQUIPMENT, TOOLS AND INCIDENTALS NECESSARY TO COMPLETE THE WORK. PAYMENT SHALL NOT BE MADE FOR SETTLEMENT PLATFORMS WHICH BECOME USELESS DUE TO DAMAGE CAUSED BY THE CONTRACTOR'S OPERATIONS.*




***SETTLEMENT PLATFORM DETAILS***

***SEQUENCE OF CONSTRUCTION***

*THE PROPOSED BRIDGE WORK (INCLUDING THE APPROACH SLABS AND MSE WALL) SHALL BE COORDINATED WITH OVERALL PROJECT MAINTENANCE OF TRAFFIC (MOT) PLANS.*

*FOR ADDITIONAL DETAILS REGARDING SEQUENCE OF CONSTRUCTION OF TEMPORARY SHORING, SEE SHEET 17.*

***PHASE 3A***

1. *INSTALL PORTABLE CONCRETE BARRIERS ON NORTHBOUND (RIGHT) AND SOUTHBOUND (LEFT) LANES AND DIVERT TRAFFIC AS SHOWN ON MOT PLANS.*
2. *REMOVE PORTIONS OF THE EXISTING SUPERSTRUCTURE AS SHOWN IN THE PLANS.*
3. *INSTALL TEMPORARY SHORING.*
4. *REMOVE PORTIONS OF EXISTING SUBSTRUCTURE.*
5. *COMPLETE PHASE 3A CONSTRUCTION.*

***PHASE 3B***

1. *INSTALL PORTABLE CONCRETE BARRIER ON PHASE 3A CONSTRUCTION AND DIVERT SOUTHBOUND TRAFFIC TO MOT PHASE 3B.*
2. *REMOVE REMAINING PORTIONS OF EXISTING SOUTHBOUND (LEFT) BRIDGE.*
3. *CONSTRUCT PHASE 3B AND CLOSURE POUR.*

***PHASE 4A***

1. *INSTALL PORTABLE CONCRETE BARRIERS ON NORTHBOUND (RIGHT) AND SOUTHBOUND (LEFT) LANES AND DIVERT TRAFFIC AS SHOWN ON MOT PLANS.*
2. *REMOVE PORTIONS OF THE EXISTING NORTHBOUND SUPERSTRUCTURE AS SHOWN IN THE PLANS.*
3. *INSTALL TEMPORARY SHORING.*
4. *REMOVE PORTIONS OF EXISTING SUBSTRUCTURE.*
5. *COMPLETE PHASE 4A CONSTRUCTION.*

***PHASE 4B***

1. *INSTALL PORTABLE CONCRETE BARRIER ON PHASE 4A CONSTRUCTION AND DIVERT NORTHBOUND TRAFFIC TO MOT PHASE 4B.*
2. *REMOVE REMAINING PORTIONS OF EXISTING NORTBOUND (RIGHT) BRIDGE.*
3. *CONSTRUCT PHASE 4B AND CLOSURE POUR.*

***ABBREVIATION LEGEND:***

*ABUT. - ABUTMENT*
*ADT - AVERAGE DAILY TRAFFIC*
*ADTT - AVERAGE DAILY TRUCK TRAFFIC*
*APPR. - APPROACH*
*B OR BOT. - BOTTOM*
*BM - BENCHMARK*
*BRG. - BEARING*
*℄ - CENTERLINE*
*C/C - CENTER TO CENTER*
*C.I.P. - CAST-IN-PLACE*
*C.J. - CONSTRUCTION JOINT*
*CLR. - CLEAR*
*C&MS - CONSTRUCTION AND MATERIAL SPECIFICATIONS*
*CONST. - CONSTRUCTION*
*C.P. - CLOSURE POUR*
*CVN - CHARPY V-NOTCH*
*DIA. - DIAMETER*
*DIST. - DISTANCE*
*DND - DO NOT DISTURB*
*DWG. - DRAWING*
*E.F. - EACH FACE*
*EL. OR ELEV. - ELEVATION*
*EOP - EDGE OF PAVEMENT*
*EQ. - EQUAL*
*EST. - ESTIMATED*
*EX. - EXISTING*
*EXP. - EXPANSION*
*F.A. - FORWARD ABUTMENT*
*F/F - FACE TO FACE*
*FT. - FOOT OR FEET*
*FTG. - FOOTING*
*FWD. - FORWARD*
*HMWM - HIGH MOLECULAR WEIGHT METHACRYLATE*
*IN. - INCH*
*JT. - JOINT*
*LT. - LEFT*
*MAX. - MAXIMUM*
*MISC. - MISCELLANEOUS*
*MSE - MECHANICALLY STABILIZED EARTH*
*NB - NORTHBOUND*
*NO. - NUMBER*
*N.P.C.P.P - NON-PERFORATED CORRUGATED PLASTIC PIPE*
*O/O - OUT TO OUT*
*P.C.P.P. - PERFORATED CORRUGATED PLASTIC PIPE*
*P.E.J.F. - PREFORMED EXPANSION JOINT FILLER*
*PG - PROFILE GRADE*
*PGL - PROFILE GRADE LINE*
*PROP. - PROP.*
*R - RADIUS*
*R.C. - REFERENCE CHORD*
*REF. - REFERENCE*
*RNDG. - ROUNDING*
*RT. - RIGHT*
*R/W - RIGHT OF WAY*
*SB - SOUTHBOUND*
*SCD - STANDARD CONSTRUCTION DRAWING*
*SER. - SERIES*
*SHD. OR SHLDR. - SHOULDER*
*SPA. - SPACE OR SPACES*
*STA. - STATION*
*STD. - STANDARD*
*STR - STRAIGHT*
*S.U.P. - SHARED USE PATH*
*T - TOP*
*T/T - TOE TO TOE*
*TEMP - TEMPORARY*
*T&B - TOP AND BOTTOM*
*TBR - TO BE REMOVED*
*TBRO - TO BE RELOCATED BY OTHERS*
*TBRR - TO BE REMOVED AND REPLACED*
*TYP. - TYPICAL*
*U.N.O. - UNLESS NOTED OTHERWISE*
*VAR. - VARIES*
*W.R.T. - WITH RESPECT TO*

# STRUCTURE GENERAL NOTES (2 OF 2)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MJR |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 5 |
| TOTAL | 65 |
| SHEET | P. 425 |
| TOTAL | 618 |

# ESTIMATED QUANTITIES

| CALC. | DATE | CHK'D | DATE |
|---|---|---|---|
| MJR | 4/4/24 | XXX | XX/YY/ZZ |

| ITEM | ITEM EXT. | TOTAL LEFT | TOTAL RIGHT | UNIT | DESCRIPTION | LEFT BRIDGE FRA-71-24.46 L (SFN 250XXXX) | | | | RIGHT BRIDGE FRA-71-24.46 R (SFN 250XXXX) | | | | SHEET REF. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | ABUT. | PIERS | SUPER. | GEN. | ABUT. | PIERS | SUPER. | GEN. | |
| 202 | 11003 | | | LS | STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN | | | | | | | | | 4/65 |
| 202 | 22900 | | | SY | APPROACH SLAB REMOVED | | | | | | | | | |
| 503 | 11101 | | | LS | COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN | | | | | | | | | 4/65 |
| 503 | 21300 | | | LS | UNCLASSIFIED EXCAVATION | | | | | | | | | |
| 505 | 11100 | | | LS | PILE DRIVING MOBILIZATION | | | | | | | | | |
| 507 | 00600 | | | FT | 14" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN | | | | | | | | | |
| 507 | 00650 | | | FT | 14" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED | | | | | | | | | |
| 507 | 92201 | | | FT | PREBORED HOLES, AS PER PLAN | | | | | | | | | 4/65 |
| 509 | 10000 | | | LB | EPOXY COATED STEEL REINFORCEMENT | | | | | | | | | |
| 509 | 30020 | | | FT | NO. 4 DEFORMED GFRP REINFORCEMENT | | | | | | | | | |
| 511 | 33500 | | | EA | SEMI-INTEGRAL DIAPHRAGM GUIDE | | | | | | | | | |
| 511 | 34446 | | | CY | CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK | | | | | | | | | |
| 511 | 34450 | | | CY | CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPET) | | | | | | | | | |
| 511 | 44112 | | | CY | CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT NOT INCLUDING FOOTING | | | | | | | | | |
| 511 | 46512 | | | CY | CLASS QC1 CONCRETE WITH QC/QA, FOOTING | | | | | | | | | |
| 512 | 10100 | | | SY | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) | | | | | | | | | |
| 512 | 33000 | | | SY | TYPE 2 WATERPROOFING | | | | | | | | | |
| 513 | 10280 | | | LB | STRUCTURAL STEEL MEMBERS, LEVEL 4 | | | | | | | | | |
| 513 | 20000 | | | EA | WELDED STUD SHEAR CONNECTORS | | | | | | | | | |
| 514 | 00060 | | | SF | FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT | | | | | | | | | |
| 514 | 00066 | | | SF | FIELD PAINTING STRUCTURAL STEEL, FINISH COAT | | | | | | | | | |
| 516 | 13600 | | | SF | 1" PREFORMED EXPANSION JOINT FILLER | | | | | | | | | |
| 516 | 13900 | | | SF | 2" PREFORMED EXPANSION JOINT FILLER | | | | | | | | | |
| 516 | 14020 | | | FT | SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL | | | | | | | | | |
| 516 | 44300 | | | EA | ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), (18" x 19" x 4.504" WITH 14" x 26" x 2.5" TOP LOAD PLATE AND 19" x 20" x 2.0" BOT. LOAD PLATE AND HP 10x42 PEDESTAL) | | | | | | | | | 32/65 |
| 518 | 21050 | | | SY | POROUS BACKFILL WITH GEOTEXTILE FABRIC | | | | | | | | | |
| 518 | 40000 | | | FT | 6" PERFORATED CORRUGATED PLASTIC PIPE | | | | | | | | | |
| 518 | 40010 | | | FT | 6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS | | | | | | | | | |
| 523 | 20001 | | | EA | DYNAMIC LOAD TESTING, AS PER PLAN | | | | | | | | | 4/65 |
| 523 | 20501 | | | EA | RESTRIKE, AS PER PLAN | | | | | | | | | 4/65 |
| 526 | 30000 | | | SY | REINFORCED CONCRETE APPROACH SLABS (T=17") | | | | | | | | | |
| 526 | 90030 | | | FT | TYPE C INSTALLATION | | | | | | | | | |
| 867 | 00100 | | | LS | TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL | | | | | | | | | |
| SPECIAL | 53000400 | | | EA | SPECIAL - STRUCTURES - SETTLEMENT PLATFORMS | | | | | | | | | 5/65 |

***NOTES:***

1. *UNLESS NOTED OTHERWISE, ALL PAY ITEMS ARE INCLUDED IN THE FUNDING PARTICIPATION SPLIT CODE XX/YY/ZZ.*
2. *FOR MSE WALL ESTIMATED QUANTITIES, SEE SHEET 59.*

STRUCTURE ESTIMATED QUANTITIES
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

SFN TBD

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | DBL |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 6 | 65 |


| SHEET | TOTAL |
|---|---|
| P. 426 | 618 |

FRA-71-19.10


MODEL: Estimated Quantities PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:43:54 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCfx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SQ001.dgn





**PHASE 3A REMOVAL**




**PHASE 3A CONSTRUCTION**




**PHASE 3B REMOVAL**




**PHASE 3B CONSTRUCTION**

**LEGEND:**

- ▨ - *ITEM 202 - STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN*
- A - *VARIES 0" TO 8 13/16"*
- B - *I-71 SB ACCELERATION LANE FROM SINCLAIR ENTRANCE RAMP VARIES, 6'-7"± TO 2'-10"± FROM EX. FWD. ABUT. ℄ BRG. TO EX. REAR ABUT. ℄ BRG. (SEE NOTE 5)*
- C - *SHOULDER VARIES, 3'-7½"± TO 2'-7½"± FROM EX. FWD. ABUT. ℄ BRG. TO EX. REAR ABUT. ℄ BRG. (SEE NOTE 5)*

**NOTES:**


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *FINISHING MACHINE SHALL NOT EXTEND BEYOND TOE (TRAFFIC SIDE) OF ANCHORED BARRIER, AS PER PLAN*
3. *PORTABLE BARRIER INCLUDED WITH ROADWAY QUANTITIES. SEE SHEET 5 FOR ADDITIONAL NOTES INCLUDING ANCHORAGE REQUIREMENTS.*
4. *PHASE REMOVAL LINES ARE SET BASED UPON THE ROADWAY ALIGNMENT (℄ CONST. I-71). THE REMOVAL LIMITS WILL VARY AS THE EXISTING SLAB LIMITS ARE NOT ALWAYS CONCENTRIC (A.K.A. PARALLEL) TO THE ℄CONST. I-71 ALIGNMENT. THE INTENT IS TO PROVIDE A CONSTANT EDGE DISTANCE OF 1'-0" FROM THE PHASE REMOVAL LINES TO THE BACK OF THE ANCHORED PORTABLE BARRIER.WHEREAS THE PROPOSED BRIDGE CONSTRUCTION USES STRAIGHT (I.E. NON-CURVED) PHASED CONSTRUCTION JOINTS, GIRDERS AND DECK EDGES. PHASE CONSTRUCTION JOINTS ARE PARALLEL TO THE PROPOSED BRIDGE REFERENCE CHORD.*
5. *REFER TO THE MAINTENANCE OF TRAFFIC PLANS FOR ADDITIONAL INFORMATION AND TEMPORARY STRIPING.*
6. *CROSSFRAMES NOT SHOWN FOR CLARITY. DO NOT PERMANENTLY ATTACH INTERMEDIATE CROSSFRAMES IN THE CLOSURE POUR LOCATION UNTIL THE CONCRETE POURS ON BOTH SIDES OF THE CLOSURE POUR LOCATION HAVE BEEN COMPLETED.*
7. *FOR SEQUENCE OF CONSTRUCTION, SEE SHEET 5.*

# STAGED CONSTRUCTION DETAILS (1 OF 2)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 7 |
| TOTAL | 65 |
| SHEET | P. 427 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:44:08 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SC001.dgn





**PHASE 4A REMOVAL**




**PHASE 4A CONSTRUCTION**




**PHASE 4B REMOVAL**




**PHASE 4B CONSTRUCTION**

**LEGEND:**

- ITEM 202 - STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN
- A - VARIES 0" TO $8\frac{13}{16}$"
- B - SHOULDER VARIES, 2'-0" MIN. REFER TO MOT PLANS FOR TEMORARY STRIPING (SEE NOTE 5)
- C - GORE VARIES, 0'-0" MIN. REFER TO MOT PLANS FOR TEMORARY STRIPING (SEE NOTE 5)
- D - I-71 SB ACCELERATION LANE FROM SINCLAIR ENTRANCE RAMP VARIES, 12'-0"± TO 10'-$5\frac{1}{2}$"± (SEE NOTE 5)
- E - SHOULDER VARIES, 9'-$1\frac{3}{8}$"± MIN. REFER TO MOT PLANS FOR TEMORARY STRIPING (SEE NOTE 5)

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. FINISHING MACHINE SHALL NOT EXTEND BEYOND TOE (TRAFFIC SIDE) OF ANCHORED BARRIER, AS PER PLAN
3. PORTABLE BARRIER INCLUDED WITH ROADWAY QUANTITIES. SEE SHEET 5 FOR ADDITIONAL NOTES INCLUDING ANCHORAGE REQUIREMENTS.
4. PHASE REMOVAL LINES ARE SET BASED UPON THE ROADWAY ALIGNMENT (℄ CONST. I-71). THE REMOVAL LIMITS WILL VARY AS THE EXISTING SLAB LIMITS ARE NOT ALWAYS CONCENTRIC (A.K.A. PARALLEL) TO THE ℄CONST. I-71 ALIGNMENT. THE INTENT IS TO PROVIDE A CONSTANT EDGE DISTANCE OF 1'-0" FROM THE PHASE REMOVAL LINES TO THE BACK OF THE ANCHORED PORTABLE BARRIER.WHEREAS THE PROPOSED BRIDGE CONSTRUCTION USES STRAIGHT (I.E. NON-CURVED) PHASED CONSTRUCTION JOINTS, GIRDERS AND DECK EDGES. PHASE CONSTRUCTION JOINTS ARE PARALLEL TO THE PROPOSED BRIDGE REFERENCE CHORD.
5. REFER TO THE MAINTENANCE OF TRAFFIC PLANS FOR ADDITIONAL INFORMATION AND TEMPORARY STRIPING.
6. CROSSFRAMES NOT SHOWN FOR CLARITY. DO NOT PERMANENTLY ATTACH INTERMEDIATE CROSSFRAMES IN THE CLOSURE POUR LOCATION UNTIL THE CONCRETE POURS ON BOTH SIDES OF THE CLOSURE POUR LOCATION HAVE BEEN COMPLETED.
7. FOR SEQUENCE OF CONSTRUCTION, SEE SHEET 5.

# STAGED CONSTRUCTION DETAILS (2 OF 2)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 8 |
| TOTAL | 65 |
| SHEET | P. 428 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:44:23 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SC002.dgn




**PLAN - RIGHT BRIDGE (REAR ABUTMENT)**
*(TEMPORARY SHORING NOT SHOWN FOR CLARITY)*




**A/9 SECTION**




**ELEVATION - RIGHT BRIDGE (REAR ABUTMENT)**
*(TEMPORARY SHORING NOT SHOWN FOR CLARITY)*

**LEGEND:**

- PHASE 4A REMOVAL
- PHASE 4B REMOVAL

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. PHASE REMOVAL LINE IS PARALLEL TO ℄ CONST. I-71.
3. ALL REMOVAL SHALL BE PAID UNDER ITEM 202, STRUCTURE REMOVED OVER 20 FOOT SPAN, AS PER PLAN. SEE SHEET 5 FOR ADDITIONAL NOTES.

# EXISTING REAR ABUTMENT REMOVAL DETAILS (RIGHT BRIDGE)
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 9 |
| TOTAL | 65 |
| SHEET | P. 429 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:44:38 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SV007.dgn





***LEGEND:***

- PHASE 4A REMOVAL
- PHASE 4B REMOVAL

***PLAN - RIGHT BRIDGE (FORWARD ABUTMENT)***
*(TEMPORARY SHORING NOT SHOWN FOR CLARITY)*




***ELEVATION - RIGHT BRIDGE (FORWARD ABUTMENT)***
*(TEMPORARY SHORING NOT SHOWN FOR CLARITY)*

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *PHASE REMOVAL LINE IS PARALLEL TO ℄ CONST. I-71.*
3. *EXISTING PILES SHALL BE CUT 1'-0" MIN. BELOW THE PROPOSED BOTTOM OF FOOTING ELEVATION.*
4. *ALL REMOVAL SHALL BE PAID UNDER ITEM 202, STRUCTURE REMOVED OVER 20 FOOT SPAN, AS PER PLAN. SEE SHEET 5 FOR ADDITIONAL NOTES.*

# EXISTING FORWARD ABUTMENT REMOVAL DETAILS - RIGHT BRIDGE
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 10 |
| TOTAL | 65 |
| SHEET | P. 430 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:44:53 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SV008.dgn





**LEGEND:**

- PHASE 3A REMOVAL
- PHASE 3B REMOVAL

***PLAN - LEFT BRIDGE (REAR ABUTMENT)***
*(TEMPORARY SHORING NOT SHOWN FOR CLARITY)*




***A 11 SECTION***




***ELEVATION - LEFT BRIDGE (REAR ABUTMENT)***
*(TEMPORARY SHORING NOT SHOWN FOR CLARITY)*

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *PHASE REMOVAL LINE IS PARALLEL TO ℄ CONST. I-71.*
3. *ALL REMOVAL SHALL BE PAID UNDER ITEM 202, STRUCTURE REMOVED OVER 20 FOOT SPAN, AS PER PLAN. SEE SHEET 5 FOR ADDITIONAL NOTES.*

# EXISTING REAR ABUTMENT REMOVAL DETAILS - LEFT BRIDGE
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 11 |
| TOTAL | 65 |
| SHEET | P. 431 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:45:09 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SV006.dgn





***PLAN - LEFT BRIDGE (FORWARD ABUTMENT)***




***A 12 SECTION***

***LEGEND:***

- PHASE 3A REMOVAL
- PHASE 3B REMOVAL




***ELEVATION - LEFT BRIDGE (FORWARD ABUTMENT)***

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *PHASE REMOVAL LINE IS PARALLEL TO ℄ CONST. I-71.*
3. *EXISTING PILES SHALL BE CUT 1'-0" MIN. BELOW THE PROPOSED BOTTOM OF FOOTING ELEVATION.*
4. *ALL REMOVAL SHALL BE PAID UNDER ITEM 202, STRUCTURE REMOVED OVER 20 FOOT SPAN, AS PER PLAN. SEE SHEET 5 FOR ADDITIONAL NOTES.*

# EXISTING FORWARD ABUTMENT REMOVAL DETAILS - LEFT BRIDGE
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 12 |
| TOTAL | 65 |
| SHEET | P. 432 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:45:26 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SV009.dgn




***(PIER REMOVAL, TYPICAL OF ALL 3 PIERS RIGHT BRIDGE NORTHBOUND - PLAN)***




***(PIER REMOVAL, TYPICAL OF ALL 3 PIERS RIGHT BRIDGE NORTHBOUND - ELEVATION)***




| LOCATION | ELEV. A | ELEV. B | ELEV. C |
|---|---|---|---|
| PIER 1 | 896.02± | 893.29± | 873.79± |
| PIER 2 | 896.08± | 893.33± | 873.83± |
| PIER 3 | 896.08± | 893.32± | 873.82± |

***LEGEND:***

= PHASE 4A REMOVAL LIMITS

= PHASE 4B REMOVAL LIMITS

= 1'-6" MIN. BELOW PROP. GROUND LINE FOR PIER 2
1'-0" MIN. BELOW PROP. GROUND LINE FOR PIERS 1 & 3

***NOTES:***


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. ALL REMOVAL SHALL BE PAID UNDER ITEM 202, STRUCTURE REMOVED OVER 20 FOOT SPAN, AS PER PLAN. SEE SHEET 5 FOR ADDITIONAL DETAILS.
3. EXISITNG REINFORCING NOT SHOWN FOR CLARITY, REFER TO RECORD PLANS FOR REINFORCING.
4. ALL EXCAVATION REQUIRED TO REMOVE PORTIONS OF THE EXISTING PIERS SHALL BE INCLUDED FOR PAYMENT UNDER ITEM 503 - UNCLASSIFIED EXCAVATION. REFER TO ROADWAY TYPICAL SECTIONS FOR PROPOSED PAVEMENT BUILD-UP FOR MORSE ROAD.

# EXISTING PIER REMOVAL DETAILS (1 OF 3)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 13 |
| TOTAL | 65 |
| SHEET | P. 433 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:45:38 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SV005.dgn





**PIER 1 REMOVAL, LEFT BRIDGE SOUTHBOUND - PLAN**





**PIER 1 REMOVAL, LEFT BRIDGE SOUTHBOUND - ELEVATION**




**PIER 2 REMOVAL, LEFT BRIDGE SOUTHBOUND - PLAN**




**PIER 2 REMOVAL, LEFT BRIDGE SOUTHBOUND - ELEVATION**

***LEGEND***

= PHASE 3A REMOVAL LIMITS

= PHASE 3B REMOVAL LIMITS

= 1'-6" MIN. BELOW PROP. GROUND LINE FOR PIER 2
1'-0" MIN. BELOW PROP. GROUND LINE FOR PIERS 1 & 3

***NOTES:***


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. ALL REMOVAL SHALL BE PAID UNDER ITEM 202, STRUCTURE REMOVE OVER 20 FOOT SPAN, AS PER PLAN. SEE SHEET 5 FOR ADDITIONAL NOTES.
3. EXISTING REINFORCING NOT SHOWN FOR CLARITY, REFER TO RECORD PLANS FOR REINFORCING.
4. ALL EXCAVATION REQUIRED TO REMOVE PORTIONS OF THE EXISTING PIERS SHALL BE INCLUDED FOR PAYMENT UNDER ITEM 503 - UNCLASSIFIED EXCAVATION. REFER TO ROADWAY TYPICAL SECTIONS FOR PROPOSED PAVEMENT BUILD-UP FOR MORSE ROAD.

# EXISTING PIER REMOVAL DETAILS (2 OF 3)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 14 |
| TOTAL | 65 |
| SHEET | P. 434 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:45:50 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SV003.dgn




***PIER 3 REMOVAL, LEFT BRIDGE SOUTHBOUND - PLAN***




***PIER 3 REMOVAL, LEFT BRIDGE SOUTHBOUND - ELEVATION***

***LEGEND***

= PHASE 3A REMOVAL LIMITS

= PHASE 3B REMOVAL LIMITS

= 1'-6" MIN. BELOW PROP. GROUND LINE FOR PIER 2
1'-0" MIN. BELOW PROP. GROUND LINE FOR PIERS 1 & 3

***NOTES:***

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. ALL REMOVAL SHALL BE PAID UNDER ITEM 202, STRUCTURE REMOVED OVER 20 FOOT SPAN, AS PER PLAN. SEE SHEET 5 FOR ADDITIONAL NOTES.
3. EXISTING REINFORCING NOT SHOWN FOR CLARITY, REFER TO RECORD PLANS FOR REINFORCING.

# EXISTING PIER REMOVAL DETAILS (3 OF 3)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 15 |
| TOTAL | 65 |
| SHEET | P. 435 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:46:02 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SV004.dgn

***ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN***

*1.0 DESIGN SPECIFICATIONS:*

*THIS STRUCTURE CONFORMS TO THE 9TH EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020, THE 2nd EDITION OF THE "AASHTO GUIDE DESIGN SPECIFICATIONS FOR BRIDGE TEMPORARY WORKS", 2017 AND THE ODOT BRIDGE DESIGN MANUAL, 2020, DATED JULY 2025.*

*2.0 OPERATIONAL IMPORTANCE:*

*A LOAD MODIFIER OF 1.0 HAS BEEN ASSUMED FOR THE DESIGN OF TEMPORARY WORKS.*

*3.0 DESIGN DATA:*

*CONCRETE CLASS QC2 - COMPRESSIVE STRENGTH 4.5 KSI (DRILLED SHAFT)*

*STEEL SOLDIER PILES - ASTM A572 GRADE 50 - YIELD STRENGTH 50 KSI*

*STEEL SHEET PILING - ASTM A572 GRADE 50 - YIELD STRENGTH 50 KSI*

*4.0 UNCLASSIFIED EXCAVATION:*

*THIS WORK CONSISTS OF ALL EXCAVATION NECESSARY TO PERFORM THE WORK DESCRIBED IN THE TEMPORARY SHORING WALL PLANS.*

*THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE EXCAVATION LIMITS NECESSARY FOR INSTALLATION OF THE WORK. THE CONTRACTOR MAY NOT EXCAVATE OR WORK OUTSIDE OF THE RIGHT OF WAY UNLESS OTHERWISE SHOWN IN THESE PLANS.*

*5.0 STEEL SOLDIER PILES*

*THE FOLLOWING STEEL PILE SECTIONS ARE INCLUDED IN THE DESIGN OF TEMPORARY SOLDIER PILE AND LAGGING WALLS:*

*STEEL PILES, MISC.: SOLDIER PILES HP14x89*
*STEEL PILES, MISC.: SOLDIER PILES W18x311*
*STEEL PILES, MISC.: SOLDIER PILES W24x176*
*STEEL PILES, MISC.: SOLDIER PILES W24x306*
*STEEL PILES, MISC.: SOLDIER PILES W30x292*

*THIS WORK CONSISTS OF FURNISHING AND PLACING STEEL SOLDIER PILES INTO DRILLED HOLES. FURNISH SOLDIER PILES CONSISTING OF STRUCTURAL STEEL MEMBERS THAT MEET THE PLAN REQUIREMENTS AND CONFORM TO ASTM A572, GRADE 50 IN ACCORDANCE WITH C&MS 711.01. DO NOT FIELD WELD OR SPLICE STEEL SOLDIER PILES.*

*6.0 DRILLED SHAFTS*

*THE FOLLOWING DRILLED SHAFT SIZES ARE INCLUDED IN THE DESIGN OF TEMPORARY SOLDIER PILE AND LAGGING WALLS:*

*DRILLED SHAFTS, 36" DIAMETER, ABOVE BEDROCK*
*DRILLED SHAFTS, 42" DIAMETER, ABOVE BEDROCK*

*THIS WORK CONSISTS OF FURNISHING AND INSTALLING DRILLED SHAFTS FOR TEMPORARY SOLDIER PILE AND LAGGING WALLS. THE DRILLED SHAFTS ARE REINFORCED WITH SOLDIER PILES INSTEAD OF REINFORCING STEEL CAGES. THE SOLDIER PILES EXTEND ABOVE THE TOP OF THE DRILLED SHAFT. FURNISH AND INSTALL THE DRILLED SHAFTS IN ACCORDANCE WITH C&MS 524 EXCEPT AS MODIFIED AND SUPPLEMENTED BELOW.*

*THE BOTTOM OF THE DRILLED SHAFT EXCAVATION SHALL BE AS CLEAN AS PRACTICAL PRIOR TO CONCRETE PLACEMENT. THE DRILLED SHAFT EXCAVATION SHALL BE INSPECTED BY THE ENGINEER IMMEDIATELY BEFORE THE CONCRETE IS PLACED. NO CONCRETE SHALL BE PLACED DURING INCLEMENT WEATHER CONDITIONS WHICH PROHIBIT A THOROUGH INSPECTION.*

*EXCAVATE THE HOLE FOR THE DRILLED SHAFT WITHIN 3 INCHES OF THE PLAN LOCATION. PLACE THE SOLDIER PILE WITHIN THE HOLE SO IT IS VERTICAL AND NOT INCLINED MORE THAN 1 INCH BETWEEN TOP TO BOTTOM. PLACE THE SOLDIER PILES SO THAT THE FLANGES ARE PARALLEL TO THE CENTERLINE OF THE ROW OF DRILLED SHAFTS. DO NOT ALLOW THE ORIENTATION OF THE FLANGES TO VARY BY MORE THAN 10 DEGREES. SUPPORT THE SOLDIER PILE SO THAT IT DOES NOT MOVE DURING CONCRETE PLACEMENT.*

*USE CLASS QC1 CONCRETE ACCORDING TO C&MS 511. PLACE CONCRETE TO THE ELEVATION FOR THE TOP OF THE DRILLED SHAFT. THE CONTRACTOR MAY PLACE CONCRETE USING THE FREE FALL METHOD PROVIDED THE DEPTH OF WATER IS LESS THAN 6 INCHES AND THE CONCRETE FALLS WITHOUT STRIKING THE SIDES OF THE HOLE. POURING CONCRETE ALONG THE WEB OF THE SOLIDER PILE IS ACCEPTABLE.*

*6.0 DRILLED SHAFTS CONTINUED...*

*CHECK THE POSITION, THE VERTICAL ALIGNMENT AND ORIENTATION OF THE SOLDIER PILE IMMEDIATELY CONCRETE PLACEMENT. MAKE CORRECTIONS AS NECESSARY TO MEET THE ABOVE TOLERANCES. FILL THE HOLE ABOVE THE BOTTOM OF THE DRILLED SHAFT TO THE EXISTING GROUND SURFACE WITH ITEM C&MS 613 LOW STRENGTH MORTAR (LSM) BACKFILL.*

*REMOVE CONCRETE AND LSM AS NECESSARY FROM AROUND THE SOLDIER PILE IN ORDER TO PLACE THE LAGGING. PLACE LAGGING SO THAT THE SOLDIER PILE FLANGE OVERLAPS THE ENDS OF THE LAGGING BY AT LEAST 3 INCHES AT BOTH ENDS OF THE LAGGING. WAIT AT LEAST 12 HOURS AFTER PLACING CONCRETE IN THE DRILLED SHAFTS BEFORE PLACING LAGGING.*

*SEQUENCE OF INSTALLATION: INSTALL THE DRILLED SHAFTS IN SEQUENCE SUCH THAT NO DRILLED SHAFT IS INSTALLED ADJACENT TO EITHER AN OPEN DRILLED SHAFT EXCAVATION OR A DRILLED SHAFT IN WHICH THE CONCRETE HAS LESS THAN A 48-HOUR CURE. INSTALLING THE SHAFTS IN AN ALTERNATING SEQUENCE OR ANY OTHER SEQUENCE THAT MEETS THESE CRITERIA IS PERMISSIBLE.*

*PROTECTION OF UNATTENDED OPEN SHAFTS: COVER UNATTENDED OPEN SHAFTS. USE TEMPORARY COVERS OF ADEQUATE STRENGTH TO PREVENT A PERSON OR ANIMAL FROM FALLING IN. LEAVE NO DRILLED SHAFT EXCAVATION UN-POURED OVERNIGHT.*

*THE CONTRACTOR IS RESPONSIBLE FOR THE MEANS AND METHODS USED TO CONSTRUCT THE DRILLED SHAFTS AND PLACE LAGGING. ANY TEMPORARY GRADING, EXCAVATION, EMBANKMENT, AGGREGATE, DRAINAGE, SHEETING, ETC. NEEDED TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE CONTRACT LUMP SUM PRICE FOR ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN. NO SEPARATE PAYMENT WILL BE MADE.*

*7.0 RETAINING WALL, TIMBER LAGGING:*

*THIS WORK CONSISTS OF FURNISHING AND PLACING TIMBER LAGGING BETWEEN THE SOLDIER PILES AS TEMPORARY SUPPORT FOR THE RETAINED SOIL. FURNISH TIMBER LAGGING CONSISTING OF CONSTRUCTION GRADE, UNTREATED HARDWOOD WITH A MINIMUM THICKNESS OF 3 INCHES UNLESS OTHERWISE SHOWN IN THE PLANS. TO PERMIT DRAINAGE, PROVIDE ¼ TO ½-INCH SPACES BETWEEN THE LAGGING BOARDS USING ⅜-INCH THICK SPACER BLOCKS OR OTHER MEANS ACCEPTABLE TO THE ENGINEER. PLACE THE LAGGING BOARDS BETWEEN THE FLANGES OF THE SOLDIER PILES AND BEARING AGAINST THE FLANGES ON THE EXPOSED SIDE OF THE WALL SO THAT THE SOLIDER PILE FLANGE OVERLAPS THE END OF THE LAGGING BY AT LEAST 3 INCHES AT BOTH ENDS OF THE LAGGING BOARDS. PERFORM EXCAVATION FOR PLACEMENT OF THE LAGGING IN SUCH A MANNER THAT THE LAGGING IS TIGHT AGAINST THE EXCAVATION CUT FACE. BACKFILL ANY VOIDS BEHIND THE LAGGING WITH A SUITABLE COMPACTED GRANULAR MATERIAL CONFORMING TO C&MS 703.16.C ACCEPTABLE TO THE ENGINEER. THE COST OF ANY SUCH BACKFILLING REQUIRED, INCLUDING MATERIAL, PLACEMENT AND COMPACTION, IS INCIDENTAL TO THE CONTRACT LUMP SUM PRICE FOR ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN. NO SEPARATE PAYMENT WILL BE MADE.*

*THE SAME SPECIES SHALL BE USED FOR ALL THE TIMBER MEMBERS REQUIRED. THE TIMBER MEMBERS SHALL BE OF A GRADE AND TYPE WITH AN ALLOWABLE EXTREME FIBER STRESS IN BENDING OF A MINIMUM OF 1250 PSI AND ALLOWABLE STRESS IN SHEAR OF A MINIMUM OF 85 PSI. THE WOOD SHALL BE SEASONED, SOUND, AND FREE FROM DECAY AND INSECT ATTACK, WITHOUT LOOSE AND/OR CLUTTER KNOTS. THE TIMBER LAGGING USED SHALL CONFORM TO THE REQUIREMENTS SHOWN IN THE PLANS. IF THE LAGGING USED AT ANY LOCATION IS FOUND TO BE INADEQUATE, THE CONTRACTOR IS RESPONSIBLE FOR ALL CORRECTIVE MEASURES. LAGGING MAY BE FIELD CUT.*

*8.0 ENGINEER DESIGNED TEMPORARY SHEETING:*

*FOR LOCATIONS OF TEMPORARY SHEET PILING REFER TO SHEET 17. STEEL SHEET PILING SHALL CONFORM TO ASTM A572 GRADE 50 WITH A MINIMUM YIELD STRENGTH OF 50 KSI, A MINIMUM SECTION MODULUS OF 48.5 IN3/FT, AND MINIMUM MOMENT OF INERTIA OF 361.22 IN4/FT. REFER TO THE TABLE BELOW FOR DESIGN REQUIREMENTS.*

*DESIGN CRITERIA:*
*MAXIMUM RETAINED HEIGHT, H: 9'-6"*
*EARTH PRESSURE: ACTIVE (Ka)*
*LIVE LOAD SURCHARGE: 250 PSF (UNFACTORED)*
*MAXIMUM PERMITTED DEFLECTION: 1%H*

*9.0 ENGINEER DESIGNED TEMPORARY SHEETING:*

*IN ADDITION TO THE LOCATIONS DEPICTED IN THE PLANS, TEMPORARY SHEETING MAY BE REQUIRED AT VARIOUS LOCATIONS/STAGES TO CONSTRUCT THE PROPOSED BRIDGE WORK. THE CONTRACTOR IS PERMITTED TO USE THE DESIGN SHOWN IN SECTION 8.0 PROVIDED THE THE USE DOES NOT EXCEED THE DESIGN CRITERIA SHOWN IN SECTION 8.0. ELSE THE CONTRACTOR SHALL DESIGN, PREPARE AND PROVIDE PLANS IN ACCORDANCE WITH C&MS 501.05 FOR TEMPORARY SUPPORT OF EXCAVATION.*

*10.0 REMOVAL OF TEMPORARY SHORING*

*REMOVE TEMPORARY SHORING WHEN NO LONGER REQUIRED TO SUPPORT THE EXCAVATION. THE CONTRACTOR IS RESPONSIBLE FOR THE MEANS AND METHODS TO REMOVE AND/OR DECONSTRUCT TEMPORARY SHORING. THE CONTRACTOR IS RESPONSIBLE FOR PROTECTING THE EXISTING AND PROPOSED STRUCTURE(S). THE CONTRACTOR SHALL PERFORM DEMOLITION OPERATIONS SUCH THAT THERE IS NOT ANY DAMAGE TO THE NEW STRUCTURE OR TO PORTIONS OF THE EXISTING STRUCTURE BEING TEMPORARILY MAINTAINED. THE USE OF EXPLOSIVES AND HEADACHE BALLS WILL NOT BE PERMITTED FOR ANY DEMOLITION OF TEMPORARY SHORING. UNLESS OTHERWISE NOTED, TEMPORARY SHORING SHALL BE REMOVED TO A MINIMUM OF 1 FOOT BELOW THE PROPOSED GROUND SURFACE AND/OR NEAREST PROPOSED BRIDGE ELEMENT (I.E. MSE LEVELING PAD, ABUTMENT FOOTING, ETC.).*

*STEEL SHEET PILING - LEFT IN PLACE*

*EXTRACTION OF SHEET PILING NEAR TEMPORARY WIRE FACED MSE WALL MAY UNACCEPTABLY DEFORM THE NEARBY TEMPORARY WIRE FACED MSE WALL(S). THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND TEMPORARY WIRE FACED MSE WALL SUPPLIER ON THE SAFE EXTRACTION OF SHEET PILING NEAR SUCH WALLS. THE CONTRACTOR IS PERMITTED TO LEAVE SHEET PILING IN PLACE AS APPROVED BY THE ENGINEER.*

*ALL LABOR, MATERIALS, TOOLS, EQUIPMENT AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE INCLUDED WITH THE CONTRACT THE CONTRACT LUMP SUM PRICE BID FOR ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN.*

*11.0 METHOD OF MEASUREMENT AND PAYMENT:*

*THIS WORK INCLUDES ALL MATERIALS, LABOR, TOOLS, EQUIPMENT AND INCIDENTALS NECESSARY TO FURNISH AND INSTALL TEMPORARY SHORING AS DESCRIBED HEREIN. THE DEPARTMENT WILL PAY FOR THE TEMPORARY SHORING (E.G. SOLDIER PILE AND LAGGING WALLS, SHEET PILE WALLS) AT THE CONTRACT LUMP SUM PRICE BID FOR ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN.*

TEMPORARY SHORING NOTES
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

SFN TBD

SFN TBD

DESIGN AGENCY
Jacobs

| DESIGNER | CHECKER |
|---|---|
| DBL | DBL |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 16 | 65 |

| SHEET | TOTAL |
|---|---|
| P. 436 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:46:15 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SH008.dgn




**TEMPORARY SHORING - PLAN**

## TEMPORARY SHORING - CONSTRUCTION SEQUENCE

### PHASE 3A REMOVAL & CONSTRUCTION

1. REMOVE PORTIONS OF EXISTING FRA-71-24.46 L (SOUTHBOUND) BRIDGE AND A PORTION OF THE EXISTING FRA-71-24.46 R (NORTHBOUND) BRIDGE INCLUDING PORTIONS OF APPROACH SLABS, ABUTMENTS, PIERS, PAVEMENT, MEDIAN BARRIER AND CAPPED MEDIAN CONCRETE SLOPE PROTECTION TO ALLOW FOR INSTALLATION OF TEMPORARY SHORING SYSTEMS.
2. DRILL SHAFTS AND INSTALL SOLDIER PILES (WALL #2, #4, #5 & #6).
3. INSTALL SHEET PILING AS SHOWN IN THE PLANS.
4. EXCAVATE AND INSTALL LAGGING IN TOP-DOWN MANNER TO BOTTOM OF EXCAVATION (ALL WALLS).
5. COMPLETE PHASE 3A ABUTMENT AND MSE WALL #1 CONSTRUCTION.
6. INSTALL THE TEMPORARY WIRE FACED MSE WALLS (B,D, E & F) AND EMBANKMENT TO SUPPORT THE PROPOSED ROADWAY APPROACH EMBANKMENT IN PHASE 3A.
7. COMPLETE PHASE 3A SUPERSTRUCTURE CONSTRUCTION OF BRIDGE, APPROACH SLABS AND APPROACH ROADWAY WORK.

### PHASE 3B REMOVAL & CONSTRUCTION

1. REMOVE REMAINING PORTIONS OF EXISTING FRA-71-24.46 L (SOUTHBOUND) BRIDGE, APPROACH SLABS, ABUTMENT, PIERS, PAVEMENT, LANDSCAPING AND LANDSCAPING WALLS TO ALLOW FOR INSTALLATION OF TEMPORARY SHORING SYSTEMS AND PROPOSED WORK.
2. INSTALL SHEET PILING AS SHOWN IN THE PLANS.
3. EXCAVATE. REMOVE PORTIONS OF TEMPORARY SHORING SYSTEMS (WALLS #5 & WALL #6) FROM PHASE 3A ENCOUNTERED DURING EXCAVATION.
4. COMPLETE PHASE 3B ABUTMENT AND MSE WALL #1 CONSTRUCTION.
5. COMPLETE PHASE 3B SUPERSTRUCTURE CONSTRUCTION OF BRIDGE, APPROACH SLAB AND APPROACH ROADWAY WORK.

### PHASE 4A REMOVAL & CONSTRUCTION

1. REMOVE PORTIONS OF EXISTING FRA-71-24.46 R (NORTHBOUND) BRIDGE, APPROACH SLABS, ABUTMENTS, PIERS, PAVEMENT, MEDIAN BARRIER AND CAPPED MEDIAN CONCRETE SLOPE PROTECTION TO ALLOW FOR INSTALLATION OF TEMPORARY SHORING SYSTEMS.
2. INSTALL SHEET PILING AS SHOWN IN THE PLANS.
3. EXCAVATE. REMOVE PORTIONS OF TEMPORARY SHORING SYSTEMS (WALLS #2 & WALL #4) FROM PHASE 3A ENCOUNTERED DURING EXCAVATION.
4. DRILL SHAFTS AND INSTALL SOLDIER PILES (WALL #1 & WALL #3).
5. EXCAVATE AND INSTALL LAGGING IN TOP-DOWN MANNER TO BOTTOM OF EXCAVATION (ALL WALLS).
6. COMPLETE PHASE 4A ABUTMENT AND MSE WALL #1 CONSTRUCTION.
7. COMPLETE PHASE 4A SUPERSTRUCTURE CONSTRUCTION OF BRIDGE, APPROACH SLAB AND APPROACH ROADWAY WORK.

### PHASE 4B REMOVAL & CONSTRUCTION

1. REMOVE REMAINING PORTIONS OF EXISTING FRA-71-24.46 R (NORTHBOUND) BRIDGE, APPROACH SLABS, ABUTMENT, PIERS, PAVEMENT, LANDSCAPING AND LANDSCAPING WALLS TO ALLOW FOR INSTALLATION OF TEMPORARY SHORING SYSTEMS AND PROPOSED WORK.
2. INSTALL SHEET PILING AS SHOWN IN THE PLANS.
3. EXCAVATE. REMOVE PORTIONS OF TEMPORARY SHORING SYSTEMS (WALLS #1 & WALL #3) FROM PHASE 4A ENCOUNTERED DURING EXCAVATION.
4. COMPLETE PHASE 4B ABUTMENT AND MSE WALL #1 CONSTRUCTION.
5. COMPLETE PHASE 4B SUPERSTRUCTURE CONSTRUCTION OF BRIDGE, APPROACH SLAB AND APPROACH ROADWAY WORK.

## NOTES:


1. FOR ADDITIONAL NOTES, SEE SHEET 16.
2. ALL STATIONS AND OFFSETS SHOWN ARE AT THE CENTERLINE OF SOLDIER PILE AND ALL STATIONS AND OFFSETS ARE BASED ON THE ℄ CONSTRUCTION I-71.
3. RECORD PLANS INDICATE THE FRONT ROW OF EXISTING PILES (12" CIP) AT BOTH THE EXISTING REAR AND FORWARD ABUTMENTS TO BE BATTERED (1H:4V). PILE LOCATIONS SHOWN ARE BASED UPON RECORD PLANS AND SHALL BE CONSIDERED APPROXIMATE. THE ENGINEER HAS ESTABLISHED A TEMPORARY SHORING LAYOUT MINDFUL OF THE EXISTING PILE LOCATIONS, PILE BATTER AND PILE LIMITS TO MITIGATE RISK OF ENCOUNTERING AN EXISTING PILE DURING INSTALLATION OF TEMPORARY SHORING (I.E. DRILLING SHAFTS) AND THE CONSTRUCTION OF PROPOSED WORK (PRIMARILY PROPOSED PILE LAYOUT AT THE PROPOSED FORWARD ABUTMENT). THE DESIGN SHOWN IN THE PLANS ALLOWS FOR PILE/SHAFT RELOCATION RESULTING IN AN INCREASE TO THE PILE/SHAFT SPACING OF 1-FOOT. NOTIFY THE ENGINEER IF CONFLICTS ARE ENCOUNTERED REQUIRING FURTHER RELOCATION. THE ENGINEER WILL PROVIDE RECOMMENDATIONS ON HOW TO PROCEED.

# TEMPORARY SHORING PLAN
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 17 |
| TOTAL | 65 |
| SHEET | P. 437 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:46:40 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A201000 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SH002.dgn
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A201000 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SH002.dgn




***TEMPORARY SHORING "WALL 1" ELEVATION***





***TEMPORARY WIRE FACED MSE "WALL A" (FOR PHASE 4A)***

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *FOR ADDITIONAL SHORING DETAILS AND NOTES, SEE SHEET 16.*
3. *FOR SOLDIER PILE AND LAGGING SCHEDULE, SEE SHEET 21.*
4. *FOR STEEL SHEET PILING INFORMATION, SEE SHEET 16.*
5. *PAYMENT FOR TEMPORARY WIRE FACED MSE WALLS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM BID PRICE FOR ITEM 867, TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL.*
6. *ALL STATIONS AND OFFSETS SHOWN ARE AT THE CENTERLINE OF SOLIDER PILE AND ALL STATIONS AND OFFSETS ARE BASED ON THE ℄ CONSTRUCTION I-71.*

***LEGEND:***

= *TEMPORARY WIRE FACED MSE WALL*




***TEMPORARY SHORING "WALL 2" ELEVATION***





***TEMPORARY WIRE FACED MSE WALL "WALL B" (FOR PHASE 3A)***

TEMPORARY SHORING ELEVATIONS (1 OF 3)
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 18 |
| TOTAL | 65 |
| SHEET | P. 438 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:46:54 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SH003.dgn




***TEMPORARY SHORING "WALL 3" ELEVATION***





***TEMPORARY WIRE FACED MSE "WALL C" (FOR PHASE 4A)***

***LEGEND:***


= TEMPORARY WIRE FACED MSE WALL

***NOTES:***

1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *FOR ADDITIONAL SHORING DETAILS AND NOTES, SEE SHEET 16.*
3. *FOR SOLDIER PILE AND LAGGING SCHEDULE, SEE SHEET 21.*
4. *FOR STEEL SHEET PILING INFORMATION, SEE SHEET 16.*
5. *PAYMENT FOR TEMPORARY WIRE FACED MSE WALLS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM BID PRICE FOR ITEM 867, TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL.*
6. *ALL STATIONS AND OFFSETS SHOWN ARE AT THE CENTERLINE OF SOLIDER PILE AND ALL STATIONS AND OFFSETS ARE BASED ON THE ℄ CONSTRUCTION I-71.*
7. *CONTRACTOR SHALL ADJUST SOLDIER PILE SPACING IF NECESSARY TO AVOID CONFLICT WITH PORTIONS OF EXISTING SUBSTRUCTURE (ABUTMENT AND PILES) DURING INSTALLATION OF TEMPORARY SHORING WALL #3.*




***TEMPORARY SHORING "WALL 4" ELEVATION***





***TEMPORARY WIRE FACED MSE "WALL D" (FOR PHASE 3A)***

TEMPORARY SHORING ELEVATIONS (2 OF 3)
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 19 |
| TOTAL | 65 |
| SHEET | P. 439 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:47:10 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SH004.dgn




## TEMPORARY SHORING "WALL 5" ELEVATION (FOR PHASE 3A)





## TEMPORARY WIRE FACED MSE "WALL E" (FOR PHASE 3A)

### LEGEND:


= TEMPORARY WIRE FACED MSE WALL

### NOTES:

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. FOR ADDITIONAL SHORING DETAILS AND NOTES, SEE SHEET 16.
3. FOR SOLDIER PILE AND LAGGING SCHEDULE, SEE SHEET 21.
4. FOR STEEL SHEET PILING INFORMATION, SEE SHEET 16.
5. PAYMENT FOR TEMPORARY WIRE FACED MSE WALLS SHALL BE INCLUDED IN THE CONTRACT LUMP SUM BID PRICE FOR ITEM 867 - TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL.
6. ALL STATIONS AND OFFSETS SHOWN ARE AT THE CENTERLINE OF SOLDIER PILE AND ALL STATIONS AND OFFSETS ARE BASED ON THE ℄ CONSTRUCTION I-71.
7. CONTRACTOR SHALL ADJUST SOLDIER PILE SPACING NECESSARY TO AVOID CONFLICT WITH PORTIONS OF EXISTING SUBSTRUCTURE (ABUTMENT AND PILES) DURING INSTALLATIONS OF TEMPORARY SHORING WALL #5 & WALL #6.




## TEMPORARY SHORING "WALL 6" ELEVATION (FOR PHASE 3A)




## TEMPORARY WIRE FACED MSE "WALL F" (FOR PHASE 3A)

TEMPORARY SHORING ELEVATIONS (3 OF 3)
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 20 |
| TOTAL | 65 |
| SHEET | P. 440 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:47:26 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SH005.dgn

| TEMPORARY SHORING WALL #1 | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| SOLDIER PILE NUMBER | SOLDIER PILE SIZE | SOLDIER PILE STATION ALONG ℄ CONST. I-71 | SOLDIER PILE OFFSET FROM ℄ CONST. I-71 | TOP OF SOLDIER PILE ELEVATION "A" | TOP OF DRILLED SHAFT ELEVATION "B" | PILE TIP ELEVATION "C" | LENGTH OF DRILLED SHAFT "L" | DRILLED SHAFT DIAMETER, D |
| 1 | HP14x89 | 1311+82.98 | 35.21' RT. | 897.00 | 895.00 | 875.00 | 20'-0" | 3'-0" |
| 2 | HP14x89 | 1311+89.03 | 35.30' RT. | 897.00 | 891.00 | | 20'-0" | 3'-0" |
| 3 | W24x176 | 1311+95.08 | 35.85' RT. | 897.00 | 887.00 | | 25'-0" | 3'-0" |
| 4 | W24x176 | 1312+01.14 | 35.93' RT. | 897.00 | 883.00 | | 25'-0" | 3'-0" |
| 5 | W24x176 | 1312+06.19 | 35.99' RT. | 897.00 | 880.00 | | 25'-0" | 3'-0" |
| 6 | W30x292 | 1312+12.24 | 36.33' RT. | 897.00 | 876.00 | | 40'-0" | 3'-6" |
| 7 | W30x292 | 1312+26.38 | 36.44' RT. | 894.00 | 871.50 | | 40'-0" | 3'-6" |
| 8 | W24x176 | 1312+33.19 | 36.19' RT. | 889.00 | 871.50 | | 25'-0" | 3'-0" |
| 9 | W24x176 | 1312+44.30 | 36.22' RT. | 886.00 | 871.50 | | 25'-0" | 3'-0" |


| TEMPORARY SHORING WALL #2 | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| SOLDIER PILE NUMBER | SOLDIER PILE SIZE | SOLDIER PILE STATION ALONG ℄ CONST. I-71 | SOLDIER PILE OFFSET FROM ℄ CONST. I-71 | TOP OF SOLDIER PILE ELEVATION "A" | TOP OF DRILLED SHAFT ELEVATION "B" | PILE TIP ELEVATION "C" | LENGTH OF DRILLED SHAFT "L" | DRILLED SHAFT DIAMETER, D |
| 1 | HP14x89 | 1311+76.39 | 3.36' RT. | 896.00 | 895.00 | | 25'-0" | 3'-0" |
| 2 | HP14x89 | 1311+82.39 | 3.56' RT. | 896.00 | 891.00 | | 25'-0" | 3'-0" |
| 3 | HP14x89 | 1311+88.40 | 3.76' RT. | 896.00 | 887.00 | | 25'-0" | 3'-0" |
| 4 | W18x311 | 1311+94.93 | 4.29' RT. | 896.00 | 883.00 | | 35'-0" | 3'-0" |
| 5 | W18x311 | 1312+00.39 | 4.47' RT. | 896.00 | 879.50 | | 35'-0" | 3'-0" |
| 6 | W18x311 | 1312+06.40 | 4.63' RT. | 895.00 | 876.00 | | 35'-0" | 3'-0" |
| 7 | W18x311 | 1312+12.40 | 4.79' RT. | 893.00 | 871.50 | | 35'-0" | 3'-0" |
| 8 | W18x311 | 1312+18.41 | 4.94' RT. | 890.50 | 871.50 | | 35'-0" | 3'-0" |
| 9 | W18x311 | 1312+24.41 | 5.07' RT. | 888.50 | 871.50 | | 35'-0" | 3'-0" |
| 10 | W18x311 | 1312+30.42 | 5.20' RT. | 886.00 | 871.50 | | 35'-0" | 3'-0" |
| 11 | W18x311 | 1312+40.43 | 5.39' RT. | 883.50 | 871.50 | | 35'-0" | 3'-0" |

| TEMPORARY SHORING WALL #3 | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| SOLDIER PILE NUMBER | SOLDIER PILE SIZE | SOLDIER PILE STATION ALONG ℄ CONST. I-71 | SOLDIER PILE OFFSET FROM ℄ CONST. I-71 | TOP OF SOLDIER PILE ELEVATION "A" | TOP OF DRILLED SHAFT ELEVATION "B" | PILE TIP ELEVATION "C" | LENGTH OF DRILLED SHAFT "L" | DRILLED SHAFT DIAMETER, D |
| 1 | W24x176 | 1313+80.37 | 36.63' RT. | 897.50 | 885.00 | | 30'-0" | 3'-0" |
| 2 | W24x176 | 1313+95.52 | 36.67' RT. | 897.50 | 884.00 | | 30'-0" | 3'-0" |
| 3 | W24x176 | 1314+01.58 | 36.68' RT. | 897.50 | 886.50 | | 20'-0" | 3'-0" |
| 4 | W24x176 | 1314+07.64 | 36.67' RT. | 897.50 | 890.00 | | 20'-0" | 3'-0" |
| 5 | W24x176 | 1314+13.69 | 36.65' RT. | 897.50 | 893.00 | | 20'-0" | 3'-0" |
| 6 | W24x176 | 1314+19.75 | 36.63' RT. | 897.50 | 894.50 | | 20'-0" | 3'-0" |


| TEMPORARY SHORING WALL #4 | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| SOLDIER PILE NUMBER | SOLDIER PILE SIZE | SOLDIER PILE STATION ALONG ℄ CONST. I-71 | SOLDIER PILE OFFSET FROM ℄ CONST. I-71 | TOP OF SOLDIER PILE ELEVATION "A" | TOP OF DRILLED SHAFT ELEVATION "B" | PILE TIP ELEVATION "C" | LENGTH OF DRILLED SHAFT "L" | DRILLED SHAFT DIAMETER, D |
| 1 | W24x176 | 1313+75.83 | 5.54' RT. | 896.00 | 886.50 | | 30'-0" | 3'-0" |
| 2 | W24x176 | 1313+90.85 | 5.25' RT. | 896.00 | 884.00 | | 30'-0" | 3'-0" |
| 3 | W24x176 | 1313+96.85 | 5.11' RT. | 896.00 | 888.00 | | 20'-0" | 3'-0" |
| 4 | W24x176 | 1314+02.86 | 4.97' RT. | 896.00 | 891.00 | | 20'-0" | 3'-0" |
| 5 | W24x176 | 1314+10.87 | 4.77' RT. | 896.00 | 894.00 | | 20'-0" | 3'-0" |

| TEMPORARY SHORING WALL #5 | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| SOLDIER PILE NUMBER | SOLDIER PILE SIZE | SOLDIER PILE STATION ALONG ℄ CONST. I-71 | SOLDIER PILE OFFSET FROM ℄ CONST. I-71 | TOP OF SOLDIER PILE ELEVATION "A" | TOP OF DRILLED SHAFT ELEVATION "B" | PILE TIP ELEVATION "C" | LENGTH OF DRILLED SHAFT "L" | DRILLED SHAFT DIAMETER, D |
| 1 | HP14x89 | 1311+70.99 | 38.39' LT. | 895.50 | 891.00 | | 20'-0" | 3'-0" |
| 2 | HP14x89 | 1311+76.93 | 38.32' LT. | 895.50 | 887.00 | | 20'-0" | 3'-0" |
| 3 | HP14x89 | 1311+82.87 | 38.26' LT. | 895.50 | 883.00 | | 20'-0" | 3'-0" |
| 4 | W24x176 | 1311+88.81 | 38.68' LT. | 895.50 | 879.00 | | 25'-0" | 3'-0" |
| 5 | W24x176 | 1311+94.75 | 38.64' LT. | 895.50 | 875.00 | | 25'-0" | 3'-0" |
| 6 | W24x306 | 1312+00.69 | 38.69' LT. | 895.50 | 872.50 | | 40'-0" | 3'-0" |
| 7 | W24x306 | 1312+08.61 | 38.66' LT. | 895.50 | 871.50 | | 40'-0" | 3'-0" |
| 8 | W24x176 | 1312+16.28 | 38.56' LT. | 889.50 | 871.50 | | 25'-0" | 3'-0" |
| 9 | W24x176 | 1312+22.22 | 38.56' LT. | 887.50 | 871.50 | | 25'-0" | 3'-0" |
| 10 | W24x176 | 1312+32.12 | 38.58' LT. | 884.50 | 871.50 | | 25'-0" | 3'-0" |

| TEMPORARY SHORING WALL #6 | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| SOLDIER PILE NUMBER | SOLDIER PILE SIZE | SOLDIER PILE STATION ALONG ℄ CONST. I-71 | SOLDIER PILE OFFSET FROM ℄ CONST. I-71 | TOP OF SOLDIER PILE ELEVATION "A" | TOP OF DRILLED SHAFT ELEVATION "B" | PILE TIP ELEVATION "C" | LENGTH OF DRILLED SHAFT "L" | DRILLED SHAFT DIAMETER, D |
| 1 | W24x176 | 1313+63.03 | 38.10' LT. | 889.00 | 884.00 | | 20'-0" | 3'-0" |
| 2 | W24x176 | 1313+70.95 | 38.22' LT. | 895.50 | 883.00 | | 25'-0" | 3'-0" |
| 3 | W24x176 | 1313+80.85 | 38.39' LT. | 895.50 | 883.00 | | 25'-0" | 3'-0" |
| 4 | W24x176 | 1313+90.75 | 38.59' LT. | 895.50 | 889.00 | | 20'-0" | 3'-0" |
| 5 | W24x176 | 1314+02.62 | 38.87' LT. | 895.50 | 892.00 | | 20'-0" | 3'-0" |




**SOLDIER PILE & LAGGING WALL TYPICAL SECTION**




**SECTION A-A**

**NOTES:**

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. ALL STATIONS AND OFFSETS SHOWN ARE AT THE ℄ OF SOLDIER PILE AND ALL STATIONS AND OFFSETS ARE BASED ON THE ℄ CONSTRUCTION I-71.
3. SOLDIER PILES SHALL BE GRADE 50 STEEL.

# SOLDIER PILE SCHEDULE
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.

SFN TBD

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| DBL | MAN |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 21 | 65 |

| SHEET | TOTAL |
|---|---|
| P. 441 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:47:38 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SH006.dgn




**REAR ABUTMENT PLAN**


## LEGEND:

- ○ - PROP. 14" DIA. CAST-IN-PLACE REINFORCED CONCRETE PILE
- ◌ - PROP. 14" DIA. CAST-IN-PLACE REINFORCED CONCRETE PILE WITH PILE SLEEVE
- (XX) - PILE NUMBER
- ◌ - EX. 12" CLOSED END PIPE PILE (SEE NOTE 5)

## NOTES:

1. REAR ABUTMENT ESTIMATED PILE LENGTH = 65'-0".
2. FORWARD ABUTMENT ESTIMATED PILE LENGTH = 65'-0".
3. FOR PILE DRIVING CRITERIA AND UBV, SEE SHEET 4.
4. PREBORE ALL FORWARD ABUTMENT PILES (PILE NUMBERS 107-136) TO ELEVATION 872.00. SEE SHEET 4 FOR ADDITIONAL NOTES.
5. EXISTING PILES AT THE FORWARD ABUTMENT SHALL BE CUT 1'-0" MIN. BELOW THE PROPOSED BOTTOM OF FOOTING ELEVATION. EXISTING PILES IN CONFLICT WITH A PROPOSED PILE(S) SHALL NOTIFY THE ENGINEER IN WRITING TO OBTAIN ENGINEER'S RECOMMENDATION ON RELOCATION OF THE PROPOSED PILE(S).
6. FOR ABBREVIATION LEGEND, SEE SHEET 5.

**RIGHT (NORTHBOUND) PILE LAYOUT**





**FORWARD ABUTMENT PLAN**

# PILE LAYOUT - RIGHT BRIDGE
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 22 |
| TOTAL | 65 |
| SHEET | P. 442 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:47:55 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SO001.dgn




## REAR ABUTMENT PLAN


### LEGEND:

- ○ - PROP. 14" DIA. CAST-IN-PLACE REINFORCED CONCRETE PILE
- ◌ - PROP. 14" DIA. CAST-IN-PLACE REINFORCED CONCRETE PILE WITH PILE SLEEVE
- (XX) - PILE NUMBER
- ◌ - EX. 12" CLOSED END PIPE PILE (SEE NOTE 5)

### NOTES:

1. REAR ABUTMENT ESTIMATED PILE LENGTH = 65'-0".
2. FORWARD ABUTMENT ESTIMATED PILE LENGTH = 65'-0".
3. FOR PILE DRIVING CRITERIA AND UBV, SEE SHEET 4.
4. PREBORE ALL FORWARD ABUTMENT PILES (PILE NUMBERS 69-106) TO ELEVATION 869.00. SEE SHEET 4 FOR ADDITIONAL NOTES.
5. EXISTING PILES AT THE FORWARD ABUTMENT SHALL BE CUT 1'-0" MIN. BELOW THE PROPOSED BOTTOM OF FOOTING ELEVATION. EXISTING PILES IN CONFLICT WITH A PROPOSED PILE(S) SHALL NOTIFY THE ENGINEER IN WRITING TO OBTAIN ENGINEER'S RECOMMENDATION ON RELOCATION OF THE PROPOSED PILE(S).
6. FOR ABBREVIATION LEGEND, SEE SHEET 5.

## LEFT (SOUTHBOUND) PILE LAYOUT





## FORWARD ABUTMENT PLAN

# PILE LAYOUT- LEFT BRIDGE
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 23 |
| TOTAL | 65 |
| SHEET | P. 443 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:48:09 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SO002.dgn





**PLAN - RIGHT BRIDGE**




**PLAN - LEFT BRIDGE**




**A / - SECTION REAR ABUT. FTG.**




**B / 25 SECTION FWD. ABUT. FTG.**

***LEGEND:***

▪ *SEE SECTION FOR REINFORCING SPACING*

*ΔΔ 4-RA804 @ 3 EQ. SPA. = 6'-0" (T&B)*

***MIN. LAP LENGTHS***

*#5 BAR = 3'-1"*
*#8 BAR = 5'-4"*

***NOTES:***


1. *FOR FOUNDATION PLAN/PILE LAYOUT, SEE SHEETS 22 & 23 .*

# FOUNDATION PLAN - REAR ABUTMENT
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 24 |
| TOTAL | 65 |
| SHEET | P. 444 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:48:26 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SO003.dgn




***PLAN - LEFT BRIDGE***




***PLAN - RIGHT BRIDGE***

***LEGEND:***

*Δ - 6-FA5XX (SER., TOP) @ EQ. SPA. = 6'-0"*
*& 6-FA8XX (SER., BOT.), SEE SECTION FOR SPA.*
*ΔΔ - 9-FA601 @ 3 EQ. SPA. = 5'-6" (T&B)*
*- 6-FA5XX (SER., TOP) @ EQ. SPA. = 6'-0"*
*ΔΔΔ & 6-FA8XX (SER., BOT.), SEE SECTION FOR SPA.*

*+ - 6-FA601 @ 9" MAX. = 3'-3" (T&B)*
*++ - 8-FA601 @ 9" MAX. = 3'-7" (T&B)*
*+++ - 8-FA601 @ 9" MAX. = 5'-0" (T&B)*

*■ - SEE SECTION FOR REINFORCING SPACING*

***MIN. LAP LENGTHS***

*#5 BAR = 3'-1"*
*#8 BAR = 5'-4"*

***NOTES:***


1. *FOR FOUNDATION PLAN/PILE LAYOUT, SEE SHEETS 22 & 23.*

FOUNDATION PLAN - FORWARD ABUTMENT
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 25 |
| TOTAL | 65 |
| SHEET | P. 445 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:48:42 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10-I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192_SO004.dgn




## REAR ABUTMENT PLAN - RIGHT BRIDGE

*(PILES NOT SHOWN FOR CLARITY)*




### LEGEND:

*FOR REINFORCING STEEL LEGEND, SEE SHEET 28.*

## REAR ABUTMENT ELEVATION - RIGHT BRIDGE

*(DIMENSIONS AND ELEVATIONS ABOUT ℄ BRG.)*
*(FOOTING REINFORCING AND PRECAST DRAINAGE OUTLET NOT SHOWN FOR CLARITY)*

### MIN. LAP LENGTHS

*#5 BAR: 3'-1"*
*#6 BAR: 4'-0"*
*#8 BAR: 5'-4"*

### NOTES:


1. *FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 22 THRU 31.*
2. *FOR PIPE OUTLET DETAILS SEE SHEET 31.*
3. *PLACE TYPE 2 WATERPROOFING CENTERED ON THE VERTICAL JOINT FROM THE BEAM SEAT TO THE BOTTOM OF FOOTING.*

# REAR ABUTMENT PLAN AND ELEVATION - RIGHT BRIDGE
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 26 |
| TOTAL | 65 |
| SHEET | P. 446 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:48:58 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SR001.dgn




***REAR ABUTMENT PLAN - LEFT BRIDGE***

*(PILES NOT SHOWN FOR CLARITY)*




***REAR ABUTMENT ELEVATION - LEFT BRIDGE***

*(DIMENSIONS AND ELEVATIONS SHOWN ABOUT ℄ BRG.)*
*(FOOTING REINFORCING AND PRECAST DRAIN OUTLET NOT SHOWN FOR CLARITY)*

***LEGEND:***

*FOR REINFORCING STEEL LEGEND, SEE SHEET 28.*

***MIN. LAP LENGTHS***

*#5 BAR: 3'-1"*
*#6 BAR: 4'-0"*
*#8 BAR: 5'-4"*

***NOTES:***

1. *FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 22 THRU 31.*
2. *FOR PIPE OUTLET DETAILS, SEE SHEET 31.*
3. *PLACE TYPE 2 WATERPROOFING CENTERED ON THE VERTICAL JOINT FROM THE BEAM SEAT TO THE BOTTOM OF FOOTING.*

# REAR ABUTMENT PLAN AND ELEVATION - LEFT BRIDGE
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 27 |
| TOTAL | 65 |
| SHEET | P. 447 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:49:14 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SR002.dgn

## *REINF. LEGEND:*


| *REAR LEFT* | *REAR RIGHT* |
|---|---|
| *A: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *N: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *B: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *O: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *C: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *P: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *D: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *Q: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *E: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *R: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *F: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *S: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *G: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *T: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *H: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *U: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *J: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *V: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *K: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *W: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *L: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *X: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *M: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *Y: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |
| *N: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* | *Z: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q"* |




A 26 A 27 **SECTION** *(SEE NOTE 1)*




B 26 B 27 **SECTION** *(SEE NOTE 1)*




C 26 C 27 **SECTION**

### *LEGEND:*

*Δ - 6-#5 BARS (SER., E.F.) @ 12" MAX.*

*ΔΔ - 3-#8 BARS LAP WITH FTG. REINFORCING*

### *NOTES:*


1. *FOR MSE WALL DETAILS AND SEALING LIMITS, SEE SHEETS 59 THRU 61.*
2. *FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 22 THRU 31.*

# REAR ABUTMENT DETAILS
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 28 |
| TOTAL | 65 |
| SHEET | P. 448 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:49:28 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SR003.dgn




***FORWARD ABUTMENT PLAN - RIGHT BRIDGE***

*(PILES NOT SHOWN FOR CLARITY)*




***LEGEND:***

*FOR REINFORCING STEEL LEGEND, SEE SHEET 31.*

***FORWARD ABUTMENT ELEVATION - RIGHT BRIDGE***

*(DIMENSIONS AND ELEVATIONS SHOWN ABOUT ℄ BRG.)*
*(FOOTING REINFORCING AND PRECAST DRAINAGE OUTLET NOT SHOWN FOR CLARITY)*

***MIN. LAP LENGTHS***

*#5 BAR: 3'-1"*
*#6 BAR: 4'-0"*
*#8 BAR: 5'-4"*

***NOTES:***

1. *FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 22 THRU 25.*
2. *MAINTAIN 2" CLR. AROUND 6" N.P.C.P.P. OPENING. FIELD CUT BARS IF REQUIRED.*
3. *FOR PIPE OUTLET DETAILS, SEE SHEET 31.*
4. *PLACE TYPE 2 WATERPROOFING CENTERED ON THE VERTICAL JOINT FROM THE BEAM SEAT TO THE BOTTOM OF FOOTING.*


# FORWARD ABUTMENT PLAN AND ELEVATION - RIGHT BRIDGE

BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 29 |
| TOTAL | 65 |
| SHEET | P. 449 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:49:44 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SF001.dgn




***FORWARD ABUTMENT PLAN - LEFT BRIDGE***

*(PILES NOT SHOWN FOR CLARITY)*




***FORWARD ABUTMENT ELEVATION - LEFT BRIDGE***

*(DIMENSIONS AND ELEVATIONS SHOWN ABOUT ℄ BRG.)*
*(FOOTING REINFORCING AND PRECAST CONCRETE DRAINAGE OUTLET NOT SHOWN FOR CLARITY)*

***MIN. LAP LENGTHS***

*#5 BAR: 3'-1"*
*#6 BAR: 4'-0"*
*#8 BAR: 5'-4"*

***LEGEND:***

*FOR REINFORCING STEEL LEGEND, SEE SHEET 31.*

***NOTES:***

1. *FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 22 THRU 31.*
2. *FOR PIPE OUTLET DETAILS, SEE SHEET 31.*
3. *PLACE TYPE 2 WATERPROOFING CENTERED ON THE VERTICAL JOINT FROM THE BEAM SEAT TO THE BOTTOM OF FOOTING.*

# FORWARD ABUTMENT PLAN AND ELEVATION - LEFT BRIDGE
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 30 |
| TOTAL | 65 |
| SHEET | P. 450 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:49:57 AM PLTDRV: OHDOT_PDF_Ex.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SF002.dgn

## REINF. LEGEND:


| FWD LEFT | FWD RIGHT |
|---|---|
| P: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | A: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| Q: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | B: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| R: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | C: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| S: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | D: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| T: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | E: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| U: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | F: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| V: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | G: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| W: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | H: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| X: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | J: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| Y: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | K: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| Z: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" | L: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| | M: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| | N: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |
| | O: X-SETS OF 2-RA6XX @ ZZ MAX. = Q'-Q" |





**E 29 E 30 SECTION** *(SEE NOTE 1)*




**F 29 F 30 SECTION** *(SEE NOTE 1)*




**TYPICAL DRAIN PIPE OUTLET DETAIL**




**FORWARD ABUTMENT MEDIAN WALL DRAIN PIPE OUTLET DETAIL**

**NOTES:**

1. *FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 22 THRU 31.*

FORWARD ABUTMENT DETAILS
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 31 |
| TOTAL | 65 |
| SHEET | P. 451 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:50:11 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6AA20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SF003.dgn
ctures\SFN_2508192\Sheets\109164_SFN_2508192_SF003.dgn


| TABLE OF ELASTOMERIC BEARING DIMENSIONS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| LOCATION | INTERNAL ELASTOMER LAYER THICKNESS | EXTERNAL ELASTOMER LAYER THICKNESS | STEEL LAMINATE THICKNESS | NO. OF INTERNAL ELASTOMER LAYERS | NO. OF EXTERNAL ELASTOMER LAYERS | NO. OF STEEL LAMINATES | TOTAL BEARING THICKNESS | REACTIONS | | * MAXIMUM DESIGN LOAD |
| | | | | | | | | DL + DW | * LL | |
| LEFT (R.A. & F.A.) | 0.375" | 0.1875" | 0.1046" | 9 | 1 | 9 | 4.504" | 293 k | 118 k | 411 k |
| RIGHT (R.A. & F.A.) | 0.375" | 0.1875" | 0.1046" | 9 | 1 | 9 | 4.504" | 285 k | 113 k | 398 k |

* - LOADS GIVEN ARE SERVICE LOADS WITHOUT IMPACT





**PARTIAL BEARING PLAN AT ABUTMENTS**

(R.A. SHOWN, F.A. SIMILAR)
(BEARING STIFFENER NOT SHOWN FOR CLARITY)





**SECTION**

(R.A. SHOWN, F.A. SIMILAR, NOT TO SCALE)
(EXPANDED POLYSTYRENE OR EXPANDABLE FORMS NOT SHOWN FOR CLARITY)
(BEARING STIFFENER NOT SHOWN FOR CLARITY)




**SECTION**

(EXPANDED POLYSTYRENE OR EXPANDABLE FORMS NOT SHOWN FOR CLARITY)
(BEARING STIFFENER NOT SHOWN FOR CLARITY)




**FIELD DRILLED VENT HOLE PLAN**

(R.A. SHOWN, F.A. SIMILAR)

**NOTES:**


1. ELASTOMERIC BEARINGS: THE ELASTOMER SHALL HAVE A HARDNESS OF 60 DUROMETER. THE BEARINGS WERE DESIGNED IN ACCORDANCE WITH SECTION 14.7.6 (METHOD A) OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS. THE LONG-TERM COMPRESSION PROOF LOAD TEST (AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, DIVISION II, SECTION 18.7.2.6) IS NOT REQUIRED.
2. LOAD PLATES: THE STEEL LOAD PLATE SHALL BE BONDED BY VULCANIZATION TO THE ELASTOMER DURING THE MOLDING PROCESS. THE STEEL LOAD PLATES SHALL BE ASTM A709 GRADE 50 STRUCTURAL STEEL.
3. STEEL UPPER LOAD PLATE, STEEL LOWER LOAD PLATE AND HP10x42 SUPPORT BLOCK SHALL BE CONSIDERED COMPONENTS OF THE ELASTOMERIC BEARING ASSEMBLY. THE COST OF ALL LABOR, EQUIPMENT, MATERIAL AND INCIDENTALS NECESSARY TO FURNISH AND INSTALL THE BEARING ASSEMBLY SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 516 - BEARING DEVICE MISC.: ELASTOMERIC BEARING ASSEMBLY.
4. EACH BEARING SHALL BE SHOP MARKED WITH THE FOLLOWING INFORMATION: FORWARD STATION DIRECTION, LOCATION (REAR ABUTMENT OR FORWARD ABUTMENT) AND BEAM NUMBER. THE MARK SHALL BE PLACED SO THAT IT WILL BE VISIBLE ONCE THE BEARING ASSEMBLY HAS BEEN INSTALLED.
5. WELDING: CONTROL WELDING SO THAT THE PLATE TEMPERATURE AT THE ELASTOMER BONDED SURFACE DOES NOT EXCEED 300°F AS DETERMINED BY USE OF PYROMETRIC STICKS OR OTHER TEMPERATURE MONITORING DEVICES.

# BEARING DETAILS
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 32 |
| TOTAL | 65 |
| SHEET | P. 452 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:50:23 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SB001.dgn




***FRAMING PLAN - RIGHT BRIDGE***

***LEGEND:***

(GXX) - *GIRDER LINE DESIGNATION*

℄ - *0" MIN. TO 8¹³⁄₁₆" MAX.*

***NOTES:***


1. *SEE SHEET 35 FOR GIRDER ELEVATIONS AND FIELD SPLICE DETAILS.*
2. *ALL GIRDERS SHALL BE ORIENTED PARALLEL TO REFERENCE CHORD. ALL INTERMEDIATE CROSSFRAMES SHALL BE PLACED NORMAL TO ℄ GIRDERS.*
3. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
4. *FOR STAGED CONSTRUCTION DETAILS, SEE SHEETS 7 THROUGH 8.*
5. *THE CONTRACTOR SHALL NOT PERMANENTLY ATTACH INTERMEDIATE CROSSFRAMES IN THE CLOSURE POUR LOCATION UNTIL THE CONCRETE POURS ON BOTH SIDE OF THE CLOSURE POUR LOCATION HAVE BEEN COMPLETED. SEE SHEET 37 FOR ADDITIONAL NOTES.*

# FRAMING PLAN - RIGHT BRIDGE
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 33 |
| TOTAL | 65 |
| SHEET | P. 453 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:50:48 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SS003.dgn




## FRAMING PLAN - LEFT BRIDGE

**LEGEND:**

(GXX) - GIRDER LINE DESIGNATION

◔ - 0" MIN. TO 8 13/16" MAX.

**NOTES:**


1. SEE SHEET 35 FOR GIRDER ELEVATIONS AND FIELD SPLICE DETAILS.
2. ALL GIRDERS SHALL BE ORIENTED PARALLEL TO REFERENCE CHORD. ALL INTERMEDIATE CROSSFRAMES SHALL BE PLACED NORMAL TO ℄ GIRDERS.
3. FOR ABBREVIATION LEGEND, SEE SHEET 5.
4. FOR STAGED CONSTRUCTION DETAILS, SEE SHEETS 7 THROUGH 8.
5. THE CONTRACTOR SHALL NOT PERMANENTLY ATTACH INTERMEDIATE CROSSFRAMES IN THE CLOSURE POUR LOCATION UNTIL THE CONCRETE POURS ON BOTH SIDE OF THE CLOSURE POUR LOCATION HAVE BEEN COMPLETED. SEE SHEET 37 FOR ADDITIONAL NOTES.

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:51:02 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SS002.dgn

FRAMING PLAN - LEFT BRIDGE
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 34 |
| TOTAL | 65 |
| SHEET | P. 454 |
| TOTAL | 618 |





## GIRDER ELEVATION





## GIRDER SPLICE ELEVATION

(2 WEB PLATES REQUIRED)
(104 BOLTS REQUIRED)




(1 OUTSIDE PLATE AND 2 INSIDE PLATES REQUIRED AT TOP FLANGE)
(84 FLANGE BOLTS REQUIRED AT TOP FLANGE)

(1 OUTSIDE PLATE AND 2 INSIDE PLATES REQUIRED AT BOTTOM FLANGE)
(96 FLANGE BOLTS REQUIRED AT BOTTOM FLANGE)




## SHEAR CONNECTOR DETAIL

**NOTES:**

1. CVN: WHERE A SHAPE OR PLATE IS DESIGNATED (CVN), FURNISH MATERIAL THAT MEETS THE MINIMUM NOTCH TOUGHNESS REQUIREMENTS SPECIFIED IN C&MS 711.01.
2. WELD ATTACHMENT OF SUPPORTS FOR CONCRETE DECK FINISHING MACHINE TO AREAS OF GIRDER FLANGES DESIGNATED "COMPRESSION". FILLET WELDS TO COMPRESSION FLANGES SHALL BE AT LEAST 1" FROM EDGE OF FLANGE, BE NO MORE THAN 2" LONG, AND BE AT LEAST ¼" FOR THICKNESSES UP TO ¾" OR 5/16" FOR GREATER THAN ¾" THICK.
3. BUTT WELDS AT SHOP SPLICES SHALL BE COMPLETE PENETRATION WELDS. WELD REINFORCEMENT SHALL BE COMPLETELY REMOVED BY GRINDING IN THE DIRECTION OF MAIN STRESS.
4. INSTALL STIFFENERS/CONNECTION PLATES ACCORDING TO C&MS 513.
5. FOR CROSSFRAME DETAILS, SEE SHEET 37.
6. HIGH STRENGTH BOLTS SHALL BE 1"ϕ F3125, GRADE A325, UNLESS NOTED OTHERWISE. PROVIDE TYPE I BOLTS PER C&MS 711.02 FOR ALL GIRDERS. PROVIDE CLASS A SURFACE CONDITION FOR THE CONTACT AREA OF BOLTED FIELD SPLICES.
7. SHEAR CONNECTOR PLACEMENT ON THE FLANGE SPLICE PLATES IS NOT PERMITTED. ADJUST SPACING IF NECESSARY TO AVOID INTERFERENCE WITH SPLICE PLATES AND CONNECTION BOLTS.

**LEGEND:**

(C) - DENOTES COMPRESSION

(T) - DENOTES TENSION

(CS) - INDICATES BUTT WELD SUBJECTED TO COMPRESSION STRESS ONLY

(CP) - INDICATES COMPLETE JOINT PENETRATION WELD

(CVN) - CHARPY V-NOTCH

# GIRDER ELEVATION AND DETAILS
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 35 |
| TOTAL | 65 |
| SHEET | P. 455 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:51:16 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SS001.dgn

| | GIRDERS 2 -6 (LEFT BRIDGE SOUTHBOUND) | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | R.A. | 1/10 SPAN | 2/10 SPAN | 3/10 SPAN | 4/10 SPAN | 1/2 SPAN | 6/10 SPAN | 7/10 SPAN | 8/10 SPAN | 9/10 SPAN | F.A. |
| DEFLECTION DUE TO WEIGHT OF STEEL | 0 | 5/8 | 1 1/8 | 1 9/16 | 1 13/16 | 1 7/8 | 1 3/4 | 1 1/2 | 1 1/8 | 5/8 | 0 |
| DEFLECTION DUE TO STAGED DECK PLACEMENT | 0 | 1 11/16 | 3 3/16 | 4 5/16 | 5 | 5 1/4 | 5 | 4 5/16 | 3 3/16 | 1 11/16 | 0 |
| DEFLECTION DUE TO REMAINING DEAD LOAD | 0 | 3/16 | 5/16 | 3/8 | 7/16 | 1/2 | 7/16 | 3/8 | 5/16 | 3/16 | 0 |
| ADJUSTMENT REQUIRED FOR VERTICAL CURVE | 0 | 1/4 | 1/2 | 5/8 | 3/4 | 7/8 | 3/4 | 3/4 | 1/2 | 3/8 | 0 |
| REQUIRED SHOP CAMBER | 0 | 2 11/16 | 5 | 6 3/4 | 7 15/16 | 8 3/8 | 7 7/8 | 6 7/8 | 5 | 2 13/16 | 0 |


| | GIRDERS 1,7 (LEFT BRIDGE SOUTHBOUND) | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | R.A. | 1/10 SPAN | 2/10 SPAN | 3/10 SPAN | 4/10 SPAN | 1/2 SPAN | 6/10 SPAN | 7/10 SPAN | 8/10 SPAN | 9/10 SPAN | F.A. |
| DEFLECTION DUE TO WEIGHT OF STEEL | 0 | 9/16 | 1 1/16 | 1 7/16 | 1 11/16 | 1 3/4 | 1 11/16 | 1 7/16 | 1 1/16 | 9/16 | 0 |
| DEFLECTION DUE TO STAGED DECK PLACEMENT | 0 | 1 9/16 | 2 15/16 | 3 15/16 | 4 5/8 | 4 13/16 | 4 5/8 | 3 15/16 | 2 15/16 | 1 9/16 | 0 |
| DEFLECTION DUE TO REMAINING DEAD LOAD | 0 | 3/16 | 5/16 | 7/16 | 1/2 | 1/2 | 1/2 | 7/16 | 5/16 | 3/16 | 0 |
| ADJUSTMENT REQUIRED FOR VERTICAL CURVE | 0 | 5/16 | 9/16 | 11/16 | 13/16 | 13/16 | 13/16 | 11/16 | 1/2 | 1/4 | 0 |
| REQUIRED SHOP CAMBER | 0 | 2 1/2 | 4 3/4 | 6 3/8 | 7 1/2 | 7 13/16 | 7 1/2 | 6 7/16 | 4 11/16 | 2 1/2 | 0 |

***CAMBER TABLE (LEFT BRIDGE - SOUTHBOUND)***

| | GIRDERS 9 - 12 - (RIGHT BRIDGE NORTHBOUND) | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | R.A. | 1/10 SPAN | 2/10 SPAN | 3/10 SPAN | 4/10 SPAN | 1/2 SPAN | 6/10 SPAN | 7/10 SPAN | 8/10 SPAN | 9/10 SPAN | F.A. |
| DEFLECTION DUE TO WEIGHT OF STEEL | 0 | 5/8 | 1 1/8 | 1 1/2 | 1 3/4 | 1 7/8 | 1 3/4 | 1 1/2 | 1 1/8 | 5/8 | 0 |
| DEFLECTION DUE TO STAGED DECK PLACEMENT | 0 | 1 5/8 | 3 | 4 1/16 | 4 3/4 | 4 15/16 | 4 3/4 | 4 1/16 | 3 | 1 5/8 | 0 |
| DEFLECTION DUE TO REMAINING DEAD LOAD | 0 | 3/16 | 3/8 | 7/16 | 9/16 | 9/16 | 9/16 | 7/16 | 3/8 | 3/16 | 0 |
| ADJUSTMENT REQUIRED FOR VERTICAL CURVE | 0 | 1/4 | 7/16 | 5/8 | 3/4 | 13/16 | 3/4 | 5/8 | 7/16 | 5/16 | 0 |
| REQUIRED SHOP CAMBER | 0 | 2 9/16 | 4 13/16 | 6 5/8 | 7 11/16 | 8 1/8 | 7 11/16 | 6 9/16 | 4 13/16 | 2 5/8 | 0 |

| | GIRDERS 8,13 (RIGHT BRIDGE NORTHBOUND) | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | R.A. | 1/10 SPAN | 2/10 SPAN | 3/10 SPAN | 4/10 SPAN | 1/2 SPAN | 6/10 SPAN | 7/10 SPAN | 8/10 SPAN | 9/10 SPAN | F.A. |
| DEFLECTION DUE TO WEIGHT OF STEEL | 0 | 9/16 | 1 1/16 | 1 7/16 | 1 11/16 | 1 3/4 | 1 11/16 | 1 7/16 | 1 1/16 | 9/16 | 0 |
| DEFLECTION DUE TO STAGED DECK PLACEMENT | 0 | 1 1/2 | 2 13/16 | 3 13/16 | 4 7/16 | 4 11/16 | 4 7/16 | 3 13/16 | 2 13/16 | 1 1/2 | 0 |
| DEFLECTION DUE TO REMAINING DEAD LOAD | 0 | 3/16 | 3/8 | 1/2 | 9/16 | 5/8 | 9/16 | 1/2 | 3/8 | 3/16 | 0 |
| ADJUSTMENT REQUIRED FOR VERTICAL CURVE | 0 | 1/4 | 7/16 | 5/8 | 3/4 | 13/16 | 3/4 | 5/8 | 7/16 | 5/16 | 0 |
| REQUIRED SHOP CAMBER | 0 | 2 7/16 | 4 5/8 | 6 5/16 | 7 5/16 | 7 3/4 | 7 3/8 | 6 1/4 | 4 5/8 | 2 1/2 | 0 |

***CAMBER TABLE (RIGHT BRIDGE - NORTHBOUND)***




***CAMBER DIAGRAM (NORTHBOUND & SOUTHBOUND)***

***NOTES:***

*1. CAMBER IS ROUNDED TO THE NEAREST 1/16".*

CAMBER AND DEFLECTION TABLES
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

SFN TBD

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | DBL |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 36 | 65 |


| SHEET | TOTAL |
|---|---|
| P. 456 | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:51:28 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SS009.dgn





**INTERMEDIATE CROSSFRAME - LEFT BRIDGE**





**TYPICAL BEARING STIFFENER DETAIL**





**TYPICAL CONNECTION PLATE DETAIL**




**INTERMEDIATE CROSSFRAME - RIGHT BRIDGE**
*(SIMILAR TO LEFT BRIDGE, BUT DIFFERENT GIRDER SPACING)*




**CONNECTION PLATE**




**TYPICAL FLANGE TRANSITION DETAIL**
*(TO BE USED AT FLANGE THICKNESS TRANSITIONS)*

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. THE FABRICATOR SHALL CHECK LONGITUDINAL CROSSFRAME SPACING SO THAT INTERFERENCE WITH BOLTED SPLICES, COMPLETE PENETRATION WEB OR FLANGE WELDED SPLICES IS AVOIDED. SPACING SHALL BE ADJUSTED TO PROVIDE AT LEAST SIX (6) INCHES OF LONGITUDINAL CLEARANCE.
3. IN ACCORDANCE WITH C&MS 513, THE FABRICATOR SHALL DETAIL ALL CROSSFRAMES TO FIT WITH THE WEBS PLUMB AT THE COMPLETION OF SUPERSTRUCTURE ERECTION (STEEL DEAD LOAD FIT, SDLF).
4. CONNECTION PLATES SHALL BE NORMAL TO ℄ GIRDER.
5. IN BAYS WITH CLOSURE POUR, THE FABRICATOR SHALL DETAIL CROSSFRAMES TO FIT AT THE COMPLETION OF DECK PLACEMENT ON EACH SIDE OF THE CLOSURE POUR. BOLT HOLES IN THE CONNECTION PLATE ON ONE OF THE GIRDER LINES SHALL BE FIELD DRILLED AND SHOP DRILLED ON THE OTHER.
6. THE CONTRACTOR SHALL NOT PERMANENTLY ATTACH INTERMEDIATE CROSSFRAMES IN THE CLOSURE POUR LOCATION UNTIL THE CONCRETE POURS ON BOTH SIDES OF THE CLOSURE POUR LOCATION HAVE BEEN COMPLETED.
7. ALL MATERIAL SHALL BE ASTM A709, GRADE 50, YIELD STRENGTH 50-KSI.
8. ALL MATERIAL SHALL BE SHOP PRIMED AND FIELD PAINTED PER C&MS 514.
9. HIGH STRENGTH BOLTS SHALL BE 1" DIAMETER ASTM F3125, GRADE A325, TYPE 1 WITH THREADS EXCLUDED FROM SHEAR PLANE UNLESS OTHERWISE NOTED. PROVIDE CLASS A SURFACE CONDITION FOR THE CONTACT AREA OF BOLTED PARTS OF THE CROSSFRAME.

# INTERMEDIATE CROSSFRAME DETAILS
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MJR |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 37 |
| TOTAL | 65 |
| SHEET | P. 457 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:51:54 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SS010.dgn





***DIAPHRAGM PLAN - NORTHBOUND***

*(DIMENSIONS AND ELEVATIONS SHOWN ALONG SKEW)*





***DIAPHRAGM GUIDE PLAN***




***DIAPHRAGM ELEVATION - NORTHBOUND***

*(DIMENSIONS AND ELEVATIONS SHOWN ALONG SKEW @ ℄ BRG.)*




***DIAPHRAGM GUIDE ELEVATION***

***LEGEND:***

| | |
|---|---|
| *Δ* | *2 SETS OF 2-D504 @ 1'-6" MAX.* |
| *ΔΔ* | *4 SETS OF 2-D502 @ 1'-6" MAX.* |
| *ΔΔΔ* | *MECHANICAL CONNECTOR (TYP.)* |

***NOTES:***

1. *FOR REAR ABUTMENT DETAILS, SEE SHEETS 26 THRU 28.*
2. *PLACE THE DIAPHRAGM CONCRETE ENCASING THE STRUCTURAL STEEL MEMBER ENDS WITH THE DECK CONCRETE OR AT LEAST 48 HOURS BEFORE PLACEMENT OF THE DECK CONCRETE. IF PLACED SEPARATELY, LOCATE A HORIZONTAL CONSTRUCTION JOINT IN THE DIAPHRAGM AS SHOWN IN SECTION A AND PLACE REMAINING DIAPHRAGM CONCRETE WITH THE DECK.*
3. *ALL REINFORCING STEEL SHALL MAINTAIN A 2" MINIMUM CLEARANCE TO FACE OF CONCRETE UNLESS NOTED OTHERWISE.*
4. *ALL VERTICAL REINFORCEMENT SHALL BE PLACED PARALLEL TO BEAMS.*

# REAR ABUTMENT DIAPHRAGM PLAN AND ELEVATION - RIGHT BRIDGE


BRIDGE NO. FRA-00071-24.460 L/R

I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 38 |
| TOTAL | 65 |
| SHEET | P. 458 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:52:11 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192_SR006.dgn





***DIAPHRAGM PLAN - SOUTHBOUND***


*(DIMENSIONS AND ELEVATIONS SHOWN ALONG SKEW)*




A - 38 SECTION (NOT TO SCALE)




B - 38 SECTION (NOT TO SCALE)




***DIAPHRAGM ELEVATION - SOUTHBOUND***

*(DIMENSIONS AND ELEVATIONS SHOWN ALONG SKEW @ ℄ BRG.)*

***LEGEND:***

- Δ 2 SETS OF 2-D507 @ 1'-6" MAX.
- ΔΔ 4 SETS OF 2-D502 @ 1'-6" MAX.
- ΔΔΔ MECHANICAL CONNECTOR (TYP.)

***NOTES:***


1. FOR REAR ABUTMENT DETAILS, SEE SHEETS 26 THRU 28.
2. FOR SEMI-INTEGRAL ABUTMENT DIAPHRAGM GUIDE DETAILS, SEE SHEET 38.
3. PLACE THE DIAPHRAGM CONCRETE ENCASING THE STRUCTURAL STEEL MEMBER ENDS WITH THE DECK CONCRETE OR AT LEAST 48 HOURS BEFORE PLACEMENT OF THE DECK CONCRETE. IF PLACED SEPARATELY, LOCATE A HORIZONTAL CONSTRUCTION JOINT IN THE DIAPHRAGM AS SHOWN IN SECTION A AND PLACE REMAINING DIAPHRAGM CONCRETE WITH THE DECK.
4. ALL REINFORCING STEEL SHALL MAINTAIN A 2" MINIMUM CLEARANCE TO FACE OF CONCRETE UNLESS NOTED OTHERWISE.
5. ALL VERTICAL REINFORCEMENT SHALL BE PLACED PARALLEL TO BEAMS.

# REAR ABUTMENT DIAPHRAGM PLAN AND ELEVATION - LEFT BRIDGE
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 39 |
| TOTAL | 65 |
| SHEET | P. 459 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:52:26 AM PLTDRV: OHDOT_PDF_Ex.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SR007.dgn





***DIAPHRAGM PLAN - NORTHBOUND***

*(DIMENSIONS AND ELEVATIONS SHOWN ALONG SKEW)*





***DIAPHRAGM ELEVATION - NORTHBOUND***

*(DIMENSIONS AND ELEVATIONS SHOWN ALONG SKEW @ ℄ BRG.)*




**A - A 41** ***SECTION*** *(NOT TO SCALE)*




**B - B 41** ***SECTION*** *(NOT TO SCALE)*

***LEGEND:***

*Δ - 2 SETS OF 2-D504 @ 1'-6" MAX.*

*ΔΔ - 4 SETS OF 2-D502 @ 1'-6" MAX.*

*ΔΔΔ - MECHANICAL CONNECTOR (TYP.)*

***MIN. LAP LENGTHS***

*#8 BAR = 5'-4"*

***NOTES:***

1. *FOR FORWARD ABUTMENT DETAILS, SEE SHEETS 29 THRU 31.*
2. *FOR SEMI-INTEGRAL ABUTMENT DIAPHRAGM GUIDE DETAILS, SEE SHEET 38.*
3. *PLACE THE DIAPHRAGM CONCRETE ENCASING THE STRUCTURAL STEEL MEMBER ENDS WITH THE DECK CONCRETE OR AT LEAST 48 HOURS BEFORE PLACEMENT OF THE DECK CONCRETE. IF PLACED SEPARATELY, LOCATE A HORIZONTAL CONSTRUCTION JOINT IN THE DIAPHRAGM AS SHOWN IN SECTION A AND PLACE REMAINING DIAPHRAGM CONCRETE WITH THE DECK.*
4. *ALL REINFORCING STEEL SHALL MAINTAIN A 2" MINIMUM CLEARANCE TO FACE OF CONCRETE UNLESS NOTED OTHERWISE.*
5. *ALL VERTICAL REINFORCEMENT SHALL BE PLACED PARALLEL TO BEAMS.*


# FORWARD ABUTMENT DIAPHRAGM PLAN AND ELEVATION - RIGHT BRIDGE

BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 40 |
| TOTAL | 65 |
| SHEET | P. 460 |
| TOTAL | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:52:42 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SF004.dgn




***DIAPHRAGM PLAN - SOUTHBOUND***

*(DIMENSIONS AND ELEVATIONS SHOWN ALONG SKEW)*




***DIAPHRAGM ELEVATION - SOUTHBOUND***

*(DIMENSIONS AND ELEVATIONS SHOWN ALONG SKEW @ ℄ BRG.)*

***LEGEND:***

| | |
|---|---|
| Δ | 2 SETS OF 2-D507 @ 1'-6" MAX. |
| ΔΔ | 4 SETS OF 2-D502 @ 1'-6" MAX. |
| ΔΔΔ | MECHANICAL CONNECTOR (TYP.) |

***NOTES:***

1. FOR FORWARD ABUTMENT DETAILS, SEE SHEETS 29 THRU 31.
2. FOR SEMI-INTEGRAL ABUTMENT DIAPHRAGM GUIDE DETAILS, SEE SHEET 38.
3. PLACE THE DIAPHRAGM CONCRETE ENCASING THE STRUCTURAL STEEL MEMBER ENDS WITH THE DECK CONCRETE OR AT LEAST 48 HOURS BEFORE PLACEMENT OF THE DECK CONCRETE. IF PLACED SEPARATELY, LOCATE A HORIZONTAL CONSTRUCTION JOINT IN THE DIAPHRAGM AS SHOWN IN SECTION A AND PLACE REMAINING DIAPHRAGM CONCRETE WITH THE DECK.
4. ALL REINFORCING STEEL SHALL MAINTAIN A 2" MINIMUM CLEARANCE TO FACE OF CONCRETE UNLESS NOTED OTHERWISE.
5. ALL VERTICAL REINFORCEMENT SHALL BE PLACED PARALLEL TO BEAMS.

# FORWARD ABUTMENT DIAPHRAGM PLAN AND ELEVATION - LEFT BRIDGE

BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 41 |
| TOTAL | 65 |
| SHEET | P. 461 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:52:56 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SF005.dgn

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:53:10 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\SFN_2508192_SD001.dgn






***DECK PLAN RIGHT BRIDGE (NB) - BOTTOM REINFORCING***

*(DIAPHRAGM BARS NOT SHOWN FOR CLARITY)*

***LEGEND:***

(GXX) - GIRDER LINE DESIGNATION

***NOTES:***


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. MINIMUM REINFORCING STEEL LAP LENGTHS:
   - NO. 4 BAR = 2'-6"
   - NO. 5 BAR = 3'-1"
   - NO. 6 BAR = 4'-0"

# DECK PLAN - RIGHT BRIDGE (BOTTOM MAT)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 42 |
| TOTAL | 65 |
| SHEET | P. 462 |
| TOTAL | 618 |

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:53:23 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SD002.dgn






***DECK PLAN RIGHT BRIDGE (NB) - TOP REINFORCING***

*(DIAPHRAGM BARS NOT SHOWN FOR CLARITY)*

***LEGEND:***

(GXX) - *GIRDER LINE DESIGNATION*

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *MINIMUM REINFORCING STEEL LAP LENGTHS:*
   - *NO. 4 BAR = 2'-6"*
   - *NO. 5 BAR = 3'-1"*
   - *NO. 6 BAR = 4'-0"*

# DECK PLAN - RIGHT BRIDGE (TOP MAT)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 43 |
| TOTAL | 65 |
| SHEET | P. 463 |
| TOTAL | 618 |

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:53:38 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SD003.dgn






***DECK PLAN LEFT BRIDGE (SB) - BOTTOM REINFORCING***
*(DIAPHRAGM BARS NOT SHOWN FOR CLARITY)*

***LEGEND:***

(GXX) - GIRDER LINE DESIGNATION

***NOTES:***

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. MINIMUM REINFORCING STEEL LAP LENGTHS:
   - NO. 4 BAR = 2'-6"
   - NO. 5 BAR = 3'-1"
   - NO. 6 BAR = 4'-0"

# DECK PLAN - LEFT BRIDGE (BOTTOM MAT)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 44 |
| TOTAL | 65 |
| SHEET | P. 464 |
| TOTAL | 618 |

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:53:52 AM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SD004.dgn

FRA-71-19.10

DECK LENGTH = 152'-0⅜" W.R.T. REFERENCE CHORD
SPAN LENGTH = 150'-0" W.R.T. REFERENCE CHORD
318 - S60X LAP WITH S60X @ 5¾" MAX. = 151'-10¾"

PHASE 3B CONSTRUCTION LIMITS = 49'-11"
8'-2" (TYP.)
36'-8"
5'-1" C.P.
PHASE 3A CONSTRUCTION LIMITS = 31'-9"

CROWN
FRONT FACE OF DIAPHRAGM
℄ BRG. REAR ABUTMENT
10°20'00" SKEW (R.F.) (TYP.)
4'-0" OVERHANG
PHASE 3B CONSTRUCTION JOINT
318 - S60X LAP WITH S60X @ 5¾" MAX. = 151'-10¾"
4'-0" MIN. LAP (TYP.)
3'-3" OVERHANG
PHASE 3A CONSTRUCTION JOINT
I-71 SB PROFILE GRADE LINE
2'-6" MIN. LAP (TYP.)
318 - S60X LAP WITH S60X @ 5¾" MAX. = 151'-10¾"
20-S5XX (5 LENGTHS) & 20-S5XX (1 LENGTH) @ 7¾" MAX. = 11'-10" (TYP. EACH BAY)
2'-6" MIN. LAP (TYP.)
1313
EDGE OF DECK (TYP.)
℄ CONSTRUCTION I-71
6-S5XX (5 LENGTHS) & 6-S5XX (1 LENGTH) @ 7½" MAX. = 3'-2" (TYP. EACH OVERHANG)
REFERENCE CHORD
318 - S40X LAP WITH S60X @ 5¾" MAX. = 151'-10¾" (ADDITIONAL OVERHANG BARS)

G1
G2
G3
G4
G5
G6
G7
1'-0" (TYP.)
6" APPR. SLAB SEAT (TYP.)
3'-0" DIAPHRAGM
FRONT FACE OF DIAPHRAGM
℄ BRG. FORWARD ABUTMENT
21'-3" (PGL TO ℄ CONST. I-71) (TYP.)

## DECK PLAN LEFT BRIDGE (SB) - TOP REINFORCING
(DIAPHRAGM BARS NOT SHOWN FOR CLARITY)

**LEGEND:**


(GXX) - GIRDER LINE DESIGNATION

**NOTES:**

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. MINIMUM REINFORCING STEEL LAP LENGTHS:
   - NO. 4 BAR = 2'-6"
   - NO. 5 BAR = 3'-1"
   - NO. 6 BAR = 4'-0"

# DECK PLAN - LEFT BRIDGE (TOP MAT)
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 45 |
| TOTAL | 65 |
| SHEET | P. 465 |
| TOTAL | 618 |




## TRANSVERSE SECTION - RIGHT BRIDGE NORTHBOUND


*(LOOKING UPSTATION)*
*(CROSSFRAMES NOT SHOWN FOR CLARITY)*
*(PARAPET REINFORCING STEEL NOT SHOWN FOR CLARITY)*

| MIN. LAP LENGTHS | |
|---|---|
| NO. 4 BARS | 2'-6" |
| NO. 5 BARS | 3'-1" |
| NO. 6 BARS | 4'-0" |




### TYPICAL REINFORCING AND OVERHANG DETAIL - RIGHT BRIDGE NORTHBOUND

*(BAY BETWEEN GIRDERS G8 AND G9 SHOWN, BAY BETWEEN GIRDERS G13 AND G12 OPPOSITE HAND)*




### TYPICAL REINFORCING - RIGHT BRIDGE NORTHBOUND

*(BAY BETWEEN GIRDERS G10 AND G11 FOR CLOSURE POUR SHOWN)*

**NOTES:**

1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *FOR PARAPET DETAILS, SEE SHEETS 54 THROUGH 55.*
3. *PER C&MS 511.19, THE 2'-0" HMWM CENTERED ON THE PHASE CONSTRUCTION JOINT IS CONSIDERED INCIDENTAL TO ITEM 511-CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK.*
4. *DECK SLAB CONCRETE QUANTITY: THE ESTIMATED QUANTITY OF DECK SLAB CONCRETE IS BASED ON THE CONSTANT DECK SLAB THICKNESS, AS SHOWN, PLUS THE QUANTITY OF CONCRETE THAT FORMS EACH BEAM/GIRDER HAUNCH. THE ESTIMATE ASSUMES A CONSTANT HAUNCH THICKNESS OF 2.85 INCHES AND A HAUNCH WIDTH EQUAL TO THE TOP FLANGE WIDTH. DEVIATE FROM THIS HAUNCH THICKNESS AS NECESSARY TO PLACE THE DECK SURFACE AT THE FINISHED GRADE.*


*THE HAUNCH THICKNESS WAS MEASURED AT THE CENTERLINE OF THE BEAM/GIRDER, FROM THE SURFACE OF THE DECK TO THE BOTTOM OF THE TOP FLANGE MINUS THE DECK SLAB THICKNESS. THE AREA OF ALL EMBEDDED STEEL PLATES HAS BEEN DEDUCTED FROM THE HAUNCH QUANTITY IN ACCORDANCE WITH C&MS 511.23.*

# TRANSVERSE SECTION - RIGHT BRIDGE
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

SFN TBD
SFN TBD
DESIGN AGENCY
Jacobs
DESIGNER DBL | CHECKER MAN
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 46 | TOTAL 65
SHEET P. 466 | TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:54:06 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_ST003.dgn
Asad.Nawaz@jacobs.com
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192_ST003.dgn




## TRANSVERSE SECTION - LEFT BRIDGE SOUTHBOUND


(LOOKING UPSTATION)
(CROSSFRAMES NOT SHOWN FOR CLARITY)
(PARAPET REINFORCING STEEL NOT SHOWN FOR CLARITY)

| MIN. LAP LENGTHS | |
|---|---|
| NO. 4 BARS | 2'-6" |
| NO. 5 BARS | 3'-1" |
| NO. 6 BARS | 4'-0" |




## TYPICAL REINFORCING AND OVERHANG DETAIL -LEFT BRIDGE SOUTHBOUND

BAY BETWEEN GIRDERS 1 AND 2 SHOWN,
BAY BETWEEN GIRDERS 7 AND 6 OPPOSITE HAND




## TYPICAL REINFORCING -LEFT BRIDGE SOUTHBOUND

(BAY BETWEEN GIRDERS G4 AND G5 FOR CLOSURE POUR SHOWN)

### NOTES:

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. FOR PARAPET DETAILS, SEE SHEETS 54 THROUGH 55.
3. PER C&MS 511.19, THE 2'-0" HMWM CENTERED ON THE PHASE CONSTRUCTION JOINT IS CONSIDERED INCIDENTAL TO ITEM 511-CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK.
4. DECK SLAB CONCRETE QUANTITY: THE ESTIMATED QUANTITY OF DECK SLAB CONCRETE IS BASED ON THE CONSTANT DECK SLAB THICKNESS, AS SHOWN, PLUS THE QUANTITY OF CONCRETE THAT FORMS EACH BEAM/GIRDER HAUNCH. THE ESTIMATE ASSUMES A CONSTANT HAUNCH THICKNESS OF 4.10 INCHES AND A HAUNCH WIDTH EQUAL TO THE TOP FLANGE WIDTH. DEVIATE FROM THIS HAUNCH THICKNESS AS NECESSARY TO PLACE THE DECK SURFACE AT THE FINISHED GRADE.


   THE HAUNCH THICKNESS WAS MEASURED AT THE CENTERLINE OF THE BEAM/GIRDER, FROM THE SURFACE OF THE DECK TO THE BOTTOM OF THE TOP FLANGE MINUS THE DECK SLAB THICKNESS. THE AREA OF ALL EMBEDDED STEEL PLATES HAS BEEN DEDUCTED FROM THE HAUNCH QUANTITY IN ACCORDANCE WITH C&MS 511.23.

# TRANSVERSE SECTION - LEFT BRIDGE
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 47 |
| TOTAL | 65 |
| SHEET | P. 467 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:54:20 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_ST002.dgn





***TRANSVERSE SECTION***




***TYPICAL ROUNDING DETAIL***
*(NOT TO SCALE)*




***TYPICAL LIMITS OF CONCRETE SEALING***
*(NOT TO SCALE)*




***LIMITS OF PAINTING OF STRUCTURAL STEEL***
*(NOT TO SCALE)*

***LEGEND:***

*A - VARIES, 0" MIN. TO $8^{13}/_{16}$" MAX.*

*B - SHOULDER VARIES, 9'-$1^{3}/_{8}$"± MIN. TO 12'-$6^{3}/_{4}$"± MAX.*
*(REFER TO PAVEMENT MARKING PLANS)*

*C - RAMP LANE VARIES, 16'-$1^{1}/_{2}$"± MIN. TO 19'-2"± MAX.*
*(REFER TO PAVEMENT MARKING PLANS)*

*D - SHOULDER VARIES, 4'-$8^{3}/_{4}$"± MIN. TO 4'-$9^{3}/_{4}$"± MAX.*
*(REFER TO PAVEMENT MARKING PLANS)*

*E - SHOULDER VARIES, 5'-$11^{1}/_{2}$"± MIN. TO 6'-$0^{1}/_{2}$"± MAX.*
*(REFER TO PAVEMENT MARKING PLANS)*

*F - SHOULDER VARIES, 10'-3"± MIN. TO 11'-$4^{1}/_{8}$"± MAX.*
*(REFER TO PAVEMENT MARKING PLANS)*

*Δ - 2'-0"*

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*

TRANSVERSE SECTION - GENERAL GEOMETRY
BRIDGE NO. FRA-00071-24.460 L/R L/R
I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 48 |
| TOTAL | 65 |
| SHEET | P. 468 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:54:33 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_ST001.dgn




## CRITICAL BRIDGE POINTS PLAN

*(FOR USE WITH CAMBER, SCREED, TOP OF HAUNCH AND FINAL DECK SURFACE ELEVATION TABLES)*

**LEGEND:**

(GXX) - GIRDER LINE DESIGNATION

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. FOR ROUNDING DETAIL, SEE SHEET 48.
3. FOR SCREED ELEVATIONS, SEE SHEET 50.
4. FOR TOP OF HAUNCH ELEVATIONS, SEE SHEET 51.
5. FOR FINAL DECK SURFACE ELEVATIONS, SEE SHEET 53.

# BRIDGE CRITICAL POINTS PLAN
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 49 |
| TOTAL | 65 |
| SHEET | P. 469 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:54:50 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SS004.dgn




***SCREED LOCATION TRANSVERSE SECTION - LEFT BRIDGE & RIGHT BRIDGE***

*(FOR USE WITH CAMBER, SCREED, TOP OF HAUNCH AND FINAL DECK SURFACE ELEVATION TABLES)*

***LEGEND:***

(GXX) - GIRDER LINE DESIGNATION

***NOTES:***

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. FOR ROUNDING DETAIL, SEE SHEET 48.
3. FOR SCREED ELEVATIONS, SEE SHEET 50.
4. FOR TOP OF HAUNCH ELEVATIONS, SEE SHEET 51.
5. FOR FINAL DECK SURFACE ELEVATIONS, SEE SHEET 53.

# BRIDGE CRITICAL POINTS TRANSVERSE SECTION
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER / CHECKER | MAN / DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET / TOTAL | 50 / 65 |
| SHEET / TOTAL | P. 470 / 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:55:02 AM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SS005.dgn

| SCREED ELEVATIONS - LEFT BRIDGE SOUTHBOUND | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | ℄ BRG. R.A. | | 1/10 SPAN | | 2/10 SPAN | | 3/10 SPAN | | 4/10 SPAN | | 1/2 SPAN | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| TOE OF LEFT PARAPET | 1312+20.47 | 902.60 | 1312+35.15 | 902.76 | 1312+49.83 | 902.89 | 1312+64.50 | 902.99 | 1312+79.18 | 903.05 | 1312+93.86 | 903.07 |
| CROWN | 1312+21.49 | 902.86 | 1312+36.19 | 903.02 | 1312+50.89 | 903.15 | 1312+65.59 | 903.25 | 1312+80.30 | 903.31 | 1312+95.00 | 903.33 |
| PHASE 3B CONSTRUCTION JOINT | 1312+27.27 | 901.04 | 1312+42.11 | 901.20 | 1312+56.95 | 901.34 | 1312+71.80 | 901.45 | 1312+86.64 | 901.51 | 1313+01.49 | 901.52 |
| PHASE 3A CONSTRUCTION JOINT | 1312+28.08 | 900.78 | 1312+42.94 | 900.95 | 1312+57.80 | 901.08 | 1312+72.67 | 901.20 | 1312+87.53 | 901.26 | 1313+02.40 | 901.27 |
| PROFILE GRADE LINE | 1312+30.38 | 900.07 | 1312+45.24 | 900.25 | 1312+60.12 | 900.39 | 1312+75.01 | 900.51 | 1312+89.91 | 900.58 | 1313+04.82 | 900.59 |
| TOE OF RIGHT PARAPET | 1312+32.91 | 899.29 | 1312+47.89 | 899.44 | 1312+62.87 | 899.57 | 1312+77.85 | 899.67 | 1312+92.83 | 899.72 | 1313+07.81 | 899.74 |

| SCREED ELEVATIONS - LEFT BRIDGE SOUTHBOUND | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | 6/10 SPAN | | 7/10 SPAN | | 8/10 SPAN | | 9/10 SPAN | | ℄ BRG. F.A. | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| TOE OF LEFT PARAPET | 1313+08.55 | 903.04 | 1313+23.23 | 902.97 | 1313+37.91 | 902.85 | 1313+52.59 | 902.71 | 1313+67.26 | 902.54 |
| CROWN | 1313+09.71 | 903.30 | 1313+24.41 | 903.23 | 1313+39.12 | 903.11 | 1313+53.82 | 902.96 | 1313+68.52 | 902.79 |
| PHASE 3B CONSTRUCTION JOINT | 1313+16.33 | 901.49 | 1313+31.18 | 901.42 | 1313+46.02 | 901.28 | 1313+60.86 | 901.13 | 1313+75.71 | 900.94 |
| PHASE 3A CONSTRUCTION JOINT | 1313+17.26 | 901.24 | 1313+32.12 | 901.16 | 1313+46.99 | 901.03 | 1313+61.85 | 900.87 | 1313+76.71 | 900.69 |
| PROFILE GRADE LINE | 1313+19.74 | 900.56 | 1313+34.67 | 900.48 | 1313+49.61 | 900.34 | 1313+64.56 | 900.17 | 1313+79.53 | 899.97 |
| TOE OF RIGHT PARAPET | 1313+22.79 | 899.70 | 1313+37.77 | 899.62 | 1313+52.75 | 899.50 | 1313+67.73 | 899.35 | 1313+82.71 | 899.17 |

***SCREED ELEVATIONS - LEFT BRIDGE SOUTHBOUND***

| SCREED ELEVATIONS - RIGHT BRIDGE NORTHBOUND | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | ℄ BRG. R.A. | | 1/10 SPAN | | 2/10 SPAN | | 3/10 SPAN | | 4/10 SPAN | | 1/2 SPAN | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| TOE OF LEFT PARAPET | 1312+34.49 | 903.79 | 1312+49.51 | 903.95 | 1312+64.53 | 904.08 | 1312+79.54 | 904.18 | 1312+94.56 | 904.24 | 1313+09.58 | 904.26 |
| CROWN | 1312+34.82 | 903.87 | 1312+49.84 | 904.03 | 1312+64.87 | 904.16 | 1312+79.89 | 904.26 | 1312+94.92 | 904.32 | 1313+09.95 | 904.34 |
| PROFILE GRADE LINE | 1312+37.27 | 903.13 | 1312+52.31 | 903.30 | 1312+67.36 | 903.45 | 1312+82.42 | 903.56 | 1312+97.49 | 903.63 | 1313+12.57 | 903.64 |
| PHASE 4A CONSTRUCTION LINE | 1312+39.26 | 902.52 | 1312+54.39 | 902.69 | 1312+69.52 | 902.82 | 1312+84.65 | 902.93 | 1312+99.79 | 902.99 | 1313+14.92 | 903.01 |
| PHASE 4B CONSTRUCTION LINE | 1312+39.89 | 902.33 | 1312+55.04 | 902.50 | 1312+70.19 | 902.63 | 1312+85.34 | 902.74 | 1313+00.49 | 902.80 | 1313+15.64 | 902.82 |
| TOE OF RIGHT PARAPET | 1312+44.80 | 900.87 | 1312+60.06 | 901.03 | 1312+75.33 | 901.16 | 1312+90.60 | 901.25 | 1313+05.86 | 901.31 | 1313+21.13 | 901.33 |

| SCREED ELEVATIONS - RIGHT BRIDGE NORTHBOUND | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | 6/10 SPAN | | 7/10 SPAN | | 8/10 SPAN | | 9/10 SPAN | | ℄ BRG. R.A. | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| TOE OF LEFT PARAPET | 1313+24.60 | 904.23 | 1313+39.62 | 904.16 | 1313+54.64 | 904.06 | 1313+69.66 | 903.92 | 1313+84.67 | 903.75 |
| CROWN | 1313+24.98 | 904.31 | 1313+40.00 | 904.24 | 1313+55.03 | 904.14 | 1313+70.05 | 904.00 | 1313+85.08 | 903.83 |
| PROFILE GRADE LINE | 1313+27.66 | 903.62 | 1313+42.76 | 903.54 | 1313+57.88 | 903.41 | 1313+73.00 | 903.26 | 1313+88.14 | 903.07 |
| PHASE 4A CONSTRUCTION LINE | 1313+30.06 | 902.98 | 1313+45.19 | 902.91 | 1313+60.32 | 902.79 | 1313+75.45 | 902.65 | 1313+90.58 | 902.47 |
| PHASE 4B CONSTRUCTION LINE | 1313+30.78 | 902.79 | 1313+45.93 | 902.71 | 1313+61.08 | 902.60 | 1313+76.23 | 902.46 | 1313+91.37 | 902.28 |
| TOE OF RIGHT PARAPET | 1313+36.40 | 901.30 | 1313+51.67 | 901.22 | 1313+66.93 | 901.11 | 1313+82.20 | 900.97 | 1313+97.46 | 900.80 |

***SCREED ELEVATIONS - RIGHT BRIDGE NORTHBOUND***

***NOTES:***

1. *SCREED ELEVATIONS SHOWN REPRESENT THE THEORETICAL DECK SURFACE LOCATION PRIOR TO DEFLECTIONS CAUSED BY DECK PLACEMENT AND OTHER ANTICIPATED DEAD LOADS.*
2. *SEE SHEET 49 AND 52 FOR CRITICAL BRIDGE POINTS PLAN AND SCREED LOCATION TRANSVERSE SECTION.*

# SCREED ELEVATION TABLES
## BRIDGE NO. FRA-00071-24.460 L/R
## I-71 OVER MORSE RD.

SFN TBD

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | DBL |

REVIEWER MJR 03/13/26

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 51 | 65 |

| SHEET | TOTAL |
|---|---|
| P. 471 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:55:15 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19101-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SS006.dgn

| TOP OF HAUNCH ELEVATIONS - LEFT BRIDGE SOUTHBOUND | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | ℄ BRG. R.A. | | 1/10 SPAN | | 2/10 SPAN | | 3/10 SPAN | | 4/10 SPAN | | 1/2 SPAN | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| GIRDER 1 | 1312+20.81 | 901.90 | 1312+35.50 | 902.05 | 1312+50.18 | 902.19 | 1312+64.87 | 902.29 | 1312+79.55 | 902.35 | 1312+94.24 | 902.36 |
| GIRDER 2 | 1312+22.74 | 901.67 | 1312+37.47 | 901.84 | 1312+52.20 | 901.98 | 1312+66.94 | 902.08 | 1312+81.67 | 902.15 | 1312+96.41 | 902.17 |
| GIRDER 3 | 1312+24.68 | 901.06 | 1312+39.46 | 901.22 | 1312+54.24 | 901.36 | 1312+69.02 | 901.47 | 1312+83.80 | 901.54 | 1312+98.58 | 901.55 |
| GIRDER 4 | 1312+26.64 | 900.44 | 1312+41.46 | 900.61 | 1312+56.29 | 900.75 | 1312+71.11 | 900.85 | 1312+85.94 | 900.92 | 1313+00.77 | 900.93 |
| GIRDER 5 | 1312+28.60 | 899.83 | 1312+43.47 | 899.99 | 1312+58.35 | 900.13 | 1312+73.22 | 900.23 | 1312+88.10 | 900.30 | 1313+02.98 | 900.32 |
| GIRDER 6 | 1312+30.58 | 899.22 | 1312+45.50 | 899.38 | 1312+60.42 | 899.52 | 1312+75.35 | 899.62 | 1312+90.27 | 899.69 | 1313+05.20 | 899.70 |
| GIRDER 7 | 1312+32.57 | 898.60 | 1312+47.54 | 898.75 | 1312+62.51 | 898.88 | 1312+77.48 | 898.98 | 1312+92.46 | 899.04 | 1313+07.43 | 899.05 |

| TOP OF HAUNCH ELEVATIONS - LEFT BRIDGE SOUTHBOUND | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | 6/10 SPAN | | 7/10 SPAN | | 8/10 SPAN | | 9/10 SPAN | | ℄ BRG. F.A. | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| GIRDER 1 | 1313+08.93 | 902.33 | 1313+23.62 | 902.26 | 1313+38.31 | 902.15 | 1313+53.00 | 902.00 | 1313+67.68 | 901.83 |
| GIRDER 2 | 1313+11.14 | 902.14 | 1313+25.88 | 902.06 | 1313+40.61 | 901.94 | 1313+55.35 | 901.78 | 1313+70.08 | 901.60 |
| GIRDER 3 | 1313+13.37 | 901.52 | 1313+28.15 | 901.44 | 1313+42.93 | 901.32 | 1313+57.71 | 901.16 | 1313+72.49 | 900.98 |
| GIRDER 4 | 1313+15.60 | 900.90 | 1313+30.43 | 900.82 | 1313+45.26 | 900.69 | 1313+60.09 | 900.54 | 1313+74.92 | 900.36 |
| GIRDER 5 | 1313+17.86 | 900.28 | 1313+32.73 | 900.20 | 1313+47.61 | 900.07 | 1313+62.48 | 899.92 | 1313+77.36 | 899.73 |
| GIRDER 6 | 1313+20.12 | 899.66 | 1313+35.05 | 899.58 | 1313+49.97 | 899.45 | 1313+64.89 | 899.29 | 1313+79.81 | 899.11 |
| GIRDER 7 | 1313+22.40 | 899.02 | 1313+37.38 | 898.94 | 1313+52.35 | 898.81 | 1313+67.32 | 898.66 | 1313+82.29 | 898.49 |

***TOP OF HAUNCH ELEVATIONS - LEFT BRIDGE SOUTHBOUND***

| TOP OF HAUNCH ELEVATIONS - RIGHT BRIDGE NORTHBOUND | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | ℄ BRG. R.A. | | 1/10 SPAN | | 2/10 SPAN | | 3/10 SPAN | | 4/10 SPAN | | 1/2 SPAN | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| GIRDER 8 | 1312+34.83 | 903.07 | 1312+49.86 | 903.23 | 1312+64.88 | 903.36 | 1312+79.91 | 903.46 | 1312+94.94 | 903.53 | 1313+09.96 | 903.54 |
| GIRDER 9 | 1312+36.73 | 902.50 | 1312+51.80 | 902.65 | 1312+66.87 | 902.80 | 1312+81.94 | 902.90 | 1312+97.02 | 902.97 | 1313+12.09 | 902.98 |
| GIRDER 10 | 1312+38.64 | 901.92 | 1312+53.75 | 902.08 | 1312+68.87 | 902.22 | 1312+83.99 | 902.33 | 1312+99.11 | 902.39 | 1313+14.23 | 902.40 |
| GIRDER 11 | 1312+40.56 | 901.34 | 1312+55.72 | 901.50 | 1312+70.88 | 901.64 | 1312+86.05 | 901.75 | 1313+01.21 | 901.81 | 1313+16.38 | 901.83 |
| GIRDER 12 | 1312+42.49 | 900.77 | 1312+57.70 | 900.92 | 1312+72.91 | 901.06 | 1312+88.12 | 901.17 | 1313+03.33 | 901.23 | 1313+18.55 | 901.25 |
| GIRDER 13 | 1312+44.43 | 900.19 | 1312+59.69 | 900.34 | 1312+74.95 | 900.47 | 1312+90.20 | 900.57 | 1313+05.46 | 900.63 | 1313+20.72 | 900.65 |


| TOP OF HAUNCH ELEVATIONS - RIGHT BRIDGE NORTHBOUND | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | 6/10 SPAN | | 7/10 SPAN | | 8/10 SPAN | | 9/10 SPAN | | ℄ BRG. F.A. | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| GIRDER 8 | 1313+24.99 | 903.52 | 1313+40.02 | 903.45 | 1313+55.04 | 903.34 | 1313+70.07 | 903.20 | 1313+85.09 | 903.04 |
| GIRDER 9 | 1313+27.16 | 902.96 | 1313+42.24 | 902.89 | 1313+57.31 | 902.77 | 1313+72.38 | 902.62 | 1313+87.45 | 902.46 |
| GIRDER 10 | 1313+29.35 | 902.38 | 1313+44.47 | 902.31 | 1313+59.58 | 902.19 | 1313+74.70 | 902.04 | 1313+89.81 | 901.87 |
| GIRDER 11 | 1313+31.55 | 901.80 | 1313+46.71 | 901.72 | 1313+61.87 | 901.61 | 1313+77.04 | 901.45 | 1313+92.20 | 901.29 |
| GIRDER 12 | 1313+33.76 | 901.22 | 1313+48.97 | 901.14 | 1313+64.18 | 901.02 | 1313+79.39 | 900.87 | 1313+94.59 | 900.70 |
| GIRDER 13 | 1313+35.98 | 900.62 | 1313+51.24 | 900.54 | 1313+66.50 | 900.43 | 1313+81.75 | 900.29 | 1313+97.01 | 900.12 |

***TOP OF HAUNCH ELEVATIONS - RIGHT BRIDGE NORTHBOUND***

***NOTES:***

1. *TOP OF HAUNCH ELEVATIONS SHOWN REPRESENT THE THEORETICAL LOCATION OF THE BOTTOM OF THE DECK ABOVE THE ℄ OF THE GIRDER HAUNCH PRIOR TO DEFLECTIONS CAUSED BY DECK PLACEMENT AND OTHER ANTICIPATED DEAD LOADS.*

2. *SEE SHEET 49 FOR GIRDERS NUMBERS AND TOP OF HAUNCH ELEVATION LOCATIONS.*




***HAUNCH DETAIL***

TOP OF HAUNCH ELEVATIONS TABLES
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

SFN TBD

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | DBL |

REVIEWER MJR 03/13/26

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 52 | 65 |

| SHEET | TOTAL |
|---|---|
| P. 472 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:55:52 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SS007.dgn

| FINAL DECK SURFACE ELEVATIONS - LEFT BRIDGE SOUTHBOUND | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | ℄ BRG. R.A. | | 1/10 SPAN | | 2/10 SPAN | | 3/10 SPAN | | 4/10 SPAN | | 1/2 SPAN | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| LEFT EDGE OF DECK | 1312+20.22 | 902.60 | 1312+34.88 | 902.62 | 1312+49.55 | 902.63 | 1312+64.23 | 902.63 | 1312+78.90 | 902.63 | 1312+93.57 | 902.63 |
| TOE OF LEFT PARAPET | 1312+20.47 | 902.60 | 1312+35.15 | 902.62 | 1312+49.83 | 902.63 | 1312+64.50 | 902.63 | 1312+79.18 | 902.63 | 1312+93.86 | 902.63 |
| ℄ GIRDER 1 | 1312+20.81 | 902.69 | 1312+35.50 | 902.70 | 1312+50.18 | 902.71 | 1312+64.87 | 902.72 | 1312+79.55 | 902.72 | 1312+94.24 | 902.72 |
| CROWN | 1312+21.49 | 902.86 | 1312+36.19 | 902.88 | 1312+50.89 | 902.89 | 1312+65.59 | 902.89 | 1312+80.30 | 902.89 | 1312+95.00 | 902.89 |
| ℄ GIRDER 2 | 1312+22.74 | 902.46 | 1312+37.47 | 902.48 | 1312+52.20 | 902.49 | 1312+66.94 | 902.49 | 1312+81.67 | 902.49 | 1312+96.41 | 902.49 |
| ℄ GIRDER 3 | 1312+24.68 | 901.85 | 1312+39.46 | 901.86 | 1312+54.24 | 901.87 | 1312+69.02 | 901.88 | 1312+83.80 | 901.88 | 1312+98.58 | 901.87 |
| ℄ GIRDER 4 | 1312+26.64 | 901.23 | 1312+41.46 | 901.25 | 1312+56.29 | 901.26 | 1312+71.11 | 901.26 | 1312+85.94 | 901.26 | 1313+00.77 | 901.25 |
| PHASE 3B CONSTRUCTION JOINT | 1312+27.27 | 901.04 | 1312+42.11 | 901.05 | 1312+56.95 | 901.06 | 1312+71.80 | 901.06 | 1312+86.64 | 901.06 | 1313+01.49 | 901.05 |
| PHASE 3A CONSTRUCTION JOINT | 1312+28.08 | 900.78 | 1312+42.94 | 900.80 | 1312+57.80 | 900.80 | 1312+72.67 | 900.81 | 1312+87.53 | 900.81 | 1313+02.40 | 900.80 |
| ℄ GIRDER 5 | 1312+28.60 | 900.62 | 1312+43.47 | 900.63 | 1312+58.35 | 900.64 | 1312+73.22 | 900.64 | 1312+88.10 | 900.64 | 1313+02.98 | 900.64 |
| PROFILE GRADE LINE | 1312+30.38 | 900.07 | 1312+45.24 | 900.10 | 1312+60.12 | 900.11 | 1312+75.01 | 900.12 | 1312+89.91 | 900.13 | 1313+04.82 | 900.12 |
| ℄ GIRDER 6 | 1312+30.58 | 900.01 | 1312+45.50 | 900.02 | 1312+60.42 | 900.03 | 1312+75.35 | 900.03 | 1312+90.27 | 900.03 | 1313+05.20 | 900.02 |
| ℄ GIRDER 7 | 1312+32.57 | 899.39 | 1312+47.54 | 899.40 | 1312+62.51 | 899.41 | 1312+77.48 | 899.41 | 1312+92.46 | 899.41 | 1313+07.43 | 899.40 |
| TOE OF RIGHT PARAPET | 1312+32.91 | 899.29 | 1312+47.89 | 899.30 | 1312+62.87 | 899.31 | 1312+77.85 | 899.31 | 1312+92.83 | 899.30 | 1313+07.81 | 899.30 |

| FINAL DECK SURFACE ELEVATIONS - LEFT BRIDGE SOUTHBOUND | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | 6/10 SPAN | | 7/10 SPAN | | 8/10 SPAN | | 9/10 SPAN | | ℄ BRG. F.A. | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| LEFT EDGE OF DECK | 1313+08.25 | 902.62 | 1313+22.92 | 902.61 | 1313+37.60 | 902.59 | 1313+52.27 | 902.57 | 1313+66.94 | 902.54 |
| TOE OF LEFT PARAPET | 1313+08.55 | 902.62 | 1313+23.23 | 902.61 | 1313+37.91 | 902.59 | 1313+52.59 | 902.57 | 1313+67.26 | 902.54 |
| ℄ GIRDER 1 | 1313+08.93 | 902.71 | 1313+23.62 | 902.69 | 1313+38.31 | 902.68 | 1313+53.00 | 902.65 | 1313+67.68 | 902.62 |
| CROWN | 1313+09.71 | 902.88 | 1313+24.41 | 902.87 | 1313+39.12 | 902.85 | 1313+53.82 | 902.82 | 1313+68.52 | 902.79 |
| ℄ GIRDER 2 | 1313+11.14 | 902.48 | 1313+25.88 | 902.47 | 1313+40.61 | 902.45 | 1313+55.35 | 902.42 | 1313+70.08 | 902.39 |
| ℄ GIRDER 3 | 1313+13.37 | 901.86 | 1313+28.15 | 901.85 | 1313+42.93 | 901.83 | 1313+57.71 | 901.80 | 1313+72.49 | 901.77 |
| ℄ GIRDER 4 | 1313+15.60 | 901.24 | 1313+30.43 | 901.23 | 1313+45.26 | 901.20 | 1313+60.09 | 901.18 | 1313+74.92 | 901.15 |
| PHASE 3B CONSTRUCTION JOINT | 1313+16.33 | 901.04 | 1313+31.18 | 901.03 | 1313+46.02 | 901.00 | 1313+60.86 | 900.98 | 1313+75.71 | 900.94 |
| PHASE 3A CONSTRUCTION JOINT | 1313+17.26 | 900.79 | 1313+32.12 | 900.77 | 1313+46.99 | 900.75 | 1313+61.85 | 900.72 | 1313+76.71 | 900.69 |
| ℄ GIRDER 5 | 1313+17.86 | 900.62 | 1313+32.73 | 900.61 | 1313+47.61 | 900.58 | 1313+62.48 | 900.56 | 1313+77.36 | 900.52 |
| PROFILE GRADE LINE | 1313+19.74 | 900.11 | 1313+34.67 | 900.09 | 1313+49.61 | 900.06 | 1313+64.56 | 900.02 | 1313+79.53 | 899.97 |
| ℄ GIRDER 6 | 1313+20.12 | 900.00 | 1313+35.05 | 899.99 | 1313+49.97 | 899.96 | 1313+64.89 | 899.93 | 1313+79.81 | 899.90 |
| ℄ GIRDER 7 | 1313+22.40 | 899.39 | 1313+37.38 | 899.37 | 1313+52.35 | 899.34 | 1313+67.32 | 899.31 | 1313+82.29 | 899.28 |
| TOE OF RIGHT PARAPET | 1313+22.79 | 899.28 | 1313+37.77 | 899.26 | 1313+52.75 | 899.24 | 1313+67.73 | 899.21 | 1313+82.71 | 899.17 |

***FINAL DECK SURFACE ELEVATIONS - LEFT BRIDGE SOUTHBOUND***

| FINAL DECK SURFACE ELEVATIONS - RIGHT BRIDGE NORTHBOUND | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | ℄ BRG. R.A. | | 1/10 SPAN | | 2/10 SPAN | | 3/10 SPAN | | 4/10 SPAN | | 1/2 SPAN | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| TOE OF LEFT PARAPET | 1312+34.49 | 903.79 | 1312+49.51 | 903.81 | 1312+64.53 | 903.82 | 1312+79.54 | 903.83 | 1312+94.56 | 903.83 | 1313+09.58 | 903.83 |
| CROWN | 1312+34.82 | 903.87 | 1312+49.84 | 903.89 | 1312+64.87 | 903.90 | 1312+79.89 | 903.91 | 1312+94.92 | 903.91 | 1313+09.95 | 903.91 |
| ℄ GIRDER 8 | 1312+34.83 | 903.86 | 1312+49.86 | 903.88 | 1312+64.88 | 903.89 | 1312+79.91 | 903.90 | 1312+94.94 | 903.91 | 1313+09.96 | 903.90 |
| ℄ GIRDER 9 | 1312+36.73 | 903.29 | 1312+51.80 | 903.30 | 1312+66.87 | 903.32 | 1312+81.94 | 903.32 | 1312+97.02 | 903.33 | 1313+12.09 | 903.32 |
| PROFILE GRADE LINE | 1312+37.27 | 903.13 | 1312+52.31 | 903.15 | 1312+67.36 | 903.18 | 1312+82.42 | 903.19 | 1312+97.49 | 903.20 | 1313+12.57 | 903.19 |
| ℄ GIRDER 10 | 1312+38.64 | 902.71 | 1312+53.75 | 902.73 | 1312+68.87 | 902.74 | 1312+83.99 | 902.75 | 1312+99.11 | 902.75 | 1313+14.23 | 902.74 |
| PHASE 2A CONSTRUCTION JOINT | 1312+39.26 | 902.52 | 1312+54.39 | 902.54 | 1312+69.52 | 902.55 | 1312+84.65 | 902.56 | 1312+99.79 | 902.56 | 1313+14.92 | 902.56 |
| PHASE 2B CONSTRUCTION JOINT | 1312+39.89 | 902.33 | 1312+55.04 | 902.35 | 1312+70.19 | 902.36 | 1312+85.34 | 902.37 | 1313+00.49 | 902.37 | 1313+15.64 | 902.37 |
| ℄ GIRDER 11 | 1312+40.56 | 902.13 | 1312+55.72 | 902.15 | 1312+70.88 | 902.16 | 1312+86.05 | 902.17 | 1313+01.21 | 902.17 | 1313+16.38 | 902.17 |
| ℄ GIRDER 12 | 1312+42.49 | 901.56 | 1312+57.70 | 901.57 | 1312+72.91 | 901.58 | 1312+88.12 | 901.59 | 1313+03.33 | 901.59 | 1313+18.55 | 901.59 |
| ℄ GIRDER 13 | 1312+44.43 | 900.98 | 1312+59.69 | 900.99 | 1312+74.95 | 901.00 | 1312+90.20 | 901.01 | 1313+05.46 | 901.01 | 1313+20.72 | 901.01 |
| TOE OF RIGHT PARAPET | 1312+44.80 | 900.87 | 1312+60.06 | 900.89 | 1312+75.33 | 900.90 | 1312+90.60 | 900.90 | 1313+05.86 | 900.90 | 1313+21.13 | 900.90 |
| RIGHT EDGE OF DECK | 1312+45.08 | 900.87 | 1312+60.35 | 900.89 | 1312+75.62 | 900.90 | 1312+90.90 | 900.90 | 1313+06.17 | 900.90 | 1313+21.45 | 900.90 |

| FINAL DECK SURFACE ELEVATIONS - RIGHT BRIDGE NORTHBOUND | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| LOCATIONS | 6/10 SPAN | | 7/10 SPAN | | 8/10 SPAN | | 9/10 SPAN | | ℄ BRG. F.A. | |
| | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION | STATION | ELEVATION |
| TOE OF LEFT PARAPET | 1313+24.60 | 903.82 | 1313+39.62 | 903.81 | 1313+54.64 | 903.80 | 1313+69.66 | 903.78 | 1313+84.67 | 903.75 |
| CROWN | 1313+24.98 | 903.90 | 1313+40.00 | 903.89 | 1313+55.03 | 903.88 | 1313+70.05 | 903.86 | 1313+85.08 | 903.83 |
| ℄ GIRDER 8 | 1313+24.99 | 903.90 | 1313+40.02 | 903.89 | 1313+55.04 | 903.87 | 1313+70.07 | 903.85 | 1313+85.09 | 903.83 |
| ℄ GIRDER 9 | 1313+27.16 | 903.32 | 1313+42.24 | 903.31 | 1313+57.31 | 903.29 | 1313+72.38 | 903.27 | 1313+87.45 | 903.25 |
| PROFILE GRADE LINE | 1313+27.66 | 903.19 | 1313+42.76 | 903.17 | 1313+57.88 | 903.14 | 1313+73.00 | 903.11 | 1313+88.14 | 903.07 |
| ℄ GIRDER 10 | 1313+29.35 | 902.74 | 1313+44.47 | 902.73 | 1313+59.58 | 902.71 | 1313+74.70 | 902.69 | 1313+89.81 | 902.66 |
| PHASE 2A CONSTRUCTION JOINT | 1313+30.06 | 902.55 | 1313+45.19 | 902.54 | 1313+60.32 | 902.52 | 1313+75.45 | 902.50 | 1313+90.58 | 902.47 |
| PHASE 2B CONSTRUCTION JOINT | 1313+30.78 | 902.36 | 1313+45.93 | 902.35 | 1313+61.08 | 902.33 | 1313+76.23 | 902.31 | 1313+91.37 | 902.28 |
| ℄ GIRDER 11 | 1313+31.55 | 902.16 | 1313+46.71 | 902.14 | 1313+61.87 | 902.13 | 1313+77.04 | 902.10 | 1313+92.20 | 902.08 |
| ℄ GIRDER 12 | 1313+33.76 | 901.58 | 1313+48.97 | 901.56 | 1313+64.18 | 901.54 | 1313+79.39 | 901.52 | 1313+94.59 | 901.49 |
| ℄ GIRDER 13 | 1313+35.98 | 901.00 | 1313+51.24 | 900.98 | 1313+66.50 | 900.96 | 1313+81.75 | 900.94 | 1313+97.01 | 900.91 |
| TOE OF RIGHT PARAPET | 1313+36.40 | 900.89 | 1313+51.67 | 900.87 | 1313+66.93 | 900.85 | 1313+82.20 | 900.83 | 1313+97.46 | 900.80 |
| RIGHT EDGE OF DECK | 1313+36.72 | 900.89 | 1313+52.00 | 900.87 | 1313+67.27 | 900.85 | 1313+82.54 | 900.83 | 1313+97.81 | 900.80 |

***FINAL DECK SURFACE ELEVATIONS - RIGHT BRIDGE NORTHBOUND***

***NOTES:***


1. *FINAL DECK SURFACE ELEVATIONS SHOWN REPRESENT THE DECK SURFACE LOCATION AFTER ALL ANTICIPATED DEAD LOAD DEFLECTIONS HAVE OCCURED.*
2. *SEE SHEET 49 FOR GIRDER NUMBERS AND FINAL DECK SURFACE ELEVATION LOCATIONS.*

FINAL DECK SURFACE ELEVATION TABLES
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

SFN TBD
SFN TBD
DESIGN AGENCY Jacobs
DESIGNER MAN | CHECKER DBL
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 53 | TOTAL 65
SHEET P. 473 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:56:19 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SS008.dgn





**BRIDGE RAILING PLAN**

BRIDGE PARAPET PLAN
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER / CHECKER | DBL / MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET / TOTAL | 54 / 65 |
| SHEET / TOTAL | P. 474 / 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:57:02 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SA001.dgn





***TYPICAL EXTERIOR BRIDGE RAILING ELEVATION***

*(SBR-1-20)*





***TYPICAL MEDIAN BRIDGE RAILING ELEVATION***


*(SBR-2-20)*





***DETAIL 1***




***A SECTION***




***DETAIL 2***




***B SECTION***

| *PARAPET STIFFENING G.F.R.P. REINFORCEMENT* | | | |
|---|---|---|---|
| *BAR MARK* | *NUMBER* | *LENGTH* | *TYPE* |
| *R401* | *XX* | *X'-X"* | *ST* |
| *R402* | *XX* | *X'-X"* | *ST* |
| *R403* | *XX* | *X'-X"* | *ST* |
| *R404* | *XX* | *X'-X"* | *ST* |
| *R405* | *XX* | *X'-X"* | *ST* |
| *R406* | *XX* | *X'-X"* | *ST* |

***NOTES:***


1. *FOR APPROACH PARAPET DETAILS SEE SHEET 58.*

BRIDGE PARAPET DETAILS
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.


SFN TBD
SFN TBD
DESIGN AGENCY Jacobs
DESIGNER DBL | CHECKER MAN
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 55 | TOTAL 65
SHEET P. 475 | TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:57:14 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SA002.dgn




***APPROACH SLAB PLAN (LEFT BRIDGE SOUTHBOUND)***




***TYPE 4-C CURB DETAIL (TYP.)***




***TYPICAL SLEEPER SLAB SECTION***

| SLEEPER SLAB SURFACE ELEVATION AT TOP OF ROADWAY | | | |
|---|---|---|---|
| 1 | 902.55 | 13 | 902.46 |
| 2 | 902.81 | 14 | 902.71 |
| 3 | 900.99 | 15 | 900.85 |
| 4 | 900.73 | 16 | 900.60 |
| 5 | 899.98 | 17 | 899.84 |
| 6 | 899.35 | 18 | 899.08 |

| SLEEPER SLAB SURFACE ELEVATION UNDER APPROACH SLAB | | | |
|---|---|---|---|
| 7 | 901.14 | 19 | 901.05 |
| 8 | 901.40 | 20 | 901.31 |
| 9 | 899.58 | 21 | 899.45 |
| 10 | 899.32 | 22 | 899.20 |
| 11 | 898.58 | 23 | 898.45 |
| 12 | 897.83 | 24 | 897.68 |

***NOTES:***


1. *FOR ADDITIONAL APPROACH SLAB DETAILS, SEE ODOT STANDARD DRAWINGS AS-1-15 AND AS-2-15 TYPE C INSTALLATION.*
2. *FOR BRIDGE RAILING DETAILS, SEE SHEET 55.*
3. *FOR ADDITIONAL BRIDGE RAILING TRANSITION DETAILS, SEE ODOT STANDARD DRAWING SBR-1-20 AND SICD-1-21.*
4. *THE APPROACH SLAB SHALL BE PAID FOR WITH ITEM 526 - REINFORCED CONCRETE APPROACH SLABS WITH QA/QC (T=17").*
5. *FOR INTEGRAL CURB TYPE 4C DETAILS, SEE ODOT STANDARD DRAWING BP-5.1. THE INTEGRAL CURB TYPE 4C SHALL BE PAID FOR WITH ITEM 526 - TYPE C INSTALLATION.*
6. *THE SLEEPER SLAB SHALL BE PAID FOR WITH ITEM 526 - TYPE C INSTALLATION.*

# APPROACH SLAB DETAILS - RIGHT BRIDGE
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:57:29 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SM001.dgn


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 56 |
| TOTAL | 65 |
| SHEET | P. 476 |
| TOTAL | 618 |




## APPROACH SLAB PLAN (RIGHT BRIDGE NORTHBOUND)




### TYPE 4-C CURB DETAIL (TYP.)




### TYPICAL SLEEPER SLAB SECTION

| SLEEPER SLAB SURFACE ELEVATION AT TOP OF ROADWAY | | | |
|---|---|---|---|
| 1 | 903.73 | 13 | 903.68 |
| 2 | 903.81 | 14 | 903.75 |
| 3 | 903.04 | 15 | 902.96 |
| 4 | 902.47 | 16 | 902.40 |
| 5 | 902.28 | 17 | 902.20 |
| 6 | 900.82 | 18 | 900.72 |

| SLEEPER SLAB SURFACE ELEVATION UNDER APPROACH SLAB | | | |
|---|---|---|---|
| 7 | 903.75 | 19 | 903.70 |
| 8 | 903.83 | 20 | 903.78 |
| 9 | 903.05 | 21 | 902.98 |
| 10 | 902.48 | 22 | 902.41 |
| 11 | 902.29 | 23 | 902.22 |
| 12 | 900.83 | 24 | 900.73 |

### NOTES:


1. FOR ADDITIONAL APPROACH SLAB DETAILS, SEE ODOT STANDARD DRAWINGS AS-1-15 AND AS-2-15 TYPE C INSTALLATION.
2. FOR BRIDGE RAILING DETAILS, SEE SHEET 55.
3. FOR ADDITIONAL BRIDGE RAILING TRANSITION DETAILS, SEE ODOT STANDARD DRAWING SBR-1-20 AND SICD-1-21.
4. THE APPROACH SLAB SHALL BE PAID FOR WITH ITEM 526 - REINFORCED CONCRETE APPROACH SLABS WITH QA/QC (T=17").
5. FOR INTEGRAL CURB TYPE 4C DETAILS, SEE ODOT STANDARD DRAWING BP-5.1. THE INTEGRAL CURB TYPE 4C SHALL BE PAID FOR WITH ITEM 526 - TYPE C INSTALLATION.
6. THE SLEEPER SLAB SHALL BE PAID FOR WITH ITEM 526 - TYPE C INSTALLATION.

# APPROACH SLAB DETAILS - LEFT BRIDGE
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

SFN TBD
SFN TBD
DESIGN AGENCY
Jacobs
DESIGNER MAN | CHECKER DBL
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 57 | TOTAL 65
SHEET P. 477 | TOTAL 618


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:57:42 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SM002.dgn
Asad.Nawaz@jacobs.com





***TYPICAL EXTERIOR APPROACH RAILING ELEVATION***


*(SBR-1-20)*




C - ***SECTION***




D - ***SECTION***




***TYPICAL MEDIAN APPROACH PARAPET ELEVATION***

*(SBR-2-20)*

| *PARAPET STIFFENING G.F.R.P. REINFORCEMENT* | | | |
|---|---|---|---|
| *BAR MARK* | *NUMBER* | *LENGTH* | *TYPE* |
| *R407* | *XX* | *X'-X"* | *ST* |
| *R408* | *XX* | *X'-X"* | *ST* |
| *R409* | *XX* | *X'-X"* | *ST* |

***NOTES:***

*1. FOR ADDITIONAL PARAPET DETAILS, SEE SHEETS 54 & 55.*

# APPROACH PARAPET DETAILS
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

SFN TBD

SFN TBD

DESIGN AGENCY

Jacobs

| DESIGNER | CHECKER |
|---|---|
| DBL | MAN |

REVIEWER MJR 03/13/26

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 58 | 65 |

| SHEET | TOTAL |
|---|---|
| P. 478 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:57:56 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SA003.dgn

**STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS**

REFER TO THE FOLLOWING SUPPLEMENTAL SPECIFICATION(S):

| | | |
|---|---|---|
| 800 | DATED | XX/YY/ZZZZ |
| 840 | DATED | 01/16/2026 |
| 878 | DATED | 01/16/2026 |

**DESIGN SPECIFICATIONS**

THIS STRUCTURE CONFORMS TO THE 9th EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020 AND THE ODOT BRIDGE DESIGN MANUAL, 2020 DATED JULY 2025.

**DESIGN DATA**

CONCRETE CLASS QC1 (LEVELING PAD, COPING & GUTTER)
- COMPRESSIVE STRENGTH 4.0 KSI

CONCRETE REINFORCEMENT
EPOXY COATED STEEL REINFORCEMENT
- MINIMUM YIELD STRENGTH 60-KSI

**FOUNDATION BEARING RESISTANCE**

THE REINFORCED SOIL MASSES, AS DESIGNED PRODUCE MAXIMUM SERVICE LIMIT STATE BEARING PRESSURES [1], MAXIMUM STRENGTH LIMIT STATE BEARING PRESSURE [2] AND PROVIDE THE FACTORED BEARING RESISTANCE [3] AS DEPICTED BELOW FOR EACH WALL.

| FOUNDATION BEARING RESISTANCE | | | |
|---|---|---|---|
| MSE WALL NO. | SERVICE BEARING PRESSURE (KSF) [1] | FACTORED BEARING PRESSURE (KSF) [2] | FACTORED BEARING RESISTANCE (KSF) [3] |
| #1 | 7.56 | 5.50 | 11.1 |

**MSE WALL DESIGN PARAMETERS**

THE FOLLOWING TABLE LIST THE MINIMUM SOIL REINFORCEMENT LENGTHS FOR EACH WALL. THE SOIL REINFORCEMENT LENGTH IS A FUNCTION OF THE DESIGN WALL HEIGHT (H) AND WILL VARY ALONG THE LENGTH OF THE WALL.

| MSE WALL DESIGN PARAMETERS | |
|---|---|
| MSE WALL NO. | MINIMUM SOIL REINFORCEMENT LENGTH (FT.) |
| #1 | 0.70H |

**PROPRIETARY RETAINING WALL DATA**

THE PROPRIETARY WALL SUPPLIER SHALL DESIGN THE INTERNAL STABILITY OF A MECHANICALLY STABILIZED EARTH (MSE) WALL IN ACCORDANCE WITH ODOT SUPPLEMENTAL SPECIFICATION (SS) 840 TO SUPPORT THE ABUTMENT. THE DESIGN FOR INTERNAL STABILITY SHALL INCLUDE THE FOLLOWING NOMINAL (I.E. UNFACTORED) HORIZONTAL STRIP LOADS DUE TO FRICTION (FR) FROM THE SUPERSTRUCTURES LISTED IN THE FOLLOWING TABLE, APPLIED PERPENDICULAR TO THE FACE OF WALL AT THE BASE OF THE CONCRETE FOOTING. THIS STRIP LOAD DOES NOT INCLUDE EARTH PRESSURE LOADS FROM THE ABUTMENT BACKFILL OR LIVE LOAD SURCHARGE. HOWEVER, THE PROPRIETARY WALL SUPPLIER SHALL INCLUDE EARTH PRESSURE LOADS FROM THE ABUTMENT BACKFILL AND LIVE LOAD SURCHARGE IN THE DESIGN CALCULATIONS.

| BRIDGE SUPERSTRUCTURE LOADS (K/FT.) | | |
|---|---|---|
| MSE WALL NO. | BRIDGE NO. | FRICTION LOAD (FR) |
| #1 | FRA-71-24.46 L/R | 3.00 |

**ITEM 511 - CONCRETE MISC.: CLASS QC1 CONCRETE, GUTTER**


THIS ITEM INCLUDES ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO CONSTRUCT A CAST-IN-PLACE CONCRETE GUTTER ATOP THE MSE WALL COPING AS DETAILED WITHIN THE PLANS.

**AESTHETIC SURFACE TREATMENT**

ALL PROVISIONS OF ODOT SUPPLEMENTAL SPECIFICATION 840 APPLY IN ADDITION TO THOSE LISTED HEREIN.


THE RELIEF OF AESTHETIC PATTERN FORMLINER SHALL NOT EXCEED A MAXIMUM RELIEF OF 2.0 INCHES. THE MINIMUM RELIEF OF THE AESTHETIC PATTERN FORMLINER IS 1.0 INCHES. AESTHETIC TREATMENT SHALL UTILIZE AN ASHLAR BLOCK FORMLINER PATTERN OR APPROVED EQUAL. SEAL ALL CONCRETE SURFACES WITH A LIGHT-NEUTRAL EPOXY-URETHANE SEALER (FEDERAL COLOR 17778).

THE AESTHETIC SURFACE TREATMENT MUST BE SUBMITTED TO THE DEPARTMENT FOR APPROVAL.




**AESTHETIC SURFACE TREATMENT ELEVATION**

(ASHLAR BLOCK OR APPROVED EQUAL)




**AESTHETIC SURFACE TREATMENT SECTION A-A**




**LIMITS OF MSE WALL EARTHWORK**

**LEGEND:**

- ITEM 203 - EMBANKMENT
- ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN
- ITEM 840 - WALL EXCAVATION
- ITEM 840 - SELECT GRANULAR BACKFILL

**ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN**

EXCAVATION NECESSARY TO CONSTRUCT THE MSE WALL AND/OR PROPOSED BRIDGE ABUTMENT NOT SEPARATELY INCLUDED WITH ITEM 840 - WALL EXCAVATION SHALL BE INCLUDED WITH THE LUMP SUM BID PRICE FOR ITEM 503, UNCLASSIFIED EXCAVATION, AS PER PLAN, FOR PAYMENT. PLAN DETAILS DEPICT ANTICIPATED EXCAVATION; HOWEVER THE CONTRACTOR SHALL DETERMINE THE FINAL QUANTITIES BASED UPON FIELD MEASUREMENTS.

THE FOLLOWING ESTIMATED EXCAVATION QUANTITY IS PROVIDED FOR REFERENCE ONLY AND ARE BASED UPON AN ASSUMED MAXIMUM CUT SLOPE OF 1.5H:1V.

| ESTIMATED - ITEM 203 EXCAVATION | |
|---|---|
| MSE WALL NO. | EXCAVATION (CY.) |
| #1 | X.XX |

ALL EXCAVATION AND SUBSEQUENT BACKFILL BELOW THE EXISTING GROUND SHALL BE PERFORMED PER THE APPLICABLE SECTIONS OF C&MS 203 AND 503. SUITABLE SITE SOILS DISPLACED DURING WALL EXCAVATION MAY BE REUSED AS EMBANKMENT MATERIAL WITHIN THE LIMITS SHOWN WITHIN THESE PLANS. THE SUITABILITY OF ALL SITE SOILS INTENDED FOR REUSE SHALL BE APPROVED BY AN ON-SITE GEOTECHNICAL ENGINEER LICENSED IN THE STATE OF OHIO PRIOR TO PLACEMENT AND SOILS SHALL CONFORM TO BACKFILL REQUIREMENTS OF C&MS 203.

**ESTIMATED QUANTITIES - MSE WALL #1**

| CALC. | DATE | CHK'D | DATE |
|---|---|---|---|
| XXX | XX/YY/ZZ | XXX | XX/YY/ZZ |


| ITEM | ITEM EXT. | TOTAL | UNIT | DESCRIPTION | SHEET REF. |
|---|---|---|---|---|---|
| 203 | 20000 | | CY | EMBANKMENT | |
| 203 | 35120 | | CY | GRANULAR MATERIAL, TYPE C | |
| | | | | | |
| 503 | 21301 | | LS | UNCLASSIFIED EXCAVATION, AS PER PLAN | XX |
| | | | | | |
| 509 | 10000 | | LB | EPOXY COATED STEEL REINFORCEMENT | |
| 510 | 10000 | | EA | DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT | |
| 511 | 71100 | | CY | CONCRETE, MISC.: CLASS QC1 CONCRETE, GUTTER | XX |
| 512 | 10100 | | SY | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) | |
| 516 | 13600 | | SF | 1" PREFORMED EXPANSION JOINT FILLER | |
| | | | | | |
| 840 | 20000 | | SF | MECHANICALLY STABILIZED EARTH WALL | |
| 840 | 21000 | | CY | WALL EXCAVATION | |
| 840 | 22000 | | SY | FOUNDATION PREPARATION | |
| 840 | 23000 | | CY | SELECT GRANULAR BACKFILL | |
| 840 | 25010 | | FT | 6" DRAINAGE PIPE, PERFORATED | |
| 840 | 25020 | | FT | 6" DRAINAGE PIPE, NON-PERFORATED | |
| 840 | 26000 | | FT | CONCRETE COPING | |
| 840 | 26050 | | SF | AESTHETIC SURFACE TREATMENT | XX |
| 840 | 27000 | | DAY | ON-SITE ASSISTANCE | |
| 840 | 28000 | | LS | SGB INSPECTION AND COMPACTION TESTING | |
| | | | | | |
| SPECIAL | 530000400 | | EA | STRUCTURES: SETTLEMENT PLATFORMS | XX |

# MSE WALL NOTES & ESTIMATED QUANTITIES
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.

| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MJR |
| CHECKER | DBL |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 59 |
| TOTAL | 65 |
| SHEET | P. 479 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: MSE Wall Notes and Quantities PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:58:13 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SN010.dgn




**PLAN**

| MSE WALL INFORMATION | | | |
|---|---|---|---|
| LOCATION | BORING NO. | MAX WALL DESIGN HEIGHT | REINFORCING LENGTH (FT) |
| R.A. | B-043-0-22 | 32.50' | 0.70H |

| MSE WALL CRITICAL POINT DATA | | | | |
|---|---|---|---|---|
| CONTROL POINT NO. | MSE WALL STATION | ℄ CONST. I-71 STATION | ℄ CONST. I-71 OFFSET | TOP OF WALL ELEVATION |
| 1 | 1+00.00 | 1312+53.02 | 115.72' RT. | 883.50 |
| 2 | 1+12.00 | 1312+57.34 | 104.47' RT. | 889.30 |
| 3 | 3+44.00 | 1312+13.02 | 124.49' LT. | 889.30 |
| 4 | 3+64.00 | 1312+07.88 | 140.06' LT. | 881.20 |

***LEGEND:***


*Δ - SEALING OF CONCRETE SURFACES (EPOXY URETHANE): SEAL EXTERIOR SURFACES OF ALL PANELS AND COPING*

*ΔΔ - 3'-0" MIN.*

*C.P. - CRITICAL POINT*

***NOTES:***

1. *FOR ADDITIONAL MSE WALL DETAILS, SEE SHEET 61.*





***PROFILE ALONG ℄ CONST. MSE WALL 1***

# MSE WALL PLAN AND ELEVATION
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 60 |
| TOTAL | 65 |
| SHEET | P. 480 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: BLP_WALL1 - MSE WALL 1 [Sheet] PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:59:34 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SR004.dgn




**TYPICAL MSE WALL SECTION UNDER BRIDGE**




**COPING EXPANSION DETAIL**
(NOT TO SCALE)





**TYPICAL MSE WALL SECTION ALONG WINGWALL**

**LEGEND:**


\+ - LIMITS OF SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)

**NOTES:**


1. FOR MSE WALL PLAN, ELEVATION AND MSE WALL DATA, SEE SHEET 60.





**CONCRETE SEALING DETAIL AT ABUTMENT AND WINGWALL**





**CONCRETE SEALING DETAIL AT END OF MSE WALL**




**TYPICAL MSE WALL SECTION AT END OF WINGWALL**




**MSE WALL COPING DETAIL**
(NOT TO SCALE)




**TYPICAL MSE WALL SECTION AT END OF MSE WALL**

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 11:59:50 AM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508192\Sheets\109164_SFN_2508192_SR005.dgn

MSE WALL DETAILS
BRIDGE NO. FRA-00071-24.460 L/R
I-71 OVER MORSE RD.


| | |
|---|---|
| SFN | TBD |
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 61 |
| TOTAL | 65 |
| SHEET | P. 481 |
| TOTAL | 618 |

| NUMBERS | | | | LENGTH | WEIGHT | TYPE | DIMENSIONS | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MARK | SOUTHBOUND | NORTHBOUND | TOTAL | | | | A | B | C | D | E | R | INC |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | |

| NUMBERS | | | | LENGTH | WEIGHT | TYPE | DIMENSIONS | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MARK | SOUTHBOUND | NORTHBOUND | TOTAL | | | | A | B | C | D | E | R | INC |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | |

| NUMBERS | | | | LENGTH | WEIGHT | TYPE | DIMENSIONS | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MARK | SOUTHBOUND | NORTHBOUND | TOTAL | | | | A | B | C | D | E | R | INC |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | |

| NUMBERS | | | | LENGTH | WEIGHT | TYPE | DIMENSIONS | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MARK | SOUTHBOUND | NORTHBOUND | TOTAL | | | | A | B | C | D | E | R | INC |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | |




**PLAN**

*(GIRDERS AND TEMPORARY SHORING NOT SHOWN FOR CLARITY)*

*(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS*

## BENCHMARK DATA

| | | | | | | |
|---|---|---|---|---|---|---|
| BM #1 STA. | 1411+79.28 | ELEV. | 929.73 | OFFSET | 82.29' | LT. |
| BM #2 STA. | 1415+27.64 | ELEV. | 914.36 | OFFSET | 488.63' | LT. |
| BM #3 STA. | 1418+93.64 | ELEV. | 930.93 | OFFSET | 81.12' | LT. |

## NOTES

1. EARTHWORK LIMITS SHOWN ARE APPROXIMATE. ACTUAL SLOPES SHALL CONFORM TO PLAN CROSS SECTIONS.
2. FOR ADDITIONAL SURVEY INFORMATION, SEE ROADWAY PLANS.
3. FOR BRIDGE PROFILES, SEE SHEET 2.
4. FOR GENERAL PLAN, SEE SHEET 3.

*DESIGN TRAFFIC:*

*2030 ADT = 129,542 2030 ADTT = 14,326*
*2050 ADT = 151,092 2050 ADTT = 16,709*
*DIRECTIONAL DISTRIBUTION = 0.535 NORTHBOUND*

## LEGEND

- BORING LOCATION
- 15'-6" REQUIRED MINIMUM VERTICAL CLEARANCE
  15'-6" ACTUAL MINIMUM VERTICAL CLEARANCE (SEE SHEET 2)

## EXISTING STRUCTURE

*TYPE:* 4-SPAN CONTINUOUS REINFORCED CONCRETE SLAB SUPPORTED ON REINFORCED CONCRETE STUB ABUTMENTS AND CAP AND COLUMN PIERS

*SPANS:* 38'-0", 47'-6", 47'-6", 38'-0" C/C BEARINGS

*ROADWAY:* 64'-3" T/T PARAPET - RIGHT (NORTHBOUND) BRIDGE
76'-9" T/T PARAPET - LEFT (SOUTHBOUND) BRIDGE

*LOADING:* CF2000

*SKEW:* NONE

*WEARING SURFACE:* LMC OVERLAY/MONOLITHIC CONCRETE

*APPROACH SLABS:* AS-1-54/AS-1-81 (25' LONG)

*ALIGNMENT:* TANGENT

*CROWN:* 0.0156 FT/FT

*STRUCTURE FILE NUMBER:* 2508257

*DATE BUILT:* 1959

*DISPOSITION:* TO BE REPLACED

## PROPOSED STRUCTURE

*TYPE:* SINGLE SPAN STEEL PLATE GIRDER (ASTM A709, GRADE 50) WITH COMPOSITE REINFORCED CONCRETE DECK SUPPORTED ON SEMI-INTEGRAL ABUTMENTS WITH MSE WALLS

*SPAN:* 129'-11" C/C BEARINGS

*ROADWAY:* 62'-2" TOE/TOE PARAPET (RIGHT BRIDGE)
76'-9" TOE/TOE PARAPET (LEFT BRIDGE)

*LOADING:* HL93 AND 60 PSF FUTURE WEARING SURFACE

*SKEW:* NONE

*WEARING SURFACE:* 1" MONOLITHIC CONCRETE

*APPROACH SLABS:* 30'-0" LONG (AS-1-15, AS-2-15) W/ TYPE C (REAR AND FWD.)

*CROWN:* 0.016 FT/FT

*DECK AREA:* 8,653 SF (RIGHT), 10,577 SF (LEFT)

*STRUCTURE FILE NUMBER:* TBD (LEFT), TBD (RIGHT)

*COORDINATES:* LATITUDE 40° 05'14.60" NORTH
LONGITUDE 82°59'14.23" WEST


HORIZONTAL SCALE IN FEET
0 10 20 40

# SITE PLAN (1 OF 2)
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | ZF |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 1 |
| TOTAL | 64 |
| SHEET | P. 486 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: CLP_173 - Site Plan [Sheet] PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 2:41:36 PM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Matt.Rotar@jacobs.com WORKSPACE: OHDOTCfx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19101-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SP001.dgn




***PROFILE ALONG PROFILE GRADE - LEFT BRIDGE (SOUTHBOUND)***




***PROFILE ALONG PROFILE GRADE - RIGHT BRIDGE (NORTHBOUND)***

***LEGEND:***

- ● *15'-6" REQUIRED MINIMUM VERTICAL CLEARANCE*
  *15'-6" ACTUAL MINIMUM VERTICAL CLEARANCE*

*(**) - FOR EXISTING FIBER OPTIC AND ELECTRIC UTILITY DISPOSITIONS, SEE LIGHTING & ITS PLANS*

***NOTES:***

1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *FOR GENERAL PLAN, SEE SHEET 3.*

HORIZONTAL SCALE IN FEET
0 10 20 40

# SITE PLAN (2 OF 2)
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | ZF |

REVIEWER MJR 03/13/26

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 2 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 487 | 618 |

FRA-71-19.10

MODEL: CLP_173 - Bridge Profiles [Sheet] PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 3:05:22 PM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SP002.dgn

**GENERAL PLAN**

**NOTES:**

1. FOR TEMPORARY SHORING PLAN, SEE SHEET 13.
2. FOR STAGED CONSTRUCTION DETAILS, SEE SHEETS 7 THRU 8.
3. FOR ABBREVIATION LEGEND, SEE SHEET 5.

HORIZONTAL SCALE IN FEET
0 10 20 40

# GENERAL PLAN
## BRIDGE NO. FRA-00071-26.460 L/R
## I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | ZF |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 3 |
| TOTAL | 64 |
| SHEET | P.488 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: CLP_173 - Bridge General Plan [Sheet] PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 3:35:23 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Chris.Lawrence1@jacobs.com WORKSPACE: OHDOTCEx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SG001.dgn

**STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS**

REFER TO THE FOLLOWING STANDARD BRIDGE DRAWINGS:

| | | |
|---|---|---|
| AS-1-15 | REVISED | 1/20/2023 |
| AS-2-15 | REVISED | 7/21/2023 |
| GSD-1-19 | REVISED | 7/19/2024 |
| PCB-91 | REVISED | 7/17/2020 |
| SBR-1-20 | REVISED | 7/19/2024 |
| SBR-2-20 | REVISED | 7/19/2024 |
| SICD-1-21 | REVISED | 1/19/2024 |
| SICD-2-14 | REVISED | 1/15/2021 |

AND TO THE FOLLOWING SUPPLEMENTAL SPECIFICATION(S):

| | | |
|---|---|---|
| 800 | DATED | XX/YY/ZZZZ |
| 840 | DATED | 1/16/2026 |
| 866 | DATED | 4/21/2017 |
| 867 | DATED | 4/15/2022 |

**DESIGN SPECIFICATIONS**

THIS STRUCTURE CONFORMS TO THE 9th EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020 AND THE ODOT BRIDGE DESIGN MANUAL, 2020, DATED JULY 2025.

**OPERATIONAL IMPORTANCE**

A LOAD MODIFIER OF 1.05 HAS BEEN ASSUMED FOR THE DESIGN OF THIS STRUCTURE IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, ARTICLE 1.3.5 AND THE ODOT BRIDGE DESIGN MANUAL.

**DESIGN LOADING**

DESIGN LOADING INCLUDES:
VEHICULAR LIVE LOAD: HL-93
FUTURE WEARING SURFACE (FWS) OF 0.060 KIPS/SQ.FT.

**DESIGN DATA**

CONCRETE CLASS QC2 - COMPRESSIVE STRENGTH 4.5 KSI (SUPERSTRUCTURE)

CONCRETE CLASS QC2 - COMPRESSIVE STRENGTH 4.5 KSI (DRILLED SHAFT)

CONCRETE CLASS QC1 - COMPRESSIVE STRENGTH 4.0 KSI (SUBSTRUCTURE)

CONCRETE REINFORCEMENT:

EPOXY COATED STEEL REINFORCEMENT - MINIMUM YIELD STRENGTH - 60-KSI

GFRP REINFORCEMENT (PARAPETS)

STRUCTURAL STEEL - ASTM A709 GRADE 50 - YIELD STRENGTH 50 KSI (GIRDERS, CONNECTION PLATES, SPLICE PLATES, CROSS FRAMES MEMBERS, BEARING STIFFENERS, LOAD PLATES, SEMI-INTEGRAL ABUTMENT PEDESTALS)

STEEL CAST-IN-PLACE (C.I.P.) REINFORCED CONCRETE PIPE PILES (C&MS 507) - ASTM A252 GRADE 3 - YIELD STRENGTH 45 KSI

**DECK PROTECTION METHOD**

EPOXY COATED REINFORCING STEEL
2½" CONCRETE COVER

**MONOLITHIC WEARING SURFACE**

A MONOLITHIC WEARING SURFACE IS ASSUMED, FOR DESIGN PURPOSES TO BE 1 INCH THICK.

**EXISTING BRIDGE PLANS**

FOR INFORMATION NOT SHOWN, EXISTING BRIDGE PLANS MAY BE INSPECTED IN THE OFFICE OF STRUCTURAL ENGINEERING IN COLUMBUS, OHIO OR AT THE DISTRICT 6 OFFICE, 400 EAST WILLIAM STREET, DELAWARE, OHIO 43015.

**MAINTENANCE OF TRAFFIC**

FOR MAINTENANCE OF TRAFFIC PLANS, SEE ROADWAY SHEETS.

**UTILITIES**

FOR UTILITY NOTES, SEE ROADWAY SHEETS.

**EXISTING STRUCTURE VERIFICATION**

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURES HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURES AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE(S) AND THE PROPOSED WORK, BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO C&MS SECTIONS 102.05, 105.02 AND 513.04 FOR FURTHER INFORMATION.

BASE CONTRACT BID PRICES UPON A RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON A PREBID EXAMINATION OF THE EXISTING STRUCTURE. HOWEVER, THE DEPARTMENT WILL PAY FOR ALL PROJECT WORK BASED UPON ACTUAL DETAILS AND DIMENSIONS THAT HAVE BEEN VERIFIED IN THE FIELD.

**ASBESTOS NOTIFICATION**

AN ASBESTOS SURVEY OF THE BRIDGE WAS CONDUCTED BY A CERTIFIED ASBESTOS HAZARD EVALUATION SPECIALIST. THE SURVEY DETERMINED THAT NO ASBESTOS IS PRESENT AT THE BRIDGES.

A COPY OF THE OHIO ENVIRONMENTAL PROTECTION AGENCY (OEPA) NOTIFICATION OF DEMOLITION AND RENOVATION FORMS, PARTIALLY COMPLETED AND SIGNED BY THE BRIDGE OWNER, WILL BE PROVIDED TO THE SUCCESSFUL BIDDER. THE CONTRACTOR SHALL COMPLETE THE FORM AND SUBMIT IT TO:

OHIO EPA, CDO
50 WEST TOWN ST, SUITE 700
COLUMBUS, OHIO 43215
KELLY TOTH, APC MANAGER
(614) 728-3778
FAX: (614) 728-3898

THE CONTRACTOR SHALL PROVIDE A COPY OF THE COMPLETED FORM TO THE ENGINEER AT LEAST TEN (10) WORKING DAYS PRIOR TO THE START OF ANY DEMOLITION AND/OR REHABILITATION.

INFORMATION REQUIRED ON THE FORM SHALL INCLUDE: 1) THE CONTRACTOR NAME, ADDRESS AND CONTACT INFORMATION 2) THE SCHEDULED DATES FOR THE START AND COMPLETION OF THE BRIDGE REMOVAL AND 3) A DESCRIPTION OF THE PLANNED DEMOLITION WORK AND THE METHOD(S) TO BE USED.

THE CONTRACTOR SHALL FURNISH ALL FEES, LABOR, MATERIAL, EQUIPMENT AND INCIDENTALS NECESSARY TO COMPLETE AND SUBMIT THE OEPA NOTIFICATION FORM.

**ITEM 202 - PORTIONS OF STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN**

THE PROVISIONS OF C&MS 202 APPLY, IN ADDITION TO THOSE LISTED HEREIN. THIS ITEM SHALL INCLUDE THE ELEMENTS INDICATED IN THE PLANS AND GENERAL NOTES AND THAT ARE NOT SEPARATELY LISTED FOR PAYMENT. ITEMS TO BE REMOVED INCLUDE ALL EXISTING MATERIALS BEING REPLACED BY NEW CONSTRUCTION AND MISCELLANEOUS ITEMS THAT ARE NOT SHOWN TO BE INCORPORATED INTO THE FINAL CONSTRUCTION AND ARE DIRECTED TO BE REMOVED BY THE ENGINEER. THE USE OF EXPLOSIVES AND HEADACHE BALLS WILL NOT BE PERMITTED. THE METHOD OF REMOVAL AND THE WEIGHT OF HAMMER SHALL BE APPROVED BY THE ENGINEER. PERFORM ALL WORK CAREFULLY TO PROTECT PORTIONS OF SUCH SYSTEMS THAT ARE TO BE SALVAGED FOR MAINTAINING TRAFFIC.

**CUT LINE CONSTRUCTION JOINT PREPARATION:**
SAW CUT BOUNDARIES OF PROPOSED CONCRETE REMOVALS 1 INCH DEEP. REMOVE CONCRETE TO A ROUGH SURFACE.

**REMOVAL METHODS:**
THE CONTRACTOR MAY REMOVE CONCRETE BY CUTTING AND BY MEANS OF HAND OPERATED PNEUMATIC HAMMERS EMPLOYING POINTED OR BLUNTED CHISEL TYPE TOOLS. UNLESS OTHERWISE ADVISED BY THE ENGINEER, THE CONTRACTOR IS PERMITTED TO USE A HYDRAULIC HOE-RAM ONLY FOR SUBSTRUCTURE REMOVALS ONLY AFTER THE PHASED REMOVAL LIMITS OF THE SUPERSTRUCTURE ARE COMPLETE FOR THAT PHASE. THE CONTRACTOR MUST SUBMIT DEMOLITION PLAN(S) ACCORDING TO C&MS 501.05.

**PILE DRIVING CONSTRAINTS**

PRIOR TO DRIVING REAR AND FORWARD ABUTMENT PILES TO THE ULTIMATE BEARING VALUE (UBV), CONSTRUCT THE MSE WALL AND THE BRIDGE APPROACH EMBANKMENT BEHIND THE ABUTMENTS UP TO THE BOTTOM OF FOOTING ELEVATION FOR A MINIMUM DISTANCE OF 200 FEET BEHIND EACH ABUTMENT. THE CONTRACTOR MAY PRE-DRIVE ABUTMENT PILES INTO THE SOILS ONLY AS FAR AS NECESSARY SO THAT THE PILE WILL REMAIN VERTICAL DURING MSE WALL CONSTRUCTION. IF PRE-DRIVING PILES, INSTALL PILE SLEEVES AROUND PILES BEFORE CONSTRUCTING THE MSE WALL. PROVIDE AT LEAST 3-FEET OF PILE ABOVE THE TOP OF PILE SLEEVE TO MEET THE REQUIREMENTS OF C&MS 507.09 REGARDING SPLICES. DO NOT DRIVE ABUTMENT PILES TO THE DRIVING CRITERIA DETERMINED BY RESTRIKE TESTING UNTIL AFTER THE ABOVE REQUIRED MSE ALL AND EMBANKMENT HAVE BEEN CONSTRUCTED AND A 21 CALENDAR WAITING PERIOD HAS ELAPSED. THE ENGINEER MAY ADJUST THE LENGTH OF THE WAITING PERIOD BASED ON SETTLEMENT PLATFORM READINGS. AFTER THE SPECIFIED WAITING PERIOD HAS ELAPSED, DRIVE ABUTMENT PILES TO THE DRIVING CRITERIA DETERMINED BY RESTRIKE TESTING. IN ORDER TO REMOVE ANY NEGATIVE SKIN FRICTION THAT HAS DEVELOPED DURING THE WAITING PERIOD, DRIVE EACH ABUTMENT PILE A DISTANCE OF AT LEAST 0.5-INCH.

IF NOT PRE-DRIVING ABUTMENT PILES, INSTALL THE ABUTMENT PILES THROUGH THE PILE SLEEVES AFTER THE ABOVE REQUIRED MSE WALL AND EMBANKMENT HAVE BEEN CONSTRUCTED AND THE SPECIFIED WAITING PERIOD HAS ELAPSED.

**PILE DESIGN LOADS (ULTIMATE BEARING VALUE, UBV)**

THE ULTIMATE BEARING VALUE IS 357 KIPS PER FOOT FOR ABUTMENT PILES.

ABUTMENT PILES:
14" DIAMETER C.I.P. PILES

REAR ABUTMENT:
ESTIMATED LENGTH = 75'-0"
ORDER LENGTH = 80'-0"

FORWARD ABUTMENT:
ESTIMATED LENGTH = 70'-0"
ORDER LENGTH = 75'-0"

PILE DRIVING: THE MAXIMUM RATED ENERGY OF THE HAMMER USED TO INSTALL THE PILES SHALL NOT EXCEED 47,000 FOOT-POUNDS. ENSURE THAT STRESSES IN THE PILES DURING DRIVING DO NOT EXCEED 40,500 POUNDS PER SQUARE INCH.

A MINIMUM WALL THICKNESS OF 0.250" SHALL BE USED AT ALL THE REAR ABUTMENT PILES. A MINIMUM WALL THICKNESS OF 0.500" SHALL BE USED AT THE FORWARD ABUTMENT PILES. ALL STEEL SHALL BE ASTM A252 STEEL, GRADE 3 WITH A MINIMUM YIELD STRENGTH OF 45 KSI.

**PILES DRIVEN TO FULL ESTIMATED LENGTH WITH PILE/SOIL SETUP**
**ITEM 523 - DYNAMIC LOAD TESTING, AS PER PLAN**
**ITEM 523 - RESTRIKE, AS PER PLAN**

THE ULTIMATE BEARING VALUE (UBV) LISTED ABOVE WILL BE ACHIEVED THROUGH PILE/SOIL SETUP, WHICH IS A TIME DEPENDENT INCREASE THAT OCCURS IN SOME SOILS.

NOTIFY THE ENGINEER AT LEAST 5 WORKING DAYS BEFORE DRIVING PILES SO THAT THE ENGINEER CAN NOTIFY THE DISTRICT GEOTECHNICAL ENGINEER, THE OFFICE OF CONSTRUCTION ADMINISTRATION, AND THE OFFICE OF GEOTECHNICAL ENGINEERING.

DRIVE THE FIRST TWO PILES IN EACH SUBSTRUCTURE TO THEIR FULL ESTIMATED LENGTHS, 75-FEET AT THE REAR ABUTMENT AND 70-FEET AT THE FORWARD ABUTMENT. PERFORM DYNAMIC LOAD TESTING ON BOTH PILES WHILE DRIVING. AFTER DRIVING AND TESTING THE FIRST TWO PILES, DRIVE THE REMAINING PILES IN THE SUBSTRUCTURE TO THE SAME DEPTH AS THE FIRST TWO PILES. AFTER DRIVING ALL PILES TO THE ESTIMATED LENGTH, CEASE ALL DRIVING OPERATIONS AT THE SUBSTRUCTURE FOR A PERIOD OF 7 DAYS. INCLUDE THE WAITING PERIOD AS A SEPARATE ACTIVITY IN THE PROGRESS SCHEDULE. AFTER THE WAITING PERIOD, PERFORM RESTRIKES ON BOTH OF THE FIRST TWO PILES (ONE RESTRIKE ITEM).

SUBMIT ALL TEST RESULTS TO THE ENGINEER. IF THE RESTRIKE RESULTS INDICATE THAT BOTH PILES ACHIEVED THE REQUIRED UBV, ALL PILES IN THE SUBSTRUCTURE MAY BE ACCEPTED BY THE ENGINEER.

IF THE RESTRIKE RESULTS INDICATE THAT EITHER OF THE TWO PILES DID NOT ACHIEVE THE REQUIRED UBV, IMMEDIATELY NOTIFY THE ENGINEER SO THAT THE ENGINEER CAN NOTIFY THE DISTRICT GEOTECHNICAL ENGINEER, THE OFFICE OF CONSTRUCTION ADMINISTRATION, AND THE OFFICE OF GEOTECHNICAL ENGINEERING. THE ENGINEER WILL REVIEW THE TEST RESULTS AND ESTABLISH ADDITIONAL RESTRIKE TESTING OR DRIVING CRITERIA FOR THE PILING IN THE SUBSTRUCTURE WITH THE ASSISTANCE OF THE DISTRICT GEOTECHNICAL ENGINEER, THE OFFICE OF CONSTRUCTION ADMINISTRATION, AND THE OFFICE OF GEOTECHNICAL ENGINEERING.

IF DIRECTED BY THE ENGINEER, PERFORM ADDITIONAL RESTRIKE TESTING OR DRIVE ALL PILES IN THE SUBSTRUCTURE TO THE ESTABLISHED DRIVING CRITERIA. THE DEPARTMENT WILL PAY FOR SPLICING OF THE PILES BEYOND THE ESTIMATED LENGTH PROVIDED IN THE PLANS UNDER C&MS 109.05 WITH A NEGOTIATED PRICE PER SPLICE.

THIS PLAN NOTE INCLUDES A QUANTITY OF ONE EACH ITEM 523 DYNAMIC LOAD TESTING, AS PER PLAN AND A QUANTITY OF ONE EACH ITEM 523 RESTRIKE, AS PER PLAN PER EACH SUBSTRUCTURE UNIT.

**ITEM 514 - FIELD PAINTING OF STRUCTURAL STEEL, FINISH COAT**

THE COLOR OF THE FINISH COAT SHALL BE FEDERAL COLOR NO. FS 595 17038, OSHA BLACK/ANA 515/622.

**DECK PLACEMENT ASSUMPTIONS**

THE FOLLOWING ASSUMPTIONS OF CONSTRUCTION MEANS AND METHODS WERE MADE FOR THE ANALYSIS AND DESIGN OF THE SUPERSTRUCTURE. THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN OF THE FALSEWORK SUPPORT SYSTEM WITHIN THESE PARAMETERS AND WILL ASSUME RESPONSIBILITY FOR SUPERSTRUCTURE ANALYSIS FOR DEVIATION FROM THESE DESIGN ASSUMPTIONS.

AN EIGHT WHEEL FINISHING MACHINE.

| BRIDGE | CONST. PHASE | MAX. WHEEL LOAD (KIP) | MAX. RAIL-TO-RAIL WIDTH (FT.) | MAX. BRACKET OVERHANG (MEASURED ℄ FROM GIRDER) (IN.) |
|---|---|---|---|---|
| LEFT | 3A | 2.2 | 42.33 | 70 |
| LEFT | 3B | 2.2 | 31.67 | 70 |
| RIGHT | 4A | 2.2 | 31.11 | 70 |
| RIGHT | 4B | 2.2 | 31.21 | 70 |

A MINIMUM OUT-TO-OUT WHEEL SPACING AT EACH END OF THE MACHINE OF 103".

A MAXIMUM SPACING OF OVERHANG FALSEWORK BRACKETS OF 48".

**ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN**

THE DESIGN(S) SHOWN ON THE PLANS FOR TEMPORARY SUPPORT OF EXCAVATION IS ONE REPRESENTATIVE DESIGN THAT MAY BE USED TO CONSTRUCT THE PROJECT. THE CONTRACTOR MAY CONSTRUCT THE DESIGN SHOWN ON THE PLANS OR PREPARE AN ALTERNATE DESIGN TO SUPPORT THE SIDES OF EXCAVATIONS. IF CONSTRUCTING AN ALTERNATE DESIGN FOR TEMPORARY SUPPORT OF EXCAVATION, PREPARE AND PROVIDE PLANS IN ACCORDANCE WITH C&MS 501.05. THE DEPARTMENT WILL PAY FOR THE TEMPORARY SUPPORT OF EXCAVATION AT THE CONTRACT LUMP SUM PRICE FOR COFFERDAMS AND EXCAVATION BRACING. THE DEPARTMENT WILL NOT MAKE ADDITIONAL PAYMENT FOR PROVIDING AN ALTERNATE DESIGN. THE FOLLOWING CRITERIA APPLIES TO CANTILEVER (I.E. UNANCHORED), STEEL SHEET PILING SHOWN IN THE PLANS.

REFER TO SHEET 12 FOR ADDITIONAL NOTES.

**ITEM 622 - PORTABLE BARRIER, 32", BRIDGE MOUNTED, AS PER PLAN**

THE CONTRACTOR SHALL UTILIZE AN ANCHORED PORTABLE BARRIER SYSTEM WHERE SPECIFIED IN THE PLANS AND GENERAL NOTES. THE CONTRACTOR IS PERMITTED TO USE PCB-91 OR RM-4.2 SEGMENTS EXCEPT AS NOTED HEREIN. THE USE OF RM-4.2 IS NOT PERMITTED WHERE LESS THAN ONE FOOT OF EDGE DISTANCE (MEASURED FROM THE EDGE OF DECK ALONG THE REMOVAL LINE TO THE NEAREST TOE OF BARRIER) IS PROVIDED. THE CONTRACTOR SHALL UTILIZE PCB-91 OR THE EASI-SET WORLDWIDE TEMPORARY BARRIER (OR APPROVED EQUAL) WHERE LESS THAN ONE FOOT OF EDGE DISTANCE IS PROVIDED.

THE FOLLOWING ANCHOR REQUIREMENTS APPLY:

| | NO. OF ANCHORS REQUIRED (EACH BARRIER SEGMENT) | |
|---|---|---|
| | EDGE DISTANCE, D < 1'-0" | EDGE DISTANCE, D >= 1'-0" |
| PCB-91 | 6 | 3 |
| RM-4.2 | NOT PERMITTED | 2 |
| EASI-SET WORLDWIDE (OR APPROVED EQUAL) | SEE MANUFACTURER RECOMMENDATIONS | SEE MANUFACTURER RECOMMENDATIONS |

ALL LABOR, MATERIALS, TOOLS, EQUIPMENT AND INCIDENTALS TO CONSTRUCT ANCHORED PORTABLE BARRIER INCLUDING APPROVED ALTERNATES AS DESCRIBED ABOVE WILL BE PAID AT THE CONTRACT BID PRICE FOR ITEM 622 - PORTABLE BARRIER, 32", BRIDGE MOUNTED, AS PER PLAN.

STRUCTURE GENERAL NOTES (1 OF 2)
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN
TBD

DESIGN AGENCY
Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | FM |

REVIEWER
MJR 03/13/26

PROJECT ID
109164

| SUBSET | TOTAL |
|---|---|
| 4 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 489 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:22:31 PM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19101-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SN001.dgn

## ITEM SPECIAL - SETTLEMENT PLATFORMS

*DESCRIPTION:*

*THIS ITEM CONSISTS OF FURNISHING, CONSTRUCTING, AND MAINTAINING SETTLEMENT PLATFORMS WITHIN THE PROPOSED ABUTMENT EMBANKMENTS AND/OR MSE WALL BACKFILL AND OBTAINING SETTLEMENT READINGS AS REQUIRED BY THE PLANS OR AS DIRECTED BY THE ENGINEER. AT THE OPTION AND THE EXPENSE OF THE CONTRACTOR, ADDITIONAL SETTLEMENT PLATFORMS MAY BE INSTALLED AT LOCATIONS APPROVED BY THE ENGINEER. SETTLEMENT READINGS SHALL BE TAKEN WEEKLY DURING CONSTRUCTION AND DURING THE WAITING PERIOD. THE READINGS SHALL BE PLOTTED ON GRAPH PAPER PRESENTING DEFORMATION (ON THE NEGATIVE Y-AXIS) AND FILL HEIGHT (ON THE POSITIVE Y-AXIS) VERSUS TIME (ON THE X-AXIS). IN ORDER TO CREATE THE GRAPH, USE THE SETTLEMENT PLATFORM SPREADSHEET LOCATED AT THE LINK BELOW ON THE OGE WEBSITE PUBLICATIONS AND DOCUMENTS SECTION.*

*HTTP://WWW.DOT.STATE.OH.US/GEOTECHNICAL/PAGES/SETTELMENT.ASPX*

*A COPY OF EACH CUMULATIVE PLOT SHALL BE SENT TO THE OFFICE OF GEOTECHNICAL ENGINEERING, ATTENTION: GEOTECHNICAL DESIGN COORDINATOR, AFTER EACH SETTLEMENT READING IS RECORDED.*

***MATERIALS:***

*SOUND LUMBER SUCH AS 19MMM (3/4-INCH) EXTERIOR GRADE PLYWOOD SHALL BE USED FOR THE BASE. THE PIPE SHALL BE 64MM (2-1/2-INCH) STANDARD BLACK PIPE WITH THREADED FITTINGS AS SHOWN ON THE PLANS. A STEEL PLATE 915MM X 915MM X 3.2MM (36" X 36" X 1/8") MAY BE SUBSTITUTED FOR THE LUMBER FOR THE PLATFORMS, AT THE CONTRACTOR'S OPTION.*

***CONSTRUCTION METHODS:***

*THE PLATFORM SHALL CONFORM TO THE DETAILS SHOWN ON THE PLANS. THE PLATFORM SHALL BE SET ON A LEVEL SURFACE. THE PIPE SHALL BE FIRMLY SECURED TO THE PLATFORM AND SHALL BE MAINTAINED IN A PLUMB POSITION DURING PLACEMENT OF THE EMBANKMENT AND/OR MSE WALL CONSTRUCTION. THE PIPE SHALL BE MARKED AT INTERVALS TO FACILITATE MEASUREMENT OF THE DEPTH OF FILL. THE CONTRACTOR SHALL PROTECT SETTLEMENT PLATFORMS FROM CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL STOP WORK IN ANY LOCATION WHERE THE SETTLEMENT PLATFORM HAS BEEN DISTURBED OR DAMAGED. PLATFORMS OR PIPES DAMAGED OR DISPLACED DURING CONSTRUCTION SHALL BE RESTORED TO THEIR PROPER CONDITION AT THE CONTRACTOR'S EXPENSE.*

*THE TOP OF SETTLEMENT PLATFORM PIPE SHALL BE CUT OFF ONE FOOT BELOW THE BOTTOM OF FOOTING ELEVATION OR TWO FEET BELOW THE FINISHED GROUND SURFACE, WHICHEVER IS APPLICABLE.*

***CRITERIA:***

*REMAINING SETTLEMENT (AFTER WAITING PERIOD) IS LESS THAN OR EQUAL TO 1 INCH FOR WALLS AND EMBANKMENTS.*

***WAITING PERIOD:***

*THE WAITING PERIOD SHALL NOT BE CONSIDERED TO BEGIN UNTIL ALL FILL IS CONSTRUCTED TO THE BOTTOM OF FOOTING ELEVATIONS. THE FILL SHALL CONSISTS OF THE PROPOSED MSE WALL BACKFILL OR EMBANKMENT CONSTRUCTED TO THE ENTIRE LATERAL EXTENTS OF THE PHASED CONSTRUCTION WITHIN ONE FOOT OF THE PROPOSED VERTICAL EXTENTS.*

*NO CONSTRUCTION OF STRUCTURES (INCLUDING FOUNDATIONS, LIMITED CONSTRUCTION OF PILE DRIVING SPECIFIED HEREIN, MSE WALL TOP PANELS, COPING, ETC.) OR PAVING OF ROADWAYS SHALL BEGIN UNTIL CONFIRMATION HAS BEEN RECEIVED FROM THE ENGINEER THAT THE CRITERIA TO END THE WAITING PERIOD HAVE BEEN MET.*


*IT IS ANTICIPATED THAT AFTER COMPLETION OF MSE WALL AND/OR EMBANKMENT CONSTRUCTION, A 21 CALENDAR DAY WAITING PERIOD AT THE REAR ABUTMENT (MSE WALL 1) AND A 21 CALENDAR DAY WAITING PERIOD AT THE FORWARD ABUTMENT WILL BE REQUIRED BEFORE THE SETTLEMENT RATE THRESHOLD IS ACHIEVED.*

***METHOD OF MEASUREMENT**:*

*THE NUMBER OF SETTLEMENT PLATFORMS TO BE PAID FOR SHALL BE THE ACTUAL NUMBER OF SETTLEMENT PLATFORMS COMPLETED, MAINTAINED, AND ACCEPTED BY THE ENGINEER.*

***BASIS OF PAYMENT:***

*PAYMENT SHALL BE MADE AT THE CONTRACT UNIT PRICE EACH FOR ITEM SPECIAL - SETTLEMENT PLATFORMS WHICH IS COMPENSATION FOR CONSTRUCTING, MAINTAINING, AND MONITORING THE SETTLEMENT PLATFORMS INCLUDING FURNISHING ALL LABOR, MATERIAL, EQUIPMENT, TOOLS AND INCIDENTALS NECESSARY TO COMPLETE THE WORK. PAYMENT SHALL NOT BE MADE FOR SETTLEMENT PLATFORMS WHICH BECOME USELESS DUE TO DAMAGE CAUSED BY THE CONTRACTOR'S OPERATIONS.*




***SETTLEMENT PLATFORM DETAILS***

## SEQUENCE OF CONSTRUCTION

*THE PROPOSED BRIDGE WORK (INCLUDING THE APPROACH SLABS) SHALL BE COORDINATED WITH OVERALL PROJECT MAINTENANCE OF TRAFFIC PLANS.*

*FOR ADDITIONAL DETAILS REGARDING SEQUENCE OF CONSTRUCTION OF TEMPORARY SHORING, SEE SHEET 13.*

***PHASE 3A***

1. *INSTALL PORTABLE CONCRETE BARRIERS ON NORTHBOUND (RIGHT) AND SOUTHBOUND (LEFT) LANES AND DIVERT TRAFFIC AS SHOWN ON MOT PLANS.*
2. *REMOVE PORTIONS OF THE EXISTING SUPERSTRUCTURE AS SHOWN IN THE PLANS.*
3. *INSTALL TEMPORARY SHORING.*
4. *REMOVE PORTIONS OF EXISTING SUBSTRUCTURE.*
5. *COMPLETE PHASE 3A CONSTRUCTION.*

***PHASE 3B***

1. *INSTALL PORTABLE CONCRETE BARRIER ON PHASE 3A CONSTRUCTION AND DIVERT SOUTHBOUND TRAFFIC TO MOT PHASE 3B.*
2. *REMOVE REMAINING PORTIONS OF EXISTING SOUTHBOUND (LEFT) BRIDGE.*
3. *CONSTRUCT PHASE 3B AND CLOSURE POUR.*

***PHASE 4A***

1. *INSTALL PORTABLE CONCRETE BARRIERS ON NORTHBOUND (RIGHT) AND SOUTHBOUND (LEFT) LANES AND DIVERT TRAFFIC AS SHOWN ON MOT PLANS.*
2. *REMOVE PORTIONS OF THE EXISTING NORTHBOUND SUPERSTRUCTURE AS SHOWN IN THE PLANS.*
3. *INSTALL TEMPORARY SHORING.*
4. *REMOVE PORTIONS OF EXISTING SUBSTRUCTURE.*
5. *COMPLETE PHASE 4A CONSTRUCTION.*

***PHASE 4B***

1. *INSTALL PORTABLE CONCRETE BARRIER ON PHASE 4A CONSTRUCTION AND DIVERT NORTHBOUND TRAFFIC TO MOT PHASE 4B.*
2. *REMOVE REMAINING PORTIONS OF EXISTING NORTHBOUND (RIGHT) BRIDGE.*
3. *CONSTRUCT PHASE 4B AND CLOSURE POUR.*

***ABBREVIATION LEGEND:***

*ABUT. - ABUTMENT*
*ADT - AVERAGE DAILY TRAFFIC*
*ADTT - AVERAGE DAILY TRUCK TRAFFIC*
*APPR. - APPROACH*
*B OR BOT. - BOTTOM*
*BM - BENCHMARK*
*BRG. - BEARING*
*℄ - CENTERLINE*
*C/C - CENTER TO CENTER*
*C.I.P. - CAST-IN-PLACE*
*C.J. - CONSTRUCTION JOINT*
*CLR. - CLEAR*
*C&MS - CONSTRUCTION AND MATERIAL SPECIFICATIONS*
*CONST. - CONSTRUCTION*
*C.P. - CLOSURE POUR*
*CVN - CHARPY V-NOTCH*
*DIA. - DIAMETER*
*DIST. - DISTANCE*
*DND - DO NOT DISTURB*
*DWG. - DRAWING*
*E.F. - EACH FACE*
*EL. OR ELEV. - ELEVATION*
*EOP - EDGE OF PAVEMENT*
*EQ. - EQUAL*
*EST. - ESTIMATED*
*EX. - EXISTING*
*EXP. - EXPANSION*
*F.A. - FORWARD ABUTMENT*
*F/F - FACE TO FACE*
*FT. - FOOT OR FEET*
*FTG. - FOOTING*
*FWD. - FORWARD*
*HMWM - HIGH MOLECULAR WEIGHT METHACRYLATE*
*IN. - INCH*
*JT. - JOINT*
*LT. - LEFT*
*MAX. - MAXIMUM*
*MISC. - MISCELLANEOUS*
*MSE - MECHANICALLY STABILIZED EARTH*
*NB - NORTHBOUND*
*NO. - NUMBER*
*N.P.C.P.P - NON-PERFORATED CORRUGATED PLASTIC PIPE*
*O/O - OUT TO OUT*
*P.C.P.P. - PERFORATED CORRUGATED PLASTIC PIPE*
*P.E.J.F. - PREFORMED EXPANSION JOINT FILLER*
*PG - PROFILE GRADE*
*PGL - PROFILE GRADE LINE*
*PROP. - PROP.*
*R - RADIUS*
*REF. - REFERENCE*
*RNDG. - ROUNDING*
*RT. - RIGHT*
*R/W - RIGHT OF WAY*
*SB - SOUTHBOUND*
*SCD - STANDARD CONSTRUCTION DRAWING*
*SER. - SERIES*
*SHD. OR SHLDR. - SHOULDER*
*SPA. - SPACE OR SPACES*
*STA. - STATION*
*STD. - STANDARD*
*STR - STRAIGHT*
*S.U.P. - SHARED USE PATH*
*T - TOP*
*T/T - TOE TO TOE*
*TEMP - TEMPORARY*
*T&B - TOP AND BOTTOM*
*TBR - TO BE REMOVED*
*TBRO - TO BE RELOCATED BY OTHERS*
*TBRR - TO BE REMOVED AND REPLACED*
*TYP. - TYPICAL*
*U.N.O. - UNLESS NOTED OTHERWISE*
*VAR. - VARIES*
*W.R.T. - WITH RESPECT TO*

STRUCTURE GENERAL NOTES (2 OF 2)
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 5 |
| TOTAL | 64 |
| SHEET | P. 490 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:22:44 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SN002.dgn

## ESTIMATED QUANTITIES

| CALC. | DATE | CHK'D | DATE |
|---|---|---|---|
| MJR | XX/YY/ZZ | XXX | XX/YY/ZZ |

| ITEM | ITEM EXT. | TOTAL LEFT | TOTAL RIGHT | GRAND TOTAL | UNIT | DESCRIPTION | LEFT BRIDGE FRA-71-26.46 L (SFN 250XXXX) | | | | RIGHT BRIDGE FRA-71-26.46 R (SFN 250XXXX) | | | | SHEET REF. |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | ABUT. | PIERS | SUPER. | GEN. | ABUT. | PIERS | SUPER. | GEN. | |
| 202 | 11003 | | | | LS | STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN | | | | | | | | | |
| 202 | 22900 | | | | SY | APPROACH SLAB REMOVED | | | | | | | | | |
| 503 | 11101 | | | | LS | COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN | | | | | | | | | |
| 505 | 11100 | | | | LS | PILE DRIVING MOBILIZATION | | | | | | | | | |
| 507 | 00600 | | | | FT | 14" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN | | | | | | | | | |
| 507 | 00650 | | | | FT | 14" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED | | | | | | | | | |
| 509 | 10000 | | | | LB | EPOXY COATED STEEL REINFORCEMENT | | | | | | | | | |
| 509 | 30020 | | | | FT | NO. 4 DEFORMED GFRP REINFORCEMENT | | | | | | | | | |
| 511 | 33500 | | | | EA | SEMI-INTEGRAL DIAPHRAGM GUIDE | | | | | | | | | |
| 511 | 34446 | | | | CY | CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK | | | | | | | | | |
| 511 | 34450 | | | | CY | CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPET) | | | | | | | | | |
| 511 | 44112 | | | | CY | CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT NOT INCLUDING FOOTING | | | | | | | | | |
| 511 | 46512 | | | | CY | CLASS QC1 CONCRETE WITH QC/QA, FOOTING | | | | | | | | | |
| 512 | 10100 | | | | SY | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) | | | | | | | | | |
| 512 | 33000 | | | | SY | TYPE 2 WATERPROOFING | | | | | | | | | |
| 513 | 10280 | | | | LB | STRUCTURAL STEEL MEMBERS, LEVEL 4 | | | | | | | | | |
| 513 | 20000 | | | | EA | WELDED STUD SHEAR CONNECTORS | | | | | | | | | |
| 514 | 00060 | | | | SF | FIELD PAINTING STRUCTURAL STEEL, INTERMEDIATE COAT | | | | | | | | | |
| 514 | 00066 | | | | SF | FIELD PAINTING STRUCTURAL STEEL, FINISH COAT | | | | | | | | | |
| 516 | 13600 | | | | SF | 2" PREFORMED JOINT FILLER | | | | | | | | | |
| 516 | 13900 | | | | SF | 2" PREFORMED EXPANSION JOINT FILLER | | | | | | | | | |
| 516 | 14020 | | | | FT | SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL | | | | | | | | | |
| 516 | 44300 | | | | EA | ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), (17" x 18" x 4.983" WITH 14" x 25" x 2.0" TOP LOAD PLATE AND 18" x 19" x 2.0" BOT. LOAD PLATE AND W10x49 PEDESTAL) | | | | | | | | | |
| 518 | 21050 | | | | SY | POROUS BACKFILL WITH GEOTEXTILE FABRIC | | | | | | | | | |
| 518 | 40000 | | | | FT | 6" PERFORATED CORRUGATED PLASTIC PIPE | | | | | | | | | |
| 518 | 40010 | | | | FT | 6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS | | | | | | | | | |
| 523 | 20001 | | | | EA | DYNAMIC LOAD TESTING, AS PER PLAN | | | | | | | | | |
| 523 | 20501 | | | | EA | RESTRIKE, AS PER PLAN | | | | | | | | | |
| 526 | 30000 | | | | SY | REINFORCED CONCRETE APPROACH SLABS (T=17") | | | | | | | | | |
| 526 | 90030 | | | | FT | TYPE C INSTALLATION | | | | | | | | | |
| 867 | 00100 | | | | LS | TEMPORARY WIRE FACED MECHANICALLY STABILIZED EARTH WALL | | | | | | | | | |
| SPECIAL | 53000400 | | | | EA | SPECIAL - STRUCTURES - SETTLEMENT PLATFORMS | | | | | | | | | |

**NOTES:**

1. UNLESS NOTED OTHERWISE, ALL PAY ITEMS ARE INCLUDED IN THE FUNDING PARTICIPATION SPLIT CODE XX/YY/ZZ.
2. FOR MSE WALL ESTIMATED QUANTITIES, SEE SHEET 57.

STRUCTURE ESTIMATED QUANTITIES
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | FM |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 6 | 64 |


| SHEET | TOTAL |
|---|---|
| P. 491 | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:22:57 PM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_250825Y\Sheets\109164_SFN_2508257_SQ001.dgn





**PHASE 3A REMOVAL**




**PHASE 3A CONSTRUCTION**




**PHASE 3B REMOVAL**




**PHASE 3B CONSTRUCTION**

***LEGEND:***

- ITEM 202 - STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN

***NOTES:***


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. FINISHING MACHINE SHALL NOT EXTEND BEYOND TOE (TRAFFIC SIDE) OF ANCHORED BARRIER.
3. PORTABLE BARRIER INCLUDED WITH ROADWAY QUANTITIES. SEE SHEET 4 FOR ADDITIONAL NOTES INCLUDING ANCHORAGE REQUIREMENTS.
4. PHASE CONSTRUCTION JOINTS ARE PARALLEL TO THE CENTERLINE CONSTRUCTION I-71. MAINTAIN TRAFFIC PER THE MAINTENANCE OF TRAFFIC PLANS. THE CONTRACTOR SHALL VERIFY THE DIMENSIONS OF THE EXISTING STRUCTURE AND MAY ADJUST EDGE DISTANCES PROVIDED TO NON-TRAFFIC SIDE OF PORTABLE BARRIER AS APPROVED BY THE ENGINEER TO MEET THE VERIFIED CONDITIONS.
5. CROSSFRAMES NOT SHOWN FOR CLARITY. DO NOT PERMANENTLY ATTACH INTERMEDIATE CROSSFRAMES IN THE CLOSURE POUR LOCATION UNTIL THE CONCRETE POURS ON BOTH SIDES OF THE CLOSURE POUR LOCATION HAVE BEEN COMPLETED.
6. FOR SEQUENCE OF CONSTRUCTION, SEE SHEET 5.

# STAGED CONSTRUCTION DETAILS (1 OF 2)
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 7 |
| TOTAL | 64 |
| SHEET | P. 492 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet 1 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:23:12 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SC001a.dgn





**PHASE 4A REMOVAL**




**PHASE 4A CONSTRUCTION**




**PHASE 4B REMOVAL**




**PHASE 4B CONSTRUCTION**

***LEGEND:***

- ITEM 202 - STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN

***NOTES:***


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. FINISHING MACHINE SHALL NOT EXTEND BEYOND TOE (TRAFFIC SIDE) OF ANCHORED BARRIER.
3. PORTABLE BARRIER INCLUDED WITH ROADWAY QUANTITIES. SEE SHEET 4 FOR ADDITIONAL NOTES INCLUDING ANCHORAGE REQUIREMENTS.
4. PHASE CONSTRUCTION JOINTS ARE PARALLEL TO THE CENTERLINE CONSTRUCTION I-71. MAINTAIN TRAFFIC PER THE MAINTENANCE OF TRAFFIC PLANS. THE CONTRACTOR SHALL VERIFY THE DIMENSIONS OF THE EXISTING STRUCTURE AND MAY ADJUST EDGE DISTANCES PROVIDED TO NON-TRAFFIC SIDE OF PORTABLE BARRIER AS APPROVED BY THE ENGINEER TO MEET THE VERIFIED CONDITIONS.
5. CROSSFRAMES NOT SHOWN FOR CLARITY. DO NOT PERMANENTLY ATTACH INTERMEDIATE CROSSFRAMES IN THE CLOSURE POUR LOCATION UNTIL THE CONCRETE POURS ON BOTH SIDES OF THE CLOSURE POUR LOCATION HAVE BEEN COMPLETED.
6. FOR SEQUENCE OF CONSTRUCTION, SEE SHEET 5.

# STAGED CONSTRUCTION DETAILS (2 OF 2)
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 8 |
| TOTAL | 64 |
| SHEET | P. 493 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet 2 PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:23:15 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SC001a.dgn




***REAR ABUTMENT REMOVAL PLAN***




***REAR ABUTMENT REMOVAL ELEVATION***




***A SECTION***
***-***

***LEGEND:***

- *PHASE 3A REMOVAL*
- *PHASE 3B REMOVAL*
- *PHASE 2A REMOVAL*
- *PHASE 2B REMOVAL*

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *ALL REMOVAL SHALL BE PAID UNDER ITEM 202, STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN. SEE SHEET 4 FOR ADDITIONAL NOTES.*
3. *EXISTING REINFORCING NOT SHOWN FOR CLARITY, REFER TO RECORD PLANS FOR REINFORCING.*

# EXISTING REAR ABUTMENT REMOVAL DETAILS
## BRIDGE NO. FRA-00071-26.460 L/R
## I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 9 |
| TOTAL | 64 |
| SHEET | P. 494 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:23:28 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SV001.dgn




***FORWARD ABUTMENT REMOVAL PLAN***




***FORWARD ABUTMENT REMOVAL ELEVATION***




A
-
***SECTION***

***LEGEND:***

- *PHASE 3A REMOVAL*
- *PHASE 3B REMOVAL*
- *PHASE 4A REMOVAL*
- *PHASE 4B REMOVAL*

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *ALL REMOVAL SHALL BE PAID FOR UNDER ITEM 202, STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN. SEE SHEET 4 FOR ADDITIONAL NOTES.*
4. *EXISTING REINFORCING NOT SHOWN FOR CLARITY, REFER TO RECORD PLANS FOR REINFORCING.*

# EXISTING FORWARD ABUTMENT REMOVAL DETAILS
## BRIDGE NO. FRA-00071-26.460 L/R
## I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 10 |
| TOTAL | 64 |
| SHEET | P. 495 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:23:41 PM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SV002.dgn




***EXISTING PIER REMOVAL PLAN***




***EXISTING PIER REMOVAL ELEVATION***
*(EXISTING CONCRETE BARRIER NOT SHOWN FOR CLARITY)*




A - **SECTION**

| EXISTING PIER ELEVATIONS | | |
|---|---|---|
| LOCATION | A | B |
| PIER #1 | 927.38± | 911.44± |
| PIER #2 | 927.44± | 911.44± |
| PIER #3 | 927.45± | 911.44± |

***LEGEND:***

- PHASE 3A REMOVAL
- PHASE 3B REMOVAL
- PHASE 4A REMOVAL
- PHASE 4B REMOVAL

***NOTES:***

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. ALL REMOVAL SHALL BE PAID UNDER ITEM 202, STRUCTURE REMOVED OVER 20 FOOT SPAN, AS PER PLAN. SEE SHEET 4 FOR ADDITIONAL NOTES.
3. EXISTING REINFORCING NOT SHOWN FOR CLARITY, REFER TO RECORD PLANS FOR REINFORCING.
4. ALL EXCAVATION REQUIRED TO REMOVE PORTIONS OF THE EXISTING PIERS SHALL BE INCLUDED FORPAYMENT UNDER ITEM 503 - UNCLASSIFIED EXCAVATION. REFER TO ROADWAY TYPICAL SECTIONS FOR PROPOSED PAVEMENT REPAIRS FOR SR-161.

# EXISTING PIER REMOVAL DETAILS
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | FM |

REVIEWER MJR 03/13/26

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 11 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 496 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:23:54 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SV003.dgn

**ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN**

1.0 DESIGN SPECIFICATIONS:

THIS STRUCTURE CONFORMS TO THE 9th EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020, THE 2nd EDITION OF THE "AASHTO GUIDE DESIGN SPECIFICATIONS FOR BRIDGE TEMPORARY WORKS", 2017 AND THE ODOT BRIDGE DESIGN MANUAL, 2020, DATED JULY 2025.

2.0 OPERATIONAL IMPORTANCE:

A LOAD MODIFIER OF 1.0 HAS BEEN ASSUMED FOR THE DESIGN OF TEMPORARY WORKS.

3.0 DESIGN DATA:

CONCRETE CLASS QC1 - COMPRESSIVE STRENGTH 4.0 KSI (DRILLED SHAFT)

STEEL SOLDIER PILES - ASTM A572 GRADE 50 - YIELD STRENGTH 50 KSI

STEEL SHEET PILING - ASTM A572 GRADE 50 - YIELD STRENGTH 50 KSI

4.0 UNCLASSIFIED EXCAVATION:

THIS WORK CONSISTS OF ALL EXCAVATION NECESSARY TO PERFORM THE WORK DESCRIBED IN THE TEMPORARY SHORING WALL PLANS.

THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING THE EXCAVATION LIMITS NECESSARY FOR INSTALLATION OF THE WORK. THE CONTRACTOR MAY NOT EXCAVATE OR WORK OUTSIDE OF THE RIGHT OF WAY UNLESS OTHERWISE SHOWN IN THESE PLANS.

5.0 STEEL SOLDIER PILES

THE FOLLOWING STEEL PILE SECTIONS ARE INCLUDED IN THE DESIGN OF TEMPORARY SOLDIER PILE AND LAGGING WALLS:

STEEL PILES, MISC.: SOLDIER PILES HP14x73
STEEL PILES, MISC.: SOLDIER PILES W14x193

THIS WORK CONSISTS OF FURNISHING AND PLACING STEEL SOLDIER PILES INTO DRILLED HOLES. FURNISH SOLDIER PILES CONSISTING OF STRUCTURAL STEEL MEMBERS THAT MEET THE PLAN REQUIREMENTS AND CONFORM TO ASTM A572, GRADE 50 IN ACCORDANCE WITH C&MS 711.01. DO NOT FIELD WELD OR SPLICE STEEL SOLDIER PILES.

6.0 DRILLED SHAFTS

THE FOLLOWING DRILLED SHAFT SIZES ARE INCLUDED IN THE DESIGN OF TEMPORARY SOLDIER PILE AND LAGGING WALLS:

DRILLED SHAFTS, 30" DIAMETER, ABOVE BEDROCK

THIS WORK CONSISTS OF FURNISHING AND INSTALLING DRILLED SHAFTS FOR TEMPORARY SOLDIER PILE AND LAGGING WALLS. THE DRILLED SHAFTS ARE REINFORCED WITH SOLDIER PILES INSTEAD OF REINFORCING STEEL CAGES. THE SOLDIER PILES EXTEND ABOVE THE TOP OF THE DRILLED SHAFT. FURNISH AND INSTALL THE DRILLED SHAFTS IN ACCORDANCE WITH C&MS 524 EXCEPT AS MODIFIED AND SUPPLEMENTED BELOW.

THE BOTTOM OF THE DRILLED SHAFT EXCAVATION SHALL BE AS CLEAN AS PRACTICAL PRIOR TO CONCRETE PLACEMENT. THE DRILLED SHAFT EXCAVATION SHALL BE INSPECTED BY THE ENGINEER IMMEDIATELY BEFORE THE CONCRETE IS PLACED. NO CONCRETE SHALL BE PLACED DURING INCLEMENT WEATHER CONDITIONS WHICH PROHIBIT A THOROUGH INSPECTION.

EXCAVATE THE HOLE FOR THE DRILLED SHAFT WITHIN 3 INCHES OF THE PLAN LOCATION. PLACE THE SOLDIER PILE WITHIN THE HOLE SO IT IS VERTICAL AND NOT INCLINED MORE THAN 1 INCH BETWEEN TOP TO BOTTOM. PLACE THE SOLDIER PILES SO THAT THE FLANGES ARE PARALLEL TO THE CENTERLINE OF THE ROW OF DRILLED SHAFTS. DO NOT ALLOW THE ORIENTATION OF THE FLANGES TO VARY BY MORE THAN 10 DEGREES. SUPPORT THE SOLDIER PILE SO THAT IT DOES NOT MOVE DURING CONCRETE PLACEMENT.

USE CLASS QC1 CONCRETE ACCORDING TO C&MS 511. PLACE CONCRETE TO THE ELEVATION FOR THE TOP OF THE DRILLED SHAFT. THE CONTRACTOR MAY PLACE CONCRETE USING THE FREE FALL METHOD PROVIDED THE DEPTH OF WATER IS LESS THAN 6 INCHES AND THE CONCRETE FALLS WITHOUT STRIKING THE SIDES OF THE HOLE. POURING CONCRETE ALONG THE WEB OF THE SOLIDER PILE IS ACCEPTABLE.

6.0 DRILLED SHAFTS CONTINUED...

CHECK THE POSITION, THE VERTICAL ALIGNMENT AND ORIENTATION OF THE SOLDIER PILE IMMEDIATELY CONCRETE PLACEMENT. MAKE CORRECTIONS AS NECESSARY TO MEET THE ABOVE TOLERANCES. FILL THE HOLE ABOVE THE BOTTOM OF THE DRILLED SHAFT TO THE EXISTING GROUND SURFACE WITH ITEM C&MS 613 LOW STRENGTH MORTAR (LSM) BACKFILL.

REMOVE CONCRETE AND LSM AS NECESSARY FROM AROUND THE SOLDIER PILE IN ORDER TO PLACE THE LAGGING. PLACE LAGGING SO THAT THE SOLDIER PILE FLANGE OVERLAPS THE ENDS OF THE LAGGING BY AT LEAST 3 INCHES AT BOTH ENDS OF THE LAGGING. WAIT AT LEAST 12 HOURS AFTER PLACING CONCRETE IN THE DRILLED SHAFTS BEFORE PLACING LAGGING.

SEQUENCE OF INSTALLATION: INSTALL THE DRILLED SHAFTS IN SEQUENCE SUCH THAT NO DRILLED SHAFT IS INSTALLED ADJACENT TO EITHER AN OPEN DRILLED SHAFT EXCAVATION OR A DRILLED SHAFT IN WHICH THE CONCRETE HAS LESS THAN A 48-HOUR CURE. INSTALLING THE SHAFTS IN AN ALTERNATING SEQUENCE OR ANY OTHER SEQUENCE THAT MEETS THESE CRITERIA IS PERMISSIBLE.

PROTECTION OF UNATTENDED OPEN SHAFTS: COVER UNATTENDED OPEN SHAFTS. USE TEMPORARY COVERS OF ADEQUATE STRENGTH TO PREVENT A PERSON OR ANIMAL FROM FALLING IN. LEAVE NO DRILLED SHAFT EXCAVATION UN-POURED OVERNIGHT.

THE CONTRACTOR IS RESPONSIBLE FOR THE MEANS AND METHODS USED TO CONSTRUCT THE DRILLED SHAFTS AND PLACE LAGGING. ANY TEMPORARY GRADING, EXCAVATION, EMBANKMENT, AGGREGATE, DRAINAGE, SHEETING, ETC. NEEDED TO COMPLETE THIS WORK SHALL BE INCLUDED IN THE CONTRACT LUMP SUM PRICE FOR ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN. NO SEPARATE PAYMENT WILL BE MADE.

7.0 RETAINING WALL, TIMBER LAGGING:

THIS WORK CONSISTS OF FURNISHING AND PLACING TIMBER LAGGING BETWEEN THE SOLDIER PILES AS TEMPORARY SUPPORT FOR THE RETAINED SOIL. FURNISH TIMBER LAGGING CONSISTING OF CONSTRUCTION GRADE, UNTREATED HARDWOOD WITH A MINIMUM THICKNESS OF 3 INCHES UNLESS OTHERWISE SHOWN IN THE PLANS. TO PERMIT DRAINAGE, PROVIDE ¼ TO ½-INCH SPACES BETWEEN THE LAGGING BOARDS USING ⅜-INCH THICK SPACER BLOCKS OR OTHER MEANS ACCEPTABLE TO THE ENGINEER. PLACE THE LAGGING BOARDS BETWEEN THE FLANGES OF THE SOLDIER PILES AND BEARING AGAINST THE FLANGES ON THE EXPOSED SIDE OF THE WALL SO THAT THE SOLIDER PILE FLANGE OVERLAPS THE END OF THE LAGGING BY AT LEAST 3 INCHES AT BOTH ENDS OF THE LAGGING BOARDS. PERFORM EXCAVATION FOR PLACEMENT OF THE LAGGING IN SUCH A MANNER THAT THE LAGGING IS TIGHT AGAINST THE EXCAVATION CUT FACE. BACKFILL ANY VOIDS BEHIND THE LAGGING WITH A SUITABLE COMPACTED GRANULAR MATERIAL CONFORMING TO C&MS 703.16.C ACCEPTABLE TO THE ENGINEER. THE COST OF ANY SUCH BACKFILLING REQUIRED, INCLUDING MATERIAL, PLACEMENT AND COMPACTION, IS INCIDENTAL TO THE CONTRACT LUMP SUM PRICE FOR ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN. NO SEPARATE PAYMENT WILL BE MADE.

THE SAME SPECIES SHALL BE USED FOR ALL THE TIMBER MEMBERS REQUIRED. THE TIMBER MEMBERS SHALL BE OF A GRADE AND TYPE WITH AN ALLOWABLE EXTREME FIBER STRESS IN BENDING OF A MINIMUM OF 1250 PSI AND ALLOWABLE STRESS IN SHEAR OF A MINIMUM OF 85 PSI. THE WOOD SHALL BE SEASONED, SOUND, AND FREE FROM DECAY AND INSECT ATTACK, WITHOUT LOOSE AND/OR CLUTTER KNOTS. THE TIMBER LAGGING USED SHALL CONFORM TO THE REQUIREMENTS SHOWN IN THE PLANS. IF THE LAGGING USED AT ANY LOCATION IS FOUND TO BE INADEQUATE, THE CONTRACTOR IS RESPONSIBLE FOR ALL CORRECTIVE MEASURES. LAGGING MAY BE FIELD CUT.

8.0 ENGINEER DESIGNED TEMPORARY SHEETING:

FOR LOCATIONS OF TEMPORARY SHEET PILING REFER TO SHEETS XX THRU XX. STEEL SHEET PILING SHALL CONFORM TO ASTM A572 GRADE 50 WITH A MINIMUM YIELD STRENGTH OF 50 KSI, A MINIMUM SECTION MODULUS OF 48.5 IN3/FT, AND MINIMUM MOMENT OF INERTIA OF 361.22 IN4/FT. REFER TO THE TABLE BELOW FOR DESIGN REQUIREMENTS.

DESIGN CRITERIA:
MAXIMUM RETAINED HEIGHT, H: 20'-0"
EARTH PRESSURE: ACTIVE (Ka)
LIVE LOAD SURCHARGE: 250 PSF (UNFACTORED)
EXISTING ABUTMENT SOIL PRESSURE: 3000 PSF (UNFACTORED)
MAXIMUM PERMITTED DEFLECTION: 1%H

9.0 ENGINEER DESIGNED TEMPORARY SHEETING:

IN ADDITION TO THE LOCATIONS DEPICTED IN THE PLANS, TEMPORARY SHEETING MAY BE REQUIRED AT VARIOUS LOCATIONS/STAGES TO CONSTRUCT THE PROPOSED BRIDGE WORK. THE CONTRACTOR IS PERMITTED TO USE THE DESIGN SHOWN IN SECTION 8.0 PROVIDED THE THE USE DOES NOT EXCEED THE DESIGN CRITERIA SHOWN IN SECTION 8.0. ELSE THE CONTRACTOR SHALL DESIGN, PREPARE AND PROVIDE PLANS IN ACCORDANCE WITH C&MS 501.05 FOR TEMPORARY SUPPORT OF EXCAVATION.

10.0 REMOVAL OF TEMPORARY SHORING

REMOVE TEMPORARY SHORING WHEN NO LONGER REQUIRED TO SUPPORT THE EXCAVATION. THE CONTRACTOR IS RESPONSIBLE FOR THE MEANS AND METHODS TO REMOVE AND/OR DECONSTRUCT TEMPORARY SHORING. THE CONTRACTOR IS RESPONSIBLE FOR PROTECTING THE EXISTING AND PROPOSED STRUCTURE(S). THE CONTRACTOR SHALL PERFORM DEMOLITION OPERATIONS SUCH THAT THERE IS NOT ANY DAMAGE TO THE NEW STRUCTURE OR TO PORTIONS OF THE EXISTING STRUCTURE BEING TEMPORARILY MAINTAINED. THE USE OF EXPLOSIVES AND HEADACHE BALLS WILL NOT BE PERMITTED FOR ANY DEMOLITION OF TEMPORARY SHORING. UNLESS OTHERWISE NOTED, TEMPORARY SHORING SHALL BE REMOVED TO A MINIMUM OF 1 FOOT BELOW THE PROPOSED GROUND SURFACE AND/OR NEAREST PROPOSED BRIDGE ELEMENT (I.E. MSE LEVELING PAD, ABUTMENT FOOTING, ETC.).

STEEL SHEET PILING - LEFT IN PLACE

EXTRACTION OF SHEET PILING NEAR TEMPORARY WIRE FACED MSE WALL MAY UNACCEPTABLY DEFORM THE NEARBY TEMPORARY WIRE FACED MSE WALL(S). THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND TEMPORARY WIRE FACED MSE WALL SUPPLIER ON THE SAFE EXTRACTION OF SHEET PILING NEAR SUCH WALLS. THE CONTRACTOR IS PERMITTED TO LEAVE SHEET PILING IN PLACE AS APPROVED BY THE ENGINEER.

ALL LABOR, MATERIALS, TOOLS, EQUIPMENT AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK SHALL BE INCLUDED WITH THE CONTRACT THE CONTRACT LUMP SUM PRICE BID FOR ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN.

11.0 METHOD OF MEASUREMENT AND PAYMENT:

THIS WORK INCLUDES ALL MATERIALS, LABOR, TOOLS, EQUIPMENT AND INCIDENTALS NECESSARY TO FURNISH AND INSTALL TEMPORARY SHORING AS DESCRIBED HEREIN. THE DEPARTMENT WILL PAY FOR THE TEMPORARY SHORING (E.G. SOLDIER PILE AND LAGGING WALLS, SHEET PILE WALLS) AT THE CONTRACT LUMP SUM PRICE BID FOR ITEM 503 - COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN.

TEMPORARY SHORING NOTES
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN
TBD

DESIGN AGENCY
Jacobs

| DESIGNER | CHECKER |
|---|---|
| DBL | MAN |

REVIEWER
MJR 03/13/26


PROJECT ID
109164

| SUBSET | TOTAL |
|---|---|
| 12 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 497 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:24:07 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SH002.dgn




**NOTES:**

1. FOR ABBREVIATION LEGEND, SEE SHEET 5/63.
2. STATIONS AND OFFSETS ARE SHOWN AT ℄ SOLDIER PILE WALLS AND AT THE EXPOSED FACE OF THE SHEET PILE WALLS

**TEMPORARY SHORING - PLAN**

## TEMPORARY SHORING - CONSTRUCTION SEQUENCE

### PHASE 3A REMOVAL & CONSTRUCTION

1. REMOVE PORTIONS OF EXISTING FRA-71-26.46 L (SOUTHBOUND) BRIDGE, APPROACH SLABS, ABUTMENTS, PIERS, PAVEMENT, MEDIAN BARRIER AND CAPPED MEDIAN CONCRETE SLOPE PROTECTION TO ALLOW FOR INSTALLATION OF TEMPORARY SHORING SYSTEMS.
2. INSTALL SHEET PILING WALLS #2, #3, #5 & #6, AS SHOWN IN THE PLANS.
3. EXCAVATE TO THE DEPTH OF THE TOPMOST WALER FOR THE UPPER TIEBACKS. REMOVE TEMPORARY SHORING SYSTEMS FROM PHASE 2A ENCOUNTERED DURING EXCAVATION. CUT TIEBACKS WHERE ENCOUNTERED.
4. INSTALL WALER AND UPPER TIEBACKS.
5. REPEAT STEPS 3 AND 4 TO THE DEPTH OF WALER FOR THE NEXT LEVEL OF TIEBACKS. EXCAVATE AND INSTALL LAGGING IN TOP-DOWN MANNER TO BOTTOM OF EXCAVATION.
6. REMOVE SHEET PILING OR CUT AT MINIMUM ELEVATION OF 1 FOOT BELOW THE FINISHED GROUND LINE.
7. INSTALL THE TEMPORARY WIRE FACED MSE WALL AND EMBANKMENT TO SUPPORT THE PROPOSED ROADWAY APPROACH EMBANKMENT IN PHASE 3A.
8. COMPLETE PHASE 3A SUPERSTRUCTURE CONSTRUCTION OF BRIDGE AND APPROACH.

### PHASE 3B REMOVAL & CONSTRUCTION

1. REMOVE REMAINING PORTIONS OF EXISTING FRA-71-26.46 L (SOUTHBOUND) BRIDGE, APPROACH SLABS, ABUTMENT, PIERS, AND PAVEMENT TO ALLOW FOR PROPOSED WORK.
2. EXCAVATE. REMOVE TEMPORARY SHORING SYSTEMS FROM PHASE 3A ENCOUNTERED DURING EXCAVATION. CUT SOLDIER PILES A MAXIMUM OF 1 FOOT ABOVE THE BOTTOM OF EXCAVATION. CUT TIEBACKS WHERE ENCOUNTERED.
3. COMPLETE PHASE 3B ABUTMENT AND MSE WALL CONSTRUCTION.
4. CONSTRUCT THE EMBANKMENT TO SUPPORT THE PROPOSED ROADWAY APPROACH EMBANKMENT IN PHASE 3B.
5. REMOVE SHEET PILING OR CUT AT MINIMUM ELEVATION OF 1 FOOT BELOW THE FINISHED GROUND LINE.
6. COMPLETE PHASE 3B SUPERSTRUCTURE CONSTRUCTION OF BRIDGE AND APPROACH.

### PHASE 4A REMOVAL & CONSTRUCTION

1. REMOVE PORTIONS OF EXISTING FRA-71-26.46 R (NORTHBOUND) BRIDGE, APPROACH SLABS, ABUTMENTS, PIERS AND PAVEMENT TO ALLOW FOR INSTALLATION OF TEMPORARY SHORING SYSTEMS AND PROPOSED WORK.
2. DRILL SHAFTS AND INSTALL SOLDIER PILES (WALL #1 AND #4).
3. EXCAVATE TO THE DEPTH OF THE TOPMOST WALER FOR THE UPPER TIEBACKS. REMOVE TEMPORARY SHORING SYSTEMS FROM PHASE 3A ENCOUNTERED DURING EXCAVATION. CUT TIEBACKS WHERE ENCOUNTERED.
4. INSTALL WALER AND UPPER TIEBACKS.
5. REPEAT STEPS 3 AND 4 TO THE DEPTH OF WALER FOR THE NEXT LEVEL OF TIEBACKS.
6. COMPLETE PHASE 4A ABUTMENT AND MSE WALL CONSTRUCTION.
7. INSTALL THE TEMPORARY WIRE FACED MSE WALL AND EMBANKMENT TO SUPPORT THE PROPOSED ROADWAY APPROACH EMBANKMENT IN PHASE 4A.
8. REMOVE SHEET PILING OR CUT AT MINIMUM ELEVATION OF 1 FOOT BELOW THE FINISHED GROUND LINE.
9. COMPLETE PHASE 4A SUPERSTRUCTURE CONSTRUCTION OF BRIDGE AND APPROACH.

### PHASE 4B REMOVAL & CONSTRUCTION


1. REMOVE REMAINING PORTIONS OF EXISTING FRA-71-26.46 R (NORTHBOUND) BRIDGE, APPROACH SLABS, ABUTMENT, PIERS, AND PAVEMENT TO ALLOW FOR PROPOSED WORK.
2. EXCAVATE. REMOVE TEMPORARY SHORING SYSTEMS FROM PHASE 3A OR 4A ENCOUNTERED DURING EXCAVATION. CUT TIEBACKS WHERE ENCOUNTERED.
3. COMPLETE PHASE 4B ABUTMENT AND MSE WALL CONSTRUCTION.
4. CONSTRUCT THE EMBANKMENT TO SUPPORT THE PROPOSED ROADWAY APPROACH EMBANKMENT IN PHASE 4B.
5. CUT SOLDIER PILES A MAXIMUM OF 1 FOOT ABOVE THE BOTTOM OF EXCAVATION.
6. COMPLETE PHASE 4B SUPERSTRUCTURE CONSTRUCTION OF BRIDGE AND APPROACH.

# TEMPORARY SHORING PLAN
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 13 |
| TOTAL | 64 |
| SHEET | P. 498 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:24:21 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SH001.dgn




***TEMPORARY SHORING WALL #2 ELEVATION***
*(LOOKING EAST)*





***TEMPORARY WIRE FACED MSE WALL #2 ELEVATION***
*(LOOKING WEST)*


***LEGEND:***

TEMPORARY WIRE FACED MSE WALL

| WALL #2 AND #3 WALER AND TIE-BACK ANCHOR INFORMATION | | | | | | |
|---|---|---|---|---|---|---|
| WALER NO. | CL WALER EL. | WALER LENGTH | NUMBER OF ANCHORS | ANCHOR INCLINATION | LOCK-OFF LOAD (K/FT) | FACTORED DESIGN LOAD (K/FT) |
| W1 | 928.50 | 13'-0" | 3 | 15° | 7 | 9 |
| W2 | 923.00 | 17'-0" | 3 | 15° | 10 | 13 |
| W3 | 918.00 | 16'-0" | 3 | 15° | 10 | 13 |
| W4 | 913.00 | 9'-0" | 2 | 15° | 10 | 13 |
| W5 | 928.50 | 13'-0" | 3 | 15° | 7 | 9 |
| W6 | 923.00 | 17'-0" | 3 | 15° | 10 | 13 |
| W7 | 918.00 | 16'-0" | 3 | 15° | 10 | 13 |
| W8 | 913.00 | 9'-0" | 2 | 15° | 10 | 13 |




***TEMPORARY SHORING WALL #3 ELEVATION***
*(LOOKING WEST)*




***TEMPORARY WIRE FACED MSE WALL #3 ELEVATION***
*(LOOKING EAST)*

# TEMPORARY SHORING ELEVATIONS (1 OF 3)
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| DBL | MAN |

REVIEWER MJR 03/05/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 14 | 64 |


| SHEET | TOTAL |
|---|---|
| P. 499 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/6/2026 TIME: 3:22:46 PM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SC010.dgn




## TEMPORARY SHORING WALL #5 ELEVATION
(LOOKING WEST)





## TEMPORARY WIRE FACED MSE WALL #5 ELEVATION
(LOOKING EAST)


**LEGEND:**

TEMPORARY WIRE FACED MSE WALL

| WALL #5 AND #6 WALER AND TIE-BACK ANCHOR INFORMATION | | | | | | |
|---|---|---|---|---|---|---|
| WALER NO. | CL WALER EL. | WALER LENGTH | NUMBER OF ANCHORS | ANCHOR INCLINATION | LOCK-OFF LOAD (K/FT) | FACTORED DESIGN LOAD (K/FT) |
| W1 | 928.25 | 14'-0" | 3 | 15° | 10 | 19 |
| W2 | 923.25 | 18'-0" | 4 | 15° | 10 | 19 |
| W3 | 918.25 | 19'-0" | 4 | 15° | 10 | 19 |
| W4 | 913.25 | 14'-0" | 3 | 15° | 10 | 19 |
| W5 | 928.25 | 14'-0" | 3 | 15° | 10 | 19 |
| W6 | 923.25 | 18'-0" | 4 | 15° | 10 | 19 |
| W7 | 918.25 | 19'-0" | 4 | 15° | 10 | 19 |
| W8 | 913.25 | 14'-0" | 3 | 15° | 10 | 19 |




## TEMPORARY SHORING WALL #6 ELEVATION
(LOOKING WEST)





## TEMPORARY WIRE FACED MSE WALL #6 ELEVATION
(LOOKING EAST)

TEMPORARY SHORING ELEVATIONS (2 OF 3)
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161


SFN TBD
DESIGN AGENCY Jacobs
DESIGNER DBL | CHECKER MAN
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 15 | TOTAL 64
SHEET P. 500 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/6/2026 TIME: 2:29:05 PM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SC012.dgn




***TEMPORARY SHORING WALL #1 ELEVATION***
*(LOOKING EAST)*





***TEMPORARY WIRE FACED MSE WALL #1 ELEVATION***
*(LOOKING WEST)*


| WALL #1 AND #4 WALER AND TIE-BACK ANCHOR INFORMATION | | | | | | |
|---|---|---|---|---|---|---|
| WALER NO. | CL WALER EL. | WALER LENGTH | NUMBER OF ANCHORS | ANCHOR INCLINATION | LOCK-OFF LOAD (K/FT) | FACTORED DESIGN LOAD (K/FT) |
| W1 | 929.00 | 15'-0" | 3 | 15° | 7 | 9 |
| W2 | 924.00 | 16'-3" | 3 | 15° | 10 | 14 |
| W3 | 919.00 | 22'-3" | 4 | 15° | 10 | 14 |
| W4 | 914.00 | 15'-0" | 3 | 15° | 10 | 14 |
| W5 | 928.25 | 15'-0" | 3 | 15° | 7 | 10 |
| W6 | 923.25 | 24'-0" | 4 | 15° | 10 | 16 |
| W7 | 918.25 | 24'-0" | 4 | 15° | 10 | 16 |
| W8 | 913.25 | 15'-0" | 3 | 15° | 10 | 16 |

***LEGEND:***

TEMPORARY WIRE FACED MSE WALL




***TEMPORARY SHORING WALL #4 ELEVATION***
*(LOOKING EAST)*




***TEMPORARY WIRE FACED MSE WALL #4 ELEVATION***
*(LOOKING WEST)*

TEMPORARY SHORING ELEVATIONS (3 OF 3)
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

CTY-RTE-SECTION

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| DBL | MAN |

REVIEWER MJR 03/05/26

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 16 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 501 | 618 |

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/6/2026 TIME: 2:59:33 PM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257_SC011.dgn


| TEMPORARY SHORING WALL #1 | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| SOLDIER PILE NO. | SOLDIER PILE STATION ALONG ℄ CONST. I-71 | SOLDIER PILE OFFSET (FROM ℄ CONST. I-71) | TOP OF SOLDIER PILE ELEVATION "A" | TOP OF DRILLED SHAFT ELEVATION "B" | BOT. OF DRILLED SHAFT OR PILE TIP ELEVATION "C" | LENGTH OF DRILLED SHAFT "D" | SOLDIER PILE SIZE | DRILLED SHAFT DIAMETER |
| P1 | 1414+95.40 | 34.00' RT. | 924.00 | 912.00 | 887.00 | 25'-0" | W14x193 | 2'-6" |
| P2 | 1415+03.40 | 34.00' RT. | 926.00 | 912.00 | 897.00 | 15'-0" | HP14x73 | 2'-6" |
| P3 | 1415+09.40 | 34.00' RT. | 928.00 | 912.00 | 897.00 | 15'-0" | HP14x73 | 2'-6" |
| P4 | 1415+15.40 | 34.00' RT. | 939.42 | 912.42 | 897.42 | 15'-0" | HP14x73 | 2'-6" |
| P5 | 1415+22.65 | 34.00' RT. | 938.25 | 917.25 | 902.25 | 15'-0" | HP14x73 | 2'-6" |
| P6 | 1415+28.65 | 34.00' RT. | 938.25 | 921.25 | 906.25 | 15'-0" | HP14x73 | 2'-6" |
| P7 | 1415+34.65 | 34.00' RT. | 938.25 | 925.25 | 910.25 | 15'-0" | HP14x73 | 2'-6" |
| P8 | 1415+43.65 | 34.00' RT. | 933.59 | 930.59 | 915.59 | 15'-0" | HP14x73 | 2'-6" |


| TEMPORARY SHORING WALL #4 | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| SOLDIER PILE NO. | SOLDIER PILE STATION ALONG ℄ CONST. I-71 | SOLDIER PILE OFFSET (FROM ℄ CONST. I-71) | TOP OF SOLDIER PILE ELEVATION "A" | TOP OF DRILLED SHAFT ELEVATION "B" | BOT. OF DRILLED SHAFT OR PILE TIP ELEVATION "C" | LENGTH OF DRILLED SHAFT "D" | SOLDIER PILE SIZE | DRILLED SHAFT DIAMETER |
| P1 | 1416+66.44 | 34.00' RT. | 924.00 | 931.53 | 916.53 | 15'-0" | W14x193 | 2'-6" |
| P2 | 1416+75.44 | 34.00' RT. | 926.00 | 927.53 | 897.53 | 30'-0" | W14x193 | 2'-6" |
| P3 | 1416+81.44 | 34.00' RT. | 928.00 | 923.53 | 908.53 | 15'-0" | HP14x73 | 2'-6" |
| P4 | 1416+87.44 | 34.00' RT. | 939.42 | 919.53 | 904.53 | 15'-0" | HP14x73 | 2'-6" |
| P5 | 1416+96.44 | 34.00' RT. | 938.25 | 915.53 | 900.53 | 15'-0" | HP14x73 | 2'-6" |
| P6 | 1417+02.44 | 34.00' RT. | 938.25 | 911.50 | 896.50 | 15'-0" | HP14x73 | 2'-6" |
| P7 | 1417+08.44 | 34.00' RT. | 938.25 | 911.50 | 896.50 | 15'-0" | HP14x73 | 2'-6" |
| P8 | 1417+14.44 | 34.00' RT. | 933.59 | 911.50 | 896.50 | 15'-0" | HP14x73 | 2'-6" |
| P9 | 1417+20.44 | 34.00' RT. | 933.59 | 911.50 | 881.50 | 30'-0" | W14x193 | 2'-6" |

## SOLDIER PILE & LAGGING WALL SCHEDULE




## SECTION A-A




## SOLDIER PILE & LAGGING WALL TYPICAL SECTION

**NOTES:**

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. STATIONS AND OFFSETS ARE SHOWN AT THE CENTERLINE OF THE SOLDIER PILE WALLS AND AT THE EXPOSED FACE OF THE SHEET PILE WALLS. THE STATIONS AND OFFSETS ARE BARSED ON THE ℄ CONSTRUCTION I-71.
3. SOLDIER PILES SHALL BE GRADE 50 (50 KSI) STEEL.

# SOLDIER PILE SCHEDULE
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| DBL | MAN |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 17 | 64 |


| SHEET | TOTAL |
|---|---|
| P. 502 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:25:16 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SC013.dgn




T 17 **PLAN VIEW**





***TYP. STEEL WEDGE PLATE***


***DETAIL B***

***NOTES:***

1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *DESIGN, CONSTRUCT, AND TEST TIE BACKS IN ACCORDANCE WITH ODOT SUPPLEMENTAL SPECIFICATION 866 FOR ADDITIONAL INFORMATION.*
3. *ALL STEEL SHALL BE GRADE 50 (ASTM A572).*
4. *WELD MATERIAL SHALL BE Fexx = 70 KSI.*
5. *FOR SHEET PILE WALL TIEBACK SCHEDULES, SEE SHEETS 13 AND 14.*




S 17 ***SIDE VIEW***





A 17 ***TYPICAL SECTION***

TEMPORARY SHORING DETAILS (1 OF 2)
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | DBL |
| CHECKER | MAN |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 18 |
| TOTAL | 64 |
| SHEET | P. 503 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:25:29 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\SFN_2508257_SC014.dgn




**T 18 PLAN VIEW**





**A 18 TYPICAL SECTION**





**TYP. STEEL WEDGE PLATE**


**DETAIL B**




**S 18 SIDE VIEW**




**TYPICAL SECTION**
*(TIMBER LAGGING)*




**E 18 SECTION**

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. DESIGN, CONSTRUCT AND TEST TIE BACKS IN ACCORDANCE WITH ODOT SUPPLEMENTAL SPECIFICATION 866 FOR ADDTIONAL INFORMATION.
3. ALL STEEL SHALL BE GRADE 50 (ASTM A572).
4. TIMBER LAGGING SHALL BE ROUGH SAWN OAK HARDWOOD STRUCTURAL GRADE #2 OR BETTER.
5. WELD MATERIAL SHALL BE Fexx = 70 KSI.
6. FOR SOLIDER PILE SCHEDULES AND TIEBACK INFORMATION, SEE SHEET 16.

TEMPORARY SHORING DETAILS (2 OF 2)
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN TBD
DESIGN AGENCY Jacobs
DESIGNER DBL | CHECKER MAN
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 19 | TOTAL 64
SHEET P. 504 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:25:42 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SC015.dgn





**REAR ABUTMENT PLAN**

***LEGEND:***

- ◯ - 14" DIA. CAST-IN-PLACE REINFORCED CONCRETE PILE WITH PILE SLEEVE
- (XX) - PILE NUMBER

***NOTES:***

1. REAR ABUTMENT ESTIMATED PILE LENGTH = 75'-0".
2. FORWARD ABUTMENT ESTIMATED PILE LENGTH = 70'-0".
3. FOR PILE DRIVING CRITERIA AND UBV, SEE SHEET 4.
4. FOR ABBREVIATION LEGEND, SEE SHEET 5.




**FORWARD ABUTMENT PLAN**


***PILE LAYOUT - RIGHT BRIDGE***

PILE LAYOUT - RIGHT BRIDGE
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 20 |
| TOTAL | 64 |
| SHEET | P. 505 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:25:56 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SO002.dgn




**REAR ABUTMENT PLAN**


***LEGEND:***

- 14" DIA. CAST-IN-PLACE REINFORCED CONCRETE PILE WITH PILE SLEEVE

XX - PILE NUMBER

***NOTES:***

1. REAR ABUTMENT ESTIMATED PILE LENGTH = 75'-0".
2. FORWARD ABUTMENT ESTIMATED PILE LENGTH = 70'-0".
3. FOR PILE DRIVING CRITERIA AND UBV, SEE SHEET 4.
4. FOR ABBREVIATION LEGEND, SEE SHEET 5.




**FORWARD ABUTMENT PLAN**

**PILE LAYOUT - LEFT BRIDGE**

# PILE LAYOUT - LEFT BRIDGE
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | FM |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 21 | 64 |


| SHEET | TOTAL |
|---|---|
| P. 506 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:26:09 PM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SO001.dgn




## FOUNDATION PLAN - REAR ABUTMENT
(RIGHT BRIDGE)




## FOUNDATION PLAN - REAR ABUTMENT
(LEFT BRIDGE)

### REINFORCING LEGEND:

A: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)

B: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)


C: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)

D: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)

E: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)

F: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)

G: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)




A - SECTION REAR ABUT. FTG.

### MIN. LAP LENGTHS:

#5 BAR = 3'-1"
#8 BAR = 5'-4"

### NOTES:


1. FOR FOUNDATION PLAN/PILE LAYOUT, SEE SHEETS 20 THRU 21.

FOUNDATION PLAN - REAR ABUTMENT
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161


SFN TBD
DESIGN AGENCY Jacobs
DESIGNER MAN | CHECKER ZF
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 22 | TOTAL 64
SHEET P. 507 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:26:21 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_S0003.dgn




## FOUNDATION PLAN - FORWARD ABUTMENT
(LEFT BRIDGE)




## FOUNDATION PLAN - FORWARD ABUTMENT
(RIGHT BRIDGE)

### REINFORCING LEGEND:

A: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)

B: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)


C: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)

D: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)

E: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)

F: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)

G: 6-RA6XX @ EQ. SPA. = 6'-0" (TOP) & 4-RA8XX (BOT., SEE SECTION FOR SPA.)




B - SECTION FWD ABUT. FTG.

### MIN. LAP LENGTHS:

#5 BAR = 3'-1"
#8 BAR = 5'-4"

### NOTES:


1. FOR FOUNDATION PLAN/PILE LAYOUT, SEE SHEETS 20 THRU 21.

FOUNDATION PLAN - FORWARD ABUTMENT
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | ZF |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 23 |
| TOTAL | 64 |
| SHEET | P. 508 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:26:33 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_S0004.dgn





## REAR ABUTMENT PLAN - RIGHT BRIDGE

*(PILES AND TEMP. SHORING NOT SHOWN FOR CLARITY)*

**LEGEND:**

(GX) - GIRDER LINE DESIGNATION




## REAR ABUTMENT ELEVATION - RIGHT BRIDGE

**REINFORCING LEGEND:**

A: 3 SETS OF RA5XX (BOT.) & RA5XX (TOP) @ 1'-0" MAX. = 1'-6"

B: 2 SETS OF RA5XX (BOT.) & RA5XX (TOP) @ 1'-0" MAX.

C: 2-RA5XX (E.F.) @ 1'-0" MAX.

D: 2-RA5XX (E.F.) @ 1'-0" MAX.

E: 2-RA5XX (E.F.) @ 1'-0" MAX. LAP W/ RA5XX

F: 7-RA5XX (E.F., SER.) @ 1'-0" MAX. = 5'-6"

**NOTES:**


1. FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 20 THRU 23.
2. FOR PIPE OUTLET LOCATIONS, SEE SHEET 1. FOR OUTLET DETAILS SEE SHEET 26. MINIMUM SLOPE SHALL BE ⅛" PER FOOT. CAP AT HIGH POINT(S).
3. PLACE TYPE 2 WATERPROOFING CENTERED ON THE VERTICAL JOINT FROM THE BEAM SEAT TO THE BOTTOM OF FOOTING.

REAR ABUTMENT PLAN AND ELEVATION - RIGHT BRIDGE
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 24 |
| TOTAL | 64 |
| SHEET | P. 509 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:26:55 PM PLTDRV: OHDOT_PDF_Ex.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257_SFN_2508257_SR001.dgn




***REAR ABUTMENT PLAN - LEFT BRIDGE***
*(PILES AND TEMP. SHORING NOT SHOWN FOR CLARITY)*

***LEGEND:***

(GX) - GIRDER LINE DESIGNATION




***REAR ABUTMENT ELEVATION - LEFT BRIDGE***
*(FTG. REINFORCING & MSE WALL NOT SHOWN FOR CLARITY)*

***REINFORCING LEGEND:***

*A: 3 SETS OF RA5XX (BOT.) & RA5XX (TOP) @ 1'-0" MAX. = 1'-6"*

*B: 2-RA5XX (E.F.) @ 1'-0" MAX.*

*C: 2-RA5XX (E.F.) @ 1'-0" MAX. LAP W/ RA5XX*

*D: 2-RA5XX (E.F.) @ 1'-0" MAX.*

*E: 2-RA5XX (E.F.) @ 1'-0" MAX. LAP W/ RA5XX*

*F: 7-RA5XX (E.F., SER.) @ 1'-0" MAX. = 5'-6"*

***NOTES:***


1. *FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 20 THRU 23.*
2. *FOR PIPE OUTLET LOCATIONS, SEE SHEET 1. FOR OUTLET DETAILS SEE SHEET 26. MINIMUM SLOPE SHALL BE ⅛" PER FOOT. CAP AT HIGH POINT(S).*
3. *PLACE TYPE 2 WATERPROOFING CENTERED ON THE VERTICAL JOINT FROM THE BEAM SEAT TO THE BOTTOM OF FOOTING.*

# REAR ABUTMENT PLAN AND ELEVATION - LEFT BRIDGE
## BRIDGE NO. FRA-00071-26.460 L/R
## I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 25 |
| TOTAL | 64 |
| SHEET | P. 510 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:27:12 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\V00-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SR002.dgn





**A 24 A 25 SECTION**
REAR ABUTMENT




**B 24 B 25 SECTION**
REAR ABUTMENT
WINGWALL ON FTG.




**C 24 C 25 SECTION**
REAR ABUTMENT
WINGWALL W/O FTG.




***TYPICAL DRAIN PIPE OUTLET DETAIL***

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 20 THRU 23.*
3. *FOR MSE WALL DETAILS AND SEALING LIMITS, SEE SHEETS 57 THRU 60.*

# REAR ABUTMENT DETAILS
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | ZF |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 26 |
| TOTAL | 64 |
| SHEET | P. 511 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:27:26 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SR005.dgn




***FORWARD ABUTMENT PLAN - RIGHT BRIDGE***
*(PILES AND TEMP. SHORING NOT SHOWN FOR CLARITY)*

***LEGEND:***

(GX) - GIRDER LINE DESIGNATION




***FORWARD ABUTMENT ELEVATION - RIGHT BRIDGE***
*(FTG. REINFORCING & MSE WALL NOT SHOWN FOR CLARITY)*

***REINFORCING LEGEND:***

*A: 3 SETS OF FA5XX (BOT.) & FA5XX (TOP) @ 1'-0" MAX. = 1'-6"*

*B: 2 SETS OF FA5XX (BOT.) & FA5XX (TOP) @ 1'-0" MAX.*

*C: 2-FA5XX (E.F.) @ 1'-0" MAX.*

*D: 2-FA5XX (E.F.) @ 1'-0" MAX.*

*E: 2-FA5XX (E.F.) @ 1'-0" MAX. LAP W/ FA5XX*

*F: 7-FA5XX (E.F., SER.) @ 1'-0" MAX. = 5'-6"*

***NOTES:***


1. *FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 20 THRU 23.*
2. *FOR PIPE OUTLET LOCATIONS, SEE SHEET 1. FOR OUTLET DETAILS SEE SHEET 26. MINIMUM SLOPE SHALL BE ⅛" PER FOOT. CAP AT HIGH POINT(S).*
3. *PLACE TYPE 2 WATERPROOFING CENTERED ON THE VERTICAL JOINT FROM THE BEAM SEAT TO THE BOTTOM OF FOOTING.*

FORWARD ABUTMENT PLAN AND ELEVATION - RIGHT BRIDGE
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN TBD
DESIGN AGENCY Jacobs
DESIGNER MAN | CHECKER FM
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 27 | TOTAL 64
SHEET P. 512 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:27:40 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SF002.dgn





## FORWARD ABUTMENT PLAN - LEFT BRIDGE

*(PILES AND TEMP. SHORING NOT SHOWN FOR CLARITY)*

**LEGEND:**

(GX) - GIRDER LINE DESIGNATION




## FORWARD ABUTMENT ELEVATION - LEFT BRIDGE

*(FTG. REINFORCING & MSE WALL NOT SHOWN FOR CLARITY)*

**REINFORCING LEGEND:**

A: 3 SETS OF FA5XX (BOT.) & FA5XX (TOP) @ 1'-0" MAX. = 1'-6"

B: 2-FA5XX (E.F.) @ 1'-0" MAX.

C: 2-FA5XX (E.F.) @ 1'-0" MAX. LAP W/ FA5XX

D: 2-FA5XX (E.F.) @ 1'-0" MAX.

E: 2-FA5XX (E.F.) @ 1'-0" MAX. LAP W/ FA5XX

F: 7-FA5XX (E.F., SER.) @ 1'-0" MAX. = 5'-6"

**NOTES:**

1. FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 20 THRU 23.
2. FOR PIPE OUTLET LOCATIONS, SEE SHEET 1. FOR OUTLET DETAILS SEE SHEET 26. MINIMUM SLOPE SHALL BE ⅜" PER FOOT. CAP AT HIGH POINT(S).
3. PLACE TYPE 2 WATERPROOFING CENTERED ON THE VERTICAL JOINT FROM THE BEAM SEAT TO THE BOTTOM OF FOOTING.

# FORWARD ABUTMENT PLAN AND ELEVATION - LEFT BRIDGE


BRIDGE NO. FRA-00071-26.460 L/R

I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 28 |
| TOTAL | 64 |
| SHEET | P. 513 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:27:55 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19\10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SF001.dgn





A/27 A/28 **SECTION**
FWD. ABUTMENT




B/27 B/28 **SECTION**
FWD. ABUTMENT
WINGWALL ON FTG.




C/27 C/28 **SECTION**
FWD. ABUTMENT
WINGWALL W/O FTG.




***TYPICAL DRAIN PIPE OUTLET DETAIL***

***NOTES:***

1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *FOR FOUNDATION PLAN AND FOOTING REINFORCING, SEE SHEETS 20 THRU 23.*
3. *FOR MSE WALL DETAILS AND SEALING LIMITS, SEE SHEETS 57 THRU 60.*

# FORWARD ABUTMENT DETAILS
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | ZF |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 29 |
| TOTAL | 64 |
| SHEET | P. 514 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:28:07 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19101-I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SF005.dgn


| TABLE OF ELASTOMERIC BEARING DIMENSIONS | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| LOCATION | INTERNAL ELASTOMER LAYER THICKNESS | EXTERNAL ELASTOMER LAYER THICKNESS | STEEL LAMINATE THICKNESS | NO. OF INTERNAL ELASTOMER LAYERS | NO. OF EXTERNAL ELASTOMER LAYERS | NO. OF STEEL LAMINATES | TOTAL BEARING THICKNESS | * REACTIONS | | * MAXIMUM DESIGN LOAD |
| | | | | | | | | DL + DW | LL | |
| LEFT BRIDGE (R.A. & F.A.) | 0.375" | 0.1875" | 0.1046" | 10 | 1 | 10 | 4.984" | 242 k | 108 k | 350 k |
| RIGHT BRIDGE (R.A. & F.A.) | 0.375" | 0.1875" | 0.1046" | 10 | 1 | 10 | 4.984" | 238 k | 107 k | 345 k |

* LOADS GIVEN ARE SERVICE LOADS WITH NO IMPACT





***PARTIAL BEARING PLAN AT ABUTMENTS***


*(R.A. SHOWN, F.A. SIMILAR)*
*(BEARING STIFFENER NOT SHOWN FOR CLARITY)*




*(R.A. SHOWN, F.A. SIMILAR, NOT TO SCALE)*
*(EXPANDED POLYSTYRENE OR EXPANDABLE FORMS AND BEARING STIFFENER NOT SHOWN FOR CLARITY)*




*(EXPANDED POLYSTYRENE OR EXPANDABLE FORMS AND BEARING STIFFENERS NOT SHOWN FOR CLARITY)*




***FIELD DRILLED VENT HOLE PLAN***

*(R.A. SHOWN, F.A. SIMILAR)*

***NOTES:***

1. *ELASTOMERIC BEARINGS: THE ELASTOMER SHALL HAVE A HARDNESS OF 50 DUROMETER. THE BEARINGS WERE DESIGNED IN ACCORDANCE WITH SECTION 14.7.6 (METHOD A) OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS. THE LONG-TERM COMPRESSION PROOF LOAD TEST (AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, DIVISION II, SECTION 18.7.2.6) IS NOT REQUIRED.*

2. *LOAD PLATES: THE STEEL LOAD PLATE SHALL BE BONDED BY VULCANIZATION TO THE ELASTOMER DURING THE MODLING PROCESS. THE STEEL LOAD PLATES SHALL BE ASTM A709 GRADE 50 STRUCTURAL STEEL.*

3. *TOP STEEL LOAD PLATE, BOTTOM STEEL LOAD PLATE AND W10x49 SUPPORT BLOCK SHALL BE CONSIDERED COMPONENTS OF THE ELASTOMERIC BEARING ASSEMBLY. THE COST OF ALL LABOR, EQUIPMENT, MATERIAL AND INCIDENTALS NECESSARY TO FURNISH AND INSTALL THE BEARING ASSEMBLY SHALL BE INCLUDED IN THE UNIT BID PRICE FOR ITEM 516 - BEARING DEVICE MISC.: ELASTOMERIC BEARING ASSEMBLY.*

4. *EACH BEARING SHALL BE SHOP MARKED WITH THE FOLLOWING INFORMATION: FORWARD STATION DIRECTION, LOCATION (REAR ABUTMENT, PIER OR FORWARD ABUTMENT) AND BEAM NUMBER. THE MARK SHALL BE PLACED SO THAT IT WILL BE VISIBLE ONCE THE BEARING ASSEMBLY HAS BEEN INSTALLED.*

5. *WELDING: CONTROL WELDING SO THAT THE PLATE TEMPERATURE AT THE ELASTOMER BONDED SURFACE DOES NOT EXCEED 300° F AS DETERMINED BY USE OF PYROMETRIC STICKS OR OTHER TEMPERATURE MONITORING DEVICES.*

# BEARING DETAILS
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

SFN
TBD

DESIGN AGENCY
Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | HS |

REVIEWER
MJR 03/13/26


PROJECT ID
109164

| SUBSET | TOTAL |
|---|---|
| 30 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 515 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:28:22 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SB001.dgn




***FRAMING PLAN - RIGHT BRIDGE***

***LEGEND:***

(GX) - GIRDER LINE DESIGNATION

***NOTES:***


1. SEE SHEET 33 FOR GIRDER ELEVATIONS AND DETAILS.
2. ALL GIRDERS SHALL BE ORIENTED PARALLEL TO ℄ CONSTRUCTION I-71. ALL INTERMEDIATE CROSSFRAMES SHALL BE PLACED NORMAL TO ℄ GIRDERS.
3. FOR ABBREVIATION LEGEND, SEE SHEET 5.
4. FOR STAGED CONSTRUCTION DETAILS, SEE SHEETS 7 THRU 8.
5. THE CONTRACTOR SHALL NOT PERMANENTLY ATTACH INTERMEDIATE CROSSFRAMES IN THE CLOSURE POUR LOCATION UNTIL THE CONCRETE POURS ON BOTH SIDES OF THE CLOSURE POUR LOCATION HAVE BEEN COMPLETED. SEE SHEET 35 FOR ADDITIONAL NOTES.

# FRAMING PLAN - RIGHT BRIDGE
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 31 |
| TOTAL | 64 |
| SHEET | P. 516 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:28:38 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SS003.dgn




***FRAMING PLAN - LEFT BRIDGE***

***NOTES:***

1. *SEE SHEET 33 FOR GIRDER ELEVATIONS AND DETAILS.*
2. *ALL GIRDERS SHALL BEORIENTED PARALLEL TO ℄ CONSTRUCITON I-71. INTERMEDIATE CROSSFRAMES SHALL BE PLACED NORMAL TO ℄ GIRDE.*
3. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
4. *FOR STAGED CONSTRUCTION DETAILSSEE SHEETS 7 THRU 8.*
5. *THE CONTRACTOR SHALL NOT PERMANENTLY ATTACH INTERMEDIATE CROSSFRAMES IN THE CLOSURE POUR LOCATION UNTIL THE CONCRET POURS ON BOTH SIDE OF THE CLOSURE POUR LOCATION HAVE BEEN COMPLETED. SEE SHEET 35 FOR ADDITIONAL NOTES.*

***LEGEND:***


(GX) - *GIRDER LINE DESIGNATION*

# FRAMING PLAN - LEFT BRIDGE
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 32 |
| TOTAL | 64 |
| SHEET | P. 517 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:28:55 PM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SS002.dgn




## GIRDER ELEVATION

**NOTES:**

1. CVN: WHERE A SHAPE OR PLATE IS DESIGNATED (CVN), FURNISH MATERIAL THAT MEETS THE MINIMUM NOTCH TOUGHNESS REQUIREMENTS SPECIFIED IN C&MS 711.01.
2. WELD ATTACHMENT OF SUPPORTS FOR CONCRETE DECK FINISHING MACHINE: FILLET WELDS TO COMPRESSION FLANGES SHALL BE AT LEAST 1" FROM EDGE OF FLANGE, BE NO MORE THAN 2" LONG, AND BE AT LEAST ¼" FOR THICKNESSES UP TO ¾" OR 5/16" FOR GREATER THAN ¾" THICK.
3. BUTT WELDS AT SHOP SPLICES SHALL BE COMPLETE PENETRATION WELDS. WELD REINFORCEMENT SHALL BE COMPLETELY REMOVED BY GRINDING IN THE DIRECTION OF MAIN STRESS.
4. INSTALL STIFFENERS/CONNECTION PLATES ACCORDING TO C&MS 513.
5. FOR CROSSFRAME DETAILS, SEE SHEET 35.
6. HIGH STRENGTH BOLTS SHALL BE 1" DIAMETER F3125, GRADE A325, UNLESS NOTED OTHERWISE. PROVIDE TYPE 1 BOLTS PER C&MS 711.02 FOR ALL GIRDERS.
7. SHEAR CONNECTOR PLACEMENT ON THE FLANGE SPLICE PLATES IS NOT PERMITTED. ADJUST SPACING IF NECESSARY TO AVOID INTERFERENCE WITH SPLICE PLATES AND CONNECTION BOLTS.

**LEGEND:**

(C) - DENOTES COMPRESSION

(T) - DENOTES TENSION

(CS) - INDICATES BUTT WELD SUBJECT TO COMPRESSION STRESS ONLY

(CP) - INDICATES COMPLETE JOINT PENETRATION WELD

(CVN) - CHARPY V-NOTCH

# GIRDER ELEVATION AND DETAILS
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | HS |

REVIEWER MJR 03/13/26

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 33 | 64 |


| SHEET | TOTAL |
|---|---|
| P. 518 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:29:11 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SS001.dgn

| DEFLECTION AND CAMBER TABLE (LEFT BRIDGE) | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| GIRDER G1 DEFLECTION AND CAMBER | LOCATION | | | | | | | | | | |
| | CL BRG. R.A. | 0.10L | 0.20L | 0.30L | 0.40L | 0.50L | 0.60L | 0.70L | 0.80L | 0.90L | CL BRG. F.A. |
| DEFLECTION DUE TO WEIGHT OF STEEL | 0" | 1/2" | 7/8" | 1 3/16" | 1 5/16" | 1 3/8" | 1 5/16" | 1 1/8" | 7/8" | 1/2" | 0" |
| DEFLECTION DUE TO STAGED DECK PLACEMENT | 0" | 1 1/2" | 2 3/4" | 3 3/4" | 4 5/16" | 4 9/16" | 4 5/16" | 3 3/4" | 2 3/4" | 1 1/2" | 0" |
| DEFLECTION DUE TO REMAINING DEAD LOAD | 0" | 3/16" | 5/16" | 3/8" | 7/16" | 7/16" | 7/16" | 3/8" | 5/16" | 3/16" | 0" |
| ADJUSTMENT REQUIRED FOR VERTICAL CURVE | 0" | 7/16" | 13/16" | 1 1/16" | 1 3/16" | 1 1/4" | 1 3/16" | 1 1/16" | 13/16" | 7/16" | 0" |
| REQUIRED SHOP CAMBER | 0" | 2 5/8" | 4 3/4" | 6 3/8" | 7 1/4" | 7 5/8" | 7 1/4" | 6 5/16" | 4 3/4" | 2 5/8" | 0" |
| GIRDERS G2 - G6 DEFLECTION AND CAMBER | LOCATION | | | | | | | | | | |
| | CL BRG. R.A. | 0.10L | 0.20L | 0.30L | 0.40L | 0.50L | 0.60L | 0.70L | 0.80L | 0.90L | CL BRG. F.A. |
| DEFLECTION DUE TO WEIGHT OF STEEL | 0" | 1/2" | 15/16" | 1 1/4" | 1 7/16" | 1 1/2" | 1 7/16" | 1 3/16" | 7/8" | 1/2" | 0" |
| DEFLECTION DUE TO STAGED DECK PLACEMENT | 0" | 1 5/8" | 3" | 4 1/16" | 4 3/4" | 5" | 4 3/4" | 4 1/16" | 3" | 1 5/8" | 0" |
| DEFLECTION DUE TO REMAINING DEAD LOAD | 0" | 3/16" | 1/4" | 3/8" | 7/16" | 7/16" | 7/16" | 3/8" | 1/4" | 3/16" | 0" |
| ADJUSTMENT REQUIRED FOR VERTICAL CURVE | 0" | 7/16" | 13/16" | 1 1/16" | 1 3/16" | 1 1/4" | 1 3/16" | 1 1/16" | 13/16" | 7/16" | 0" |
| REQUIRED SHOP CAMBER | 0" | 2 3/4" | 5" | 6 3/4" | 7 13/16" | 8 3/16" | 7 13/16" | 6 11/16" | 4 15/16" | 2 3/4" | 0" |
| GIRDER G7 DEFLECTION AND CAMBER | LOCATION | | | | | | | | | | |
| | CL BRG. R.A. | 0.10L | 0.20L | 0.30L | 0.40L | 0.50L | 0.60L | 0.70L | 0.80L | 0.90L | CL BRG. F.A. |
| DEFLECTION DUE TO WEIGHT OF STEEL | 0" | 1/2" | 7/8" | 1 3/16" | 1 5/16" | 1 3/8" | 1 5/16" | 1 1/8" | 7/8" | 1/2" | 0" |
| DEFLECTION DUE TO STAGED DECK PLACEMENT | 0" | 1 1/4" | 2 5/16" | 3 3/16" | 3 11/16" | 3 7/8" | 3 11/16" | 3 3/16" | 2 5/16" | 1 1/4" | 0" |
| DEFLECTION DUE TO REMAINING DEAD LOAD | 0" | 3/16" | 5/16" | 3/8" | 7/16" | 1/2" | 7/16" | 3/8" | 5/16" | 3/16" | 0" |
| ADJUSTMENT REQUIRED FOR VERTICAL CURVE | 0" | 7/16" | 13/16" | 1 1/16" | 1 3/16" | 1 1/4" | 1 3/16" | 1 1/16" | 13/16" | 7/16" | 0" |
| REQUIRED SHOP CAMBER | 0" | 2 3/8" | 4 5/16" | 5 13/16" | 6 5/8" | 7" | 6 5/8" | 5 3/4" | 4 5/16" | 2 3/8" | 0" |

| DEFLECTION AND CAMBER TABLE (RIGHT BRIDGE) | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| GIRDERS G1 & G6 DEFLECTION AND CAMBER | LOCATION | | | | | | | | | | |
| | CL BRG. R.A. | 0.10L | 0.20L | 0.30L | 0.40L | 0.50L | 0.60L | 0.70L | 0.80L | 0.90L | CL BRG. F.A. |
| DEFLECTION DUE TO WEIGHT OF STEEL | 0" | 1/2" | 7/8" | 1 3/16" | 1 5/16" | 1 3/8" | 1 5/16" | 1 1/8" | 7/8" | 1/2" | 0" |
| DEFLECTION DUE TO STAGED DECK PLACEMENT | 0" | 1 1/4" | 2 5/16" | 3 3/16" | 3 11/16" | 3 7/8" | 3 11/16" | 3 3/16" | 2 5/16" | 1 1/4" | 0" |
| DEFLECTION DUE TO REMAINING DEAD LOAD | 0" | 3/16" | 5/16" | 7/16" | 1/2" | 9/16" | 1/2" | 7/16" | 5/16" | 3/16" | 0" |
| ADJUSTMENT REQUIRED FOR VERTICAL CURVE | 0" | 7/16" | 13/16" | 1 1/16" | 1 3/16" | 1 1/4" | 1 3/16" | 1 1/16" | 13/16" | 7/16" | 0" |
| REQUIRED SHOP CAMBER | 0" | 2 3/8" | 4 5/16" | 5 7/8" | 6 11/16" | 7 1/16" | 6 11/16" | 5 13/16" | 4 5/16" | 2 3/8" | 0" |
| GIRDERS G2 - G5 DEFLECTION AND CAMBER | LOCATION | | | | | | | | | | |
| | CL BRG. R.A. | 0.10L | 0.20L | 0.30L | 0.40L | 0.50L | 0.60L | 0.70L | 0.80L | 0.90L | CL BRG. F.A. |
| DEFLECTION DUE TO WEIGHT OF STEEL | 0" | 1/2" | 15/16" | 1 1/4" | 1 7/16" | 1 1/2" | 1 3/8" | 1 3/16" | 7/8" | 1/2" | 0" |
| DEFLECTION DUE TO STAGED DECK PLACEMENT | 0" | 1 9/16" | 2 15/16" | 4" | 4 5/8" | 4 7/8" | 4 5/8" | 4" | 2 15/16" | 1 9/16" | 0" |
| DEFLECTION DUE TO REMAINING DEAD LOAD | 0" | 3/16" | 5/16" | 7/16" | 1/2" | 1/2" | 1/2" | 7/16" | 5/16" | 3/16" | 0" |
| ADJUSTMENT REQUIRED FOR VERTICAL CURVE | 0" | 7/16" | 13/16" | 1 1/16" | 1 3/16" | 1 1/4" | 1 3/16" | 1 1/16" | 13/16" | 7/16" | 0" |
| REQUIRED SHOP CAMBER | 0" | 2 11/16" | 5" | 6 3/4" | 7 3/4" | 8 1/8" | 7 11/16" | 6 11/16" | 4 15/16" | 2 11/16" | 0" |




***CAMBER DIAGRAM (NORTHBOUND & SOUTHBOUND)***

***NOTES:***


*1. CAMBER IS ROUNDED TO THE NEAREST $1/16$".*

CAMBER AND DEFLECTION TABLES
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161


SFN TBD
DESIGN AGENCY Jacobs
DESIGNER DBL | CHECKER FM
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 34 | TOTAL 64
SHEET P. 519 | TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:29:25 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SS006.dgn





**INTERMEDIATE CROSSFRAME - LEFT BRIDGE**




**TYPICAL CONNECTION PLATE DETAIL**





**TYPICAL BEARING STIFFENER DETAIL**





**INTERMEDIATE CROSSFRAME - RIGHT BRIDGE**

*(SIMILAR TO LEFT BRIDGE, BUT DIFFERENT GIRDER SPACING)*




**CONNECTION PLATE**




**TYPICAL FLANGE TRANSITION DETAIL**
*(TO BE USED AT FLANGE THICKNESS TRANSITIONS)*

**NOTES:**

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. THE FABRICATOR SHALL CHECK LONGITUDINAL CROSSFRAME SPACING SO THAT INTERFERENCE WITH COMPLETE PENETRATION WEB OR FLANGE WELDED SPLICES IS AVOIDED. SPACING SHALL BE ADJUSTED TO PROVIDE AT LEAST SIX (6) INCHES OF LONGITUDINAL CLEARANCE.
3. IN ACCORDANCE WITH C&MS 513, THE FABRICATOR SHALL DETAIL ALL CROSSFRAMES TO FIT WITH THE WEBS PLUMB AT THE COMPLETION OF SUPERSTRUCTURE ERECTION (STEEL DEAD LOAD FIT, SDLF).
4. CONNECTION PLATES SHALL BE NORMAL TO ℄ GIRDER.
5. IN BAYS WITH CLOSURE POUR, THE FABRICATOR SHALL DETAIL CROSSFRAMES TO FIT AT THE COMPLETION OF DECK PLACEMENT ON EACH SIDE OF THE CLOSURE POUR. BOLT HOLES IN THE CONNECTION PLATE ON ONE OF THE GIRDER LINES SHALL BE FIELD DRILLED AND SHOP DRILLED ON THE OTHER.
6. THE CONTRACTOR SHALL NOT PERMANENTLY ATTACH INTERMEDIATE CROSSFRAMES IN THE CLOSURE POUR LOCATION UNTIL THE CONCRETE POURS ON BOTH SIDES OF THE CLOSURE POUR LOCATION HAVE BEEN COMPLETED.
7. ALL MATERIAL SHALL BE ASTM A709, GRADE 50, YIELD STRENGTH 50-KSI.
8. ALL MATERIAL SHALL BE SHOP PRIMED AND FIELD PAINTED PER C&MS 514.
9. HIGH STRENGTH BOLTS SHALL BE 1" DIAMETER ASTM F3125, GRADE A325, TYPE 1 WITH THREADS EXCLUDED FROM SHEAR PLANE UNLESS OTHERWISE NOTED.

# INTERMEDIATE CROSSFRAME DETAILS
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

SFN TBD

DESIGN AGENCY

Jacobs

| DESIGNER | CHECKER |
|---|---|
| DBL | FM |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 35 | 64 |


| SHEET | TOTAL |
|---|---|
| P. 520 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:29:37 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19101-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SS011.dgn





**DIAPHRAGM PLAN - RIGHT BRIDGE**




**DIAPHRAGM GUIDE PLAN**


***LEGEND:***

GX - GIRDER LINE DESIGNATION




**DIAPHRAGM ELEVATION - RIGHT BRIDGE**

*(DIMENSIONS AND ELEVATIONS SHOWN ALONG ℄ BRG.)*




**DIAPHRAGM GUIDE ELEVATION**

***REINFORCING STEEL LEGEND***

*A: 3 - RD8XX (E.F.) @ 1'-0" MAX. = 2'-0"*
*B: 4 - RD8XX (E.F.) @ 1'-0" MAX. = 3'-0"*
*C: 4 - RD8XX (E.F.) @ 1'-0" MAX. = 3'-0"*
*D: 2 SETS OF 2-RD5XX, RD5XX & RD8XX = 1'-5"*
*E: 3 SETS OF 2-RD5XX, RD5XX & RD8XX @ 1'-6" MAX. = 2'-6"*
*F: 4 SETS OF 2-RD5XX, RD5XX & RD8XX @ 1'-6" MAX. = 3'-8"*
*G: 3 SETS OF 2-RD5XX, RD5XX & RD8XX @ 1'-6" MAX. = 2'-8"*
*H: 3 SETS OF RD5XX & RD8XX @ 1'-6" MAX. = 2'-6"*

***MIN. LAP LENGTHS:***

*#5 BAR = 3'-1"*
*#8 BAR = 5'-4"*

***NOTES:***

1. *FOR REAR ABUTMENT DETAILS, SEE SHEETS 24 THRU 26.*
2. *PLACE THE DIAPHRAGM CONCRETE ENCASING THE STRUCTURAL MEMBER ENDS WITH THE DECK CONCRETE OR AT LEAST 48 HOURS BEFORE PLACEMENT OF THE DECK CONCRETE. IF PLACED SEPARATELY, LOCATE A HORIZONTAL CONSTRUCTION JOINT IN THE DIAPHRAGM AS SHOWN IN SECTION A AND PLACE REMAINING DIAPHRAGM CONCRETE WITH THE DECK.*
3. *ALL REINFORCING STEEL SHALL MAINTAIN A 2" MINIMUM CLEARANCE TO FACE OF CONCRETE UNLESS NOTED OTHERWISE.*


# REAR ABUTMENT DIAPHRAGM PLAN AND ELEVATION - RIGHT BRIDGE

BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 36 |
| TOTAL | 64 |
| SHEET | P. 521 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:29:49 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SR003.dgn




## DIAPHRAGM PLAN - LEFT BRIDGE





A - 37 **SECTION**

## LEGEND:

(GX) - GIRDER LINE DESIGNATION


## MIN. LAP LENGTHS:

#5 BAR = 3'-1"
#8 BAR = 5'-4"




## DIAPHRAGM ELEVATION - LEFT BRIDGE

(DIMENSIONS AND ELEVATIONS SHOWN ALONG ℄ BRG.)




B - 37 **SECTION**

## REINFORCING STEEL LEGEND

A: 3 - RD8XX (E.F.) @ 1'-0" MAX. = 2'-0"
B: 3 - RD8XX (E.F.) @ 1'-0" MAX. = 2'-0"
C: 4 - RD8XX (E.F.) @ 1'-0" MAX. = 3'-0"
D: 4 - RD8XX (E.F.) @ 1'-0" MAX. = 3'-0"
E: 2 SETS OF 2-RD5XX, RD5XX & RD8XX = 1'-5"
F: 3 SETS OF 2-RD5XX, RD5XX & RD8XX = 2'-6"
G: 2 SETS OF 2-RD5XX, RD5XX & RD8XX @ 1'-6" MAX.
H: 3 SETS OF 2-RD5XX, RD5XX & RD8XX @ 1'-6" MAX. = 3'-0"
J: 3 SETS OF RD5XX & RD8XX @ 1'-6" MAX. = 2'-6"

## NOTES:

1. FOR REAR ABUTMENT DETAILS, SEE SHEETS 24 THRU 26.
2. FOR SEMI-INTEGRAL ABUTMENT DIAPHRAGM GUIDE DETAILS, SEE SHEET 36.
3. PLACE THE DIAPHRAGM CONCRETE ENCASING THE STRUCTURAL MEMBER ENDS WITH THE DECK CONCRETE OR AT LEAST 48 HOURS BEFORE PLACEMENT OF THE DECK CONCRETE. IF PLACED SEPARATELY, LOCATE A HORIZONTAL CONSTRUCTION JOINT IN THE DIAPHRAGM AS SHOWN IN SECTION A AND PLACE REMAINING DIAPHRAGM CONCRETE WITH THE DECK.
4. ALL REINFORCING STEEL SHALL MAINTAIN A 2" MINIMUM CLEARANCE TO FACE OF CONCRETE UNLESS NOTED OTHERWISE.
5. 2" DIA. HOLES IN STEEL GIRDER FOR REINFORCING IN FRONT FACE OF DIAPHRAGM.

# REAR ABUTMENT DIAPHRAGM PLAN AND ELEVATION - LEFT BRIDGE
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161


SFN TBD
DESIGN AGENCY
Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | FM |


REVIEWER: MJR 03/13/26
PROJECT ID: 109164
SUBSET 37 | TOTAL 64
SHEET P. 522 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:30:05 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SR004.dgn




***DIAPHRAGM PLAN - RIGHT BRIDGE***





***SECTION*** A - A / 39

***LEGEND:***

(GX) - GIRDER LINE DESIGNATION

***MIN. LAP LENGTHS:***

#5 BAR = 3'-1"
#8 BAR = 5'-4"




***DIAPHRAGM ELEVATION - RIGHT BRIDGE***

*(DIMENSIONS AND ELEVATIONS SHOWN ALONG ℄ BRG.)*




***SECTION*** B - B / 39

***REINFORCING STEEL LEGEND***

| | | |
|---|---|---|
| A: 3 - FD8XX (E.F.) @ 1'-0" MAX. = 2'-0" | D: 2 SETS OF 2-FD5XX, FD5XX & FD8XX = 1'-5" | G: 3 SETS OF 2-FD5XX, FD5XX & FD8XX @ 1'-6" MAX. = 2'-8" |
| B: 4 - FD8XX (E.F.) @ 1'-0" MAX. = 3'-0" | E: 3 SETS OF 2-FD5XX, FD5XX & FD8XX @ 1'-6" MAX. = 2'-6" | H: 3 SETS OF FD5XX & FD8XX @ 1'-6" MAX. = 2'-6" |
| C: 4 - FD8XX (E.F.) @ 1'-0" MAX. = 3'-0" | F: 4 SETS OF 2-FD5XX, FD5XX & FD8XX @ 1'-6" MAX. = 3'-8" | |

***NOTES:***


1. *FOR FORWARD ABUTMENT DETAILS, SEE SHEETS 27 THRU 29.*
2. *FOR SEMI-INTEGRAL ABUTMENT DIAPHRAGM GUIDE DETAILS, SEE SHEET 36.*
3. *PLACE THE DIAPHRAGM CONCRETE ENCASING THE STRUCTURAL MEMBER ENDS WITH THE DECK CONCRETE OR AT LEAST 48 HOURS BEFORE PLACEMENT OF THE DECK CONCRETE. IF PLACED SEPARATELY, LOCATE A HORIZONTAL CONSTRUCTION JOINT IN THE DIAPHRAGM AS SHOWN IN SECTION A AND PLACE REMAINING DIAPHRAGM CONCRETE WITH THE DECK.*
4. *ALL REINFORCING STEEL SHALL MAINTAIN A 2" MINIMUM CLEARANCE TO FACE OF CONCRETE UNLESS NOTED OTHERWISE.*
5. *2" DIA. HOLES IN STEEL GIRDER FOR REINFORCING IN FRONT FACE OF DIAPHRAGM.*

# FORWARD ABUTMENT DIAPHRAGM PLAN AND ELEVATION - RIGHT BRIDGE
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 38 |
| TOTAL | 64 |
| SHEET | P. 523 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:30:18 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SF004.dgn





***DIAPHRAGM PLAN - LEFT BRIDGE***

***LEGEND:***

(GX) - GIRDER LINE DESIGNATION

***MIN. LAP LENGTHS:***

*#5 BAR = 3'-1"*
*#8 BAR = 5'-4"*




***DIAPHRAGM ELEVATION - LEFT BRIDGE***
*(DIMENSIONS AND ELEVATIONS SHOWN ALONG ℄ BRG.)*

***REINFORCING STEEL LEGEND***

*A: 3 - FD8XX (E.F.) @ 1'-0" MAX. = 2'-0"*
*B: 3 - FD8XX (E.F.) @ 1'-0" MAX. = 2'-0"*
*C: 4 - FD8XX (E.F.) @ 1'-0" MAX. = 3'-0"*
*D: 4 - FD8XX (E.F.) @ 1'-0" MAX. = 3'-0"*
*E: 2 SETS OF 2-FD5XX, FD5XX & FD8XX = 1'-5"*
*F: 3 SETS OF 2-FD5XX, FD5XX & FD8XX = 2'-6"*
*G: 2 SETS OF 2-FD5XX, FD5XX & FD8XX @ 1'-6" MAX.*
*H: 3 SETS OF 2-FD5XX, FD5XX & FD8XX @ 1'-6" MAX. = 3'-0"*
*J: 3 SETS OF FD5XX & FD8XX @ 1'-6" MAX. = 2'-6"*

***NOTES:***

1. *FOR FORWAFD ABUTMENT DETAILS, SEE SHEETS 27 THRU 29.*
2. *FOR SEMI-INTEGRAL ABUTMENT DIAPHRAGM GUIDE DETAILS, SEE SHEET 36.*
3. *PLACE THE DIAPHRAGM CONCRETE ENCASING THE STRUCTURAL MEMBER ENDS WITH THE DECK CONCRETE OR AT LEAST 48 HOURS BEFORE PLACEMENT OF THE DECK CONCRETE. IF PLACED SEPARATELY, LOCATE A HORIZONTAL CONSTRUCTION JOINT IN THE DIAPHRAGM AS SHOWN IN SECTION A AND PLACE REMAINING DIAPHRAGM CONCRETE WITH THE DECK.*
4. *ALL REINFORCING STEEL SHALL MAINTAIN A 2" MINIMUM CLEARANCE TO FACE OF CONCRETE UNLESS NOTED OTHERWISE.*


# FORWARD ABUTMENT DIAPHRAGM PLAN AND ELEVATION - LEFT BRIDGE

BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 39 |
| TOTAL | 64 |
| SHEET | P. 524 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:30:34 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SF003.dgn




***DECK PLAN - RIGHT BRIDGE (NB) - BOTTOM REINFORCING***
*(DIAPHRAGM BARS NOT SHOWN FOR CLARITY)*

***LEGEND:***

(GXX) - GIRDER LINE DESIGNATION

***NOTES:***

1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. MINIMUM REINFORCING STEEL LAP LENGTHS:
   NO. 4 BAR = 2'-6"
   NO. 5 BAR = 3'-1"
   NO. 6 BAR = 4'-0"

# DECK PLAN - RIGHT BRIDGE (BOTTOM MAT)
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161


SFN TBD
DESIGN AGENCY Jacobs
DESIGNER MAN | CHECKER FM
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 40 | TOTAL 64
SHEET P. 525 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:30:50 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SD003.dgn

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:31:03 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SD004.dgn






***DECK PLAN - RIGHT BRIDGE (NB) - TOP REINFORCING***

*(DIAPHRAGM BARS NOT SHOWN FOR CLARITY)*

***LEGEND:***


(GXX) - *GIRDER LINE DESIGNATION*

***NOTES:***

1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *MINIMUM REINFORCING STEEL LAP LENGTHS:*
   *NO. 4 BAR = 2'-6"*
   *NO. 5 BAR = 3'-1"*
   *NO. 6 BAR = 4'-0"*

# DECK PLAN - RIGHT BRIDGE (TOP MAT)
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 41 |
| TOTAL | 64 |
| SHEET | P. 526 |
| TOTAL | 618 |




## DECK PLAN - LEFT BRIDGE (SB) - BOTTOM REINFORCING

*(DIAPHRAGM BARS NOT SHOWN FOR CLARITY)*

**LEGEND:**

(GXX) - GIRDER LINE DESIGNATION

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. MINIMUM REINFORCING STEEL LAP LENGTHS:
   NO. 4 BAR = 2'-6"
   NO. 5 BAR = 3'-1"
   NO. 6 BAR = 4'-0"

# DECK PLAN - LEFT BRIDGE (BOTTOM MAT)
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 42 |
| TOTAL | 64 |
| SHEET | P. 527 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:31:20 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SD001.dgn




## DECK PLAN - LEFT BRIDGE (SB) - TOP REINFORCING

*(DIAPHRAGM BARS NOT SHOWN FOR CLARITY)*

**LEGEND:**

(GXX) - GIRDER LINE DESIGNATION

**NOTES:**


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. MINIMUM REINFORCING STEEL LAP LENGTHS:
   - NO. 4 BAR = 2'-6"
   - NO. 5 BAR = 3'-1"
   - NO. 6 BAR = 4'-0"

# DECK PLAN - LEFT BRIDGE (TOP MAT)
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 43 |
| TOTAL | 64 |
| SHEET | P. 528 |
| TOTAL | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:31:40 PM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\40D-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SD002.dgn




***TRANSVERSE SECTION - RIGHT BRIDGE (NORTHBOUND)***


*(LOOKING UPSTATION)*
*(CROSSFRAMES NOT SHOWN FOR CLARITY)*
*(PARAPET REINFORCING STEEL NOT SHOWN FOR CLARITY)*

| MIN. LAP LENGTHS | |
|---|---|
| NO. 4 BARS | 2'-6" |
| NO. 5 BARS | 3'-1" |
| NO. 6 BARS | 4'-0" |




***TYPICAL REINFORCING AND OVERHANG DETAIL - RIGHT BRIDGE (NORTHBOUND)***

*(BAY BETWEEN GIRDERS G8 AND G9 SHOWN,*
*BAY BETWEEN GIRDERS G13 AND G12 OPPOSITE HAND)*




***TYPICAL REINFORCING - RIGHT BRIDGE (NORTHBOUND)***

*(BAY BETWEEN GIRDERS G10 AND G11 FOR CLOSURE POUR SHOWN)*

***LEGEND:***

(GXX) - GIRDER LINE DESIGNATION

***NOTES:***


1. FOR ABBREVIATION LEGEND, SEE SHEET 5.
2. FOR PARAPET DETAILS, SEE SHEETS 52 THRU 53..
3. PER C&MS 511.19, THE 2'-0" HMWM CENTERED ON THE PHASE CONSTRUCTION JOINT IS CONSIDERED INCIDENTAL TO ITEM 511 - CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK.
4. DECK SLAB CONCRETE QUANTITY: THE ESTIMATED QUANTITY OF DECK SLAB CONCRETE IS BASED ON THE CONSTANT DECK SLAB THICKNESS, AS SHOWN, PLUS THE QUANTITY OF CONCRETE THAT FORMS EACH BEAM/GIRDER HAUNCH. THE ESTIMATE ASSUMES A CONSTANT HAUNCH THICKNESS OF 3.43" AND A HAUNCH WITH EQUAL TO THE TOP FLANGE WIDTH. DEVIATE FROM THIS HAUNCH THICKNESS AS NECESSARY TO PLACE THE DECK SURFACE AT THE FINISHED GRADE.
5. THE HAUNCH THICKNESS WAS MEASURED AT THE CENTERLINE OF THE BEAM/GIRDER, FROM THE SURFACE OF THE DECK TOO THE BOTTOM OF THE TOP FLANGE MINUS THE DECK SLAB THICKNESS. THE AREA OF ALL EMBEDDED STEEL PLATES HAS BEEN DEDUCTED FROM THE HAUNCH QUANTITY IN ACCORDANCE WITH C&MS 511.23.

TRANSVERSE SECTION - RIGHT BRIDGE
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN TBD
DESIGN AGENCY Jacobs
DESIGNER MAN | CHECKER FM
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 44 | TOTAL 64
SHEET P. 529 | TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:31:52 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SD006.dgn




***TRANSVERSE SECTION - LEFT BRIDGE (SOUTHBOUND)***


*(LOOKING UPSTATION)*
*(CROSSFRAMES NOT SHOWN FOR CLARITY)*
*(PARAPET REINFORCING STEEL NOT SHOWN FOR CLARITY)*

| MIN. LAP LENGTHS | |
|---|---|
| NO. 4 BARS | 2'-6" |
| NO. 5 BARS | 3'-1" |
| NO. 6 BARS | 4'-0" |




***TYPICAL REINFORCING AND OVERHANG DETAIL - LEFT BRIDGE (SOUTHBOUND)***

*(WEST OVERHANG AND BAY BETWEEN GIRDERS G1 AND G2 SHOWN,*
*EAST OVERHANG AND BAY BETWEEN GIRDERS G6 AND G7 SIMILAR AND OPPOSITE HAND)*




***TYPICAL REINFORCING - LEFT BRIDGE (SOUTHBOUND)***

*(BAY BETWEEN GIRDERS G3 AND G4 FOR CLOSURE POUR SHOWN)*

***NOTES:***

1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*
2. *FOR PARAPET DETAILS, SEE SHEETS 52 THRU 53.*
3. *PER C&MS 511.19, THE 2'-0" HMWM CENTERED ON THE PHASE CONSTRUCTION JOINT IS CONSIDERED INCIDENTAL TO ITEM 511 - CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK.*

TRANSVERSE SECTION - LEFT BRIDGE
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | FM |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 45 | 64 |


| SHEET | TOTAL |
|---|---|
| P. 530 | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:32:06 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SD005.dgn




***TRANSVERSE SECTION***




***TYPICAL LIMITS OF CONCRETE SEALING***
*(NOT TO SCALE)*




***LIMITS OF PAINTING OF STRUCTURAL STEEL***
*(NOT TO SCALE)*

***NOTES:***


1. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*

TRANSVERSE SECTION - GENERAL GEOMETRY
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 46 |
| TOTAL | 64 |
| SHEET | P. 531 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:32:19 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_ST002.dgn




***CRITICAL BRIDGE POINTS PLAN***

*(FOR USE WITH CAMBER, SCREED, TOP OF HAUNCH AND FINAL DECK SURFACE ELEVATION TABLES)*

***LEGEND:***

(GXX) - *GIRDER LINE DESIGNATION*

***NOTES:***


1. *FOR SCREED TABLES, SEE SHEETS 49 THRU 51.*
2. *FOR SCREED LOCATION TRANSVERSE SECTIONS, SEE SHEET 48.*
3. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*

# BRIDGE CRITICAL POINTS PLAN
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | MAN |
| CHECKER | ZF |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 47 |
| TOTAL | 64 |
| SHEET | P. 532 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:32:35 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SS004.dgn




***SCREED LOCATION TRANSVERSE SECTION - LEFT BRIDGE & RIGHT BRIDGE***

*(FOR USE WITH CAMBER, SCREED, TOP OF HAUNCH AND FINAL DECK SURFACE ELEVATION TABLES)*

***NOTES:***

1. *FOR SCREED TABLE, SEE SHEETS 49 THRU 51.*
2. *FOR CRITICAL BRIDGE POINTS PLAN, SEE SHEET 47.*
3. *FOR ABBREVIATION LEGEND, SEE SHEET 5.*

BRIDGE CRITICAL POINTS TRANSVERSE SECTION
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN
TBD

DESIGN AGENCY
Jacobs

| DESIGNER | CHECKER |
|---|---|
| MAN | ZF |

REVIEWER
MJR 03/13/26

PROJECT ID
109164

| SUBSET | TOTAL |
|---|---|
| 48 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 533 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:32:49 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SS005.dgn

| SCREED ELEVATIONS (SOUTHBOUND) | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATION | TOE OF LEFT PARAPET | | PHASE 3B C.J. | | PHASE 3A C.J. | | CROWN | | PGL | | TOE OF RIGHT PARAPET | |
| | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. |
| CL BRG. R.A. | 1415+40.04 | 937.54 | 141540.04 | 938.00 | 1415+40.04 | 938.10 | 1415+40.04 | 938.11 | 141540.04 | 937.74 | 1415+40.04 | 9+37.49 |
| 0.10L | 1415+53.03 | 937.73 | 141553.03 | 938.20 | 1415+53.03 | 938.30 | 1415+53.03 | 938.31 | 141553.03 | 937.94 | 1415+53.03 | 9+37.66 |
| 0.20L | 1415+66.02 | 937.90 | 141566.02 | 938.38 | 1415+66.02 | 938.47 | 1415+66.02 | 938.49 | 141566.02 | 938.11 | 1415+66.02 | 9+37.81 |
| 0.30L | 1415+79.01 | 938.03 | 141579.01 | 938.51 | | 938.61 | 1415+79.01 | 938.62 | 141579.01 | 938.25 | 1415+79.01 | 9+37.92 |
| 0.40L | 1415+92.00 | 938.11 | 141592.00 | 938.61 | 1415+92.00 | 938.70 | 1415+92.00 | 938.72 | 141592.00 | 938.34 | 1415+92.00 | 9+38.01 |
| 0.50L | 1416+05.00 | 938.16 | 141605.00 | 938.65 | 1416+05.00 | 938.75 | 1416+05.00 | 938.76 | 141605.00 | 938.39 | 1416+05.00 | 9+38.05 |
| 0.60L | 1416+17.99 | 938.16 | 141617.99 | 938.65 | 1416+17.99 | 938.74 | 1416+17.99 | 938.76 | 141617.99 | 938.39 | 1416+17.99 | 9+38.05 |
| 0.70L | 1416+30.98 | 938.11 | 141630.98 | 938.60 | 1416+30.98 | 938.69 | 1416+30.98 | 938.71 | 141630.98 | 938.33 | 1416+30.98 | 9+38.01 |
| 0.80L | 1416+43.97 | 938.02 | 141643.97 | 938.50 | 1416+43.97 | 938.60 | 1416+43.97 | 938.61 | 141643.97 | 938.24 | 1416+43.97 | 9+37.93 |
| 0.90L | 1416+56.96 | 937.90 | 141656.96 | 938.37 | 1416+56.96 | 938.47 | 1416+56.96 | 938.48 | 141656.96 | 938.11 | 1416+56.96 | 9+37.83 |
| CL BRG. F.A. | 1416+69.95 | 937.75 | 141669.95 | 938.21 | 1416+69.95 | 938.31 | 1416+69.95 | 938.32 | 141669.95 | 937.95 | 1416+69.95 | 9+37.70 |

| SCREED ELEVATIONS (NORTHBOUND) | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATION | TOE OF LEFT PARAPET | | PGL | | PHASE 4A C.J. | | PHASE 4B C.J. | | CROWN | | TOE OF RIGHT PARAPET | |
| | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. |
| CL BRG. R.A. | 1415+40.04 | 937.53 | 1415+40.04 | 937.81 | 1415+40.04 | 937.98 | 1415+40.04 | 938.04 | 1415+40.04 | 938.15 | 1415+40.04 | 937.81 |
| 0.10L | 1415+53.03 | 937.70 | 1415+53.03 | 938.01 | 1415+53.03 | 938.18 | 1415+53.03 | 938.24 | 1415+53.03 | 938.35 | 1415+53.03 | 937.98 |
| 0.20L | 1415+66.02 | 937.85 | 1415+66.02 | 938.18 | 1415+66.02 | 938.35 | 1415+66.02 | 938.42 | 1415+66.02 | 938.53 | 1415+66.02 | 938.14 |
| 0.30L | 1415+79.01 | 937.97 | 1415+79.01 | 938.32 | 1415+79.01 | 938.49 | 1415+79.01 | 938.55 | 1415+79.01 | 938.66 | 1415+79.01 | 938.25 |
| 0.40L | 1415+92.00 | 938.05 | 1415+92.00 | 938.41 | 1415+92.00 | 938.58 | 1415+92.00 | 938.65 | 1415+92.00 | 938.76 | 1415+92.00 | 938.34 |
| 0.50L | 1416+05.00 | 938.10 | 1416+05.00 | 938.46 | 1416+05.00 | 938.63 | 1416+05.00 | 938.69 | 1416+05.00 | 938.80 | 1416+05.00 | 938.38 |
| 0.60L | 1416+17.99 | 938.10 | 1416+17.99 | 938.46 | 1416+17.99 | 938.63 | 1416+17.99 | 938.69 | 1416+17.99 | 938.80 | 1416+17.99 | 938.38 |
| 0.70L | 1416+30.98 | 938.06 | 1416+30.98 | 938.41 | 1416+30.98 | 938.58 | 1416+30.98 | 938.64 | 1416+30.98 | 938.75 | 1416+30.98 | 938.34 |
| 0.80L | 1416+43.97 | 937.98 | 1416+43.97 | 938.31 | 1416+43.97 | 938.48 | 1416+43.97 | 938.55 | 1416+43.97 | 938.66 | 1416+43.97 | 938.27 |
| 0.90L | 1416+56.96 | 937.87 | 1416+56.96 | 938.18 | 1416+56.96 | 938.35 | 1416+56.96 | 938.42 | 1416+56.96 | 938.53 | 1416+56.96 | 938.16 |
| CL BRG. F.A. | 1416+69.95 | 937.74 | 1416+69.95 | 938.03 | 1416+69.95 | 938.20 | 1416+69.95 | 938.26 | 1416+69.95 | 938.37 | 1416+69.95 | 938.03 |

***NOTES:***

1. *SCREED ELEVATIONS SHOWN REPRESENT THE THEORETICAL DECK SURFACE LOCATION PRIOR TO DEFLECTIONS CAUSED BY DECK PLACEMENT AND OTHER ANTICIPATED DEAD LOADS.*
2. *SEE SHEET 47 AND SHEET 48 FOR CRITICAL BRIDGE POINTS PLAN AND SCREEN LOCATION TRANSVERSE SECTION.*

# SCREED ELEVATION TABLES
## BRIDGE NO. FRA-00071-26.460 L/R
## I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| DBL | FM |

REVIEWER MJR 03/13/26

PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 49 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 534 | 618 |

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:33:02 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SS008.dgn

| TOP OF HAUNCH ELEVATIONS (LEFT BRIDGE) | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATION | G1 | | G2 | | G3 | | G4 | | G5 | | G6 | | G7 | |
| | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. |
| CL BRG. R.A. | 1415+40.04 | 936.79 | 1415+40.04 | 936.98 | 1415+40.04 | 937.17 | 1415+40.04 | 937.28 | 1415+40.04 | 937.09 | 1415+40.04 | 936.90 | 1415+40.04 | 936.71 |
| 0.10L | 1415+53.03 | 936.98 | 1415+53.03 | 937.18 | 1415+53.03 | 937.37 | 1415+53.03 | 937.48 | 1415+53.03 | 937.29 | 1415+53.03 | 937.10 | 1415+53.03 | 936.88 |
| 0.20L | 1415+66.02 | 937.14 | 1415+66.02 | 937.35 | 1415+66.02 | 937.54 | 1415+66.02 | 937.66 | 1415+66.02 | 937.47 | 1415+66.02 | 937.27 | 1415+66.02 | 937.03 |
| 0.30L | 1415+79.01 | 937.27 | 1415+79.01 | 937.49 | 1415+79.01 | 937.68 | 1415+79.01 | 937.79 | 1415+79.01 | 937.60 | 1415+79.01 | 937.41 | 1415+79.01 | 937.15 |
| 0.40L | 1415+92.00 | 937.36 | 1415+92.00 | 937.58 | 1415+92.00 | 937.77 | 1415+92.00 | 937.89 | 1415+92.00 | 937.70 | 1415+92.00 | 937.50 | 1415+92.00 | 937.23 |
| 0.50L | 1416+05.00 | 937.40 | 1416+05.00 | 937.63 | 1416+05.00 | 937.82 | 1416+05.00 | 937.93 | 1416+05.00 | 937.74 | 1416+05.00 | 937.55 | 1416+05.00 | 937.27 |
| 0.60L | 1416+17.99 | 937.40 | 1416+17.99 | 937.62 | 1416+17.99 | 937.82 | 1416+17.99 | 937.93 | 1416+17.99 | 937.74 | 1416+17.99 | 937.55 | 1416+17.99 | 937.27 |
| 0.70L | 1416+30.98 | 937.35 | 1416+30.98 | 937.57 | 1416+30.98 | 937.76 | 1416+30.98 | 937.88 | 1416+30.98 | 937.69 | 1416+30.98 | 937.50 | 1416+30.98 | 937.23 |
| 0.80L | 1416+43.97 | 937.27 | 1416+43.97 | 937.48 | 1416+43.97 | 937.67 | 1416+43.97 | 937.78 | 1416+43.97 | 937.59 | 1416+43.97 | 937.40 | 1416+43.97 | 937.16 |
| 0.90L | 1416+56.96 | 937.14 | 1416+56.96 | 937.35 | 1416+56.96 | 937.54 | 1416+56.96 | 937.65 | 1416+56.96 | 937.46 | 1416+56.96 | 937.27 | 1416+56.96 | 937.05 |
| CL BRG. F.A. | 1416+69.95 | 937.00 | 1416+69.95 | 937.19 | 1416+69.95 | 937.38 | 1416+69.95 | 937.49 | 1416+69.95 | 937.30 | 1416+69.95 | 937.11 | 1416+69.95 | 936.92 |

| TOP OF HAUNCH ELEVATIONS (RIGHT BRIDGE) | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATION | G8 | | G9 | | G10 | | G11 | | G12 | | G13 | |
| | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. |
| CL BRG. R.A. | 1415+40.04 | 936.75 | 1415+40.04 | 936.94 | 1415+40.04 | 937.13 | 1415+40.04 | 937.32 | 1415+40.04 | 937.23 | 1415+40.04 | 937.04 |
| 0.10L | 1415+53.03 | 936.92 | 1415+53.03 | 937.14 | 1415+53.03 | 937.33 | 1415+53.03 | 937.52 | 1415+53.03 | 937.43 | 1415+53.03 | 937.21 |
| 0.20L | 1415+66.02 | 937.08 | 1415+66.02 | 937.32 | 1415+66.02 | 937.51 | 1415+66.02 | 937.70 | 1415+66.02 | 937.60 | 1415+66.02 | 937.36 |
| 0.30L | 1415+79.01 | 937.20 | 1415+79.01 | 937.45 | 1415+79.01 | 937.64 | 1415+79.01 | 937.84 | 1415+79.01 | 937.74 | 1415+79.01 | 937.48 |
| 0.40L | 1415+92.00 | 937.28 | 1415+92.00 | 937.55 | 1415+92.00 | 937.74 | 1415+92.00 | 937.93 | 1415+92.00 | 937.83 | 1415+92.00 | 937.56 |
| 0.50L | 1416+05.00 | 937.32 | 1416+05.00 | 937.59 | 1416+05.00 | 937.78 | 1416+05.00 | 937.98 | 1416+05.00 | 937.88 | 1416+05.00 | 937.61 |
| 0.60L | 1416+17.99 | 937.32 | 1416+17.99 | 937.59 | 1416+17.99 | 937.78 | 1416+17.99 | 937.97 | 1416+17.99 | 937.87 | 1416+17.99 | 937.61 |
| 0.70L | 1416+30.98 | 937.28 | 1416+30.98 | 937.54 | 1416+30.98 | 937.73 | 1416+30.98 | 937.92 | 1416+30.98 | 937.82 | 1416+30.98 | 937.57 |
| 0.80L | 1416+43.97 | 937.21 | 1416+43.97 | 937.45 | 1416+43.97 | 937.64 | 1416+43.97 | 937.83 | 1416+43.97 | 937.73 | 1416+43.97 | 937.49 |
| 0.90L | 1416+56.96 | 937.10 | 1416+56.96 | 937.32 | 1416+56.96 | 937.51 | 1416+56.96 | 937.70 | 1416+56.96 | 937.60 | 1416+56.96 | 937.38 |
| CL BRG. F.A. | 1416+69.95 | 936.97 | 1416+69.95 | 937.16 | 1416+69.95 | 937.35 | 1416+69.95 | 937.54 | 1416+69.95 | 937.44 | 1416+69.95 | 937.25 |

**NOTES:**

1. TOP OF HAUNCH ELEVATIONS SHOWN REPRESENT THE THEORETICAL LOCATION OF THE BOTTOM OF THE DECK ABOVE THE ℄ OF THE GIRDER HAUNCH PRIOR TO DEFLECTIONS CAUSED BY DECK PLACEMENT AND OTHER ANTICIPATED DEAD LOADS.
2. SEE SHEETS 47 AND 48 FOR GIRDERS NUMBERS AND TOP OF HAUNCH ELEVATION LOCATIONS.




**HAUNCH DETAIL**

# TOP OF HAUNCH ELEVATIONS TABLES
# BRIDGE NO. FRA-00071-26.460 L/R
# I-71 OVER SR 161

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:33:28 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SS009.dgn

SFN TBD
DESIGN AGENCY Jacobs
DESIGNER DBL | CHECKER FM
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 50 | TOTAL 64
SHEET P. 535 | TOTAL 618

| FINAL DECK SURFACE ELEVATIONS (SOUTHBOUND) | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATION | TOE OF LEFT PARAPET | | G1 | | G2 | | G3 | | PHASE 3B C.J. | | PHASE 3A C.J. | | CROWN | |
| | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. |
| CL BRG. R.A. | 1415+40.04 | 937.54 | 1415+40.04 | 937.58 | 1415+40.04 | 937.77 | 1415+40.04 | 937.96 | 1415+40.04 | 938.00 | 1415+40.04 | 938.10 | 1415+40.04 | 938.11 |
| 0.10L | 1415+53.03 | 937.60 | 1415+53.03 | 937.64 | 1415+53.03 | 937.83 | 1415+53.03 | 938.02 | 1415+53.03 | 938.06 | 1415+53.03 | 938.15 | 1415+53.03 | 938.17 |
| 0.20L | 1415+66.02 | 937.65 | 1415+66.02 | 937.68 | 1415+66.02 | 937.88 | 1415+66.02 | 938.07 | 1415+66.02 | 938.11 | 1415+66.02 | 938.20 | 1415+66.02 | 938.22 |
| 0.30L | 1415+79.01 | 937.69 | 1415+79.01 | 937.73 | 1415+79.01 | 937.92 | 1415+79.01 | 938.11 | 1415+79.01 | 938.15 | 1415+79.01 | 938.24 | 1415+79.01 | 938.26 |
| 0.40L | 1415+92.00 | 937.72 | 1415+92.00 | 937.76 | 1415+92.00 | 937.95 | 1415+92.00 | 938.14 | 1415+92.00 | 938.18 | 1415+92.00 | 938.28 | 1415+92.00 | 938.29 |
| 0.50L | 1416+05.00 | 937.75 | 1416+05.00 | 937.78 | 1416+05.00 | 937.97 | 1416+05.00 | 938.17 | 1416+05.00 | 938.21 | 1416+05.00 | 938.30 | 1416+05.00 | 938.32 |
| 0.60L | 1416+17.99 | 937.76 | 1416+17.99 | 937.80 | 1416+17.99 | 937.99 | 1416+17.99 | 938.18 | 1416+17.99 | 938.23 | 1416+17.99 | 938.32 | 1416+17.99 | 938.33 |
| 0.70L | 1416+30.98 | 937.77 | 1416+30.98 | 937.81 | 1416+30.98 | 938.00 | 1416+30.98 | 938.19 | 1416+30.98 | 938.23 | 1416+30.98 | 938.33 | 1416+30.98 | 938.34 |
| 0.80L | 1416+43.97 | 937.77 | 1416+43.97 | 937.81 | 1416+43.97 | 938.00 | 1416+43.97 | 938.19 | 1416+43.97 | 938.24 | 1416+43.97 | 938.33 | 1416+43.97 | 938.34 |
| 0.90L | 1416+56.96 | 937.77 | 1416+56.96 | 937.80 | 1416+56.96 | 937.99 | 1416+56.96 | 938.19 | 1416+56.96 | 938.23 | 1416+56.96 | 938.32 | 1416+56.96 | 938.34 |
| CL BRG. F.A. | 1416+69.95 | 937.75 | 1416+69.95 | 937.79 | 1416+69.95 | 937.98 | 1416+69.95 | 938.17 | 1416+69.95 | 938.21 | 1416+69.95 | 938.31 | 1416+69.95 | 938.32 |

| FINAL DECK SURFACE ELEVATIONS (SOUTHBOUND) CONT. | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATION | G4 | | G5 | | PGL | | G6 | | G7 | | TOE OF RIGHT PARAPET | |
| | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. |
| CL BRG. R.A. | 1415+40.04 | 938.07 | 1415+40.04 | 937.88 | 1415+40.04 | 937.74 | 1415+40.04 | 937.69 | 1415+40.04 | 937.50 | 1415+40.04 | 937.49 |
| 0.10L | 1415+53.03 | 938.13 | 1415+53.03 | 937.94 | 1415+53.03 | 937.80 | 1415+53.03 | 937.75 | 1415+53.03 | 937.56 | 1415+53.03 | 937.54 |
| 0.20L | 1415+66.02 | 938.18 | 1415+66.02 | 937.99 | 1415+66.02 | 937.84 | 1415+66.02 | 937.80 | 1415+66.02 | 937.61 | 1415+66.02 | 937.59 |
| 0.30L | 1415+79.01 | 938.22 | 1415+79.01 | 938.03 | 1415+79.01 | 937.88 | 1415+79.01 | 937.84 | 1415+79.01 | 937.65 | 1415+79.01 | 937.63 |
| 0.40L | 1415+92.00 | 938.25 | 1415+92.00 | 938.06 | 1415+92.00 | 937.92 | 1415+92.00 | 937.87 | 1415+92.00 | 937.68 | 1415+92.00 | 937.67 |
| 0.50L | 1416+05.00 | 938.28 | 1416+05.00 | 938.09 | 1416+05.00 | 937.94 | 1416+05.00 | 937.90 | 1416+05.00 | 937.71 | 1416+05.00 | 937.69 |
| 0.60L | 1416+17.99 | 938.30 | 1416+17.99 | 938.10 | 1416+17.99 | 937.96 | 1416+17.99 | 937.91 | 1416+17.99 | 937.72 | 1416+17.99 | 937.71 |
| 0.70L | 1416+30.98 | 938.30 | 1416+30.98 | 938.11 | 1416+30.98 | 937.97 | 1416+30.98 | 937.92 | 1416+30.98 | 937.73 | 1416+30.98 | 937.72 |
| 0.80L | 1416+43.97 | 938.31 | 1416+43.97 | 938.11 | 1416+43.97 | 937.97 | 1416+43.97 | 937.92 | 1416+43.97 | 937.73 | 1416+43.97 | 937.72 |
| 0.90L | 1416+56.96 | 938.30 | 1416+56.96 | 938.11 | 1416+56.96 | 937.96 | 1416+56.96 | 937.92 | 1416+56.96 | 937.73 | 1416+56.96 | 937.71 |
| CL BRG. F.A. | 1416+69.95 | 938.28 | 1416+69.95 | 938.09 | 1416+69.95 | 937.95 | 1416+69.95 | 937.90 | 1416+69.95 | 937.71 | 1416+69.95 | 937.70 |

| FINAL DECK SURFACE ELEVATIONS (NORTHBOUND) | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATION | TOE OF LEFT PARAPET | | G8 | | G9 | | PGL | | G10 | | PHASE 4A C.J. | |
| | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. |
| CL BRG. R.A. | 1415+40.04 | 937.53 | 1415+40.04 | 937.54 | 1415+40.04 | 937.73 | 1415+40.04 | 937.81 | 1415+40.04 | 937.92 | 1415+40.04 | 937.98 |
| 0.10L | 1415+53.03 | 937.58 | 1415+53.03 | 937.60 | 1415+53.03 | 937.79 | 1415+53.03 | 937.87 | 1415+53.03 | 937.98 | 1415+53.03 | 938.04 |
| 0.20L | 1415+66.02 | 937.63 | 1415+66.02 | 937.65 | 1415+66.02 | 937.84 | 1415+66.02 | 937.92 | 1415+66.02 | 938.03 | 1415+66.02 | 938.09 |
| 0.30L | 1415+79.01 | 937.67 | 1415+79.01 | 937.69 | 1415+79.01 | 937.88 | 1415+79.01 | 937.96 | 1415+79.01 | 938.07 | 1415+79.01 | 938.13 |
| 0.40L | 1415+92.00 | 937.71 | 1415+92.00 | 937.72 | 1415+92.00 | 937.92 | 1415+92.00 | 937.99 | 1415+92.00 | 938.11 | 1415+92.00 | 938.16 |
| 0.50L | 1416+05.00 | 937.73 | 1416+05.00 | 937.75 | 1416+05.00 | 937.94 | 1416+05.00 | 938.02 | 1416+05.00 | 938.13 | 1416+05.00 | 938.19 |
| 0.60L | 1416+17.99 | 937.75 | 1416+17.99 | 937.77 | 1416+17.99 | 937.96 | 1416+17.99 | 938.04 | 1416+17.99 | 938.15 | 1416+17.99 | 938.20 |
| 0.70L | 1416+30.98 | 937.76 | 1416+30.98 | 937.78 | 1416+30.98 | 937.97 | 1416+30.98 | 938.05 | 1416+30.98 | 938.16 | 1416+30.98 | 938.21 |
| 0.80L | 1416+43.97 | 937.76 | 1416+43.97 | 937.78 | 1416+43.97 | 937.97 | 1416+43.97 | 938.05 | 1416+43.97 | 938.16 | 1416+43.97 | 938.22 |
| 0.90L | 1416+56.96 | 937.76 | 1416+56.96 | 937.77 | 1416+56.96 | 937.96 | 1416+56.96 | 938.04 | 1416+56.96 | 938.16 | 1416+56.96 | 938.21 |
| CL BRG. F.A. | 1416+69.95 | 937.74 | 1416+69.95 | 937.76 | 1416+69.95 | 937.95 | 1416+69.95 | 938.03 | 1416+69.95 | 938.14 | 1416+69.95 | 938.20 |


| FINAL DECK SURFACE ELEVATIONS (NORTHBOUND) CONT. | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| LOCATION | PHASE 4B C.J. | | G11 | | CROWN | | G12 | | G13 | | TOE OF RIGHT PARAPET | |
| | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. | STATION | ELEV. |
| CL BRG. R.A. | 1415+40.04 | 938.04 | 1415+40.04 | 938.12 | 1415+40.04 | 938.15 | 1415+40.04 | 938.02 | 1415+40.04 | 937.83 | 1415+40.04 | 937.81 |
| 0.10L | 1415+53.03 | 938.10 | 1415+53.03 | 938.17 | 1415+53.03 | 938.21 | 1415+53.03 | 938.08 | 1415+53.03 | 937.88 | 1415+53.03 | 937.87 |
| 0.20L | 1415+66.02 | 938.15 | 1415+66.02 | 938.22 | 1415+66.02 | 938.26 | 1415+66.02 | 938.13 | 1415+66.02 | 937.93 | 1415+66.02 | 937.92 |
| 0.30L | 1415+79.01 | 938.19 | 1415+79.01 | 938.26 | 1415+79.01 | 938.30 | 1415+79.01 | 938.17 | 1415+79.01 | 937.98 | 1415+79.01 | 937.96 |
| 0.40L | 1415+92.00 | 938.22 | 1415+92.00 | 938.30 | 1415+92.00 | 938.34 | 1415+92.00 | 938.20 | 1415+92.00 | 938.01 | 1415+92.00 | 937.99 |
| 0.50L | 1416+05.00 | 938.25 | 1416+05.00 | 938.32 | 1416+05.00 | 938.36 | 1416+05.00 | 938.23 | 1416+05.00 | 938.04 | 1416+05.00 | 938.02 |
| 0.60L | 1416+17.99 | 938.27 | 1416+17.99 | 938.34 | 1416+17.99 | 938.38 | 1416+17.99 | 938.24 | 1416+17.99 | 938.05 | 1416+17.99 | 938.04 |
| 0.70L | 1416+30.98 | 938.28 | 1416+30.98 | 938.35 | 1416+30.98 | 938.39 | 1416+30.98 | 938.25 | 1416+30.98 | 938.06 | 1416+30.98 | 938.05 |
| 0.80L | 1416+43.97 | 938.28 | 1416+43.97 | 938.35 | 1416+43.97 | 938.39 | 1416+43.97 | 938.26 | 1416+43.97 | 938.06 | 1416+43.97 | 938.05 |
| 0.90L | 1416+56.96 | 938.27 | 1416+56.96 | 938.35 | 1416+56.96 | 938.38 | 1416+56.96 | 938.25 | 1416+56.96 | 938.06 | 1416+56.96 | 938.04 |
| CL BRG. F.A. | 1416+69.95 | 938.26 | 1416+69.95 | 938.33 | 1416+69.95 | 938.37 | 1416+69.95 | 938.24 | 1416+69.95 | 938.04 | 1416+69.95 | 938.03 |

FINAL DECK SURFACE ELEVATION TABLES
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN TBD
DESIGN AGENCY Jacobs
DESIGNER DBL | CHECKER FM
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 51 | TOTAL 64
SHEET P. 536 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:33:43 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SS010.dgn




***BRIDGE RAILING PLAN***

HORIZONTAL SCALE IN FEET
0 ---NA--- ---NA---
---NA---


# BRIDGE PARAPET PLAN
## BRIDGE NO. FRA-00071-26.460 L/R
## I-71 OVER SR 161

DESIGN AGENCY
Jacobs

| | |
|---|---|
| DESIGNER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET / TOTAL | 52 / 64 |
| SHEET / TOTAL | P. 537 / 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:34:23 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SA001.dgn




***TYPICAL EXTERIOR BRIDGE RAILING ELEVATION***


*(SBR-1-20)*





***TYPICAL MEDIAN BRIDGE RAILING ELEVATION***

*(SBR-2-20)*


| PARAPET STIFFENING G.F.R.P. REINFORCEMENT | | | |
|---|---|---|---|
| BAR MARK | NUMBER | LENGTH | TYPE |
| R401 | 220 | 30'-0" | ST |
| R402 | 44 | 7'-0" | ST |
| R403 | 16 | 10'-11" | ST |
| R404 | 104 | 10'-0" | ST |
| R405 | 16 | 11'-4" | ST |
| R406 | 104 | 10'-5" | ST |





***DETAIL 1***




***SECTION A-A***




***DETAIL 2***




***SECTION B-B***

***NOTES:***


1. *FOR APPROACH SLAB RAILING DETAILS SEE SHEET 56.*

BRIDGE PARAPET DETAILS
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161


SFN TBD
DESIGN AGENCY Jacobs
DESIGNER FM | CHECKER ZF
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 53 | TOTAL 64
SHEET P. 538 | TOTAL 618

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:34:35 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19101-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SA002.dgn




## APPROACH SLAB PLAN (RIGHT BRIDGE NORTHBOUND)




### TYPE 4-C CURB DETAIL (TYP.)




### TYPICAL SLEEPER SLAB SECTION

| SLEEPER SLAB SURFACE ELEVATION AT TOP OF ROADWAY | | | |
|---|---|---|---|
| 1 | 937.35 | 13 | 937.68 |
| 2 | 937.63 | 14 | 937.96 |
| 3 | 937.80 | 15 | 938.13 |
| 4 | 937.87 | 16 | 938.19 |
| 5 | 937.98 | 17 | 938.31 |
| 6 | 937.63 | 18 | 937.96 |

| SLEEPER SLAB SURFACE ELEVATION UNDER APPROACH SLAB | | | |
|---|---|---|---|
| 7 | 937.39 | 19 | 937.70 |
| 8 | 937.67 | 20 | 937.98 |
| 9 | 937.84 | 21 | 938.15 |
| 10 | 937.90 | 22 | 938.21 |
| 11 | 938.01 | 23 | 938.32 |
| 12 | 937.67 | 24 | 937.98 |

**NOTES:**

1. FOR ADDITIONAL APPROACH SLAB DETAILS, SEE ODOT STANDARD DRAWINGS AS-1-15 AND AS-2-15 TYPE C INSTALLATION.
2. FOR BRIDGE RAILING DETAILS, SEE SHEETS 52 THRU 53.
3. FOR ADDITIONAL BRIDGE RAILING TRANSITION DETAILS, SEE ODOT STANDARD DRAWING SBR-1-20 AND SICD-1-21.
4. THE APPROACH SLAB SHALL BE PAID FOR WITH ITEM 526 - REINFORCED CONCRETE APPROACH SLABS WITH QA/QC (T=17").
5. FOR INTEGRAL CURB TYPE 4C DETAILS, SEE ODOT STANDARD DRAWING BP-5.1. THE INTEGRAL CURB TYPE 4C SHALL BE PAID FOR WITH ITEM 526 - TYPE C INSTALLATION.
6. THE SLEEPER SLAB SHALL BE PAID FOR WITH ITEM 526 - TYPE C INSTALLATION.

HORIZONTAL SCALE IN FEET
0 ---NA--- ---NA---
---NA--- ---NA---


# APPROACH SLAB DETAILS - RIGHT BRIDGE
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER SR 161


DESIGN AGENCY
Jacobs

DESIGNER FM
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 54 TOTAL 64
SHEET P. 539 TOTAL 618


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:34:47 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SM002.dgn
Asad.Nawaz@jacobs.com





**APPROACH SLAB PLAN (LEFT BRIDGE SOUTHBOUND)**




**TYPE 4-C CURB DETIL (TYP.)**




**TYPICAL SLEEPER SLAB SECTION**

***NOTES:***

1. FOR ADDITIONAL APPROACH SLAB DETAILS, SEE ODOT STANDARD DRAWINGS AS-1-15 AND AS-2-15 TYPE C INSTALLATION.
2. FOR BRIDGE RAILING DETAILS, SEE SHEETS 52 THRU 53.
3. FOR ADDITIONAL BRIDGE RAILING TRANSITION DETAILS, SEE ODOT STANDARD DRAWING SBR-1-20 AND SICD-1-21.
4. THE APPROACH SLAB SHALL BE PAID FOR WITH ITEM 526 - REINFORCED CONCRETE APPROACH SLABS WITH QA/QC (T=17").
5. FOR INTEGRAL CURB TYPE 4C DETAILS, SEE ODOT STANDARD DRAWING BP-5.1. THE INTEGRAL CURB TYPE 4C SHALL BE PAID FOR WITH ITEM 526 - TYPE C INSTALLATION.
6. THE SLEEPER SLAB SHALL BE PAID FOR WITH ITEM 526 - TYPE C INSTALLATION.

HORIZONTAL SCALE IN FEET
0 ---NA--- ---NA---
---NA--- ---NA---

# APPROACH SLAB DETAILS - LEFT BRIDGE
# BRIDGE NO. FRA-00071-24.460 L/R
# I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| FM | ZF |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 55 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 540 | 618 |


FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:35:01 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SM001.dgn





***TYPICAL EXTERIOR APPROACH RAILING ELEVATION***

*(SBR-1-20)*





***TYPICAL MEDIAN APPROACH RAILING ELEVATION***

*(SBR-2-20)*




***SECTION C-C***




***SECTION D-D***

| PARAPET STIFFENING G.F.R.P. REINFORCEMENT | | | |
|---|---|---|---|
| BAR MARK | NUMBER | LENGTH | TYPE |
| R407 | 44 | 29'-10" | ST |
| R408 | 32 | 15'-3" | ST |
| R409 | 44 | 17'-3" | ST |
| R410 | 16 | 16'-2" | ST |

***NOTES:***

1. *FOR BRIDGE RAILING DETAILS SEE SHEETS 52 THRU 53.*

APPROACH PARAPET DETAILS
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN
TBD

DESIGN AGENCY
Jacobs

| DESIGNER | CHECKER |
|---|---|
| FM | ZF |

REVIEWER
MJR 03/13/26

PROJECT ID
109164

| SUBSET | TOTAL |
|---|---|
| 56 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 541 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:35:13 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_SA003.dgn

**STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS**

REFER TO THE FOLLOWING SUPPLEMENTAL SPECIFICATION(S):

| | | |
|---|---|---|
| 800 | DATED | XX/YY/ZZZZ |
| 840 | DATED | 7/21/2023 |
| 878 | DATED | 01/21/2022 |

**DESIGN SPECIFICATIONS**

THIS STRUCTURE CONFORMS TO THE 9th EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2020 AND THE ODOT BRIDGE DESIGN MANUAL, 2020.

**DESIGN DATA**

CONCRETE CLASS QC1 (LEVELING PAD, COPING & GUTTER)
- COMPRESSIVE STRENGTH 4.0 KSI

CONCRETE REINFORCEMENT
EPOXY COATED STEEL REINFORCEMENT
- MINIMUM YIELD STRENGTH 60-KSI

**FOUNDATION BEARING RESISTANCE**

THE REINFORCED SOIL MASSES, AS DESIGNED PRODUCE MAXIMUM SERVICE LIMIT STATE BEARING PRESSURES [1], MAXIMUM STRENGTH LIMIT STATE BEARING PRESSURE [2] AND PROVIDE THE FACTORED BEARING RESISTANCE [3] AS DEPICTED BELOW FOR EACH WALL.

| FOUNDATION BEARING RESISTANCE | | | |
|---|---|---|---|
| MSE WALL NO. | SERVICE BEARING PRESSURE (KSF) [1] | FACTORED BEARING PRESSURE (KSF) [2] | FACTORED BEARING RESISTANCE (KSF) [3] |
| #1 | 5.95 | 4.31 | 9.10 |
| #2 | 5.33 | 3.86 | 5.70 |

**MSE WALL DESIGN PARAMETERS**

THE FOLLOWING TABLE LIST THE MINIMUM SOIL REINFORCEMENT LENGTHS FOR EACH WALL. THE SOIL REINFORCEMENT LENGTH IS A FUNCTION OF THE DESIGN WALL HEIGHT (H) AND WILL VARY ALONG THE LENGTH OF THE WALL.

| MSE WALL DESIGN PARAMETERS | |
|---|---|
| MSE WALL NO. | MINIMUM SOIL REINFORCEMENT LENGTH (FT.) |
| #1 | 0.70H |
| #2 | 0.90H |

**PROPRIETARY RETAINING WALL DATA**

THE PROPRIETARY WALL SUPPLIER SHALL DESIGN THE INTERNAL STABILITY OF A MECHANICALLY STABILIZED EARTH (MSE) WALL IN ACCORDANCE WITH ODOT SUPPLEMENTAL SPECIFICATION (SS) 840 TO SUPPORT THE ABUTMENT. THE DESIGN FOR INTERNAL STABILITY SHALL INCLUDE THE FOLLOWING NOMINAL (I.E. UNFACTORED) HORIZONTAL STRIP LOADS DUE TO FRICTION (FR) FROM THE SUPERSTRUCTURES LISTED IN THE FOLLOWING TABLE, APPLIED PERPENDICULAR TO THE FACE OF WALL AT THE BASE OF THE CONCRETE FOOTING. THIS STRIP LOAD DOES NOT INCLUDE EARTH PRESSURE LOADS FROM THE ABUTMENT BACKFILL OR LIVE LOAD SURCHARGE. HOWEVER, THE PROPRIETARY WALL SUPPLIER SHALL INCLUDE EARTH PRESSURE LOADS FROM THE ABUTMENT BACKFILL AND LIVE LOAD SURCHARGE IN THE DESIGN CALCULATIONS.

| BRIDGE SUPERSTRUCTURE LOADS (K/FT.) | | |
|---|---|---|
| MSE WALL NO. | BRIDGE NO. | FRICTION LOAD (FR) |
| #1 | FRA-71-26.46 L/R | 4.70 |
| #2 | FRA-71-26.46 L/R | 4.70 |

**ITEM 511 - CONCRETE MISC.: CLASS QC1 CONCRETE, GUTTER**

THIS ITEM INCLUDES ALL LABOR, MATERIAL, TOOLS, EQUIPMENT AND INCIDENTALS TO CONSTRUCT A CAST-IN-PLACE CONCRETE GUTTER ATOP THE MSE WALL COPING AS DETAILED WITHIN THE PLANS.

**ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN**

EXCAVATION NECESSARY TO CONSTRUCT THE MSE WALL AND/OR PROPOSED BRIDGE ABUTMENT NOT SEPARATELY INCLUDED WITH ITEM 840 - WALL EXCAVATION SHALL BE INCLUDED WITH THE LUMP SUM BID PRICE FOR ITEM 503, UNCLASSIFIED EXCAVATION, AS PER PLAN, FOR PAYMENT. PLAN DETAILS DEPICT ANTICIPATED EXCAVATION; HOWEVER THE CONTRACTOR SHALL DETERMINE THE FINAL QUANTITIES BASED UPON FIELD MEASUREMENTS.

THE FOLLOWING ESTIMATED EXCAVATION QUANTITY IS PROVIDED FOR REFERENCE ONLY AND ARE BASED UPON AN ASSUMED MAXIMUM CUT SLOPE OF 1.5H:1V.

| ESTIMATED - ITEM 203 EXCAVATION | |
|---|---|
| MSE WALL NO. | EXCAVATION (CY.) |
| #1 | X.XX |
| #2 | X.XX |


ALL EXCAVATION AND SUBSEQUENT BACKFILL BELOW THE EXISTING GROUND SHALL BE PERFORMED PER THE APPLICABLE SECTIONS OF C&MS 203 AND 503. SUITABLE SITE SOILS DISPLACED DURING WALL EXCAVATION MAY BE REUSED AS EMBANKMENT MATERIAL WITHIN THE LIMITS SHOWN WITHIN THESE PLANS. THE SUITABILITY OF ALL SITE SOILS INTENDED FOR REUSE SHALL BE APPROVED BY AN ON-SITE GEOTECHNICAL ENGINEER LICENSED IN THE STATE OF OHIO PRIOR TO PLACEMENT AND SOILS SHALL CONFORM TO BACKFILL REQUIREMENTS OF C&MS 203.

**AESTHETIC SURFACE TREATMENT**

ALL PROVISIONS OF ODOT SUPPLEMENTAL SPECIFICATION 840 APPLY IN ADDITION TO THOSE LISTED HEREIN.


THE RELIEF OF AESTHETIC PATTERN FORMLINER SHALL NOT EXCEED A MAXIMUM RELIEF OF 1.0 INCHES. THE MINIMUM RELIEF OF THE AESTHETIC PATTERN FORMLINER IS 1.0 INCHES. AESTHETIC TREATMENT SHALL UTILIZE AN ASHLAR BLOCK FORMLINER PATTERN OR APPROVED EQUAL. SEAL ALL CONCRETE SURFACES WITH A LIGHT-NEUTRAL EPOXY-URETHANE SEALER (FEDERAL COLOR 17778).

THE AESTHETIC TREATMENT MUST BE SUBMITTED TO THE DEPARTMENT FOR APPROVAL




**LIMITS OF MSE WALL EARTHWORK**

**AESTHETIC SURFACE TREATMENT**




A - SECTION

**LEGEND:**

- ITEM 203 - EMBANKMENT
- ITEM 503 - UNCLASSIFIED EXCAVATION, AS PER PLAN
- ITEM 840 - WALL EXCAVATION
- ITEM 840 - SELECT GRANULAR BACKFILL

**ESTIMATED QUANTITIES - MSE WALLS**

| CALC. | DATE | CHK'D | DATE |
|---|---|---|---|
| XXX | XX/YY/ZZ | XXX | XX/YY/ZZ |

| ITEM | ITEM EXT. | MSE WALL #1 | MSE WALL #2 | TOTAL | UNIT | DESCRIPTION | SHEET REF. |
|---|---|---|---|---|---|---|---|
| 203 | 20000 | | | | CY | EMBANKMENT | |
| 203 | 35120 | | | | CY | GRANULAR MATERIAL, TYPE C | |
| | | | | | | | |
| 503 | 21301 | | | | LS | UNCLASSIFIED EXCAVATION, AS PER PLAN | XX |
| | | | | | | | |
| 509 | 10000 | | | | LB | EPOXY COATED STEEL REINFORCEMENT | |
| 510 | 10000 | | | | EA | DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT | |
| 511 | 71100 | | | | CY | CONCRETE, MISC.: CLASS QC1 CONCRETE, GUTTER | XX |
| 512 | 10100 | | | | SY | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) | |
| 516 | 13600 | | | | SF | 1" PREFORMED EXPANSION JOINT FILLER | |
| | | | | | | | |
| 840 | 20000 | | | | SF | MECHANICALLY STABILIZED EARTH WALL | |
| 840 | 21000 | | | | CY | WALL EXCAVATION | |
| 840 | 22000 | | | | SY | FOUNDATION PREPARATION | |
| 840 | 23000 | | | | CY | SELECT GRANULAR BACKFILL | |
| 840 | 25010 | | | | FT | 6" DRAINAGE PIPE, PERFORATED | |
| 840 | 25020 | | | | FT | 6" DRAINAGE PIPE, NON-PERFORATED | |
| 840 | 26000 | | | | FT | CONCRETE COPING | |
| 840 | 26050 | | | | SF | AESTHETIC SURFACE TREATMENT | XX |
| 840 | 27000 | | | | DAY | ON-SITE ASSISTANCE | |
| 840 | 28000 | | | | LS | SGB INSPECTION AND COMPACTION TESTING | |
| | | | | | | | |
| SPECIAL | 530000400 | | | | EA | STRUCTURES: SETTLEMENT PLATFORMS | XX |

MSE WALL NOTES AND QUANTITIES
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN TBD

DESIGN AGENCY Jacobs

| DESIGNER | CHECKER |
|---|---|
| ZF | FM |

REVIEWER MJR 03/13/26


PROJECT ID 109164

| SUBSET | TOTAL |
|---|---|
| 57 | 64 |

| SHEET | TOTAL |
|---|---|
| P. 542 | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:35:27 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN010.dgn




***MSE WALL #1 PLAN***

| MSE WALL #1 CRITICAL POINT DATA | | | | |
|---|---|---|---|---|
| CONTROL POINT NO. | MSE WALL STATION | CL CONST. I-71 STA. | CL CONST. I-71 OFFSET | TOP OF WALL ELEVATION |
| 1 | 1+00.00 | 1415+24.07 | 111.88' RT. | 919.00 |
| 2 | 1+30.00 | 1415+45.29 | 90.67' RT. | 928.00 |
| 3 | 3+25.92 | 1415+45.29 | 105.25' LT | 928.00 |
| 4 | 3+50.92 | 1415+27.61 | 122.93' LT. | 920.00 |


| MSE WALL #1 INFORMATION | | | |
|---|---|---|---|
| LOCATION | BORING NO. | MAX. WALL DESIGN HEIGHT (FT) | REINFORCING LENGTH |
| R.A. | B-046-0-22 | 26.0 | 0.7H |

***LEGEND:***

*Δ - SEALING OF CONCRETE SURFACES (EPOXY URETHANE): SEALING EXTERIOR SURFACES OF ALL PANELS AND COPING*
*ΔΔ - 3'-0" MIN.*
*C.P. - CRITICAL POINT*

***NOTES:***

*1. FOR ADDITIONAL MSE WALL DETAILS, SEE SHEET 60.*





***PROFILE ALONG BACK FACE OF MSE WALL #1***

REAR ABUTMENT MSE WALL PLAN AND ELEVATION
BRIDGE NO. FRA-00071-26.460 L/R
I-71 OVER SR 161

SFN TBD
DESIGN AGENCY Jacobs
DESIGNER ZF | CHECKER FM
REVIEWER MJR 03/13/26
PROJECT ID 109164
SUBSET 58 | TOTAL 64
SHEET P. 543 | TOTAL 618

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:35:42 PM PLTDRV: OHDOT_PDF_F+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_WD001.dgn




## MSE WALL #2 PLAN

| MSE WALL #2 CRITICAL POINT DATA | | | | |
|---|---|---|---|---|
| CONTROL POINT NO. | MSE WALL STATION | CL CONST. I-71 STA. | CL CONST. I-71 OFFSET | TOP OF WALL ELEVATION |
| 1 | 1+00.00 | 1416+86.63 | 127.17' LT. | 918.50 |
| 2 | 1+31.00 | 1416+64.70 | 105.25' LT. | 928.25 |
| 3 | 3+27.00 | 1416+64.70 | 90.75' RT. | 928.25 |
| 4 | 3+58.00 | 1416+86.63 | 112.67' RT. | 918.50 |


| MSE WALL #2 INFORMATION | | | |
|---|---|---|---|
| LOCATION | BORING NO. | MAX. WALL DESIGN HEIGHT (FT) | REINFORCING LENGTH |
| F.A | B-048-0-22 | 26.0 | 0.9H |

**LEGEND:**

Δ - SEALING OF CONCRETE SURFACES (EPOXY URETHANE): SEALING EXTERIOR SURFACES OF ALL PANELS AND COPING
ΔΔ - 3'-0" MIN.
C.P. - CRITICAL POINT

**NOTES:**

1. FOR ADDITIONAL MSE WALL DETAILS, SEE SHEET 60.





## PROFILE ALONG BACK FACE OF MSE WALL #2

FRA-71-19.10


MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 12:36:02 PM PLTDRV: OHDOT_PDF_E+.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Nawaz@jacobs.com WORKSPACE: OHDOTCEv02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_WD002.dgn

# FORWARD ABUTMENT MSE WALL PLAN AND ELEVATION
## BRIDGE NO. FRA-00071-26.460 L/R
## I-71 OVER SR 161


| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ZF |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 59 |
| TOTAL | 64 |
| SHEET | P. 544 |
| TOTAL | 618 |




**TYPICAL MSE WALL SECTION UNDER BRIDGE**




**COPING EXPANSION DETAIL**
(NOT TO SCALE)




**TYPICAL MSE WALL SECTION ALONG WINGWALL**


**LEGEND:**

\+ = LIMITS OF SEALING OF CONCRETE SURFACE (EPOXY-URETHANE)


ELEV. A = 925.70 FOR REAR ABUTMENT
= 925.90 FOR FORWARD ABUTMENT

**NOTES:**


1. FOR MSE WALL PLAN, ELEVATION AND MSE WALL DATA, SEE SHEETS 58 THRU 59.





**CONCRETE SEALING DETAIL AT ABUTMENT AND WINGWALL**





**CONCRETE SEALING DETAIL AT END OF MSE WALL**




**TYPICAL MSE WALL SECTION AT END OF WINGWALL**




**MSE WALL COPING DETAIL**
(NOT TO SCALE)




**TYPICAL MSE WALL SECTION AT END OF MSE WALL**

# MSE WALL DETAILS
## BRIDGE NO. FRA-00071-26.460 L/R
## I-71 OVER SR 161

| | |
|---|---|
| SFN | TBD |
| DESIGN AGENCY | Jacobs |
| DESIGNER | ZF |
| CHECKER | FM |
| REVIEWER | MJR 03/13/26 |
| PROJECT ID | 109164 |
| SUBSET | 60 |
| TOTAL | 64 |
| SHEET | P. 545 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 3/31/2026 TIME: 2:59:22 PM PLTDRV: OHDOT_PDF.pltcfg PENTBL: OHDOT_Pen.tbl USER: Asad.Navaz@jacobs.com WORKSPACE: OHDOTCfx02 WORKSET: 109164 PRODUCT: OpenRoadsDesigner 24.00.02.25
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-19.10 I-71 HSR\30 WIP\109164\400-Engineering\Structures\SFN_2508257\Sheets\109164_SFN_2508257_WD003.dgn

| NUMBERS | | | | LENGTH | WEIGHT | TYPE | DIMENSIONS | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MARK | SOUTHBOUND | NORTHBOUND | TOTAL | | | | A | B | C | D | E | R | INC |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | TO BE COMPLETED WITH STAGE 3 | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | |

| NUMBERS | | | | LENGTH | WEIGHT | TYPE | DIMENSIONS | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MARK | SOUTHBOUND | NORTHBOUND | TOTAL | | | | A | B | C | D | E | R | INC |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | |

| NUMBERS | | | | LENGTH | WEIGHT | TYPE | DIMENSIONS | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MARK | SOUTHBOUND | NORTHBOUND | TOTAL | | | | A | B | C | D | E | R | INC |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | |

| NUMBERS | | | | LENGTH | WEIGHT | TYPE | DIMENSIONS | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| MARK | SOUTHBOUND | NORTHBOUND | TOTAL | | | | A | B | C | D | E | R | INC |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | |

## PROJECT DESCRIPTION

FRA-071-19.10 PROJECT (PID 109164) IS ALONG THE IR-71 CORRIDOR BETWEEN 5TH AVE AND SR 161 IN FRANKLIN COUNTY, OHIO. THE OVERALL PROJECT OBJECTIVE IS TO ALLEVIATE CONGESTION, IMPROVE SAFETY, AND IMPROVE TRAFFIC INCIDENT MANAGEMENT, REPLACEMENT OF THE EXISTING BRIDGES CARRYING IR 71 OVER MORSE ROAD AND SR 161.

## HISTORIC RECORDS

THE FOLLOWING REPORT/PLANS WERE AVAILABLE FOR REVIEW AND EVALUATION FOR THIS REPORT:

- STRUCTURE FOUNDATION EXPLORATION SHEETS AND BORING LOGS FOR THE BRIDGE PROJECT FRA-1 OVER SR 161 DESIGN SECTION D-12 DATED SEPTEMBER 12, 1957.
- SOIL PROFILE SHEETS AND BORING LOGS FOR THE SOIL PROFILE INVESTIGATION PROJECT FRA-1-25.30 DATED JUNE 17, 1958.
- SOIL PROFILE SHEETS AND BORING LOGS FOR THE SOIL PROFILE INVESTIGATION PROJECT FRA-3-20.49 DATED APRIL 7, 1958.
- SOIL PROFILE SHEETS AND BORING LOGS FOR THE SOIL PROFILE INVESTIGATION PROJECT FRA-3-18.31 DATED JANUARY 2, 1958.

HISTORICAL SOIL BORINGS ASSOCIATED WITH THE ABOVE PLANS WERE REVIEWED. SEVEN HISTORICAL BORINGS DRILLED AT THE SITE OF BRIDGE OVER SR 161 IN 1957 WERE UTILIZED DURING THE CURRENT DESIGN.

## GEOLOGY

THE PROJECT SITE IS LOCATED WITHIN THE COLUMBUS LOWLAND TILL PLAINS, A SUBDIVISION OF THE SOUTHERN OHIO LOAMY TILL PLAIN. THIS IS A MODERATELY LOW RELIEF (25 FT) LOWLAND SURROUNDED IN ALL DIRECTIONS BY RELATIVE UPLANDS, HAVING A BROAD REGIONAL SLOPE TOWARD THE SCIOTO VALLEY, CONTAINING MANY LARGER STREAMS. ELEVATIONS OF THE REGION RANGE FROM 600 TO 850 FT ABOVE MEAN SEA LEVEL (AMSL) (950 FT AMSL NEAR POWELL MORAINE). THE GEOLOGY WITHIN THIS REGION IS DESCRIBED AS WISCONSINAN-AGE TILL THAT IS HIGH LIME IN THE WEST TO MEDIUM-LIME IN THE EAST. THE GEOLOGY IS ALSO DESCRIBED AS CONTAINING EXTENSIVE OUTWASH IN SCIOTO VALLEY OVERLYING DEEP DEVONIAN- TO MISSISSIPPIAN-AGE CARBONATE ROCKS, SHALES, AND SILTSTONES.

## RECONNAISSANCE

A FIELD RECONNAISSANCE VISIT FOR THE OVERALL PROJECT AREA WAS CONDUCTED ON AUGUST 11, 2022, ALONG IR-71 BETWEEN E 11TH AVE. AND E DUBLIN GRANVILLE RD. THE LAND USE OF MOST OF THE PROJECT AREA CONSISTS OF COMMERCIAL PROPERTIES, INDUSTRIAL PROPERTIES, AND RESIDENTIAL PROPERTIES. IN GENERAL, THE PAVEMENT CONDITION OF THIS SECTION OF IR-71 WAS OBSERVED TO BE FAIR TO GOOD WITH SOME SIGNS OF WEATHERING AND SURFACE WEAR. MODERATE SEVERITY LONGITUDINAL AND TRANSVERSE CRACKING WAS COMMON ALONG THIS SECTION, AS WELL AS MODERATE SEVERITY PATCHING AND CRACK SEALING DEFICIENCIES. THE PROJECT AREA STARTS OUT IN A CUT BELOW THE SURROUNDING LAND NEAR E 11TH AVE. THEN TRANSITIONS TO EMBANKMENTS ABOVE THE SURROUNDING LAND NEAR E 17TH AVE., AFTER WHICH IR-71 TRANSITIONS TO BE ROUGHLY LEVEL WITH THE SURROUNDING LAND. THE ROADWAY IN THE PROJECT AREA DRAINS TO A DRAINAGE DITCH OFF THE OUTSIDE SHOULDERS OF THE ROADWAY, AS WELL AS DRAINAGE BASINS IN THE MEDIAN. THE EMBANKMENT APPEARED TO BE LIGHTLY TO HEAVILY VEGETATED, AND SIGNS OF STANDING WATER SUCH AS THE AFOREMENTIONED HEAVY VEGETATION WERE OBSERVED. NO SIGNS OF ISSUES DUE TO GEOTECHNICAL CONDITIONS WERE OBSERVED.

## SUBSURFACE EXPLORATION

THE SUBSURFACE EXPLORATION WAS CONDUCTED BETWEEN AUGUST 15, 2022, AND SEPTEMBER 20, 2022, WHICH INCLUDED 48 BORINGS DRILLED TO DEPTHS RANGING BETWEEN 7.5 FT TO 91.5 FT BELOW GROUND SURFACE. BORINGS WERE DRILLED USING A CME 75T AND CME 45B TRUCK-MOUNTED DRILLING RIGS UTILIZING 3.25-INCH (INNER DIAMETER) HOLLOW STEM AUGERS. STRUCTURAL BORING SAMPLES WERE GENERALLY RECOVERED USING A SPLIT SPOON SAMPLER (AASHTO T-206 "STANDARD METHOD FOR PENETRATION TEST AND SPLIT BARREL SAMPLING OF SOILS.") AT 2.5-FT TO 5.0-FT INTERVALS, WHILE SUBGRADE BORING SAMPLES WERE RECOVERED CONTINUOUSLY FOR SUBGRADE EVALUATION PURPOSES. STANDARD PENETRATION TESTS (SPT) WERE CONDUCTED USING A CME AUTO HAMMER THAT HAS BEEN CALIBRATED ON JANUARY 24, 2022, TO BE 79 % AND 72.6 % EFFICIENT, RESPECTIVELY.

## EXPLORATION FINDINGS


THE SUBGRADE CONDITIONS IN THE PROJECT AREA ARE RELATIVELY CONSISTENT AND ARE GENERALLY COMPRISED OF FIFTEEN- TO TWENTY-THREE-INCH-THICK EXISTING PAVEMENT SECTIONS (ASPHALT, CONCRETE, AND GRANULAR BASE) UNDERLAIN BY PRIMARILY COHESIVE FINE-GRAINED SOILS WITH MINOR NON-COHESIVE COARSE-GRAINED SOILS. THE SOILS ENCOUNTERED WITHIN THE PROJECT LIMITS ARE GENERALLY CLASSIFIED AS NON-COHESIVE A-1-a, A-1-b, A-2-4 AND A-4a OR COHESIVE A-4a, A-6a, A-6b AND A-7-6 SOILS ACCORDING TO THE ODOT SOIL CLASSIFICATION SYSTEM.

ALONG THE SOUTHBOUND (SB) OF IR-71, EIGHTY-FOUR PERCENT (84%) OF THE SAMPLES TAKEN ALONG IR-71 WERE CLASSIFIED AS COHESIVE FINE-GRAINED SOILS AND WERE COMPRISED OF: 1) SANDY SILT (A-4a, 46% OF THE SAMPLES); 2) SILT AND CLAY (A-6a, 22% OF THE SAMPLES); 3) SILTY CLAY (A-6b, 8% OF THE SAMPLES); 4) CLAY (A-7-6, 7% OF THE SAMPLES); AND 5) SILT (A-4b, 1% OF THE SAMPLES). IN TERMS OF CONSISTENCY OF THE COHESIVE SOILS, THE DESCRIPTION VARIES FROM VERY STIFF TO HARD CORRELATING TO CONVERTED SPT-N VALUES ($N_{60}$) RANGING FROM 4 BLOWS PER FOOT (BPF) TO REFUSAL. NATURAL MOISTURE CONTENTS RANGED FROM 1 TO 27 PERCENT. BASED ON ATTERBERG LIMITS TEST PERFORMED ON REPRESENTATIVE SAMPLES OF THE COHESIVE SOILS, THE LIQUID AND PLASTIC LIMIT WERE ESTIMATED TO RANGE FROM 18 TO 52 PERCENT AND FROM 12 TO 23 PERCENT, RESPECTIVELY. SIXTEEN PERCENT (16%) OF THE SAMPLES TAKEN ALONG THE IR-71 WERE CLASSIFIED AS NON-COHESIVE COARSE-GRAINED SOILS AND WERE COMPRISED OF: COMPRISED OF 1) GRAVEL AND/OR STONE FRAGMENTS (A-1-a, 2% OF THE SAMPLES); 2) GRAVEL WITH SAND (A-1-b, 7% OF THE SAMPLES); AND 3) GRAVEL WITH SAND AND SILT (A-2-4, 7% OF THE SAMPLES). WITH RESPECT TO THE RELATIVE DENSITY OF THE NON-COHESIVE GRANULAR SOILS, THE MATERIAL DESCRIPTION VARIES FROM LOOSE TO DENSE CORRELATING TO $N_{60}$VALUES RANGING FROM 4 TO 45 BPF. NATURAL MOISTURE CONTENTS OF GRANULAR SOILS RANGED FROM 4 TO 16 PERCENT.

## LEGEND

| | DESCRIPTION | ODOT CLASS | CLASSIFIED MECH./VISUAL | |
|---|---|---|---|---|
| | GRAVEL AND/OR STONE FRAGMENTS | A-1-a | 2 | 3 |
| | GRAVEL AND/OR STONE FRAGMENTS WITH SAND | A-1-b | 9 | 19 |
| | GRAVEL AND/OR STONE FRAGMENTS WITH SAND & SILT | A-2-4 | 10 | 15 |
| | GRAVEL/STONE FRAGMENTS WITH SAND, SILT & CLAY | A-2-6 | 2 | 1 |
| | COARSE AND FINE SAND | A-3a | 0 | 5 |
| | SANDY SILT | A-4a | 81 | 240 |
| | SILT | A-4b | 3 | 0 |
| | SILT AND CLAY | A-6a | 31 | 35 |
| | SILTY CLAY | A-6b | 18 | 18 |
| | CLAY | A-7-6 | 21 | 18 |
| | | TOTAL | 177 | 356 |
| | ROCK | VISUAL | | |
| | PAVEMENT OR BASE = X = APPROXIMATE THICKNESS | VISUAL | | |
| | SOD AND TOPSOIL = X = APPROXIMATE THICKNESS | VISUAL | | |
| | BORING LOCATION - PLAN VIEW. | | | |
| | HISTORICAL BORING LOCATION - PLAN VIEW. | | | |
| | DRIVE SAMPLE AND/OR ROCK CORE BORING PLOTTED TO VERTICAL SCALE ONLY. HORIZONTAL BAR INDICATES A CHANGE IN STRATIGRAPHY. | | | |
| WC | INDICATES WATER CONTENT IN PERCENT. | | | |
| $N_{60}$ | INDICATES STANDARD PENETRATION RESISTANCE NORMALIZED TO 60% DRILL ROD ENERGY RATIO. | | | |
| X/Y/D" | NUMBER OF BLOWS FOR STANDARD PENETRATION TEST (SPT): X= NUMBER OF BLOWS FOR FIRST 6 INCHES. Y= NUMBER OF BLOWS (UNCORRECTED) FOR SECOND D INCHES OF PENETRATION AT REFUSAL. | | | |
| W | INDICATES FREE WATER ELEVATION. | | | |
| | INDICATES STATIC WATER ELEVATION. | | | |
| SS | INDICATES A SPLIT SPOON SAMPLE. | | | |
| NP | INDICATES A NON-PLASTIC SAMPLE. | | | |

**RECON. -** EB 08/11/22
**DRILLING -** JH 08/15/22 - 09/20/22
**DRAWN -** ZM 07/31/23 - 08/28/23
**REVIEWED -** CH 08/28/23




LOCATION MAP

SCALE IN MILES

0 1 2 3 4

## PARTICLE SIZE DEFINITIONS

| 12" | 3" | 2.0 mm | 0.42 mm | 0.074 mm | 0.005 mm |
|---|---|---|---|---|---|
| BOULDERS | COBBLES | GRAVEL | COARSE SAND | FINE SAND | SILT | CLAY |

### INDEX OF SHEETS

EXPLORATION NOTES (CONT.), SHEET 2.

SUMMARY OF SOIL TEST DATA, SHEET 3.

| LOCATION FROM STA. | LOCATION TO STA. | PLAN | PROFILE | CROSS SECTION | STRUCTURE INCLUDED BRIDGE NO. | STRUCTURE INCLUDED SFN |
|---|---|---|---|---|---|---|
| IR 71 | | | | | | |
| 1048+00 | 1060+50 | 4 - 5 | 4- 5 | - | | |
| 1060+50 | 1073+00 | 6 - 7 | 6 - 7 | - | | |
| 1073+00 | 1085+50 | 8 - 9 | 8 - 9 | - | | |
| 1085+50 | 1098+00 | 10 - 11 | 10 - 11 | - | | |
| 1098+00 | 1110+50 | 12 - 13 | 12 - 13 | - | | |
| 1110+50 | 1123+00 | 14 - 15 | 14 - 15 | - | | |
| 1123+00 | 1135+50 | 16 - 17 | 16 - 17 | - | | |
| 1148+00 | 1160+50 | 18 - 19 | 18 - 19 | - | | |
| 1160+50 | 1173+00 | 20 - 21 | 20 - 21 | - | | |
| 1185+50 | 1198+00 | 22 - 23 | 22 - 23 | - | | |
| 1198+00 | 1210+50 | 24 - 25 | 24 - 25 | - | | |
| 1210+50 | 1223+00 | 26 - 27 | 26 - 27 | - | | |
| 1310+50 | 1315+50 | 28 | 29 | - | FRA-71-24.46 | 2508192 L & 2508222 R |
| 1413+50 | 1418+50 | 30 | 31 | - | FRA-71-26.46 | 2508257 |

BORING LOGS, SHEETS 32 - 69.

GEOTECHNICAL PROFILE - ROADWAY

DESIGN AGENCY: NEAS

DESIGNER: ZM

REVIEWER: CH 08-28-23

PROJECT ID: 109164

SUBSET 1 | TOTAL 69

SHEET P.550 | TOTAL 618

FRA-71-19.10

MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:54:57 PM USER: zil
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IC001.dgn

## EXPLORATION FINDINGS, CONTINUED

ALONG THE NORTHBOUND (NB) OF IR-71, EIGHTY-FOUR PERCENT (84%) OF THE SAMPLES TAKEN ALONG IR-71 WERE CLASSIFIED AS COHESIVE FINE-GRAINED SOILS AND WERE COMPRISED OF: 1) SANDY SILT (A-4a, 45% OF THE SAMPLES); 2) SILT AND CLAY (A-6a, 23% OF THE SAMPLES); 3) SILTY CLAY (A-6b, 8% OF THE SAMPLES); 4) CLAY (A-7-6, 7% OF THE SAMPLES); AND 5) SILT (A-4b, 1% OF THE SAMPLES). IN TERMS OF CONSISTENCY OF THE COHESIVE SOILS, THE DESCRIPTION VARIES FROM VERY STIFF TO HARD CORRELATING TO CONVERTED SPT-N VALUES ($N_{60}$) RANGING FROM 4 BLOWS PER FOOT (BPF) TO REFUSAL. NATURAL MOISTURE CONTENTS RANGED FROM 1 TO 27 PERCENT. BASED ON ATTERBERG LIMITS TEST PERFORMED ON REPRESENTATIVE SAMPLES OF THE COHESIVE SOILS, THE LIQUID AND PLASTIC LIMIT WERE ESTIMATED TO RANGE FROM 18 TO 52 PERCENT AND FROM 12 TO 23 PERCENT, RESPECTIVELY. SIXTEEN PERCENT (16%) OF THE SAMPLES TAKEN ALONG THE IR-71 WERE CLASSIFIED AS NON-COHESIVE COARSE-GRAINED SOILS AND WERE COMPRISED OF: COMPRISED OF 1) GRAVEL AND/OR STONE FRAGMENTS (A-1-a, 2% OF THE SAMPLES); 2) GRAVEL WITH SAND (A-1-b, 7% OF THE SAMPLES); AND 3) GRAVEL WITH SAND AND SILT (A-2-4, 7% OF THE SAMPLES). WITH RESPECT TO THE RELATIVE DENSITY OF THE NON-COHESIVE GRANULAR SOILS, THE MATERIAL DESCRIPTION VARIES FROM LOOSE TO DENSE CORRELATING TO $N_{60}$ VALUES RANGING FROM 4 TO 45 BPF. NATURAL MOISTURE CONTENTS OF GRANULAR SOILS RANGED FROM 4 TO 16 PERCENT.

GROUNDWATER WAS ENCOUNTERED IN 10 OUT OF 48 PROJECT BORINGS DURING DRILLING AS PART OF THE PROJECT. GROUNDWATER WAS ENCOUNTERED AT DEPTHS RANGING FROM 12.5 TO 35.0 FT BELOW GROUND SURFACE (APPROXIMATE ELEVATIONS 820.2 TO 906.9 FT AMSL).

BEDROCK WAS ENCOUNTERED IN FOUR PROJECT BORINGS (B-027-0-22, B-028-0-22, B-029-0-22 AND B-030-0-22) AS SLIGHTLY TO HIGHLY WEATHERED SHALE, DEPTHS RANGING FROM 17.0 TO 23.0 FT BELOW GROUND SURFACE (APPROXIMATE ELEVATIONS 832.3 TO 838.2 FT AMSL).

## SPECIFICATIONS

THIS GEOTECHNICAL EXPLORATION WAS PERFORMED IN ACCORDANCE WITH THE STATE OF OHIO, DEPARTMENT OF TRANSPORTATION, OFFICE OF GEOTECHNICAL ENGINEERING, SPECIFICATIONS FOR GEOTECHNICAL EXPLORATIONS, DATED JULY 2023.

## AVAILABLE INFORMATION

THE GEOTECHNICAL, BEDROCK, AND GROUNDWATER INFORMATION COLLECTED FOR THIS SUBSURFACE EXPLORATION THAT CAN BE CONVENIENTLY DISPLAYED ON THE SOIL PROFILE SHEETS HAS BEEN PRESENTED. GEOTECHNICAL REPORTS, IF PREPARED, ARE AVAILABLE FOR REVIEW ON THE OFFICE OF CONTRACT SALES WEBSITE.

**ORGANIC CONTENT BY LOSS ON IGNITION TEST**

| BORING ID | SAMPLE ID | SAMPLE ELEVATION | SAMPLE DEPTH | LOI (%) |
|---|---|---|---|---|
| B-025-0-22 | SS-4 | 842.8' - 841.3' | 8.5' - 10.0' | 2.7 |
| B-026-0-22 | SS-6 | 840.2' - 838.7' | 11.0' - 12.5' | 2.7 |

GEOTECHNICAL PROFILE - ROADWAY

DESIGN AGENCY
NEAS National Engineering & Architectural Services Inc.

DESIGNER ZM
REVIEWER CH 08-28-23
PROJECT ID 109164
SUBSET 2 | TOTAL 69
SHEET P.551 | TOTAL 618


FRA-71-19.10

MODEL: Sheet_SurvFt PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:55:10 PM USER: zil
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\00-Engineering\Geotechnical\Sheets\109164_IC002.dgn

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:44:51 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ID001.dgn

# SUMMARY OF SOIL TEST DATA
## IR 71

| EXPLORATION NO., STATION & OFFSET | FROM | TO | SAMPLE ID | N60 | % REC | HP tsf | % GR | % CS | % FS | % SILT | % CLAY | LL | PL | PI | % WC | ODOT CLASS (GI) | ppm SO4 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| B-001-0-22 | 01.50 | 03.00 | SS-1 | 45 | 33 | 4.50 | | | | SAME AS SS-2 | | | | | 1 | A-4a (VISUAL) | |
| STA. 1049+43, 55' LT. | 03.00 | 04.50 | SS-2 | 41 | 44 | 4.50 | 7 | 8 | 14 | 44 | 27 | 24 | 16 | 8 | 10 | A-4a (7) | 280 |
| LATITUDE = 39.992665 | 04.50 | 06.00 | SS-3 | 41 | 44 | 4.50 | 22 | 14 | 17 | 31 | 16 | 21 | 15 | 6 | 8 | A-4a (2) | |
| LONGITUDE = -82.985422 | 06.00 | 07.50 | SS-4 | 32 | 28 | 4.50 | | | | SAME AS SS-3 | | | | | 10 | A-4a (VISUAL) | |
| B-002-0-22 | 01.50 | 03.00 | SS-1 | 14 | 56 | 4.50 | 8 | 11 | 22 | 38 | 21 | 18 | 12 | 6 | 10 | A-4a (5) | 133 |
| STA. 1051+82, 50' RT. | 03.00 | 04.50 | SS-2 | 34 | 50 | 4.50 | 29 | 17 | 18 | 23 | 13 | 21 | 14 | 7 | 7 | A-4a (0) | |
| LATITUDE = 39.993297 | 04.50 | 06.00 | SS-3 | 38 | 61 | 4.50 | | | | SAME AS SS-2 | | | | | 10 | A-4a (VISUAL) | |
| LONGITUDE = -82.984982 | 06.00 | 07.50 | SS-4 | 40 | 100 | 4.50 | | | | SAME AS SS-2 | | | | | 11 | A-4a (VISUAL) | |
| B-005-0-22 | 01.50 | 03.00 | SS-1 | 8 | 44 | 3.00 | 13 | 13 | 16 | 33 | 25 | 26 | 17 | 9 | 16 | A-4a (5) | 60 |
| STA. 1071+38, 54' RT. | 03.00 | 04.50 | SS-2 | 26 | 67 | - | 59 | 18 | 9 | 10 | 4 | NP | NP | NP | 9 | A-1-a (0) | |
| LATITUDE = 39.998650 | 04.50 | 06.00 | SS-3 | 7 | 39 | 2.25 | | | | SAME AS SS-1 | | | | | 16 | A-4a (VISUAL) | |
| LONGITUDE = -82.984438 | 06.00 | 07.50 | SS-4 | 13 | 100 | 3.00 | | | | SAME AS SS-1 | | | | | 16 | A-4a (VISUAL) | |
| B-006-0-22 | 01.50 | 03.00 | SS-1 | 21 | 100 | - | 43 | 23 | 14 | 16 | 4 | NP | NP | NP | 7 | A-1-b (0) | 100 |
| STA. 1075+26, 52' LT. | 03.00 | 04.50 | SS-2 | 16 | 100 | 4.50 | 11 | 14 | 19 | 35 | 21 | 24 | 16 | 8 | 11 | A-4a (4) | |
| LATITUDE = 39.999730 | 04.50 | 06.00 | SS-3 | 24 | 100 | 4.50 | | | | SAME AS SS-2 | | | | | 11 | A-4a (VISUAL) | |
| LONGITUDE = -82.984734 | 06.00 | 07.50 | SS-4 | 30 | 100 | 4.50 | | | | SAME AS SS-2 | | | | | 12 | A-4a (VISUAL) | |
| B-007-0-22 | 01.50 | 03.00 | SS-1 | 13 | 100 | 4.25 | 11 | 15 | 18 | 35 | 21 | 24 | 16 | 8 | 13 | A-4a (4) | 80 |
| STA. 1081+28, 53' LT. | 03.00 | 04.50 | SS-2 | 16 | 100 | 4.50 | 23 | 13 | 15 | 30 | 19 | 25 | 16 | 9 | 12 | A-4a (3) | |
| LATITUDE = 40.001377 | 04.50 | 06.00 | SS-3 | 27 | 100 | 4.00 | | | | SAME AS SS-2 | | | | | 25 | A-4a (VISUAL) | |
| LONGITUDE = -82.984697 | 06.00 | 07.50 | SS-4 | 19 | 100 | 4.50 | | | | SAME AS SS-2 | | | | | 12 | A-4a (VISUAL) | |
| B-008-0-22 | 01.50 | 03.00 | SS-1 | 17 | 100 | - | 36 | 17 | 14 | 23 | 10 | NP | NP | NP | 8 | A-2-4 (0) | 160 |
| STA. 1085+48, 55' LT. | 03.00 | 04.50 | SS-2 | 21 | 100 | - | 31 | 12 | 13 | 27 | 17 | 29 | 17 | 12 | 11 | A-6a (2) | |
| LATITUDE = 40.002529 | 04.50 | 06.00 | SS-3 | 19 | 100 | 3.50 | 15 | 8 | 15 | 34 | 28 | 32 | 18 | 14 | 15 | A-6a (7) | |
| LONGITUDE = -82.984705 | 06.00 | 07.50 | SS-4 | 28 | 100 | 4.50 | | | | HARD, BROWN, SANDY SILT | | | | | 15 | A-4a (VISUAL) | |
| B-009-0-22 | 01.50 | 03.00 | SS-1 | 29 | 89 | - | 36 | 25 | 12 | 21 | 6 | NP | NP | NP | 6 | A-2-4 (0) | 73 |
| STA. 1090+50, 64' RT. | 03.00 | 04.50 | SS-2 | 11 | 78 | 3.25 | 4 | 5 | 12 | 37 | 42 | 41 | 19 | 22 | 22 | A-7-6 (13) | |
| LATITUDE = 40.003906 | 04.50 | 06.00 | SS-3 | 8 | 100 | 2.25 | | | | SAME AS SS-2 | | | | | 25 | A-7-6 (VISUAL) | |
| LONGITUDE = -82.984281 | 06.00 | 07.50 | SS-4 | 12 | 100 | 3.00 | | | | SAME AS SS-2 | | | | | 24 | A-7-6 (VISUAL) | |
| B-010-0-22 | 01.50 | 03.00 | SS-1 | 17 | 100 | 4.50 | 5 | 11 | 18 | 38 | 28 | 25 | 17 | 8 | 14 | A-4a (6) | 140 |
| STA. 1094+34, 63' LT. | 03.00 | 04.50 | SS-2 | 13 | 100 | 4.25 | | | | SAME AS SS-1 | | | | | 14 | A-4a (VISUAL) | |
| LATITUDE = 40.004957 | 04.50 | 06.00 | SS-3 | 19 | 100 | 2.25 | 4 | 7 | 13 | 39 | 37 | 34 | 16 | 18 | 18 | A-6b (11) | |
| LONGITUDE = -82.984740 | 06.00 | 07.50 | SS-4 | 18 | 100 | 2.50 | | | | VERY STIFF, BROWN, SILT AND CLAY, SOME SAND | | | | | 18 | A-6a (VISUAL) | |
| B-011-0-22 | 01.50 | 03.00 | SS-1 | 24 | 100 | - | 18 | 36 | 21 | 20 | 5 | NP | NP | NP | 8 | A-1-b (0) | 160 |
| STA. 1098+37, 59' RT. | 03.00 | 04.50 | SS-2 | 22 | 100 | 4.50 | 12 | 10 | 15 | 33 | 30 | 33 | 18 | 15 | 13 | A-6a (8) | |
| LATITUDE = 40.006090 | 04.50 | 06.00 | SS-3 | 17 | 100 | 4.50 | | | | SAME AS SS-2 | | | | | 13 | A-6a (VISUAL) | |
| LONGITUDE = -82.984466 | 06.00 | 07.50 | SS-4 | 21 | 33 | 3.50 | | | | SAME AS SS-2 | | | | | 20 | A-6a (VISUAL) | |
| B-012-0-22 | 01.50 | 03.00 | SS-1 | 8 | 100 | 3.00 | 6 | 4 | 10 | 32 | 48 | 49 | 21 | 28 | 24 | A-7-6 (17) | 380 |
| STA. 1102+35, 53' LT. | 03.00 | 04.50 | SS-2 | 14 | 100 | 4.50 | | | | SAME AS SS-1 | | | | | 16 | A-7-6 (VISUAL) | |
| LATITUDE = 40.007055 | 04.50 | 06.00 | SS-3 | 17 | 100 | 4.50 | 6 | 10 | 16 | 38 | 30 | 28 | 17 | 11 | 16 | A-6a (7) | |
| LONGITUDE = -82.985244 | 06.00 | 07.50 | SS-4 | 17 | 100 | 4.50 | | | | SAME AS SS-3 | | | | | 14 | A-6a (VISUAL) | |
| B-013-0-22 | 01.50 | 03.00 | SS-1 | 18 | 83 | - | 26 | 33 | 18 | 17 | 6 | NP | NP | NP | 8 | A-1-b (0) | 220 |
| STA. 1106+36, 49' RT. | 03.00 | 04.50 | SS-2 | 28 | 100 | 4.50 | 8 | 9 | 20 | 38 | 25 | 23 | 14 | 9 | 10 | A-4a (6) | |
| LATITUDE = 40.008162 | 04.50 | 06.00 | SS-3 | 21 | 100 | 4.50 | | | | SAME AS SS-2 | | | | | 13 | A-4a (VISUAL) | |
| LONGITUDE = -82.985552 | 06.00 | 07.50 | SS-4 | 22 | 100 | 4.50 | | | | HARD, BROWN, SILT AND CLAY | | | | | 17 | A-6a (VISUAL) | |
| B-038-0-22 | 01.50 | 03.00 | SS-1 | 22 | 89 | - | 30 | 23 | 17 | 23 | 7 | NP | NP | NP | 8 | A-2-4 (0) | 60 |
| STA. 1207+01, 86' RT. | 03.00 | 04.50 | SS-2 | 38 | 100 | - | | | | SAME AS SS-1 | | | | | 9 | A-2-4 (VISUAL) | |
| LATITUDE = 40.032767 | 04.50 | 06.00 | SS-3 | 51 | 44 | - | 23 | 18 | 23 | 23 | 13 | NP | NP | NP | 8 | A-4a (0) | |
| LONGITUDE = -82.995104 | 06.00 | 07.50 | SS-4 | 50 | 100 | - | | | | SAME AS SS-3 | | | | | 12 | A-4a (VISUAL) | |
| B-039-0-22 | 01.50 | 03.00 | SS-1 | 30 | 94 | - | 27 | 33 | 21 | 14 | 5 | NP | NP | NP | 8 | A-1-b (0) | 420 |
| STA. 1210+81, 68' RT. | 03.00 | 04.50 | SS-2 | 18 | 100 | - | | | | SAME AS SS-1 | | | | | 8 | A-1-b (VISUAL) | |
| LATITUDE = 40.033732 | 04.50 | 06.00 | SS-3 | 17 | 33 | - | 68 | 10 | 7 | 11 | 4 | NP | NP | NP | 5 | A-1-a (0) | |
| LONGITUDE = -82.995601 | 06.00 | 07.50 | SS-4 | 20 | 39 | 4.00 | | | | VERY STIFF, GRAY, SILT AND CLAY | | | | | 14 | A-6a (VISUAL) | |
| B-040-0-22 | 01.50 | 03.00 | SS-1 | 9 | 78 | 2.25 | 2 | 5 | 11 | 43 | 39 | 43 | 21 | 22 | 23 | A-7-6 (13) | 260 |
| STA. 1214+91, 69' RT. | 03.00 | 04.50 | SS-2 | 9 | 100 | 4.25 | 3 | 5 | 14 | 38 | 40 | 38 | 19 | 19 | 21 | A-6b (12) | |
| LATITUDE = 40.034805 | 04.50 | 06.00 | SS-3 | 7 | 100 | 2.50 | | | | SAME AS SS-2 | | | | | 21 | A-6b (VISUAL) | |
| LONGITUDE = -82.995984 | 06.00 | 07.50 | SS-4 | 5 | 100 | 3.50 | | | | VERY STIFF, BROWN, SILT AND CLAY | | | | | 12 | A-6a (VISUAL) | |
| B-041-0-22 | 01.50 | 03.00 | SS-1 | 7 | 72 | 2.00 | 2 | 7 | 15 | 31 | 45 | 52 | 19 | 33 | 27 | A-7-6 (18) | 260 |
| STA. 1218+90, 62' RT. | 03.00 | 04.50 | SS-2 | 13 | 100 | 4.50 | | | | SAME AS SS-1 | | | | | 17 | A-7-6 (VISUAL) | |
| LATITUDE = 40.035863 | 04.50 | 06.00 | SS-3 | 16 | 100 | 4.50 | 11 | 11 | 18 | 37 | 23 | 26 | 17 | 9 | 14 | A-4a (5) | |
| LONGITUDE = -82.996289 | 06.00 | 07.50 | SS-4 | 17 | 100 | 4.50 | | | | SAME AS SS-3 | | | | | 15 | A-4a (VISUAL) | |
| B-042-0-22 | 01.50 | 03.00 | SS-1 | 18 | 56 | - | 17 | 33 | 25 | 18 | 7 | NP | NP | NP | 11 | A-1-b (0) | 140 |
| STA. 1222+88, 62' RT. | 03.00 | 04.50 | SS-2 | 22 | 100 | 4.50 | 11 | 11 | 15 | 37 | 26 | 28 | 18 | 10 | 13 | A-4a (6) | |
| LATITUDE = 40.036934 | 04.50 | 06.00 | SS-3 | 13 | 100 | 3.50 | 1 | 5 | 11 | 38 | 45 | 46 | 21 | 25 | 22 | A-7-6 (15) | |
| LONGITUDE = -82.996469 | 06.00 | 07.50 | SS-4 | 14 | 100 | 3.00 | | | | SAME AS SS-3 | | | | | 23 | A-7-6 (VISUAL) | |




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1048+00 TO STA. 1060+50 IR 71 SOUTHBOUND

DESIGN AGENCY
KEA National Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 4 |
| TOTAL | 69 |
| SHEET | P.553 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP001 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:56:41 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP001_SB.dgn




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1048+00 TO STA. 1060+50 IR 71 NORTHBOUND

FRA-71-19.10

MODEL: 109164_IP001 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:57:12 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP001_NB.dgn

DESIGN AGENCY
KEA National Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET / TOTAL | 5 / 69 |
| SHEET / TOTAL | P.554 / 618 |




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1060+50 TO STA. 1073+00 IR 71 SOUTHBOUND


DESIGN AGENCY
HEAS Heavy Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 6 |
| TOTAL | 69 |
| SHEET | P.555 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP002 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:57:40 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP002_SB.dgn




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
# STA. 1060+50 TO STA. 1073+00 IR 71 NORTHBOUND


DESIGN AGENCY
VDOT Virginia Department of Transportation
HEAS Highway Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 7 |
| TOTAL | 69 |
| SHEET | P.556 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP002 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:58:07 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP002_NB.dgn




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1073+00 TO STA. 1085+50 IR 71 SOUTHBOUND


FRA-71-19.10

MODEL: 109164_IP003 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:58:35 PM USER: zil
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A201000 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP003_SB.dgn

DESIGN AGENCY
KEA Kimley Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 8 |
| TOTAL | 69 |
| SHEET | P.557 |
| TOTAL | 618 |




HORIZONTAL SCALE IN FEET
0 25 50 100

# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1073+00 TO STA. 1085+50 IR 71 NORTHBOUND


DESIGN AGENCY
HNTB Engineering & Architectural Services Inc.


| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 9 |
| TOTAL | 69 |
| SHEET | P.558 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP003 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:59:03 PM USER: zil
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A201000 - FRA-071-19\10 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP003_NB.dgn

MODEL: 109164_IP004 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:59:31 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP004_SB.dgn





| DESIGNER | DESIGN AGENCY |
|---|---|
| ZM | NEAS National Engineering & Architectural Services Inc. |


| REVIEWER | PROJECT ID | SUBSET | SHEET |
|---|---|---|---|
| CH 08-28-23 | 109164 | 10 TOTAL 69 | P.559 TOTAL 618 |

# GEOTECHNICAL PROFILE - ROADWAY
# STA. 1085+50 TO STA. 1098+00 IR 71 SOUTHBOUND

HORIZONTAL SCALE IN FEET
0 50
25 100

MODEL: 109164_IP004 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 4:59:58 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP004_NB.dgn





| DESIGNER | REVIEWER | PROJECT ID | SUBSET | SHEET |
|---|---|---|---|---|
| ZM | CH | 109164 | 11 | P.560 |
| | 08-28-23 | | TOTAL 69 | TOTAL 618 |

DESIGN AGENCY: NEAS National Engineering & Architectural Services Inc.

# GEOTECHNICAL PROFILE - ROADWAY
# STA. 1085+50 TO STA. 1098+00 IR 71 NORTHBOUND


HORIZONTAL SCALE IN FEET
0 50
25 100

MODEL: 109164_IP005 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:00:26 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP005_SB.dgn




| | | |

MODEL: 109164_IP005 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:00:53 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP005_NB.dgn





| | | | | | | |
|---|---|---|---|---|---|---|
| SHEET P.562 | TOTAL 618 | SUBSET 13 | TOTAL 69 | PROJECT ID 109164 | REVIEWER CH 08-28-23 | DESIGNER ZM |

DESIGN AGENCY: NEAS National Engineering & Architectural Services Inc.

# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1098+00 TO STA. 1100+50 IR 71 NORTHBOUND

HORIZONTAL SCALE IN FEET
0 50
25 100




HORIZONTAL SCALE IN FEET
0 25 50 100

# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1100+50 TO STA. 1123+00 IR 71 SOUTHBOUND


DESIGN AGENCY
NEAS
National Engineering & Architectural Services Inc.


| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET / TOTAL | 14 / 69 |
| SHEET / TOTAL | P.563 / 618 |

FRA-71-19.10

MODEL: 109164_IP006 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:01:21 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP006_SB.dgn

MODEL: 109164_IP006 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:01:49 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP006_NB.dgn





# GEOTECHNICAL PROFILE - ROADWAY
# STA. 1100+50 TO STA. 1123+00 IR 71 NORTHBOUND

HORIZONTAL SCALE IN FEET
0 50
25 100

| DESIGNER | DESIGN AGENCY |
|---|---|
| ZM | NEAS National Engineering & Architectural Services Inc. |

| REVIEWER | PROJECT ID | SUBSET | TOTAL |
|---|---|---|---|
| CH 08-28-23 | 109164 | 15 | 69 |

| SHEET | TOTAL |
|---|---|
| P.564 | 618 |




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1123+00 TO STA. 1135+50 IR 71 SOUTHBOUND

DESIGN AGENCY
HNTB National Engineering & Architectural Services for Ohio

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 16 |
| TOTAL | 69 |
| SHEET | P.565 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP007 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:02:16 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP007_SB.dgn




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
# STA. 1123+00 TO STA. 1135+50 IR 71 NORTHBOUND


DESIGN AGENCY
HNTB National Engineering & Architectural Services for

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 17 |
| TOTAL | 69 |
| SHEET | P.566 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP007 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:02:44 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP007_NB.dgn




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1148+00 TO STA. 1160+50 IR 71 SOUTHBOUND

DESIGN AGENCY
KEA Kleinfelder Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 18 |
| TOTAL | 69 |
| SHEET | P.567 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP009 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:03:12 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP009_SB.dgn




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
# STA. 1148+00 TO STA. 1160+50 IR 71 NORTHBOUND

DESIGN AGENCY
KEA Kleinfelder Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 19 |
| TOTAL | 69 |
| SHEET | P.568 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP009 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:03:43 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP009_NB.dgn




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
# STA. 1160+50 TO STA. 1173+00 IR 71 SOUTHBOUND

DESIGN AGENCY
HNTB National Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 20 |
| TOTAL | 69 |
| SHEET | P.569 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP010 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:04:11 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP010_SB.dgn




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
# STA. 1160+50 TO STA. 1173+00 IR 71 NORTHBOUND


DESIGN AGENCY
HNTB Engineering & Architectural Services for

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET / TOTAL | 21 / 69 |
| SHEET / TOTAL | P.570 / 618 |

FRA-71-19.10

MODEL: 109164_IP010 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:04:40 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP010_NB.dgn




HORIZONTAL SCALE IN FEET
0 25 50 100


# GEOTECHNICAL PROFILE - ROADWAY
# STA. 1185+50 TO STA. 1198+00 IR 71 SOUTHBOUND


DESIGN AGENCY
AMEC Foster Wheeler Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 22 |
| TOTAL | 69 |
| SHEET | P.571 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP012 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:05:08 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A2O100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP012_SB.dgn




HORIZONTAL SCALE IN FEET
0 25 50 100

# GEOTECHNICAL PROFILE - ROADWAY
# STA. 1185+50 TO STA. 1198+00 IR 71 NORTHBOUND


DESIGN AGENCY
KEA National Engineering & Architectural Services Inc.


| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 23 |
| TOTAL | 69 |
| SHEET | P.572 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP012 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:05:59 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP012_NB.dgn

MODEL: 109164_IP013 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:06:27 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP013_SB.dgn









GEOTECHNICAL PROFILE - ROADWAY
STA. 1198+00 TO STA. 1210+50 IR 71 SOUTHBOUND

HORIZONTAL SCALE IN FEET
0 50
25 100

| DESIGN AGENCY | DESIGNER | REVIEWER | PROJECT ID | SUBSET | SHEET |
|---|---|---|---|---|---|
| NEAS National Engineering & Architectural Services Inc. | ZM | CH 08-28-23 | 109164 | 24 TOTAL 69 | P.573 TOTAL 618 |




HORIZONTAL SCALE IN FEET
0 25 50 100

# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1198+00 TO STA. 1210+50 IR 71 NORTHBOUND


DESIGN AGENCY
HNTB Engineering & Architectural Services Inc.


| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 25 |
| TOTAL | 69 |
| SHEET | P.574 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP013 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:06:56 PM USER: zil
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP013_NB.dgn

MODEL: 109164_IP014 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:07:24 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP014_SB.dgn








GEOTECHNICAL PROFILE - ROADWAY
STA. 1210+50 TO STA. 1223+00 IR 71 SOUTHBOUND

HORIZONTAL SCALE IN FEET
0 50
25 100

| DESIGNER | DESIGN AGENCY |
|---|---|
| ZM | NEAS National Engineering & Architectural Services Inc. |

| REVIEWER | PROJECT ID | SUBSET | SHEET |
|---|---|---|---|
| CH 08-28-23 | 109164 | 26 TOTAL 69 | P.575 TOTAL 618 |




HORIZONTAL SCALE IN FEET
0 25 50 100

# GEOTECHNICAL PROFILE - ROADWAY
## STA. 1210+50 TO STA. 1223+00 IR 71 NORTHBOUND


DESIGN AGENCY
HNTB National Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 27 |
| TOTAL | 69 |
| SHEET | P.576 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_IP014 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:07:51 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_IP014_NB.dgn

MODEL: 109164_ZP001 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:08:19 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZP001.dgn




GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD

HORIZONTAL SCALE IN FEET
0 20
10 40

| SHEET | TOTAL |
|---|---|
| P.577 | 618 |


| SUBSET | TOTAL |
|---|---|
| 28 | 69 |

PROJECT ID: 109164

REVIEWER: CH 08-28-23

DESIGNER: ZM

DESIGN AGENCY: NEAS National Engineering & Architectural Services Inc.




HORIZONTAL
SCALE IN FEET
0 10 20 40

# GEOTECHNICAL PROFILE - ROADWAY
# BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD


DESIGN AGENCY
KEA Kleinfelder Engineering & Architectural Services Inc.

| | |
|---|---|
| DESIGNER | ZM |
| REVIEWER | CH 08-28-23 |
| PROJECT ID | 109164 |
| SUBSET | 29 |
| TOTAL | 69 |
| SHEET | P.578 |
| TOTAL | 618 |

FRA-71-19.10

MODEL: 109164_ZF001 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:45:52 PM USER: ZLi
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZF001.dgn

MODEL: 109164_ZP002 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 6:29:25 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZP002.dgn





GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161

HORIZONTAL SCALE IN FEET
0 20
10 40

| DESIGNER | DESIGN AGENCY |
|---|---|
| ZM | NEAS National Engineering & Architectural Services Inc. |

| REVIEWER | PROJECT ID | SUBSET | SHEET |
|---|---|---|---|
| CH 08-28-23 | 109164 | 30 TOTAL 69 | P.579 TOTAL 618 |




HORIZONTAL
SCALE IN FEET
0 10 20 40

# GEOTECHNICAL PROFILE - ROADWAY
## BRIDGE NO. FRA-71-26.46 OVER SR 161

DESIGN AGENCY
KEA Infrastructure Engineering & Architectural Services Inc

DESIGNER ZM
REVIEWER CH 08-28-23
PROJECT ID 109164
SUBSET 31 TOTAL 69
SHEET P.580 TOTAL 618

FRA-71-19.10

MODEL: 109164_ZF002 PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:48:21 PM USER: ZLi
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZF002.dgn

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:10:07 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL001.dgn

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:52 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / CP | DRILL RIG: CME 75T | STATION / OFFSET: 1062+63, 64' LT. | EXPLORATION ID B-003-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | PAGE 1 OF 1
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 827.1 (MSL) EOB: 21.5 ft.
START: 9/6/22 END: 9/6/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 39.996280, -82.985097

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **10.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 825.8 | | | | | | | | | | | | | | | | | |
| HARD, BROWN BECOMING GRAY, **SANDY SILT**, LITTLE TO SOME CLAY, LITTLE TO SOME GRAVEL, GLACIAL TILL, DAMP | | 1 | | | | | | | | | | | | | | | | |
| | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | 7 6 4 | 13 | 39 | SS-1 | 4.50 | 22 | 23 | 15 | 28 | 12 | 22 | 16 | 6 | 7 | A-4a (1) | |
| | | 4 | | | | | | | | | | | | | | | | |
| | | 5 | 3 4 5 | 12 | 28 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 6 | | | | | | | | | | | | | | | | |
| | | 7 | 7 7 7 | 18 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 8 | | | | | | | | | | | | | | | | |
| | | 9 | | | | | | | | | | | | | | | | |
| | | 10 | 6 7 10 | 22 | 44 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 11 | | | | | | | | | | | | | | | | |
| | | 12 | | | | | | | | | | | | | | | | |
| | | 13 | 14 25 26 | 67 | 50 | SS-5 | 4.25 | 11 | 15 | 17 | 34 | 23 | 24 | 15 | 9 | 12 | A-4a (4) | |
| | | 14 | | | | | | | | | | | | | | | | |
| | | 15 | 15 26 30 | 74 | 83 | SS-6 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | 16 | | | | | | | | | | | | | | | | |
| | | 17 | | | | | | | | | | | | | | | | |
| | | 18 | 5 14 22 | 47 | 100 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 19 | | | | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | 10 12 25 | 49 | 100 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | 805.6 | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:52 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / CP | DRILL RIG: CME 45B | STATION / OFFSET: 1064+19, 65' LT. | EXPLORATION ID B-004-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | PAGE 1 OF 1
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 831.2 (MSL) EOB: 21.5 ft.
START: 9/6/22 END: 9/6/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 72.6 | LAT / LONG: 39.996706, -82.985056

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **11.0" ASPHALT AND 7.0" BASE (DRILLERS DESCRIPTION)** | 829.7 | | | | | | | | | | | | | | | | | |
| **UNCONTROLLED FILL** | 827.2 | 1 | | | | | | | | | | | | | | | | |
| | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | 15 14 30 | 53 | 17 | SS-1 | 4.50 | - | - | - | - | - | - | - | - | 0 | UCF (V) | |
| HARD, BROWN BECOMING GRAY, **SANDY SILT**, LITTLE TO SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | 4 | | | | | | | | | | | | | | | | |
| | | 5 | 2 4 4 | 10 | 39 | SS-2 | 4.25 | 7 | 11 | 17 | 36 | 29 | 22 | 15 | 7 | 14 | A-4a (6) | |
| | | 6 | | | | | | | | | | | | | | | | |
| | | 7 | | | | | | | | | | | | | | | | |
| | | 8 | 6 7 9 | 19 | 33 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 9 | | | | | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | 9 10 14 | 29 | 100 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 12 | | | | | | | | | | | | | | | | |
| | | 13 | 15 12 14 | 31 | 50 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 14 | | | | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | 6 9 13 | 27 | 39 | SS-6 | 4.50 | 15 | 13 | 16 | 36 | 20 | 23 | 15 | 8 | 11 | A-4a (4) | |
| | | 17 | | | | | | | | | | | | | | | | |
| | | 18 | 6 8 12 | 24 | 83 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 19 | | | | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | 10 25 29 | 65 | 17 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | 809.7 | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; SHOVELED SOIL CUTTINGS

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.581 | 32 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |
| TOTAL 618 | TOTAL 69 | | | | |

GEOTECHNICAL PROFILE - ROADWAY
BORING LOGS B-003-0-22 & B-004-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:10:41 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL002.dgn

| | | | | | |
|---|---|---|---|---|---|
| PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / CP | DRILL RIG: CME 75T | STATION / OFFSET: 1108+37, 52' LT. | EXPLORATION ID B-014-0-22 |
| TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | |
| PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 856.6 (MSL) EOB: 46.5 ft. | PAGE 1 OF 1 |
| START: 8/31/22 END: 8/31/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.008466, -82.986249 | |

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **11.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 855.1 | | | | | | | | | | | | | | | | | |
| HARD, BROWN AND DARK GRAY, **SILT AND CLAY**, SOME SAND, TRACE GRAVEL, DAMP | 847.1 | | 5 8 8 | 21 | 100 | SS-1 | 4.50 | 6 | 10 | 18 | 37 | 29 | 28 | 17 | 11 | 12 | A-6a (7) | |
| | | | 5 9 12 | 28 | 100 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 16 | A-6a (V) | |
| | | | 6 9 10 | 25 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 21 | A-6a (V) | |
| MEDIUM DENSE, DARK GRAY AND GRAY, **STONE FRAGMENTS WITH SAND AND SILT**, LITTLE CLAY, DAMP | 844.6 | | 4 5 11 | 21 | 100 | SS-4 | - | - | - | - | - | - | - | - | - | 9 | A-2-4 (V) | |
| HARD, DARK GRAY AND BLACK, **CLAY**, "AND" SILT, LITTLE SAND, TRACE GRAVEL, MODERATELY ORGANIC, MOIST | 842.1 | | 5 5 7 | 16 | 100 | SS-5 | 4.25 | 1 | 2 | 9 | 42 | 46 | 54 | 25 | 29 | 27 | A-7-6 (18) | |
| VERY STIFF, BROWN MOTTLED WITH ORANGISH BROWN AND GRAY, **CLAY**, "AND" SILT, LITTLE SAND, TRACE GRAVEL, IRON STAINING, DAMP | 837.1 | | 3 5 6 | 14 | 100 | SS-6 | 3.75 | 2 | 3 | 9 | 41 | 45 | 42 | 21 | 21 | 21 | A-7-6 (13) | |
| | | | 2 4 5 | 12 | 100 | SS-7 | 3.50 | - | - | - | - | - | - | - | - | 17 | A-7-6 (V) | |
| VERY STIFF, BROWN, **SILT AND CLAY**, SOME SAND, LITTLE GRAVEL, DAMP | 832.1 | | 3 4 5 | 12 | 100 | SS-8 | 3.75 | 13 | 14 | 18 | 32 | 23 | 27 | 15 | 12 | 12 | A-6a (5) | |
| | | | 2 4 6 | 13 | 100 | SS-9 | 4.00 | - | - | - | - | - | - | - | - | 13 | A-6a (V) | |
| VERY STIFF TO HARD, GRAY AND DARK GRAY, **CLAY**, SOME SILT, TRACE TO LITTLE SAND, TRACE GRAVEL, DAMP TO MOIST | 827.1 | | 7 10 12 | 29 | 100 | SS-10 | 4.00 | 1 | 2 | 11 | 34 | 52 | 47 | 18 | 29 | 18 | A-7-6 (17) | |
| | | | 4 12 11 | 30 | 100 | SS-11 | 4.25 | - | - | - | - | - | - | - | - | 19 | A-7-6 (V) | |
| VERY DENSE, DARK BROWNISH GRAY, **COARSE AND FINE SAND**, SOME SILT, LITTLE GRAVEL, TRACE CLAY, DAMP TO MOIST | 822.8 | | 18 24 23 | 62 | 100 | SS-12 | - | - | - | - | - | - | - | - | - | 11 | A-3a (V) | |
| | | | 15 22 26 | 63 | 100 | SS-13 | - | - | - | - | - | - | - | - | - | 14 | A-3a (V) | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, GLACIAL TILL, DAMP | 810.1 | EOB | 9 10 16 | 34 | 56 | SS-14 | 4.50 | 0 | 9 | 14 | 47 | 30 | 25 | 16 | 9 | 11 | A-4a (8) | |
| | | | 8 12 14 | 34 | 100 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 5 9 18 | 36 | 83 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 6 10 20 | 40 | 28 | SS-17 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 14 10 19 | 38 | 50 | SS-18 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:47 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.582 | 618 | 33 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

# GEOTECHNICAL PROFILE - ROADWAY
# BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
# BORING LOG B-014-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:11:20 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL003.dgn

| | | | |
|---|---|---|---|
| PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / CP | DRILL RIG: CME 75T | STATION / OFFSET: 1109+85, 52' LT. |
| TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 |
| PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 859.2 (MSL) EOB: 46.5 ft. |
| START: 8/30/22 END: 8/31/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.008779, -82.986568 |

EXPLORATION ID B-015-0-22

PAGE 1 OF 1

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **10.0" ASPHALT AND 7.0" BASE (DRILLERS DESCRIPTION)** | 857.8 | | | | | | | | | | | | | | | | | |
| HARD, BROWN AND ORANGISH BROWN, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, IRON STAINING, DAMP **(FILL)** | 849.7 | | 6 7 11 | 24 | 100 | SS-1 | 4.50 | 10 | 12 | 17 | 37 | 24 | 26 | 16 | 10 | 10 | A-4a (5) | |
| | | | 5 6 11 | 22 | 100 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 6 8 9 | 22 | 44 | SS-3 | 4.25 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| HARD, DARK GRAY AND BLACK, **SANDY SILT**, SOME CLAY, LITTLE GRAVEL, CONTAINS COAL AND BRICK FRAGMENTS, MOIST **(FILL)** | 844.7 | | 6 7 12 | 25 | 100 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 21 | A-4a (V) | |
| | | | 5 6 22 | 37 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 19 | A-4a (V) | |
| HARD, ORANGISH BROWN AND GRAY, **SILT AND CLAY**, SOME SAND, LITTLE GRAVEL, IRON STAINING, CONTAINS CONCRETE FRAGMENTS, DAMP **(FILL)** | 839.7 | | 4 4 5 | 12 | 83 | SS-6 | 4.25 | 11 | 9 | 12 | 36 | 32 | 32 | 19 | 13 | 15 | A-6a (8) | |
| | | | 4 5 7 | 16 | 28 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 17 | A-6a (V) | |
| MEDIUM STIFF TO VERY STIFF, BROWN AND ORANGISH BROWN, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, DAMP | | | 3 3 4 | 9 | 100 | SS-8 | 2.50 | 7 | 12 | 19 | 37 | 25 | 27 | 17 | 10 | 15 | A-4a (5) | |
| | | | 3 4 4 | 11 | 100 | SS-9 | 2.50 | - | - | - | - | - | - | - | - | 15 | A-4a (V) | |
| | | | 20 17 23 | 53 | 39 | SS-10 | 2.25 | - | - | - | - | - | - | - | - | 14 | A-4a (V) | |
| | | | 17 20 28 | 63 | 28 | SS-11 | 2.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | W 829.2 | | | | | | | | | | | | | | | | |
| | | | 4 4 6 | 13 | 100 | SS-12 | 1.00 | - | - | - | - | - | - | - | - | 17 | A-4a (V) | |
| | 827.2 | | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, GRAY AND BROWN, **GRAVEL WITH SAND AND SILT**, TRACE CLAY, MOIST | 824.7 | | 3 4 6 | 13 | 44 | SS-13 | - | - | - | - | - | - | - | - | - | 14 | A-2-4 (V) | |
| HARD, GRAY AND ORANGISH BROWN, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, SS-14 CONTAINS IRON STAINING, GLACIAL TILL, DAMP | | | 16 27 28 | 72 | 44 | SS-14 | 4.25 | 8 | 12 | 19 | 40 | 21 | 23 | 16 | 7 | 13 | A-4a (5) | |
| | | | 15 22 21 | 57 | 56 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | | 10 10 14 | 32 | 39 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 9 15 15 | 40 | 100 | SS-17 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | 812.7 | EOB | 12 15 17 | 42 | 50 | SS-18 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |

NOTES: GROUNDWATER ENCOUNTERED AT 30' DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:47 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.583 / 618 TOTAL | 34 / 69 TOTAL | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-015-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:11:57 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL004.dgn

PROJECT: FRA-71-19.10
TYPE: RETAINING WALL
PID: 109164 SFN:
START: 8/30/22 END: 8/30/22

DRILLING FIRM / OPERATOR: NEAS / CP
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1111+45, 52' LT.
ALIGNMENT: IR-71
ELEVATION: 860.9 (MSL) EOB: 46.5 ft.
LAT / LONG: 40.009098, -82.986941

EXPLORATION ID B-016-0-22
PAGE 1 OF 1

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **10.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 859.6 | | | | | | | | | | | | | | | | | |
| HARD, BROWNISH GRAY, **SILT AND CLAY**, SOME SAND, TRACE GRAVEL, SS-3 IS SLIGHTLY ORGANIC, DAMP | 848.9 | | 7 6 5 | 14 | 100 | SS-1 | 4.50 | 7 | 9 | 15 | 40 | 29 | 27 | 16 | 11 | 12 | A-6a (7) | |
| | | | 5 6 8 | 18 | 100 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-6a (V) | |
| | | | 7 9 10 | 25 | 100 | SS-3 | 4.50 | 5 | 8 | 16 | 40 | 31 | 31 | 18 | 13 | 15 | A-6a (8) | |
| | | | 2 7 8 | 20 | 100 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 15 | A-6a (V) | |
| HARD, BROWN AND DARK GRAY, **SILT AND CLAY**, SOME SAND, SOME STONE FRAGMENTS, DAMP | 846.4 | | 10 9 6 | 20 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 16 | A-6a (V) | |
| VERY STIFF TO HARD, BROWN AND DARK GRAY, **SILTY CLAY**, LITTLE SAND, TRACE GRAVEL, MOIST TO DAMP | 836.4 | | 4 7 7 | 18 | 100 | SS-6 | 4.50 | 1 | 5 | 12 | 36 | 46 | 40 | 18 | 22 | 20 | A-6b (13) | |
| | | | 5 6 7 | 17 | 100 | SS-7 | 4.25 | - | - | - | - | - | - | - | - | 14 | A-6b (V) | |
| | | | 4 4 3 | 9 | 100 | SS-8 | 2.50 | - | - | - | - | - | - | - | - | 16 | A-6b (V) | |
| | | | 3 4 4 | 11 | 100 | SS-9 | 2.25 | - | - | - | - | - | - | - | - | 17 | A-6b (V) | |
| LOOSE, GRAY, **GRAVEL AND STONE FRAGMENTS WITH SAND**, SOME SILT, TRACE CLAY, MOIST | 833.9 | | 5 3 3 | 8 | 100 | SS-10 | - | - | - | - | - | - | - | - | - | 13 | A-1-b (V) | |
| STIFF TO VERY STIFF, BROWN AND GRAY, **SANDY SILT**, LITTLE TO SOME CLAY, TRACE TO LITTLE GRAVEL, DAMP TO MOIST | 828.9 | W 830.9 | 4 3 4 | 9 | 100 | SS-11 | 2.00 | 17 | 15 | 19 | 31 | 18 | 23 | 14 | 9 | 12 | A-4a (3) | |
| | | | 3 2 5 | 9 | 100 | SS-12 | 1.25 | - | - | - | - | - | - | - | - | 16 | A-4a (V) | |
| MEDIUM DENSE, BROWN, **COARSE AND FINE SAND** SOME SILT, LITTLE GRAVEL, TRACE CLAY, MOIST | 826.4 | | 3 3 5 | 11 | 100 | SS-13 | - | - | - | - | - | - | - | - | - | 16 | A-3a (V) | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | 814.4 | EOB | 7 8 10 | 24 | 100 | SS-14 | 4.50 | 9 | 9 | 13 | 43 | 26 | 26 | 16 | 10 | 11 | A-4a (7) | |
| | | | 9 7 12 | 25 | 100 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 13 14 15 | 38 | 100 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | | 10 15 15 | 40 | 50 | SS-17 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | | 10 14 15 | 38 | 50 | SS-18 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |

NOTES: GROUNDWATER ENCOUNTERED AT 30' DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:47 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.584 / TOTAL 618 | 35 / TOTAL 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-016-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:12:35 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL005.dgn

PROJECT: FRA-71-19.10
TYPE: RETAINING WALL
PID: 109164 SFN:
START: 8/25/22 END: 8/30/22

DRILLING FIRM / OPERATOR: NEAS / CP
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1112+90, 52' LT.
ALIGNMENT: IR-71
ELEVATION: 861.8 (MSL) EOB: 46.5 ft.
LAT / LONG: 40.009371, -82.987304

EXPLORATION ID B-017-0-22



| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 861.8 | | | | | | | | | | | | | | | | | |
| | 860.3 | | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, BROWN AND GRAY, **SILT AND CLAY**, SOME SAND, TRACE GRAVEL, DAMP | | 1 | | | | | | | | | | | | | | | | |
| | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | 5 4 5 | 12 | 100 | SS-1 | 4.00 | 4 | 8 | 14 | 42 | 32 | 30 | 18 | 12 | 15 | A-6a (9) | |
| | | 4 | | | | | | | | | | | | | | | | |
| | | 5 | 5 10 6 | 21 | 100 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-6a (V) | |
| | | 6 | | | | | | | | | | | | | | | | |
| | | 7 | | | | | | | | | | | | | | | | |
| | | 8 | 4 4 7 | 14 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 16 | A-6a (V) | |
| | 852.3 | 9 | | | | | | | | | | | | | | | | |
| HARD, BROWN AND GRAY, **SILTY CLAY**, LITTLE SAND, TRACE GRAVEL, DAMP | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | 4 5 5 | 13 | 100 | SS-4 | 4.50 | 5 | 6 | 10 | 41 | 38 | 39 | 21 | 18 | 19 | A-6b (11) | |
| | | 12 | | | | | | | | | | | | | | | | |
| | | 13 | 3 5 7 | 16 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 21 | A-6b (V) | |
| | 847.3 | 14 | | | | | | | | | | | | | | | | |
| HARD, BROWN AND GRAY, **SANDY SILT**, SOME CLAY, LITTLE STONE FRAGMENTS, DAMP | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | 9 17 25 | 55 | 50 | SS-6 | 4.25 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | 17 | | | | | | | | | | | | | | | | |
| | | 18 | 4 15 22 | 49 | 44 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | 842.3 | 19 | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, BROWN AND GRAY, **STONE FRAGMENTS WITH SAND** SOME SILT, TRACE CLAY, CONTAINS A 2.25" STONE FRAGMENT, MOIST | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | 6 6 4 | 13 | 78 | SS-8 | - | - | - | - | - | - | - | - | - | 14 | A-1-b (V) | |
| | 839.8 | 22 | | | | | | | | | | | | | | | | |
| VERY STIFF, BROWN AND GRAY, **SILT AND CLAY**, SOME SAND, TRACE GRAVEL, TRACE IRON STAINING, DAMP | | 23 | 5 6 7 | 17 | 56 | SS-9 | 3.75 | 7 | 8 | 15 | 37 | 33 | 34 | 19 | 15 | 19 | A-6a (9) | |
| | | 24 | | | | | | | | | | | | | | | | |
| | | 25 | | | | | | | | | | | | | | | | |
| | | 26 | 19 8 8 | 21 | 100 | SS-10 | 2.50 | - | - | - | - | - | - | - | - | 13 | A-6a (V) | |
| | 834.8 | 27 | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, BROWN AND GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, DAMP | | 28 | 7 8 8 | 21 | 39 | SS-11 | 3.25 | 12 | 12 | 16 | 36 | 24 | 24 | 15 | 9 | 13 | A-4a (5) | |
| | | 29 | | | | | | | | | | | | | | | | |
| | | 30 | | | | | | | | | | | | | | | | |
| | | 31 | 4 10 9 | 25 | 100 | SS-12 | 4.50 | - | - | - | - | - | - | - | - | 15 | A-4a (V) | |
| | | 32 | | | | | | | | | | | | | | | | |
| | | 33 | 3 10 8 | 24 | 89 | SS-13 | 4.50 | 10 | 13 | 18 | 37 | 22 | 25 | 16 | 9 | 13 | A-4a (5) | |
| | | 34 | | | | | | | | | | | | | | | | |
| | | 35 | | | | | | | | | | | | | | | | |
| | | 36 | 7 10 11 | 28 | 100 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | 824.8 | 37 | | | | | | | | | | | | | | | | |
| VERY STIFF, BROWN AND GRAY, **SILT**, SOME SAND, LITTLE CLAY, TRACE GRAVEL, MOIST | | 38 | 6 9 16 | 33 | 100 | SS-15 | 3.75 | 2 | 5 | 17 | 57 | 19 | NP | NP | NP | 17 | A-4b (8) | |
| | 822.8 | 39 | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, BROWN AND GRAY, **COARSE AND FINE SAND**, SOME SILT, TRACE GRAVEL, TRACE CLAY, MOIST | | 40 | | | | | | | | | | | | | | | | |
| | | 41 | 6 8 14 | 29 | 100 | SS-16 | - | - | - | - | - | - | - | - | - | 16 | A-3a (V) | |
| | 819.8 | 42 | | | | | | | | | | | | | | | | |
| HARD, BROWN AND GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | 43 | 20 50/3" | - | 33 | SS-17 | 4.50 | - | - | - | - | - | - | - | - | 8 | A-4a (V) | |
| | | 44 | | | | | | | | | | | | | | | | |
| | | 45 | | | | | | | | | | | | | | | | |
| | | 46 | 10 15 18 | 43 | 44 | SS-18 | 4.50 | - | - | - | - | - | - | - | - | 8 | A-4a (V) | |
| | 815.3 | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:47 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1\ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.585 / TOTAL 618 | 36 / TOTAL 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-017-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:13:12 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL006.dgn

PROJECT: FRA-71-19.10
TYPE: RETAINING WALL
PID: 109164 SFN:
START: 8/25/22 END: 8/25/22

DRILLING FIRM / OPERATOR: NEAS / CP
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1117+30, 52' LT.
ALIGNMENT: IR-71
ELEVATION: 861.5 (MSL) EOB: 46.5 ft.
LAT / LONG: 40.010087, -82.988532

EXPLORATION ID B-018-0-22

PAGE 1 OF 1

| MATERIAL DESCRIPTION AND NOTES | ELEV. 861.5 | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 5.0" BASE (DRILLERS DESCRIPTION)** | 860.1 | 1 | | | | | | | | | | | | | | | | |
| HARD, BROWN, **SILT AND CLAY**, SOME SAND, TRACE TO LITTLE GRAVEL, DAMP TO MOIST | | 2 | 23 10 13 | 30 | 100 | SS-1 | 4.50 | 11 | 12 | 16 | 32 | 29 | 31 | 16 | 15 | 10 | A-6a (7) | |
| | | 3 | | | | | | | | | | | | | | | | |
| | | 4 | 9 10 13 | 30 | 100 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-6a (V) | |
| | | 5 | 10 13 20 | 43 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 20 | A-6a (V) | |
| | 855.5 | 6 | | | | | | | | | | | | | | | | |
| MEDIUM DENSE TO DENSE, GRAY, **STONE FRAGMENTS**, SOME SAND, TRACE SILT, TRACE CLAY, DAMP TO MOIST | | 7 | 17 19 15 | 45 | 33 | SS-4 | - | - | - | - | - | - | - | - | - | 12 | A-1-a (V) | |
| | | 8 | 15 17 9 | 34 | 6 | SS-5 | - | - | - | - | - | - | - | - | - | 19 | A-1-a (V) | |
| | | 9 | | | | | | | | | | | | | | | | |
| SS-6A CONTAINS A 2.0" STONE FRAGMENT | 850.5 | 10 | | | | | | | | | | | | | | | | |
| | | 11 | 10 12 7 | 25 | 44 | SS-6A | - | - | - | - | - | - | - | - | - | 12 | A-1-a (V) | |
| HARD, BROWNISH GRAY, **SILTY CLAY**, SOME SAND, TRACE GRAVEL, DAMP | | | | | | SS-6B | 4.50 | 5 | 9 | 14 | 39 | 33 | 38 | 21 | 17 | 20 | A-6b (10) | |
| | | 12 | | | | | | | | | | | | | | | | |
| | | 13 | 6 6 7 | 17 | 100 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 14 | A-6b (V) | |
| | 847.0 | 14 | | | | | | | | | | | | | | | | |
| HARD, BROWN MOTTLED WITH GRAY, **CLAY**, "AND" SILT, LITTLE SAND, TRACE GRAVEL, DAMP TO MOIST | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | 11 8 11 | 25 | 100 | SS-8 | 4.50 | 4 | 5 | 11 | 41 | 39 | 41 | 19 | 22 | 18 | A-7-6 (13) | |
| | | 17 | | | | | | | | | | | | | | | | |
| | | 18 | 1 4 5 | 12 | 100 | SS-9 | 4.25 | - | - | - | - | - | - | - | - | 23 | A-7-6 (V) | |
| | 842.0 | 19 | | | | | | | | | | | | | | | | |
| VERY STIFF, BROWN MOTTLED WITH ORANGISH BROWN AND GRAY, **CLAY**, "AND" SILT, TRACE TO LITTLE SAND, TRACE GRAVEL, IRON STAINING, MOIST | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | 3 4 6 | 13 | 100 | SS-10 | 3.00 | 1 | 2 | 9 | 40 | 48 | 47 | 21 | 26 | 25 | A-7-6 (16) | |
| | | 22 | | | | | | | | | | | | | | | | |
| | | 23 | 2 4 6 | 13 | 100 | SS-11 | 2.75 | - | - | - | - | - | - | - | - | 22 | A-7-6 (V) | |
| | 837.0 | 24 | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, BROWN AND BROWNISH GRAY, **SILT AND CLAY**, SOME SAND, TRACE TO LITTLE GRAVEL, DAMP | | 25 | | | | | | | | | | | | | | | | |
| | | 26 | 5 5 5 | 13 | 100 | SS-12 | 4.00 | 16 | 11 | 19 | 33 | 21 | 25 | 14 | 11 | 12 | A-6a (4) | |
| | | 27 | | | | | | | | | | | | | | | | |
| | | 28 | 4 5 5 | 13 | 100 | SS-13 | 3.75 | - | - | - | - | - | - | - | - | 13 | A-6a (V) | |
| | | 29 | | | | | | | | | | | | | | | | |
| | | 30 | | | | | | | | | | | | | | | | |
| | | 31 | 4 5 6 | 14 | 78 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 14 | A-6a (V) | |
| | 829.5 | 32 | | | | | | | | | | | | | | | | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, GLACIAL TILL, DAMP | | 33 | 4 5 8 | 17 | 89 | SS-15 | 4.50 | 0 | 10 | 15 | 43 | 32 | 26 | 16 | 10 | 12 | A-4a (8) | |
| | | 34 | | | | | | | | | | | | | | | | |
| | | 35 | | | | | | | | | | | | | | | | |
| | | 36 | 5 11 13 | 32 | 94 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 37 | | | | | | | | | | | | | | | | |
| | | 38 | 6 10 12 | 29 | 67 | SS-17 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 39 | | | | | | | | | | | | | | | | |
| | | 40 | | | | | | | | | | | | | | | | |
| | | 41 | 20 23 34 | 75 | 56 | SS-18 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 42 | | | | | | | | | | | | | | | | |
| | | 43 | 18 25 32 | 75 | 78 | SS-19 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 44 | | | | | | | | | | | | | | | | |
| | | 45 | | | | | | | | | | | | | | | | |
| | 815.0 | 46 | 12 16 20 | 47 | 67 | SS-20 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:48 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

SHEET P.586 TOTAL 618
SUBSET 37 TOTAL 69
PROJECT ID 109164
REVIEWER CH 08-28-23
DESIGNER ZM
DESIGN AGENCY NEAS National Engineering & Architectural Services Inc.

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-018-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:13:50 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL007.dgn

| | | | |
|---|---|---|---|
| PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / CP | DRILL RIG: CME 75T | STATION / OFFSET: 1118+85, 51' LT. |
| TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 |
| PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 860.0 (MSL) EOB: 46.5 ft. |
| START: 8/24/22 END: 8/24/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.010321, -82.988992 |

EXPLORATION ID: B-019-0-22
PAGE: 1 OF 1

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **10.0" ASPHALT AND 7.0" BASE (DRILLERS DESCRIPTION)** | 860.0 | | | | | | | | | | | | | | | | | |
| | 858.6 | | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, BROWN, **GRAVEL WITH SAND**, LITTLE SILT, TRACE CLAY, DAMP | 856.1 | 3 | 13 9 7 | 21 | 100 | SS-1 | - | 50 | 16 | 9 | 17 | 8 | NP | NP | NP | 6 | A-1-b (0) | |
| HARD, BROWN AND GRAY, **SANDY SILT**, SOME STONE FRAGMENTS, TRACE TO LITTLE CLAY, SS-2 CONTAINS NO INTACT SOIL FOR HP READINGS, DAMP | | 6 | 4 6 6 | 16 | 100 | SS-2 | - | 21 | 12 | 22 | 30 | 15 | 25 | 15 | 10 | 11 | A-4a (2) | |
| | | 8 | 4 7 9 | 21 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | 850.5 | | | | | | | | | | | | | | | | | |
| HARD, BROWN AND GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, DAMP | | 11 | 9 14 13 | 36 | 100 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 13 | 10 10 20 | 40 | 83 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 16 | 4 4 6 | 13 | 100 | SS-6 | 4.25 | - | - | - | - | - | - | - | - | 17 | A-4a (V) | |
| | 843.0 | | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, BROWN MOTTLED WITH GRAY AND ORANGISH BROWN, **SILTY CLAY**, SOME SAND, TRACE GRAVEL, IRON STAINING, DAMP | | 18 | 3 4 7 | 14 | 100 | SS-7 | 4.25 | 3 | 6 | 16 | 35 | 40 | 38 | 20 | 18 | 19 | A-6b (11) | |
| | | 21 | 2 3 6 | 12 | 100 | SS-8 | 4.00 | - | - | - | - | - | - | - | - | 18 | A-6b (V) | |
| | | 23 | 1 5 4 | 12 | 100 | SS-9 | 3.50 | - | - | - | - | - | - | - | - | 19 | A-6b (V) | |
| | 835.5 | | | | | | | | | | | | | | | | | |
| DENSE, BROWN, **GRAVEL WITH SAND AND SILT**, TRACE CLAY, DAMP | | 26 | 5 15 13 | 37 | 100 | SS-10 | - | - | - | - | - | - | - | - | - | 11 | A-2-4 (V) | |
| | 833.0 | | | | | | | | | | | | | | | | | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | 28 | 4 13 15 | 37 | 100 | SS-11 | 4.50 | 12 | 13 | 19 | 34 | 22 | 25 | 17 | 8 | 12 | A-4a (4) | |
| | | 31 | 4 5 7 | 16 | 100 | SS-12 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 33 | 3 5 7 | 16 | 100 | SS-13 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 36 | 6 10 10 | 26 | 100 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 38 | 4 8 11 | 25 | 100 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 41 | 9 14 18 | 42 | 28 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 43 | 7 16 17 | 43 | 50 | SS-17 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | 813.5 | 46 | 12 14 17 | 41 | 33 | SS-18 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:48 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.587 / 618 TOTAL | 38 / 69 TOTAL | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-019-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:14:27 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL008.dgn

PROJECT: FRA-71-19.10
TYPE: RETAINING WALL
PID: 109164 SFN:
START: 8/24/22 END: 8/24/22

DRILLING FIRM / OPERATOR: NEAS / CP
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1120+25, 53' LT.
ALIGNMENT: IR-71
ELEVATION: 858.2 (MSL) EOB: 41.5 ft.
LAT / LONG: 40.010529, -82.989411

EXPLORATION ID B-020-0-22



| MATERIAL DESCRIPTION AND NOTES | ELEV. 858.2 | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **10.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 856.9 | 1 | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, GRAY AND BROWN, **SANDY SILT**, LITTLE TO SOME CLAY, TRACE TO LITTLE GRAVEL, DAMP TO MOIST | | 2 | 10 10 9 | 25 | 100 | SS-1 | 4.50 | 11 | 17 | 20 | 35 | 17 | 21 | 14 | 7 | 9 | A-4a (3) | |
| | | 3 | | | | | | | | | | | | | | | | |
| | | 4 | 10 8 4 | 16 | 28 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 5 | 9 9 5 | 18 | 39 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| SS-4 AND SS-5 BECOME SLIGHTLY ORGANIC, CONTAIN TRACE ROOTS | | 6 | | | | | | | | | | | | | | | | |
| | | 7 | 6 7 9 | 21 | 67 | SS-4 | 4.00 | - | - | - | - | - | - | - | - | 22 | A-4a (V) | |
| | | 8 | 7 8 10 | 24 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 16 | A-4a (V) | |
| | | 9 | | | | | | | | | | | | | | | | |
| | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | 5 6 7 | 17 | 100 | SS-6 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 12 | | | | | | | | | | | | | | | | |
| | | 13 | 8 16 11 | 36 | 100 | SS-7 | 4.25 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | 843.7 | 14 | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, BROWN MOTTLED WITH ORANGISH BROWN AND GRAY, **SILTY CLAY**, LITTLE TO SOME SAND, TRACE GRAVEL, IRON STAINING, MOIST TO DAMP | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | 3 4 7 | 14 | 100 | SS-8 | 3.25 | 5 | 7 | 14 | 40 | 34 | 36 | 18 | 18 | 19 | A-6b (11) | |
| | | 17 | | | | | | | | | | | | | | | | |
| | | 18 | 3 5 7 | 16 | 100 | SS-9 | 4.25 | - | - | - | - | - | - | - | - | 19 | A-6b (V) | |
| | | 19 | | | | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | 4 5 11 | 21 | 100 | SS-10 | 4.00 | - | - | - | - | - | - | - | - | 17 | A-6b (V) | |
| | | 22 | | | | | | | | | | | | | | | | |
| | | 23 | 3 6 13 | 25 | 56 | SS-11 | 4.25 | - | - | - | - | - | - | - | - | 16 | A-6b (V) | |
| | 833.7 | 24 | | | | | | | | | | | | | | | | |
| HARD, BROWN BECOMING GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, GLACIAL TILL, DAMP | | 25 | | | | | | | | | | | | | | | | |
| | | 26 | 9 12 15 | 36 | 100 | SS-12 | 4.50 | 6 | 9 | 22 | 38 | 25 | 25 | 16 | 9 | 13 | A-4a (6) | |
| | | 27 | | | | | | | | | | | | | | | | |
| | | 28 | 8 13 14 | 36 | 100 | SS-13 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 29 | | | | | | | | | | | | | | | | |
| | | 30 | | | | | | | | | | | | | | | | |
| | | 31 | 10 11 14 | 33 | 56 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 32 | | | | | | | | | | | | | | | | |
| | | 33 | 10 12 13 | 33 | 67 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 34 | | | | | | | | | | | | | | | | |
| | | 35 | | | | | | | | | | | | | | | | |
| | | 36 | 13 15 19 | 45 | 83 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 37 | | | | | | | | | | | | | | | | |
| | | 38 | 12 13 20 | 43 | 67 | SS-17 | 4.50 | - | - | - | - | - | - | - | - | 8 | A-4a (V) | |
| | | 39 | | | | | | | | | | | | | | | | |
| | | 40 | | | | | | | | | | | | | | | | |
| | 816.7 | 41 EOB | 13 14 17 | 41 | 100 | SS-18 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:48 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.588 / TOTAL 618 | 39 / TOTAL 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

# GEOTECHNICAL PROFILE - ROADWAY
## BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
## BORING LOG B-020-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:15:04 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL009.dgn

PROJECT: FRA-71-19.10
TYPE: RETAINING WALL
PID: 109164 SFN:
START: 8/23/22 END: 8/23/22

DRILLING FIRM / OPERATOR: NEAS / CP
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1121+86, 56' LT.
ALIGNMENT: IR-71
ELEVATION: 856.2 (MSL) EOB: 41.5 ft.
LAT / LONG: 40.010763, -82.989898

EXPLORATION ID B-021-0-22
PAGE 1 OF 1

| MATERIAL DESCRIPTION AND NOTES | ELEV. 856.2 | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **11.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 854.8 | | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, BROWN AND GRAY, **GRAVEL WITH SAND AND SILT**, TRACE CLAY, DAMP | 851.7 | | 12 6 5 | 14 | 100 | SS-1 | - | 29 | 26 | 14 | 21 | 10 | 26 | 16 | 10 | 10 | A-2-4 (0) | |
| HARD, BROWN AND GRAY, **SANDY SILT**, SOME CLAY, LITTLE GRAVEL, DAMP TO MOIST | | | 5 6 9 | 20 | 100 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 17 | A-4a (V) | |
| | | | 2 7 7 | 18 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 9 9 8 | 22 | 100 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 5 6 7 | 17 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 18 | A-4a (V) | |
| | 841.7 | | | | | | | | | | | | | | | | | |
| DENSE, BROWN, **SANDY SILT**, SOME GRAVEL, LITTLE CLAY, DAMP | 839.2 | | 9 16 20 | 47 | 100 | SS-6 | - | 27 | 15 | 14 | 27 | 17 | NP | NP | NP | 11 | A-4a (2) | |
| VERY STIFF TO HARD, BROWN, **SANDY SILT**, SOME GRAVEL, LITTLE CLAY, DAMP | | | 11 7 10 | 22 | 100 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 5 6 6 | 16 | 100 | SS-8 | 3.75 | - | - | - | - | - | - | - | - | 16 | A-4a (V) | |
| | 834.2 | | | | | | | | | | | | | | | | | |
| HARD, BROWN, **SILT AND CLAY**, SOME SAND, LITTLE GRAVEL, DAMP | 831.7 | | 4 6 7 | 17 | 100 | SS-9 | 4.50 | 14 | 10 | 14 | 36 | 26 | 28 | 17 | 11 | 12 | A-6a (6) | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | | 9 10 14 | 32 | 100 | SS-10 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 8 10 12 | 29 | 100 | SS-11 | 4.50 | 7 | 9 | 14 | 44 | 26 | 25 | 16 | 9 | 10 | A-4a (7) | |
| | | | 12 15 16 | 41 | 33 | SS-12 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | | 10 12 19 | 41 | 50 | SS-13 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | W 821.2 | | | | | | | | | | | | | | | | |
| | | | 15 22 30 | 68 | 67 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 12 25 35 | 79 | 83 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 17 26 37 | 83 | 100 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | 814.7 | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER ENCOUNTERED AT 35' DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:48 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.589 | 618 | 40 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

# GEOTECHNICAL PROFILE - ROADWAY
## BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
## BORING LOG B-021-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:15:41 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL010.dgn

PROJECT: FRA-71-19.10
TYPE: RETAINING WALL
PID: 109164 SFN:
START: 8/23/22 END: 8/23/22

DRILLING FIRM / OPERATOR: NEAS / CP
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1123+32, 61' LT.
ALIGNMENT: IR-71
ELEVATION: 854.5 (MSL) EOB: 41.5 ft.
LAT / LONG: 40.010975, -82.990345

EXPLORATION ID B-022-0-22

PAGE 1 OF 1

| MATERIAL DESCRIPTION AND NOTES | ELEV. 854.5 | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 5.0" BASE (DRILLERS DESCRIPTION)** | 853.1 | 1 | | | | | | | | | | | | | | | | |
| **UNCONTROLLED FILL** | 852.0 | 2 | 10 6 5 | 14 | 17 | SS-1 | - | - | - | - | - | - | - | - | - | 4 | UCF (V) | |
| HARD, GRAY AND BROWN, **SILT AND CLAY**, SOME SAND, TRACE TO LITTLE GRAVEL, DAMP | | 3 | 7 7 10 | 22 | 67 | SS-2 | 4.50 | 11 | 13 | 17 | 34 | 25 | 27 | 16 | 11 | 12 | A-6a (5) | |
| | | 4 | | | | | | | | | | | | | | | | |
| | | 5 | 4 5 6 | 14 | 44 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-6a (V) | |
| | | 6 | 5 5 6 | 14 | 39 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-6a (V) | |
| | | 7 | | | | | | | | | | | | | | | | |
| | | 8 | 4 7 8 | 20 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-6a (V) | |
| | 842.5 | 9 | | | | | | | | | | | | | | | | |
| HARD, BROWN AND GRAY, **CLAY**, SOME SILT, LITTLE SAND, TRACE GRAVEL, MOIST | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | 4 4 7 | 14 | 100 | SS-6 | 4.50 | - | - | - | - | - | - | - | - | 15 | A-6a (V) | |
| | 840.0 | 12 | | | | | | | | | | | | | | | | |
| HARD, BROWN, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, DAMP | | 13 | 2 4 7 | 14 | 100 | SS-7 | 4.50 | 2 | 4 | 12 | 31 | 51 | 53 | 22 | 31 | 25 | A-7-6 (19) | |
| | | 14 | | | | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | 11 10 14 | 32 | 100 | SS-8 | 4.50 | 5 | 13 | 16 | 36 | 30 | 27 | 17 | 10 | 14 | A-4a (6) | |
| | 837.5 | 17 | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, BROWN, **SILT**, SOME SAND, LITTLE CLAY, TRACE GRAVEL, WET | | 18 | 4 4 7 | 14 | 100 | SS-9 | - | 2 | 4 | 29 | 52 | 13 | NP | NP | NP | 20 | A-4b (6) | |
| | 835.0 | 19 | | | | | | | | | | | | | | | | |
| HARD, GRAY, **SANDY SILT**, "AND" CLAY, TRACE GRAVEL, GLACIAL TILL, DAMP | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | 4 5 7 | 16 | 100 | SS-10 | 4.50 | 5 | 6 | 7 | 41 | 41 | 28 | 18 | 10 | 18 | A-4a (8) | |
| | | 22 | | | | | | | | | | | | | | | | |
| | | 23 | 3 6 6 | 16 | 100 | SS-11 | 4.25 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | 830.0 | 24 | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, GRAY, **GRAVEL WITH SAND** TRACE SILT, TRACE CLAY, GLACIAL TILL, WET | | 25 | | | | | | | | | | | | | | | | |
| | | 26 | 5 5 7 | 16 | 100 | SS-12 | - | 4 | 46 | 35 | 10 | 5 | NP | NP | NP | 18 | A-1-b (0) | |
| | | 27 | | | | | | | | | | | | | | | | |
| | | 28 | 5 6 7 | 17 | 100 | SS-13 | - | - | - | - | - | - | - | - | - | 15 | A-1-b (V) | |
| | | 29 | | | | | | | | | | | | | | | | |
| | | 30 | | | | | | | | | | | | | | | | |
| | | 31 | 7 8 10 | 24 | 100 | SS-14 | - | - | - | - | - | - | - | - | - | 21 | A-1-b (V) | |
| | 822.5 | 32 | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, GRAY, **GRAVEL WITH SAND** TRACE SILT, TRACE CLAY, GLACIAL TILL, MOIST | | 33 | | | | | | | | | | | | | | | | |
| | | 34 | 8 8 12 | 26 | 100 | SS-15 | - | 45 | 29 | 13 | 10 | 3 | NP | NP | NP | 12 | A-1-b (0) | |
| | 819.3 | 35 | | | | | | | | | | | | | | | | |
| STIFF TO HARD, GRAY, **SILT AND CLAY**, SOME SAND, LITTLE GRAVEL, GLACIAL TILL, DAMP | | 36 | 4 5 7 | 16 | 50 | SS-16 | 2.00 | - | - | - | - | - | - | - | - | 17 | A-6a (V) | |
| | | 37 | | | | | | | | | | | | | | | | |
| | | 38 | 2 6 8 | 18 | 39 | SS-17 | 4.50 | 13 | 12 | 13 | 35 | 27 | 28 | 17 | 11 | 12 | A-6a (6) | |
| | | 39 | | | | | | | | | | | | | | | | |
| | | 40 | | | | | | | | | | | | | | | | |
| | 813.0 | 41 | 8 13 15 | 37 | 100 | SS-18 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-6a (V) | |
| | | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:48 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.590 | 618 | 41 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-022-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:16:19 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL011.dgn

| | | | | |
|---|---|---|---|---|
| PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / CP | DRILL RIG: CME 75T | STATION / OFFSET: 1124+78, 65' LT. | EXPLORATION ID B-023-0-22 |
| TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | |
| PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 853.5 (MSL) EOB: 41.5 ft. | PAGE 1 OF 1 |
| START: 8/22/22 END: 8/22/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.011198, -82.990790 | |

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **10.0" ASPHALT AND 5.0" BASE (DRILLERS DESCRIPTION)** | 853.5 | | | | | | | | | | | | | | | | | |
| | 852.2 | | | | | | | | | | | | | | | | | |
| HARD, GRAY AND BROWN, **SILT AND CLAY**, SOME SAND, SOME GRAVEL, DAMP | | 1 | | | | | | | | | | | | | | | | |
| | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | 17 6 7 | 17 | 100 | SS-1 | 4.50 | 22 | 14 | 12 | 29 | 23 | 30 | 16 | 14 | 8 | A-6a (5) | |
| | 849.0 | 4 | | | | | | | | | | | | | | | | |
| HARD, GRAY, **SILTY CLAY**, SOME SAND, TRACE GRAVEL, DAMP | | 5 | | | | | | | | | | | | | | | | |
| | | 6 | 3 4 4 | 11 | 100 | SS-2 | 4.50 | 8 | 10 | 15 | 34 | 33 | 34 | 18 | 16 | 14 | A-6b (9) | |
| | 846.5 | 7 | | | | | | | | | | | | | | | | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, DAMP | | 8 | 50 | - | 50 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | 844.0 | 9 | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, GRAY AND BROWN, **CLAY**, SOME SILT, SOME SAND, TRACE GRAVEL, GLACIAL TILL, MOIST TO DAMP | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | 3 3 5 | 11 | 100 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 21 | A-7-6 (V) | |
| | | 12 | | | | | | | | | | | | | | | | |
| | | 13 | 2 2 5 | 9 | 100 | SS-5 | 3.25 | 7 | 7 | 16 | 32 | 38 | 41 | 20 | 21 | 21 | A-7-6 (12) | |
| | | 14 | | | | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | 2 3 4 | 9 | 100 | SS-6 | 2.25 | - | - | - | - | - | - | - | - | 23 | A-7-6 (V) | |
| | | 17 | | | | | | | | | | | | | | | | |
| | | 18 | 3 6 6 | 16 | 100 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 14 | A-7-6 (V) | |
| | 834.0 | 19 | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | 2 7 8 | 20 | 100 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 22 | W 831.0 | | | | | | | | | | | | | | | |
| | | 23 | 12 15 16 | 41 | 100 | SS-9 | 4.00 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 24 | | | | | | | | | | | | | | | | |
| | | 25 | | | | | | | | | | | | | | | | |
| | | 26 | 10 14 18 | 42 | 100 | SS-10 | 4.00 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | 27 | | | | | | | | | | | | | | | | |
| | | 28 | 14 18 15 | 43 | 100 | SS-11 | 4.00 | - | - | - | - | - | - | - | - | 17 | A-4a (V) | |
| | | 29 | | | | | | | | | | | | | | | | |
| | | 30 | | | | | | | | | | | | | | | | |
| | | 31 | 12 16 14 | 40 | 100 | SS-12 | 4.25 | 4 | 10 | 17 | 41 | 28 | 25 | 16 | 9 | 13 | A-4a (7) | |
| | | 32 | | | | | | | | | | | | | | | | |
| | | 33 | 11 16 23 | 51 | 100 | SS-13 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 34 | | | | | | | | | | | | | | | | |
| | | 35 | | | | | | | | | | | | | | | | |
| | | 36 | 10 18 20 | 50 | 50 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | 37 | | | | | | | | | | | | | | | | |
| | | 38 | 10 13 21 | 45 | 39 | SS-15 | 4.25 | - | - | - | - | - | - | - | - | 15 | A-4a (V) | |
| | | 39 | | | | | | | | | | | | | | | | |
| | | 40 | | | | | | | | | | | | | | | | |
| | 812.0 | 41 | 8 15 18 | 43 | 56 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER ENCOUNTERED AT 22.5' DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:48 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.591 | 618 | 42 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

# GEOTECHNICAL PROFILE - ROADWAY
## BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
## BORING LOG B-023-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:16:56 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL012.dgn

PROJECT: FRA-71-19.10
TYPE: RETAINING WALL
PID: 109164 SFN:
START: 8/22/22 END: 8/22/22

DRILLING FIRM / OPERATOR: NEAS / CP
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1126+31, 64' LT.
ALIGNMENT: IR-71
ELEVATION: 852.3 (MSL) EOB: 36.5 ft.
LAT / LONG: 40.011460, -82.991232

EXPLORATION ID B-024-0-22
PAGE 1 OF 1

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **11.0" ASPHALT AND 5.0" BASE (DRILLERS DESCRIPTION)** | 851.0 | | | | | | | | | | | | | | | | | |
| HARD, BROWN AND GRAY, **SANDY SILT**, LITTLE CLAY, LITTLE GRAVEL, DAMP | 849.8 | 1 | 19 14 7 | 28 | 39 | SS-1 | 4.50 | - | - | - | - | - | - | - | - | 8 | A-4a (V) | |
| HARD, BROWN AND GRAY, **SILTY CLAY**, SOME SAND, TRACE TO LITTLE GRAVEL, DAMP | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | 4 4 4 | 11 | 22 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-6b (V) | |
| | | 4 | | | | | | | | | | | | | | | | |
| | | 5 | 4 3 3 | 8 | 33 | SS-3 | 4.50 | 8 | 10 | 15 | 35 | 32 | 37 | 17 | 20 | 17 | A-6b (10) | |
| | | 6 | 4 4 4 | 11 | 100 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 14 | A-6b (V) | |
| | | 7 | | | | | | | | | | | | | | | | |
| | | 8 | 2 3 4 | 9 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-6b (V) | |
| | 842.8 | 9 | | | | | | | | | | | | | | | | |
| VERY STIFF, BROWN AND GRAY, **CLAY**, "AND" SILT, LITTLE SAND, TRACE GRAVEL, MOIST | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | 2 3 5 | 11 | 100 | SS-6 | 3.50 | 6 | 6 | 10 | 37 | 41 | 44 | 20 | 24 | 22 | A-7-6 (14) | |
| | 840.3 | 12 | | | | | | | | | | | | | | | | |
| HARD, BROWN BECOMING GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | 13 | 1 6 14 | 26 | 100 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | 14 | | | | | | | | | | | | | | | | |
| | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | 8 8 10 | 24 | 100 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | 17 | | | | | | | | | | | | | | | | |
| | | 18 | 6 15 15 | 40 | 100 | SS-9 | 4.50 | 9 | 11 | 17 | 38 | 25 | 26 | 16 | 10 | 11 | A-4a (6) | |
| | | 19 | | | | | | | | | | | | | | | | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | 8 11 13 | 32 | 100 | SS-10 | 4.50 | - | - | - | - | - | - | - | - | 14 | A-4a (V) | |
| | | 22 | | | | | | | | | | | | | | | | |
| | | 23 | 10 17 18 | 46 | 100 | SS-11 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 24 | | | | | | | | | | | | | | | | |
| | | 25 | | | | | | | | | | | | | | | | |
| | | 26 | 8 15 20 | 46 | 100 | SS-12 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 27 | | | | | | | | | | | | | | | | |
| | | 28 | 13 13 20 | 43 | 100 | SS-13 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 29 | | | | | | | | | | | | | | | | |
| | | 30 | | | | | | | | | | | | | | | | |
| | | 31 | 10 12 18 | 40 | 100 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 32 | | | | | | | | | | | | | | | | |
| | | 33 | 11 17 22 | 51 | 100 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 34 | | | | | | | | | | | | | | | | |
| | | 35 | | | | | | | | | | | | | | | | |
| | 815.8 | 36 | 10 20 20 | 53 | 100 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:48 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ



GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-024-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:17:33 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL013.dgn

PROJECT: FRA-71-19.10
TYPE: RETAINING WALL
PID: 109164 SFN:
START: 8/18/22 END: 8/18/22

DRILLING FIRM / OPERATOR: NEAS / J. HODGES
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1127+72, 66' LT.
ALIGNMENT: IR-71
ELEVATION: 851.3 (MSL) EOB: 35.0 ft.
LAT / LONG: 40.011712, -82.991626

EXPLORATION ID B-025-0-22



| MATERIAL DESCRIPTION AND NOTES | ELEV. 851.3 | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 5.0" BASE (DRILLERS DESCRIPTION)** | 849.9 | | | | | | | | | | | | | | | | | |
| HARD, GRAY AND BROWN, **SANDY SILT**, LITTLE TO SOME GRAVEL, LITTLE TO SOME CLAY, CONTAINS ASPHALT FRAGMENTS, DAMP | | 1 | 3 5 4 | 12 | 67 | SS-1 | 4.50 | 23 | 13 | 16 | 29 | 19 | 24 | 15 | 9 | 9 | A-4a (3) | |
| | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | | | | | | | | | | | | | | | | |
| | | 4 | 7 11 15 | 34 | 100 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 5 | | | | | | | | | | | | | | | | |
| | | 6 | | | | | | | | | | | | | | | | |
| | | 7 | 4 7 10 | 22 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | 843.3 | 8 | | | | | | | | | | | | | | | | |
| VERY STIFF, GRAY AND DARK BROWN, **SILT**, SOME CLAY, LITTLE SAND, TRACE GRAVEL, SLIGHTLY ORGANIC (LOI: 2.7%), MOIST | | 9 | 4 2 4 | 8 | 100 | SS-4 | 3.50 | 4 | 5 | 14 | 50 | 27 | 31 | 22 | 9 | 23 | A-4b (8) | |
| | 840.8 | 10 | | | | | | | | | | | | | | | | |
| VERY STIFF, BROWN, **SILTY CLAY**, SOME STONE FRAGMENTS, LITTLE SAND, DAMP | | 11 | | | | | | | | | | | | | | | | |
| | | 12 | 4 10 13 | 30 | 100 | SS-5 | 3.75 | 21 | 7 | 10 | 29 | 33 | 39 | 19 | 20 | 15 | A-6b (9) | |
| | 838.3 | 13 | | | | | | | | | | | | | | | | |
| HARD, BROWN, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, DAMP | | 14 | 8 8 15 | 30 | 100 | SS-6 | 4.50 | - | - | - | - | - | - | - | - | 14 | A-4a (V) | |
| | 835.8 | 15 | | | | | | | | | | | | | | | | |
| VERY STIFF, GRAY, **SANDY SILT**, SOME STONE FRAGMENTS, SOME SAND, CONTAINS NO INTACT SOIL FOR HP READINGS, GLACIAL TILL, DAMP | | 16 | | | | | | | | | | | | | | | | |
| | | 17 | 7 9 10 | 25 | 100 | SS-7 | - | 29 | 16 | 13 | 24 | 18 | 26 | 16 | 10 | 8 | A-4a (1) | |
| | 833.3 | 18 | | | | | | | | | | | | | | | | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL AND STONE FRAGMENTS, GLACIAL TILL, DAMP | | 19 | 9 14 12 | 34 | 39 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | | | | | | | | | | | | | | | | |
| | | 22 | 6 9 10 | 25 | 50 | SS-9 | 4.50 | 5 | 9 | 16 | 41 | 29 | 25 | 16 | 9 | 11 | A-4a (7) | |
| | | 23 | | | | | | | | | | | | | | | | |
| | | 24 | 5 10 12 | 29 | 44 | SS-10 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 25 | | | | | | | | | | | | | | | | |
| | | 26 | | | | | | | | | | | | | | | | |
| | | 27 | 15 16 18 | 45 | 33 | SS-11 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 28 | | | | | | | | | | | | | | | | |
| | | 29 | 20 21 17 | 50 | 33 | SS-12 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 30 | | | | | | | | | | | | | | | | |
| | | 31 | | | | | | | | | | | | | | | | |
| | | 32 | 8 10 13 | 30 | 44 | SS-13 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 33 | | | | | | | | | | | | | | | | |
| | | 34 | 9 14 14 | 37 | 33 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | 816.3 EOB | 35 | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:49 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.593 | 618 | 44 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-025-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:18:09 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL014.dgn

PROJECT: FRA-71-19.10
TYPE: RETAINING WALL
PID: 109164 SFN:
START: 8/18/22 END: 8/18/22

DRILLING FIRM / OPERATOR: NEAS / J. HODGES
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1129+19, 75' LT.
ALIGNMENT: IR-71
ELEVATION: 851.2 (MSL) EOB: 35.0 ft.
LAT / LONG: 40.011978, -82.992039

EXPLORATION ID B-026-0-22



| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 849.7 | | | | | | | | | | | | | | | | | |
| HARD, BROWNISH GRAY AND GRAY, **SANDY SILT**, LITTLE CLAY, LITTLE GRAVEL, DAMP | 845.2 | | 7 6 4 | 13 | 28 | SS-1 | 4.50 | 14 | 16 | 19 | 33 | 18 | 22 | 15 | 7 | 10 | A-4a (3) | |
| | | | 4 5 6 | 14 | 100 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 2 3 5 | 11 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| VERY STIFF, GRAY, **SILTY CLAY**, LITTLE TO SOME GRAVEL, SOME SAND, DAMP | 840.7 | | 3 3 5 | 11 | 100 | SS-4 | 4.00 | 27 | 9 | 12 | 27 | 25 | 33 | 17 | 16 | 14 | A-6b (6) | |
| | | | 3 1 2 | 4 | 100 | SS-5 | 2.75 | - | - | - | - | - | - | - | - | 13 | A-6b (V) | |
| VERY STIFF, BROWN AND BLACK, **SILT AND CLAY**, SOME SAND, TRACE GRAVEL, SLIGHTLY ORGANIC (LOI: 3.4%), MOIST | 838.2 | | 2 3 2 | 7 | 100 | SS-6 | 2.25 | 5 | 10 | 14 | 42 | 29 | 35 | 21 | 14 | 26 | A-6a (9) | |
| VERY STIFF TO HARD, BROWN MOTTLED WITH GRAY AND ORANGISH BROWN, **CLAY**, SOME SILT, LITTLE TO SOME SAND, TRACE GRAVEL, IRON STAINING, MOIST TO DAMP | 833.2 | | 3 4 9 | 17 | 100 | SS-7 | 3.00 | 8 | 4 | 10 | 30 | 48 | 54 | 22 | 32 | 25 | A-7-6 (19) | |
| | | | 3 5 6 | 14 | 100 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 15 | A-7-6 (V) | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | | 11 15 18 | 43 | 100 | SS-9 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 7 10 13 | 30 | 100 | SS-10 | 4.50 | 4 | 7 | 12 | 47 | 30 | 26 | 18 | 8 | 12 | A-4a (8) | |
| | | | 5 8 12 | 26 | 100 | SS-11 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 6 10 16 | 34 | 100 | SS-12 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 5 12 16 | 37 | 100 | SS-13 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | W 820.2 | 9 10 14 | 32 | 100 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | 816.2 | EOB | 10 15 16 | 41 | 100 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |

NOTES: GROUNDWATER ENCOUNTERED AT 31' DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:49 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.594 | 618 | 45 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

# GEOTECHNICAL PROFILE - ROADWAY
# BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
# BORING LOG B-026-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:18:46 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL015.dgn

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / J. HODGES | DRILL RIG: CME 75T | STATION / OFFSET: 1155+83, 67' LT. | EXPLORATION ID B-027-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | PAGE 1 OF 1
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 853.7 (MSL) EOB: 23.8 ft.
START: 8/17/22 END: 8/17/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.018791, -82.995292

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **11.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 853.7 | | | | | | | | | | | | | | | | | |
| VERY STIFF, BROWN AND DARK GRAY, **SILT AND CLAY**, "AND" SAND, SOME STONE FRAGMENTS, DAMP | 852.3 | | 4 2 1 | 4 | 56 | SS-1 | 3.00 | 24 | 23 | 13 | 23 | 17 | 31 | 19 | 12 | 14 | A-6a (2) | |
| STIFF, BROWN AND DARK GRAY, **SILTY CLAY**, SOME SAND, LITTLE STONE FRAGMENTS, MOIST | 851.2 | | 1 1 2 | 4 | 89 | SS-2 | 1.75 | 20 | 11 | 10 | 27 | 32 | 40 | 23 | 17 | 26 | A-6b (8) | |
| MEDIUM DENSE, DARK GRAY, **STONE FRAGMENTS WITH SAND**, SOME SILT, TRACE CLAY, IRON STAINING, DAMP | 848.2 | | 9 10 7 | 22 | 100 | SS-3 | - | - | - | - | - | - | - | - | - | 12 | A-1-b (V) | |
| MEDIUM DENSE TO DENSE, DARK GRAY, **STONE FRAGMENTS WITH SAND AND SILT**, TRACE CLAY, STONE FRAGMENTS ARE WEAK SHALE, DAMP TO MOIST | 845.7 | | 6 7 14 | 28 | 100 | SS-4 | - | 43 | 19 | 12 | 14 | 12 | NP | NP | NP | 11 | A-2-4 (0) | |
| | | | 5 7 8 | 20 | 100 | SS-5 | - | - | - | - | - | - | - | - | - | 19 | A-2-4 (V) | |
| | | | 5 8 22 | 40 | 100 | SS-6 | - | - | - | - | - | - | - | - | - | 21 | A-2-4 (V) | |
| | | | 4 9 8 | 22 | 100 | SS-7 | - | - | - | - | - | - | - | - | - | 13 | A-2-4 (V) | |
| | 835.2 | TR | | | | | | | | | | | | | | | | |
| **SHALE**, GRAY, SLIGHTLY WEATHERED, WEAK TO SLIGHTLY STRONG, FISSILE. | | | 50 | - | 50 | SS-8 | - | - | - | - | - | - | - | - | - | 4 | Rock (V) | |
| | | | 50 | - | 50 | SS-9 | - | - | - | - | - | - | - | - | - | 4 | Rock (V) | |
| | 829.9 | EOB | 50/4" | - | 50 | SS-10 | - | - | - | - | - | - | - | - | - | 3 | Rock (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / J. HODGES | DRILL RIG: CME 75T | STATION / OFFSET: 1157+31, 64' LT. | EXPLORATION ID B-028-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | PAGE 1 OF 1
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 854.9 (MSL) EOB: 23.8 ft.
START: 8/17/22 END: 8/17/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.019201, -82.995311

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **10.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 854.9 | | | | | | | | | | | | | | | | | |
| HARD, BROWNISH GRAY, **SANDY SILT**, SOME GRAVEL, LITTLE CLAY, DAMP | 853.6 | | 6 6 7 | 17 | 44 | SS-1 | 4.50 | 26 | 21 | 12 | 26 | 15 | 25 | 16 | 9 | 8 | A-4a (1) | |
| | 849.4 | | 2 1 3 | 5 | 39 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| MEDIUM DENSE, DARK BROWNISH GRAY, **STONE FRAGMENTS WITH SAND AND SILT**, TRACE CLAY, STONE FRAGMENTS ARE WEAK SHALE, DAMP | 846.9 | | 6 7 8 | 20 | 100 | SS-3 | - | 47 | 22 | 11 | 12 | 8 | 25 | 16 | 9 | 11 | A-2-4 (0) | |
| VERY STIFF, BROWNISH GRAY AND ORANGISH BROWN, **SILTY CLAY**, SOME SAND, SOME GRAVEL, IRON STAINING, DAMP | 844.4 | | 3 4 5 | 12 | 100 | SS-4 | 3.50 | 23 | 14 | 14 | 25 | 24 | 39 | 20 | 19 | 17 | A-6b (6) | |
| VERY STIFF, DARK GRAY, **SILTY CLAY**, SOME STONE FRAGMENTS, SOME SAND, STONE FRAGMENTS ARE WEAK SHALE, CONTAINS NO INTACT SOIL FOR HP READINGS, DAMP | 841.9 | | 2 3 12 | 20 | 100 | SS-5 | - | 35 | 18 | 11 | 18 | 18 | 40 | 23 | 17 | 15 | A-6b (2) | |
| DENSE, DARK GRAY, **STONE FRAGMENTS WITH SAND**, LITTLE SILT, TRACE CLAY, STONE FRAGMENTS ARE WEAK SHALE, DAMP | 839.4 | | 8 13 14 | 36 | 100 | SS-6 | - | - | - | - | - | - | - | - | - | 12 | A-1-b (V) | |
| HARD, DARK GRAY, **STONE FRAGMENTS WITH SAND, SILT, AND CLAY**, STONE FRAGMENTS ARE WEAK SHALE, DAMP | 836.4 | | 6 10 5 | 20 | 100 | SS-7 | 4.50 | 45 | 18 | 11 | 13 | 13 | 36 | 23 | 13 | 11 | A-2-6 (0) | |
| | | TR | | | | | | | | | | | | | | | | |
| **SHALE**, GRAY, HIGHLY WEATHERED, WEAK TO SLIGHTLY STRONG, SILTY. | | | 13 50/4" | - | 30 | SS-8 | - | - | - | - | - | - | - | - | - | - | Rock (V) | |
| | | | 50/4" | - | 75 | SS-9 | - | - | - | - | - | - | - | - | - | - | Rock (V) | |
| | 831.1 | EOB | 50/3" | - | 100 | SS-10 | - | - | - | - | - | - | - | - | - | - | Rock (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.595 | 46 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |
| TOTAL 618 | TOTAL 69 | | | | |

GEOTECHNICAL PROFILE - ROADWAY
BORING LOGS B-027-0-22 & B-028-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:19:21 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL016.dgn

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / J. HODGES | DRILL RIG: CME 75T | STATION / OFFSET: 1158+83, 65' LT. | EXPLORATION ID B-029-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | PAGE 1 OF 1
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 855.3 (MSL) EOB: 24.5 ft.
START: 8/17/22 END: 8/17/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.019619, -82.995336

| MATERIAL DESCRIPTION AND NOTES | ELEV. 855.3 | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **10.0" ASPHALT AND 7.0" BASE (DRILLERS DESCRIPTION)** | 853.9 | | | | | | | | | | | | | | | | | |
| HARD, BROWNISH GRAY, **SANDY SILT**, LITTLE TO SOME GRAVEL AND STONE FRAGMENTS, LITTLE TO SOME CLAY, DAMP | | 1 | 4 6 8 | 18 | 61 | SS-1 | 4.25 | 27 | 15 | 16 | 29 | 13 | 25 | 17 | 8 | 11 | A-4a (1) | |
| | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | | | | | | | | | | | | | | | | |
| | | 4 | 5 6 6 | 16 | 67 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 5 | | | | | | | | | | | | | | | | |
| | | 6 | 6 4 6 | 13 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 14 | A-4a (V) | |
| | | 7 | | | | | | | | | | | | | | | | |
| | | 8 | | | | | | | | | | | | | | | | |
| | | 9 | 5 5 9 | 18 | 100 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | | | | | | | | | | | | | | | | |
| | | 12 | 4 6 9 | 20 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | 13 | | | | | | | | | | | | | | | | |
| | | 14 | 14 8 9 | 22 | 44 | SS-6 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | | | | | | | | | | | | | | | | |
| | | 17 | 7 7 6 | 17 | 100 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | 837.3 | 18 | | | | | | | | | | | | | | | | |
| MEDIUM DENSE TO DENSE, GRAY, **STONE FRAGMENTS WITH SAND AND SILT**, TRACE CLAY, DAMP | | 19 | 3 7 10 | 22 | 78 | SS-8 | - | 46 | 21 | 10 | 13 | 10 | 31 | 21 | 10 | 8 | A-2-4 (0) | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | 7 12 17 | 38 | 33 | SS-9 | - | - | - | - | - | - | - | - | - | 12 | A-2-4 (V) | |
| | 832.3 | 22 | | | | | | | | | | | | | | | | |
| | | 23 | TR | | | | | | | | | | | | | | | |
| **SHALE**, GRAY, HIGHLY WEATHERED, WEAK TO SLIGHTLY STRONG, SILTY. | 830.8 | 24 | 16 50 | - | 58 | SS-10 | - | - | - | - | - | - | - | - | - | - | Rock (V) | |
| | | | EOB | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / J. HODGES | DRILL RIG: CME 75T | STATION / OFFSET: 1160+38, 66' LT. | EXPLORATION ID B-030-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | PAGE 1 OF 1
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 855.2 (MSL) EOB: 23.9 ft.
START: 8/16/22 END: 8/16/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.020046, -82.995352

| MATERIAL DESCRIPTION AND NOTES | ELEV. 855.2 | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **11.0" ASPHALT AND 5.0" BASE (DRILLERS DESCRIPTION)** | 853.9 | | | | | | | | | | | | | | | | | |
| HARD, GRAY AND BROWN, **SANDY SILT**, SOME CLAY, LITTLE TO SOME GRAVEL AND STONE FRAGMENTS, DAMP TO MOIST | | 1 | 4 4 3 | 9 | 22 | SS-1 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | | | | | | | | | | | | | | | | |
| | | 4 | 5 4 4 | 11 | 89 | SS-2 | 4.50 | 9 | 13 | 17 | 36 | 25 | 25 | 15 | 10 | 11 | A-4a (5) | |
| | | 5 | | | | | | | | | | | | | | | | |
| | | 6 | | | | | | | | | | | | | | | | |
| | | 7 | 4 8 6 | 18 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 8 | | | | | | | | | | | | | | | | |
| | | 9 | 4 3 3 | 8 | 22 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | | | | | | | | | | | | | | | | |
| | | 12 | 3 4 5 | 12 | 72 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 18 | A-4a (V) | |
| | 842.2 | 13 | | | | | | | | | | | | | | | | |
| HARD, GRAY AND BROWN, **SILT AND CLAY**, "AND" SAND, SOME STONE FRAGMENTS, CONTAINS A RELIC SHALE ROCK STRUCTURE, DAMP | | 14 | 5 11 32 | 57 | 100 | SS-6 | 4.50 | 22 | 21 | 15 | 24 | 18 | 38 | 25 | 13 | 13 | A-6a (2) | |
| | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | | | | | | | | | | | | | | | | |
| | 838.2 | 17 | 8 50/5" | - | 55 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-6a (V) | |
| | | 18 | TR | | | | | | | | | | | | | | | |
| **SHALE**, GRAY, HIGHLY WEATHERED, VERY WEAK TO WEAK, FISSILE. | | 19 | 50 | - | 67 | SS-8 | - | - | - | - | - | - | - | - | - | - | Rock (V) | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | 50 | - | 67 | SS-9 | - | - | - | - | - | - | - | - | - | - | Rock (V) | |
| | | 22 | | | | | | | | | | | | | | | | |
| | 831.3 | 23 | | | | | | | | | | | | | | | | |
| | | | EOB | 50/5" | - | 60 | SS-10 | - | - | - | - | - | - | - | - | - | Rock (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.596 | 618 | 47 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BORING LOGS B-029-0-22 & B-030-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:19:57 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL017.dgn

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / J. HODGES | DRILL RIG: CME 75T | STATION / OFFSET: 1161+80, 64' LT. | EXPLORATION ID B-031-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | PAGE 1 OF 1
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 854.4 (MSL) EOB: 25.0 ft.
START: 8/16/22 END: 8/16/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.020440, -82.995355

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 5.0" BASE (DRILLERS DESCRIPTION)** | 854.4 | | | | | | | | | | | | | | | | | |
| | 853.0 | | | | | | | | | | | | | | | | | |
| HARD, BROWN AND GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, CONTAINS BRICK FRAGMENTS, DAMP **(FILL)** | | 1 | 3 5 4 | 12 | 28 | SS-1 | 4.50 | 8 | 13 | 17 | 40 | 22 | 23 | 16 | 7 | 16 | A-4a (5) | |
| | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | | | | | | | | | | | | | | | | |
| | | 4 | 9 17 15 | 42 | 39 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 5 | | | | | | | | | | | | | | | | |
| | | 6 | | | | | | | | | | | | | | | | |
| | | 7 | 13 6 6 | 16 | 50 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 16 | A-4a (V) | |
| | 846.4 | | | | | | | | | | | | | | | | | |
| VERY STIFF, BROWN AND DARK GRAY, **CLAY**, SOME SILT, SOME SAND, LITTLE GRAVEL, SLIGHTLY ORGANIC, DAMP | | 8 | | | | | | | | | | | | | | | | |
| | | 9 | 5 4 3 | 9 | 83 | SS-4 | 2.50 | 17 | 11 | 11 | 31 | 30 | 41 | 21 | 20 | 20 | A-7-6 (9) | |
| | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | | | | | | | | | | | | | | | | |
| | | 12 | 3 4 3 | 9 | 100 | SS-5 | 2.50 | - | - | - | - | - | - | - | - | 18 | A-7-6 (V) | |
| | 841.4 | 13 | | | | | | | | | | | | | | | | |
| LOOSE, DARK GRAY, **STONE FRAGMENTS WITH SAND AND SILT**, TRACE CLAY, DAMP | | 14 | 6 4 3 | 9 | 100 | SS-6 | - | 53 | 22 | 10 | 9 | 6 | 33 | 25 | 8 | 8 | A-2-4 (0) | |
| | 838.9 | 15 | | | | | | | | | | | | | | | | |
| VERY STIFF, BROWN AND DARK GRAY, **SILT AND CLAY**, "AND" SAND, SOME STONE FRAGMENTS, CONTAINS NO INTACT SOIL FOR HP READINGS, DAMP | | 16 | | | | | | | | | | | | | | | | |
| | | 17 | 3 5 6 | 14 | 100 | SS-7 | - | 26 | 20 | 17 | 21 | 16 | 38 | 25 | 13 | 14 | A-6a (1) | |
| | 836.4 | 18 | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, DARK GRAY, **STONE FRAGMENTS WITH SAND**, LITTLE SILT, TRACE CLAY, DAMP | | 19 | 7 6 8 | 18 | 100 | SS-8 | - | - | - | - | - | - | - | - | - | 6 | A-1-b (V) | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | | | | | | | | | | | | | | | | |
| | | 22 | 6 7 6 | 17 | 33 | SS-9 | - | - | - | - | - | - | - | - | - | 7 | A-1-b (V) | |
| | | 23 | | | | | | | | | | | | | | | | |
| | | 24 | 9 6 4 | 13 | 39 | SS-10 | - | - | - | - | - | - | - | - | - | 9 | A-1-b (V) | |
| | 829.4 | EOB 25 | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / J. HODGES | DRILL RIG: CME 75T | STATION / OFFSET: 1163+36, 65' LT. | EXPLORATION ID B-032-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | PAGE 1 OF 1
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 853.1 (MSL) EOB: 25.0 ft.
START: 8/16/22 END: 8/16/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.020870, -82.995357

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 853.1 | | | | | | | | | | | | | | | | | |
| | 851.6 | | | | | | | | | | | | | | | | | |
| HARD, BROWNISH GRAY, **SANDY SILT**, LITTLE CLAY, LITTLE GRAVEL, DAMP **(FILL)** | 850.1 | 1 | 3 4 8 | 16 | 67 | SS-1 | 4.50 | 12 | 16 | 16 | 38 | 18 | 23 | 16 | 7 | 11 | A-4a (4) | |
| HARD, BROWN AND GRAY, **SILTY CLAY**, SOME SAND, LITTLE GRAVEL AND STONE FRAGMENTS, DAMP **(FILL)** | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | 2 5 7 | 16 | 72 | SS-2 | 4.50 | 20 | 10 | 13 | 30 | 27 | 35 | 18 | 17 | 13 | A-6b (7) | |
| | 847.6 | 4 | | | | | | | | | | | | | | | | |
| HARD, BROWN AND GRAY, **SILT AND CLAY**, SOME STONE FRAGMENTS, SOME SAND, DAMP **(FILL)** | | 5 | | | | | | | | | | | | | | | | |
| | | 6 | 4 8 5 | 17 | 89 | SS-3 | 4.50 | 32 | 15 | 13 | 21 | 19 | 33 | 19 | 14 | 11 | A-6a (2) | |
| | | 7 | | | | | | | | | | | | | | | | |
| | | 8 | | | | | | | | | | | | | | | | |
| | | 9 | 3 4 4 | 11 | 78 | SS-4 | 4.50 | 35 | 16 | 12 | 21 | 16 | 31 | 19 | 12 | 10 | A-6a (1) | |
| | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | | | | | | | | | | | | | | | | |
| | | 12 | 3 2 3 | 7 | 56 | SS-5 | 4.25 | - | - | - | - | - | - | - | - | 13 | A-6a (V) | |
| | 840.1 | 13 | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, BROWNISH GRAY, **STONE FRAGMENTS WITH SAND AND SILT**, TRACE CLAY, CONTAINS CONCRETE FRAGMENTS, DAMP **(FILL)** | | 14 | 5 3 10 | 17 | 61 | SS-6 | - | 49 | 18 | 10 | 13 | 10 | 34 | 23 | 11 | 10 | A-2-6 (0) | |
| | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | | | | | | | | | | | | | | | | |
| | | 17 | 3 9 7 | 21 | 100 | SS-7 | - | - | - | - | - | - | - | - | - | 10 | A-2-6 (V) | |
| | 835.1 | 18 | | | | | | | | | | | | | | | | |
| STIFF TO HARD, BROWN AND GRAY, **SILTY CLAY**, SOME SAND, LITTLE TO SOME GRAVEL, DAMP | | 19 | 3 3 3 | 8 | 44 | SS-8 | 2.00 | 21 | 14 | 13 | 29 | 23 | 35 | 19 | 16 | 16 | A-6b (6) | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | | | | | | | | | | | | | | | | |
| | | 22 | 5 12 25 | 49 | 28 | SS-9 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-6b (V) | |
| | | 23 | | | | | | | | | | | | | | | | |
| | | 24 | 6 16 37 | 70 | 33 | SS-10 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-6b (V) | |
| | 828.1 | EOB 25 | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

| SHEET | TOTAL |
|---|---|
| P.597 | 618 |

| SUBSET | TOTAL |
|---|---|
| 48 | 69 |

PROJECT ID: 109164

| REVIEWER | DESIGNER |
|---|---|
| CH 08-28-23 | ZM |

DESIGN AGENCY: NEAS National Engineering & Architectural Services Inc.

GEOTECHNICAL PROFILE - ROADWAY
BORING LOGS B-031-0-22 & B-032-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:20:32 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL018.dgn

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / J. HODGES | DRILL RIG: CME 75T | STATION / OFFSET: 1186+56, 67' LT. | EXPLORATION ID B-033-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 850.9 (MSL) EOB: 25.0 ft. | PAGE 1 OF 1
START: 8/16/22 END: 8/16/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.027203, -82.994484

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GR | CS | FS | SI | CL | LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **10.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 850.9 / 849.6 | | | | | | | | | | | | | | | | | |
| LOOSE TO MEDIUM DENSE, BROWN, **GRAVEL WITH SAND AND SILT**, TRACE CLAY, DAMP **(FILL)** | 843.6 | | 8 9 9 | 24 | 28 | SS-1 | - | 31 | 29 | 11 | 19 | 10 | NP | NP | NP | 6 | A-2-4 (0) | |
| | | | 5 3 3 | 8 | 33 | SS-2 | - | - | - | - | - | - | - | - | - | 6 | A-2-4 (V) | |
| | | | 11 7 8 | 20 | 44 | SS-3 | - | - | - | - | - | - | - | - | - | 6 | A-2-4 (V) | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, DAMP | 840.4 | | 6 7 8 | 20 | 83 | SS-4 | 4.50 | 9 | 14 | 16 | 33 | 28 | 22 | 15 | 7 | 10 | A-4a (5) | |
| VERY DENSE, BROWN, **GRAVEL WITH SAND**, LITTLE SILT, TRACE CLAY, DAMP | 837.9 | | 10 22 23 | 59 | 100 | SS-5 | - | - | - | - | - | - | - | - | - | 11 | A-1-b (V) | |
| DENSE, GRAY, **SANDY SILT**, LITTLE CLAY, TRACE GRAVEL, GLACIAL TILL, MOIST | 835.4 | | 7 14 20 | 45 | 100 | SS-6 | - | 4 | 12 | 29 | 42 | 13 | NP | NP | NP | 14 | A-4a (4) | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | 825.9 | | 3 9 9 | 24 | 100 | SS-7 | 4.50 | 19 | 8 | 12 | 28 | 33 | 25 | 15 | 10 | 11 | A-4a (5) | |
| | | | 7 12 15 | 36 | 44 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | | 8 11 15 | 34 | 39 | SS-9 | 4.50 | - | - | - | - | - | - | - | - | 8 | A-4a (V) | |
| | | EOB | 7 13 16 | 38 | 28 | SS-10 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / J. HODGES | DRILL RIG: CME 75T | STATION / OFFSET: 1188+34, 66' LT. | EXPLORATION ID B-034-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 852.3 (MSL) EOB: 25.0 ft. | PAGE 1 OF 1
START: 8/15/22 END: 8/15/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.027684, -82.994456

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GR | CS | FS | SI | CL | LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 7.0" BASE (DRILLERS DESCRIPTION)** | 852.3 / 850.7 | | | | | | | | | | | | | | | | | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, LITTLE GRAVEL, DAMP | 849.3 | | 12 8 10 | 24 | 67 | SS-1 | 4.50 | 15 | 16 | 15 | 29 | 25 | 23 | 15 | 8 | 10 | A-4a (4) | |
| MEDIUM DENSE, GRAY, **GRAVEL WITH SAND AND SILT**, LITTLE CLAY, DAMP | 846.8 | | 6 6 7 | 17 | 28 | SS-2 | - | 44 | 16 | 10 | 17 | 13 | 22 | 15 | 7 | 6 | A-2-4 (0) | |
| DENSE, BROWN, **SANDY SILT**, LITTLE CLAY, TRACE GRAVEL, CONTAINS INTERBEDDED SILT SEAMS, MOIST | 844.3 | | 14 15 12 | 36 | 100 | SS-3 | - | 2 | 8 | 23 | 49 | 18 | NP | NP | NP | 16 | A-4a (6) | |
| VERY DENSE, GRAY, **STONE FRAGMENTS WITH SAND**, LITTLE SILT, TRACE GRAVEL, ENCOUNTER WITH LIMESTONE COBBLE, DAMP | 841.8 | | 40 38 21 | 78 | 50 | SS-4 | - | - | - | - | - | - | - | - | - | 6 | A-1-b (V) | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | 827.3 | | 12 12 13 | 33 | 100 | SS-5 | 4.50 | 14 | 14 | 16 | 30 | 26 | 23 | 14 | 9 | 10 | A-4a (4) | |
| | | | 25 23 10 | 43 | 28 | SS-6 | 4.50 | - | - | - | - | - | - | - | - | 7 | A-4a (V) | |
| | | | 6 6 9 | 20 | 89 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | | 6 9 11 | 26 | 44 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 6 8 8 | 21 | 100 | SS-9 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | EOB | 5 6 8 | 18 | 100 | SS-10 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

| SHEET | TOTAL | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|
| P.598 | 618 | 49 / 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BORING LOGS B-033-0-22 & B-034-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:21:08 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL019.dgn

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / J. HODGES | DRILL RIG: CME 75T | STATION / OFFSET: 1189+87, 66' LT. | EXPLORATION ID B-035-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | PAGE 1 OF 1
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 852.6 (MSL) EOB: 25.0 ft.
START: 8/15/22 END: 8/15/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.028097, -82.994452

| MATERIAL DESCRIPTION AND NOTES | ELEV. 852.6 | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **11.0" ASPHALT AND 7.0" BASE (DRILLERS DESCRIPTION)** | 851.1 | | | | | | | | | | | | | | | | | |
| VERY LOOSE TO MEDIUM DENSE, BROWN, **GRAVEL WITH SAND**, LITTLE SILT, TRACE CLAY, CONTAINS BRICK FRAGMENTS, DAMP TO MOIST **(FILL)** | 847.1 | 1 | 6 11 12 | 30 | 22 | SS-1 | - | - | - | - | - | - | - | - | - | 5 | A-1-b (V) | |
| | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | 2 1 2 | 4 | 28 | SS-2 | - | - | - | - | - | - | - | - | - | 12 | A-1-b (V) | |
| | | 4 | | | | | | | | | | | | | | | | |
| | | 5 | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, BROWNISH GRAY, **SANDY SILT**, LITTLE TO SOME GRAVEL, LITTLE TO SOME CLAY, DAMP | | 6 | 3 4 5 | 12 | 33 | SS-3 | 2.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | 7 | | | | | | | | | | | | | | | | |
| | | 8 | | | | | | | | | | | | | | | | |
| | | 9 | 3 3 7 | 13 | 100 | SS-4 | 4.50 | 21 | 14 | 16 | 30 | 19 | 21 | 14 | 7 | 10 | A-4a (3) | |
| | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | | | | | | | | | | | | | | | | |
| | | 12 | 2 2 2 | 5 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | 839.6 | 13 | | | | | | | | | | | | | | | | |
| STIFF TO HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | 14 | 2 2 3 | 7 | 83 | SS-6 | 2.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | | | | | | | | | | | | | | | | |
| | | 17 | 1 2 2 | 5 | 100 | SS-7 | 2.50 | 13 | 15 | 18 | 31 | 23 | 20 | 14 | 6 | 13 | A-4a (4) | |
| | | 18 | | | | | | | | | | | | | | | | |
| | | 19 | 1 2 3 | 7 | 100 | SS-8 | 2.25 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | | | | | | | | | | | | | | | | |
| | | 22 | 2 2 3 | 7 | 100 | SS-9 | 1.75 | - | - | - | - | - | - | - | - | 14 | A-4a (V) | |
| | | 23 | | | | | | | | | | | | | | | | |
| | 827.6 | 24 | | | | | | | | | | | | | | | | |
| | EOB | 25 | 6 8 12 | 26 | 100 | SS-10 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-

PROJECT: FRA-71-19.10 | DRILLING FIRM / OPERATOR: NEAS / J. HODGES | DRILL RIG: CME 75T | STATION / OFFSET: 1191+32, 67' LT. | EXPLORATION ID B-036-0-22
TYPE: RETAINING WALL | SAMPLING FIRM / LOGGER: NEAS / J. HODGES | HAMMER: CME AUTOMATIC | ALIGNMENT: IR-71 | PAGE 1 OF 1
PID: 109164 SFN: | DRILLING METHOD: 3.25" HSA | CALIBRATION DATE: 1/24/22 | ELEVATION: 852.1 (MSL) EOB: 25.0 ft.
START: 8/15/22 END: 8/15/22 | SAMPLING METHOD: SPT | ENERGY RATIO (%): 79 | LAT / LONG: 40.028490, -82.994470

| MATERIAL DESCRIPTION AND NOTES | ELEV. 852.1 | DEPTHS | SPT/RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 850.6 | | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, BROWN, **GRAVEL WITH SAND**, LITTLE SILT, TRACE CLAY, CONTAINS BRICK FRAGMENTS, DAMP | | 1 | 5 7 6 | 17 | 28 | SS-1 | - | 48 | 28 | 8 | 11 | 5 | NP | NP | NP | 4 | A-1-b (0) | |
| | | 2 | | | | | | | | | | | | | | | | |
| | | 3 | | | | | | | | | | | | | | | | |
| SS-2 BECOMES WET | | 4 | 8 5 4 | 12 | 78 | SS-2 | - | - | - | - | - | - | - | - | - | 16 | A-1-b (V) | |
| | 846.6 | 5 | | | | | | | | | | | | | | | | |
| HARD, BROWNISH GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, DAMP | | 6 | 7 7 8 | 20 | 100 | SS-3 | 4.50 | 8 | 10 | 19 | 35 | 28 | 23 | 14 | 9 | 10 | A-4a (6) | |
| | | 7 | | | | | | | | | | | | | | | | |
| | | 8 | | | | | | | | | | | | | | | | |
| | | 9 | 5 9 12 | 28 | 100 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 10 | | | | | | | | | | | | | | | | |
| | | 11 | | | | | | | | | | | | | | | | |
| | | 12 | 8 12 14 | 34 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 13 | | | | | | | | | | | | | | | | |
| | | 14 | 7 9 10 | 25 | 100 | SS-6 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 15 | | | | | | | | | | | | | | | | |
| | | 16 | | | | | | | | | | | | | | | | |
| | | 17 | 5 8 9 | 22 | 100 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | 834.1 | 18 | | | | | | | | | | | | | | | | |
| HARD, BROWNISH GRAY AND GRAY, **CLAY**, LITTLE TO SOME SILT, TRACE SAND, TRACE GRAVEL, DAMP TO MOIST | | 19 | 4 5 7 | 16 | 100 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 24 | A-7-6 (V) | |
| | | 20 | | | | | | | | | | | | | | | | |
| | | 21 | | | | | | | | | | | | | | | | |
| | | 22 | 3 5 5 | 13 | 61 | SS-9 | 4.50 | 2 | 3 | 5 | 12 | 78 | 48 | 22 | 26 | 22 | A-7-6 (16) | |
| | | 23 | | | | | | | | | | | | | | | | |
| | 827.1 | 24 | | | | | | | | | | | | | | | | |
| | EOB | 25 | 3 4 6 | 13 | 100 | SS-10 | 4.50 | - | - | - | - | - | - | - | - | 24 | A-7-6 (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.599 | 618 | 50 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

# GEOTECHNICAL PROFILE - ROADWAY
# BORING LOGS B-035-0-22 & B-036-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:21:43 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL020.dgn

STANDARD ODOT SOIL BORING LOG (8.5 X 11) - OH DOT GDT - 7/21/23 13:53 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-

PROJECT: FRA-71-19.10
TYPE: RETAINING WALL
PID: 109164 SFN:
START: 8/15/22 END: 8/15/22

DRILLING FIRM / OPERATOR: NEAS / J. HODGES
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1192+90, 73' LT.
ALIGNMENT: IR-71
ELEVATION: 850.3 (MSL) EOB: 25.0 ft.
LAT / LONG: 40.028915, -82.994522

EXPLORATION ID B-037-0-22

PAGE 1 OF 1

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 7.0" BASE (DRILLERS DESCRIPTION)** | 850.3 | | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, BROWN, **GRAVEL WITH SAND**, LITTLE SILT, TRACE CLAY, DAMP **(FILL)** | 848.7 | | 7 11 7 | 24 | 44 | SS-1 | - | - | - | - | - | - | - | - | - | 4 | A-1-b (V) | |
| VERY STIFF TO HARD, GRAY, **SANDY SILT**, LITTLE TO SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | 847.3 | | 2 3 2 | 7 | 100 | SS-2 | 2.50 | 11 | 16 | 20 | 34 | 19 | 19 | 14 | 5 | 12 | A-4a (4) | |
| | | | 4 1 3 | 5 | 100 | SS-3 | 2.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 4 8 8 | 21 | 100 | SS-4 | 4.25 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 6 9 14 | 30 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 6 13 15 | 37 | 100 | SS-6 | 4.50 | 8 | 14 | 20 | 31 | 27 | 21 | 14 | 7 | 9 | A-4a (5) | |
| | | | 8 10 11 | 28 | 100 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 6 17 22 | 51 | 100 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | | 8 15 23 | 50 | 100 | SS-9 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | 825.3 | EOB | 8 18 25 | 57 | 100 | SS-10 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.600 TOTAL 618 | 51 TOTAL 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BORING LOG B-037-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:22:05 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL021.dgn

PROJECT: FRA-71-19.10
TYPE: BRIDGE
PID: 109164 SFN:
START: 9/7/22 END: 9/7/22

DRILLING FIRM / OPERATOR: NEAS / CP
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1311+83, 70' LT.
ALIGNMENT: IR-71
ELEVATION: 895.5 (MSL) EOB: 61.5 ft.
LAT / LONG: 40.061323, -82.998253

EXPLORATION ID B-043-0-22



| MATERIAL DESCRIPTION AND NOTES | ELEV. 895.5 | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **13.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 893.9 | | | | | | | | | | | | | | | | | |
| HARD, BROWN, **SILT AND CLAY**, SOME SAND, TRACE GRAVEL, DAMP TO MOIST | 888.5 | | 4 4 6 | 13 | 100 | SS-1 | 4.50 | 8 | 11 | 17 | 35 | 29 | 29 | 17 | 12 | 14 | A-6a (7) | |
| | | | 3 4 5 | 12 | 100 | SS-2 | 4.50 | - | - | - | - | - | - | - | - | 20 | A-6a (V) | |
| VERY STIFF, BROWN AND GRAY, **SILTY CLAY**, SOME SAND, TRACE GRAVEL, DAMP | 886.0 | | 2 4 7 | 14 | 100 | SS-3 | 3.50 | 4 | 9 | 15 | 38 | 34 | 35 | 18 | 17 | 16 | A-6b (10) | |
| HARD, BROWN, **SILT AND CLAY**, SOME SAND, LITTLE GRAVEL, SS-5 CONTAINS NO INTACT SOIL FOR HP READINGS, DAMP | 881.0 | | 4 3 2 | 7 | 50 | SS-4 | 4.25 | 15 | 14 | 13 | 34 | 24 | 32 | 19 | 13 | 15 | A-6a (6) | |
| | | | 3 5 7 | 16 | 17 | SS-5 | - | - | - | - | - | - | - | - | - | 15 | A-6a (V) | |
| VERY STIFF, BROWN MOTTLED WITH ORANGISH BROWN AND GRAY, **SILTY CLAY**, LITTLE SAND, TRACE GRAVEL, IRON STAINING, MOIST TO DAMP | 876.0 | | 2 3 7 | 13 | 100 | SS-6 | 2.25 | 8 | 6 | 12 | 35 | 39 | 40 | 20 | 20 | 22 | A-6b (12) | |
| | | | 2 3 8 | 14 | 100 | SS-7 | 2.50 | - | - | - | - | - | - | - | - | 15 | A-6b (V) | |
| VERY STIFF TO HARD, GRAY, **SANDY SILT**, LITTLE TO SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | | 3 5 7 | 16 | 100 | SS-8 | 4.25 | 8 | 13 | 17 | 38 | 24 | 22 | 15 | 7 | 12 | A-4a (5) | |
| | | | 2 4 8 | 16 | 100 | SS-9 | 4.00 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 11 17 13 | 40 | 100 | SS-10 | 4.25 | 13 | 16 | 16 | 36 | 19 | 21 | 14 | 7 | 9 | A-4a (4) | |
| | | | 10 7 8 | 20 | 100 | SS-11 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 8 8 19 | 36 | 100 | SS-12 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 13 19 24 | 57 | 100 | SS-13 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | | 19 24 22 | 61 | 100 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | | 12 27 30 | 75 | 17 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | 853.5 | | 35 50/5" | - | 27 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| VERY DENSE, GRAY, **SANDY SILT**, LITTLE CLAY, LITTLE GRAVEL, GLACIAL TILL, DAMP | 851.0 | | 15 28 32 | 79 | 56 | SS-17 | - | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, GLACIAL TILL, DAMP | | | 27 30 30 | 79 | 78 | SS-18 | 4.50 | 8 | 14 | 20 | 36 | 22 | 22 | 14 | 8 | 10 | A-4a (5) | |
| | | | 14 22 22 | 58 | 50 | SS-19 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | | 8 14 17 | 41 | 33 | SS-20 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:49 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.601 | 618 | 52 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-043-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:22:43 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL022.dgn

| PID: 109164 | SFN: | PROJECT: FRA-71-19.10 | STATION / OFFSET: 1311+83, 70' LT. | START: 9/7/22 | END: 9/7/22 | PG 2 OF 2 | B-043-0-22 |
|---|---|---|---|---|---|---|---|

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, GLACIAL TILL, DAMP *(continued)* | 835.5 | | 10 | | | | | | | | | | | | | | | |
| | 834.0 | EOB 61 | 20 20 | 53 | 44 | SS-21 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |

NOTES: GROUNDWATER NOT ENCOUNTERED DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:49 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

SHEET P.602 TOTAL 618
SUBSET 53 TOTAL 69
PROJECT ID 109164
REVIEWER CH 08-28-23
DESIGNER ZM
DESIGN AGENCY NEAS National Engineering & Architectural Services Inc.

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-043-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:23:17 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL023.dgn

PROJECT: FRA-71-19.10
TYPE: BRIDGE
PID: 109164 SFN:
START: 9/8/22 END: 9/8/22

DRILLING FIRM / OPERATOR: NEAS / J. HODGES
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1313+07, 80' RT.
ALIGNMENT: IR-71
ELEVATION: 878.2 (MSL) EOB: 46.5 ft.
LAT / LONG: 40.061567, -82.997636

EXPLORATION ID B-044-0-22



| MATERIAL DESCRIPTION AND NOTES | ELEV. 878.2 | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 876.7 | | | | | | | | | | | | | | | | | |
| HARD, BROWNISH GRAY, **SANDY SILT**, SOME CLAY, LITTLE GRAVEL, DAMP TO MOIST | | | 3 2 5 | 9 | 33 | SS-1 | 4.25 | 16 | 15 | 17 | 31 | 21 | 26 | 16 | 10 | 11 | A-4a (3) | |
| | | | 3 4 3 | 9 | 100 | SS-2 | 4.25 | - | - | - | - | - | - | - | - | 18 | A-4a (V) | |
| HARD, GRAY, **SANDY SILT**, LITTLE CLAY, TRACE TO LITTLE GRAVEL AND STONE FRAGMENTS, DAMP | 871.2 | | 6 7 14 | 28 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 9 22 33 | 72 | 100 | SS-4 | 4.50 | 12 | 12 | 21 | 37 | 18 | 20 | 14 | 6 | 8 | A-4a (4) | |
| | | | 7 21 26 | 62 | 78 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 8 | A-4a (V) | |
| | | | 7 39 43 | 108 | 100 | SS-6 | 4.50 | - | - | - | - | - | - | - | - | 8 | A-4a (V) | |
| | | | 18 38 42 | 105 | 100 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 8 | A-4a (V) | |
| | | | 6 12 14 | 34 | 61 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | W 855.7 | | | | | | | | | | | | | | | | |
| | | | 8 13 17 | 40 | 44 | SS-9 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| DENSE, GRAY, **GRAVEL AND STONE FRAGMENTS WITH SAND AND SILT**, TRACE CLAY, MOIST | 853.7 | | 17 22 16 | 50 | 100 | SS-10 | - | - | - | - | - | - | - | - | - | 12 | A-2-4 (V) | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, LITTLE GRAVEL, GLACIAL TILL, DAMP | 849.9 | | 10 15 16 | 41 | 100 | SS-11 | 4.25 | 11 | 12 | 16 | 35 | 26 | 24 | 15 | 9 | 11 | A-4a (5) | |
| | | | 8 9 18 | 36 | 100 | SS-12 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 7 12 14 | 34 | 100 | SS-13 | 4.25 | 11 | 11 | 16 | 36 | 26 | 23 | 15 | 8 | 12 | A-4a (5) | |
| | 831.7 | EOB | 9 13 16 | 38 | 100 | SS-14 | 4.25 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |

NOTES: GROUNDWATER ENCOUNTERED AT 22.5' DURING DRILLING. HOLE DID NOT CAVE.
ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED .5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:49 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.603 | 618 | 54 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

# GEOTECHNICAL PROFILE - ROADWAY
## BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
## BORING LOG B-044-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:23:55 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL024.dgn

PROJECT: FRA-71-19.10
TYPE: BRIDGE
PID: 109164 SFN:
START: 9/12/22 END: 9/12/22

DRILLING FIRM / OPERATOR: NEAS / J. HODGES
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1313+27, 86' LT.
ALIGNMENT: IR-71
ELEVATION: 874.4 (MSL) EOB: 61.5 ft.
LAT / LONG: 40.061727, -82.998195

EXPLORATION ID B-045-0-22
PAGE 1 OF 2

| MATERIAL DESCRIPTION AND NOTES | ELEV. 874.4 | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **10.0" ASPHALT AND 6.0" CONCRETE AND 7.0" BASE (DRILLERS DESCRIPTION)** | 872.4 | | | | | | | | | | | | | | | | | |
| MEDIUM DENSE, GRAY, **SANDY SILT**, SOME STONE FRAGMENTS, LITTLE CLAY, CONCRETE FRAGMENTS, DAMP | 869.9 | | 14 12 10 | 29 | 44 | SS-1 | - | 24 | 13 | 15 | 29 | 19 | NP | NP | NP | 8 | A-4a (3) | |
| VERY STIFF TO HARD, GRAY, **SANDY SILT**, LITTLE CLAY, LITTLE GRAVEL, DAMP | | | 3 4 3 | 9 | 100 | SS-2 | 3.25 | 11 | 14 | 20 | 37 | 18 | 19 | 14 | 5 | 11 | A-4a (4) | |
| | | | 2 3 3 | 8 | 100 | SS-3 | 3.00 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 8 18 23 | 54 | 100 | SS-4 | 4.50 | 15 | 19 | 23 | 29 | 14 | 19 | 14 | 5 | 7 | A-4a (2) | |
| | | | 4 7 15 | 29 | 100 | SS-5 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | | 12 15 24 | 51 | 83 | SS-6 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | | 3 17 18 | 46 | 28 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | 852.4 | | 8 31 34 | 86 | 33 | SS-8 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| VERY STIFF, GRAY, **SANDY SILT**, LITTLE CLAY, TRACE GRAVEL, WET | | W 851.4 | 6 13 17 | 40 | 100 | SS-9 | 4.00 | - | - | - | - | - | - | - | - | 18 | A-4a (V) | |
| DENSE, GRAY, **COARSE AND FINE SAND** LITTLE GRAVEL, TRACE SILT, TRACE CLAY, WET | 849.9 | | 5 11 14 | 33 | 100 | SS-10 | - | - | - | - | - | - | - | - | - | 19 | A-3a (V) | |
| HARD, GRAY, **SANDY SILT**, LITTLE TO SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | 847.4 | | 7 10 15 | 33 | 50 | SS-11 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 9 17 40 | 75 | 61 | SS-12 | 4.50 | 14 | 16 | 18 | 32 | 20 | 22 | 14 | 8 | 11 | A-4a (3) | |
| | | | 11 20 41 | 80 | 50 | SS-13 | 4.25 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 10 16 38 | 71 | 100 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 13 17 40 | 75 | 100 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 14 17 23 | 53 | 100 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 15 21 25 | 61 | 100 | SS-17 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 20 22 35 | 75 | 39 | SS-18 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 17 21 37 | 76 | 50 | SS-19 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | | 12 15 24 | 51 | 100 | SS-20 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:49 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.604 | 618 | 55 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-045-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:24:33 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL025.dgn

PID: 109164 | SFN: | PROJECT: FRA-71-19.10 | STATION / OFFSET: 1313+27, 86' LT. | START: 9/12/22 | END: 9/12/22 | PG 2 OF 2 | B-045-0-22

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| HARD, GRAY, **SANDY SILT**, LITTLE TO SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP *(continued)* | 814.4 | 61 | 12 18 25 | 57 | 100 | SS-21 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | 812.9 | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER ENCOUNTERED AT 23.0' DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED 0.5 BAG ASPHALT PATCH; PUMPED 50 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:49 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ



GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-24.46 OVER MORSE ROAD
BORING LOG B-045-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:25:07 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL026.dgn

PROJECT: FRA-71-19.10
TYPE: BRIDGE
PID: 109164 SFN:
START: 9/14/22 END: 9/14/22

DRILLING FIRM / OPERATOR: NEAS / J. HODGES
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1414+99, 61' RT.
ALIGNMENT: IR-71
ELEVATION: 931.9 (MSL) EOB: 91.5 ft.
LAT / LONG: 40.087293, -82.987079

EXPLORATION ID B-046-0-22
PAGE 1 OF 2

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 5.0" BASE (DRILLERS DESCRIPTION)** | 930.5 | | | | | | | | | | | | | | | | | |
| HARD, BROWN, **SILT AND CLAY**, SOME SAND, TRACE GRAVEL, DAMP | 922.4 | | 5 6 9 | 20 | 72 | SS-1 | 4.50 | 5 | 10 | 16 | 39 | 30 | 28 | 17 | 11 | 13 | A-6a (7) | |
| | | | 2 5 10 | 20 | 56 | SS-2 | 4.50 | 8 | 10 | 15 | 37 | 30 | 31 | 17 | 14 | 14 | A-6a (8) | |
| | | | 5 9 12 | 28 | 100 | SS-3 | 4.50 | - | - | - | - | - | - | - | - | 15 | A-6a (V) | |
| VERY STIFF, BROWNISH GRAY MOTTLED WITH GRAY, **CLAY**, "AND" SILT, LITTLE SAND, TRACE GRAVEL, DAMP | 919.9 | | 5 6 11 | 22 | 100 | SS-4 | 3.75 | 2 | 3 | 10 | 41 | 44 | 43 | 20 | 23 | 19 | A-7-6 (14) | |
| HARD, BROWN, **SILT AND CLAY**, SOME SAND, TRACE GRAVEL, DAMP | 917.4 | | 4 11 18 | 38 | 44 | SS-5 | 4.50 | 8 | 9 | 15 | 36 | 32 | 31 | 18 | 13 | 14 | A-6a (8) | |
| DENSE, BROWN AND GRAY, **STONE FRAGMENTS WITH SAND AND SILT**, TRACE CLAY, DAMP | 914.9 | | 13 12 13 | 33 | 17 | SS-6 | - | - | - | - | - | - | - | - | - | 10 | A-2-4 (V) | |
| VERY STIFF TO HARD, BROWNISH GRAY BECOMING DARK GRAY MOTTLED WITH GREENISH GRAY, **CLAY**, "AND" SILT, TRACE SAND, TRACE GRAVEL, SS-8 IS SLIGHTLY ORGANIC, DAMP TO MOIST | 907.4 | | 10 11 14 | 33 | 33 | SS-7 | 4.25 | - | - | - | - | - | - | - | - | 18 | A-7-6 (V) | |
| | | | 4 7 11 | 24 | 33 | SS-8 | 3.25 | 0 | 2 | 7 | 44 | 47 | 51 | 22 | 29 | 24 | A-7-6 (18) | |
| | | | 5 8 9 | 22 | 28 | SS-9 | 3.25 | - | - | - | - | - | - | - | - | 24 | A-7-6 (V) | |
| MEDIUM DENSE, BROWN AND ORANGISH BROWN, **GRAVEL WITH SAND AND SILT**, TRACE CLAY, IRON STAINING, MOIST | 904.9 | W 906.9 | 5 6 13 | 25 | 100 | SS-10 | - | - | - | - | - | - | - | - | - | 14 | A-2-4 (V) | |
| VERY STIFF, BROWN MOTTLED WITH ORANGISH BROWN AND GRAY, **SILT AND CLAY**, SOME SAND, LITTLE GRAVEL, IRON STAINING, DAMP | 902.4 | | 6 8 12 | 26 | 50 | SS-11 | 2.25 | 14 | 12 | 15 | 34 | 25 | 31 | 19 | 12 | 18 | A-6a (6) | |
| VERY STIFF TO HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, MOIST TO DAMP | | | 5 5 8 | 17 | 28 | SS-12 | 2.75 | - | - | - | - | - | - | - | - | 17 | A-4a (V) | |
| | | | 7 6 7 | 17 | 33 | SS-13 | 3.00 | 12 | 13 | 16 | 34 | 25 | 24 | 15 | 9 | 12 | A-4a (5) | |
| | | | 6 5 7 | 16 | 39 | SS-14 | 4.00 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 7 7 8 | 20 | 44 | SS-15 | 2.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 5 8 11 | 25 | 100 | SS-16 | 2.50 | - | - | - | - | - | - | - | - | 14 | A-4a (V) | |
| | | | 5 7 9 | 21 | 100 | SS-17 | 4.00 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 15 28 35 | 83 | 28 | SS-18 | 4.25 | 3 | 9 | 22 | 40 | 26 | 21 | 12 | 9 | 9 | A-4a (6) | |
| | | | 16 24 24 | 63 | 39 | SS-19 | 4.25 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | 873.6 | | | | | | | | | | | | | | | | | |
| DENSE, GRAY, **GRAVEL WITH SAND**, SOME SILT, TRACE CLAY, WET | | | | | | | | | | | | | | | | | | |

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:49 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-71-19.10.GPJ

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.606 / TOTAL 618 | 57 / TOTAL 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
BORING LOG B-046-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:25:45 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL027.dgn

PID: 109164 | SFN: | PROJECT: FRA-71-19.10 | STATION / OFFSET: 1414+99, 61' RT. | START: 9/14/22 | END: 9/14/22 | PG 2 OF 2 | B-046-0-22

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| DENSE, GRAY, **GRAVEL WITH SAND** SOME SILT, TRACE CLAY, WET *(continued)* | 871.9 | 61 | 6 12 14 | 34 | 39 | SS-20 | - | - | - | - | - | - | - | - | - | 15 | A-1-b (V) | |
| | 868.6 | 62 | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, GRAY, **SANDY SILT**, LITTLE CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | 63 | | | | | | | | | | | | | | | | |
| | | 64 | | | | | | | | | | | | | | | | |
| | | 65 | | | | | | | | | | | | | | | | |
| | | 66 | 7 13 17 | 40 | 33 | SS-21 | 4.00 | 13 | 20 | 19 | 29 | 19 | 20 | 14 | 6 | 12 | A-4a (3) | |
| | | 67 | | | | | | | | | | | | | | | | |
| | | 68 | | | | | | | | | | | | | | | | |
| | | 69 | | | | | | | | | | | | | | | | |
| | | 70 | | | | | | | | | | | | | | | | |
| | | 71 | 10 19 23 | 55 | 28 | SS-22 | 4.50 | - | - | - | - | - | - | - | - | 9 | A-4a (V) | |
| | | 72 | | | | | | | | | | | | | | | | |
| | | 73 | | | | | | | | | | | | | | | | |
| | | 74 | | | | | | | | | | | | | | | | |
| | | 75 | | | | | | | | | | | | | | | | |
| | | 76 | 9 21 26 | 62 | 44 | SS-23 | 4.50 | - | - | - | - | - | - | - | - | 7 | A-4a (V) | |
| | | 77 | | | | | | | | | | | | | | | | |
| | | 78 | | | | | | | | | | | | | | | | |
| | | 79 | | | | | | | | | | | | | | | | |
| | | 80 | | | | | | | | | | | | | | | | |
| | | 81 | 23 37 43 | 105 | 39 | SS-24 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | | 82 | | | | | | | | | | | | | | | | |
| | | 83 | | | | | | | | | | | | | | | | |
| | | 84 | | | | | | | | | | | | | | | | |
| | | 85 | | | | | | | | | | | | | | | | |
| | | 86 | 21 26 37 | 83 | 78 | SS-25 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 87 | | | | | | | | | | | | | | | | |
| | | 88 | | | | | | | | | | | | | | | | |
| | | 89 | | | | | | | | | | | | | | | | |
| | | 90 | | | | | | | | | | | | | | | | |
| | | 91 | 22 29 39 | 90 | 56 | SS-26 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | 840.4 | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER ENCOUNTERED AT 25.0' DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED 0.5 BAG ASPHALT PATCH; PUMPED 100 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:49 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.607 | 618 | 58 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
BORING LOG B-046-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:26:21 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL028.dgn

PROJECT: FRA-71-19.10
TYPE: BRIDGE
PID: 109164 SFN:
START: 9/15/22 END: 9/15/22

DRILLING FIRM / OPERATOR: NEAS / J. HODGES
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1416+08, 96' LT.
ALIGNMENT: IR-71
ELEVATION: 915.4 (MSL) EOB: 81.5 ft.
LAT / LONG: 40.087613, -82.987619

EXPLORATION ID B-047-0-22
PAGE 1 OF 2

| MATERIAL DESCRIPTION AND NOTES | ELEV. 915.4 | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **11.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 914.0 | | | | | | | | | | | | | | | | | |
| VERY STIFF, BROWN MOTTLED WITH GRAY AND ORANGISH BROWN, **CLAY**, "AND" SILT, LITTLE SAND, TRACE GRAVEL, IRON STAINING, MOIST | 910.9 | | 3 3 3 | 8 | 78 | SS-1 | 2.25 | 5 | 7 | 9 | 40 | 39 | 42 | 20 | 22 | 23 | A-7-6 (13) | |
| VERY STIFF, BROWN, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, DAMP | 908.4 | | 2 2 2 | 5 | 100 | SS-2 | 3.75 | 5 | 9 | 16 | 41 | 29 | 27 | 18 | 9 | 17 | A-4a (7) | |
| VERY STIFF, BROWN, **SANDY SILT**, LITTLE CLAY, LITTLE GRAVEL, DAMP | 905.9 | | 3 4 5 | 12 | 100 | SS-3 | 3.25 | 14 | 23 | 22 | 25 | 16 | 22 | 17 | 5 | 16 | A-4a (1) | |
| VERY STIFF, GRAY AND BROWN, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, DAMP | 903.4 | | 3 6 3 | 12 | 100 | SS-4 | 2.75 | 9 | 13 | 17 | 36 | 25 | 23 | 15 | 8 | 13 | A-4a (5) | |
| MEDIUM DENSE TO DENSE, GRAY, **STONE FRAGMENTS WITH SAND AND SILT**, LITTLE CLAY, WET | 898.4 | W 902.9 | 9 10 13 | 30 | 39 | SS-5 | - | - | - | - | - | - | - | - | - | 14 | A-2-4 (V) | |
| | | | 12 17 12 | 38 | 28 | SS-6 | - | - | - | - | - | - | - | - | - | 14 | A-2-4 (V) | |
| HARD, GRAY, **SANDY SILT**, SOME CLAY, LITTLE GRAVEL, CONTAINS NO INTACT SOIL FOR HP READINGS, DAMP | 895.9 | | 10 15 16 | 41 | 39 | SS-7 | - | 17 | 14 | 16 | 32 | 21 | 22 | 15 | 7 | 13 | A-4a (4) | |
| STIFF, GRAY, **SANDY SILT**, LITTLE CLAY, TRACE GRAVEL, CONTAINS INTERBEDDED SAND SEAMS, GLACIAL TILL, MOIST | 893.4 | | 11 17 20 | 49 | 83 | SS-8 | 1.25 | - | - | - | - | - | - | - | - | 16 | A-4a (V) | |
| HARD, GRAY, **SANDY SILT**, SOME GRAVEL, LITTLE CLAY, GLACIAL TILL, MOIST TO DAMP | 887.1 | | 10 14 22 | 47 | 33 | SS-9 | 4.50 | 31 | 11 | 14 | 29 | 15 | 22 | 14 | 8 | 15 | A-4a (2) | |
| | | | 13 16 25 | 54 | 39 | SS-10 | 4.25 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| VERY DENSE, GRAY, **SANDY SILT**, TRACE CLAY, TRACE GRAVEL, CONTAINS INTERBEDDED SAND SEAMS, GLACIAL TILL, DAMP | 882.1 | | 15 27 27 | 71 | 100 | SS-11 | - | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| HARD, GRAY, **SANDY SILT**, LITTLE TO SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | | 10 15 23 | 50 | 100 | SS-12 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | | 16 16 33 | 65 | 100 | SS-13 | 4.50 | 15 | 14 | 24 | 30 | 17 | 20 | 13 | 7 | 9 | A-4a (2) | |
| | | | 15 19 40 | 78 | 100 | SS-14 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 27 30 37 | 88 | 67 | SS-15 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | | 14 25 40 | 86 | 100 | SS-16 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:50 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.608 | 618 | 59 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR-161
BORING LOG B-047-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:26:59 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL029.dgn

PID: 109164 | SFN: | PROJECT: FRA-71-19.10 | STATION / OFFSET: 1416+08, 96' LT. | START: 9/15/22 | END: 9/15/22 | PG 2 OF 2 | B-047-0-22

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| HARD, GRAY, **SANDY SILT**, LITTLE TO SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP *(continued)* | 855.4 | 61 | 16 21 33 | 71 | 100 | SS-17 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 62 | | | | | | | | | | | | | | | | |
| | | 63 | | | | | | | | | | | | | | | | |
| | | 64 | | | | | | | | | | | | | | | | |
| | | 65 | | | | | | | | | | | | | | | | |
| | | 66 | 14 22 32 | 71 | 100 | SS-18 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 67 | | | | | | | | | | | | | | | | |
| | | 68 | | | | | | | | | | | | | | | | |
| | | 69 | | | | | | | | | | | | | | | | |
| | | 70 | | | | | | | | | | | | | | | | |
| | | 71 | 20 29 41 | 92 | 100 | SS-19 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | 72 | | | | | | | | | | | | | | | | |
| | | 73 | | | | | | | | | | | | | | | | |
| | | 74 | | | | | | | | | | | | | | | | |
| | | 75 | | | | | | | | | | | | | | | | |
| | | 76 | 15 18 37 | 72 | 100 | SS-20 | 4.50 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | 77 | | | | | | | | | | | | | | | | |
| | | 78 | | | | | | | | | | | | | | | | |
| | | 79 | | | | | | | | | | | | | | | | |
| | | 80 | | | | | | | | | | | | | | | | |
| | | 81 | 17 23 36 | 78 | 72 | SS-21 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| | 833.9 | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER ENCOUNTERED AT 12.5' DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED 0.5 BAG ASPHALT PATCH; PUMPED 100 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:50 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.609 / TOTAL 618 | 60 / TOTAL 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
BORING LOG B-047-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:27:34 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL030.dgn

PROJECT: FRA-71-19.10
TYPE: BRIDGE
PID: 109164 SFN:
START: 9/13/22 END: 9/13/22

DRILLING FIRM / OPERATOR: NEAS / J. HODGES
SAMPLING FIRM / LOGGER: NEAS / J. HODGES
DRILLING METHOD: 3.25" HSA
SAMPLING METHOD: SPT

DRILL RIG: CME 75T
HAMMER: CME AUTOMATIC
CALIBRATION DATE: 1/24/22
ENERGY RATIO (%): 79

STATION / OFFSET: 1417+11, 60' RT.
ALIGNMENT: IR-71
ELEVATION: 932.2 (MSL) EOB: 91.5 ft.
LAT / LONG: 40.087875, -82.987044

EXPLORATION ID B-048-0-22
PAGE 1 OF 2

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **12.0" ASPHALT AND 6.0" BASE (DRILLERS DESCRIPTION)** | 930.7 | | | | | | | | | | | | | | | | | |
| VERY STIFF TO HARD, BROWN, **SILT AND CLAY**, SOME SAND, TRACE GRAVEL, DAMP | 917.7 | | 1 4 3 | 9 | 56 | SS-1 | 3.00 | 9 | 9 | 15 | 37 | 30 | 31 | 17 | 14 | 16 | A-6a (8) | |
| | | | 4 9 10 | 25 | 100 | SS-2 | 4.25 | - | - | - | - | - | - | - | - | 15 | A-6a (V) | |
| | | | 5 5 8 | 17 | 100 | SS-3 | 3.75 | - | - | - | - | - | - | - | - | 15 | A-6a (V) | |
| | | | 5 6 8 | 18 | 100 | SS-4 | 4.50 | - | - | - | - | - | - | - | - | 17 | A-6a (V) | |
| | | | 4 7 8 | 20 | 100 | SS-5 | 4.25 | 6 | 9 | 15 | 37 | 33 | 33 | 18 | 15 | 16 | A-6a (9) | |
| HARD, BROWN MOTTLED WITH GRAY AND ORANGISH BROWN, **CLAY**, "AND" SILT, LITTLE SAND, TRACE GRAVEL, DAMP | 915.2 | | 4 6 7 | 17 | 100 | SS-6 | 4.50 | 2 | 4 | 11 | 39 | 44 | 44 | 21 | 23 | 19 | A-7-6 (14) | |
| HARD, BROWNISH GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, DAMP | 912.7 | | 3 9 13 | 29 | 100 | SS-7 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |
| VERY STIFF, BROWN MOTTLED WITH GRAY AND ORANGISH BROWN, **CLAY**, "AND" SILT, LITTLE SAND, TRACE GRAVEL, DAMP | 910.2 | | 2 3 7 | 13 | 100 | SS-8 | 3.75 | 2 | 5 | 14 | 38 | 41 | 42 | 20 | 22 | 20 | A-7-6 (13) | |
| STIFF TO HARD, BROWN BECOMING GRAY, **SANDY SILT**, SOME CLAY, TRACE GRAVEL, DAMP | 902.7 | | 4 6 7 | 17 | 100 | SS-9 | 4.50 | 5 | 12 | 19 | 37 | 27 | 26 | 16 | 10 | 14 | A-4a (6) | |
| | | | 2 3 4 | 9 | 100 | SS-10 | 4.25 | - | - | - | - | - | - | - | - | 15 | A-4a (V) | |
| | | | 2 2 3 | 7 | 100 | SS-11 | 1.25 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| MEDIUM DENSE, DARK GRAY, **GRAVEL WITH SAND**, TRACE SILT, TRACE CLAY, WET | 900.2 | W 902.2 | 17 17 6 | 30 | 39 | SS-12 | - | - | - | - | - | - | - | - | - | 16 | A-1-b (V) | |
| STIFF TO HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | | 8 5 6 | 14 | 100 | SS-13 | 1.75 | 17 | 14 | 17 | 31 | 21 | 22 | 14 | 8 | 12 | A-4a (3) | |
| | | | 2 2 4 | 8 | 100 | SS-14 | 1.75 | - | - | - | - | - | - | - | - | 14 | A-4a (V) | |
| | | | 3 5 8 | 17 | 100 | SS-15 | 2.25 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 3 7 9 | 21 | 100 | SS-16 | 4.25 | - | - | - | - | - | - | - | - | 12 | A-4a (V) | |
| | | | 7 7 10 | 22 | 100 | SS-17 | 4.25 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | | | 12 23 32 | 72 | 33 | SS-18 | 4.50 | 7 | 8 | 21 | 40 | 24 | 20 | 13 | 7 | 9 | A-4a (6) | |
| | | | 15 21 26 | 62 | 56 | SS-19 | 4.50 | - | - | - | - | - | - | - | - | 11 | A-4a (V) | |

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:50 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\FRA-71-19.10.GPJ

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.610 / TOTAL 618 | 61 / TOTAL 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
BORING LOG B-048-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:28:12 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL031.dgn

PID: 109164 | SFN: | PROJECT: FRA-71-19.10 | STATION / OFFSET: 1417+11, 60' RT. | START: 9/13/22 | END: 9/13/22 | PG 2 OF 2 | B-048-0-22

| MATERIAL DESCRIPTION AND NOTES | ELEV. | DEPTHS | SPT/ RQD | $N_{60}$ | REC (%) | SAMPLE ID | HP (tsf) | GRADATION (%) GR | CS | FS | SI | CL | ATTERBERG LL | PL | PI | WC | ODOT CLASS (GI) | BACK FILL |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| STIFF TO HARD, GRAY, **SANDY SILT**, SOME CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP *(continued)* | 872.2 | 61 | 13 22 29 | 67 | 78 | SS-20 | 4.50 | - | - | - | - | - | - | - | - | 8 | A-4a (V) | |
| | 868.9 | 62–63 | | | | | | | | | | | | | | | | |
| DENSE, GRAY, **GRAVEL AND STONE FRAGMENTS WITH SAND**, TRACE SILT, TRACE CLAY, GLACIAL TILL, WET | | 64–65 | | | | | | | | | | | | | | | | |
| | | 66 | 12 17 20 | 49 | 33 | SS-21 | - | - | - | - | - | - | - | - | - | 14 | A-1-b (V) | |
| | 863.9 | 67–68 | | | | | | | | | | | | | | | | |
| STIFF TO HARD, GRAY, **SANDY SILT**, LITTLE CLAY, TRACE TO LITTLE GRAVEL, GLACIAL TILL, DAMP | | 69–70 | | | | | | | | | | | | | | | | |
| | | 71 | 8 15 15 | 40 | 39 | SS-22 | 1.75 | 16 | 17 | 20 | 31 | 16 | 19 | 13 | 6 | 12 | A-4a (2) | |
| | | 72–75 | | | | | | | | | | | | | | | | |
| | | 76 | 21 27 38 | 86 | 44 | SS-23 | 4.25 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 77–80 | | | | | | | | | | | | | | | | |
| | | 81 | 20 32 40 | 95 | 50 | SS-24 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 82–85 | | | | | | | | | | | | | | | | |
| | | 86 | 19 31 41 | 95 | 100 | SS-25 | 4.50 | - | - | - | - | - | - | - | - | 10 | A-4a (V) | |
| | | 87–90 | | | | | | | | | | | | | | | | |
| | | 91 | 18 28 40 | 90 | 67 | SS-26 | 4.50 | - | - | - | - | - | - | - | - | 13 | A-4a (V) | |
| | 840.7 | EOB | | | | | | | | | | | | | | | | |

NOTES: GROUNDWATER ENCOUNTERED AT 30.0' DURING DRILLING. HOLE DID NOT CAVE.

ABANDONMENT METHODS, MATERIALS, QUANTITIES: PLACED 0.5 BAG ASPHALT PATCH; PUMPED 100 GAL. BENTONITE GROUT; SHOVELED SOIL CUTTINGS

STANDARD ODOT SOIL BORING LOG (11 X 17) - OH DOT.GDT - 7/21/23 13:50 - X:\ACTIVE PROJECTS\ACTIVE SOIL PROJECTS\1ARCHIVE BY YEAR\2022 ARCHIVE\FRA-71-19.10\GINT FILES\XFRA-71-19.10.GPJ

| SHEET | SUBSET | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|
| P.611 / TOTAL 618 | 62 / TOTAL 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
BORING LOG B-048-0-22

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:28:48 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL032.dgn

# LOG OF BORING NO DB-1

## OHIO INTERSTATE SYSTEM - DESIGN SECTION D-12

1½" I.D. Split-barrel
DATE 6-18, 6-19-57 TYPE 3" I.D. Shelby Tube
LOC S.R. 161 44+11 78' L

SURFACE ELEVATION 913.6

| DEPTH, FEET | Sample NO. | SAMPLES | BLOWS PER FOOT | DESCRIPTION | UNIT DRY WT. LB/CU.FT. | T.S.F. Penetrom. |
|---|---|---|---|---|---|---|
| 0 | 1 | | 6 | Topsoil-Dark brown silt & clay | | 1.2 |
| | 2 | | 13 | Firm to very stiff light brown silt and clay, some sand, trace gravel | | 2.5 |
| 10 | 3 | | 11 | Medium-dense to dense brown * coarse and fine sand, some silt, some gravel, trace clay, with black shale fragments | | 1.5 |
| | 4 | | 17 | | | 2.7 |
| 20 | 5 | | 25 | - @ 18.0' hard to very hard | | 4.5 |
| | 6 | | 28 | Very stiff dark gray sandy silt, some clay, little gravel with black shale fragments | | 4.5 |
| 30 | 7 | | 25 | | | 4.5 |
| | 8 | | 35 | | | 4.5 |
| 40 | 9 | | 35 | | | 4.0 |
| | 10 | | P | - @ 48.0' to 49.0' layer fine to medium gravel | 132 | 4.5 |
| | 10A | | | | | |
| 50 | 11 | | 59 | - @ 49.0' very hard to extremely hard | | 4.5+ |
| | 12 | | 55 | | | 4.5+ |
| 60 | 13 | | 42 | - from 60.0' small pockets dark brown weathered fine sandstone and shale | | 4.5+ |
| | 14 | | 70 | | | 4.5+ |
| 70 | 15 | | 36/5½" | | | 4.5+ |

Mud Method.

4 3/4" fish tail bit.
140-pound hammer
30" drop
Used 30" of 5" casing.

*5.0'-5.5' cobble; lost drilling fluid; used heavier mud.

COMPLETION DEPTH 70.5' WATER DEPTH 34" DATE 36 Hours
APPLIED ENERGY 4200 INCH POUNDS PER BLOW

PLATE 6

7-10-01, II, 1.



GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
HISTORICAL BORING LOG DB-001-0-57

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:29:23 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL033.dgn

# LOG OF BORING NO DB-2

## OHIO INTERSTATE SYSTEM - DESIGN SECTION D-12

DATE 6-19-57 TYPE 1½" I.D. Split-barrel [illegible] S.R. 161 44+66 36' L

SURFACE ELEVATION 913.5

| DEPTH, FEET | Sample No. | SAMPLES BLOWS PER FOOT | DESCRIPTION | T.S.F. Penetrom. |
|---|---|---|---|---|
| 0 | | | Topsoil-dark brown silt and clay | |
| | 1 | 5 | Very stiff gray-brown silty clay, | 1.5 |
| | 2 | 7 | little sand, trace gravel | 2.5 |
| 10 | 3 | 7 | Very stiff to hard dark gray sandy silt, some clay, little gravel | 2.5 |
| | 4 | 14 | | 3.0 |
| 20 | - | 29 | - @ 20.0' drove on large | - |
| | 5 | 26 | gravel. | 4.5 |
| | 6 | 26 | - from 22.0' hard to very hard. | 4.5 |
| 30 | 7 | 24 | | 4.5+ |
| | 8 | 32 | | 4.5+ |
| 40 | 9 | 31 | | 4.0 |
| | 10 | 35 | | 3.5 |
| 50 | 11 | 56 | | 4.5+ |
| 60 | | | Mud Method<br>3 7/8" fish tail bit<br>140-pound hammer<br>30" drop<br>Used no casing | |
| 70 | | | | |
| 80 | | | | |
| 90 | | | | |

COMPLETION DEPTH 51.5' WATER DEPTH 34" DATE 36 Hours

APPLIED ENERGY 4200 INCH POUNDS PER BLOW

PLATE 7

7-1-01, II-1.

| SHEET | TOTAL |
|---|---|
| P.613 | 618 |

| SUBSET | TOTAL |
|---|---|
| 64 | 69 |

PROJECT ID 109164

REVIEWER CH 08-28-23

DESIGNER ZM

DESIGN AGENCY NEAS National Engineering & Architectural Services Inc.

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
HISTORICAL BORING LOG DB-002-0-57

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:30:01 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL034.dgn

# LOG OF BORING NO. DB-3

## OHIO INTERSTATE SYSTEM - DESIGN SECTION D-12

DATE 6-20-57 TYPE 1½" and 2" I.D. Split-barrel; 3" I.D. Shelby tube LOC S.R. 161 44+66 68' R

SURFACE ELEVATION 915.0

| DEPTH, FEET | Sample No. | SAMPLES | BLOWS PER FOOT | DESCRIPTION | UNIT DRY WT LB/FT³ | SHEARING STRENGTHS/FT² (0 0.5 1.0 1.5 2.0 2.5) MOISTURE CONTENT % NATURAL (PL — ● — LL) | T.S.F. Penetrom. |
|---|---|---|---|---|---|---|---|
| 0 | | | | Topsoil-Soft dark brown silty clay | | | |
| | 1 | | 9 | Very stiff brown sandy silt, some clay, trace gravel, with black shale fragments | | | 2.5 |
| 5 | 2 | | P/300 | | 121 | | 3.5 |
| | 2A | | | | | | |
| | 3 | | P/350 | Very stiff dark gray sandy silt, some clay, trace gravel - from 11.2' to 12.0' lenses of water bearing silty fine sand | 110 | | - |
| 10 | 3A | | | | | | |
| | 3B | | | | | | |
| 15 | 4 | | 13 | | | | 2.5 |
| 20 | | | 23 | - @ 20.0' gravel too large for 1½" ϕ sampler. | | | - |
| | 5 | | 32 2-s | - @ 24.0' hard | | | 4.5 |
| 25 | 6 | | 44 | | | | 4.5+ |
| 30 | 7 | | 29 | | | | 3.7 |
| 35 | 8 | | 23 | | | | 3.0 |
| | | | | Mud Method<br>3 7/8" fish tail bit<br>140-pound hammer<br>30" drop<br>Used 5.0' of 4" casing | | | |
| 40 | | | | | | | |
| 45 | | | | | | | |

COMPLETION DEPTH 36.5' WATER DEPTH 52" DATE 36 Hours

APPLIED ENERGY 4200 INCH POUNDS PER BLOW

PLATE 8

7-1-01, II, 1.



GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
HISTORICAL BORING LOG DB-003-0-57

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:30:37 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL035.dgn

7-1-01, II, 1.

# LOG OF BORING NO. DB-4

## OHIO INTERSTATE SYSTEM - DESIGN SECTION D-12

DATE 6-20-57 TYPE 1½" and 2" I.D. Split-barrel 3" I.D. Shelby tube LOC S.R. 161 44+11 36' R

SURFACE ELEVATION 914.5

| DEPTH, FEET | Sample No. | SAMPLES | BLOWS PER FOOT | DESCRIPTION | UNIT DRY WT. LB/FT³ | SHEARING STRENGTH TONS/FT² / MOISTURE CONTENT % NATURAL (PL, LL) | T.S.F. Penetrom. |
|---|---|---|---|---|---|---|---|
| 0 | | | | Topsoil-Soft dark brown silty clay | | | |
| | 1 | | 6 | Very stiff to hard brown sandy silt, some gravel, little clay | | | 2.0 |
| 5 | 2<br>2A | | P | - from 8.5' to 16.0' some medium to large gravel<br>- @ 10.0' refused on gravel | 124 | | 1.7 |
| 10 | - | H | S | | | | - |
| | 3 | | 30<br>2-8 | Very stiff to very hard dark gray sandy silt, some clay, little gravel<br>- @ 15.0' gravel too large for 1½" ϕ sampler | | | 4.0 |
| 15 | - | | | | | | - |
| | 4 | | 28<br>2-8 | | | | 4.5 |
| 20 | | | | | | | - |
| | 5 | | 34<br>2-8 | | | | |
| 25 | | | | | | | 4.5 |
| | 6 | | 45 | | | | |
| 30 | - | H | P/450 | - @ 30.0' too hard to push | | | - |
| | 7 | | 34 | | | | 4.0 |
| 35 | | | | | | | 3.5 |
| | 8 | | 26 | | | | |
| 40 | | | | Mud Method<br>3 7/8" fish tail bit<br>140-pound hammer<br>30" drop<br>Used 6.0' of 4" casing | | | |
| 45 | | | | | | | |

COMPLETION DEPTH 36.5' WATER DEPTH 34" DATE 36 Hours

APPLIED ENERGY 4200 INCH POUNDS PER BLOW

PLATE 9

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.615 | 618 | 66 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
HISTORICAL BORING LOG DB-004-0-57

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:31:12 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL037.dgn

7-1-01, II, 1.

# LOG OF BORING NO. DB-5

## OHIO INTERSTATE SYSTEM - DESIGN SECTION D-12

DATE 6-26-57 TYPE 1½" and 2" I.D. Split-barrel; 3" I.D. Shelby tube LOC S.R. 161 43+20 78' R

| DEPTH, FEET | Sample No. | SAMPLES | BLOWS PER FOOT | DESCRIPTION | UNIT DRY WT. LB/FT³ | SHEARING STRENGTH TONS/FT² (0 0.5 1.0 1.5 2.0 2.5) / MOISTURE CONTENT % NATURAL (PL ×—● LL) (10 15 20 25 30) | T.S.F. Penetrom. |
|---|---|---|---|---|---|---|---|
| 0 | | | | SURFACE ELEVATION 914.0 | | | |
| | | | | Topsoil-Loose silt, with sod | | | |
| | | | | Firm to very stiff brown silt and clay, some sand, trace gravel | | | |
| 5 | 1 | | 5 | | | | 0.7 |
| | 2 | | P/250 | | 114 | | 2.0 |
| | 2A | | | | 121 | | |
| | 2B | | | | | | |
| | | | | Dense fine to medium gravel with stiff gray clayey silt binder | | | |
| 10 | 3 | | 17 (2-8) | | | | 3.5 |
| | | | | Very stiff to hard dark gray sandy silt, some clay, little gravel | | | |
| 15 | 4 | | 20 (2-8) | | | | 4.0 |
| 20 | 5 | | 20 (2-8) | | | | 2.7 |
| | | | | - @ 24.0' to 28.0' with less gravel | | | |
| 25 | 6 | | 20 (2-8) | | | | 1.3 |
| | | | | - @ 28.0' hard to very hard | | | |
| | | | | Note: Shelby tried at 10.0' and 20.0' but refused on gravel | | | |
| 30 | 7 | | 56 | | | | 4.5+ |
| 35 | 8 | | 57 | | | | 4.5+ |
| | | | | Mud Method | | | |
| | | | | 3 7/8" Fish tail bit | | | |
| | | | | 140-pound hammer | | | |
| | | | | 30" drop | | | |
| | | | | Used 30" of 5" casing | | | |
| 40 | | | | | | | |
| 45 | | | | | | | |

COMPLETION DEPTH 36.5' WATER DEPTH 37" DATE 48 Hours

APPLIED ENERGY 4200 INCH POUNDS PER BLOW

PLATE 10

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.616 | 618 | 67 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
HISTORICAL BORING LOG DB-005-0-57

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:31:47 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL038.dgn

# LOG OF BORING NO. DB-7

## OHIO INTERSTATE SYSTEM - DESIGN SECTION D-12

DATE 6-25, 6-26-57 TYPE 1½" and 2" I.D. Split-barrel; 3" I.D. Shelby tube LOC S.R.161 42+66 78' L

SURFACE ELEVATION 914.0

| DEPTH, FEET | Sample No. | SAMPLES | BLOWS PER FOOT | DESCRIPTION | UNIT DRY WT LB/FT³ | SHEARING STRENGTH TONS/FT² (0 0.5 1.0 1.5 2.0 2.5) / MOISTURE CONTENT % NATURAL (P_L — ✕ — ● — ✕ — LL) (10 15 20 25 30) | T.S.F. Penetrom. |
|---|---|---|---|---|---|---|---|
| 0 | | | | Topsoil-soft brown clay | | | |
| | 1 | | 6 | Very stiff to hard silty clay, becoming sandy silt, some clay, trace gravel with depth | 115 | | 2.0 |
| | 2 | | P/150 | | | | 2.5 |
| | 2A | | | | | | |
| | 2B | | | | | | |
| 10 | 3 | | 60 (2-8) | Very dense layered brown fine to coarse sand and fine to medium gravel with gray silt binder | | | 3.5 |
| | 4 | | 17 (2-8) | | | | 3.5 |
| 20 | 5* | | 30 (2-8) | Hard dark gray sandy silt, some clay, little gravel | | | 4.0 |
| | 6* | | 3½/6 (2-8) | - @ 16.0' hard to very hard | | | - |
| | 7 | | 66 (2-8) | - @ 27.0' very hard | | | 4.5+ |
| 30 | 8 | | 35 (2-8) | | | | 4.5+ |
| | 9 | | 74 (2-8) | | | | 4.5+ |
| 40 | 10 | | 58 (2-8) | | | | 4.5+ |
| | 11 | | 53 (2-8) | | | | 4.5+ |
| 50 | 12 | | 56 | - @ 50.0' several fine to coarse sand lenses | | | 4.5+ |
| 60 | | | | Mud Method<br>3 7/8" fish tail bit<br>140-pound hammer<br>30" drop<br>Used 30" of 5" casing. | | | |
| 70 | | | | *Note<br>(a) Sample #5 had 10" of cuttings<br>(b) Sample #6 had 12" of cuttings, drove on piece of gravel | | | |
| 80 | | | | | | | |
| 90 | | | | | | | |

COMPLETION DEPTH 51.5' WATER DEPTH 44" DATE 24 Hours

APPLIED ENERGY 4200 INCH POUNDS PER BLOW

PLATE 11

7-1-01, II-1.



GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
HISTORICAL BORING LOG DB-007-0-57

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 8/29/2023 TIME: 5:32:26 PM USER: zli
pw:\\jacobs-us-va-pw.bentley.com:jacobs-us-va-pw-02\Documents\C6A20100 - FRA-071-1910 I-71 HSR\30 WIP\109164\400-Engineering\Geotechnical\Sheets\109164_ZL039.dgn

7-1-01, II, 1.

## LOG OF BORING NO. DB-8

**OHIO INTERSTATE SYSTEM - DESIGN SECTION D-12**

DATE 6-27-57 TYPE 1½" and 2" I.D. Split-barrel 3" I.D. Shelby tube LOC S.R. 161 43+20 36' L

SURFACE ELEVATION 913.7

| DEPTH, FEET | Sample No. | SAMPLES | BLOWS PER FOOT | DESCRIPTION | UNIT DRY WT LB/FT³ | SHEARING STRENGTH TONS/FT² (0 0.5 1.0 1.5 2.0 2.5) / MOISTURE CONTENT % NATURAL (PL — ○ — LL) | T.S.F. Penetrom. |
|---|---|---|---|---|---|---|---|
| 0 | | | | Topsoil-Soft brown silt and sod | | | |
| | 1 | | 6 | Firm, becoming very stiff with depth, brown silt and clay, some sand, trace gravel | | | 0.7 |
| 5 | 2 | | W/250 | | | | 1.7 |
| | 2A | | | | | | |
| 10 | 3 | | 23 2-s | Dense fine to medium gravel with medium to coarse sand with silty clay binder | | | 2.25 |
| | | | | Very stiff to hard dark gray sandy silt, some clay, trace to little gravel | | | |
| 15 | 4 | | 24 2-s | - @ 18.0' hard | | | 3.0 |
| 20 | 5 | | P/400 | | 126 | | 4.5 |
| | 5A | | | | | | |
| | | | | - @ 24.0' very stiff to hard | 125 | | |
| 25 | 6 | | P/200 | | | | 2.0 |
| | 6A | | | | | | |
| 30 | 7 | | P/350 | - @ 30.5' hard | | | 4.5 |
| | 7A | | | | | | |
| | 7B | | | | | | |
| | | | | Very dense dark gray gravel with sand, little silt, trace clay | | | |
| 35 | 8 | | 60 2-s | | | | - |
| | 8A | | | | | | |
| 40 | | | | Mud Method<br>3 7/8" Fish tail bit<br>140-pound hammer<br>30" drop<br>Used 30" of 5" casing | | | |
| 45 | | | | | | | |

COMPLETION DEPTH 36.0' WATER DEPTH 37" DATE 48 Hours

APPLIED ENERGY 4200 INCH POUNDS PER BLOW

PLATE 12

| SHEET | TOTAL | SUBSET | TOTAL | PROJECT ID | REVIEWER | DESIGNER | DESIGN AGENCY |
|---|---|---|---|---|---|---|---|
| P.618 | 618 | 69 | 69 | 109164 | CH 08-28-23 | ZM | NEAS National Engineering & Architectural Services Inc. |

GEOTECHNICAL PROFILE - ROADWAY
BRIDGE NO. FRA-71-26.46 OVER SR 161
HISTORICAL BORING LOG DB-008-0-57