SHEET NUM. 3	4	5	7	8							PART. 01/STR/OT	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																ROADWAY	
											LUMP	201	11000	LS		CLEARING AND GRUBBING	3
				334							334	202	75001	334	FT	FENCE REMOVED, AS PER PLAN	3
			5,874								5,874	203	10000	5,874	CY	EXCAVATION	
											LUMP	208	10000	LS		PRE-BLAST CONDITION SURVEY	
											LUMP	208	12000	LS		BLASTING CONSULTANT	
											LUMP	208	13000	LS		AIR BLAST AND NOISE CONTROL	
											LUMP	208	14000	LS		VIBRATION CONTROL AND MONITORING	
																EROSION CONTROL	
			3,355								3,355	659	00541	3,355	SY	SEEDING AND MULCHING, CLASS 3C, AS PER PLAN	3
0.5											0.5	659	20000	0.5	TON	COMMERCIAL FERTILIZER	
0.7											0.7	659	31000	0.7	ACRE	LIME	
18.2											18.2	659	35000	18.2	MGAL	WATER	
											5,000	832	30000	5,000	EACH	EROSION CONTROL	
																PAVEMENT	
			155								155	407	20000	155	GAL	NON-TRACKING TACK COAT	
			152								152	408	10000	152	GAL	PRIME COAT	
			81								81	441	50000	81	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), PG64-22	
			32								32	617	10100	32	CY	COMPACTED AGGREGATE	
																TRAFFIC CONTROL	
			22								22	621	00100	22	EACH	RPM	
			22								22	621	54000	22	EACH	RAISED PAVEMENT MARKER REMOVED	
			0.32								0.32	642	00104	0.32	MILE	EDGE LINE, 6", TYPE 1	
			0.16								0.16	642	00300	0.16	MILE	CENTER LINE, TYPE 1	
																MAINTENANCE OF TRAFFIC	
											1	SPECIAL	61411300	1	EACH	WORK ZONE TRAFFIC SIGNAL	4
		2									2	614	12338	2	EACH	WORK ZONE IMPACT ATTENUATOR (BIDIRECTIONAL)	
	1										1	614	12740	1	EACH	WORK ZONE LIGHTING SYSTEM	
		13									13	614	13310	13	EACH	BARRIER REFLECTOR, TYPE 1 (BIDIRECTIONAL)	
		13									13	614	13360	13	EACH	OBJECT MARKER, TWO WAY	
	6										6	614	18601	6	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	4
		0.16									0.16	614	22010	0.16	MILE	WORK ZONE EDGE LINE, CLASS I, 6"	
		22									22	614	26000	22	FT	WORK ZONE STOP LINE, CLASS I	
		620									620	622	41000	620	FT	PORTABLE BARRIER, 32"	
																INCIDENTALS	
											LUMP	103	05000	LS		PREMIUM FOR CONTRACT PERFORMANCE BOND AND FOR PAYMENT BOND	
											LUMP	614	11000	LS		MAINTAINING TRAFFIC	
											LUMP	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
											LUMP	624	10000	LS		MOBILIZATION	

CALCULATED JDW
CHECKED ARM

GENERAL SUMMARY

GAL-141-8.85

I:\ProjectData\GAL\104975_GAL-141-8.85\Design\Roadway\Sheets\104975_GG001.dgn Sheet 4/3/2020 2:16:14 PM jwiseman