SHEET NUM. 7-10	11-13		16-17	18								PART. 01/STR/PV		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																		ROADWAY	
												430		202	30000	430	SF	WALK REMOVED	
			3.86									3.86		209	60500	3.86	MILE	LINEAR GRADING	
			3.86									3.86		209	72050	3.86	MILE	PREPARING SUBGRADE FOR SHOULDER PAVING	
												430		608	10000	430	SF	4" CONCRETE WALK	
												846		608	52001	846	SF	CURB RAMP, AS PER PLAN	
8												8		623	39501	8	EACH	MONUMENT BOX ADJUSTED TO GRADE, AS PER PLAN	8
1												1		623	39600	1	EACH	MONUMENT BOX RECONSTRUCTED TO GRADE	
																		EROSION CONTROL	
												1,000		832	30000	1,000	EACH	EROSION CONTROL	
																		DRAINAGE	
7												7		611	98630	7	EACH	CATCH BASIN ADJUSTED TO GRADE	
65												65		611	98631	65	EACH	CATCH BASIN ADJUSTED TO GRADE, AS PER PLAN	8
20												20		611	99655	20	EACH	MANHOLE ADJUSTED TO GRADE, AS PER PLAN	8
2												2		611	99660	2	EACH	MANHOLE RECONSTRUCTED TO GRADE	
15,000												15,000		SPECIAL	61199820	15,000	LB	MISCELLANEOUS METAL	8
20												20		638	10801	20	EACH	VALVE BOX ADJUSTED TO GRADE, AS PER PLAN	8
																		PAVEMENT	
1,600												1,600		251	01001	1,600	SY	PARTIAL DEPTH PAVEMENT REPAIR (441), AS PER PLAN	9
560												564		253	02000	564	CY	PAVEMENT REPAIR	
			30,082									30,082		254	01001	30,082	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, 1.5"	9
			36,807									36,807		254	01001	36,807	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, 2.5"	9
			9,699									9,699		407	20000	9,699	GAL	NON-TRACKING TACK COAT	
			2,784									2,784		441	10101	2,784	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), AS PER PLAN, 1.5"	9
			110									110		441	50101	110	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), AS PER PLAN, PG64-22, 1.5"	9
			1,765									1,765		441	50201	1,765	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), AS PER PLAN, PG64-22, 1.0"	9
			9									9		441	50400	9	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), (DRIVEWAYS), 1.5"	
			252									252		617	10101	252	CY	COMPACTED AGGREGATE, AS PER PLAN	8
			6,517									6,517		875	10000	6,517	LB	LONGITUDINAL JOINT ADHESIVE	
																		TRAFFIC CONTROL	
				147								147		621	00100	147	EACH	RPM (YELLOW\YELLOW)	
111												111		621	54000	111	EACH	RAISED PAVEMENT MARKER REMOVED	
			0.09	4.36								4.45		646	10010	4.45	MILE	EDGE LINE, 6"	
			1.2	2.46								3.66		646	10200	3.66	MILE	CENTER LINE	
			1,152	43								1,195		646	10300	1,195	FT	CHANNELIZING LINE, 8"	
			98	91								189		646	10400	189	FT	STOP LINE	
			292	1,153								1,445		646	10510	1,445	FT	CROSSWALK LINE, 12"	
			585	32								617		646	10600	617	FT	TRANSVERSE/DIAGONAL LINE	
			242									242		646	10800	242	SF	ISLAND MARKING	
			58	210								268		646	20200	268	FT	PARKING LOT STALL MARKING	
			33	1								34		646	20300	34	EACH	LANE ARROW	
																		TRAFFIC SIGNALS	
18												18		632	26501	18	EACH	DETECTOR LOOP, AS PER PLAN	11

General Summary

DESIGN AGENCY

DESIGNER JDA

REVIEWER EMK 11/01/21

PROJECT ID 108104

SHEET 14 TOTAL 28

GEA-87-15.93

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 2/16/2022 TIME: 7:43:20 AM USER: jalbrig1
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 12\Geauga\108104\400-Engineering\Roadway\Sheets\108104_GG001.dgn

Pavement Markings Subsummary

SHEET NO.	PLAN SPLIT NO.	STATION FROM	STATION TO	LENGTH FT	646 EDGE LINE, 6", WHITE FT		646 CENTER LINE YELLOW, DOUBLE SOLID FT	646 CENTER LINE YELLOW, SOLID AND BROKEN FT	646 CHANNELIZING LINE, 8"	646 STOP LINE FT	646 CROSSWALK LINE, 12" FT	646 PARKING LOT STALL MARKING FT	646 LANE ARROW EACH	646 TRANSVERSE/DIAGONAL LINE FT	646 ISLAND MARKING SF		621 RPM (YELLOW/YELLOW) EACH						
	1	0+00.00	3+14.47	314.47	314.47		628.94																
	1	3+14.47	4+48.87	134.40	134.40		134.40						2										
	1	4+48.87	4+81.62	32.75																			
	1	4+81.62	6+78.52	196.90			393.80							145	67								
	1	6+78.52	8+51.21	172.69			172.69		173	25			3										
	1	8+51.21	9+60.02	108.81																			
	1	9+60.02	9+72.84	12.82							72												
	1	9+72.84	11+12.27	139.43			139.43		140	25			3										
	1	11+12.27	11+30.26	17.99			17.99																
	1	11+30.26	11+89.67	59.41			118.82							48	62								
	1	11+89.67	12+69.63	79.96																			
	1	12+69.63	13+81.73	112.10			112.10		113				2										
	1	13+81.73	14+97.12	115.39			230.78							113	62								
	1	14+97.12	15+33.66	36.54																			
	1	15+33.66	20+67.94	534.28				534.28					6										
	1	20+67.94	21+13.68	45.74																			
	1	21+13.68	21+93.18	79.50				79.50															
	1	21+93.18	22+13.50	20.32				20.33															
	1	22+13.50	24+23.66	210.16			420.32																
	1	24+23.66	24+87.73	64.07				64.08					2										
	1	24+87.73	26+01.08	113.35			113.35		114	12			2										
	1	26+01.08	26+16.12	15.04					16	12	72												
	1	26+16.12	27+16.04	99.92																			
	1	27+16.04	27+28.09	12.05						12	74												
	1	27+28.09	27+43.45	15.36					16														
	1	27+43.45	28+57.20	113.75			113.75		114				3										
	1	28+57.20	29+21.53	64.33			128.67																
	1	29+21.53	37+21.64	800.11				800.11															
	1	37+21.64	37+91.58	69.94			139.88			12			4	78									
	1	37+91.58	38+87.34	95.76							74												
	1	38+87.34	39+00.74	13.40																			
	1	39+00.74	41+56.75	256.01			256.01		257				3										
	1	41+56.75	42+78.81	122.06			244.13							78									
	1	42+78.81	43+77.30	98.49			98.49		99				2										
	1	43+77.30	44+30.81	53.51																			
	1	44+30.81	45+14.11	83.30			166.60							123	51								
	1	45+14.11	45+65.90	51.79																			
	1	45+65.90	57+05.21	1139.31			1139.31																
	1	57+05.21	58+15.11	109.90			109.90		110			58	1										
SUBTOTALS					448.87		4879.36	1498.3	1152	98	292	58	33	585	242								
TOTALS CARRIED TO GENERAL SUMMARY					0.09 MI		0.92 MI	0.28 MI	1152	98	292	58	33	585	242								

DESIGN AGENCY

DESIGNER
JDA

REVIEWER
EMK 11/01/21

PROJECT ID
108104

SHEET 17 TOTAL 28

GEA-87-15.93

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 2/16/2022 TIME: 8:53:43 AM USER: jalbrig1
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 12\Geauga\108104\400-Engineering\Roadway\Sheets\108104_GS002.dgn

Pavement Markings Subsummary

SHEET NO.	PLAN SPLIT NO.	STATION FROM	STATION TO	LENGTH	646 EDGE LINE, 6", WHITE		646 CENTER LINE YELLOW, DOUBLE SOLID	646 CENTER LINE YELLOW, SOLID AND BROKEN	646 CHANNELIZING LINE, 8"	646 STOP LINE	646 CROSSWALK LINE, 12"	646 PARKING LOT STALL MARKING	646 LANE ARROW	646 TRANSVERSE/DIAGONAL LINE	646 ISLAND MARKING		621 RPM (YELLOW/YELLOW)						
		FROM	TO	FT	FT		FT	FT	FT	FT	FT	FT	EACH	FT	SF		EACH						
		S.R. 87 - Curbed Section																					
	1	62+10.01	62+52.89	42.88			43.00		43				1										
	1	62+52.89	69+59.63	706.74								210											
	1	69+59.63	70+21.77	62.14							54												
	1	70+21.77	80+14.53	992.76			993.00																
	1	80+14.53	86+25.56	611.03			612.00																
	1	86+25.56	86+50.00	24.44	48.89		25.00																
		S.R. 87 - Non-Curbed Section																					
	1	86+50.00	118+54.88	3204.88	6409.76		3205.00			14							41						
	1	118+54.88	118+97.14	42.26	84.53		43.00										1						
	1	118+97.14	119+93.34	96.20													2						
	1	119+93.34	120+11.68	18.34	18.35		19.00			13							1						
	1	120+11.68	199+65.04	7953.36	15906.72		7954.00										100						
	1	199+65.04	200+11.22	46.18													1						
	1	200+11.22	200+23.48	12.26	24.52		13.00										1						
		Intersection Extra Areas																					
	1	Tare Creek Parkway, 4+49 LT.			40																		
	1	Ames Plaza,9+00 RT.																					
	1	Market Square, 9+00 LT.								28	117												
	1	Woodsong Drive, 12+22 RT.																					
	1	Crestwood Drive, 15+13 RT.								10	64												
	1	Northview Drive, 20+91 LT.									97												
	1	Springdale Avenue, 26+79 LT & RT.									228												
	1	Elmwood Street, 30+48 LT.									69												
	1	Lake Avenue, 38+38 RT.									113												
	1	Standish Avenue, 44+07 LT.									65												
	1	Linda Avenue, 45+53 RT.									45												
	1	SR-608, 60+20 LT. & RT.																					
	1	Thompson Avenue, 69+93 LT. & RT.									170												
	1	Hillcrest Avenue, 80+53 LT.									78												
	1	Lenny Avenue, 85+91 RT.									53												
	1	Glen Valley Drive, 100+11 LT.																					
	1	SR-528, 119+54 LT. & RT.			469		90			26				32									
	1	Hayes Road, 199+86 LT. & RT.																					
SUBTOTALS					23001.8		12997		43	91	1153	210	1	32			147						
TOTALS CARRIED TO GENERAL SUMMARY					4.36 MI		2.46 MI		43	91	1153	210	1	32			147						

DESIGN AGENCY

DESIGNER
JDA

REVIEWER
EMK 11/01/21

PROJECT ID
108104

SHEET 18 TOTAL 28

GEA-87-15.93

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 2/16/2022 TIME: 8:41:46 AM USER: jalbrig1
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 12\Geauga\108104\400-Engineering\Roadway\Sheets\108104_GS003.dgn