

**Pavement Quantities (GEA 87-19.75) - Job #720**

		Item 441 (#1 & #2)	Item 301 (#3)	Item 304 (#4)	Item 609 (#5)	Item 407 (#6)	Item 204 (#7)	Item 254 (#9)	Item 202 (#10)		
		1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1 (448), PG70-22M	1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2 (448)	6" ASPHALT CONCRETE BASE, PG64-22	6" AGGREGATE BASE	CURB, TYPE 6	NON-TRACKING COAT (0.075 GAL/S.Y.)	SUBGRADE COMPACTION	PAVEMENT PLANING, ASPHALT CONCRETE (T=1 1/2" MAX.)	PAVEMENT REMOVED	
<i>FEATHER SECTION/PARTIAL FULL DEPTH REPLACEMENT</i>		AREA (SQ FT)	1011.64	132.15	137.64	145.88	-----	-----	181.65	1011.64	84.83
FROM 113+39	TO 113+60	AREA (SQ YDS)	112.40	14.68	15.29	16.21	-----	-----	<b>20.18</b>	<b>112.40</b>	<b>9.43</b>
		VOLUME (CU YDS)	<b>4.68</b>	<b>0.71</b>	<b>2.55</b>	<b>2.70</b>	-----	-----	-----	-----	-----
		VOLUME (GAL)	-----	-----	-----	-----	-----	-----	-----	-----	-----
<i>FULL DEPTH REPLACEMENT</i>		AREA (SQ FT)	23730.77	23730.77	23930.17	24583.53	-----	47461.54	25370.00	0.00	15734.60
FROM 113+60	TO 119+50	AREA (SQ YDS)	2636.75	2636.75	2658.91	2731.50	-----	5295.66	<b>2818.89</b>	<b>0.00</b>	<b>1748.29</b>
		VOLUME (CU YDS)	<b>109.86</b>	<b>128.18</b>	<b>443.15</b>	<b>455.25</b>	-----	-----	-----	-----	-----
		VOLUME (GAL)	-----	-----	-----	-----	-----	<b>397.17</b>	-----	-----	-----
<i>WIDENING &amp; RESURFACING</i>		AREA (SQ FT)	180418.00	91080.60	94050.60	98580.30	-----	271498.60	104481.73	90418.00	31635.43
FROM 119+50	TO 164+50	AREA (SQ YDS)	20046.44	10120.07	10450.07	10953.37	-----	30166.51	<b>11609.08</b>	<b>10046.44</b>	<b>3515.05</b>
		VOLUME (CU YDS)	<b>835.27</b>	<b>491.95</b>	<b>1741.68</b>	<b>1825.56</b>	-----	-----	-----	-----	-----
		VOLUME (GAL)	-----	-----	-----	-----	-----	<b>2262.49</b>	-----	-----	-----
<i>CURBING SECTION</i>		LENGTH (FT)	-----	-----	-----	-----	<b>237.00</b>	-----	-----	-----	-----
FROM 126+25	TO 128+62	LENGTH (FT)	-----	-----	-----	-----	-----	-----	-----	-----	-----
<b>TOTALS</b>	<b>APPROXIMATE CALCULATIONS</b>	<b>949.82</b>	<b>620.84</b>	<b>2187.38</b>	<b>2283.51</b>	<b>237.00</b>	<b>2659.66</b>	<b>14448.15</b>	<b>10158.85</b>	<b>5272.76</b>	
	<b>CARRIED TO GENERAL SUMMARY</b>	<b>950</b>	<b>621</b>	<b>2187</b>	<b>2284</b>	<b>237</b>	<b>2660</b>	<b>14448</b>	<b>10159</b>	<b>5273</b>	
		<i>CU YDS</i>	<i>CU YDS</i>	<i>CU YDS</i>	<i>CU YDS</i>	<i>FT</i>	<i>GAL</i>	<i>SQ YDS</i>	<i>SQ YDS</i>	<i>SQ YDS</i>	