SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
P.05	P.07	P.08	P.17	P.34									01/BRO/10						
																		STRUCTURE REPAIR (GEA-00322-19.410)	
				LS									LS	202	11003	LS		STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	P.33
				80									80	202	22900	80	SY	APPROACH SLAB REMOVED	
				LS									LS	503	11101	LS		COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN	P.33, P.38
				LS									LS	503	21301	LS		UNCLASSIFIED EXCAVATION, AS PER PLAN	P.33
				48,063									48,063	509	10000	48,063	LB	EPOXY COATED REINFORCING STEEL	
				3,308									3,308	509	30020	3,308	FT	NO. 4 GFRP DEFORMED BARS	
				2									2	511	33500	2	EACH	SEMI-INTEGRAL DIAPHRAGM GUIDE	
				181									181	511	34446	181	CY	CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK	
				33									33	511	34450	33	CY	CLASS QC2 CONCRETE WITH QC/QA, BRIDGE DECK (PARAPET)	
				158									158	511	43512	158	CY	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING	
				459									459	512	10100	459	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
				67									67	512	33000	67	SY	TYPE 2 WATERPROOFING	
				6									6	515	15010	6	EACH	DRAPED STRAND PRESTRESSED CONCRETE BRIDGE I-BEAM MEMBERS, LEVEL 3, TYPE 3 (LENGTH = 81'-8")	
				15									15	515	20000	15	EACH	INTERMEDIATE DIAPHRAGMS	
				17									17	516	13600	17	SF	1" PREFORMED EXPANSION JOINT FILLER	
				69									69	516	13900	69	SF	2" PREFORMED EXPANSION JOINT FILLER	
				132									132	516	14020	132	FT	SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL	
				12									12	516	44101	12	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE),	P.43
																		AS PER PLAN (17"x12"x2.625" BEARING WIDTH WITH 18"x13"x1.5" LOAD PLATE)	
				114									114	518	21200	114	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	
				149									149	518	40000	149	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	
				60									60	518	40012	60	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE	
				38									38	524	94702	38	FT	DRILLED SHAFTS, 36" DIAMETER, ABOVE BEDROCK	
				166									166	524	94704	166	FT	DRILLED SHAFTS, 36" DIAMETER, INTO BEDROCK	
				236									236	526	25000	236	SY	REINFORCED CONCRETE APPROACH SLABS (T=15")	
				95									95	526	90011	95	FT	TYPE A INSTALLATION, AS PER PLAN	P.55
																		MAINTENANCE OF TRAFFIC	
	10												10	410	12000	10	CY	TRAFFIC COMPACTED SURFACE, TYPE A OR B	
	10												10	410	13000	10	CY	TRAFFIC COMPACTED SURFACE, TYPE C	
		300											300	614	11110	300	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
	1												1	SPECIAL	61411300	1	EACH	WORK ZONE TRAFFIC SIGNAL	P.07
		1,740											1,740	614	11630	1,740	FT	INCREASED BARRIER DELINEATION	
			6										6	614	12380	6	EACH	~~WORK ZONE IMPACT ATTENUATOR, 24" WIDE HAZARDS, (UNIDIRECTIONAL)~~	
	10												10	614	13000	10	CY	~~ASPHALT CONCRETE FOR MAINTAINING TRAFFIC~~	
		18											18	614	13310	18	EACH	BARRIER REFLECTOR, TYPE 1, (TWO-WAY)	
	11												11	614	13314	11	EACH	BARRIER REFLECTOR, TYPE 3, (BI-DIRECTIONAL)	
	11	18											29	614	13360	29	EACH	OBJECT MARKER, TWO WAY	
		8											8	614	18601	8	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	P.08
			0.38										0.38	614	21100	0.38	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
			0.42										0.42	614	22100	0.42	MILE	WORK ZONE EDGE LINE, CLASS I, 4", 642 PAINT	
			0.4										0.4	614	22210	0.4	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 740.06, TYPE I	
			24										24	614	26200	24	FT	WORK ZONE STOP LINE, CLASS I, 642 PAINT	
			196										196	615	25000	196	SY	PAVEMENT FOR MAINTAINING TRAFFIC, CLASS B	
	20												20	616	10000	20	MGAL	WATER	
		100											100	630	97800	100	SF	SIGNING, MISC.: ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY THE ENGINEER	P.08
																		INCIDENTALS	
													LS	614	11000	LS		MAINTAINING TRAFFIC	
6													6	619	16011	6	MNTH	FIELD OFFICE, TYPE B, AS PER PLAN	P.05
													LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													LS	623	50000	LS		PRECONSTRUCTION SURVEY MONUMENT VERIFICATION AND REPORT	
													LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

GEA-322-19.410

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 11/7/2024 TIME: 8:03:47 AM USER: jthomas
Z:\2022\221619\CAD\ODOT\115823\400-Engineering\Roadway\Sheets\115823_GG002.dgn

DESIGN AGENCY
fishbeck

DESIGNER
AJV

REVIEWER
JBD 04/12/24

PROJECT ID
115823

SHEET P.13 TOTAL 69