



SHEET NUM.												PART.		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4-6	7-9	11	12							01/STR/PV	02/SAE/PV								
		6.32								6.32			209	60501	6.32	MILE	ROADWAY	5	
3										3			623	39501	3	EACH	LINEAR GRADING, AS PER PLAN MONUMENT BOX ADJUSTED TO GRADE, AS PER PLAN	5	
										1,000			832	30000	1,000	EACH	EROSION CONTROL		
										1,000			251	01001	1,000	SY	PAVEMENT	5	
1,000										900			253	02000	900	CY	PARTIAL DEPTH PAVEMENT REPAIR (441), AS PER PLAN		
900										49,873			254	01001	49,873	SY	PAVEMENT REPAIR PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN, 1.5"	5	
		49,873								4,239			407	20000	4,239	GAL	NON-TRACKING TACK COAT		
		4,239								2,078			441	10101	2,078	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), AS PER PLAN, 1-1/2"	6	
		2,078																	
										102.87			617	10101	102.87	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), AS PER PLAN, 1-1/2"		
3.13													618	43000	3.13	MILE	COMPACTED AGGREGATE, AS PER PLAN RUMBLE STRIPES, CENTER LINE (ASPHALT CONCRETE)	5	
		102.87								3.16	3.13		874	21000	3.16	MILE	LONGITUDINAL JOINT PREPARATION		
		3.16																	
										629			621	00100	629	EACH	TRAFFIC CONTROL RPM		
472										472			621	54000	472	EACH	RAISED PAVEMENT MARKER REMOVED		
										6.26			646	10010	6.26	MILE	EDGE LINE, 6"		
										3.13			646	10200	3.13	MILE	CENTER LINE		
										75			646	10400	75	FT	STOP LINE		
										140			646	10500	140	FT	CROSSWALK LINE		
										LS			SPECIAL	69098400	LS		INVENTORY EXISTING PAVEMENT MARKINGS	6	
										2			632	26500	2	EACH	TRAFFIC SIGNALS DETECTOR LOOP		
2																			
										80			614	11110	80	HOUR	MAINTENANCE OF TRAFFIC LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE		
										50			614	13001	50	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC, AS PER PLAN	9	
										2			614	18600	2	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN		
										3.13			614	21100	3.13	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT		
										3.13			614	21550	3.13	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT		
										6.26			614	22110	6.26	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT		
										6.26			614	22360	6.26	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT		
										75			614	26200	75	FT	WORK ZONE STOP LINE, CLASS I, 642 PAINT		
										75			614	26610	75	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT		
										140			614	27200	140	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT WORK ZONE CROSSWALK LINE, CLASS I, 642 PAINT		
										140			614	27620	140	FT	WORK ZONE CROSSWALK LINE, CLASS III, 642 PAINT		
										300			630	97800	300	SF	SIGNING, MISC.: ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY THE ENGINEER		
										LS			614	11000	LS		INCIDENTALS MAINTAINING TRAFFIC		
6										6			619	16011	6	MNTH	FIELD OFFICE, TYPE B, AS PER PLAN	5	
										LS			623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING		
										LS			624	10000	LS		MOBILIZATION		

General Summary

DESIGN AGENCY	
DESIGNER	JDA
REVIEWER	EJK
PROJECT ID	08-03-20
	99628
SHEET	TOTAL
10	22

REF. NO.	SHEET NO.	PLAN SPLIT NO.	STATION TO STATION	LENGTH	BEGIN WIDTH	ENDING WIDTH	AVERAGE WIDTH	AREA			209		441	254	407		617	874		
				FT.	FT.	FT.	FT.	SQ. YD.			MILE		CY	SY	GAL		CY	FT		
			<u>S.R. 608</u>																	
	1		0+17.49	0+56.82	39.33	135.00	26.00	80.50	351.79		0.01		15	351.79	30		0.2	39.33		
	1		0+56.82	39+67.84	3911.02	26.00	26.00	26.00	11298.51		1.48		471	11298.51	960		24.1	3911.02		
	1		39+67.84	39+96.21	28.37	26.00	39.00	32.50	102.45		0.01		4	102.45	9		0.2	28.37		
	1		39+96.21	40+36.50	40.29	39.00	40.00	39.50	176.83		0.02		7	176.83	15		0.2	40.29		
	1		40+36.50	40+62.65	26.15	40.00	26.00	33.00	95.89		0.01		4	95.89	8		0.2	26.15		
	1		40+62.65	165+13.24	12450.59	26.00	26.00	26.00	35968.38		4.72		1499	35968.38	3057		76.9	12450.59		
	1		165+13.24	165+37.30	24.06	26.00	36.00	31.00	82.88		0.01		3	82.88	7		0.1	24.06		
	1		165+37.30	165+57.79	20.49	36.00	26.00	31.00	70.58		0.01		3	70.58	6		0.1	20.49		
	1		165+57.79	166+82.32	124.53	CADD AREA			1725.17		0.05		72	1725.17	147		0.8	124.53		
SUBTOTALS											6.32		2078	49873	4239		102.87	16664.8		
TOTALS CARRIED TO GENERAL SUMMARY											6.32		2078	49873	4239		102.87	3.16 MI		

Pavement Subsummary

DESIGN AGENCY

 DESIGNER
 JDA
 REVIEWER
 EJK 08-03-20
 PROJECT ID
 99628
 SHEET TOTAL
 11 22