SHEET NUM. 4-6	7-9	11	12									PART. 01/MPO/PV		ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
																		ROADWAY	
		148										148		209	60201	148	STA	LINEAR GRADING, AS PER PLAN	5
		2.74										2.74		209	72051	2.74	MILE	PREPARING SUBGRADE FOR SHOULDER PAVING, AS PER PLAN	5
																		EROSION CONTROL	
												1,000		832	30000	1,000	EACH	EROSION CONTROL	
																		DRAINAGE	
1												1		611	98631	1	EACH	CATCH BASIN ADJUSTED TO GRADE, AS PER PLAN	5
150												150		SPECIAL	61199820	150	LB	MISCELLANEOUS METAL	5
																		PAVEMENT	
200												200		251	01000	200	SY	PARTIAL DEPTH PAVEMENT REPAIR (441)	
100												100		253	02000	100	CY	PAVEMENT REPAIR	
		20,068										20,068		254	01001	20,068	SY	PAVEMENT PLANING, ASPHALT CONCRETE, AS PER PLAN , 1.5"	5
		2,810										2,810		407	20000	2,810	GAL	NON-TRACKING TACK COAT	
		831										831		441	10101	831	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (446), AS PER PLAN, PG70-22M, (1-1/2")	6
		19										19		441	50101	19	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), AS PER PLAN, PG64-22, 1.5"	6
		548										548		441	50200	548	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, (448), (1")	
		20										20		441	50400	20	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (448), (DRIVEWAYS) , 2"	
		44										44		617	10101	44	CY	COMPACTED AGGREGATE, AS PER PLAN	5
		1,807										1,807		875	10000	1,807	LB	LONGITUDINAL JOINT ADHESIVE	
																		TRAFFIC CONTROL	
			107									107		621	00100	107	EACH	RPM	
68												68		621	54000	68	EACH	RAISED PAVEMENT MARKER REMOVED	
			1									1		642	01110	1	EACH	SCHOOL SYMBOL MARKING, 96", TYPE 1	
			2.74									2.74		646	10010	2.74	MILE	EDGE LINE, 6"	
			1.37									1.37		646	10200	1.37	MILE	CENTER LINE	
			20									20		646	10400	20	FT	STOP LINE	
LS												LS		SPECIAL	69098400	LS		INVENTORY EXISTING PAVEMENT MARKINGS	5
																		MAINTENANCE OF TRAFFIC	
	80											80		614	11110	80	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	
	15											15		614	13001	15	CY	ASPHALT CONCRETE FOR MAINTAINING TRAFFIC, AS PER PLAN	8
	6											6		614	18601	6	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	9
	1.37											1.37		614	21100	1.37	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
	1.37											1.37		614	21550	1.37	MILE	WORK ZONE CENTER LINE, CLASS III, 642 PAINT	
	2.74											2.74		614	22110	2.74	MILE	WORK ZONE EDGE LINE, CLASS I, 6", 642 PAINT	
	2.74											2.74		614	22360	2.74	MILE	WORK ZONE EDGE LINE, CLASS III, 6", 642 PAINT	
	20											20		614	26200	20	FT	WORK ZONE STOP LINE, CLASS I, 642 PAINT	
	20											20		614	26610	20	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
	1											1		614	31744	1	EACH	WORK ZONE SCHOOL SYMBOL MARKING, 96", CLASS I, 642 PAINTs	
	1											1		614	31750	1	EACH	WORK ZONE SCHOOL SYMBOL MARKING, 96", CLASS III, 642 PAINTs	
	300											300		630	97800	300	SF	SIGNING, MISC.:ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY THE ENGINEER	8
																		INCIDENTALS	
												LS		614	11000	LS		MAINTAINING TRAFFIC	
6												6		619	16010	6	MNTH	FIELD OFFICE, TYPE B, AS PER PLAN	4
LS												LS		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
												LS		624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

GEA-168-00.21

MODEL: Sheet PAPERSIZE: 17x11 (in.) DATE: 10/5/2021 TIME: 6:58:15 AM USER: jalbrig1
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 12\Geauga\99700\400-Engineering\Roadway\Sheets\99700_GG001.dgn

DESIGN AGENCY

DESIGNER
JDA

REVIEWER
EJK 6-3-21

PROJECT ID
99700

SHEET 10 TOTAL 16