SHEET NUM.													PART.	ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
		3		6	7	9	20						01/STR/44						
																		ROADWAY	
		LS											LS	201	11000	LS		CLEARING AND GRUBBING	
		10											10	203	10000	10	CY	EXCAVATION	
		10											10	203	20000	10	CY	EMBANKMENT	
						340							340	204	13001	340	CY	EXCAVATION OF SUBGRADE, AS PER PLAN	4
						203							203	204	30041	203	CY	GRANULAR MATERIAL, TYPE E, AS PER PLAN	4
						1							1	204	45000	1	HOUR	PROOF ROLLING	4
						322							322	204	50001	322	SY	GEOTEXTILE FABRIC, AS PER PLAN (A)	4
						116							116	204	50001	116	SY	GEOTEXTILE FABRIC, AS PER PLAN (B)	5
						300							300	209	10000	300	FT	DITCH CLEANOUT	
							19						19	623	40500	19	EACH	REFERENCE MONUMENT	
																		EROSION CONTROL	
		4											4	601	21050	4	SY	TIED CONCRETE BLOCK MAT WITH TYPE 1 UNDERLAYMENT	
		300											300	659	10000	300	SY	SEEDING AND MULCHING	
		0.04											0.04	659	20000	0.04	TON	COMMERCIAL FERTILIZER	
		0.07											0.07	659	31000	0.07	ACRE	LIME	
		2											2	659	35000	2	MGAL	WATER	
		2,000											2,000	832	30000	2,000	EACH	EROSION CONTROL	
																		DRAINAGE	
		100											100	605	13301	100	FT	6" UNCLASSIFIED PIPE UNDERDRAINS, AS PER PLAN	5
		30											30	611	00510	30	FT	6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	
		50											50	611	01500	50	FT	6" CONDUIT, TYPE F	
		1											1	611	99710	1	EACH	PRECAST REINFORCED CONCRETE OUTLET	
																		PAVEMENT	
						46							46	301	56000	46	CY	ASPHALT CONCRETE BASE, PG64-22, (449)	
					15	51							66	304	20000	66	CY	AGGREGATE BASE	
						32							32	407	20000	32	GAL	NON-TRACKING TACK COAT	
					10	10							20	441	70100	20	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, (449), PG70-22M	
						13							13	441	70300	13	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, (449)	
						9							9	617	10100	9	CY	COMPACTED AGGREGATE	
																		TRAFFIC CONTROL	
						0.04							0.04	642	00104	0.04	MILE	EDGE LINE, 6", TYPE 1	
						0.02							0.02	642	00300	0.02	MILE	CENTER LINE, TYPE 1	
																		MAINTENANCE OF TRAFFIC	
					LS								LS	614	12420	LS		DETOUR SIGNING	
				2									2	614	18601	2	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	6
																		INCIDENTALS	
				LS									LS	614	11000	LS		MAINTAINING TRAFFIC	
													LS	623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
													LS	624	10000	LS		MOBILIZATION	

GENERAL SUMMARY

DESIGN AGENCY

DESIGNER
XXX

REVIEWER
XXX MM-DD-YY

PROJECT ID
111607

SHEET P.8 TOTAL 27

GUE-265-5.68

MODEL: Sheet PAPERSIZE: 34x22 (in.) DATE: 1/30/2023 TIME: 8:45:09 AM USER: bharlow
pw:\\ohiodot-pw.bentley.com:ohiodot-pw-02\Documents\01 Active Projects\District 05\Guernsey\111607\400-Engineering\Roadway\Sheets\111607_GG001.dgn