A MINIMUM OF ONE LANE OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES FOR THE PROJECT EXCEPT FOR THE RONALD REGAN CROSS COUNTY HIGHWAY INTERCHANGE AREA AT THE FOLLOWING STATIONS:

ONE LEFT TURN LANE AND ONE THROUGH LANE MUST BE MAINTAINED IN EACH DIRECTION BETWEEN STATION 97+25 TO 100+00.

TEMPORARY DETECTION DURING CONSTRUCTION WILL BE NECESSARY FOR THE PROPER OPERATION OF SIGNALS AT THE RONALD REGAN CROSS COUNTY HIGHWAY AND POTENTIALLY AT OTHER SIGNALIZED INTERSECTIONS.

THE CONTRACTOR SHALL SUBMIT A CONSTRUCTION SEQUENCING SCHEDULE PRIOR TO WORK BEGINNING FOR APPROVAL BY THE CITY ENGINEER. THE CONSTRUCTION SEQUENCING SCHEDULE SHALL TAKE INTO CONSIDERATION ALL ASPECTS OF THE PROJECT INCLUDING HOW LOCAL TRAFFIC TO THE BUSINESSES WILL BE MAINTAINED. THE CONSTRUCTION SEQUENCE WILL NEED TO BE APPROVED BY THE ENGINEER BEFORE THE COMMENCEMENT OF WORK.

ACCESS TO AND FROM ALL LOCAL RESIDENTIAL AND BUSINESS DRIVES WITHIN THE LIMITS OF THIS PROJECT SHALL BE MAINTAINED AT ALL TIMES BY USING THE EXISTING PAVEMENT, TEMPORARY PAVEMENT, AND THE PROPOSED PAVEMENT, UNLESS OTHERWISE DIRECTED BY THE CITY ENGINEER

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF MAINTENANCE OF TRAFFIC SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

THE CONTRACTOR SHALL ADJUST THE LOCATION AND/OR SPACING OF ALL TRAFFIC CONTROL CHANNELIZING DEVICES AS DICTATED BY THE PROGRESS OF THE REQUIRED WORK TO ALLOW CONSTRUCTION ACCESS TO WORK AREAS WHILE MAINTAINING SAFE AND EFFECTIVE TRAFFIC CONTROL DURING ALL CONSTRUCTION OPERATIONS. ANY DAMAGE TO MAINTENANCE OF TRAFFIC EQUIPMENT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REPLACE OR CORRECT.

THE ROADWAY SHALL NOT BE RESTRICTED TO ANY LANE CLOSURE DURING PERIODS OF INTERMITTENT OR IRREGULAR WORK, NOR CLOSED SOLELY FOR THE CONVENIENCE OF THE CONTRACTOR.

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH C&MS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614. MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

NO WORK SHALL BE PERFORMED AND ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR EVENTS:

MEMORIAL DAY - ALL LANES OPEN: 12:00N FRI. THROUGH 6:00 AM TUES.

FOURTH OF JULY - ALL LANES OPEN: 12:00N FRI. THROUGH 6:00 AM TUES.

LABOR DAY -ALL LANES OPEN: 12:00N FRI. THROUGH 6:00 AM TUES.

A DISINCENTIVE SHALL BE ASSESSED IN THE AMOUNT OF \$5,000.00 PER DAY THAT ANY LANE CLOSURES ARE PRESENT DURING THE DATES AND TIMES LISTED ABOVE.

ITEM 614 LAW ENFORCEMENT OFFICER (WITH PATROL CAR)

FOR ASSISTANCE DURING CONSTRUCTION OPERATIONS

USE OF LAW ENFORCEMENT OFFICERS (LEOS) BY CONTRACTORS OTHER THAN THE USES SPECIFIED BELOW WILL NOT BE PERMITTED AT PROJECT COST. LEOS SHOULD NOT BE USED WHERE THE OMUTCD INTENDS THAT FLAGGERS BE USED

IN ADDITION TO THE REQUIREMENTS OF CMS 614 AND THE OMUTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHALL BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS:

- DURING THE ENTIRE ADVANCE PREPARATION AND CLOSURE SEQUENCE WHERE COMPLETE BLOCKAGE OF TRAFFIC IS REQUIRED.
- DURING A TRAFFIC SIGNAL INSTALLATION WHEN IMPACTING THE NORMAL FUNCTION OF THE SIGNAL OR THE FLOW OF TRAFFIC OR WHEN TRAFFIC NEEDS TO BE DIRECTED THROUGH AN ENERGIZED TRAFFIC SIGNAL CONTRARY TO THE SIGNAL DISPLAY (E.G., DIRECTING MOTORISTS THROUGH A RED LIGHT).

LEOS SHOULD NOT FORGO THEIR TRAFFIC CONTROL RESPONSIBILITIES TO APPREHEND MOTORISTS FOR ROUTINE TRAFFIC VIOLATIONS. HOWEVER, IF A MOTORIST'S ACTIONS ARE CONSIDERED TO BE RECKLESS, THEN PURSUIT OF THE MOTORIST IS APPROPRIATE.

ANY ADDITIONAL COSTS (ADMINISTRATIVE OR OTHERWISE) INCURRED BY THE CONTRACTOR TO OBTAIN THE SERVICES OF AN LEO ARE INCLUDED WITH THE BID UNIT PRICE FOR ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR

FOR ASSISTANCE.
THE LEOS WORK AT THE DIRECTION OF THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR SECURING THE SERVICES OF THE LEOS WITH THE APPROPRIATE AGENCIES AND COMMUNICATING THE INTENTIONS OF THE PLANS WITH RESPECT TO DUTIES OF THE LEOS. THE ENGINEER SHALL HAVE FINAL CONTROL OVER THE LEOS' DUTIES AND PLACEMENT, AND WILL RESOLVE ANY ISSUES THAT MAY ARISE BETWEEN THE TWO PARTIES.

THE LEO SHALL REPORT IN TO THE CONTRACTOR PRIOR TO THE START OF THE SHIFT, IN ORDER TO RECEIVE INSTRUCTIONS REGARDING SPECIFIC WORK ASSIGNMENTS DURING HIS/HER SHIFT. THE LEO IS EXPECTED TO STAY AT THE PROJECT SITE FOR THE ENTIRE DURATION OF HIS/HER SHIFT. THE LEO SHALL REPORT TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT. ONCE THE LEO HAS COMPLETED THE DUTIES DESCRIBED ABOVE AND STILL HAS TIME REMAINING ON HIS/HER SHIFT, THE LEO MAY BE ASKED TO PATROL THROUGH THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT A LOCATION TO DETER MOTORISTS FROM SPEEDING. SHOULD IT BE NECESSARY TO LEAVE THE PROJECT SITE, THE LEO SHALL NOTIFY THE ENGINEER. THE CONTRACTOR SHALL PROVIDE THE LEO WITH A TWO—WAY COMMUNICATION DEVICE WHICH SHALL BE RETURNED TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT.

LEOS (WITH PATROL CAR) REQUIRED BY THE TRAFFIC MAINTENANCE TASKS ABOVE SHALL BE PAID FOR ON A UNIT PRICE (HOURLY) BASIS UNDER ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE 800 HOURS.

THE HOURS PAID SHALL INCLUDE ANY MINIMUM SHOW-UP TIME REQUIRED BY THE LAW ENFORCEMENT AGENCY INVOLVED.

ANY ADDITIONAL COSTS (ADMINISTRATIVE OR OTHERWISE) INCURRED BY THE CONTRACTOR TO OBTAIN THE SERVICES OF A LEO ARE INCLUDED WITH THE BID UNIT PRICE FOR ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE.

ITEM 614- WORK ZONE PAVEMENT MARKINGS

WORK ZONE PAVEMENT MARKINGS SHALL BE PLACED AFTER SURFACE COURSE APPLICATION
IF THE PERMANENT MARKINGS ARE NOT INSTALLED. THE FOLLOWING QUANTITIES
HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR THE ABOVE WORK:

TEN CAA ACO MUE WORK ZONE OFNITED LINE (DOUBLE COUR) OLACCI.	642 PAINT
(ITEM 614 — 1.62 MILE WORK ZONE, CENTER LINE (DOUBLE SOLID), CLASS I,	, 0 12 1 / (1111)
(ITEM 614 - 0.48 MILE WORK ZONE, CENTER LINE (SOLID/DASHED), CLASS I,	. 642 PAINT 1
(ITEM 614 - 796 FEET WORK ZONE, STOP LINE, CLASS I, 642 PAINT	, · · · · · · · · · · · · · · · · · · ·
(ITEM 614 - 50 EACH WORK ZONE, LANE ARROW, CLASS I, 642 PAINT	ζ
ITEM 614 — 1752 FEET WORK ZONE, CHANNELIZING LINE, CLASS 1, 8", 642 PA	AINT 3
ITEM 614 - 4.6 MILE WORK ZONE, LANE LINE, CLASS 1,4", 642 PAINT	Α
ITEM 614 - 4 EACH WORK ZONE, SCHOOL SYMBOL MARKING, 72", CLASS	1. 642 PAINT
\(\tag{ \ta	7
	\prec
ITEM 614 - 0.81 MILE WORK ZONE, CENTER LINE (DOUBLE SOLID), CLASS III	I, 642 PAINT 🗸
ITEM 614 - 0.24 MILE WORK ZONE, CENTER LINE (SOLID/DASHED), CLASS II	I, 642 PAINT ≺
ITEM 614 - 398 FEET WORK ZONE, STOP LINE, CLASS III, 642 PAINT	·
ITEM 614 - 25 EACH WORK ZONE, LANE ARROW, CLASS III, 642 PAINT	2
ITEM 614 - 876 FEET WORK ZONE, CHANNELIZING LINE, CLASS III, 8", 642 F	PAINT)
ITEM 614 - 2.3 MILE WORK ZONE, LANE LINE, CLASS III, 4", 642 PAINT)
FITEM 614 - 2 EACH WORK ZONE, SCHOOL SYMBOL MARKING, 72", CLASS	III, 642 PAINT
)

IF VEHICLE DETECTION BECOMES UNEXPECTEDLY DISABLED, REQUIRES MODIFICATION, OR IS SCHEDULED TO BE TEMPORARILY REMOVED DURING THE CONSTRUCTION PROJECT, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE PROJECT ENGINEER AND DISTRICT TRAFFIC ENGINEER.

IF THE LOSS OF VEHICLE DETECTION IS KNOWN PRIOR TO THE START OF CONSTRUCTION, IT SHALL BE DISCUSSED AT THE PRE—CONSTRUCTION MEETING. AT SUCH TIME, THE DISTRICT TRAFFIC ENGINEER SHALL ADVISE THE PROJECT ENGINEER AND CONTRACTOR ON THE APPROPRIATE ACTION TO RECTIFY ANY LOSS OF VEHICLE DETECTION. THIS MAY INCLUDE PLACING THE TRAFFIC SIGNAL ON MINIMUM OR MAXIMUM RECALL, MODIFYING THE MINIMUM GREEN TIMES, AND REMOVING THE MALFUNCTIONING DETECTION FROM SERVICE. WHERE NON—INTRUSIVE DETECTION (I.E. VIDEO, RADAR) ALREADY EXISTS, THE CONTRACTOR SHALL INSURE THAT DETECTION IS OPERATING AND MAINTAINED BY RECONFIGURING THE DETECTION UNITS ACCORDINGLY DURING ALL CONSTRUCTION PHASES. THIS IS TO AVOID THE SIGNAL FROM MAXING OUT THE EFFECTED SIGNAL PHASE AND CREATING UNNECESSARY DELAYS.

TEMPORARY NON-INTRUSIVE DETECTION IS ANTICIPATED FOR THIS PROJECT.

LOCATIONS WHERE NON-INTRUSIVE DETECTION IS PROPOSED AND THE EXISTING VEHICLE DETECTION IS TO BE ABANDON, THE NON-INTRUSIVE VEHICLE DETECTION SHALL BE INSTALLED, CONFIGURED AND MADE FULLY FUNCTIONAL PRIOR TO THE EXISTING DETECTION BEING DISABLED. THE CONTRACTOR SHALL CONTINUE TO MAINTAIN AND MODIFY THE DETECTION UNTIL FINAL ACCEPTANCE OF THE TRAFFIC SIGNAL. THIS IS TO ENSURE VEHICLE DETECTION REMAINS FULLY FUNCTIONAL THROUGHOUT CONSTRUCTION.

ALL WORK ASSOCIATED WITH THIS ITEM IS INCLUDED WITH LS 614 MAINTAINING TRAFFIC

CONSTRUCTION NOTIFICATION

THROUGHOUT THE DURATION OF THE PROJECT, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITTEN NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO ALLOW THE PROJECT ENGINEER TO MEET THE REQUIRED TIME FRAMES SET FORTH IN THE TABLE BELOW TO INFORM THE OFFICE OF COMMUNICATIONS. THIS NOTIFICATION SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE BOARDS. INFORMATION SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL CONSTRUCTION ACTIVITIES THAT IMPACT OR INTERFERE WITH TRAFFIC AND SHALL LIST THE SPECIFIC LOCATION, TYPE OF WORK, ROAD STATUS, DATE AND TIME OF RESTRICTION, DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, NUMBER OF LANES CLOSED, DETOUR ROUTES, IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

NOTICE TO OFFICE OF COMMUNICATIONS TIME TABLE

NOTICE TO OFFICE	- OF COMMUNICA	HONS TIME TABLE
ITEM	DURATION	NOTICE DUE TO OFFICE
	>= 2 WEEKS	21 CALENDAR DAYS PRIOR TO CLOSURE
ROAD CLOSURE	12 HRS2 DAYS	14 CALENDAR DAYS PRIOR TO CLOSURE
	< 12 WEEKS	4 BUSINESS DAYS PRIOR TO CLOSURE
ROAD CLOSURE	>= 2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOSURE
NOAD CLOSUNE	< 2 WEEKS	2 BUSINESS DAYS PRIOR TO CLOSURE
START OF CONSTRUCTION	N/A	14 CALENDAR DAYS PRIOR TO CLOSURE
TRAFFIC PATTERN CHANGE	N/A	14 CALENDAR DAYS PRIOR TO CLOSURE

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTICE TO OFFICE OF COMMUNICATIONS TIME TABLE.

ALCULATED ALH CHECKED

 \bigcirc

FF/

V

TR,

OF

MAINTENANCE

SHEET NUM.								PAR	<u></u>		ITEM	ITEM GRAND			SEE		
3	4	6	7	8	9	10	17	i8	01/52	2/PV 02/S>2 /NC	/P) 03/SAF/0	ITEM	EXT	TOTAL	UNIT	DESCRIPTION	SHEET NO.
										THE	,					ROADWAY	
500						1,090				1,59		202 202	30000 32000	1,590	SF FT	WALK REMOVED CURB REMOVED	
						1,759				216 1,75		252	01500	216 1,759	FT	FULL DEPTH PAVEMENT SAWING	
									1,0	00		832	30000	1,000	EACH	EROSION CONTROL EROSION CONTROL	
									7,0			032	30000	1,000	LACIT	ENOSION GONTHOL	
																DAVEHENT	
441										44		253	01000	441	SY	PAVEMENT REPAIR	
						33,954			33,			254	01000	33,954	SY	PAVEMENT PLANING, ASPHALT CONCRETE, 3"	
21										21		301	46000	21	CY	ASPHALT CONCRETE BASE, PG64-22	
						3,905			3,9	05		407	20000	3,905	GAL	NON-TRACKING TACK COAT	
						1,415			1,4			442	20000	1,415	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (448)	
00					-	1,415 1,095	-		1,4	1,59	5	442 608	20100 52001	1,415 1,595	CY SF	ASPHALT CONCRETE INTERMEDIATE COURSE, 9.5 MM, TYPE A (448) CURB RAMP, AS PER PLAN	.3
						238				238		609	26000	238	FT	CURB, TYPE 6	
					1	-	-			1		623	39500	1	EACH	MONUMENT BOX ADJUSTED TO GRADE	
				 		1	1			LS		SPECIAL	69098400	LS		MISC.: CONSULTANT FOR CONRETE QUALITY CONTROL INCLUDING TESTING AND INSPECTION	3
																DRAINAGE	
		6	6	11	3					26		611	99654	26	EACH	MANHOLE ADJUSTED TO GRADE, TELEPHONE	
		7	19 11	11						37		611	98654	37	EACH C	MANHOLE ADJUSTED TO GRADE CATCH BASIN ADJUSTED TO GRADE	
		20	11	15						46		611	98630	46		CATCH BASIN ADJUSTED TO GRADE Y	
		7		3	2					12		611	99654	12	EACH	WATER WORK MANHOLE ADJUSTED TO GRADE	
		3	3	J	1					7		638	10800	7	EACH	VALVE BOX ADJUSTED TO GRADE	
						<u> </u>											
																TRAFFIC CONTROL	
								293		29.		621	54000	293	EACH	RAISED PAVEMENT MARKER REMOVED	
								293 27		29°. 27		621 632	00100 26500	293 27	EACH EACH	RPM DETECTOR LOOP	
								27		27		632	27200	27	EACH	LOOP DETECTOR TIE IN	
								2.3	2	3		644	00200	2.3	MILE	LANE LINE, 4"	
								1,668	1,6	68		644	00620	1,668	FT	CROSSWALK LINE, 12"	
								120			120	644	00630	120	FT	CROSSWALK LINE, 24"	
						<u> </u>	25 876		8	5 '6		644 644	01300 00400	25 876	EACH FT	LANE ARROW CHANNELIZING LINE, 8"	
							070	398	3:			644	00500	398	FT	STOP LINE	
								200	2	10		644	00700	200	C.T.	TRINCYERS (RIAGONAL LINE	
								286 62	28	2		644 644	00700 01500	286 62	FT FT	TRANSVERSE/DIAGONAL LINE DOTTED LINE, 4", WHITE	
							0.81	0.24	1.0)5		644	00300	1.05	MILE	CENTER LINE	
								0.21 2	0.	21		644 644	00100 01100	0.21	MILE EACH	EDGE LINE, 4", YELLOW SCHOOL SYMBOL MARKING, 72"	
								175	17			644	00900	175	SF	ISLAND MARKING	
													~~	~~	~~	MAINTENANCE OF TRAFFIC	
	32			-	-	+	-			32		614	11110	32	HOUR	MAINTENANCE OF TRAFFIC LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	+
	2.1									2.		614	21100	2.1	MILE	WORK ZONE CENTER LINE, CLASS I, 642 PAINT	
	1.05									1.0.		614	21550 23200	1.05 1,752	MILE FT	WORK ZONE CHANNELIZING LINE CLASS I 8" CAS DAINT	
	1,752 876									1,75 876		614	23200	876	FT	WORK ZONE CHANNELIZING LINE, CLASS I, 8", 642 PAINT WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT	
	4.6 2.3	-		-		1	-			4.6		614	20100 20550	4.6 2.3	MILE MILE	WORK ZONE LANE LINE, CLASS I, 4", 642 PAINT WORK ZONE LANE LINE, CLASS III, 4", 642 PAINT	+
	796	1		1		1	1			798		614	26200	796	FT	WORK ZONE STOP LINE, CLASS I, 642 PAINT WORK ZONE STOP LINE, CLASS I, 642 PAINT	1
	398									398		614	26610	398	FT	WORK ZONE STOP LINE, CLASS III, 642 PAINT	
	50					-				50		614	30200	50	EACH	WORK ZONE ARROW, CLASS I, 642 PAINT	
	25									25		614	30650	25		WORK ZONE ARROW, CLASS II, 642 PAINT	
	4	1								4		614	31720	4	EACH	WORK ZONE SCHOOL SYMBOL MARKING, 72", CLASS I 642 PAINT	
	2			I	1	1				2		614	31740		EACH	WORK ZONE SCHOOL SYMBOL MARKING, 72", CLASS III, 642 PAINT ✓	

 \bigcirc

 \bigcirc

 \bigcirc

 \bigcirc

GENERAL SUMMARY

HAM-US 127-9.11

5 31

THE PROPOSED WORK SHALL BE PERFORMED WITH THE LEAST INCONVENIENCE TO, AND THE MAXIMUM SAFETY OF THE TRAVELING PUBLIC AND WORKERS. ANY VARIANCES FROM THE PERMITTED REQUIREMENTS MUST BE APPROVED IN ADVANCE, IN WRITING, BY THE CITY. EXCEPT AS MODIFIED BELOW, THE REQUIREMENT FOR MAINTAINING TRAFFIC AS INDICATED IN THE "OHIO MANUAL OF UNIFORM TRAFFIC CONTROL SHALL APPLY. IN ADDITION TO ITEM 614, MAINTAINING TRAFFIC, AS SET FORTH IN THE STATE OF OHIO DEPARTMENT OF TRANSPORTATION CONSTRUCTION AND MATERIALS SPECIFICATIONS, THE FOLLOWING NOTES SHALL APPLY TO THE WORK CARRIED OUT WITHIN THE LIMITS OF THE PROJECT:

A MINIMUM OF ONE LANE OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES FOR THE PROJECT EXCEPT FOR THE RONALD REGAN CROSS COUNTY HIGHWAY INTERCHANGE AREA AT THE FOLLOWING

ONE LEFT TURN LANE AND ONE THROUGH LANE MUST BE MAINTAINED IN EACH DIRECTION BETWEEN STATION 100+00 TO 104+50.

TEMPORARY DETECTION DURING CONSTRUCTION WILL BE NECESSARY FOR THE PROPER OPERATION OF SIGNALS AT THE RONALD REGAN CROSS COUNTY HIGHWAY AND POTENTIALLY AT OTHER SIGNALIZED INTERSECTIONS.

THE CONTRACTOR SHALL SUBMIT A CONSTRUCTION SEQUENCING SCHEDULE PRIOR TO WORK BEGINNING FOR APPROVAL BY THE CITY ENGINEER. THE CONSTRUCTION SEQUENCING SCHEDULE SHALL TAKE INTO CONSIDERATION ALL ASPECTS OF THE PROJECT INCLUDING HOW LOCAL TRAFFIC TO THE BUSINESSES WILL BE MAINTAINED. THE CONSTRUCTION SEQUENCE WILL NEED TO BE APPROVED BY THE ENGINEER BEFORE THE COMMENCEMENT OF WORK.

ACCESS TO AND FROM ALL LOCAL RESIDENTIAL AND BUSINESS DRIVES WITHIN THE LIMITS OF THIS PROJECT SHALL BE MAINTAINED AT ALL TIMES BY USING THE EXISTING PAVEMENT, TEMPORARY PAVEMENT, AND THE PROPOSED PAVEMENT, UNLESS OTHERWISE DIRECTED BY THE CITY ENGINEER.

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF MAINTENANCE OF TRAFFIC SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

THE CONTRACTOR SHALL ADJUST THE LOCATION AND/OR SPACING OF ALL TRAFFIC CONTROL CHANNELIZING DEVICES AS DICTATED BY THE PROGRESS OF THE REQUIRED WORK TO ALLOW CONSTRUCTION ACCESS TO WORK AREAS WHILE MAINTAINING SAFE AND EFFECTIVE TRAFFIC CONTROL DURING ALL CONSTRUCTION OPERATIONS. ANY DAMAGE TO MAINTENANCE OF TRAFFIC EQUIPMENT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REPLACE OR CORRECT.

THE ROADWAY SHALL NOT BE RESTRICTED TO ANY LANE CLOSURE DURING PERIODS OF INTERMITTENT OR IRREGULAR WORK, NOR CLOSED SOLELY FOR THE CONVENIENCE OF THE CONTRACTOR.

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH C&MS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614. MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

NO WORK SHALL BE PERFORMED AND ALL EXISTING LANES SHALL BE OPEN TO TRAFFIC DURING THE FOLLOWING DESIGNATED HOLIDAYS OR EVENTS:

MEMORIAL DAY -ALL LANES OPEN: 12:00N FRI. THROUGH 6:00 AM TUES.

FOURTH OF JULY -ALL LANES OPEN: 12:00N FRI. THROUGH 6:00 AM TUES.

LABOR DAY -ALL LANES OPEN: 12:00N FRI. THROUGH 6:00 AM TUES.

A DISINCENTIVE SHALL BE ASSESSED IN THE AMOUNT OF \$5,000.00 PER DAY THAT ANY LANE CLOSURES ARE PRESENT DURING THE DATES AND TIMES LISTED ABOVE.

ITEM 614 LAW ENFORCEMENT OFFICER (WITH PATROL CAR)

FOR ASSISTANCE DURING CONSTRUCTION OPERATIONS

USE OF LAW ENFORCEMENT OFFICERS (LEOS) BY CONTRACTORS OTHER THAN THE USES SPECIFIED BELOW WILL NOT BE PERMITTED AT PROJECT COST. LEOS SHOULD NOT BE USED WHERE THE OMUTCD INTENDS THAT FLAGGERS BE

IN ADDITION TO THE REQUIREMENTS OF CMS 614 AND THE OMUTCD, A UNIFORMED LEO WITH AN OFFICIAL PATROL CAR (CAR WITH TOP-MOUNTED EMERGENCY FLASHING LIGHTS AND COMPLETE MARKINGS OF THE APPROPRIATE LAW ENFORCEMENT AGENCY) SHALL BE PROVIDED FOR THE FOLLOWING TRAFFIC CONTROL TASKS:

- DURING THE ENTIRE ADVANCE PREPARATION AND CLOSURE SEQUENCE WHERE COMPLETE BLOCKAGE OF TRAFFIC IS REQUIRED.
- DURING A TRAFFIC SIGNAL INSTALLATION WHEN IMPACTING THE NORMAL FUNCTION OF THE SIGNAL OR THE FLOW OF TRAFFIC OR WHEN TRAFFIC NEEDS TO BE DIRECTED THROUGH AN ENERGIZED TRAFFIC SIGNAL CONTRARY TO THE SIGNAL DISPLAY (E.G., DIRECTING MOTORISTS THROUGH A RED LIGHT).

LEOS SHOULD NOT FORGO THEIR TRAFFIC CONTROL RESPONSIBILITIES TO APPREHEND MOTORISTS FOR ROUTINE TRAFFIC VIOLATIONS. HOWEVER, IF A MOTORIST'S ACTIONS ARE CONSIDERED TO BE RECKLESS. THEN PURSUIT OF THE MOTORIST IS APPROPRIATE.

ANY ADDITIONAL COSTS (ADMINISTRATIVE OR OTHERWISE) INCURRED BY THE CONTRACTOR TO OBTAIN THE SERVICES OF AN LEO ARÉ INCLUDED WITH THE BID UNIT PRICE FOR ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE.

THE LEOS WORK AT THE DIRECTION OF THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR SECURING THE SERVICES OF THE LEOS WITH THE APPROPRIATE AGENCIES AND COMMUNICATING THE INTENTIONS OF THE PLANS WITH RESPECT TO DUTIES OF THE LEOS. THE ENGINEER SHALL HAVE FINAL CONTROL OVER THE LEOS' DUTIES AND PLACEMENT, AND WILL RESOLVE ANY ISSUES THAT MAY ARISE BETWEEN THE TWO PARTIES.

THE LEO SHALL REPORT IN TO THE CONTRACTOR PRIOR TO THE START OF THE SHIFT, IN ORDER TO RECEIVE INSTRUCTIONS REGARDING SPECIFIC WORK ASSIGNMENTS DURING HIS/HER SHIFT. THE LEO IS EXPECTED TO STAY AT THE PROJECT SITE FOR THE ENTIRE DURATION OF HIS/HER SHIFT. THE LEO SHALL REPORT TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT. ONCE THE LEO HAS COMPLETED THE DUTIES DESCRIBED ABOVE AND STILL HAS TIME REMAINING ON HIS/HER SHIFT, THE LEO MAY BE ASKED TO PATROL THROUGH THE WORK ZONE (WITH FLASHING LIGHTS OFF) OR BE PLACED AT A LOCATION TO DETER MOTORISTS FROM SPEEDING. SHOULD IT BE NECESSARY TO LEAVE THE PROJECT SITE, THE LEO SHALL NOTIFY THE ENGINEER. THE CONTRACTOR SHALL PROVIDE THE LEO WITH A TWO-WAY COMMUNICATION DEVICE WHICH SHALL BE RETURNED TO THE CONTRACTOR AT THE END OF HIS/HER SHIFT.

LEOS (WITH PATROL CAR) REQUIRED BY THE TRAFFIC MAINTENANCE TASKS ABOVE SHALL BE PAID FOR ON A UNIT PRICE (HOURLY) BASIS UNDER ITEM 614, LAW ENFORCEMENT OFFICER (WITH PATROL CAR) FOR ASSISTANCE. THE FOLLOWING ESTIMATED SUBSUMMARY HAVE BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 614. LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE *32 HOURS.*

THE HOURS PAID SHALL INCLUDE ANY MINIMUM SHOW—UP TIME REQUIRED BY THE LAW ENFORCEMENT AGENCY INVOLVED.

ANY ADDITIONAL COSTS (ADMINISTRATIVE OR OTHERWISE) INCURRED BY THE CONTRACTOR TO OBTAIN THE SERVICES OF A LEO ARE INCLUDED WITH THE BID UNIT PRICE FOR ITEM 614, LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE.

ITEM 614- WORK ZONE PAVEMENT MARKINGS

WORK ZONE PAVEMENT MARKINGS SHALL BE PLACED AFTER SURFACE COURSE APPLICATION IF THE PERMANENT MARKINGS ARE NOT INSTALLED. THE FOLLOWING QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR THE ABOVE WORK:

>	ITEM 614 - 1.20	MILE	WORK ZONE, CENTER LINE (SOLID/DASHED), CLASS I, 642 PAINT
>	ITEM 614 - 712	FEET	WORK ZONE, STOP LINE, CLASS I, 642 PAINT
\succ	ITEM 614 - 78	EACH	WORK ZONE, LANE ARROW, CLASS I, 642 PAINT
>	ITEM 614 - 3242	FEET	WORK ZONE, CHANNELIZING LINE, CLASS 1,8", 642 PAINT
>	ITEM 614 - 0.92	MILE	WORK ZONE, LANE LINE, CLASS I, 4", 642 PAINT
>			
\rangle			
>	ITEM 614 - 0.89	MILE	WORK ZONE, CENTER LINE (DOUBLE SOLID), CLASS III, 642 PAINT
>	ITEM 614 - 0.60	MILE	WORK ZONE, CENTER LINE (SOLID/DASHED), CLASS III, 642 PAINT
>	ITEM 614 - 356	FEET	WORK ZONE, STOP LINE, CLASS III, 642 PAINT
>	ITEM 614 - 39	EACH	WORK ZONE, LANE ARROW, CLASS III, 642 PAINT

ITEM 614 - 1621 FEET WORK ZONE, CHANNELIZING LINE, CLASS III, 8", 642 PAINT

ITEM 614 - 0.46 MILE WORK ZONE, LANE LINE, CLASS III, 4", 642 PAINT

ITEM 614 - 1.78 MILE WORK ZONE, CENTER LINE (DOUBLE SOLID), CLASS I, 642 PAINT

DETECTION MAINTENANCE

IF VEHICLE DETECTION BECOMES UNEXPECTEDLY DISABLED, REQUIRES MODIFICATION, OR IS SCHEDULED TO BE TEMPORARILY REMOVED DURING THE CONSTRUCTION PROJECT, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE PROJECT ENGINEER AND DISTRICT TRAFFIC ENGINEER.

IF THE LOSS OF VEHICLE DETECTION IS KNOWN PRIOR TO THE START OF CONSTRUCTION, IT SHALL BE DISCUSSED AT THE PRE-CONSTRUCTION MEETING. AT SUCH TIME, THE DISTRICT TRAFFIC ENGINEER SHALL ADVISE THE PROJECT ENGINEER AND CONTRACTOR ON THE APPROPRIATE ACTION TO RECTIFY ANY LOSS OF VEHICLE DETECTION. THIS MAY INCLUDE PLACING THE TRAFFIC SIGNAL ON MINIMUM OR MAXIMUM RECALL, MODIFYING THE MINIMUM GREEN TIMES, AND REMOVING THE MALFUNCTIONING DETECTION FROM SERVICE. WHERE NON-INTRUSIVE DETECTION (I.E. VIDEO, RADAR) ALREADY EXISTS, THE CONTRACTOR SHALL INSURE THAT DETECTION IS OPERATING AND MAINTAINED BY RECONFIGURING THE DETECTION UNITS ACCORDINGLY DURING ALL CONSTRUCTION PHASES. THIS IS TO AVOID THE SIGNAL FROM MAXING OUT THE EFFECTED SIGNAL

TEMPORARY NON-INTRUSIVE DETECTION IS ANTICIPATED FOR THIS PROJECT.

LOCATIONS WHERE NON-INTRUSIVE DETECTION IS PROPOSED AND THE EXISTING VEHICLE DETECTION IS TO BE ABANDON, THE NON-INTRUSIVE VEHICLE DETECTION SHALL BE INSTALLED, CONFIGURED AND MADE FULLY FUNCTIONAL PRIOR TO THE EXISTING DETECTION BEING DISABLED. THE CONTRACTOR SHALL CONTINUE TO MAINTAIN AND MODIFY THE DETECTION UNTIL FINAL ACCEPTANCE OF THE TRAFFIC SIGNAL. THIS IS TO ENSURE VEHICLE DETECTION REMAINS FULLY FUNCTIONAL THROUGHOUT CONSTRUCTION.

CONSTRUCTION NOTIFICATION

PHASE AND CREATING UNNECESSARY DELAYS.

THROUGHOUT THE DURATION OF THE PROJECT, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IN WRITING OF ALL TRAFFIC RESTRICTIONS AND UPCOMING MAINTENANCE OF TRAFFIC CHANGES. THE CONTRACTOR SHALL ENSURE THE WRITTEN NOTIFICATION IS SUBMITTED IN A TIMELY MANNER TO ALLOW THE PROJECT ENGINEER TO MEET THE REQUIRED TIME FRAMES SET FORTH IN THE TABLE BELOW TO INFORM THE OFFICE OF COMMUNICATIONS. THIS NOTIFICATION SHALL BE RECEIVED BY THE PROJECT ENGINEER PRIOR TO THE PHYSICAL SETUP OF ANY APPLICABLE SIGNS OR MESSAGE BOARDS. INFORMATION SHOULD INCLUDE, BUT IS NOT LIMITED TO, ALL CONSTRUCTION ACTIVITIES THAT IMPACT OR INTERFERE WITH TRAFFIC AND SHALL LIST THE SPECIFIC LOCATION, TYPE OF WORK, ROAD STATUS, DATE AND TIME OF RESTRICTION, DURATION OF RESTRICTION, NUMBER OF LANES MAINTAINED, NUMBER OF LANES CLOSED, DETOUR ROUTES, IF APPLICABLE, AND ANY OTHER INFORMATION REQUESTED BY THE PROJECT ENGINEER.

NOTICE TO OFFICE OF COMMUNICATIONS TIME TADIS

NOTICE TO OFFICE	- OF COMMUNICA	HONS TIME TABLE
ITEM	DURATION	NOTICE DUE TO OFFICE
	>= 2 WEEKS	21 CALENDAR DAYS PRIOR TO CLOSURE
ROAD CLOSURE	12 HRS2 DAYS	14 CALENDAR DAYS PRIOR TO CLOSURE
	< 12 WEEKS	4 BUSINESS DAYS PRIOR TO CLOSURE
ROAD CLOSURE	>= 2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOSURE
NOAD CLOSURE	< 2 WEEKS	2 BUSINESS DAYS PRIOR TO CLOSURE
START OF CONSTRUCTION	N/A	14 CALENDAR DAYS PRIOR TO CLOSURE
TRAFFIC PATTERN CHANGE	N/A	14 CALENDAR DAYS PRIOR TO CLOSURE

ANY UNFORESEEN CONDITIONS NOT SPECIFIED IN THE PLANS REQUIRING TRAFFIC RESTRICTIONS SHALL ALSO BE REPORTED TO THE PROJECT ENGINEER USING THE NOTICE TO OFFICE OF COMMUNICATIONS TIME TABLE.

SEE		050001071011		GRAND	ITEM		₹₹.	PAF		SHEET NUM.								
ET N	SHE	DESCRIPTION	UNIT	TOTAL	EXT	ITEM	05/S>2/PV /MTH	04/S>2/PV			17	16	9	8	7	6	4	3
		ROADWAY					ZMIH	+ +										
		WALK REMOVED	SF	1,686	30000	202	1,686						1,286					00
		CURB REMOVED	FT	242	32000	202	242	110			<u> </u>		242					
		PAVEMENT REMOVED	SY	424	23000	202	308	116					424					
		EROSION CONTROL EROSION CONTROL	EACH	1,000	30000	832		1,000			<u> </u>						1,000	
		ENOSION CONTINUE	LACIT	7,000	30000	032		1,000									1,000	
		O LUCHEUT.																
		PAVEMENT FULL DEPTH PAVEMENT SAWING	FT	2,573	01500	252	2,573	+			<u> </u>		2,573					
		PAVEMENT REPAIR	SY	496	01000	253	496											6
		PAVEMENT PLANING, ASPHALT CONCRETE, 3" ASPHALT CONCRETE BASE. PG64-22	SY	34,732	01000	254	10	34,732			<u> </u>		34,732)
		ASPHALI LUNUKETE BASE, PG64-22	CY	18	46000	301	18	+			<u> </u>							3
		NON-TRACKING TACK COAT	GAL	3,994	20000	407		3,994					3,994					
		ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (448) ASPHALT CONCRETE INTERMEDIATE COURSE. 9.5 MM. TYPE A (448)	CY	1,448	20000 20100	442 442		1,448			<u> </u>		1,448					
		II" NON-REINFORCED CONCRETE PAVEMENT, CLASS OC IP	CY SY	1,448 424	14110	442	308	1,448 116			<u> </u>		1,448 424					
3		CURB RAMP, AS PER PLAN	SF	1,682	52001	608	1,682						1,282					00
		COMBINATION CURB AND GUTTER, TYPE 3	FT	36	18000	609	36				<u> </u>		36					
		CURB, TYPE 6	FT	209	26000	609	209	+			<u> </u>		209					
-		MONUMENT BOX ADJUSTED TO GRADE	EACH	1	39500	623	1						200			1		
		PULL BOX REMOVED AND REPLACED	EACH	3	31506	625	3				<u> </u>				3			
		MISC.: CONSULTANT FOR CONRETE QUALITY CONTROL INCLUDING TESTING AND INSPECTION		LS	69098400	SPECIAL	LS	+										
		DRAINAGE MANHOLE ADJUSTED TO GRADE, CLEANOUT	EACH	1	99654	611	1	+		\vdash	<u> </u>			,				
			EACH	29	99654	611	29	+ + +			 			10	7	12		
		CATCH BASIN ADJUSTED TO GRADE	EACH	37	98630	611	37							14	10	13		
		MANHOLE ADJUSTED TO ORADE. TO EPHONE	EACH	6	99654	611	6			\vdash	<u> </u>					6		
		WATER WORK						+										
		MANHOLE ADJUSTED TO GRADE	EACH	3	99654	611	3							1		2		
		VALVE BOX ADJUSTED TO GRADE	EACH	65	10800	638	65	+			<u> </u>			20	27	18		
		TRAFFIC CONTROL RAISED PAVEMENT MARKER REMOVED	EACH	314	54000	621	314			-	<u> </u>	314						
		RPM	EACH	314	00100	621	314	+ +			<u> </u>	314						
		DETECTOR LOOP	EACH	17	26500	632	17					17						
		LOOP DETECTOR TIE IN LANE LINE, 4"	EACH MILE	17 0.46	27200 00200	632 644	17	0.46		-	<u> </u>	17 0.46						
		LANE LINE, 4	WILL	0.40	00200	044		0.40			<u> </u>	0.40						
		EDGE LINE, 4"	MILE	0.72	00100	644		0.72			0.72							
		CROSSWALK LINE, 12" CROSSWALK LINE, 24"	FT FT	1,137 1,152	00620 00630	644 644		1,137 1,152		\vdash	<u> </u>	1,137 1,152						
		LANE ARROW	EACH	39	01300	644		39			<u> </u>	39						
		CHANNELIZING LINE, 8"	FT	1,621	00400	644		1,621			1,621							
		STOP LINE	FT	356	00500	644		356		-	 '	356						
		TRANSVERSE/DIAGONAL LINE	FT	2,358	00700	644		2,358			2,358	330						
		DOTTED LINE, 4", WHITE	FT	132	01500	644		132				132						
		CENTER LINE PARKING LOT STALL MARKING	MILE FT	1.49 1,008	00300 01200	644 644	1,008	1.49		-	0.89 1,008	0.6						
		ISLAND MARKING	SF	53	00900	644	1,000	53			1,000	53						
		MAINIENANCE OF TRAFFIC LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	HOUR	32	<u> </u>	614	32	+		\vdash	<u> </u>						32	
		WORK ZONE CENTER LINE, CLASS I, 642 PAINT	MILE	2.98	21100	614	2.98	+ +		 	 '						2.98	
_		WORK ZONE CENTER LINE, CLASS III, 642 PAINT	MILE	1.49	21550	614	1.49										1.49	
		WORK ZONE CHANNELIZING LINE, CLASS I, 8", 642 PAINT WORK ZONE CHANNELIZING LINE, CLASS III, 8", 642 PAINT	FT FT	3,242 1,621	23200 23680	614 614	3,242 1,621	+		\vdash	<u> </u>						3,242 1,621	
_		WORN ZONE GRANNELIZING LINE, CLASS III, 0 , 042 FAINT	FI	1,021	23000	OIH	1,021	+ +		 	<u> </u>						1,021	
								+ +	-									
		WORK ZONE LANE LINE, CLASS I, 4", 642 PAINT	MILE	0.92	20100	614	0.92	+ · - +			Ļ						0.92	
		WORK ZONE LANE LINE, CLASS I, 4", 642 PAINT WORK ZONE LANE LINE, CLASS III, 4", 642 PAINT WORK ZONE STOP LINE, CLASS I, 642 PAINT	MILE MILE FT	0.92 0.46 712	20100 20550 26200	614 614 614	0.92 0.46 712	-									0.92 0.46 712	

 \bigcirc

 \bigcirc

 \bigcirc

 \bigcirc

	SHEET	NUMB	BER					ITEM	ITEM	GRAND TOTAL UNIT	DESCRIPTION	LCULATED ALH		
3	4	6	7	8	9	16	17	04/S>2/PV	05/S>2/PV/MTH					NO.
	<i>78</i>								<i>78</i>	614	<i>*</i>	78 EACH	WORK ZONE ARROWS, CLASS 1, 642 PAINT,	
	39								39	614	30650	<i>39 EACH</i>	WORK ZONE ARROWS, CLASS 111, 642 PAINT,	
											· · · · · · · · · · · · · · · · · · ·		INCIDENTALS	
								LS		614	11000	LS	MAINTAINING TRAFFIC	
								LS LS		623 624	10000 10000	LS LS	CONSTRUCTION LAYOUT STAKES & SURVEYING MOBILIZATION	
														A A X
														74
														IER,
														<u> </u>
														23
														10.
														5A
														$\frac{3A}{28}$

O:\4197-C3D\DWG\4197-C3D.dwg, 12/13/2021 6:15:10 PM, DWG To PDF.pc3