SHEET NUMBER	PARTICIPATION	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
						ROADWAY	
		201	11000	LS		CLEARING AND GRUBBING	
		202	20010	1	EACH	HEADWALL REMOVED	
		202	23010	208	SY	PAVEMENT REMOVED, ASPHALT	
		202	35100	201	FT	PIPE REMOVED, 24" AND UNDER	
		202	38000	150	FT	GUARDRAIL REMOVED	
		203	10001	1471	CY	EXCAVATION, AS PER PLAN	4
		203	20000	1337	CY	EMBANKMENT	
		203	35141	75	CY	GRANULAR MATERIAL, TYPE E, AS PER PLAN	6
		204	10000	289	SY	SUBGRADE COMPACTION	
		204	50001	150	SY	GEOTEXTILE FABRIC, AS PER PLAN	6
		606	13000	150	FT	GUARDRAIL, TYPE 5	
		878	25000	LS		INSPECTION AND COMPACTION TESTING OF UNBOUND MATERIALS	
						EROSION CONTROL	
		601	32200	13	CY	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
		659	00100	2	EACH	SOIL ANALYSIS TEST	4
		659	00300	115	CY	TOPSOIL	4
		659	10000	1034	SY	SEEDING AND MULCHING	4
		659	14000	52	SY	REPAIR SEEDING AND MULCHING	4
		659	15000	52	SY	INTER-SEEDING	4
		659	20000	0.14	TON	COMMERCIAL FERTILIZER	4
		659	31000	0.21	ACRE	LIME	4
		659	35000	6	MGAL	WATER	4
		832	30000	5000	EACH	EROSION CONTROL	
						DRAINAGE	
		518	40000	418	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	
		601	21060	44	SY	TIED CONCRETE BLOCK MAT, TYPE 2	
		602	20000	0.3	CY	CONCRETE MASONRY	
		605	14000	145	FT	6" BASE PIPE UNDERDRAINS	
		611	01500	52	FT	6" CONDUIT, TYPE F	
		611	08200	77	FT	18" CONDUIT, TYPE F, 707.05 TYPE C OR 707.21	4
		611	99660	1	EACH	MANHOLE RECONSTRUCTED TO GRADE	
		611	99710	1	EACH	PRECAST REINFORCED CONCRETE OUTLET	
						PAVEMENT	
		252	01500	164	FT	FULL DEPTH PAVEMENT SAWING	
		302	46000	74	CY	ASPHALT CONCRETE BASE, PG64-22	
		304	20000	36	CY	AGGREGATE BASE	
		407	10000	8	GAL	TACK COAT	
		442	10000	9	CY	ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)	
		442	10100	10	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446)	
		609	24511	145	FT	CURB, TYPE 4-C, AS PER PLAN	4
						TRAFFIC SURVEILLANCE	
		625	22990	200	FT	NO. 6 AWG 600 VOLT DISTRIBUTION CABLE	4
		625	25750	200	FT	CONDUIT, 4", MULTICELL, 725.20, EPC-40	4
		625	29000	200	FT	TRENCH	4
		625	36000	200	FT	PLASTIC CAUTION TAPE	4
		804	15010	4375	FT	FIBER OPTIC CABLE, 24 FIBER	4
		809	70000	LS		MAINTAING ITS DURING CONSTRUCTION	4
						TRAFFIC CONTROL	
		618	40100	145	FT	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE)	
		621	00100	4	EACH	RPM	
		644	00100	0.03	MILE	EDGE LINE, 4"	
						MAINTENACE OF TRAFFIC	
		614	11110	100	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR ASSISTANCE	5
		614	18601	2	SNMT	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	6
		616	10000	9	MGAL	WATER	6
						INCIDENTALS	
		614	11000	LS		MAINTAINING TRAFFIC	
		623	10000	LS		CONSTRUCTION LAYOUT STAKES AND SURVEYING	
		624	10000	LS		MOBILIZATION	

CALCULATED SDC
CHECKED SCS

GENERAL SUMMARY

HAM-75-3.28

I:\ProjectData\HAM\110271_HAM-75-3.28\Design\Roadway\Sheets\110271_GG001.dgn Sheet 6/29/2020 10:01:19 AM asadowsk