

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000GY101.dgn 2021-01-09 4:28:23 PM william.croxtson\ODOTcadd_PDF_pltcfg ODOTV81_Pen-ME.tbi IBI Group

PROPOSED LEGEND

- 1 ITEM 442 - (1.5") ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (447), AS PER PLAN
- 2A ITEM 442 - (1.75") ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446), PG64-28
- 2B ITEM 442 - (VAR DEPTH, 2" AVG) ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446), AS PER PLAN (0" MIN, 4" MAX)
- 3 ITEM 302 - 11" ASPHALT CONCRETE BASE, PG64-22 (PLACED IN TWO 5.5" LIFTS WITH 6" EDGE COURSE)
- 4 ITEM 407 - NON-TRACKING TACK COAT (APPLIED @ AVG 0.055 GAL/SY FOR NEW ASPHALT) (APPLIED @ AVG 0.085 GAL/SY FOR MILLED ASPHALT SURFACE)
- 5 ITEM 304 - (8") AGGREGATE BASE
- 6 CHEMICALLY STABILIZED SUBGRADE:
 ITEM 204 - PROOF ROLLING (APPLIED @ 1 HR/2000 SY FOR RECONSTRUCTION) (APPLIED @ 1 HR/3000 SY FOR NEW CONSTRUCTION)
 ITEM 206 - CEMENT (APPLIED @ 5% PER 115 LB/CF SOIL)
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 ITEM 206 - CURING COAT
 ITEM 206 - MIXTURE DESIGN FOR CHEMICALLY STABILIZED SOILS (SPECIFIED ON PROJECTS > 40,000 SY, SEE SUPPLEMENT 1120)
- 7 ITEM 442 - (1.5") ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE A (448)
- 8A ITEM 442 - (1.75") ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (448), PG64-28
- 8B ITEM 442 - (VAR. DEPTH, 2" AVG) 1.75" ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (448), AS PER PLAN (0" MIN, 4" MAX)
- 9A ITEM 301 - ASPHALT CONCRETE BASE, PG64-22 (10" SHARON ROAD (PLACED IN TWO 5" LIFTS), 6" CHESTER ROAD)
- 9B ITEM 301 - (VAR. DEPTH, 2" AVG) ASPHALT CONCRETE BASE, PG64-22, AS PER PLAN (4" MIN, SHARON ROAD & CHESTER ROAD)
- 10 ITEM 204 - SUBGRADE COMPACTION
 ITEM 204 - PROOF ROLLING (APPLIED @ 1 HR/2000 SY FOR RECONSTRUCTION) (APPLIED @ 1 HR/3000 SY FOR NEW CONSTRUCTION)
- 11 ITEM 605 - 6" BASE PIPE UNDERDRAINS (18" DEPTH)
- 12 ITEM 605 - 6" SHALLOW PIPE UNDERDRAINS (24" OR 30" DEPTH)
- 13 ITEM 659 - SEEDING AND MULCHING
- 14 ITEM 622 - CONCRETE BARRIER, SINGLE SLOPE, TYPE D
- 15 UNDERCUT AND REPLACE:
 ITEM 204 - EXCAVATION OF SUBGRADE, 18 INCHES DEEP
 ITEM 204 - GRANULAR MATERIAL, TYPE C
 ITEM 204 - GEOTEXTILE FABRIC
- 16 ITEM 606 - GUARDRAIL, TYPE MGS
- 17 ITEM 452 - 13.5" NON-REINFORCED CONCRETE PAVEMENT, CLASS CQ1
- 18 ITEM 609 - COMBINATION CURB AND GUTTER, TYPE 2
- 19 ITEM 609 - COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN (13.25" THICK)
- 20 ITEM 608 - 4" CONCRETE WALK
- 21 ITEM 526 - REINFORCED CONCRETE APPROACH SLABS (T=17")
- 23 ITEM 254 - PAVEMENT PLANING, ASPHALT CONCRETE (1"-3.25") (1" MIN, 3.25" MAX)
- 24 ITEM 252 - FULL DEPTH PAVEMENT SAWING
- 25 ITEM 601 - PAVED GUTTER, TYPE 4

NOTES


1. STATION EQUATION FOR I-75 MAINLINE SPLIT
 STA. 358+82.52 @ CONST. I-75 SB BK.=
 STA. 359+17.48 @ CONST. I-75 NB BK.=
 STA. 359+00.00 @ CONST. I-75 AH.

2. THE PAVED SHOULDER WIDTHS IDENTIFIED WITH "#" INDICATES THE PAVED WIDTH IS EQUAL TO THE GRADED SHOULDER WIDTH.


3. THE EXISTING PAVEMENT BUILDUP (COMPOSITION AND DEPTHS) ARE BASED ON EXISTING PLAN INFORMATION AND AVERAGE RESULTS OF BORING LOCATIONS PER SUBSURFACE INVESTIGATION REPORT BY RESOURCE INTERNATIONAL DATED OCTOBER 2016

EXISTING LEGEND

- A EXISTING ASPHALT CONCRETE (3"± I-75 MAINLINE, 3"± RAMPS, 4" SHARON ROAD, 3" CHESTER ROAD)
- B EXISTING REINFORCED CONCRETE PAVEMENT (9" RAMPS, 9" SHARON ROAD, 10" I-75 MAINLINE)
- C EXISTING SUBBASE (VARIES 6-8", 6" TYP.)
- D EXISTING 3" WATERPROOFED BITUMINOUS BASE COURSE, TYPE B
- E EXISTING 5" STABILIZED CRUSHED AGGREGATE SHOULDERS
- F EXISTING CONCRETE CURB AND GUTTER
- G EXISTING CONCRETE WALK
- H 6"-10" ASPHALT CONCRETE BASE
- I EXISTING 12" BITUMINOUS 301 BASE
- J EXISTING 6" BITUMINOUS 301 BASE
- K EXISTING 5" BITUMINOUS 301 BASE
- L FUTURE EXISTING ITEM 442 - 1.5" ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446) (SEE HAM-75-12.60, PID 82288)
- M FUTURE EXISTING ITEM 442 - 1.75" ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446) (SEE HAM-75-12.60, PID 82288)
- N FUTURE EXISTING ITEM 302 - 13" ASPHALT CONCRETE BASE, PG64-22 (SEE HAM-75-12.60, PID 82288)
- O FUTURE EXISTING ITEM 304 - 6" AGGREGATE BASE (SEE HAM-75-12.60, PID 82288)
- P FUTURE EXISTING ITEM 622 - CONCRETE BARRIER, SINGLE SLOPE, TYPE B1 (STA. 324+00 TO STA. 327+00 @ CONST. I-75 SB) OR TYPE C1 (STA. 327+00 TO STA. 329+34.11 @ CONST. I-75 SB) (SEE HAM-75-12.60, PID 82288)
- Q EXISTING NON-REINFORCED CONCRETE PAVEMENT (13.5" RAMP C, RAMP G)




PAVED SHOULDER (3' TO 10' WIDTH) CROSS SLOPE DETAILS FOR HIGH SIDE OF SUPERELEVATED SECTION




PAVED SHOULDER CROSS SLOPE DETAILS FOR LOW SIDE OF SUPERELEVATED SECTION


A 0.040 OR SAME SLOPE AS RATE OF SUPERELEVATION, WHICHEVER IS GREATER




PAVED SHOULDER EDGE COURSE DETAIL (FLEXIBLE PAVEMENT) PAVED SHOULDER EDGE COURSE DETAIL (RIGID PAVEMENT) APPROACH SLAB EDGE COURSE DETAIL



ITEM 203 - EXCAVATION OR ITEM 203 - EMBANKMENT APPROXIMATE LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE CURB AND GUTTER - SHARON ROAD EDGE COURSE DETAIL CURB AND GUTTER - CHESTER ROAD EDGE COURSE DETAIL




PAVED SHOULDER AND SINGLE SLOPE BARRIER, TYPE D EDGE COURSE DETAIL DETAIL APPLIES: STA. 325+00, LT. TO STA. 342+00, LT. (I-75 SB)




FUTURE EXISTING MEDIAN CONCRETE BARRIER DETAIL DETAIL APPLIES: STA. 324+00 TO STA. 329+34.11


J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000GY102.dgn 2021-01-09 4:34:45 PM william.croston\ ODOTcadd_PDF.plt:fg ODOTV8I_Pen-ME.tbl IBI Group




EXISTING NORMAL SECTION - I-75
SOUTHBOUND SHOWN, NORTHBOUND OPPOSITE HAND
SECTION APPLIES BETWEEN GLENDALE-MILFORD ROAD
AND I-275 INTERCHANGES




EXISTING NORMAL SECTION - I-75
SOUTHBOUND SHOWN, NORTHBOUND OPPOSITE HAND
SECTION APPLIES APPROX. 400' IN ADVANCE OF
AND PAST EXISTING STRUCTURES HAM-75-15.39 L&R




EXISTING SUPERELEVATED SECTION - I-75 SOUTHBOUND
SECTION APPLIES BETWEEN GLENDALE-MILFORD ROAD
AND I-275 INTERCHANGES



EXISTING SUPERELEVATED SECTION - I-75 NORTHBOUND
SECTION APPLIES BETWEEN GLENDALE-MILFORD ROAD
AND I-275 INTERCHANGES



EXISTING NORMAL/SUPERELEVATED SECTION - I-75 RAMPS
RAMP G AND RAMP E SHOWN,
RAMP A AND RAMP C OPPOSITE HAND



EXISTING NORMAL SECTION - RAMP C AND RAMP G
RAMP C SECTION APPLIES 140.18' IN ADVANCE OF SHARON ROAD
RAMP G SECTION APPLIES 151.71 IN ADVANCE OF SHARON ROAD

TYPICAL SECTIONS - I-75

HAM-75-14.61

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000GN002.dgn 2021-01-09 3:19:25 PM william.croxtor' ODOTcadd_PDF.pltcfgr _ODOTV81_Pen.tbl IBI Group

ITEM 201-CLEARING AND GRUBBING:

ALTHOUGH THERE ARE NO TREES OR STUMPS SPECIFICALLY MARKED FOR REMOVAL WITHIN THE LIMITS OF THE PROJECT, A LUMP SUM QUANTITY IS INCLUDED IN THE GENERAL SUMMARY FOR ITEM 201-CLEARING AND GRUBBING. ALL PROVISIONS AS SET FORTH IN THE SPECIFICATIONS UNDER THIS ITEM ARE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 201-CLEARING AND GRUBBING.

ITEM SPECIAL-FILL AND PLUG EXISTING CONDUIT

THIS ITEM SHALL CONSIST OF THE CONSTRUCTION OF BULKHEADS IN AN EXISTING 12" DIAMETER CONDUIT AND FILLING THE AREA THUS SEALED OFF WITH ITEM 613, SAND OR OTHER MATERIAL APPROVED BY THE ENGINEER.

BULKHEADS SHALL BE LOCATED AT THE LIMITS OF THE AREA TO BE FILLED AS INDICATED ON THE PLANS. THE BULKHEADS SHALL CONSIST OF BRICK OR CONCRETE MASONRY WITH A MINIMUM THICKNESS OF 12 INCHES.

THE FILL MATERIAL SHALL BE PUMPED INTO PLACE, OR PLACED BY OTHER MEANS APPROVED BY THE ENGINEER, SO THAT, AFTER SETTLEMENT, AT LEAST 90 PERCENT OF THE CROSS- SECTIONAL AREA OF THE CONDUIT, FOR ITS ENTIRE LENGTH, SHALL BE FILLED. THE LENGTH OF FILLED AND PLUGGED CONDUIT TO BE PAID FOR SHALL BE THE ACTUAL NUMBER OF FEET (MEASURED ALONG THE CENTERLINE OF EACH CONDUIT FROM OUTER FACE TO OUTER FACE OF BULKHEADS) FILLED AND PLUGGED AS DESCRIBED ABOVE.

IN LIEU OF FILLING AND PLUGGING THE EXISTING CONDUIT, THE PIPE MAY BE CRUSHED AND BACKFILLED IN ACCORDANCE WITH THE PROVISIONS OF 203, OR IT MAY BE REMOVED. THE LENGTH, MEASURED AS PROVIDED ABOVE, SHALL BE PAID FOR AT THE CONTRACT PRICE PER FOOT FOR, ITEM SPECIAL, FILL AND PLUG EXISTING CONDUIT.

ITEM 204- EMBANKMENT, AS PER PLAN:

THE REQUIREMENTS OF ITEM 204 WILL APPLY; DEVIATIONS FROM THESE ARE AS FOLLOWS:

THE CONTRACTOR SHALL REPLACE UNSUITABLE SUBGRADE WITH NEW EMBANKMENT WITH A PLASTICITY INDEX OF 20 OR LESS. APPROXIMATE LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE ARE SHOWN AND LABELED ON THE CROSS SECTIONS AS UNSUITABLE SUBGRADE ALONG I-75 SOUTHBOUND FROM APPROXIMATELY STA. 325+00 TO STA. 351+00. THE USE OF EXISTING SHALE BEDROCK AS A REPLACEMENT MATERIAL FOR UNSUITABLE SUBGRADE IS NOT PERMITTED.

ITEM 606-ANCHOR ASSEMBLY, MGS TYPE B:

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING ANY OF THE GUARDRAIL END TERMINALS FOR TYPE MGS GUARDRAIL AS LISTED ON ROADWAY ENGINEERING'S WEB PAGE UNDER ROADSIDE SAFETY DEVICES FOR APPROVED GUARDRAIL END TREATMENTS. INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.

REFER TO THE MANUFACTURER'S INSTRUCTIONS REGARDING THE INSTALLATION OF, AND THE GRADING AROUND, THE FOUNDATION TUBES AND GROUND STRUT. THE TOP OF ANY FOUNDATION TUBE SHOULD BE LESS THAN 4 INCHES ABOVE THE GROUND. THE PLACEMENT OF THE FOUNDATION TUBES SHOULD BE AN APPROPRIATE DEPTH BELOW THE LEVEL LINE IN ORDER TO MAINTAIN THE FINISHED GUARDRAIL HEIGHT OF 31 INCHES FROM THE EDGE OF THE SHOULDER.

ON-SITE GRADING IS REQUIRED IF THE TOP OF THE FOUNDATION TUBES OR TOP OF THE GROUND STRUT DOES PROJECT MORE THAN 4 INCHES ABOVE THE GROUND LINE.

THE FACE OF THE TYPE B IMPACT HEAD SHALL BE COVERED WITH TYPE G REFLECTIVE SHEETING, PER CMS 730.19.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID FOR ITEM 606, ANCHOR ASSEMBLY, MGS TYPE B, EACH, AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT A COMPLETE AND FUNCTIONAL ANCHOR ASSEMBLY SYSTEM, INCLUDING REFLECTIVE SHEETING AND ALL RELATED HARDWARE, GRADING, EMBANKMENT AND EXCAVATION NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER.

ITEM 606- ANCHOR ASSEMBLY, MGS TYPE E:

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING ANY OF THE GUARDRAIL END TERMINALS FOR TYPE MGS GUARDRAIL AS LISTED ON ROADWAY ENGINEERING'S WEB PAGE UNDER ROADSIDE SAFETY DEVICES FOR APPROVED GUARDRAIL END TREATMENTS. INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.

THE FACE OF THE TYPE E IMPACT HEAD SHALL BE COVERED WITH A SHEET OF TYPE G REFLECTIVE SHEETING, PER CMS 730.19.

REFER TO THE MANUFACTURER'S INSTRUCTIONS REGARDING THE INSTALLATION OF, AND THE GRADING AROUND THE FOUNDATION TUBES AND GROUND STRUT. THE TOP OF ANY FOUNDATION TUBE SHOULD BE LESS THAN 4 INCHES ABOVE THE GROUND. THE PLACEMENT OF THE FOUNDATION TUBES SHOULD BE AN APPROPRIATE DEPTH BELOW THE LEVEL LINE IN ORDER TO MAINTAIN THE FINISHED GUARDRAIL HEIGHT OF 31 INCHES FROM THE EDGE OF THE SHOULDER.

ON-SITE GRADING IS REQUIRED IF THE TOP OF THE FOUNDATION TUBES OR TOP OF THE GROUND STRUT DOES PROJECT MORE THAN 4 INCHES ABOVE THE GROUND LINE.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID FOR ITEM 606, ANCHOR ASSEMBLY, MGS TYPE E, EACH, AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT A COMPLETE AND FUNCTIONAL ANCHOR ASSEMBLY SYSTEM, INCLUDING ALL RELATED TRANSITIONS, REFLECTIVE SHEETING, HARDWARE, GRADING, EMBANKMENT AND EXCAVATION NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER.

ITEM 606-IMPACT ATTENUATOR, TYPE 3 (UNIDIRECTIONAL) (DS=70 MPH, W=90 INCHES)

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING ANY OF THE TYPE 3 IMPACT ATTENUATORS AS LISTED ON THE OFFICE OF ROADWAY ENGINEERING'S WEB PAGE (REFER TO THE POSTED SHOP DRAWINGS FOR THE MOST CURRENT APPROVED PRODUCT MODELS). WHEN BI- DIRECTIONAL DESIGNS ARE SPECIFIED, THE CONTRACTOR SHALL SUPPLY APPROPRIATE TRANSITIONS. THE FACE OF THE IMPACT HEAD SHALL BE COVERED WITH TYPE G REFLECTIVE SHEETING, PER CMS 730.19.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID FOR ITEM 606, IMPACT ATTENUATOR, TYPE 3 (SPEED (IN MPH), HAZARD WIDTH (IN INCHES)), (UNIDIRECTIONAL OR BIDIRECTIONAL)), EACH, AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT A COMPLETE AND FUNCTIONAL IMPACT ATTENUATOR SYSTEM, INCLUDING ALL RELATED BACKUPS/BACKSTOPS, TRANSITIONS, HARDWARE AND GRADING, NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER. INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS, IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.

ITEM 607-FENCE MISC.: TEMPORARY CONSTRUCTION FENCE

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING TEMPORARY CONSTRUCTION FENCE ALONG THE PRINCETON CITY SCHOOL DISTRICT PROPERTY TO IMPROVE SAFETY DURING CONSTRUCTION ALONG I-75 AT LOCATIONS IN WHICH LIMITED ACCESS FENCE IS TO BE REMOVED. BEFORE ANY FENCE WORK, THE CONTRACTOR SHALL CONTACT THE SCHOOL DISTRICT FOR PERMISSION TO ACCESS THE PROPERTY AND TO MUTUALLY DETERMINE APPROPRIATE LOCATION TO CONSTRUCT TEMPORARY CONSTRUCTION FENCE ON PRIVATE PROPERTY.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AS DIRECTED BY THE ENGINEER:

ITEM 607 - FENCE MISC.: TEMPORARY CONSTRUCTION FENCE 2000 FT

ITEM 622-CONCRETE BARRIER, END SECTION, TYPE D, AS PER PLAN

IN ADDITION TO THE REQUIREMENTS OF CMS 622, THE CONCRETE BARRIER SHALL BE CONSTRUCTED AS SHOWN ON SHEET 444 OF 708. ALL LABOR, EQUIPMENT, MATERIALS, AND INCIDENTALS NECESSARY TO PERFORM THE REQUIRED WORK SHALL BE INCLUDED IN THE CONTRACT BID PRICE PER EACH FOR ITEM 622 - CONCRETE BARRIER, END SECTION, TYPE D.

ITEM 622-CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE D AS PER PLAN

IN ADDITION TO THE REQUIREMENTS OF CMS 622, THE CONCRETE BARRIER SHALL BE CONSTRUCTED AS SHOWN ON SHEET 444 OF 708. ALL LABOR, EQUIPMENT, MATERIALS, AND INCIDENTALS NECESSARY TO PERFORM THE REQUIRED WORK SHALL BE INCLUDED IN THE CONTRACT BID PRICE PER EACH FOR ITEM 622 - CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE D, AS PER PLAN.

ITEM 623-MONUMENT ASSEMBLY, ITEM 623-RIGHT OF WAY ASSEMBLY

CONSTRUCT MONUMENT ASSEMBLIES IN ACCORDANCE WITH THE DETAILS SHOWN ON THE ODOT SCD RM-1.1 AND AT THE LOCATIONS SHOWN IN THE RIGHT OF WAY PLANS ON SHEETS 692-693.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY:

ITEM 623 - MONUMENT ASSEMBLY 4 EACH
ITEM 623 - RIGHT OF WAY MONUMENT 2 EACH

ITEM SPECIAL, MISC.: BOLLARD REMOVED AND RESET

IN ADDITION TO THE REQUIREMENTS OF SCD RM-5.1, THE EXISTING BOLLARDS SHALL BE REMOVED AND RESET AT LOCATIONS SHOWN IN THE PLANS. THE BOLLARDS SHALL BE RESET INTO THE EXISTING ASPHALT CONCRETE DRIVEWAY PAVEMENT AT A DISTANCE OF 1-FOOT BEYOND THE LIMITS OF PROPOSED ASPHALT CONCRETE DRIVEWAY PAVEMENT. THE CENTER BOLLARD SHALL BE CONSTRUCTED AT CENTER OF EXISTING DRIVEWAY. THE OUTER BOLLARDS SHALL BE CONSTRUCTED AT 6-FOOT SPACING FROM CENTER BOLLARD. ALL LABOR, EQUIPMENT, MATERIALS, AND INCIDENTALS NECESSARY TO PERFORM THE REQUIRED WORK SHALL BE INCLUDED IN THE CONTRACT BID PRICE PER EACH FOR ITEM SPECIAL, MISC.: BOLLARD REMOVED AND RESET.

CALCULATED
WLC
CHECKED
JDH

GENERAL NOTES (2 OF 4)

HAM-75-14.61

PAVEMENT RESTORATION FOR PIPE INSTALLATIONS AND/OR REMOVALS:

THIS ITEM SHALL CONSIST OF RESTORATION OF ASPHALT PAVEMENT AREAS FOLLOWING INSTALLATION AND/OR REMOVAL OF PIPES OUTSIDE OF PAVEMENT LIMITS ALREADY ITEMIZED IN THE ROADWAY PLANS.

AREAS INCLUDED IN THIS ESTIMATION ARE AS FOLLOWS:

SHARON RD.: 11 SY
CHESTER RD.: 27 SY


THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY FOR USE AS DIRECTED BY THE ENGINEER:

ITEM 204-SUBGRADE COMPACTION	38 SY
ITEM 204-PROOF ROLLING	1 HR
(38 SY) X (1/3000) = 0.13 HR	
ITEM 302-ASPHALT CONCRETE BASE, PG64-22	7 CY
(38 SY) X (6") X (1/12) X (1/3) = 6.3 CY	
ITEM 304-AGGREGATE BASE	7 CY
(38 SY) X (6") X (1/12) X (1/3) = 6.3 CY	
ITEM 407-NON-TRACKING TACK COAT	5 GAL
(38 SY) X 0.055 (2) = 4.18 GAL	
*ITEM 442-ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A, (448)	2 CY
(38 SY) X (1.5") X (1/12) X (1/3) = 1.6 CY	
*ITEM 442-ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (448)	2 CY
(38 SY) X (1.75") X (1/12) X (1/3) = 1.8 CY	

* FOR AREAS WITHIN PAVEMENT PLANING & RESURFACING AREAS, ITEM 302 MAY BE INSTALLED TO EXISTING SURFACE IN PLACE OF ITEM 442 ITEMS.

THE ABOVE QUANTITIES ARE BASED ON THE PAVEMENT REPLACEMENT DETAIL BELOW AND A PAVEMENT RESTORATION WIDTH THAT INCLUDES THE TRENCH WIDTH PLUS TWO FEET ON EACH SIDE OF THE TRENCH.

PROVIDE ANY MATERIALS USED OUTSIDE THE LIMITS STATED ABOVE AT NO ADDITIONAL COST.



PAVEMENT REPLACEMENT DETAIL (NOT TO SCALE)

CONTRACTION AND/OR EXPANSION JOINTS:

ALTHOUGH SPECIFIC LOCATIONS OF CERTAIN CONTRACTION AND EXPANSION JOINTS HAVE BEEN DETAILED ON THIS PLAN, NO WAIVER OF THE SPECIFICATIONS IS INTENDED. IN ALL CASES, THE PROVISION OF EXPANSION JOINTS AT ALL MAJOR STRUCTURES INCLUDING THE MAXIMUM SPACING BETWEEN CONTRACTION JOINTS IS IN ACCORDANCE WITH STANDARD CONSTRUCTION DRAWING BP-2.2 AND THE SPECIFICATIONS.

CONTRACTION JOINTS IN CONCRETE PAVEMENT OR BASE WIDENING: WHERE NEW CONCRETE IS PLACED ADJACENT TO EXISTING CONCRETE, PROVIDE CONTRACTION JOINTS IN THE NEW CONCRETE TO FORM CONTINUOUS JOINTS WITH THOSE IN THE EXISTING CONCRETE.

THE MAXIMUM DISTANCE BETWEEN THE JOINTS IN THE NEW CONCRETE ARE IN ACCORDANCE WITH STANDARD CONSTRUCTION DRAWING BP-2.2, IF NECESSARY, ADDITIONAL JOINTS MAY BE PROVIDED IN THE NEW CONCRETE AT APPROXIMATELY EQUAL INTERVALS BETWEEN EXISTING JOINTS THAT EXCEED THE MAXIMUM SPACING.

PART-WIDTH CONSTRUCTION:

BECAUSE OF THE NECESSITY TO BUILD THIS PROJECT UNDER TRAFFIC AND TO CONSTRUCT THE FULL PAVEMENT WIDTH IN STAGES, EXERCISE CARE TO PREVENT THE CONSTRUCTION OF A BUTT JOINT IN THE BASE COURSES. LAP LONGITUDINAL JOINTS AS SHOWN ON STANDARD CONSTRUCTION DRAWING BP-3.1.

ITEM 301 - ASPHALT CONCRETE BASE, PG64-22, AS PER PLAN

THIS ITEM SHALL CONSIST OF A VARIABLE DEPTH ASPHALT CONCRETE BASE WEDGE COURSE (4" MIN) IN BETWEEN THE SALVAGED PLANED PAVEMENT SURFACE COURSE (1" MIN) AND STANDARD DEPTH INTERMEDIATE COURSE TO ACCOUNT FOR DIFFERENCES IN EXISTING/PROPOSED PAVEMENT CROSS SLOPES AND TO MEET THE PROPOSED PROFILE GRADE ELEVATIONS WITHIN THE PLANING & RESURFACING, (1" MIN, 3.25" MAX) WITH WEDGE COURSE SECTIONS BASED ON A 1-INCH MINIMUM PLANING DEPTH AS SPECIFIED IN THE PLANS. AN AVERAGE DEPTH OF 2-INCHES SHALL BE USED FOR PAVEMENT CALCULATIONS BASED ON ACTUAL CROSS SECTIONS.

ALL REQUIREMENTS OF ITEM 301 ARE APPLICABLE.

ITEM 442 - ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (447), AS PER PLAN

PLACE THE MAINLINE PAVEMENT SURFACE COURSE WITH A SINGLE COLD LONGITUDINAL JOINT LOCATED BETWEEN LANES 2 AND 3. WHERE THE NUMBER OF MAINLINE LANES EXCEEDS FOUR (4) LANES, AN ADDITIONAL COLD JOINT IS PERMITTED.

PLEASE NOTE: SHOULDERS ARE NOT MAINLINE LANES AND SHALL HAVE A HOT JOINT TO THE ADJOINING LANE PER SPECIFICATION. NO OTHER COLD JOINTS ARE PERMITTED IN THE SURFACE COURSE OF MAINLINE PAVEMENT UNLESS APPROVED BY THE ENGINEER.

ITEM 442 - ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (446), AS PER PLAN, PG64-28

THIS ITEM SHALL CONSIST OF A VARIABLE DEPTH INTERMEDIATE WEDGE COURSE (0" MIN, 4" MAX) IN BETWEEN THE SALVAGED PLANED PAVEMENT SURFACE COURSE (1" MIN) AND STANDARD DEPTH INTERMEDIATE COURSE TO ACCOUNT FOR DIFFERENCES IN EXISTING/PROFILE GRADE ELEVATIONS WITHIN THE PLANING & RESURFACING, (1" MIN, 3.25" MAX) WITH WEDGE COURSE SECTIONS BASED ON A 1-INCH MINIMUM PLANING DEPTH AS SPECIFIED IN THE PLANS. AN AVERAGE DEPTH OF 2-INCHES SHALL BE USED FOR PAVEMENT CALCULATIONS BASED ON ACTUAL CROSS SECTIONS.

ALL REQUIREMENTS OF ITEM 442 ARE APPLICABLE.

ITEM 442 - ASPHALT CONCRETE INTERMEDIATE COURSE, 19 MM, TYPE A (448), AS PER PLAN, PG64-28

THIS ITEM SHALL CONSIST OF A VARIABLE DEPTH INTERMEDIATE WEDGE COURSE (0" MIN, 4" MAX) IN BETWEEN THE SALVAGED PLANED PAVEMENT SURFACE COURSE (1" MIN) AND STANDARD DEPTH INTERMEDIATE COURSE TO ACCOUNT FOR DIFFERENCES IN EXISTING/PROFILE GRADE ELEVATIONS WITHIN THE PLANING & RESURFACING, (1" MIN, 3.25" MAX) WITH WEDGE COURSE SECTIONS BASED ON A 1-INCH MINIMUM PLANING DEPTH AS SPECIFIED IN THE PLANS. AN AVERAGE DEPTH OF 2-INCHES SHALL BE USED FOR PAVEMENT CALCULATIONS BASED ON ACTUAL CROSS SECTIONS.

ALL REQUIREMENTS OF ITEM 442 ARE APPLICABLE.

ITEM 609 - COMBINATION CURB AND GUTTER, TYPE 2, AS PER PLAN

THE REQUIREMENTS OF ITEM 609 AND STANDARD CONSTRUCTION DRAWING BP-5.1 WILL APPLY; DEVIATIONS FROM THESE ARE AS FOLLOWS:

THE GUTTER PLATE THICKNESS SHALL BE 13.25 INCHES TO MATCH PROPOSED ASPHALT BUILDUP DEPTH OF ITEM 442 AND ITEM 301 ALONG SHARON RD.

ITEM 618 - RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE) AS PER PLAN

RUMBLE STRIPS SHALL BE PLACED ALONG I-75 PER SCD BP-9.1; HOWEVER, THEY SHALL BE PLACED 5' FROM THE EDGE OF PAVEMENT FOR BOTH THE INSIDE AND OUTSIDE SHOULDERS. WHEN TRANSITIONING FROM A NORMAL SHOULDER WIDTH TO AN EXISTING SHOULDER WIDTH, THE OFFSET DISTANCE SHALL VARY FROM 5' TO THE MIDPOINT OF THE EXISTING SHOULDER WIDTH.

ITEM SPECIAL - SANITARY SEWER, MSD SANITARY SEWER PROTECTION

THE CONTRACTOR SHALL BE REQUIRED TO PROTECT ALL MSD SANITARY SEWER FACILITIES LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS. SPECIAL CARE MUST BE TAKEN TO ASSURE NO HARM TO THE MSD SEWER SYSTEM OCCURS DURING CONSTRUCTION ACTIVITIES INCLUDING EXCAVATION, DRILLING, OR EXCESSIVE WEIGHTS OVER THE SYSTEM.

IN ADDITION, THE CONTRACTOR SHALL BE REQUIRED TO VIDEO INSPECT ALL SANITARY SEWER FACILITIES BOTH PRE AND POST CONSTRUCTION. THE CONTRACTOR SHALL CONTACT WASTEWATER COLLECTION (WWC) DIVISION OF MSD (513-352-4204) AND REQUEST ADVANCE NOTIFICATION/COORDINATION OF AT LEAST 7 DAYS PRIOR TO ANY VIDEO WORK. ONE (1) COPY OF THE VIDEO INSPECTION SHALL BE PROVIDED TO THE PROJECT ENGINEER AND MSD FOR REVIEW. IF DAMAGE IS FOUND IN THE PRE-CONSTRUCTION VIDEO, THE CONTRACTOR SHALL DOCUMENT THE DAMAGE AND PROVIDE THE DOCUMENTATION TO THE PROJECT ENGINEER. IF DAMAGE IS FOUND IN THE POST-CONSTRUCTION VIDEO, THEN REPAIRS TO THE SATISFACTION OF THE DEPARTMENT AND MSD SHALL BE PERFORMED BY THE CONTRACTOR AT CONTRACTOR EXPENSE.

ALL LABOR, MATERIAL AND INCIDENTALS FOR THE ABOVE WORK SHALL BE PAID FOR BY LUMP SUM, ITEM SPECIAL - SANITARY SEWER, MSD SANITARY SEWER PROTECTION.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY:

ITEM SPECIAL-SANITARY SEWER, LS
MSD SANITARY SEWER PROTECTION

WATERWAY PERMITS:

ALL NECESSARY 404/401 WATERWAY PERMITS WILL BE ACQUIRED PRIOR TO ANY CONSTRUCTION ACTIVITY. PER THE NOVEMBER 9, 2007 COMMENTS RECEIVED FROM ODNR, NO IN-STREAM WORK WILL OCCUR BETWEEN APRIL 15 AND JUNE 30.

ENDANGERED BAT HABITAT REMOVAL:

THIS PROJECT IS LOCATED WITHIN THE KNOWN HABITAT RANGES OF THE FEDERALLY LISTED AND PROTECTED INDIANA BAT AND NORTHERN LONG-EARED BAT. NO TREES SHALL BE REMOVED UNDER THIS PROJECT FROM APRIL 1 THROUGH SEPTEMBER 30. ALL NECESSARY TREE REMOVAL SHALL OCCUR FROM OCTOBER 1 THROUGH MARCH 31. THIS REQUIREMENT IS NECESSARY TO AVOID AND MINIMIZE IMPACTS TO THESE SPECIES AS REQUIRED BY THE ENDANGERED SPECIES ACT.

WETLANDS

WETLANDS AVOIDANCE - UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR IMPACT THE WETLANDS (WETLANDS ID A AND B) INDICATED ON THE SCHEMATIC PLAN. NO EXCAVATION, GRADING OR FILLING OPERATIONS SHALL BE PERFORMED IN THESE WETLANDS. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR STORE CONSTRUCTION EQUIPMENT AND/OR MATERIALS IN THESE WETLANDS. TEMPORARY CONSTRUCTION FENCE AND FILTER FABRIC FENCE SHALL BE INSTALLED BY THE CONTRACTOR TO PROTECT THE BOUNDARY OF THESE WETLAND PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITIES WITHIN THESE LIMITS AND ADJACENT AREA AND MAINTAINED BY THE CONTRACTOR THROUGHOUT PROJECT CONSTRUCTION. BEST MANAGEMENT PRACTICES AND PRACTICES FOR SOIL EROSION CONTROL SHALL BE FULLY COMPLIED WITH, AS WELL AS, ALL OF THE REGULATIONS AND CONDITIONS ASSOCIATED WITH THE REQUIRED SWPPP AND NPDES PERMIT.

J:\pre-int\06-106-386_HAM-75_HAM\00000\roadway\sheets\00000GN004.dgn 2021-01-09 3:19:26 PM william.croxtson' ODOTcadd_PDF.pltcfgr ODOTV81_Pen.tbl IBI Group

CALCULATED
WLC
CHECKED
JDH

GENERAL NOTES (4 OF 4)

HAM-75-14.61

j:\pre-int\06-386_HAM-75_HAM\00000\mot\sheets\00000m001.dgn 2021-01-06 12:04:53 PM brian.sezoiol" ODOTV8i_PDF_Half.pltctfg ODOTV8i_Pen.tbl IBI Group

ITEM 614 - MAINTAINING TRAFFIC

IR-75 AND RAMPS
 MAINTAIN THE SAME NUMBER OF LANES AS CURRENTLY EXISTS IN EACH DIRECTION AND RAMPS AT ALL TIMES, EXCEPT IN ACCORDANCE WITH THE UNAUTHORIZED LANE USE TABLE (SEE SHEET 34), BY USE OF THE EXISTING PAVEMENT, COMPLETED PAVEMENT, ITEM 615 PAVEMENT FOR MAINTAINING TRAFFIC AND ITEM 615 ROADS FOR MAINTAINING TRAFFIC.

SHARON RD
 A MINIMUM OF 2 LANES OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES BY UTILIZING A COMBINATION OF EXISTING PAVEMENT, THE COMPLETED PAVEMENT, ITEM 615 PAVEMENT FOR MAINTAINING TRAFFIC, ITEM 615 ROADS FOR MAINTAINING TRAFFIC, AND TEMPORARY SURFACES USING ITEMS 410, AND 614.

CHESTER RD
 A MINIMUM OF 1 LANES OF TRAFFIC IN EACH DIRECTION SHALL BE MAINTAINED AT ALL TIMES, EXCEPT FOR A PERIOD WHEN TRAFFIC MAY BE MAINTAINED USING A FLAGGER OPERATION AS DETAILED IN SCD MT-97.10.

NO WORK SHALL BE PERFORMED ON I-75 AND A MINIMUM OF THREE LANES OF TRAFFIC IN EACH DIRECTION ON I-75 SHALL BE OPEN TO TRAFFIC ALONG WITH NO WORK ON THE RAMPS, SHARON ROAD, AND CHESTER ROAD DURING THE FOLLOWING DESIGNATED HOLIDAYS OR EVENTS:

CHRISTMAS	FOURTH OF JULY
NEW YEARS	LABOR DAY
MEMORIAL DAY	THANKSGIVING
EASTER	

THE PERIOD OF TIME THAT THE LANES ARE TO BE OPEN DEPENDS ON THE DAY OF THE WEEK ON WHICH THE HOLIDAY OR EVENT FALLS. THE FOLLOWING SCHEDULE SHALL BE USED TO DETERMINE THIS PERIOD:

DAY OF HOLIDAY OR EVENT	TIME ALL LANES MUST BE OPEN TO TRAFFIC
SUNDAY	6:00 AM FRIDAY THROUGH 9:00 PM MONDAY
MONDAY	6:00 AM FRIDAY THROUGH 9:00 PM TUESDAY
TUESDAY	6:00 AM MONDAY THROUGH 9:00 PM WEDNESDAY
WEDNESDAY	6:00 AM TUESDAY THROUGH 9:00 PM THURSDAY
THURSDAY	6:00 AM WEDNESDAY THROUGH 9:00 PM FRIDAY (THANKSGIVING ONLY)
FRIDAY	6:00 AM WEDNESDAY THROUGH 9:00 PM MONDAY
SATURDAY	6:00 AM THURSDAY THROUGH 9:00 PM MONDAY

SHOULD THE CONTRACTOR FAIL TO MEET ANY OF THESE REQUIREMENTS, THE CONTRACTOR SHALL BE ASSESSED A DISINCENTIVE IN THE AMOUNT SHOWN IN THE UNAUTHORIZED LANE USE TABLE ON SHEET 34 WHEN THE ABOVE DESCRIBED LANE CLOSURE RESTRICTIONS ARE VIOLATED.

LENGTH AND DURATION OF LANE CLOSURES AND RESTRICTIONS SHALL BE AT THE APPROVAL OF THE ENGINEER. IT IS THE INTENT TO MINIMIZE THE IMPACT TO THE TRAVELING PUBLIC. LANE CLOSURES OR RESTRICTIONS OVER SEGMENTS OF THE PROJECT IN WHICH NO WORK IS ANTICIPATED WITHIN A REASONABLE TIME FRAME, AS DETERMINED BY THE ENGINEER, SHALL NOT BE PERMITTED. THE LEVEL OF UTILIZATION OF MAINTENANCE OF TRAFFIC DEVICES SHALL BE COMMENSURATE WITH THE WORK IN PROGRESS.

NOTICE OF CLOSURE SIGNS (W20-H13) SHALL BE ERECTED BY THE CONTRACTOR PRIOR TO THE SCHEDULED ROAD OR RAMP CLOSURE IN ACCORDANCE WITH THE NOTICE OF CLOSURE TIME TABLE BELOW. AT THE APPROVAL OF THE ENGINEER, PORTABLE CHANGEABLE MESSAGE SIGNS MAY BE USED IN LIEU OF THE STANDARD FLATSHEET SIGN FOR CLOSURE DURATIONS OF LESS THAN 1 WEEK.

THE SIGNS SHALL BE ERECTED ON THE RIGHT-HAND SIDE OF THE ROAD/RAMP FACING TRAFFIC. THEY SHALL BE PLACED SO AS NOT TO INTERFERE WITH THE VISIBILITY OF ANY OTHER TRAFFIC CONTROL SIGNS. ON ROADWAYS, THEY SHOULD BE ERECTED AT OR NEAR THE POINT OF CLOSURE. THE SIGNS MAY BE ERECTED ANYWHERE ON RAMPS AS LONG AS THEY ARE VISIBLE TO THE MOTORISTS USING THE RAMP. ON ENTRANCE RAMPS, THE SIGN SHALL BE ERECTED WELL IN ADVANCE OF THE MERGE AREA TO AVOID DISTRACTING MOTORISTS.

NOTICE OF CLOSURE SIGN TIME TABLE

ITEM	DURATION OF CLOSURE	SIGN DISPLAYED TO PUBLIC
RAMP & ROAD CLOSURES	>= 2 WEEKS	14 CALENDAR DAYS PRIOR TO CLOSURE
	> 12 HOURS & < 2 WEEKS	7 CALENDAR DAYS PRIOR TO CLOSURE
	< 12 HOURS	2 BUSINESS DAYS PRIOR TO CLOSURE

THE SIGN SHALL DISPLAY THE DATE OF THE CLOSURE IN MMM-DD FORMAT AND THE NUMBER OF DAYS OF THE CLOSURE. THE LAST LINE OF THE W20-H13 SIGN LISTS A PHONE NUMBER WHICH A MOTORIST MAY CALL FOR ADDITIONAL INFORMATION. THIS IS TO BE A SPECIFIC OFFICE WITHIN THE DISTRICT RATHER THAN THE GENERAL SWITCHBOARD NUMBER.

THE CONTRACTOR SHALL PROVIDE, ERECT AND MAINTAIN STANDARD 48 X 30 INCH ROAD CLOSED SIGNS, SIGN SUPPORTS, BARRICADES AND LIGHTS, AS DETAILED IN SCD MT-101.60 AT THE FOLLOWING LOCATIONS DURING PERIODS IN WHICH THE AFFECTED ROADS ARE CLOSED TO TRAFFIC.

SHARON ROAD AT CURB RETURN TO I-75 SB EXIT RAMP
 SHARON ROAD AT CURB RETURN TO I-75 SB ENTRANCE RAMP
 SHARON ROAD AT CURB RETURN TO I-75 NB EXIT RAMP
 SHARON ROAD AT CURB RETURN TO I-75 SB ENTRANCE RAMP
 CHESTER ROAD STA. 95+00 AND STA. 96+50

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY FOR USE AS DETERMINED BY THE ENGINEER FOR THE MAINTENANCE OF TRAFFIC.

ITEM 410, TRAFFIC COMPACTED SURFACE, TYPE A OR B	100 CU YD
ITEM 614, ASPHALT CONCRETE FOR MAINTAINING TRAFFIC	100 CU YD
ITEM 616, WATER	50 M GAL

ALL WORK AND TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH CMS 614 AND OTHER APPLICABLE PORTIONS OF THE SPECIFICATIONS, AS WELL AS THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC, UNLESS SEPARATELY ITEMIZED IN THE PLAN.

TRENCH FOR WIDENING

TRENCH EXCAVATION FOR BASE WIDENING SHALL BE ONLY ON ONE SIDE OF THE PAVEMENT AT A TIME. THE OPEN TRENCH SHALL BE ADEQUATELY MAINTAINED AND PROTECTED WITH DRUMS OR BARRICADES AT ALL TIMES. PLACEMENT OF PROPOSED SUBBASE AND BASE MATERIAL SHALL FOLLOW AS CLOSELY AS POSSIBLE BEHIND EXCAVATION OPERATIONS. THE LENGTH OF WIDENING TRENCH WHICH IS OPEN AT ANY ONE TIME SHALL BE HELD TO A MINIMUM AND SHALL AT ALL TIMES BE SUBJECT TO APPROVAL OF THE ENGINEER.

OVERNIGHT TRENCH CLOSING

THE BASE WIDENING SHALL BE COMPLETED TO A DEPTH OF NO MORE THAN 5 INCHES BELOW THE EXISTING PAVEMENT BY THE END OF EACH WORK DAY. NO TRENCH SHALL BE LEFT OPEN OVERNIGHT EXCEPT FOR A SHORT LENGTH (25 FEET OR LESS) OF A WORK SECTION AT THE END OF THE TRENCH. IN CASE WORK MUST BE SUSPENDED BECAUSE OF INCLEMENT WEATHER OR OTHER REASONS, THE TRENCH FOR THE UN-COMPLETED BASE WIDENING SHALL BE BACKFILLED AT THE DIRECTION OF THE ENGINEER.

DRUM REQUIREMENTS

IN ADDITION TO THE REQUIREMENTS OF THE PLANS, SPECIFICATION AND PROPOSAL, DRUMS FURNISHED BY THE CONTRACTOR SHALL BE NEW AND UNUSED AT THE TIME OF ARRIVAL ON THE PROJECT. ANY DRUMS BROUGHT ON THE PROJECT, WHICH HAVE PREVIOUSLY BEEN USED ELSEWHERE, SHALL NOT BE ACCEPTED.

PAYMENT FOR DRUMS SHALL BE INCLUDED IN THE LUMP SUM PRICE BID FOR MAINTAINING TRAFFIC UNLESS SEPARATELY ITEMIZED.

DUST CONTROL

THE CONTRACTOR SHALL FURNISH AND APPLY WATER FOR DUST CONTROL AS DIRECTED BY THE ENGINEER. THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN INCLUDED FOR DUST CONTROL PURPOSES:

ITEM 616, WATER	2,500 M GAL
-----------------	-------------

ITEM 614 - REPLACEMENT DRUM

DRUMS FURNISHED BY THE CONTRACTOR IN ACCORDANCE WITH THE REQUIREMENTS OF THE PLANS, SPECIFICATIONS AND PROPOSAL WHICH BECOME DAMAGED BY TRAFFIC FOR REASONS BEYOND THE CONTROL OF THE CONTRACTOR SHALL BE REPLACED IN KIND WHEN ORDERED BY THE ENGINEER. REPLACEMENT DRUMS SHALL BE NEW.

PAYMENT FOR THE NEW DRUMS SHALL BE MADE AT THE CONTRACT PRICE PER EACH FOR ITEM 614, REPLACEMENT DRUM, AND SHALL INCLUDE THE COST OF REMOVING AND DISPOSING OF THE DAMAGED DRUM, AND PROVIDING AND MAINTAINING THE REPLACEMENT DRUM IN ACCORDANCE WITH THE CONTRACT REQUIREMENTS FOR THE ORIGINAL DRUM.

AN ESTIMATED QUANTITY OF 100 EACH HAS BEEN PROVIDED IN THE GENERAL SUMMARY.

EARTHWORK FOR MAINTAINING TRAFFIC

THE FOLLOWING QUANTITIES HAVE BEEN INCLUDED IN THE PLAN FOR INFORMATION ONLY:

EXCAVATION FOR MAINTAINING TRAFFIC	5,000 CU YD
EMBANKMENT FOR MAINTAINING TRAFFIC	5,000 CU YD

WHEN UNDERCUTS ARE NECESSARY FOR MAINLINE PAVEMENT OR EMBANKMENT CONSTRUCTION, EVALUATE THE NEED FOR TEMPORARY ROAD UNDERCUTS IF WITHIN A CLOSE PROXIMITY TO THE MAINLINE UNDERCUTS.

PAYMENT FOR ALL LABOR, EQUIPMENT AND MATERIALS SHALL BE INCLUDED IN THE LUMP SUM CONTRACT PRICE FOR ITEM 614, MAINTAINING TRAFFIC.

ITEM 614 - REPLACEMENT SIGN

FLATSHEET SIGNS FURNISHED BY THE CONTRACTOR IN ACCORDANCE WITH THE REQUIREMENTS OF THE PLANS, SPECIFICATIONS AND PROPOSAL WHICH BECOME DAMAGED BY TRAFFIC FOR REASONS BEYOND THE CONTROL OF THE CONTRACTOR SHALL BE REPLACED IN KIND WHEN ORDERED BY THE ENGINEER. REPLACEMENT SIGNS SHALL BE NEW. OTHER MATERIALS MAY BE IN USED, BUT GOOD CONDITION SUBJECT TO APPROVAL BY THE ENGINEER.

PAYMENT FOR THE NEW SIGNS SHALL BE MADE AT THE CONTRACT PRICE PER EACH FOR ITEM 614, REPLACEMENT SIGN, AND SHALL INCLUDE THE COST OF REMOVING AND DISPOSING OF DAMAGED SIGNS, HARDWARE AND SUPPORTS, AND PROVIDING THE NECESSARY REPLACEMENT HARDWARE, SUPPORTS, ETC.

AN ESTIMATED QUANTITY OF 20 EACH HAS BEEN PROVIDED IN THE GENERAL SUMMARY.

ITEM 618 - RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE), AS PER PLAN

THE CONTRACTOR SHALL MILL 2" DEEP BY 4' WIDE OF THE EXISTING ASPHALT SHOULDER IN ORDER TO ELIMINATE THE EXISTING EDGE LINE AND RUMBLE STRIPS ALONG I-75 IN THE AREA WHERE TRAFFIC IS SHIFTED. NEXT THE CONTRACTOR SHALL PLACE ITEM 407, TACK COAT, APPLIED AT 0.1 GAL/SY, AND 2" OF ITEM 448 ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-28. ALL COST ASSOCIATED WITH THIS WORK SHALL BE INCLUDED IN THE UNIT PRICE BID PER MILE OF ITEM 618, RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE), AS PER PLAN.

AN ESTIMATED QUANTITY OF 2.65 MILE HAS BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM 615 - PAVEMENT FOR MAINTAINING TRAFFIC, CLASS A, AS PER PLAN:

THE TEMPORARY PAVEMENT BUILD-UP SHALL BE CONSTRUCTED AS SPECIFIED PER CMS 615 FOR CLASS A FLEXIBLE PAVEMENT WITH THE EXCEPTION THAT A SINGLE LAYER OF 2" OF ITEM 448, TYPE 2, PG64-22 PLACED ABOVE 8" ITEM 302 AND 6" ITEM 304.

CALCULATED
 STC
 CHECKED
 JDH

MAINTENANCE OF TRAFFIC GENERAL NOTES

HAM-75-14.61

ITEM 614 - PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN

THE CONTRACTOR SHALL FURNISH, INSTALL, MAINTAIN AND REMOVE, WHEN NO LONGER NEEDED, A CHANGEABLE MESSAGE SIGN. THE SIGN SHALL BE OF A TYPE SHOWN ON A LIST OF APPROVED PCMS UNITS AVAILABLE ON THE (OFFICE OF MATERIALS MANAGEMENT WEB PAGE). THE LIST CONTAINS CLASS A AND B UNITS WITH MINIMUM LEGIBILITY DISTANCES OF 650 FEET AND 475 FEET, RESPECTIVELY.

EACH SIGN SHALL BE TRAILER-MOUNTED AND EQUIPPED WITH A FUNCTIONAL DIMMING MECHANISM, TO DIM THE SIGN DURING DARKNESS, AND A TAMPER AND VANDAL PROOF ENCLOSURE. EACH SIGN SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE ON-SITE PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT. THE SIGN SHALL ALSO BE CAPABLE OF BEING POWERED BY AN ELECTRICAL SERVICE DROP FROM A LOCAL UTILITY COMPANY. THE PCMS SHALL BE DELINEATED IN ACCORDANCE WITH C&MS 614.03.

THE PROBABLE PCMS LOCATIONS AND WORK LIMITS FOR THOSE LOCATIONS ARE SHOWN ON SHEET(S) OF THE PLAN. PLACEMENT, OPERATION, MAINTENANCE AND ALL ACTIVATION OF THE SIGNS BY THE CONTRACTOR SHALL BE AS DIRECTED BY THE ENGINEER. THE PCMS SHALL BE LOCATED IN A HIGHLY VISIBLE POSITION YET PROTECTED FROM TRAFFIC. THE CONTRACTOR SHALL, AT THE DIRECTION OF THE ENGINEER, RELOCATE THE PCMS TO IMPROVE VISIBILITY OR ACCOMMODATE CHANGED CONDITIONS. WHEN NOT IN USE, THE PCMS SHALL BE TURNED OFF. ADDITIONALLY, WHEN NOT IN USE FOR EXTENDED PERIODS OF TIME, THE PCMS SHALL BE TURNED AWAY FROM ALL TRAFFIC.

THE PROBABLE PCMS LOCATIONS AND WORK LIMITS ARE LISTED BELOW:

- NORTHBOUND - I-75 1000 FT ADVANCE OF NORTHBOUND OFF RAMP TO RONALD REAGAN HIGHWAY.
- SOUTHBOUND - 1000 FT IN ADVANCE OF I-275 SOUTHBOUND OF RAMP
- DMS LOCATION - I-75 300 FT IN ADVANCE OF SHARON RD OVERPASS.

TWO 'CLASS A' PCMS AT THE SHARON ROAD OVERPASS SHALL HAVE THE ABILITY FOR THE ODOT TRAFFIC MANAGEMENT CENTER (TMC) TO ACCESS REMOTELY AND UPDATE THE MESSAGE WHILE THE EXISTING DMS IS REMOVED AND REPLACED. THESE PCMS SHALL BE SETUP AND OPERATIONAL THRU THE TMC IN PRE-PHASE 1 AS SHOWN ON SHEET 32 PRIOR TO DEACTIVATION AND REMOVAL OF THE EXISTING DMS. THE PCMS WILL BE ACTIVE UNTIL THE PROPOSED DMS IS INSTALLED AND OPERATIONAL, HOWEVER, THE USE OF THESE PCMS SHALL NOT EXCEED 6 MONTHS.

IF THE CONTRACTOR DEACTIVATES THE EXISTING DMS PRIOR TO BOTH PCMS BEING OPERATIONAL, THEN A DISINCENTIVE OF \$500 PER DAY PER PCMS SIGN SHALL BE APPLIED UNTIL BOTH SIGNS ARE OPERATIONAL. IN ADDITION, THIS DISINCENTIVE PER SIGN SHALL ALSO APPLY FOR EACH DAY THAT THE PCMS ARE IN USE PAST 6 MONTHS.

THE ENGINEER SHALL BE PROVIDED ACCESS TO EACH SIGN UNIT AND SHALL BE PROVIDED WITH APPROPRIATE TRAINING AND OPERATION INSTRUCTIONS TO ENABLE ODOT PERSONNEL TO OPERATE AND TROUBLESHOOT THE UNIT, AND TO REVISE SIGN MESSAGES, IF NECESSARY.

THE CONTRACTOR SHALL IMPLEMENT A SYSTEM WHEREBY CHANGEABLE MESSAGES WILL BE IMPLEMENTED WITHIN 4 HOURS FOLLOWING TELEPHONE NOTIFICATION FROM THE PROJECT ENGINEER TO A DESIGNATED PHONE.

ALL MESSAGES TO BE DISPLAYED ON THE SIGN WILL BE PROVIDED BY THE ENGINEER. A LIST OF ALL REQUIRED PRE-PROGRAMMED MESSAGES WILL BE GIVEN TO THE CONTRACTOR AT THE PROJECT PRECONSTRUCTION CONFERENCE. THE SIGN SHALL HAVE THE CAPABILITY TO STORE UP TO 99 MESSAGES. MESSAGE MEMORY OR PRE-PROGRAMMED DISPLAYS

SHALL NOT BE LOST AS A RESULT OF POWER FAILURES TO THE ON-BOARD COMPUTER. THE SIGN LEGEND SHALL BE CAPABLE OF BEING CHANGED IN THE FIELD. THREE-LINE PRESENTATION FORMATS WITH UP TO SIX MESSAGE PHASES SHALL BE SUPPORTED. PCMS FORMAT SHALL PERMIT THE COMPLETE MESSAGE FOR EACH PHASE TO BE READ AT LEAST TWICE. THE PCMS SHALL CONTAIN AN ACCURATE CLOCK AND PROGRAMMING LOGIC WHICH WILL ALLOW THE SIGN TO BE ACTIVATED, DEACTIVATED OR MESSAGES CHANGED AUTOMATICALLY AT DIFFERENT TIMES OF THE DAY FOR DIFFERENT DAYS OF THE WEEK.

THE PCMS SHALL CONTAIN A CELLULAR TELEPHONE DATA LINK WHICH WILL (IN ACTIVE CELLULAR PHONE AREAS) ALLOW REMOTE SIGN ACTIVATION, MESSAGE CHANGES, MESSAGE ADDITIONS AND REVISIONS TO TIME OF DAY PROGRAMS. THE SYSTEM SHALL ALSO PERMIT VERIFICATION OF CURRENT AND PROGRAMMED MESSAGES. ONE REMOTE DATA INPUT DEVICE (LAPTOP COMPUTER PLUS MODEM OR EQUIVALENT) SHALL BE FURNISHED FOR USE BY THE DISTRICT TRAFFIC ENGINEER, OR EQUIVALENT, AND SHALL BE INSURED AGAINST THEFT.

THE PCMS UNIT SHALL BE MAINTAINED IN GOOD WORKING ORDER BY THE CONTRACTOR IN ACCORDANCE WITH THE PROVISIONS OF C&MS 614.07. THE CONTRACTOR SHALL, PRIOR TO ACTIVATING THE UNIT, MAKE ARRANGEMENTS, WITH AN AUTHORIZED SERVICE AGENT FOR THE PCMS, TO ASSURE PROMPT SERVICE IN THE EVENT OF FAILURE. ANY FAILURE SHALL NOT RESULT IN THE SIGN BEING OUT OF SERVICE FOR MORE THAN 12 HOURS, INCLUDING WEEKENDS. FAILURE TO COMPLY MAY RESULT IN AN ORDER TO STOP WORK AND OPEN ALL TRAFFIC LANES AND/OR IN THE DEPARTMENT TAKING APPROPRIATE ACTION TO SAFELY CONTROL TRAFFIC. THE ENTIRE COST TO CONTROL TRAFFIC, ACCRUED BY THE DEPARTMENT DUE TO THE CONTRACTOR'S NONCOMPLIANCE, WILL BE DEDUCTED FROM MONEYS DUE, OR TO BECOME DUE THE CONTRACTOR ON HIS CONTRACT.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR 24-HOUR-PER-DAY OPERATION AND MAINTENANCE OF THESE SIGNS ON THE PROJECT FOR THE DURATION OF THE PHASES WHEN THE PLAN REQUIRES THEIR USE.

PAYMENT FOR THE ABOVE DESCRIBED ITEM SHALL BE AT THE CONTRACT UNIT PRICE. PAYMENT SHALL INCLUDE ALL LABOR, MATERIALS, EQUIPMENT, FUELS, LUBRICATING OILS, SOFTWARE, HARDWARE AND INCIDENTALS TO PERFORM THE ABOVE DESCRIBED WORK.

ITEM 614, PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN 54 SIGN MONTH

SHORT DURATION CLOSING OF THE HIGHWAY

THE FOLLOWING NOTES SHALL APPLY TO ALL WORK ON I-75.

1. FIVE CALENDAR DAYS PRIOR TO IMPLEMENTING THE SHORT DURATION CLOSING OF THE HIGHWAY THE CONTRACTOR SHALL PLACE A PORTABLE CHANGEABLE MESSAGE SIGN AT THE STRUCTURE IN THE DIRECTION THE ROAD IS TO BE CLOSED WITH THE MESSAGE:

I-75 12M
CLOSES TO
DATE 4AM

2. CLOSURES WILL ONLY BE PERMITTED FOR REMOVAL AND ERECTION OF THE STRUCTURAL BEAMS AND SIGN TRUSSES, TO PROTECT TRAFFIC DURING DEMOLITION OPERATIONS AS CALLED FOR IN C&MS 501.05, FOR OVERHEAD UTILITY WIRE CROSSING, AND FOR TRAFFIC SWITCHES. CLOSURES WILL BE PERMITTED DURING THE HOURS SPECIFIED IN THE PERMITTED LANE CLOSURE AND UNAUTHORIZED LANE USE TABLE, ON SHEET 34. THE MAXIMUM DURATION OF THE CLOSURE SHALL NOT EXCEED 15 MINUTES SUBJECT TO A DISINCENTIVE IN THE AMOUNT SPECIFIED IN THE PERMITTED LANE CLOSURE AND UNAUTHORIZED LANE USE TABLE, ON SHEET 34. UNLESS OTHERWISE DIRECTED BY THE ENGINEER, ONLY ONE (1) BEAM SHALL BE REMOVED OR SET PER CLOSING. TRAFFIC SHALL BE COMPLETELY CLEARED BEFORE THE NEXT CLOSING.

3. THE CONTRACTOR SHALL IMPLEMENT THE TRAFFIC CONTROL CONTAINED IN STANDARD CONSTRUCTION DRAWING MT-99.60. IN THE EVENT THE CLOSURE OCCURS IN CLOSE PROXIMITY TO SYSTEM-SYSTEM INTERCHANGE, TRAFFIC CONTROL SHALL EXTEND ONTO ANY ENTERING DIVIDED HIGHWAY ACCORDING TO THE LIMITS PROVIDED IN MT-99.60.

4. THE CONTRACTOR SHALL FURNISH AND INSTALL TWO (2) WATCH FOR STOPPED TRAFFIC SIGNS (W3-H7-48) 1500 FEET UPSTREAM FROM THE ANTICIPATED BACKUP ON I-75. THE CONTRACTOR SHALL INSTALL ADDITIONAL WATCH FOR STOPPED TRAFFIC SIGNS EVERY 2000 FEET UPSTREAM FROM THE WATCH FOR STOPPED TRAFFIC SIGNS ON I-75 IF TRAFFIC BACKUPS REACH THE FIRST SET OF SIGNS. THE NEED FOR THESE SIGNS SHALL BE CONSTANTLY MONITORED BY THE CONTRACTOR. ALL WATCH FOR STOPPED TRAFFIC AND PREPARE TO STOP SIGNS SHALL BE EQUIPPED WITH TYPE B WARNING LIGHTS.

6. IN THE EVENT OF AN INCLEMENT WEATHER FORECAST (RAIN OR SNOW FORECAST AT 50% OR GREATER THE DAY THE EVENT WILL OCCUR IS DEFINED AS AN INCLEMENT FORECAST) THE CLOSURE SHALL NOT TAKE PLACE. THE CONTRACTOR WILL MAKE THE DETERMINATION BASED UPON THE WEATHER FORECAST PREDICTED BY THE NATIONAL WEATHER SERVICE.

SPECIAL - WORK ZONE GUARDRAIL

THIS WORK AND MATERIALS SHALL COMPLY WITH ITEM 606 FOR PERMANENT GUARDRAIL, EXCEPT THAT USED TYPE 5 RAILS AND POSTS MAY BE USED IF IN GOOD CONDITION AND APPROVED BY THE ENGINEER. FOR EXISTING GUARDRAIL RUNS WHICH REQUIRE AN EXTENSION, THE EXISTING END TERMINAL ASSEMBLY SHALL BE REMOVED AND RESET TO THE NEW LOCATION, AS SHOWN ON THE PLANS. NEW RUNS, FOR BRIDGE PARAPET PROTECTION, SHALL HAVE THE APPROPRIATE BRIDGE TERMINAL ASSEMBLIES INSTALLED. UPON COMPLETION OF THE PHASE WHICH REQUIRES THE TEMPORARY GUARDRAIL, ALL WORK ZONE GUARDRAIL SHALL BE REMOVED AND THE POST HOLES BACKFILLED (UNLESS PERMANENT GRADING TO BE PERFORMED LATER WOULD REPAIR THE HOLES), ALL TERMINAL ASSEMBLIES REMOVED, AND END TERMINAL ASSEMBLIES RESET TO THEIR ORIGINAL LOCATIONS.

ALL COSTS RESULTING FROM THE ABOVE REQUIREMENTS SHALL BE CONSIDERED TO BE INCLUDED IN THE LUMP SUM PRICE BID FOR ITEM 614, MAINTAINING TRAFFIC.

ITEM 614 - WORK ZONE IMPACT ATTENUATOR FOR 24" WIDE HAZARDS (UNIDIRECTIONAL OR BIDIRECTIONAL)

THIS ITEM SHALL CONSIST OF FURNISHING AND INSTALLING A NON-GATING IMPACT ATTENUATOR. FURNISH AN IMPACT ATTENUATOR FROM THE OFFICE OF ROADWAY ENGINEERING APPROVED LIST FOR WORK ZONE IMPACT ATTENUATORS. THE APPROVED LIST IS AVAILABLE AT THE "ROADWAY STANDARDS: PROPRIETARY ROADSIDE SAFETY DEVICES" WEB PAGE ON THE OFFICE OF ROADWAY ENGINEERING WEBSITE.

INSTALLATION SHALL BE AT THE LOCATIONS SPECIFIED IN THE PLANS IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.

THE CONTRACTOR SHALL REPAIR OR REPLACE A DAMAGED UNIT WITHIN 24 HOURS OF A DAMAGING IMPACT.

WHEN BIDIRECTIONAL DESIGNS ARE SPECIFIED, THE CONTRACTOR SHALL SUPPLY APPROPRIATE TRANSITIONS.

WHEN GATING IMPACT ATTENUATORS ARE DESIRED, THE CONTRACTOR SHALL SUBMIT DOCUMENTATION TO THE ENGINEER FOR ACCEPTANCE.

THE COST FOR THE ADDITIONAL BARRIER REQUIRED FOR A GATING IMPACT ATTENUATOR SHALL BE INCLUDED IN THE COST OF THE GATING IMPACT ATTENUATOR.

PAYMENT FOR THE ABOVE WORK SHALL BE MADE AT THE UNIT PRICE BID AND SHALL INCLUDE ALL LABOR, TOOLS, EQUIPMENT AND MATERIALS NECESSARY TO CONSTRUCT AND MAINTAIN A COMPLETE AND FUNCTIONAL IMPACT ATTENUATOR SYSTEM, INCLUDING ALL RELATED BACKUPS, TRANSITIONS, LEVELING PADS, HARDWARE AND GRADING, NOT SEPARATELY SPECIFIED, AS REQUIRED BY THE MANUFACTURER.

ITEM 614 - MAINTAINING TRAFFIC, MISC.: MAINTENANCE OF MAJOR GUIDE SIGNS

THE CONTRACTOR SHALL MAINTAIN THE SAME NUMBER OF GUIDE SIGNS AS CURRENTLY EXIST FOR EACH FREEWAY EXIT/ENTRANCE WHICH IS TO REMAIN OPEN DURING EACH PHASE OF CONSTRUCTION IN ORDER TO ALLOW MOTORIST TO FIND THEIR DESTINATIONS SAFELY. ERECTION/DISMANTLING OF THE OVERHEAD SIGN SUPPORTS WHICH WILL BE AFFECTED BY THE PROPOSED CONSTRUCTION SHALL BE COMPLETED PRIOR TO THAT PHASE OF CONSTRUCTION. NO MORE THAN ONE SIGN FOR ANY EXIT OR ENTRANCE RAMP MAY BE REMOVED AT ANY TIME. IN INSTANCES WHERE THE COPY ON THE REPLACEMENT SIGN IS SUBSTANTIALLY DIFFERENT FROM THE COPY ON THE EXISTING SIGNS FOR A PARTICULAR EXIT OR ENTRANCE RAMP, ALL OF THE SIGNS IN THE SEQUENCE FOR THAT RAMP SHALL BE CHANGED WITHIN ONE CALENDAR DAY. IN SOME CASES IT SHALL BE NECESSARY TO SUPPLY AND INSTALL TEMPORARY SUPPORTS. THE CONTRACTOR SHALL BE RESPONSIBLE TO DESIGN, INSTALL, PROVIDE POSITIVE PROTECTION, AND REMOVE THE TEMPORARY SUPPORTS AS NEEDED IN ACCORDANCE WITH MT-105.10.

PAYMENT FOR ALL THE MATERIALS, INSTALLATION AND WORK DESCRIBED ABOVE SHALL BE INCLUDED IN THE UNIT PRICE PER EACH FOR ITEM 614, MAINTAINING TRAFFIC, MISC.; MAINTENANCE OF MAJOR GUIDE SIGNS.

\\10.120.112.5\ibishare\pre-int\06\06-386_HAM-75\HAM-00000\mot\sheets\00000mn002.dgn_Sheet_2021-01-25 11:58:54 AM william.croxton

CALCULATED
STC
CHECKED
JDH

MAINTENANCE OF TRAFFIC GENERAL NOTES

HAM-75-14.61

j:\pre-int\06-386_HAM-75\HAM\00000\mot\sheets\00000mm008.dgn 2021-01-19 4:28:45 PM brian.sedziol" ODOTV81_PDF_Half.pltcfq ODOTV81_Pen.tbi IBI Group

MAINTENANCE OF TRAFFIC SEQUENCE

A MINIMUM OF THREE LANES OF TRAFFIC SHALL BE MAINTAINED AT ALL TIMES ON I-75 BOTH NORTHBOUND AND SOUTHBOUND. ALL LANES WILL BE 11' TYPICAL WITH 2' SHOULDERS, 2' PORTABLE CONCRETE BARRIERS AND 1' BUFFERS UNLESS OTHERWISE NOTED ON THE PLANS. 11' MINIMUM LANE WIDTH WILL BE MAINTAINED ON THE RAMPS AT ALL TIMES, EXCEPT AS NOTED ON THE PLANS. BELOW IS THE CONSTRUCTION SEQUENCE FOR THE PROJECT:

PRE-PHASE 1

TEMPORARY PAVEMENT PLACEMENT

PCMS SHALL BE SET UP 300 FT IN ADVANCE OF SHARON RD OVERPASS TO PREPARE FOR THE REMOVAL OF THE DMS SIGN AND TRUSS SUPPORT. THE CONTRACTOR SHALL COORDINATE WITH CENTRAL OFFICE (BRYAN COMER AT (614) 378-1253) TO OBTAIN A MODEM TO USE WITH THE PORTABLE CHANGEABLE MESSAGE SIGN.

PLACE TEMPORARY PAVEMENT ALONG THE WEST SIDE OF I-75 SOUTHBOUND FROM STA. 350+60 TO STA. 366+63 AND STA. 368+55 TO STA. 375+71 CLOSING THE SHOULDER.

PLACE TEMPORARY PAVEMENT ALONG THE EAST SIDE OF I-75 NORTHBOUND FROM STA. 352+85 TO STA. 366+12 AND STA. 367+90 TO STA. 375+95 CLOSING THE SHOULDER.

TWO LANES OF TRAFFIC ON I-75 SB OR NB SHALL BE MAINTAINED AS PER THE UNAUTHORIZED LANE USE TABLE DURING THE PLACEMENT OF TEMPORARY PAVEMENT.

PLACE TEMPORARY PAVEMENT ALONG THE EAST SIDE OF THE EXISTING RAMP G PAVEMENT FROM STA. 360+42 AND STA. 366+50.

ONE LANE OF TRAFFIC ON RAMP G SHALL BE MAINTAINED AS PER THE UNAUTHORIZED LANE USE TABLE DURING THE PLACEMENT OF TEMPORARY PAVEMENT.

PLACE TEMPORARY PAVEMENT ALONG THE EAST SIDE OF THE EXISTING RAMP C PAVEMENT FROM STA. 368+50 AND STA. 373+34.

ONE LANE OF TRAFFIC ON RAMP C SHALL BE MAINTAINED AS PER THE UNAUTHORIZED LANE USE TABLE DURING THE PLACEMENT OF TEMPORARY PAVEMENT.

PHASE 1

**TEMPORARY PAVEMENT PLACEMENT
I-75 NORTHBOUND AND SOUTHBOUND BRIDGE OVER
SHARON ROAD PARTIAL DEMOLITION
I-75 NORTHBOUND AND SOUTHBOUND BRIDGE OVER
SHARON ROAD PARTIAL CONSTRUCTION
RAMP G CONSTRUCTION
RAMP C CONSTRUCTION
SHARON ROAD WIDENING
CHESTER ROAD WIDENING (COMPLETED IN PHASE 1)**

RESTRIPE THE I-75 NORTHBOUND AND SOUTHBOUND LANES TO SHIFT TRAFFIC TO THE OUTSIDE OF THE NORTHBOUND AND SOUTHBOUND BRIDGES OVER SHARON ROAD.

REMOVE THE EXISTING BRIDGE DECK ON THE MEDIAN PORTION OF THE I-75 NORTHBOUND AND SOUTHBOUND BRIDGES OVER SHARON ROAD.

USING SHORT TERM CLOSURES OF SHARON ROAD, REMOVE THE MEDIAN EXISTING BEAMS OF THE I-75 NORTHBOUND AND SOUTHBOUND BRIDGES OVER SHARON ROAD (THE EXISTING BRIDGE PIERS AND CAPS WILL REMAIN INTACT AT THIS TIME).

INSTALL TEMPORARY SHEETING, SHOWN IN THE PLANS, ALONG THE MEDIAN EDGE OF THE I-75 NORTHBOUND AND SOUTHBOUND TEMPORARY ALIGNMENT.

BASED ON CONDITION III OF STANDARD CONSTRUCTION DRAWING (SCD) MT-101.90, PLACE DRUMS ALONG THE TOP OF THE CURB ALONG THE SOUTH SIDE OF SHARON ROAD FROM RAMP A TO RAMP G AND DEMOLISH THE MEDIAN PORTION OF THE EXISTING APPROACH SLAB AND CONCRETE APRON OF THE I-75 NORTHBOUND AND SOUTHBOUND BRIDGES.

CLOSE THE OUTSIDE LANE OF EASTBOUND SHARON ROAD AND CONSTRUCT THE TEMPORARY SIDEWALK ALONG THE SOUTHERN EDGE OF SHARON ROAD, DEMOLISH ENOUGH OF THE EXISTING BRIDGE PIERS AND CAPS TO ACCOMMODATE THE INSTALLATION OF THE PROPOSED BRIDGE BEAMS (THE REMAINING PORTION OF THE EXISTING BRIDGE PIERS CAN REMAIN IN PLACE) AND PLACE THE REMAINING PORTION OF TEMPORARY PAVEMENT FOR RAMP G FROM STA. 366+50 TO SHARON ROAD.

DETOUR PEDESTRIAN TRAFFIC TO THE TEMPORARY SIDEWALK CONSTRUCTED ON THE SOUTH SIDE OF SHARON ROAD.

BASED ON CONDITION III OF SCD 101.90, PLACE DRUMS ON THE TOP OF THE CURB ALONG THE NORTH SIDE OF SHARON ROAD FROM RAMP C TO RAMP E AND DEMOLISH THE MEDIAN PORTION OF THE EXISTING APPROACH SLAB AND CONCRETE APRON OF THE I-75 NORTHBOUND AND SOUTHBOUND BRIDGES.

CLOSE THE OUTSIDE LANE OF WESTBOUND SHARON ROAD AND DEMOLISH ENOUGH OF THE EXISTING BRIDGE PIERS AND CAPS TO ACCOMMODATE THE INSTALLATION OF THE PROPOSED BRIDGE BEAMS (THE REMAINING PORTION OF THE EXISTING BRIDGE PIERS CAN REMAIN IN PLACE) AND PLACE THE REMAINING PORTION OF TEMPORARY PAVEMENT FOR RAMP C FROM STA. 368+50 TO SHARON ROAD.

RESTRIPE RAMP G TRAFFIC TO SHIFT TRAFFIC ONTO THE TEMPORARY PAVEMENT AT SHARON ROAD AND ADJUST SIGNAL HEADS.

RESTRIPE RAMP C TRAFFIC TO SHIFT TRAFFIC ONTO THE TEMPORARY PAVEMENT AT SHARON ROAD AND INSTALL TEMPORARY SIGNALS AT THE FAR SIDE OF THE INTERSECTION.

BASED ON CONDITION III OF SCD 101.90, PLACE DRUMS ON THE TOP OF THE CURB ALONG THE NORTH SIDE OF SHARON ROAD FROM RAMP C TO RAMP E AND CONSTRUCT THE MEDIAN BRIDGE PIERS AND THE MEDIAN PORTIONS ABUTMENT WALLS ALONG THE NORTH SIDE OF SHARON ROAD OF THE I-75 NORTHBOUND AND SOUTHBOUND STRUCTURES (HAM-75-1539 LT AND RT), CONTINUE DETOURING PEDESTRIAN TRAFFIC TO THE SOUTH SIDE OF SHARON ROAD.

BASED ON CONDITION III OF SCD 101.90, PLACE DRUMS ON THE TOP OF THE CURB ALONG THE SOUTH SIDE OF SHARON ROAD FROM RAMP A TO RAMP G AND CONSTRUCT THE MEDIAN BRIDGE PIERS AND THE MEDIAN PORTIONS ABUTMENT WALLS ALONG THE NORTH SIDE OF SHARON ROAD OF THE I-75 NORTHBOUND AND SOUTHBOUND STRUCTURES (HAM-75-1539 LT AND RT). PEDESTRIAN TRAFFIC WILL BE SHIFTED BACK TO THE NORTH SIDE OF SHARON ROAD.

USING SHORT TERM CLOSURES OF SHARON ROAD, PLACE THE PROPOSED BRIDGE BEAMS FOR THE HAM-75-1539 LT AND RT STRUCTURES.

CONSTRUCT THE PROPOSED MEDIAN LANES OF I-75 NORTHBOUND AND SOUTHBOUND OVER SHARON ROAD, HAM-75-1539 LT AND RT, INCLUDING THE APPROACH SLABS AND THE BRIDGE DECKS.

PLACE TEMPORARY PAVEMENT ALONG THE MEDIAN SIDE OF THE I-75 SOUTHBOUND PAVEMENT FROM STA. 325+00 TO STA. 344+19 AND ON THE MEDIAN SIDE OF I-75 NORTHBOUND PAVEMENT FROM STA. 337+05 TO STA. 350+71.

PLACE TEMPORARY PAVEMENT ALONG THE WEST SIDE OF RAMP A FROM STA. 346+16 TO STA. 366+76.

CONSTRUCT A PARTIAL SEGMENT OF RAMP G FROM STA. 353+00 TO STA. 366+71, INCLUDING TEMPORARY PAVEMENT ALONG THE INSIDE EDGE OF PAVEMENT FROM STA. 362+00 TO STA. 366+68, AND INSTALL DRAINAGE PIPE AT STA. 358+10 USING JACK AND BORE TO INSTALL PIPE UNDER THE EXISTING RAMP G PAVEMENT.

CONSTRUCT DRAINAGE DITCH ALONG THE WEST SIDE OF RAMP G FROM STA. 359+00 TO STA. 365+00.

CONSTRUCT A PARTIAL SEGMENT OF RAMP C FROM STA. 368+13 TO STA. 381+00.

CONSTRUCT/INSTALL DRAINAGE DITCHES AND COMPONENTS ALONG THE WEST SIDE OF RAMP C FROM STA. 369+00 TO STA. 384+00.

PLACE TEMPORARY PAVEMENT ALONG THE EAST SIDE OF RAMP E FROM STA. 367+65 TO STA. 380+20.

PLACE TEMPORARY PAVEMENT ALONG THE WEST SIDE OF I-75 SOUTHBOUND PAVEMENT FROM STA. 381+00 TO STA. 409+50.

PLACE TEMPORARY PAVEMENT ALONG THE EAST SIDE OF I-75 NORTHBOUND PAVEMENT FROM STA. 384+50 TO STA. 414+61.

WIDEN THE NORTH SIDE OF SHARON ROAD PAVEMENT FROM STA. 10+75 TO STA. 16+00.

RESTRIPE SHARON ROAD WEST OF CHESTER ROAD TO SHIFT TRAFFIC TO THE NORTH SIDE OF SHARON ROAD.

RESTRIPE CHESTER ROAD TO THE EAST SIDE OF CHESTER ROAD.

PLACE TEMPORARY CONCRETE BARRIER AT THE SOUTHWEST CORNER OF THE SHARON ROAD AND CHESTER ROAD INTERSECTION AND DRUMS ALONG THE WESTERN TRAVEL LANE OF CHESTER ROAD.

WIDEN THE WEST EDGE OF THE CHESTER ROAD, CONSTRUCT ASSOCIATED DRAINAGE AND COMPLETE RECONSTRUCTION OF THE CURB ALONG SHARON ROAD.

DUE TO LACK OF PAVEMENT WIDTH, CHESTER ROAD WIDENING FROM STA. 94+94.95 TO STA. 96+50 SHALL BE COMPLETED WITH A FLAGGER OPERATION FOLLOWING STANDARD CONSTRUCTION DRAWING MT-97.10.

THE REALIGNMENT AND LENGTHENING OF THE STORM SEWER PIPE AT STA. 99+36 SHALL BE COMPLETED WITH A FLAGGER OPERATION FOLLOWING STANDARD CONSTRUCTION DRAWING MT-97.10.

PHASE 2

**I-75 NORTHBOUND AND SOUTHBOUND MEDIAN
PAVEMENT CONSTRUCTION
RAMP A, G, C, & E CONSTRUCTION**

RESTRIPE THE I-75 NORTHBOUND AND SOUTHBOUND LANES TO SHIFT TRAFFIC TO THE OUTSIDE PAVEMENT AND INSTALL PORTABLE CONCRETE BARRIER ALONG THE I-75 MAINLINE.

PERFORM REPAIRS ON THE EAST PARAPET OF THE HAM-75-1642 L STRUCTURE USING OVERNIGHT LANE CLOSURES ON KEMPER ROAD.

RESTRIPE RAMP A TO THE OUTSIDE PAVEMENT AND INSTALL PORTABLE CONCRETE BARRIER ALONG THE TEMPORARY RAMP A ALIGNMENT.

RESTRIPE RAMP G TO THE PROPOSED PAVEMENT AND INSTALL PORTABLE CONCRETE BARRIER ALONG THE TEMPORARY RAMP G ALIGNMENT.

RESTRIPE RAMP C TO THE PROPOSED PAVEMENT AND INSTALL PORTABLE CONCRETE BARRIER ALONG THE TEMPORARY RAMP C ALIGNMENT.

CONSTRUCT THE INSIDE LANES OF I-75 NORTHBOUND FROM STA. 337+06 TO STA. 420+00.

CONSTRUCT THE INSIDE LANES OF I-75 SOUTHBOUND FROM STA. 325+00 TO STA. 420+00.

CONSTRUCT TURNAROUNDS IN THE MEDIAN OF I-75 AT STA. 336+50 AND STA. 392+75.

CONSTRUCT TEMPORARY PAVEMENT ALONG THE NEWLY CONSTRUCTED I-75 NORTHBOUND PAVEMENT FROM STA. 390+00 TO STA. 392+23 AND STA. 392+75 TO STA. 417+00.

CONSTRUCT DRAINAGE ALONG THE MEDIAN OF I-75, INCLUDING DRAINAGE DITCH, STRUCTURES AND PIPES. USE JACK AND BORE TO PLACE DRAINAGE PIPE UNDER THE I-75 SOUTHBOUND PAVEMENT AT STA. 392+90 AND STA. 400+00.

PLACE TEMPORARY PAVEMENT AT TRAFFIC ISLAND AT RAMP A AND SHARON ROAD INTERSECTION.

CONSTRUCT EAST SIDE OF RAMP A FROM STA. 352+25 TO STA. 366+50.

CONSTRUCT DRAINAGE DITCH ALONG THE EAST SHOULDER OF RAMP A FROM STA. 364+15 TO STA. 367+02.

CONSTRUCT REMAINING SECTION OF RAMP G FROM STA. 362+00 TO STA. 366+71 AND REMOVE THE EXISTING AND TEMPORARY RAMP G PAVEMENT AND CONSTRUCT TEMPORARY PAVEMENT FOR RIGHT TURN MOVEMENT.

CONSTRUCT DRAINAGE DITCH ALONG THE EAST SIDE OF RAMP G FROM STA. 363+00 TO STA. 365+22 AND DRAINAGE PIPES.

SHIFT RAMP G RIGHT TURN MOVEMENT TO TEMPORARY PAVEMENT AND CONSTRUCT THE REMAINING SECTION OF THE RAMP G/ SHARON ROAD INTERSECTION.

SHIFT THE RAMP G RIGHT TURN MOVEMENT ONTO THE PROPOSED RAMP PAVEMENT, REMOVE THE TEMPORARY PAVEMENT AND CONSTRUCT TEMPORARY ASPHALT WALK ALONG THE SOUTH SIDE OF SHARON RD EAST OF RAMP G.

SHIFT PEDESTRIAN TRAFFIC TO THE SOUTH SIDE OF SHARON ROAD.

PLACE TEMPORARY PAVEMENT AT TRAFFIC ISLAND AT RAMP E AND SHARON ROAD INTERSECTION.

RESTRIPE RAMP E TO THE OUTSIDE PAVEMENT AND INSTALL PORTABLE CONCRETE BARRIER ALONG THE TEMPORARY RAMP E ALIGNMENT.

CONSTRUCT THE WEST SIDE OF RAMP E FROM STA. 366+66 TO STA. 376+32.

CONSTRUCT THE EAST SIDE OF RAMP C FROM STA. 368+34 TO STA. 372+00.

REMOVE EXISTING RAMP C PAVEMENT AND TEMPORARY PAVEMENT.

CONSTRUCT DRAINAGE ALONG THE EAST SIDE OF RAMP C FROM STA. 369+00 TO STA. 375+00, INCLUDING DRAINAGE DITCH, STRUCTURES AND PIPES.


CALCULATED
STC
CHECKED
JDH

MAINTENANCE OF TRAFFIC SEQUENCE OF CONSTRUCTION

HAM-75-14.61

32
708

J:\pre-int\06\06-386_HAM-75\HAM-00000\mot\sheets\00000mp\108_ph01.dgn 2021-01-19 4:25:26 PM brian.sedzlo\ ODOTV81_PDF_Half.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



MAINTENANCE OF TRAFFIC PLAN - PHASE 1
STA 363+50 TO STA 370+50

HAM-75-14.61

56
708

- NOTES:**
- FOR MAINTENANCE OF TRAFFIC LEGEND SEE SHEET 49.
 - PROVIDE W1-H16-36 SIGNS WITHIN LANE SHIFT PER MT-102.10 & MT-102.20.
 - THE CONTRACTOR SHALL ANCHOR THE PORTABLE BARRIER TO THE BRIDGE PARAPET PER STANDARD CONSTRUCTION DRAWING MT-101.80.

SHEET NUM.					PART.					ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	CALCULATED WLC	CHECKED JDH
565	566				01/IMS/PV	02/NHS/OT	03/IMS/OT	04/IMS/BR	05/IMS/BR								
														TRAFFIC SURVEILLANCE			
345						345				625	25400	345	FT	CONDUIT, 2", 725.04			
	726					726				625	25408	726	FT	CONDUIT, 2", 725.051			
676	437					1,113				625	25500	1,113	FT	CONDUIT, 3", 725.04			
	1,271					1,271				625	25504	1,271	FT	CONDUIT, 3", 725.051			
16,846	3,992					20,838				625	25750	20,838	FT	CONDUIT, 4", MULTICELL, 725.20 , EPC-40	562		
1,098	100					1,198				625	25752	1,198	FT	CONDUIT, 4", MULTICELL, 725.20 , EPC-80	562		
1,196	145					1,341				625	25901	1,341	FT	CONDUIT, JACKED OR DRILLED, AS PER PLAN ,3" OR 4"	562		
8,578	4,343					12,921				625	29010	12,921	FT	TRENCH, 30" DEEP			
1	9					10				625	30700	10	EACH	PULL BOX, 725.08, 18"			
29	9					38				625	30710	38	EACH	PULL BOX, 725.08, 32"			
6						6				625	31510	6	EACH	PULL BOX REMOVED			
	6					6				625	32000	6	EACH	GROUND ROD			
5						5				625	32001	5	EACH	GROUND ROD, AS PER PLAN	563		
4	2					6				625	34001	6	EACH	POWER SERVICE, AS PER PLAN	563		
8,578	4,343					12,921				625	36000	12,921	FT	PLASTIC CAUTION TAPE			
1						1				630	70021	1	EACH	OVERHEAD SIGN SUPPORT, DMS TRUSS, 115', AS PER PLAN	563		
1						1				630	70051	1	EACH	CATWALK, DMS TRUSS, AS PER PLAN	563		
2						2				630	70080	2	EACH	OVERHEAD SIGN SUPPORT FOUNDATION, DMS TRUSS			
	8					8				632	04905	8	EACH	VEHICULAR SIGNAL HEAD, (LED), 2-SECTION, 12" LENS, 1-WAY, POLYCARBONATE, AS PER PLAN	564		
	8					8				632	25000	8	EACH	COVERING OF VEHICULAR SIGNAL HEAD			
	8					8				632	26500	8	EACH	DETECTOR LOOP			
	8					8				632	27004	8	EACH	LOOP DETECTOR UNIT			
	2,625					2,625				632	40500	2,625	FT	SIGNAL CABLE, 5 CONDUCTOR, NO. 14 AWG			
	2					2				632	64010	2	EACH	SIGNAL SUPPORT FOUNDATION			
	2,751					2,751				632	65300	2,751	FT	LOOP DETECTOR LEAD-IN CABLE, 2 CONDUCTOR, NO. 14 AWG			
594	2,559					3,153				632	68200	3,153	FT	POWER CABLE, 2 CONDUCTOR, NO. 6 AWG			
LS	LS					LS				632	90300	LS		SIGNALIZATION, MISC.: REMOVAL OF ITS EQUIPMENT	564		
	2					2				632	90400	2	EACH	SIGNALIZATION, MISC.: RAMP METER SIGN	564		
	2					2				632	90400	2	EACH	SIGNALIZATION, MISC.: SIGNAL SUPPORT, TYPE TC-81.22, DESIGN 12	564		
	2					2				632	90400	2	EACH	SIGNALIZATION, MISC.: SIGNAL SUPPORT, MECHANICAL DAMPER FOR TC-81.22 MAST ARM (GREATER THAN 39' IN LENGTH)	564		
2	2					4				633	67100	4	EACH	CABINET FOUNDATION			
	2					2				633	67200	2	EACH	CONTROLLER WORK PAD			
3						3				633	67201	3	EACH	CONTROLLER WORK PAD, AS PER PLAN	563		
2	2					4				633	74000	4	EACH	UNINTERRUPTIBLE POWER SUPPLY (UPS)			
12,449	909					13,358				804	15010	13,358	FT	FIBER OPTIC CABLE, 24 FIBER			
5	2					7				804	34022	7	EACH	FIBER TERMINATION PANEL, 24 FIBER			
1						1				809	60000	1	EACH	CCTV IP-CAMERA SYSTEM, DOME-TYPE			
1						1				809	61000	1	EACH	CCTV CONCRETE POLE WITH LOWERING UNIT, 70 FEET			
1						1				809	63000	1	EACH	DYNAMIC MESSAGE SIGN (DMS), FULL-SIZE WALK-IN			
2						2				809	65000	2	EACH	ITS CABINET - GROUND MOUNTED			
	2					2				809	65030	2	EACH	ITS CABINET - RAMP METER			
3						3				809	65990	3	EACH	ITS DEVICE, MISC.: EX. CABINET WORK	563		
	2					2				809	67000	2	EACH	RAMP METER SYSTEM			
	2					2				809	68900	2	EACH	SIDE-FIRED RADAR DETECTOR			
2	2					4				809	69123	4	EACH	ATC V6.24 CONTROLLER, AS PER PLAN	561		
LS						LS				809	70000	LS		MAINTAINING ITS DURING CONSTRUCTION			

GENERAL SUMMARY (5 OF 10)

HAM-75-14.61

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000GG005.dgn 2021-01-20 12:10:13 PM william.croxtor ODOTcadd_PDF.plt ODOTV81_Pen.tbl IBI Group

j:\pre-int\06-386_HAM-75_HAM\00000\roadway\sheets\00000GG006.dgn 2021-01-19 4:12:40 PM william.croxton' ODOTcadd_PDF_pltcfgr ODOTV8i_Pen.tbl IBI Group

SHEET NUM.						PART.					ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
204	476	479	480	484	548	01/IMS/PV	02/NHS/OT	03/IMS/OT	04/IMS/BR	05/IMS/BR						
				1,693			1,693				621	00100	1,693	EACH	TRAFFIC CONTROL	
				1,524			1,524				621	54000	1,524	EACH	RAISED PAVEMENT MARKER REMOVED	
		8	22				30				625	32000	30	EACH	GROUND ROD	
28							28				626	00102	28	EACH	BARRIER REFLECTOR, TYPE 1, ONE-WAY	
8							8				626	00102	8	EACH	BARRIER REFLECTOR, TYPE 1, BI-DIRECTIONAL	
139							139				626	00110	139	EACH	BARRIER REFLECTOR, TYPE 2, ONE-WAY	
27							27				626	00110	27	EACH	BARRIER REFLECTOR, TYPE 2, BI-DIRECTIONAL	
		1,374			45		1,419				630	03100	1,419	FT	GROUND MOUNTED SUPPORT, NO. 3 POST	
		99.9					99.9				630	06400	99.9	FT	GROUND MOUNTED STRUCTURAL BEAM SUPPORT, S4X7.7	
		348.7					348.7				630	07500	348.7	FT	GROUND MOUNTED STRUCTURAL BEAM SUPPORT, W10X22	
		172.6					172.6				630	07600	172.6	FT	GROUND MOUNTED STRUCTURAL BEAM SUPPORT, W10X12	
		120					120				630	08004	120	FT	ONE WAY SUPPORT, NO. 3 POST	
		18					18				630	08600	18	EACH	SIGN POST REFLECTOR	
		14					14				630	09000	14	EACH	BREAKAWAY STRUCTURAL BEAM CONNECTION	
			2				2				630	20800	2	EACH	OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 8	
		2					2				630	74500	2	EACH	OVERHEAD SIGN SUPPORT, MISC.: TYPE TC-16.22 DESIGN 13	512
		2					2				630	74500	2	EACH	OVERHEAD SIGN SUPPORT, MISC.: TYPE TC-17.11 DESIGN 8	496
		1					1				630	74500	1	EACH	OVERHEAD SIGN SUPPORT, MISC.: TYPE TC-17.11 DESIGN 10	512
			2				2				630	74500	2	EACH	OVERHEAD SIGN SUPPORT, MISC.: TYPE TC-12.31 DESIGN 6	512
			4				4				630	74500	4	EACH	OVERHEAD SIGN SUPPORT, MISC.: TYPE TC-12.31 DESIGN 12	496
			6				6				630	74500	6	EACH	OVERHEAD SIGN SUPPORT, MISC.: TYPE TC-15.116 DESIGN 2	496
			1				1				630	74500	1	EACH	OVERHEAD SIGN SUPPORT, MISC.: TYPE TC-15.116 DESIGN 3	496
		3			11		14				630	79100	14	EACH	SIGN HANGER ASSEMBLY, MAST ARM	
					2		2				630	79500	2	EACH	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	
		1,087.7			115		1,202.7				630	80100	1,202.7	SF	SIGN, FLAT SHEET	
		549					549				630	80200	549	SF	SIGN, GROUND MOUNTED EXTRUSHEET	
			3,429.5				3,429.5				630	80224	3,429.5	SF	SIGN, OVERHEAD EXTRUSHEET	
		1					1				630	81020	1	EACH	CONCRETE MEDIAN BARRIER SIGN BRACKET	
			1				1				630	84010	1	EACH	CONCRETE BARRIER MEDIAN OVERHEAD SIGN SUPPORT FOUNDATION, TYPE TC-21.50	
		28					28				630	84500	28	EACH	GROUND MOUNTED STRUCTURAL BEAM SUPPORT FOUNDATION	
		2	19				21				630	84510	21	EACH	RIGID OVERHEAD SIGN SUPPORT FOUNDATION	
		6					6				630	84520	6	EACH	SPAN WIRE SIGN SUPPORT FOUNDATION	
130							130				630	84900	130	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
6							6				630	85400	6	EACH	REMOVAL OF GROUND MOUNTED MAJOR SIGN AND DISPOSAL	
7							7				630	85600	7	EACH	REMOVAL OF GROUND MOUNTED MAJOR SIGN AND REERECTION	
112							112				630	86002	112	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
43							43				630	86102	43	EACH	REMOVAL OF GROUND MOUNTED STRUCTURAL BEAM SUPPORT AND DISPOSAL	
2							2				630	86310	2	EACH	REMOVAL OF STRUCTURE MOUNTED SIGN AND DISPOSAL	
					1		1				630	87100	1	EACH	REMOVAL OF OVERHEAD MOUNTED SIGN AND REERECTION	
41					1		42				630	87400	42	EACH	REMOVAL OF OVERHEAD MOUNTED SIGN AND DISPOSAL	
4							4				630	87500	4	EACH	REMOVAL OF POLE MOUNTED SIGN AND DISPOSAL	
5							5				630	89706	5	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYPE TC-12.30	
5							5				630	89802	5	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYPE TC-7.65	
4							4				630	89810	4	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL, TYPE TC-17.10	
1							1				630	89812	1	EACH	REMOVAL OF WOOD POLE AND DISPOSAL	
							1				631	94406	1	EACH	REMOVAL OF SIGNS WIRED	
					2		2				631	97700	2	EACH	SIGN LIGHTING MISC.: REMOVE AND REERECT ILLUMINATED SIGN	545
				0.1			0.1				644	00100	0.1	MILE	EDGE LINE, 4"	
				12.74			12.74				644	00104	12.74	MILE	EDGE LINE, 6"	
				0.71			0.71				644	00200	0.71	MILE	LANE LINE, 4"	
				17			17				644	00204	17	MILE	LANE LINE, 6"	
				1			1				644	00300	1	MILE	CENTER LINE	
				6,531			6,531				644	00400	6,531	FT	CHANNELIZING LINE, 8"	
				18,756			18,756				644	00404	18,756	FT	CHANNELIZING LINE, 12"	
				392			392				644	00500	392	FT	STOP LINE	
				630			630				644	00600	630	FT	CROSSWALK LINE	
				735			735				644	00700	735	FT	TRANSVERSE/DIAGONAL LINE	
				887			887				644	00720	887	FT	CHEVRON MARKING	
				640			640				644	00900	640	SF	ISLAND MARKING	
				2			2				644	01120	2	EACH	SCHOOL SYMBOL MARKING, 120"	
				86			86				644	01300	86	EACH	LANE ARROW	
				620			620				644	01500	620	FT	DOTTED LINE, 4"	
				9,705			9,705				644	01510	9,705	FT	DOTTED LINE, 6"	
				3.72			3.72				644	30030	3.72	MILE	REMOVAL OF PAVEMENT MARKING	

CALCULATED WLC CHECKED JDH
GENERAL SUMMARY (6 OF 10)
HAM-75-14.61
 197
 708

SHEET NUM.					PART.					ITEM	ITEM EXT	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
647	680	684B			01/IMS/PV	02/NHS/OT	03/IMS/OT	04/IMS/BR	05/IMS/BR						
STRUCTURE OVER 20 FOOT SPAN (HAM-75-15.39R,SFN 3110966)															
LS								LS	LS	202	11003	LS		STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	645
288								84	204	202	22900	288	SY	APPROACH SLAB REMOVED	
4								1	3	SPECIAL	20365000	4	EACH	SETTLEMENT PLATFORM	646
LS								LS	LS	503	11101	LS		COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN	645
LS								LS	LS	505	11100	LS		PILE DRIVING EQUIPMENT MOBILIZATION	
4,680								1,357	3,323	507	00600	4,680	FT	14" CAST-IN-PLACE REINFORCED CONCRETE PILES, DRIVEN	
5,040								1,462	3,578	507	00650	5,040	FT	14" CAST-IN-PLACE REINFORCED CONCRETE PILES, FURNISHED	
135,203								39,209	95,994	509	10000	135,203	LB	EPOXY COATED REINFORCING STEEL	
648								188	460	509	30040	648	FT	NO. 6 GFRP DEFORMED BARS	
2								1	1	511	33500	2	EACH	SEMI-INTEGRAL DIAPHRAGM GUIDE	
78								23	55	511	34462	78	CY	CLASS QC SCC CONCRETE WITH QC/QA, BRIDGE DECK (PARAPET)	
252								73	179	511	43512	252	CY	CLASS QC1 CONCRETE WITH QC/QA, ABUTMENT INCLUDING FOOTING	
546								158	388	511	53014	546	CY	CLASS QC3 CONCRETE, MISC.: WITH QC/QA, BRIDGE DECK	645
1,222								354	868	512	10100	1,222	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
61								18	43	512	10300	61	SY	SEALING CONCRETE BRIDGE DECKS WITH HMWM RESIN	
13								4	9	512	33000	13	SY	TYPE 2 WATERPROOFING	
8								2	6	515	15130	8	EACH	DRAPED STRAND PRESTRESSED CONCRETE BRIDGE I-BEAM MEMBERS, LEVEL 3, TYPE WF72-49 (134'-8" LONG)	
21								6	15	515	20000	21	EACH	INTERMEDIATE DIAPHRAGMS	
163								47	116	516	13600	163	SF	1" PREFORMED EXPANSION JOINT FILLER	
85								25	60	516	13900	85	SF	2" PREFORMED EXPANSION JOINT FILLER	
203								59	144	516	14020	203	FT	SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL	
16								5	11	516	44201	16	EACH	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE), AS PER PLAN:	659
														16"x24"x 3.398" WITH 17"x25"x1.5" LOAD PLATES	
131								38	93	518	21200	131	CY	POROUS BACKFILL WITH GEOTEXTILE FABRIC	
252								73	179	518	40000	252	FT	6" PERFORATED CORRUGATED PLASTIC PIPE	
51								15	36	518	40012	51	FT	6" NON-PERFORATED CORRUGATED PLASTIC PIPE	
4								1	3	523	20000	4	EACH	DYNAMIC LOAD TESTING	
4								1	3	523	20500	4	EACH	RESTRIKE	
558								162	396	526	30000	558	SY	REINFORCED CONCRETE APPROACH SLABS (T=17")	
164								48	116	526	90010	164	FT	TYPE A INSTALLATION	
9								3	6	601	21050	9	SY	TIED CONCRETE BLOCK MAT, TYPE 1	
467								135	332	625	25604	467	FT	CONDUIT, 4", 725.051	
2								1	1	625	29921	2	EACH	STRUCTURE JUNCTION BOX, AS PER PLAN	646
2								1	1	625	30700	2	EACH	PULL BOX, 725.08, 18"	
LS								LS	LS	SPECIAL	69098400	LS		TEMPORARY SURCHARGE	646
68								20	48	846	00110	68	CF	POLYMER MODIFIED ASPHALT EXPANSION JOINT SYSTEM	
STRUCTURE 20 FOOT SPAN AND UNDER (HAM-75-15.57,SFN 3110982)															
LS								LS		202	11200	LS		PORTIONS OF STRUCTURE REMOVED	
48								48		202	35200	48	FT	PIPE REMOVED, OVER 24"	
LS								LS		503	11100	LS		COFFERDAMS AND EXCAVATION BRACING	
LS								LS		503	21300	LS		UNCLASSIFIED EXCAVATION	
10,553								10,553		509	10000	10,553	LB	EPOXY COATED REINFORCING STEEL	
113								113		511	46210	113	CY	CLASS QC1 CONCRETE, RETAINING/WINGWALL INCLUDING FOOTING	
120								120		512	10100	120	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	
LS								LS		518	21230	LS		POROUS BACKFILL WITH GEOTEXTILE FABRIC	
75								75		601	11000	75	SY	RIPRAP, TYPE D	
106								106		601	32104	106	CY	ROCK CHANNEL PROTECTION, TYPE B WITH GEOTEXTILE FABRIC	
48								48		611	30000	48	FT	96" CONDUIT, TYPE A, 706.02	
40								40		843	50001	40	SF	PATCHING CONCRETE STRUCTURES WITH TROWELABLE MORTAR, AS PER PLAN	680
STRUCTURE REPAIR (HAM-75-16.42L,SFN 3111040)															
		28						28		202	30701	28	FT	CONCRETE BARRIER REMOVED, AS PER PLAN	684B
		368						368		509	10000	368	LB	EPOXY COATED REINFORCING STEEL	
		16						16		510	10000	16	EACH	DOWEL HOLES WITH NONSHRINK, NONMETALLIC GROUT	
		3						3		511	53014	3	CY	CLASS QC3 CONCRETE, MISC.:QC3 CONCRETE, SUPERSTRUCTURE, AS PER PLAN	684B
		30						30		512	10100	30	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	

GENERAL SUMMARY (9 OF 10)

HAM-75-14.61

j:\pre-int\06-386_HAM-75_HAM\00000\roadway\sheets\00000GG009.dgn 2021-01-19 4:56:26 PM william.croxtan' ODOT\cadd_PDF.plt\cfig ODOTV81_Pen.tbl IBI Group

j:\pre-int\06-386_HAM-75_HAM\00000\roadway\sheets\00000G5002.dgn 2021-01-19 4:25:01 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen.tbl IBI Group

SHEET NO.	203	203	204	204	659	SHEET NO.	203	203	659	SHEET NO.	203	203	659	SHEET NO.	203	203	204	204	659
	EXCAVATION	EMBANKMENT	EXCAVATION OF SUBGRADE, 18 INCHES DEEP	EMBANKMENT, AS PER PLAN	SEEDING AND MULCHING		EXCAVATION	EMBANKMENT	SEEDING AND MULCHING		EXCAVATION	EMBANKMENT	SEEDING AND MULCHING		EXCAVATION	EMBANKMENT	EXCAVATION OF SUBGRADE, 18 INCHES DEEP	GRANULAR MATERIAL, TYPE C	SEEDING AND MULCHING
	CY	CY	CY	CY	SY		CY	CY	SY		CY	CY	SY		CY	CY	CY	CY	SY
I-75 SB						I-75 NB				RAMP C				SHARON ROAD					
251	0	0	0	0	0	312	825	6	803	358	599	17	328	390	29	23	30	30	165
252	296	2	243	243	39	313	2187	9	1733	359	2418	30	1049	391	166	26	120	120	198
253	341	15	723	729	217	314	1947	20	1828	360	2694	207	850	392	582	30	270	270	361
254	367	7	715	730	267	315	1552	210	2561	361	1280	651	689	393	1194	14	321	321	435
255	338	4	738	756	201	316	1168	129	1445	362	894	1286	778	394	985	70	477	478	456
256	302	39	716	753	389	317	972	110	1250	363	572	1960	689	395	212	555	278	299	562
257	129	68	457	498	223	318	1047	118	1431	364	368	2074	690	396	326	209	341	343	515
258	82	70	328	345	209	319	1371	80	1877	365	221	2200	672	397	363	25	350	350	317
259	81	107	378	398	296	320	1731	380	3977	366	104	2188	533	398	630	19	349	351	340
260	187	81	485	499	438	321	1077	1431	3093	367	73	2230	523	399	703	12	351	351	0
261	219	72	479	509	489	322	837	520	1795	368	48	1626	354	400	624	119	351	351	98
262	225	90	455	532	584	323	357	145	780					401	316	248	333	333	550
263	251	83	432	541	677	324	759	803	2143	RAMP A				402	365	67	474	474	211
264	275	96	377	543	712	325	265	1850	2005		177	36	495	403	205	65	291	293	295
265	293	52	251	382	697	326	232	5953	2238		142	133	815	404	108	30	140	140	161
266	345	74	337	449	833	327	859	4784	1513		332	363	1400	405	111	27	119	119	188
267	374	100	500	556	783	328	1216	7186	2373		509	354	1534	406	0	0	0	0	0
268	613	169	771	826	1145	329	832	4479	2240		649	211	1172						
269	835	90	818	835	1299	330	890	1352	2555		982	125	1145						
270	940	67	843	852	1366	331	671	735	1407		1408	68	1305	SHARON ROAD SUBTOTAL	6,919	1,539	4,595	4,623	4,852
271	1055	118	826	835	1621	332	1344	1053	2355		1588	45	1455						
272	1070	172	864	872	1662	333	1798	1346	2778										
273	1720	160	1180	1183	2154	334	526	817	1363	RAMP G				CHESTER ROAD					
274	1619	17			1394	335	1552	2193	2782		39	409	536	407	35	27	60	63	151
275	1453	133			2065	336	1865	3214	2699		47	1390	1165	408	22	4	48	51	30
276	1049	408			2443	337	1333	1635	2346		10	1478	845	409	48	26	97	102	122
277	609	329			1187	338	859	1160	1652		39	2247	1389	410	125	14	199	202	109
278	740	1079			1840	339	877	1127	2654		168	1533	1528						
279	612	2052			1971	340	738	1524	1994		386	1206	1332	CHESTER ROAD SUBTOTAL	230	71	404	418	412
280	579	6010			2495	341	1010	1269	2455		774	617	1279						
281	767	4561			1309	342	909	1047	2220										
282	1057	6044			1954	343	1226	1481	2972	RAMP E									
283	646	3507			3084	344	1061	1545	3271		356	134	211						
284	3485	1324			3850	345	1137	1824	2645		47	220	728						
285	1972	568			2205	346	1380	1773	3138		151	353	1217						
286	887	856			1796	347	1373	2617	3388		267	277	1156						
287	766	1270			1767	348	1574	2677	2594		151	144	494						
288	453	1963			988	349	799	1420	1317		186	165	459						
289	898	4050			2361	350	1373	1763	2018										
290	1100	2738			2400	351	1052	1353	1312										
291	1340	2071			2133	352	787	1672	1689										
292	528	860			1346	353	778	1880	1788										
293	617	356			1940	354	621	1599	1638										
294	507	913			1749	355	248	1304	1421										
295	977	723			1911	356	226	1107	1659										
296	1214	321			1880	357	104	463	2300										
297	1417	502			2484														
298	898	997			2195														
299	701	1380			2321														
300	633	1310			2423														
301	570	1329			2378														
302	620	1260			2423														
303	358	531			1222														
304	493	651			1528														
305	404	613			1278														
306	489	862			1367														
307	491	954			1406														
308	325	949			1439														
309	193	918			1457														
310	188	845			1548														
311	92	402			1033														
I-75 SB SUBTOTAL	42,085	57,392	12,916	13,866	88,871	I-75 NB SUBTOTAL	47,345	71,163	97,495	RAMPS SUBTOTAL	17,679	25,977	28,815						

GRAND TOTAL						
	203	203	204	204	204	659
	EXCAVATION	EMBANKMENT	EXCAVATION OF SUBGRADE, 18 INCHES DEEP	EMBANKMENT, AS PER PLAN	GRANULAR MATERIAL, TYPE C	SEEDING AND MULCHING
	CY	CY	CY	CY	CY	SY
I-75 SB	42,085	57,392	12,916	13,866		88,871
I-75 NB	47,345	71,163				97,495
RAMPS	17,679	25,977				28,815
SHARON ROAD	6,919	1,539	4,595		4,623	4,852
CHESTER ROAD	230	71	404		418	412
TOTALS CARRIED TO GEN SUM	114,258	156,142	17,915	13,866	5,041	220,445

CALCULATED WLC CHECKED JDH
SUBSUMMARY - EARTHWORK
HAM-75-14.61
 203
 708

J:\pre-int\06-386_HAM-75\HAM\00000\roadway\sheets\00000G5010.dgn 2021-01-08 3:12:02 PM william.croxton' ODOTcadd_PDF_pltcfgr ODOTV8:Pen.tbl IBI Group

STATION RANGE			ROUTE	SIDE	L=LENGTH (FT)	W=WIDTH (FT)	A=LxW=AREA (SF)	202	202	202	204	204	204	204	206	206	206	206	254	301	301	301	302	304	407	407	442	442	442	442	442	452	618		
								PAVEMENT REMOVED	PAVEMENT REMOVED, ASPHALT	WEARING COURSE REMOVED	SUBGRADE COMPACTION	PROOF ROLLING (APPLIED AT 1 HR/2000 SY FOR RECONSTRUCTION)	PROOF ROLLING (APPLIED AT 1 HR/3000 SY FOR NEW CONSTRUCTION)	GEOTEXTILE FABRIC	CEMENT (APPLIED AT 5% PER 115 LB/CF SOIL)	CURING COAT	CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP	MIXTURE DESIGN FOR CHEMICALLY STABILIZED SOILS	PAVEMENT PLANING, ASPHALT CONCRETE, (1"-3.25")	(6") ASPHALT CONCRETE BASE, PG64-22	(10") ASPHALT CONCRETE BASE, PG64-22	(VAR. DEPTH, 2" AVG) ASPHALT CONCRETE BASE, PG64-22, AS PER PLAN	(11") ASPHALT CONCRETE BASE, PG64-22	(8") AGGREGATE BASE	NON-TRACKING TACK COAT (APPLIED AT AVG 0.055 GAL/SY FOR NEW ASPHALT)	NON-TRACKING TACK COAT (APPLIED AT AVG 0.085 GAL/SY FOR MILLED ASPHALT SURFACE)	(1.75") ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (446)	(VAR. DEPTH, 2" AVG) ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (446), AS PER PLAN	(1.5") ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE A (447), AS PER PLAN	(1.5") ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE A (448)	(1.75") ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (448)	(VAR. DEPTH, 2" AVG) ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (448), AS PER PLAN	13.5" NON-REINFORCED CONCRETE PAVEMENT, CLASS OCl	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE), AS PER PLAN	
								SY	SY	SY	SY	HR	HR	SY	TON	SY	SY	LS	SY	CY	CY	CY	CY	CY	GAL	GAL	CY	CY	CY	CY	CY	SY	MILE		
RAMP A																																			
343+23.26	TO	367+57.83	MAIN	LT/RT			44695.05	4966.12																											
343+22.75	TO	367+49.13	INS SHLDR	RT			14448.93																												
343+22.96	TO	367+72.87	OUT SHLDR	LT/RT			25039.86																												
366+30.31	TO	367+57.86	MEDIAN SHLDR	LT/RT			1006.60																												
352+30.24	TO	367+51.17	MAIN/SHLDR FD	LT/RT			59870.00																												
352+30.24	TO	367+51.17	INS SHLDR 6" EC	RT	1520.93	0.50	760.47																												
352+30.24	TO	367+51.17	OUT SHLDR 6" EC	LT	1520.93	0.50	760.47																												
352+30.24	TO	367+51.17	INS SHLDR 18" EC	RT	1520.93	1.50	2281.40						0.08	7.65	253.49	253.49	LS																		
352+30.24	TO	367+51.17	OUT SHLDR 18" EC	LT	1520.93	1.50	2281.40						0.08	7.65	253.49	253.49	LS																		
RAMP C																																			
368+11.82	TO	379+41.35	MAIN	LT/RT			20790.61	2310.07																											
368+13.62	TO	379+41.72	INS SHLDR	RT			8076.01																												
368+15.05	TO	379+40.88	OUT SHLDR	LT/RT			10980.47																												
368+34.09	TO	380+22.92	MAIN/SHLDR FD	LT/RT			54305.00																												
368+34.09	TO	380+22.92	INS SHLDR 6" EC	RT	1188.83	0.50	594.42																												
368+34.09	TO	380+22.92	OUT SHLDR 6" EC	LT	1188.83	0.50	594.42																												
368+34.09	TO	380+22.92	INS SHLDR 18" EC	RT	1188.83	1.50	1783.25						0.07	5.98	198.14	198.14	LS																		
368+34.09	TO	380+22.92	OUT SHLDR 18" EC	LT	1188.83	1.50	1783.25						0.07	5.98	198.14	198.14	LS																		
RAMP E																																			
366+72.45	TO	383+17.33	MAIN	LT/RT			30014.08	3334.90																											
366+71.64	TO	383+17.00	INS SHLDR	LT			13115.14																												
367+11.17	TO	383+17.52	OUT SHLDR	LT/RT			14247.02																												
366+72.51	TO	367+44.44	MEDIAN SHLDR	RT			760.85																												
366+93.35	TO	376+29.48	MAIN/SHLDR FD	LT/RT			44585.00																												
366+93.35	TO	376+29.48	INS SHLDR 6" EC	RT	936.13	0.50	468.07																												
366+93.35	TO	376+29.48	OUT SHLDR 6" EC	LT	936.13	0.50	468.07																												
366+93.35	TO	376+29.48	INS SHLDR 18" EC	RT	936.13	1.50	1404.20						0.05	4.71	156.02	156.02	LS																		
366+93.35	TO	376+29.48	OUT SHLDR 18" EC	LT	936.13	1.50	1404.20						0.05	4.71	156.02	156.02	LS																		
RAMP G																																			
349+84.59	TO	366+80.08	MAIN	LT/RT			36983.83	4109.31																											
349+84.96	TO	366+80.21	INS SHLDR	LT/RT			8373.01																												
349+84.31	TO	366+70.34	OUT SHLDR	RT			14879.29																												
356+70.22	TO	366+71.35	MAIN/SHLDR FD	LT/RT			44585.00																												
356+70.22	TO	366+71.35	INS SHLDR 6" EC	RT	1001.13	0.50	500.56																												
356+70.22	TO	366+71.35	OUT SHLDR 6" EC	LT	1001.13	0.50	500.56																												
356+70.22	TO	366+71.35	INS SHLDR 18" EC	RT	1001.13	1.50	1501.70						0.06	5.04	166.86	166.86	LS																		
356+70.22	TO	366+71.35	OUT SHLDR 18" EC	LT	1001.13	1.50	1501.70						0.06	5.04	166.86	166.86	LS																		
P&R=PLANING & RESURFACING, FD=FULL DEPTH, WID=WIDENING, EC=EDGE COURSE																																			
TOTALS CARRIED TO SHEET 212								14,721	12,326	27,046	0	0	9	0	729	24,143	24,143	LS	0	0	0	0	0	5,136	0	0	0	0	0	0	0	0	22,594	0.00	

J:\pre-int\06-386_HAM-75-HAM\00000\roadway\sheets\00000G5011.dgn 2021-01-20 9:08:33 AM william.croxton' ODOTcadd_PDF.plt cfw ODOTV8i_Pen.tbl IBI Group

STATION RANGE	ROUTE	SIDE	L=LENGTH (FT)	W=WIDTH (FT)	A=LxW=AREA (SF)	202	202	202	204	204	204	204	206	206	206	206	254	301	301	301	302	304	407	407	442	442	442	442	452	618		
						PAVEMENT REMOVED	PAVEMENT REMOVED, ASPHALT	WEARING COURSE REMOVED	SUBGRADE COMPACTION	PROOF ROLLING (APPLIED AT 1 HR/2000 SY FOR RECONSTRUCTION)	PROOF ROLLING (APPLIED AT 1 HR/3000 SY FOR NEW CONSTRUCTION)	GEOTEXTILE FABRIC	CEMENT (APPLIED AT 5% PER 115 LB/CF SOIL)	CURING COAT	CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP	MIXTURE DESIGN FOR CHEMICALLY STABILIZED SOILS	PAVEMENT PLANING, ASPHALT CONCRETE, (1"-3.25")	(6") ASPHALT CONCRETE BASE, PG64-22	(10") ASPHALT CONCRETE BASE, PG64-22	(VAR. DEPTH, 2" AVG) ASPHALT CONCRETE BASE, PG64-22, AS PER PLAN	(11") ASPHALT CONCRETE BASE, PG64-22	(8") AGGREGATE BASE	NON-TRACKING TACK COAT (APPLIED AT AVG 0.055 GAL/SY FOR NEW ASPHALT)	NON-TRACKING TACK COAT (APPLIED AT AVG 0.085 GAL/SY FOR MILLED ASPHALT SURFACE)	(1.75") ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (446)	(VAR. DEPTH, 2" AVG) ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (446), AS PER PLAN	(1.5") ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE A (447), AS PER PLAN	(1.5") ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE A (448)	(1.75") ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (448)	(VAR. DEPTH, 2" AVG) ASPHALT CONCRETE INTERMEDIATE COURSE, 19MM, TYPE A (448), AS PER PLAN	13.5" NON-REINFORCED CONCRETE PAVEMENT, CLASS OCI	RUMBLE STRIPS, SHOULDER (ASPHALT CONCRETE), AS PER PLAN
SHARON ROAD						SY	SY	SY	SY	SY	SY	SY	TON	SY	SY	LS	SY	CY	CY	CY	CY	CY	GAL	GAL	CY	CY	CY	CY	CY	CY	MILE	
10+75.00 TO 28+51.86	MAIN	LT			8631.09	959.01		959.01																								
9+10.00 TO 28+24.63	MAIN	RT			7023.18	780.35		780.35																								
10+75.00 TO 14+00.00	MAIN P&R	LT	325.00	30.00	9750.00												1083.33		60.19			178.75	92.08					45.14	52.66	60.19		
14+00.00 TO 15+00.00	MAIN P&R	LT	100.00	24.00	2400.00														14.81			44.00	22.67				11.11	12.96	14.81			
15+00.00 TO 28+22.95	MAIN P&R	LT	1322.95	25.00	33073.75												3674.86		204.16			606.35	312.36				153.12	178.64	204.16			
28+22.95 TO 29+16.67	MAIN P&R	LT			2348.00												260.89		14.49			43.05	22.18				10.87	12.68	14.49			
9+10.00 TO 13+00.00	MAIN P&R	RT	390.00	21.50	8385.00												931.67		51.76			153.73	79.19				38.82	45.29	51.76			
13+00.00 TO 16+75.00	MAIN P&R	RT	375.00	22.75	8531.25												947.92		52.66			156.41	80.57				39.50	46.08	52.66			
16+75.00 TO 24+50.00	MAIN P&R	RT	775.00	24.00	18600.00												2066.67		114.81			341.00	175.67				86.11	100.46	114.81			
24+50.00 TO 28+00.00	MAIN P&R	RT	350.00	28.00	9800.00												1088.89		60.49			179.67	92.56				45.37	52.93	60.49			
10+75.00 TO 15+79.22	MAIN FD WID	LT			10813.00				1201.44	0.60		1201.44							333.73			266.99	198.24				50.06	58.40				
10+75.00 TO 15+79.22	C&G 40" EC	LT	504.22	3.33	1680.73				186.75	0.09		186.75										41.50										
15+79.22 TO 23+97.11	MAIN FD WID	LT	817.89	24.00	19629.36				2181.04	1.09		2181.04										484.68	359.87				90.88	106.02				
15+79.22 TO 23+97.11	C&G 40" EC	LT	817.89	3.33	2726.30				302.92	0.15		302.92										67.32										
23+97.11 TO 28+51.86	MAIN FD WID	LT			10011.00				1112.33	0.56		1112.33										308.98	247.19	183.54				46.35	54.07			
23+97.11 TO 28+51.86	C&G 40" EC	LT	454.75	3.33	1515.83				168.43	0.08		168.43											37.43									
9+10.00 TO 16+75.00	MAIN FD WID	RT			18861.00				2095.67	1.05		2095.67										582.13	465.70	345.79				87.32	101.87			
9+10.00 TO 16+75.00	C&G 40" EC	RT	765.00	3.33	2550.00				283.33	0.14		283.33											62.96									
16+75.00 TO 24+50.00	MAIN FD WID	RT	775.00	11.00	8525.00				947.22	0.47		947.22										263.12		210.49	156.29			39.47	46.05			
16+75.00 TO 24+50.00	C&G 40" EC	RT	775.00	3.33	2583.33				287.04	0.14		287.04											63.79									
24+50.00 TO 28+24.63	MAIN FD WID	RT			2655.00				295.00	0.15		295.00										81.94		65.56	48.68			12.29	14.34			
24+50.00 TO 28+24.63	C&G 40" EC	RT	374.63	3.33	1248.77				138.75	0.07		138.75											30.83									
TOTALS CARRIED TO SHEET 212						1,740	0	1,740	9,200	5	0	9,200	0	0	0	LS	10,321	0	2,176	574	0	2,045	2,996	878	0	0	0	757	883	574	0	0.00
CHESTER ROAD																																
94+94.95 TO 99+90.70	MAIN P&R	LT/RT			14965.00																											
94+94.95 TO 99+90.70	MAIN FD	LT			5233.00				581.44	0.29		581.44																69.28	80.83	92.38		
94+94.95 TO 99+90.70	C&G 40" EC	LT	495.75	3.33	1652.50				183.61	0.09		183.61																24.23	28.26			
P&R=PLANING & RESURFACING, FD=FULL DEPTH, WID=WIDENING, EC=EDGE COURSE																																
TOTALS CARRIED TO SHEET 212						0	0	0	766	1	0	766	0	0	0	LS	1,663	97	0	93	0	171	371	142	0	0	0	94	110	93	0	0.00
SHEET NO.	DESCRIPTION					202	202	202	204	204	204	204	206	206	206	206	254	301	301	301	302	304	407	407	442	442	442	442	452	618		
						SY	SY	SY	SY	SY	SY	SY	TON	SY	SY	LS	SY	CY	CY	CY	CY	CY	GAL	GAL	CY	CY	CY	CY	CY	CY	MILE	
208	I-75 SB					39,199	14,918	54,116	577	0	32	0	2,717	89,973	89,973	LS	2,895	0	0	0	26,906	20,045	14,686	247	4,362	161	3,740	0	0	0	3.53	
210	I-75 NB					32,543	12,200	44,742	577	0	27	0	2,337	77,382	77,382	LS	4,568	0	0	0	23,126	17,256	12,847	389	3,850	254	3,252	0	0	0	3.05	
211	RAMPS					14,721	12,326	27,046	0	0	9	0	729	24,143	24,143	LS	0	0	0	0	5,136	0	0	0	0	0	0	0	0	0	22,594	0.00
212	SHARON ROAD					1,740	0	1,740	9,200	5	0	9,200	0	0	0	LS	10,321	0	2,176	574	0	2,045	2,996	878	0	0	0	757	883	574	0	0.00
212	CHESTER ROAD					0	0	0	766	1	0	766	0	0	0	LS	1,663	97	0	93	0	171	371	142	0	0	0	94	110	93	0	0.00
TOTALS CARRIED TO GENERAL SUMMARY						88,203	39,444	127,644	11,120	74	0	9,966	5,783	191,498	191,498	LS	19,447	2,273	667	50,032	44,653		32,556		8,212	415	6,992	851	993	667	22,594	6.58
FUNDING SPLITS																																
01/MS/PV:																																
I-75 MAINLINE MULTI-LANE 71%						50937	19254	70189	819	42	0	3588	118822	118822	LS	5299	0	0	35523	26484		20000		5831	295	4964	0	0	0	0	0	4.67
02/NHS/OT:																																
I-75 MAINLINE MAJOR NEW 29%						20805	7864	28669	335	17	0	1466	48533	48533	LS	2164	0	0	14509	10817		8169		2381	120	2028	0	0	0	0	1.91	
ALL OTHERS MAJOR NEW FUNDING						16,461	12,326	28,786	9,966	15	0	9,966	729	24,143	24,143	LS	11,984	2,273	667	0	7,352		4,387		0	0	0	851	993	667	22,594	0.00
SUBTOTAL						37,266	20,190	57,455	10,301	32	0	9,966	2,195	72,676	72,676	LS	14,148	2,273	667	14,509	18,169		12,556		2,381	120	2,028	851	993	667	22,594	1.91

SUBSUMMARY - PAVEMENT (6 OF 6)

HAM-75-14.61

212
708

CALCULATED
WLC
CHECKED
JDH

J:\pre-int\06-386_HAM-75\HAM\00000\roadway\sheets\00000GP100.dgn 2021-01-19 3:41:17 PM e:\william.croxtor\ ODOTV81_Pen-ME.tbl IBI Group

--- HAM-75-12.60 (PID 82288)
--- ORIGINAL HAM-75
** DENOTES ITEM CONSTRUCTED DURING HAM-75-12.60 (PID 82288)

BEGIN WORK @ CONST. I-75 SB STA 316+00.00

BEGIN PROJECT HAM-75-14.61 (PID 76256) STA 324+00.00 SLM=14.61 E040(822)

STA. 323+39.12 BEGIN SPEED CHANGE LANE FOR RAMP Q

STA. 324+00.00, @ CONST. I-75 SB MATCH INTO HAM-75-12.60 (PID 82288) BEGIN PLANING AND RESURFACING

STA. 324+30.61, @ CONST. I-75 SB END PLANING AND RESURFACING BEGIN FULL DEPTH PAVEMENT

BEGIN CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE D STA. 325+00.00, 72.00' LT @ CONST. I-75 SB
END CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE D
BEGIN CONCRETE BARRIER, SINGLE SLOPE, TYPE D STA. 325+15.00, 72.00' LT @ CONST. I-75 SB
CONCRETE BARRIER, SINGLE SLOPE, TYPE D (10')
END CONCRETE BARRIER, SINGLE SLOPE, TYPE D
BEGIN CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE D STA. 325+25.00, 72.00' LT @ CONST. I-75 SB
END CONCRETE BARRIER, SINGLE SLOPE, TYPE D
END ANCHORAGE, REINFORCED, TYPE D STA. 325+40.00, 72.00' LT @ CONST. I-75 SB
BEGIN PAVED GUTTER, TYPE 4 STA. 325+50.00, 81.00' LT @ CONST. I-75 SB
BEGIN END ANCHORAGE, REINFORCED, TYPE D STA. 325+60.00, 72.00' LT @ CONST. I-75 SB
END END ANCHORAGE, REINFORCED, TYPE D
BEGIN CONCRETE BARRIER, SINGLE SLOPE, TYPE D STA. 325+75.00, 72.00' LT @ CONST. I-75 SB
CONCRETE BARRIER, SINGLE SLOPE, TYPE D (760')

VILLAGE OF GLENDALE
VILLAGE OF EVENDALE
SYCAMORE TWP.

BEGIN CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE D STA. 333+45.00, 72.00' LT @ CONST. I-75 SB
END/BEGIN CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE D EXPANSION JOINT PER SCD RM-4.5 STA. 333+60.00, 72.00' LT @ CONST. I-75 SB
BEGIN CONCRETE BARRIER, END ANCHORAGE, REINFORCED, TYPE D STA. 333+75.00, 72.00' LT @ CONST. I-75 SB

END GUARDRAIL, TYPE MGS BEGIN AA, MGS TYPE B STA. 334+80.30, 18.55' RT. @ CONST. I-75 SB
END AA, MGS TYPE B STA. 335+17.44, 23.50' RT. @ CONST. I-75 SB

**EX. FENCE (DND)
EX. FENCE (TBR 82288)

**EX. DITCH (DND)

**EX. DITCH (TBR)

** EX. CONCRETE BARRIER, TYPE C1 (DND)

LB-1

G-1

D-68

EX. GUARDRAIL (TBR) @ CONST. I-75 SB
EX. OVERHEAD CANTILEVER SIGN (TBR)

STA 333+19.29, 60.00' LT. @ CONST. I-75 SB
END SPEED CHANGE LANE FOR RAMP A
END SHOULDER TAPER (50:1)
END 100' SHOULDER CHANGE LANE FOR RAMP A
END 650' SPEED CHANGE LANE FOR RAMP A
BEGIN AUXILIARY LANE FOR MAINLINE

STA 334+19.29, 72.00' LT. @ CONST. I-75 SB
BEGIN 100' SHOULDER TAPER (50:1)

CONCRETE BARRIER, SINGLE SLOPE, TYPE D (820')

** EX. CONCRETE BARRIER, TYPE B1 (DND)

** EX. DITCH (TBR)

** EX. CATCH BASIN (TBR)

R-86

R-85

EC-1

EX. MANHOLE ** (DND)

LB-3

CURVE 2

CURVE 4

CURVE 3

NOTES:
1.) SEE CROSS SECTION SHEETS FOR ADDITIONAL UTILITY INFORMATION.
2.) SEE SHEETS 450A-450D FOR BMP DETAILS.

- PR. FULL DEPTH CONCRETE PAVEMENT
- PR. CONCRETE WALK
- PR. CURB RAMP
- PR. FULL DEPTH ASPHALT PAVEMENT
- PLANING & RESURFACING, (1" MIN, 3.25" MAX) WITH WEDGE COURSE (VAR. DEPTH)
- PLANING & RESURFACING, (1.5") (SEE MOT PLANS)

BEGIN GUARDRAIL, TYPE MGS MATCH EXISTING STA. 327+50.54, 74.00' RT. @ CONST. I-75 NB

120' CONCRETE BARRIER REPLACEMENT FOR NEW OVERHEAD SIGN SUPPORT FOUNDATION

END GUARDRAIL, TYPE MGS MATCH EXISTING STA. 331+77.00, 74' RT. @ CONST. I-75 NB
1-STY METAL BLDG.

EX. FENCE ** (DND)

** EX. DITCH (DND)

EX. IMPACT ATTENUATOR ** (DND)

BEGIN GUARDRAIL, TYPE MGS STA. 333+81.07, 14.00' RT. @ CONST. I-75 SB

** EX. CONCRETE BARRIER, TYPE B1 (DND)

\$=CONCRETE BARRIER AND INLET (20' LENGTH) INCLUDED WITH ITEM 611

- ITEM 670-SLOPE EROSION PROTECTION
- ITEM 659-TOPSOIL
- ITEM 670-DITCH EROSION PROTECTION
- ITEM 836-SEEDING AND EROSION CONTROL WITH TURF REINFORCING MAT, TYPE 1 OR TYPE 2

CURVE 2 @ CONST. I-75 SB
P.I. STA 336+05.55
 $\Delta = 22^\circ 07' 38''$ (LT)
 $Dc = 1^\circ 20' 00''$
 $R = 4,297.18'$
 $T = 840.24'$
 $L = 1,659.54'$
 $E = 81.38'$
 $C = 1,649.25'$
C.B. = $N 9^\circ 28' 36'' E$
 $e_{max} = 0.043$

CURVE 3 @ CONST. I-75
P.I. STA 337+74.35
 $\Delta = 22^\circ 07' 38''$ (LT)
 $Dc = 1^\circ 20' 00''$
 $R = 4,297.18'$
 $T = 840.24'$
 $L = 1,659.54'$
 $E = 81.38'$
 $C = 1,649.25'$
C.B. = $N 9^\circ 28' 36'' E$
 $e_{max} = N.C.$

CURVE 4 @ CONST. I-75 NB
P.I. STA 339+43.15
 $\Delta = 22^\circ 07' 38''$ (LT)
 $Dc = 1^\circ 20' 00''$
 $R = 4,297.18'$
 $T = 840.24'$
 $L = 1,659.54'$
 $E = 81.38'$
 $C = 1,649.25'$
C.B. = $N 9^\circ 28' 36'' E$
 $e_{max} = 0.043$




PLAN - I-75 SB / NB
STA 323+00 TO STA 335+50

HAM-75-14.61

216
708

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM-75\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:44 AM william.croxtan ODOTcadd_PDF.plt cfbg ODOTV8i_Pen-ME.tbl IBI_Group



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

SEEDING		END AREA		VOLUME		CALCULATED	
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	WLC	CHECKED
0	0	0	0	0	0	0	0
160	140	63	0	63	0	0	0


* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND EMBANKMENT, AS PER PLAN

CROSS SECTIONS I-75 SB
STA. 323+00 TO STA. 324+30.61

HAM-75-14.61

251
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:45 AM william.croxton ODOT\cadd_PDF.plt\cfig ODOTV8i_Pen-ME.tbi IBI Group



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE


END STA	AREA		VOLUME		CALCULATED WLC	CHECKED	JDH
	CUT	FILL	CUT	FILL			
63	131*	2	131*	2			
126	243*	2	243*	2			
73	131*	0	131*	0			
125	0	0	0	0			
61	0	0	0	0			
45	0	0	0	0			
296	2	2	243*	243*			

**CROSS SECTIONS I-75 SB
 STA. 324+50 TO STA. 325+50**

HAM-75-14.61

252
 708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:46 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI_Group



SEEDING
 END WIDTH SO. YDS.
 SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.


END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
66	129*	3	131*	
115	240*	5	243*	
58	130*	2	131*	
111	241*	5	243*	
61	130*	3	131*	
115	242*	5	243*	
341	723*	15	729*	

CROSS SECTIONS I-75 SB
STA. 326+00 TO STA. 327+00
HAM-75-14.61
 253
 708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:47 AM william.croxtan ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END CUT	AREA FILL	VOLUME		CALCULATED WLC	CHECKED JDH
		CUT	FILL		
70	0	129*	132*		
62	1	128*	131*	123	1
67	1	129*	131*	238*	244*
67	1	129*	131*	120	2
67	1	129*	131*	238*	243*
67	1	129*	131*	124	4
367	7	715*	730*		

CROSS SECTIONS I-75 SB
STA. 327+50 TO STA. 328+50

HAM-75-14.61

254
708

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND EMBANKMENT, AS PER PLAN


HAM-75-12.60 (PID 82288) ORIGINAL HAM-75
** DENOTES ITEM CONSTRUCTED DURING HAM-75-12.60 (PID 82288)

SEEDING
END WIDTH SO. YDS.
SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:48 AM william.croxton ODOTcadd_PDF.plt c:\odot\8i_Pen-ME.tbl IBI Group



CROSS SECTIONS I-75 SB
STA. 329+00 TO STA. 330+00

HAM-75-14.61

255
708

SEEDING
END WIDTH SO. YDS.
SEE SHEETS 23 AND 450A-450D FOR BIOTENTION NOTES AND DETAILS.

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND EMBANKMENT, AS PER PLAN

HAM-75-12.60 (PID 82288) ORIGINAL HAM-75
** DENOTES ITEM CONSTRUCTED DURING HAM-75-12.60 (PID 82288)

EARTHWORK LIMITS FOR I-75 SB

CONST. I-75
PLANING & RESURFACING, (1.5") (SEE MOT PLANS)

I-75 SB
625.33
330+00
624.02

I-75
330+00.94

EARTHWORK LIMITS FOR I-75 SB

CONST. I-75
PLANING & RESURFACING, (1.5") (SEE MOT PLANS)

I-75 SB
624.32
329+50
623.04

I-75
329+50.69

EARTHWORK LIMITS FOR I-75 SB

CONST. I-75
PLANING & RESURFACING, (1.5") (SEE MOT PLANS)

I-75 SB
623.31
329+00
622.05


I-75
329+00.46

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

CONST I-75 SB

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:50 AM william.croxton ODOTcadd_PDF.plt cfbg ODOTV8i_Pen-ME.tbl IBI Group




END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
34	120*	12	134*		
82	229*	18	249*		
54	127*	7	134*		
112	238*	13	249*		
66	129*	6	134*		
108	249*	8	255*		
302	716*	39	753*		

CROSS SECTIONS I-75 SB
 STA. 330+50 TO STA. 331+50

HAM-75-14.61

256
 708

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:51 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80	
	END WIDTH	SO. YDS.																								
			SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.																							

END AREA	VOLUME		CALCULATED	CHECKED	J.D.H.
	CUT	FILL			
33	128*	23	134*		
64	232*	39	249*		
36	122*	19	134*		
65	225*	29	249*		
129	457*	68	498*		

CROSS SECTIONS I-75 SB
STA. 332+00 TO STA. 332+50

HAM-75-14.61


257
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:52 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbi IBI_Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80	
	END WIDTH	SO. YDS.																								



HAM-75-12.60 (PID 82288) ORIGINAL HAM-75
 ** DENOTES ITEM CONSTRUCTED DURING HAM-75-12.60 (PID 82288)

END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
CUT	FILL	CUT	FILL		
28	125*	35	134*		
64	91*	23	96*		
28	127*	27	134*		
145	237*	47	249*		
209	328*	70	345*		

CROSS SECTIONS I-75 SB
 STA. 333+00 TO STA. 333+19.29

HAM-75-14.61

258
 708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000XS100_SB.dgn 2021-01-20 10:18:53 AM william.croxton ODOT\cadd_PDF.plt\cfig ODOTV8i_Pen-ME.tbl IBI_Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80	
	END WIDTH	SO. YDS.																								
33																										
184																										
32																										
112																										
296																										

SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.

HAM-75-12.60 (PID 82288) ORIGINAL HAM-75
 ** DENOTES ITEM CONSTRUCTED DURING HAM-75-12.60 (PID 82288)


END AREA	VOLUME		CALCULATED	CHECKED	J.D.H.
	CUT	FILL			
28	130*	30			
50	236*	64			
25	124*	39			
31	142*	43			
81	378*	107			

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND EMBANKMENT, AS PER PLAN

CROSS SECTIONS I-75 SB
 STA. 333+50 TO STA. 334+00

HAM-75-14.61


259
 708



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:54 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI_Group



END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
CUT	FILL	CUT	FILL		
61	133*	18	136*		
109	244*	35	250*		
56	130*	19	134*		
78	241*	46	249*		
187	485*	81	499*		


**CROSS SECTIONS I-75 SB
STA. 334+50 TO STA. 335+00**

HAM-75-14.61

260
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:55 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbi IBI_Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80		END AREA		VOLUME		CALCULATED	WLC	CHECKED	JDH
	END WIDTH	SO. YDS.	SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.																						CUT		FILL		CUT					



END AREA		VOLUME	
CUT	FILL	CUT	FILL
62	22	125*	139*
110	38	236*	256*
56	18	129*	137*
109	34	243*	253*
219	72	479*	509*


CROSS SECTIONS I-75 SB
STA. 335+50 TO STA. 336+00
HAM-75-14.61
261
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

15" TYPE B
ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:56 AM william.croxton ODOTcadd_PDF.plt c:\ib\Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80	
	END WIDTH	SO. YDS.																								



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
52	119*	20	152*		
108	225*	44	272*		
64	123*	27	141*		
117	230*	46	260*		
225	455*	90	532*		

CROSS SECTIONS I-75 SB
STA. 336+50 TO STA. 337+00

HAM-75-14.61

262
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE


SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.

HAM-75-12.60 (PID 82288) ORIGINAL HAM-75
** DENOTES ITEM CONSTRUCTED DURING HAM-75-12.60 (PID 82288)

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND EMBANKMENT, AS PER PLAN

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:57 AM william.croxton ODOTV8i_Pen-ME.tbi IBI_Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80	
	END WIDTH	SO. YDS.																								



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
78	113*	25	145*		
138	213*	44	267*		
70	117*	22	143*		
113	219*	39	274*		
251	432*	83	541*		


CROSS SECTIONS I-75 SB
STA. 337+50 TO STA. 338+00

HAM-75-14.61

263
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:58 AM william.croxton ODOT\8i_Pen-ME.tbi IBI_Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80	
	END WIDTH	SO. YDS.																								



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
84	23	140	47		
99*	148*	182*	273*		
67	27	135	49		
97*	146*	195*	270		
		275	96		
		377*	543*		

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

CROSS SECTIONS I-75 SB
STA. 338+50 TO STA. 339+00

HAM-75-14.61

264
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:18:59 AM william.croxton ODOTcadd_PDF.plt cfb ODOTV8i_Pen-ME.tbl IBI Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80	
	END WIDTH	SO. YDS.																								

SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.


END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
142	95*	21	150*	
127	97*	18	149*	
196	182*	38	275*	
293	251*	52	382*	

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND EMBANKMENT, AS PER PLAN

CROSS SECTIONS I-75 SB
STA. 339+50 TO STA. 339+69.29

HAM-75-14.61

265
708



END PARALLEL SPEED CHANGE LANE FOR RAMP A
 BEGIN 650' SPEED CHANGE LANE FOR RAMP A TAPER

J:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:19:00 AM william.croxtan\ ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80	
	END WIDTH	SO. YDS.																								

SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.


END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
CUT	FILL	CUT	FILL		
98	24	135*	150*		
198	47	223*	278*		
115	26	105*	150*		
147	27	114*	171*		
345	74	337*	449*		

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND EMBANKMENT, AS PER PLAN

CROSS SECTIONS I-75 SB
STA. 340+00 TO STA. 340+50

HAM-75-14.61

266
708




APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:19:01 AM william.croxton ODOTcodd_PDF.pltcfgr ODOTVBI_Pen-ME.tbl IBI Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80	
	END WIDTH	SO. YDS.																								



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
93	136*	29	150*		
185	250*	52	278*		
106	134*	27	150*		
189	250*	48	278*		
374	500*	100	556*		

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).


ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

CROSS SECTIONS I-75 SB
STA. 341+00 TO STA. 341+50

HAM-75-14.61

267
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:19:02 AM william.croxtan\ ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
134	30				
141*	147*				
227	61				
257*	273*				
111	35				
136*	147*				
201	57				
257*	275*				
106	26				
141*	150*				
185	51				
257*	278*				
613	169				
771*	826*				

CROSS SECTIONS I-75 SB
 STA. 342+00 TO STA. 343+00

HAM-75-14.61

268
 708

SEEDING
 END SO. WIDTH YDS.
 SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND EMBANKMENT, AS PER PLAN

D56, STA 342+40.95, 96.50' LT
 CB-5, GRATE ELEV 644.00
 30" (W) 637.59
 30" (E) 637.59
 6" UD (N) 641.50

STA 342+41.61, 10.78' RT
 (TO BE ABANDONED)
 EX. CB, GRATE ELEV 644.27
 30" W 636.68
 30" E 636.80
 12" NW 638.43

D57, STA 342+55.74,
 CB-5, GRATE ELEV 644.55
 30" (W) 636.19
 30" (E) 636.19
 6" UD (N) 640.00

EX 30" CONC (TO REMAIN)
 MASONRY COLLAR PER DM-1.1
 5'-30" TYPE C, 706.02 @ 1.23%
 SEE SHEET 451 FOR STORM DETAILS

MASONRY COLLAR PER DM-1.1
 10'-30" TYPE C, 706.02 @ 0.86%

MASONRY COLLAR PER DM-1.1

MASONRY COLLAR PER DM-1.1
 EX 30" CONC (TO REMAIN)
 10'-30" TYPE C, 706.02 @ 1%

END CONCRETE BARRIER, SINGLE SLOPE, TYPE D
 END PAVED GUTTER, TYPE 1-2


APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

CONST I-75 SB

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000XS100_SB.dgn 2021-01-20 10:19:03 AM william.croxton\ ODOTcadd_PDF.pltcfgr ODOTV8I_Pen-ME.tbl IBI Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80	
	END WIDTH	SO. YDS.																								



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
166	5	152*	152*	153*	
297	12	282*	282*	284*	
154	7	152*	152*	153*	
278	28	2732*	2732*	278*	
146	23	142*	142*	147*	
260	50	263*	263*	273*	
835	90	818*	818*	835*	

CROSS SECTIONS I-75 SB
STA. 343+50 TO STA. 344+50

HAM-75-14.61

269
708

SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.


* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND EMBANKMENT, AS PER PLAN

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000XS100_SB.dgn 2021-01-20 10:19:04 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl |BI_Group

SEEDING	160		140		120		100		80		60		40		20		0		20		40		60		80		END AREA		VOLUME		CALCULATED	CHECKED	JDH
	END WIDTH	SO. YDS.	SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.																						CUT		FILL						




END AREA	182		172		161		940	
	CUT	FILL	CUT	FILL	CUT	FILL	CUT	FILL
	153*	19	151*	15	151*	8	843*	67
	153*	328	153*	32	153*	284*	852*	270
	282*	328	280*	22	280*	284*	843*	708
	284*	309	284*	22	284*	284*	852*	708

**CROSS SECTIONS I-75 SB
STA. 345+00 TO STA. 346+00**

HAM-75-14.61


(270)
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:19:05 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8I_Pen-ME.tbl IBI Group



271
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:19:06 AM william.croxton\ ODOTcadd_PDF.plt cfig ODOTV81_Pen-ME.tbl IBI Group



CROSS SECTIONS I-75 SB
 STA. 347+50 TO STA. 349+00

HAM-75-14.61


CALCULATED WLC CHECKED JDH
 272
 708

[Hatched Box] APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

[Solid Box] ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 [Dashed Box] LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

CONST I-75 SB

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:19:07 AM william.croxton ODOTcadd_PDF.plt c:\odot\ib\Group



SEEDING		END AREA		VOLUME		CALCULATED	CHECKED	JDH
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL			
160	140	285	9	166*	167*	508	23	304*
140	120	263	15	162*	162*	446	33	297*
120	100	218	20	158*	159*	397	45	291*
100	80	210	28	156*	156*	369	59	288*
80	60					1720	160	1180*
60	40					1180*	1183*	

CROSS SECTIONS I-75 SB
STA. 349+50 TO STA. 351+00

HAM-75-14.61


273
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
LIMITS FOR EXCAVATION OF UNSUITABLE SUBGRADE

CONST I-75 SB

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:19:09 AM william.croxton ODOTcadd_PDF.plt c:\odotv81_Pen-ME.tbl IBI Group



CROSS SECTIONS I-75 SB
STA. 351+50 TO STA. 352+50

HAM-75-14.61


274
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75 SB

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:19:10 AM william.croxton ODOT\cadd_PDF\p1ctfg ODOTVBI_Pen-ME.tbl IBI Group




END STA.	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
355	199	1	388	2		
383	159	3	332	4		
411	77	16	277	18		
444	82	31	244	44		
472	87	39	212	65		
2065	1453	133			275	708

**CROSS SECTIONS I-75 SB
 STA. 353+00 TO STA. 355+00**

HAM-75-14.61


j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000\5100_SB.dgn 2021-01-20 10:19:11 AM william.croxton' ODOT\cadd_PDF\pltcfg ODOTV86_Pen-ME.tbl |BI Group



END STA	AREA		VOLUME	
	CUT	FILL	CUT	FILL
357+50	118	27	236	41
357+17.48	136	17	230	37
356+67.48	112	22	202	89
356+17.48	106	74	191	137
355+67.48	100	73	190	104
TOTAL	572	253	1049	408

CROSS SECTIONS I-75 SB
STA. 355+50 TO STA. 357+50
 CALCULATED WLC
 CHECKED JDH
HAM-75-14.61
 276
 708

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM\00000\roadway\sheets\00000X5100_SB.dgn 2021-01-20 10:19:12 AM william.croxton ODOTcadd_PDF.pltcfg ODOTV81_Pen-ME.tbl IBI Group




CROSS SECTIONS I-75 SB
STA. 358+00 TO STA. 358+82.52 (BK.)

HAM-75-14.61

277
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5\01_SB.dgn 2021-01-20 10:19:14 AM william.croxton' ODOTcadd_PDF.plt cfig ODOTV8i_Pen-ME.tbl IBI Group



END STA	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
359+00	100	150	189	250		
359+50	104	119	191	240		
360+00	84	156	185	287		
360+50	83	159	199	159		
361+00	82	167	175	302		
TOTAL	740	1079	740	1079	278	708


**CROSS SECTIONS I-75 SB
 STA. 359+00 (AH.) TO STA. 361+00**

HAM-75-14.61

STATION EQUATION:
 POT STA 358+82.52 @ CONST. I-75 SB (BK.) = POT STA. 359+00 @ CONST. I-75 (AH.)

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 @ CONST I-75

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000XS101_SB.dgn 2021-01-20 10:19:15 AM william.croxton' ODOTcadd_PDF_pltcfg ODOTV8i_Pen-ME.tbl IBI Group



**CROSS SECTIONS I-75 SB
 STA. 361+50 TO STA. 363+00**


HAM-75-14.61

CALCULATED WLC
 CHECKED JDH

279
 708

612 2052

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:16 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group




END STA.	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
365+50	70	884	109	1523		
365+00	47	760	81	1330		
364+50	40	676	71	1152		
364+00	36	568	131	1052		
363+50	105	568	187	953		
TOTAL			579	6010		

**CROSS SECTIONS I-75 SB
 STA. 363+50 TO STA. 365+50**

HAM-75-14.61

280
 708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:17 AM william.croxton' ODOTcadd_PDF_pltcfg ODOTV8i_Pen-ME.tbl IBI Group



END AREA	VOLUME	CALCULATED	CHECKED
894	1369		
897	1749		
58	821		
103	1406		
73	981		
133	1727		
767	4561		

CROSS SECTIONS I-75 SB
STA. 366+00 TO STA. 368+09.36


HAM-75-14.61

281
708

SEEDING 240 220 200 180 160 140 120 100 80 60 40 20 0
 END SO. SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.
 WIDTH YDS.

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM-00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:19 AM william.croxton' ODOTcadd_PDF.pltcfg ODOTV81_Pen-ME.tbl IBI Group




END AREA	VOLUME	CALCULATED	CHECKED		
				CUT	FILL
21	659				
168	912				
41	827				
86	767				
1057	6044				

**CROSS SECTIONS I-75 SB
 STA. 368+39.36 TO STA. 370+00**

HAM-75-14.61

282
 708

j:\pre-int\06-386_HAM-75_HAM\00000\roadway\sheets\00000\5101_SB.dgn 2021-01-20 10:19:20 AM william.croxton ODOTcodd_PDF.pltcfgr ODOTVBI_Pen-ME.tbl IBI Group




CROSS SECTIONS I-75 SB
STA. 370+50 TO STA. 372+00

HAM-75-14.61

283
708

STATION	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
372+00	238	304	336	622		
371+50	124	367	200	781		
371+00	92	476	88	967		
370+50	2	568	22	1137		
TOTAL	456	1715	646	3507		

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:21 AM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



**CROSS SECTIONS I-75 SB
 STA. 372+50 TO STA. 374+50**

HAM-75-14.61


284
 708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75

j:\pre-int\06-386_HAM-75_HAM\00000\roadway\sheet\00000X5101_SB.dgn 2021-01-20 10:19:23 AM william.croxton
 ODOT\cadd_PDF\p1ctfg ODOTV81_Pen-ME.tbl IBI Group




**CROSS SECTIONS I-75 SB
 STA. 376+50 TO STA. 378+00**

HAM-75-14.61

END AREA	VOLUME	CALCULATED	CHECKED	J.D.H.
109	153			
121	153			
137	130			
170	109			
150	87	286	708	
887	856			

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM-75\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:25 AM william.croxton ODOTcadd_PDF.pltcfg ODOTV81_Pen-ME.tbl IBI Group



END AREA	VOLUME	CALCULATED	CHECKED	J.D.H.
108	198			
108	182			
92	170			
104	158			
766	1270			

**CROSS SECTIONS I-75 SB
STA. 378+50 TO STA. 380+00**

HAM-75-14.61


287
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75

J:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:26 AM william.croxton ODOT\cadd_PDF.pltcfgr ODOTVBI_Pen-ME.tbl IBI Group




**CROSS SECTIONS I-75 SB
STA. 380+19.26 TO STA. 381+00**

HAM-75-14.61

288
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
CONST I-75

J:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:27 AM william.croxton ODOTcadd_PDF.pltcfg ODOTV81_Pen-ME.tbl IBI Group




**CROSS SECTIONS I-75 SB
STA. 381+50 TO STA. 383+00**

HAM-75-14.61

289
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
CONST I-75

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:28 AM william.croxton ODOTV81_Pen-ME.tbl IBI Group



**CROSS SECTIONS I-75 SB
 STA. 383+50 TO STA. 385+00**

HAM-75-14.61

290
 708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

STA 383+93.12, 196.93' LT
 96" NE 571.34'

STA 383+83.53, 195.33' LT
 96" NE 571.34'


RCP, TYPE B
 (2'-6" THICK)

MASONRY COLLAR PER DM-1.1
 SEE SHEET 679 FOR
 CULVERT DETAILS

REMOVE AND
 REUSE EX. CONDUIT

72" TYPE C

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:29 AM william.croxton ODOTcadd_PDF.pltcfg ODOTV8i_Pen-ME.tbl IBI Group




END STA	END AREA		VOLUME	
	CUT	FILL	CUT	FILL
387+00	107	183	198	349
386+50	106	193	328	494
386+00	248	340	431	620
385+50	217	329	383	608
TOTAL	1340	2071		

CALCULATED WLC CHECKED JDH
CROSS SECTIONS I-75 SB
STA. 385+50 TO STA. 387+00
HAM-75-14.61
 291 / 708

[Hatched Box] APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 [Grey Box] ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 @ CONST I-75

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:31 AM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



CROSS SECTIONS I-75 SB
STA. 387+50 TO STA. 388+50

HAM-75-14.61


292
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP


CONST I-75

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:32 AM william.croxton ODOTcadd_PDF.pltcfg ODOTV81_Pen-ME.tbl IBI Group



293
 708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:33 AM william.croxton




SEEDING		END AREA		VOLUME		CALCULATED	
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	WLC	CHECKED
93	517	76	206	143	344		
92	494	78	165	143	275		
86	494	76	132	148	215		
92	244	83	100	73	79		
1749	240	507	913				

**CROSS SECTIONS I-75 SB
STA. 390+50 TO STA. 392+00**

HAM-75-14.61

294
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:34 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



END AREA	VOLUME	CALCULATED	CHECKED	J.D.H.
188	73			
150	86			
144	64			
101	100			
164	284	295	708	
977	723			

**CROSS SECTIONS I-75 SB
 STA. 392+50 TO STA. 394+00**


HAM-75-14.61

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000XS101_SB.dgn 2021-01-20 10:19:35 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



END AREA	VOLUME	CALCULATED	CHECKED		
				CUT	FILL
234	48				
225	51	425	92		
214	61	407	104		
218	64	86	25		
296	100	1214	321		

**CROSS SECTIONS I-75 SB
STA. 394+39.26 TO STA. 395+50**

HAM-75-14.61


296
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000XS101_SB.dgn 2021-01-20 10:19:37 AM william.croxton ODOTcadd_PDF.pltcfg ODOTV81_Pen-ME.tbl IBI Group



END STA	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
397+50	127	106	269	172		
397+00	163	79	329	135		
396+50	192	66	390	106		
396+00	229	48	429	89		
0			1417	502		

**CROSS SECTIONS I-75 SB
STA. 396+00 TO STA. 397+50**

HAM-75-14.61


297
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:38 AM william.croxton ODOTcodd_PDF.pltcfg ODOTV81_Pen-ME.tbl IBI Group



END AREA	VOLUME	CALCULATED	CHECKED		
				CUT	FILL
203	106				
127	150	306	238		
95	154	206	282		
97	127	178	261		
208	216	898	997		


**CROSS SECTIONS I-75 SB
 STA. 398+00 TO STA. 399+50**

HAM-75-14.61

298
 708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:39 AM william.croxton ODOT\cadd_PDF.plt\cfg ODOTV81_Pen-ME.tbl IBI Group




**CROSS SECTIONS I-75 SB
STA. 400+00 TO STA. 401+50**

HAM-75-14.61

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 CONST I-75

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000XS101_SB.dgn 2021-01-20 10:19:40 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group




END AREA	VOLUME	CALCULATED	CHECKED		
				CUT	FILL
76	181				
81	169	146	325		
84	169	153	313		
97	184	168	327		
166	345	300	708		
633	1310				

**CROSS SECTIONS I-75 SB
STA. 402+00 TO STA. 403+50**

HAM-75-14.61

300
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:41 AM william.croxton' ODOTV86_PDF.pltcfg ODOTV86_Pen-ME.tbl IBI Group




**CROSS SECTIONS I-75 SB
STA. 404+00 TO STA. 405+50**

HAM-75-14.61

301
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:42 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



CROSS SECTIONS I-75 SB
STA. 406+00 TO STA. 407+50

HAM-75-14.61


302
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:44 AM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



**CROSS SECTIONS I-75 SB
STA. 408+00 TO STA. 408+50**

HAM-75-14.61


303
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:45 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group




SEEDING		END AREA		VOLUME		CALCULATED	
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	WLC	CHECKED
600	1528			178	250	304	708
240	240	73	109	148	188		
220	422	86	93	167	213		
200	75	94	136	178	250		
180	506			493	651		
160							
140							
120							
100							
80							
60							
40							
20							
0							


CROSS SECTIONS I-75 SB
STA. 409+00 TO STA. 410+00

HAM-75-14.61

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:46 AM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV81_Pen_ME.tbl IBI Group



j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:47 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75


SEEDING		END AREA		VOLUME		CALCULATED	
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	WLC	CHECKED
1367	0	91	168	173	307		JDH
467	596.3	95	163	168	300		
85	595.9	86	160	148	255		
81	595.5						
439	570						
		489	862				

CROSS SECTIONS I-75 SB
STA. 412+00 TO STA. 413+00

HAM-75-14.61

306
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:49 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
30	175			
81	325			
57	176			
119	315			
71	164			
125	309			
	325	949		

CROSS SECTIONS I-75 SB
STA. 415+00 TO STA. 416+00

HAM-75-14.61


308
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:51 AM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl |BI Group



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75


END STA	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
417+52	34	167	66	288		
417+00	40	160	68	308		
416+50	33	172	59	322		
TOTAL	107	499	193	918		

CROSS SECTIONS I-75 SB
STA. 416+50 TO STA. 417+52

HAM-75-14.61

309
708

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:52 AM william.croxton ODOTcadd_PDF.pltcfg ODOTV81_Pen-ME.tbl IBI Group




END STA	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
419+00	31	123	59	251		
418+50	32	148	62	281		
418+00	34	155	63	297		
417+50	34	165	4	16		
TOTAL	188	845			310	708

**CROSS SECTIONS I-75 SB
STA. 417+50 TO STA. 419+00**

HAM-75-14.61

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5101_SB.dgn 2021-01-20 10:19:53 AM william.croxton ODOTcadd_PDF.pltcfg ODOTV81_Pen-ME.tbl IBI Group



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST I-75


END STA	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
419+50	23	113	50	219		
420+00	22	84	42	183		
421+00						
TOTAL	92	402	92	402		

CROSS SECTIONS I-75 SB
STA. 419+50 TO STA. 420+50

HAM-75-14.61

311
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5102_NB.dgn 2021-01-20 11:23:38 AM william.croxton ODOT\cadd_PDF.plt c:\odot\8i_Pen-ME.tbl IBI Group




CROSS SECTIONS I-75 NB
STA. 338+50 TO STA. 340+00

HAM-75-14.61

313
708

CALCULATED
WLC
CHECKED
JDH

j:\pre-int\06\06-386_HAM-75\HAM-75\00000\roadway\sheets\00000X5102_NB.dgn 2021-01-20 11:23:38 AM william.croxton ODOT\cadd_PDF.plt c:\odot\8i_Pen-ME.tbl IBI Group




**CROSS SECTIONS I-75 NB
STA. 340+50 TO STA. 342+00**

HAM-75-14.61

314
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000\5102_NB.dgn 2021-01-20 11:23:38 AM william.croxton ODOT\cadd_PDF.plt\cfig ODOTV8i_Pen-ME.tbi IBI Group



NOTE TO CONTRACTOR:
BETWEEN THE STATION LIMITS OF STA. 342+50 TO STA. 349+50 (RIGHT SIDE), AFTER REMOVAL OF THE TEMPORARY MOT PAVEMENT, THE MOT GRADING CAN REMAIN AS SHOWN IN THE CROSS SECTIONS.


END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
185	37			
337	43			
178	9			
389	83			
76	80			
889	77			
243	3			
906	7			
1552	210			

**CROSS SECTIONS I-75 NB
STA. 342+50 TO STA. 344+00**

HAM-75-14.61

315
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5102_NB.dgn 2021-01-20 11:23:39 AM william.croxton\ODOT\cadd_PDF.plt\cfig ODOTV8i_Pen-ME.tbl IBI Group




END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
150	21	269	32	
140	13	279	25	
161	14	299	25	
161	13	321	47	
		1168	129	

**CROSS SECTIONS I-75 NB
 STA. 344+50 TO STA. 346+00**


HAM-75-14.61

316
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5102_NB.dgn 2021-01-20 11:23:39 AM william.croxton\ODOT\cadd_PDF.plt\cfig ODOTV8i_Pen-ME.tbl IBI Group



j:\pre-int\06\06-386_HAM-75\HAM-75\HAM\00000\roadway\sheets\00000X5102_NB.dgn 2021-01-20 11:23:40 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group




**CROSS SECTIONS I-75 NB
 STA. 348+00 TO STA. 349+50**

HAM-75-14.61

318
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5102_NB.dgn 2021-01-20 11:23:40 AM william.croxton ODOTV8i_Pen-ME.tbl IBI Group



SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.

CROSS SECTIONS I-75 NB
STA. 350+00 TO STA. 351+50

HAM-75-14.61

319
708

EARTHWORK LIMITS FOR I-75 SB

EARTHWORK LIMITS FOR I-75 NB

CONST. I-75

I-75
351+32.52

I-75 NB
655.24
351+50
654.23

I-75
350+82.52

I-75 NB
655.54
351+00
654.46

I-75
350+32.52

I-75 NB
655.77
350+50
654.68

I-75
349+82.52


I-75 NB
655.94
350+00
654.56

VARIES
MOT-TEMP PVMT
CONSTRUCTED PHASE 1
FROM STA 337+05

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM\00000\roadway\sheets\00000X5102_NB.dgn 2021-01-20 11:23:41 AM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.

MOT-TEMP PVMT CONSTRUCTED PRE-PHASE 1 TO STA 375+95

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).


**CROSS SECTIONS I-75 NB
STA. 352+00 TO STA. 354+00**

HAM-75-14.61

320
708

CALCULATED WLC
CHECKED JDH

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5102_NB.dgn 2021-01-20 11:23:41 AM william.croxton\ODOTcadd_PDF.plt\cfig_ODOTV81_Pen-ME.tbl IBI Group




**CROSS SECTIONS I-75 NB
 STA. 354+50 TO STA. 356+50**

HAM-75-14.61

CALCULATED WLC 321
 CHECKED JDH 708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5102_NB.dgn 2021-01-20 11:23:42 AM william.croxton ODOT\cadd_PDF_plt\cfig ODOTV8i_Pen-NE.tbl IBI Group




**CROSS SECTIONS I-75 NB
 STA. 356+71.18 TO STA. 358+50**

HAM-75-14.61

322
 708

j:\pre-int\06\06-386_HAM-75\HAM-75\roadway\sheets\000005\03_NB.dgn 2021-01-20 11:23:44 AM william.croxton\ODOT\cadd_PDF.plt\cfig_ODOTV8i_Pen-ME.tbi\BI_Group



SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.

END STA	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
359+00	115	73	759	803		
359+50	112	63	211	126		
360+00	102	114	199	164		
360+50	98	139	186	235		
361+00	78	161	163	278		
TOTAL						

**CROSS SECTIONS I-75 NB
STA. 359+00 (AH.) TO STA. 361+00**

HAM-75-14.61


324
708

STATION EQUATION:
 POT STA 359+17.48 @ CONST. I-75 NB (BK.) = POT STA. 359+00 @ CONST. I-75 (AH.)

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:45 AM william.croxton ODOTcadd_PDF.pltcf ODOTV8i_Pen-ME.tbl IBI Group



SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.

END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
0	371	5	628	
5	307	35	500	
32	232	91	394	
66	193	134	328	
265	1850			

**CROSS SECTIONS I-75 NB
STA. 361+50 TO STA. 363+00**


HAM-75-14.61

325
708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM-75\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:46 AM william.croxton ODOT\cadd_PDF.plt cfig ODOTV8i_Pen-ME.tbl IBI Group



SEE SHEETS 23 AND 450A-450D FOR BIORETENTION NOTES AND DETAILS.

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).


CROSS SECTIONS I-75 NB
STA. 363+50 TO STA. 366+50

HAM-75-14.61

326
708

CALCULATED
WLC
CHECKED
JDH

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:47 AM william.croxton ODOT\cadd_PDF.plt cfg ODOTV8i_Pen-ME.tbl IBI Group




CROSS SECTIONS I-75 NB
STA. 366+00 TO STA. 368+09.36

HAM-75-14.61

327
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:49 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END STA	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
109	114	884	213	1729		
112	115	983	188	1890		
113	87	1058	217	2233		
111	106	930	598	1334		
2373	1216	7186				

**CROSS SECTIONS I-75 NB
STA. 368+39.36 TO STA. 370+00**

HAM-75-14.61

328
708


* QUANTITIES FOR EXCAVATION OF SUBGRADE, 16 INCHES DEEP AND GRANULAR MATERIAL, TYPE B

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

END FORWARD APPROACH SLAB

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5\03_NB.dgn 2021-01-20 11:23:50 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI_Group




END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
CUT	FILL	CUT	FILL		
14	266	138	740		
134	533	239	1037		
124	586	232	1213		
126	724	223	1489		
		832	4479	329	708

**CROSS SECTIONS I-75 NB
STA. 370+50 TO STA. 372+00**

HAM-75-14.61

329
708

j:\pre-int\06\06-386_HAM-75\HAM-00000\roadway\sheets\00000XS103_NB.dgn 2021-01-20 11:23:51 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).


END STA.	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
374+50	129	100	245	180		
374+00	135	95	243	192		
373+50	127	112	203	252		
373+00	92	160	136	315		
372+50	54	180	63	413		
TOTAL	890	1352	890	1352	330	708

**CROSS SECTIONS I-75 NB
STA. 372+50 TO STA. 374+50**

HAM-75-14.61

330
708

J:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:52 AM william.croxton ODOTcadd_PDF.plt cfbg ODOTV8i_Pen-ME.tbl IBI Group



CROSS SECTIONS I-75 NB
STA. 375+00 TO STA. 376+27.58


HAM-75-14.61

331
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM-75\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:53 AM william.croxtan\ODOT\cadd_PDF.plt\cfig ODOTV8i_Pen-ME.tbl IBI Group




END STA	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
378+00	273	167	490	324		
377+50	256	182	410	319		
377+00	186	162	337	289		
376+50	177	150	107	121		
TOTAL	1344	1053	1344	1053	332	708

**CROSS SECTIONS I-75 NB
STA. 376+50 TO STA. 378+00**

HAM-75-14.61

332
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:54 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).


END STA	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
378+50	297	168	528	311		
379+00	261	178	517	321		
379+50	214	180	440	332		
380+00	123	232	313	382		
TOTAL	1798	1346	1798	1346		

**CROSS SECTIONS I-75 NB
STA. 378+50 TO STA. 380+00**

HAM-75-14.61

333
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:56 AM william.croxton ODOTcadd_PDF.plt c:\odot\ib\Group




CROSS SECTIONS I-75 NB
STA. 380+19.26 TO STA. 381+00

HAM-75-14.61

334
708

j:\pre-int\06\06-386_HAM-75\HAM-75\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:57 AM william.croxton\ODOT\cadd_PDF.plt\cfig_ODOTV8i_Pen-ME.tbl\BI_Group



END STA	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
381+50	146	208	276	384		
382+00	135	212	261	389		
382+50	315	436	417	600		
383+00	330	449	598	820		
TOTAL	1552	2193	1552	2193		

**CROSS SECTIONS I-75 NB
STA. 381+50 TO STA. 383+00**

HAM-75-14.61

335
708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP


APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

STA 381+35.18, 134.97' RT
(TO BE REMOVED)
EX. CB, GRATE ELEV 598.09'
12" S 593.82
12" E 593.82

STA 381+35.69, 166.95' RT
(TO BE REMOVED)
12" E 593.47

STA 381+36.22, 202.96' RT
(TO BE REMOVED)
12" W 580.42

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:58 AM william.croxton ODOT\cadd_PDF.plt cfig ODOTV8i_Pen-ME.tbl IBI Group



END STA	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
383+50	302	474	586	855		
384+00	242	466	504	871		
384+50	202	415	412	816		
385+00	190	310	363	672		
TOTAL	1865	3214	1865	3214		

**CROSS SECTIONS I-75 NB
STA. 383+50 TO STA. 385+00**


HAM-75-14.61

336
708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM-75\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:23:59 AM william.croxton ODOT\cadd_PDF.plt c:\odot\81_Pen-ME.tbl IBI Group



**CROSS SECTIONS I-75 NB
STA. 385+50 TO STA. 387+00**


HAM-75-14.61

337
708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM-75\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:00 AM william.croxton ODOT\cadd_PDF.plt\cfig ODOTV8i_Pen-ME.tbl IBI_Group




CROSS SECTIONS I-75 NB
STA. 387+50 TO STA. 388+50

HAM-75-14.61

338
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:01 AM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



CROSS SECTIONS I-75 NB
STA. 389+00 TO STA. 390+26.39

HAM-75-14.61

339
708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:02 AM william.croxton ODOT\cadd_PDF.plt cfig ODOTV8i_Pen-ME.tbl IBI Group




**CROSS SECTIONS I-75 NB
 STA. 390+50 TO STA. 392+00**

HAM-75-14.61

340
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:05 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END STA.	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
395+50	156	184	301	342		
395+00	169	185	310	345		
394+50	165	187	66	76		
394+39.26	164	191	232	284		
TOTAL	909	1047	909	1047	342	708

**CROSS SECTIONS I-75 NB
STA. 394+39.26 TO STA. 395+50**

HAM-75-14.61


342
708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

END 650' SPEED CHANGE LANE FOR RAMP E TAPER
BEGIN AUXILIARY LANE FOR MAINLINE

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:06 AM william.croxton\ODOT\cadd_PDF.plt\cfig_ODOT\8i_Pen-ME.tbl\BI_Group



ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).


END STA.	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
397+50	162	215	312	386		
397+00	174	201	316	373		
396+50	167	201	304	369		
396+00	161	197	294	353		
TOTAL	1226	1481	1226	1481		

**CROSS SECTIONS I-75 NB
 STA. 396+00 TO STA. 397+50**

HAM-75-14.61

343
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:07 AM william.croxton ODOT\cadd_PDF.plt\cfig ODOTV8i_Pen-ME.tbl IBI Group



**CROSS SECTIONS I-75 NB
STA. 398+00 TO STA. 399+50**


HAM-75-14.61

344
708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM-75\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:08 AM william.croxton ODOT\cadd_PDF.plt cfig ODOTV8i_Pen-ME.tbl IBI Group




END STA	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
401+50	180	223	309	438		
401+00	153	250	279	476		
400+50	148	264	284	499		
400+00	158	274	265	411		
TOTAL	1137	1824				

**CROSS SECTIONS I-75 NB
STA. 400+00 TO STA. 401+50**

HAM-75-14.61

345
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:09 AM william.croxtton\ODOTV8i_Pen-ME.tbl IBI Group



**CROSS SECTIONS I-75 NB
STA. 402+00 TO STA. 403+50**


HAM-75-14.61

346
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:11 AM william.croxton' ODOTV8i_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



NOTE TO CONTRACTOR:
 BETWEEN THE STATION LIMITS OF STA. 404+50 TO STA. 405+00 (RIGHT SIDE), AFTER REMOVAL OF THE TEMPORARY MOT PAVEMENT, THE MOT GRADING CAN REMAIN AS SHOWN IN THE CROSS SECTIONS.

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).


END STA.	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
405+50	213	356				
405+00	187	365				
404+50	186	377				
404+00	170	344				
TOTAL	1373	2617				

**CROSS SECTIONS I-75 NB
 STA. 404+00 TO STA. 405+50**

HAM-75-14.61

347
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5\03_NB.dgn 2021-01-20 11:24:12 AM william.croxton ODOT\cadd_PDF.plt\cfig ODOTV81_Pen-ME.tbl IBI Group




END STA.	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
407+50	209	371				
407+00	213	371	391	688		
406+50	211	358	393	675		
406+00	214	352	394	658		
TOTAL			1574	2677		

**CROSS SECTIONS I-75 NB
 STA. 406+00 TO STA. 407+50**

HAM-75-14.61

348
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:13 AM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



NOTE TO CONTRACTOR:
 BETWEEN THE STATION LIMITS OF STA. 404+50 TO STA. 412+00 (RIGHT SIDE), AFTER REMOVAL OF THE TEMPORARY MOT PAVEMENT, THE MOT GRADING CAN REMAIN AS SHOWN IN THE CROSS SECTIONS.

END AUXILIARY LANE FOR MAINLINE
 BEGIN SPEED CHANGE LANE FOR RAMP D

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).


END STA.	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
408+00	212	383	390	699		
408+22.55	213	386	178	322		
408+50	241	398	231	399		
TOTAL	799	1420	799	1420	349	708

**CROSS SECTIONS I-75 NB
 STA. 408+00 TO STA. 408+50**

HAM-75-14.61

349
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheet\00000X5103_NB.dgn 2021-01-20 11:24:14 AM william.croxton



NOTE TO CONTRACTOR:
 BETWEEN THE STATION LIMITS OF STA. 404+50 TO STA. 412+00 (RIGHT SIDE), AFTER REMOVAL OF THE TEMPORARY MOT PAVEMENT, THE MOT GRADING CAN REMAIN AS SHOWN IN THE CROSS SECTIONS.

EARTHWORK LIMITS FOR I-75 SB
 EARTHWORK LIMITS FOR I-75 NB

25' VEGETATED FILTER STRIP BMP
 7:1

592.7
 I-75
 410+00

CONST. I-75 NB

I-75 NB
 602.07
 410+00
 600.94

17.1'
 11.1'
 25.4'
 590.3
 MOT 2.1:1

EX GAS
 EX 30" WATER

208 274

398 484

EARTHWORK LIMITS FOR I-75 SB
 EARTHWORK LIMITS FOR I-75 NB

D18, STA 409+61.00, @ CB-4, GRATE ELEV 592.40
 18" (S) 589.55
 6" UD (W,E) 590.55
 STA 409+60.66, 2.34' RT (TO BE REMOVED)
 EX. CB, GRATE ELEV 591.67'
 15" S 589.17

25' VEGETATED FILTER STRIP BMP
 7:1

592.2
 I-75
 409+50

CONST. I-75 NB

I-75 NB
 601.57
 409+50
 600.83

EX 60" CULVERT (TO REMAIN)

17.6'
 10.2'
 24.9'
 590.7
 MOT 2.1:1

STA 409+14.89, 185.70' RT
 60" NW 584.46

EX GAS
 EX 30" WATER

D-19 RCP-TYPE B (12'x10.5'x2.5')

221 248

478 570

EARTHWORK LIMITS FOR I-75 SB
 EARTHWORK LIMITS FOR I-75 NB

25' VEGETATED FILTER STRIP BMP
 8:1

592.8
 I-75
 409+00

CONST. I-75 NB

I-75 NB
 601.07
 409+00
 600.17

10.6'
 10.0'
 12.7'
 590.4
 8.0'
 2.5:1
 11.4'
 16.1'
 585.0
 2:1
 583.0
 MOT 2:1

EX GAS
 EX 30" WATER

295 367

497 709

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).


END STA.	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
410+00	208	274				
409+50	221	248				
409+00	295	367				
TOTAL			1373	1763	350	708

CROSS SECTIONS I-75 NB
 STA. 409+00 TO STA. 410+00

HAM-75-14.61

350
 708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:15 AM william.croxton ODOTcadd_PDF.plt cfig ODOTV81_Pen-ME.tbl IBI Group




**CROSS SECTIONS I-75 NB
 STA. 410+50 TO STA. 411+50**

HAM-75-14.61

351
 708

CALCULATED
 WLC
 CHECKED
 JDH

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:16 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



NOTE TO CONTRACTOR:
 BETWEEN THE STATION LIMITS OF STA. 404+50 TO STA. 412+00 (RIGHT SIDE), AFTER REMOVAL OF THE TEMPORARY MOT PAVEMENT, THE MOT GRADING CAN REMAIN AS SHOWN IN THE CROSS SECTIONS.

**END FULL DEPTH PAVEMENT I-75 NB
 BEGIN FULL DEPTH PAVEMENT WIDENING, LT./RT.
 BEGIN PLANING & RESURFACING, (1" MIN, 3.25" MAX) WITH WEDGE COURSE (VAR. DEPTH)**

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).


END STA.	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
413+00	138	322	253	598		
412+50	135	323	257	578		
412+00	142	301	277	496		
TOTAL	787	1672				

**CROSS SECTIONS I-75 NB
 STA. 412+00 TO STA. 413+00**

HAM-75-14.61

352
708

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM-75\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:17 AM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group




END STA	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
414+50	148	345	263	635		
414+00	135	340	256	631		
413+50	141	341	259	614		
TOTAL	424	1026	778	1880		

**CROSS SECTIONS I-75 NB
STA. 413+50 TO STA. 414+50**

HAM-75-14.61

353
708

j:\pre-int\06\06-386_HAM-75\HAM-75\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:19 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV81_Pen-ME.tbl IBI Group



END AREA	VOLUME	CALCULATED		CHECKED
		CUT	FILL	
55	235			
85	253			
148	320			
275	616			
621	1599			

**CROSS SECTIONS I-75 NB
 STA. 415+00 TO STA. 416+00**


HAM-75-14.61

354
 708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75\HAM-75\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:20 AM william.croxton ODOTcadd_PDF.plt c:\odotv8i_Pen-ME.tbl IBI_Group



END STA.	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
417+52	61	235	70	411		
417+00	18	232	72	445		
416+50	59	248	106	448		
TOTAL	138	715	248	1304		

CROSS SECTIONS I-75 NB
STA. 416+50 TO STA. 417+47.52


HAM-75-14.61

355
708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:21 AM william.croxtton' ODOTV81_Pen-ME.tbl IBI Group



END STA	AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
417+50	44	233	5	22	356	708
418+00	47	202	85	403		
418+50	33	186	75	360		
419+00	32	161	61	322		
TOTAL	156	702	225	1087		

CROSS SECTIONS I-75 NB
STA. 417+50 TO STA. 419+00


HAM-75-14.61

356
708

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5103_NB.dgn 2021-01-20 11:24:22 AM william.croxton ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbi IBI_Group



SEEDING	
END WIDTH	SO. YDS.

END AREA	VOLUME	CALCULATED WLC	CHECKED JDH
19	93		
46	200		
30	123		
58	263		
104	463		


CROSS SECTIONS I-75 NB
STA. 419+50 TO STA. 420+50

HAM-75-14.61

357
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5200.dgn 2021-01-18 3:12:26 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END STA	AREA		VOLUME	
	CUT	FILL	CUT	FILL
369+50	241	5	317	10
369+00	101	5	282	7
368+34.09	130	0		
TOTAL	472	10	600	17

**CROSS SECTIONS RAMP C
STA. 368+34.09 TO STA. 369+50**

HAM-75-14.61


CALCULATED WLC
CHECKED JDH

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST RAMP C

358
708




**CROSS SECTIONS RAMP C
STA. 370+00 TO STA. 371+00**


HAM-75-14.61

359
708

SEEDING
 END WIDTH SO. YDS.
 SEE I-75 SB CROSS SECTIONS FOR CONTINUATION OF GRADING
 615
610
605
600
595
 52
610
605
600
595
 80
610
605
600
595
 416
 1049



j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5200.dgn 2021-01-18 3:12:26 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



**CROSS SECTIONS RAMP C
STA. 371+50 TO STA. 372+50**

HAM-75-14.61

360
708

SEEDING
END WIDTH SO. YDS.
SEE I-75 SB CROSS SECTIONS FOR CONTINUATION OF GRADING

50 40 30 20 10 0 10 20 30 40 50 60 70

610 605 600 595 590

62 60 344 278 38 228

EX ELEC

EX SANITARY

EX LA

3:1

4:1

3.9:1

593.3

595.0

598.8

597.5

597.4

599.1

18" TYPE C

18" (N) 593.90

EARTHWORK LIMITS FOR RAMP C

EARTHWORK LIMITS FOR I-75 SB

602.16
372+50
599.29

602.47
372+00
602.88

602.92
371+50
606.67

BEGIN 50' SHOULDER TAPER (RT.)
BEGIN 50' PAVEMENT TAPER (LT. & RT.)


END 50' SHOULDER TAPER (RT.)
END 50' PAVEMENT TAPER (LT. & RT.)

CONST RAMP C

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5200.dgn 2021-01-18 3:12:27 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group




SEEDING		END AREA		VOLUME		CALCULATED	
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	WLC	CHECKED
60	60	289	249	588	386		JDH
60	60	346	167	692	265		
60	60			1280	651		

CROSS SECTIONS RAMP C
STA. 373+00 TO STA. 373+50
HAM-75-14.61
 361
 708

[Hatched Box] APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 [Shaded Box] ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 CONST RAMP C

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5200.dgn 2021-01-18 3:12:27 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



**CROSS SECTIONS RAMP C
STA. 374+00 TO STA. 374+50**

HAM-75-14.61

362
708

SEEDING
END WIDTH SO. YDS.
SEE I-75 SB CROSS SECTIONS FOR CONTINUATION OF GRADING

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST RAMP C

D-22, HW-2.1 OR 2.2
E = 586.50
RIPRAP CUTOFF WALL
PER DM-1.1

EX SANITARY

18" TYPE C

72" TYPE C

EARTHWORK LIMITS FOR RAMP C

EARTHWORK LIMITS FOR I-75 SB

EARTHWORK LIMITS FOR RAMP C

EARTHWORK LIMITS FOR I-75 SB

GRADE TO DRAIN

72" TYPE C

18" TYPE C

602.32
374+50
591.18

602.11
374+00
593.07

3.5:1

2:1

4:1

3.8:1

TMP

LA

EX LA

610

605

600

595

590

585

394

610

605

600

595

590

585

384

610

605

600

595

590

585

778

60

50

40

30

20

10

0

10

20

30

40

50

60

60

50

40

30

20

10

0

10

20

30

40


50

60

894

1286

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5200.dgn 2021-01-18 3:12:28 PM william.croxton" ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tb1 B1 Group



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 CONST RAMP C
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP


END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
76	534			
163	1019			
99	566			
205	1055			
368	2074			

**CROSS SECTIONS RAMP C
 STA. 376+00 TO STA. 376+50**

HAM-75-14.61

364
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5200.dgn 2021-01-18 3:12:28 PM william.croxton" ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tb1 B1 Group




END AREA		VOLUME		CALCULATED W/LC	CHECKED JDH
CUT	FILL	CUT	FILL		
44	589	96	1125		
59	626	125	1075		
		221	2200		

**CROSS SECTIONS RAMP C
STA. 377+00 TO STA. 377+50**

HAM-75-14.61

365
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5200.dgn 2021-01-18 3:12:28 PM william.croxton\ODOTcadd_PDF.pltcfgr ODOTV86_Pen-ME.tbl IBI Group




END AREA	VOLUME	CALCULATED	CHECKED
23	589		
42	1094		
22	592		
62	1094		
104	2188		

**CROSS SECTIONS RAMP C
STA. 378+00 TO STA. 378+50**

HAM-75-14.61

366
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
CONST RAMP C
ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST RAMP C


END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
15	622			
33	1130			
20	598			
40	1100			
73	2230			

**CROSS SECTIONS RAMP C
STA. 379+00 TO STA. 379+50**

HAM-75-14.61

367
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5200.dgn 2021-01-18 3:12:29 PM william.croxton" ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group




CROSS SECTIONS RAMP C
STA. 380+00 TO STA. 380+22.92

HAM-75-14.61

368
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5200.dgn 2021-01-18 3:12:29 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5300.dgn 2021-01-18 3:12:38 PM william.croxton\ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



**CROSS SECTIONS RAMP A
STA. 352+30.24 TO STA. 353+39.29**

HAM-75-14.61

369
708

SEEDING
END WIDTH SO. YDS.

SEE I-75 SB CROSS SECTIONS FOR CONTINUATION OF GRADING

EARTHWORK LIMITS FOR RAMP A | EARTHWORK LIMITS FOR I-75 SB

MOT 3.2:1

MOT 2.8:1

MOT 3:1

MOT 3.4:1

MOT-TEMP PVMT
CONSTRUCTED PHASE 1
TO STA 367+46


END RAMP A
BEGIN CHANGE LANE FOR RAMP A
BEGIN FULL DEPTH PAVEMENT
BEGIN EARTHWORK & SEEDING

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST RAMP A

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5300.dgn 2021-01-18 3:12:38 PM william.croxton\ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST RAMP A


STATION	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
355+00	23	23	47	46		
354+50	27	26	46	46		
354+00	22	23	40	36		
353+50	21	15	9	5		
TOTAL			142	133		

CROSS SECTIONS RAMP A
STA. 353+50 TO STA. 355+00

HAM-75-14.61

370
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5300.dgn 2021-01-18 3:12:38 PM william.croxton'



SEEDING	
END WIDTH	SO. YDS.
60	60
50	50
40	40
30	30
20	20
10	10
0	0
10	10
20	20
30	30
40	40
50	50
60	60

END AREA		VOLUME	
CUT	FILL	CUT	FILL
56	58	102	100
54	49	90	100
43	58	79	98
42	47	61	65
		332	363

CROSS SECTIONS RAMP A
STA. 355+50 TO STA. 357+00

HAM-75-14.61


371
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST RAMP A

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5300.dgn 2021-01-18 3:12:39 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group




END AREA	VOLUME	CALCULATED	CHECKED		
				CUT	FILL
56	36				
78	40	125	71		
72	48	139	82		
68	55	130	96		
68	55	115	105		
		509	354		

**CROSS SECTIONS RAMP A
STA. 357+50 TO STA. 359+00**

HAM-75-14.61

372
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5300.dgn 2021-01-18 3:12:39 PM william.croxton' ODOTcadd_PDF.pltcfg ODOTV8i_Pen-ME.tbl IBI Group



SEEDING
END WIDTH SO. YDS.
60
50
40
30
20
10
0
10
20
30
40
50
60

SEEDING		END AREA		VOLUME		CALCULATED	
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	WLC	CHECKED
60	49	107	22	107	22		
60	277	97	23	189	42		
60	289	84	28	168	48		
60	300	87	33	159	57		
60	306	87	33	133	64		
		649	211				

CROSS SECTIONS RAMP A
STA. 359+50 TO STA. 361+00

HAM-75-14.61


373
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST RAMP A

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5300.dgn 2021-01-18 3:12:39 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



**CROSS SECTIONS RAMP A
STA. 361+50 TO STA. 363+00**

HAM-75-14.61

374
708


APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST RAMP A

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5300.dgn 2021-01-18 3:12:40 PM william.croxton'

SEEDING	
END WIDTH	SO. YDS.
60	71
60	63
60	54
60	55
60	300

SEE I-75 SB CROSS SECTIONS FOR CONTINUATION OF GRADING




APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 CONST RAMP A

END AREA	VOLUME	CUT		FILL	
		CUT	FILL	CUT	FILL
245	7				
420	14				
208	8				
348	15				
167	8				
322	17				
180	10				
318	22				
1408	68				

CROSS SECTIONS RAMP A
 STA. 363+50 TO STA. 365+00
 HAM-75-14.61
 CALCULATED WLC
 CHECKED JDH
 375
 708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5300.dgn 2021-01-18 3:12:40 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV86_Pen-ME.tbl IBI Group




CROSS SECTIONS RAMP A
STA. 365+50 TO STA. 367+51.17

HAM-75-14.61

376
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5400.dgn 2021-01-18 3:12:52 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



**CROSS SECTIONS RAMP G
STA. 356+70.22 TO STA. 357+50**


HAM-75-14.61

CALCULATED WLC
CHECKED JDH

**END SPEED CHANGE LANE FOR RAMP G
BEGIN RAMP G
BEGIN FULL DEPTH PAVEMENT
BEGIN EARTHWORK & SEEDING**

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
CONST RAMP G
ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

j:\pre-int\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5400.dgn 2021-01-18 3:12:52 PM william.croxton' ODOT\cadd_PDF_plt\cfig ODOTV86_Pen-ME.tbl IBI Group



END AREA	VOLUME	CALCULATED	CHECKED		
				CUT	FILL
3	366				
13	599				
16	451				
7	207				
18	340				
47	1390				

**CROSS SECTIONS RAMP G
STA. 358+00 TO STA. 359+00**

HAM-75-14.61


378
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST RAMP G

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000XS400.dgn 2021-01-18 3:12:52 PM william.croxton' ODOTcadd_PDF_pltcfgr ODOTV86_Pen-ME.tbl IBI Group



SEEDING
END SO.
WIDTH YDS.
79
434
76
411
845

SEE I-75 NB CROSS SECTIONS FOR CONTINUATION OF GRADING

50 40 30 20 10 0 10 20 30 40 50 60 70

645 645
640 640
635 635
630 630
625 625
620 620
645 645
640 640
635 635
630 630
625 625
620 620

EARTHWORK LIMITS FOR I-75 NB EARTHWORK LIMITS FOR RAMP G

4:1 4:1 16:1 16:1

633.6 636.5

634.84
360+00
626.47

637.09
359+50
629.15

CONST RAMP G

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP


END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
CUT	FILL	CUT	FILL		
3	415	5	762		
2	407	5	716		
		10	1478		

CROSS SECTIONS RAMP G
STA. 359+50 TO STA. 360+00

HAM-75-14.61

379
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000XS400.dgn 2021-01-18 3:12:52 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV86_Pen-ME.tbl IBI Group



SEEDING	50		40		30		20		10		0		10		20		30		40		50		60		70	
	END WIDTH	SO. YDS.	SEE I-75 NB CROSS SECTIONS FOR CONTINUATION OF GRADING																							

END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
21		358		
4		397		
4		429		
39		2247		

**CROSS SECTIONS RAMP G
STA. 360+50 TO STA. 361+50**

HAM-75-14.61

380
708


APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
CONST RAMP G
ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000XS400.dgn 2021-01-18 3:12:53 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV86_Pen-ME.tbl IBI Group

SEEDING	
END WIDTH	SO. YDS.
73	60
84	50
450	40
77	30
444	20
1332	10
	0
	10
	20
	30
	40
	50
	60

SEE 1-75 NB CROSS SECTIONS FOR CONTINUATION OF GRADING

APPROXIMATE LIMITS FOR REMOVAL OF EXISTING CONCRETE PAVEMENT
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 16 INCHES DEEP



APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

END AREA	VOLUME	CALCULATED	CHECKED		
				CUT	FILL
128	207				
188	385				
74	208				
114	396				
49	219				
84	425				
386	1206				


**CROSS SECTIONS RAMP G
 STA. 363+50 TO STA. 364+50**

HAM-75-14.61

382
708

CONST RAMP G

j:\pre-int\06-386_HAM-75\HAM\00000\roadway\sheets\00000XS400.dgn 2021-01-18 3:12:53 PM william.croxton' ODOTcadd_PDF_pltcfgr ODOTV86_Pen-ME.tbl IBI Group



SEEDING	70		60		50		40		30		20		10		0		10		20		30		40		50	
	END WIDTH	SO. YDS.																								
0																										
183																										
64																										
345																										
58																										
356																										
69																										
395																										
1279																										

END CUT	AREA FILL	VOLUME		CALCULATED WLC	CHECKED JDH
		CUT	FILL		
83	0	286	12		
133	9	161	53		
40	48	123	202		
92	170	204	350		
		774	617		

**CROSS SECTIONS RAMP G
STA. 365+00 TO STA. 366+71.35**

HAM-75-14.61

383
708

SEE I-75 NB CROSS SECTIONS FOR CONTINUATION OF GRADING

SEE INTERSECTION DETAIL SHEET

(TO REMAIN)
STA 365+06.57, 66.48' LT
EX HW, GRATE ELEV 602.26'
30" E 602.26

D-29
RCP-TYPE C
(8'x5'x1.5')

EX 30" CONC
(TO REMAIN)

STA. 365+18.04, 35.08' RT.
MASONRY COLLAR
PER DM-1.1

(TO BE REMOVED)
STA 365+18.04, 35.08' RT
EX HW, GRATE ELEV 602.71'
30" W 602.71

15'-30" TYPE B, 706.02
@ 0.44%


STA. 365+19.61, 49.99' RT.
D-30 HW-2.2
E=602.78

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

CONST RAMP G

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5500.dgn 2021-01-20 10:24:01 AM william.croxton" ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI_Group



END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
4		46		
		10		72
6		31		
		346		62
169		0		
		356		134

CROSS SECTIONS RAMP E
STA. 366+93.35 TO STA. 368+50

HAM-75-14.61

384
708


SEEDING
 END SO. WIDTH YDS.
 SEE I-75 NB CROSS SECTIONS FOR CONTINUATION OF GRADING

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

BEGIN RAMP E
BEGIN FULL DEPTH PAVEMENT
BEGIN EARTHWORK & SEEDING

CONST RAMP E



SEEDING
END SO.
WIDTH YDS.
SEE 1-75 NB CROSS SECTIONS
FOR CONTINUATION OF GRADING

END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
15	30			
24	64			
14	75			
5	41			
9	81			
47	220			

**CROSS SECTIONS RAMP E
STA. 369+00 TO STA. 370+00**


HAM-75-14.61

385
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5500.dgn 2021-01-20 10:24:01 AM william.croxton" ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI_Group

CONST RAMP E



SEEDING
END WIDTH SO. YDS.

60 50 40 30 20 10 0 10 20 30 40 50 60

SEE I-75 NB CROSS SECTIONS FOR CONTINUATION OF GRADING

66 605 602.3 4:1 607.91 372+00 607.28 601.7 3:1 600 610 EX LA

54 605 600.7 4:1 607.51 371+50 606.86 599.6 600 610

59 605 600 4:1 607.11 371+00 606.41 599.4 600 610

51 605 600 4:1 606.71 370+50 606.14 601.5 600 610

1217 60 50 40 30 20 10 0 10 20 30 40 50 60

END AREA	VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL		
42	53	54	111	
16	66	30	103	
16	45	34	76	
20	37	33	63	
		151	353	

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP


CONST RAMP E

**CROSS SECTIONS RAMP E
STA. 370+50 TO STA. 372+00**

HAM-75-14.61

386
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5500.dgn 2021-01-20 10:24:01 AM william.croston ODOT\cadd_PDF.plt cfg ODOTV8i_Pen-ME.tbl IBI Group



j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5500.dgn 2021-01-20 10:24:02 AM william.croxton" ODOTV86_Pen-ME.tbl IBI Group

SEEDING	
END WIDTH	SO. YDS.
60	50
60	47
60	46
60	55
60	339
1156	


END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
CUT	FILL	CUT	FILL		
24	31	58	56		
38	29	63	61		
29	36	67	72		
43	41	79	88		
		267	277		

**CROSS SECTIONS RAMP E
 STA. 372+50 TO STA. 374+00**

HAM-75-14.61

387
 708

SEE I-75 NB CROSS SECTIONS FOR CONTINUATION OF GRADING
 APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP
 CONST RAMP E



SEEDING
END WIDTH SO. YDS.

SEE I-75 NB CROSS SECTIONS FOR CONTINUATION OF GRADING

EARTHWORK LIMITS FOR I-75 NB | EARTHWORK LIMITS FOR RAMP E

I-75 NB

608.77
375+00
608.04

608.99
374+50
608.24

609.05
374+19.26
608.16

BEGIN 600' OUTSIDE SPEED CHANGE LANE FOR RAMP E TAPER

CONST RAMP E

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

ITEM 206 - CEMENT STABILIZED SUBGRADE, 14 INCHES DEEP

END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
CUT	FILL	CUT	FILL		
55	44	93	79		
45	41	40	42		
24	32	18	23		
		151	144		


CROSS SECTIONS RAMP E
STA. 374+19.26 TO STA. 375+00

HAM-75-14.61

388
708

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5500.dgn 2021-01-20 10:24:02 AM william.croxton" ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group

j:\pre-int\06\06-386_HAM-75\HAM-75\HAM\00000\roadway\sheets\00000X5500.dgn 2021-01-20 10:24:02 AM william.croxton" ODOTV86_Pen-ME.tbl IBI Group




END AREA	VOLUME	CALCULATED	
		CUT	FILL
32	33		
22	28		
45	34		
93	73		
186	165		

CROSS SECTIONS RAMP E
STA. 375+50 TO STA. 376+29.48

HAM-75-14.61

389
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:19 PM william.croxton ODOT\oad_PDF.pltcf ODOTV8i_Pen-ME.tbi IBI_Group




END AREA	VOLUME		CALCULATED	CHECKED
	CUT	FILL		
9 9*	5 9*	16 17*	13 17*	
8 9*	9 9*	13 13*	10 13*	
9 8*	4 8*			
		29 30*	23 30*	

**CROSS SECTIONS - SHARON ROAD
STA. 9+00 TO STA. 10+00**

HAM-75-14.61

390
708

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:20 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED	CHECKED
	CUT	FILL		
101	59*	13	59*	
58	49*	12	49*	
40	27*	2	27*	
166	120*	26	120*	

CROSS SECTIONS - SHARON ROAD
STA. 10+50 TO STA. 11+00

HAM-75-14.61


391
708

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND GRANULAR MATERIAL, TYPE C

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:20 PM william.croxton' ODOTcadd_PDF.plt cfig ODOTV8i_Pen-ME.tbl IBI Group




END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
177	3	80*	177	3	80*
324	9	143*	324	9	143*
172	6	74*	172	6	74*
145	9	67*	145	9	67*
141	12	70*	141	12	70*
113	12	60*	113	12	60*
582	30	270*	582	30	270*

CROSS SECTIONS - SHARON ROAD
 STA. 11+25 TO STA. 12+00
 HAM-75-14.61
 392
 708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL). LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:21 PM william.croxton ODOTcadd_PDF.pltcf ODOTV8i_Pen-ME.tbl IBI_Group



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
394	4	94*	681	7	167*
341	3	86*	242	3	63*
310	3	83*	271	4	91*
1194	14	321*	393	708	

**CROSS SECTIONS - SHARON ROAD
STA. 12+30 TO STA. 13+00**

HAM-75-14.61


393
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

BEGIN CROWN TRANSITION
END 470' TAPER FOR WB LANES

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:21 PM william.croxton\ ODOT\cadd_PDF_plt\cfdg ODOTV8i_Pen-ME.tbi IBI_Group



SEEDING		END AREA		VOLUME		CALCULATED	CHECKED
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	WLC	JDH
130	120	93	112	100	55		
110	100	108*	110*	101*	102*		
90	80						
70	60						
50	40						
30	20						
10	0						
10	20						
30	40						
50	60						
70	80						
90	100						
110	120						
139		123	5	109*	109*		
21							
139				317	8		
		195*	195*				
28		219	3	101*	101*		
206				568	7		
		181*	181*				
456		985	70	477*	478*		


**CROSS SECTIONS - SHARON ROAD
STA. 13+50 TO STA. 14+25**

HAM-75-14.61

394
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:22 PM william.croxton\ ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
81 96*	181 98*	100 130*	280	139*	
68 99*	238 110*	36 52*	120	58*	
70 98*	222 110*	76 96*	155	102*	
		212 278*	555	299*	

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND GRANULAR MATERIAL, TYPE C

**CROSS SECTIONS - SHARON ROAD
STA. 14+50 TO STA. 15+00**


HAM-75-14.61

395
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:22 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END STA.	AREA		VOLUME		CALCULATED	CHECKED	J.D.H.
	CUT	FILL	CUT	FILL			
101	95*	8	172	27			
95*		95*	171*	171*			
84	89*	21	111	101			
89*		89*	121*	122*			
82	92*	130	43	81			
92*		93*	49*	50*			
			326	209			
			341*	343*			

**CROSS SECTIONS - SHARON ROAD
STA. 15+14 TO STA. 16+00**

HAM-75-14.61


396
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

BEGIN 50' TAPER FOR RIGHT TURN LANE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:23 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
89	63*	9	63*		
132	113*	13	113*		
53	58*	4	58*		
93	101*	4	101*		
47	51*	0	51*		
138	136*	8	136*		
363	350*	25	350*		

**CROSS SECTIONS - SHARON ROAD
STA. 16+50 TO STA. 17+50**


HAM-75-14.61

397
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

J:\pre-int\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:23 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED	CHECKED	
	CUT	FILL			WLC
134	63*	2	254	4	117*
140	63*	2	212	4	117*
88	62*	2	164	11	117*
630	349*	19	351*		

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND GRANULAR MATERIAL, TYPE C

CROSS SECTIONS - SHARON ROAD
STA. 18+00 TO STA. 19+00


HAM-75-14.61

398
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:24 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
130 63*	2 63*		236 117*	4 117*	
124 63*	2 63*		229 117*	4 117*	
123 63*	2 63*		238 117*	4 117*	
			703 351*	12 351*	

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND GRANULAR MATERIAL, TYPE C

CROSS SECTIONS - SHARON ROAD
STA. 19+50 TO STA. 20+50


HAM-75-14.61

399
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:25 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV86_Pen-ME.tbl IBI Group



SEEDING		END AREA		VOLUME		CALCULATED	CHECKED
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	WLC	JDH
35		62	117	63*	63*		
98		105	2	117*	63*		
0		135	2	117*	63*		
98		624	119	351*	351*		

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND GRANULAR MATERIAL, TYPE C


**CROSS SECTIONS - SHARON ROAD
STA. 21+00 TO STA. 22+00**

HAM-75-14.61

400
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL). LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:25 PM william.croxton\ ODOT\cadd_PDF.plt\cfig ODOTV8i_Pen-ME.tbl IBI Group



STATION	END AREA		VOLUME		CALCULATED WLC	CHECKED JDH
	CUT	FILL	CUT	FILL		
23+50	42	0	53*	53*	93	27
23+00	58	29	58*	58*	110	70
22+50	60	46	63*	63*	113	151
TOTAL	316	248	333*	333*		


CROSS SECTIONS - SHARON ROAD
STA. 22+50 TO STA. 23+50

HAM-75-14.61

401
 708

[Hatched Area] APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 [Dashed Line] LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:26 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



SEEDING		END AREA		VOLUME		CALCULATED	
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	WLC	CHECKED
35		68	20	83*	83*		
117				125	25		
				168*	168*		
5		66	6	98*	98*		
55				131	24		
				174*	174*		
14		75	19	89*	89*		
39				109	18		
				132*	132*		
211				365	67		
				474*	474*		


**CROSS SECTIONS - SHARON ROAD
STA. 24+00 TO STA. 25+00**

HAM-75-14.61

402
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:26 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group




END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
56	12				
76*	76*				
	42	16			
	70*	71*			
34	21				
74*	76*				
	44	17			
	71*	72*			
60	14				
79*	79*				
	119	32			
	150*	150*			
205	65				
291*	293*				

CROSS SECTIONS - SHARON ROAD
STA. 25+50 TO STA. 26+00
HAM-75-14.61
 403
 708

[Hatched Box] APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
 [Dashed Box] LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:27 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV86_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED	CHECKED
	CUT	FILL		
21	31*	9	31*	
24	34*	7	34*	
29	42*	6	42*	
36	45*	10	45*	
47	54*	15	54*	
48	61*	13	61*	
108	140*	30	140*	

**CROSS SECTIONS - SHARON ROAD
STA. 26+25 TO STA. 26+75**


HAM-75-14.61

404
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:27 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV86_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
27 20*	3 20*				
24 24*	3 24*				
22 29*	9 29*				
111 119*	27 119*				

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND GRANULAR MATERIAL, TYPE C

**CROSS SECTIONS - SHARON ROAD
STA. 27+00 TO STA. 28+00**


HAM-75-14.61

405
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000X5700.dgn 2021-01-18 3:13:28 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



SEEDING		END AREA		VOLUME		CALCULATED	
END WIDTH	SO. YDS.	CUT	FILL	CUT	FILL	WLC	CHECKED
							JDH

* QUANTITIES FOR EXCAVATION OF SUBGRADE, 18 INCHES DEEP AND GRANULAR MATERIAL, TYPE C

CROSS SECTIONS - SHARON ROAD
STA. 28+50 TO STA. 29+17.63


HAM-75-14.61

406
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

j:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000XS800.dgn 2021-01-18 3:13:37 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV86_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED	CHECKED
	CUT	FILL		
13	20*	3	21*	
13	18*	3	19*	
13	18*	2	19*	
15	25*	9	26*	
3	8*	7	9*	
7	17*	15	18*	
3	8*	7	8*	
35	60*	27	63*	

CROSS SECTIONS - CHESTER ROAD SOUTH
STA. 94+95.95 TO STA. 96+24.95

HAM-75-14.61

407
708


APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).

LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

94+95.95 (NOT SHOWN)
 BEGIN FULL DEPTH PAVEMENT WIDENING, LT.
 BEGIN PLANING & RESURFACING, (1" MIN, 3.25" MAX) WITH WEDGE COURSE (VAR. DEPTH)
 BEGIN EARTHWORK & SEEDING

CONST CHESTER ROAD SOUTH

j:\pre-int\06\06-386_HAM-75_HAM\00000\roadway\sheets\00000XS800.dgn 2021-01-18 3:13:37 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END AREA	VOLUME	CALCULATED	CHECKED	J.D.H.
3	0			
13*	14*			
		8	1	
		15*	16*	
13	1			
18*	19*			
		7	1	
		16*	17*	
2	0			
15*	16*			
		7	2	
		17*	18*	
		22	4	
		48*	51*	


**CROSS SECTIONS - CHESTER ROAD SOUTH
STA. 96+50 TO STA. 97+00**

HAM-75-14.61

408
708

APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
CONST CHESTER ROAD SOUTH
LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

J:\pre-int\06\06-386_HAM-75\HAM\00000\roadway\sheets\00000XS800.dgn 2021-01-18 3:13:37 PM william.croxton' ODOTcadd_PDF.pltcfgr ODOTV8i_Pen-ME.tbl IBI Group



END AREA	VOLUME		CALCULATED	CHECKED	JDH
	CUT	FILL			
12	23*	4	25*		
18	38*	12	41*		
7	18*	8	19*		
17	32*	11	33*		
11	16*	3	16*		
13	27*	3	28*		
48	97*	26	102*		


**CROSS SECTIONS - CHESTER ROAD SOUTH
STA. 97+50 TO STA. 98+50**

HAM-75-14.61

409
708


APPROX. LIMITS OF EX. CONCRETE. SEE TYPICAL SECTIONS FOR ADDITIONAL DETAILS. ITEM 202-PAVEMENT REMOVED (CONCRETE REMOVAL), ITEM 202-PAVEMENT REMOVED, ASPHALT (ASPHALT REMOVAL), ITEM 202-WEARING COURSE REMOVED (WEARING COURSE REMOVAL).
CONST CHESTER ROAD SOUTH
LIMITS FOR EXCAVATION OF UNSTABLE SUBGRADE

J:\pre-int\06\06-386_HAM-75\HAM\00000\traffic\sheets\00000td002.dgn 2021-01-05 4:59:18 PM brion.sedziol\ ODOTV81_PDF_Half.pltcfgr ODOTV81_Pen-ME.tbl IBI_Group



S-3

STA. 326+00, I-75
W10 X 22 STRUCTURAL BEAM SUPPORTS
FOUNDATIONS AS PER SCD TC-41.10



S-4

STA. 328+50, I-75
TC-15.116 DESIGN 2 STEEL TRUSS OVERHEAD SIGN SUPPORT
FOUNDATIONS AS PER SCD TC-21.11 & TC-21.50

CALCULATED
BSS
CHECKED
JDH

SIGN ELEVATION VIEWS

HAM-75-14.61

521
708

J:\pre-int\06\06-386_HAM-75\HAM\00000\signals\sheets\00000CM001.dgn_Sheet 2021-01-19 2:42:41 PM william.croxton

PULL BOX COVERS

PULL BOX COVERS SHALL BE INSTALLED PER SECTION 725 OF THE CMS. THE WORD "TRAFFIC" SHALL BE CAST ON THE SURFACE OF THE PULL BOX COVER. COVERS ARE INCIDENTAL TO THE PULL BOXES.

UTILITIES

FOR LOCATING INFORMATION AND CONTACT INFORMATION REFER TO THE UTILITIES NOTE LOCATED IN THE GENERAL NOTES OF THIS PLAN SET.

MAINTAINING ITS DURING CONSTRUCTION

THE CONTRACTOR SHALL MAINTAIN ALL PREEXISTING OR NEWLY INSTALLED PERMANENT ITS/TRAFFIC DEVICES AND INFRASTRUCTURE DURING CONSTRUCTION ACCORDING TO ODOT SUPPLEMENTAL SPECIFICATION 809.

DYNAMIC MESSAGE SIGN INSTALLATIONS

THE CONTRACTOR SHALL CONSTRUCT THE DMS TRUSS SUPPORT AND RELOCATE THE EXISTING ITS DEVICES SUCH THAT IT LIMITS THE AMOUNT OF ITS DOWN TIME. WHILE THE ITS EQUIPMENT IS OUT OF SERVICE, THE CONTRACTOR SHALL UTILIZE A PORTABLE CHANGEABLE MESSAGE SIGN TO DISPLAY THE INFORMATION RELAYED ON THE EXISTING DMS SIGN. THE CONTRACTOR SHALL COORDINATE WITH CENTRAL OFFICE (BRYAN COMER AT (614) 378-1253) TO OBTAIN A MODEM TO USE WITH THE PORTABLE CHANGEABLE MESSAGE SIGN. THE WORK ASSOCIATED WITH INSTALLING AND FURNISHING THE PORTABLE CHANGEABLE MESSAGE SIGN SHALL BE PAID FOR UNDER ITEM 614 - PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN.

THE DISINCENTIVES ASSOCIATED WITH SUPPLEMENTAL SPECIFICATION 809.14 SHALL NOT BE ENFORCED, FOR THIS DMS SIGN ONLY, DURING THE 6 MONTHS THE PCMS SIGN IS ACTIVE, DUE TO THE LENGTH OF TIME THE DMS WILL BE OUT OF SERVICE.

CCTV INSTALLATIONS

THE CONTRACTOR SHALL FURNISH AND INSTALL THIS ITEM ACCORDING TO ODOT SUPPLEMENTAL SPECIFICATION 809, AS WELL AS ANY STANDARD CONSTRUCTION DRAWINGS NOTED ON THE PLANS.

ITEM 809 - ATC V6.24 CONTROLLER, AS PER PLAN

THE CONTROLLER UNIT SHALL BE FURNISHED AND INSTALLED PER SUPPLEMENTAL SPECIFICATION 809 AND BE LISTED ON THE TRAFFIC AUTHORIZED PRODUCTS (TAP) LIST.

THE CONTROLLER SHALL BE AN ECONOLITE COBALT AND COMPATIBLE WITH THE CABINET TYPE BEING INSTALLED.

CALCULATED
MAM
CHECKED
PCG

TRAFFIC SURVEILLANCE GENERAL NOTES

HAM-75-14.61

561
708

TRAFFIC SURVEILLANCE - EQUIPMENT LEGEND


- ⋯ EXISTING LOOP DETECTORS
- + - EXISTING TRAFFIC SURVEILLANCE (TS) CONDUIT
- ⊗ EXISTING TRAFFIC SURVEILLANCE (TS) PULL BOX TO BE REMOVED
- /// PROPOSED LIGHTING
- T — TRAFFIC SURVEILLANCE CONDUIT
- DETECTION AREA
- 📷 CCTV CAMERA
- ▲ POWER SOURCE
- Ⓟ (PB-1) TRAFFIC SURVEILLANCE PULL BOX
- Ⓜ (MJB-1) TRAFFIC SURVEILLANCE MEDIAN JUNCTION BOX
- Ⓛ ELECTRIC PULL BOX
- Ⓜ ITS CABINET

REMOVAL QUANTITIES	
ITEM 625-PULL BOX REMOVED	0 EACH

N

0 50 100
HORIZONTAL SCALE IN FEET

CALCULATED
JAW
CHECKED
PCG



- NOTES:
1. RUN NEW FIBER (APPROX. 2,650 FEET) THROUGH EXISTING CONDUIT FROM EX. PB-1 SOUTH TO THE EXISTING RAMP METER CABINET ON RAMP DR (AT GLENDALE MILFORD).
 2. NO SPLICES IN THE FIBER BETWEEN THE EXISTING RAMP METER CABINET ON RAMP DR (AT GLENDALE-MILFORD) AND THE PROPOSED RAMP METER CABINET ON RAMP A (AT SHARON RD).

- NOTES:
1. EXISTING TRAFFIC SURVEILLANCE EQUIPMENT LOCATIONS ARE APPROXIMATE.
 2. EXISTING TRAFFIC SURVEILLANCE SYSTEM SHALL BE KEPT FULLY FUNCTIONAL THROUGHOUT CONSTRUCTION.

j:\pre-int\06\06-386_HAM-75\HAM\00000\signals\sheets\00000CM101.dgn 2021-01-11 4:45:46 PM e_jason.watt\ ODOTV81_PDF_Half.plt cfg ODOTV81_Pen-ME.tbl IBI Group

TRAFFIC SURVEILLANCE - I-75 SB / NB
STA 330+00 TO STA 345+00

HAM-75-14.61
567
708

j:\pre-int\06-386_HAM-75_HAM\00000\lighting\sheets\00000LN001.dgn 2021-01-14 10:23:01 AM jason.watt" ODOTcadd_PDF.pltcfj ODOTV8i_Pen-ME.tbl IBI Group

ITEM 625 - POWER SERVICE, AS PER PLAN

IN ADDITION TO THE REQUIREMENTS OF THE SPECIFICATIONS, THE FOLLOWING IS ADDED.

THE POWER SUPPLYING AGENCY FOR THIS PROJECT IS:

DUKE ENERGY
139 E. 4TH STREET 467A
CINCINNATI, OH 45202
513-287-3674
AARON WRIGHT

THE ENGINEER SHALL ENSURE THAT EACH POWER SERVICE ELECTRICAL ENERGY ACCOUNT IS IN THE NAME OF AND THAT THE BILLING ADDRESS IS TO THE MAINTAINING AGENCY NOTED IN THE PLANS. THIS SHALL BE DONE NOT ONLY FOR EACH NEW POWER SERVICE ESTABLISHED BY THIS PROJECT BUT ALSO FOR EACH EXISTING POWER SERVICE, SINCE THERE MAY BE A REASSIGNMENT OF THE RESPONSIBILITY FOR AN EXISTING SERVICE AS A RESULT OF THE WORK PERFORMED BY THIS PROJECT.

PAYMENT WILL BE MADE AT THE UNIT BID PRICE FOR EACH C&MS ITEM 625, "POWER SERVICE, AS PER PLAN" WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIALS AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.

ITEM 625 - DISCONNECT CIRCUIT, AS PER PLAN

THIS ITEM OF WORK SHALL CONSIST OF THE DISCONNECTION OF AN EXISTING LIGHT CIRCUIT AT A PULL BOX OR TRANSFORMER BASE.

DISCONNECTION AT A PULL BOX SHALL INVOLVE CUTTING THE EXISTING CIRCUIT AND REMOVING ALL SPLICE KITS. ANY CABLE THAT IS TO BE ABANDONED SHALL BE TERMINATED FROM THE PULL BOX SO THAT NO CABLE IS LEFT IN THE BOX.

DISCONNECTION AT A TRANSFORMER BASE SHALL INVOLVE CUTTING THE EXISTING CIRCUIT AND REMOVING ALL CONNECTOR KITS. ALL DUCT-CABLE NOT TO BE REUSED SHALL BE REMOVED FROM THE TRANSFORMER BASE AND THE EXISTING CONDUIT IN THE FOUNDATION SHALL BE CLEANED OF ALL CABLE AND DEBRIS SO THAT THE NEW DUCT-CABLE CAN BE INSTALLED. ALL EXISTING CABLE TO REMAIN ACTIVE SHALL BE CUT IN A MANNER SO THAT THERE IS SUFFICIENT CABLE LEFT FOR RECONNECTION.

THOSE WIRES THAT ARE TO REMAIN ON ACTIVE CIRCUITS SHALL HAVE A WATER-RESISTANT SEAL AT THE CUT END. THE WATER-RESISTANT SEAL SHALL BE ACCOMPLISHED BY PLUGGING THE DEACTIVATED PORT OF AN EXISTING CONNECTOR KIT OR BY INSTALLING A CABLE SPLICE KIT ON THE CUT END OF THE CABLE.

PAYMENT SHALL BE MADE AT THE UNIT BID PRICE PER EACH UNDER C&MS ITEM 625, DISCONNECT CIRCUIT, AS PER PLAN AT EACH LOCATION WHERE DISCONNECTION IS REQUIRED WHICH SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIALS AND INCIDENTALS REQUIRED TO COMPLETE THIS ITEM IN A SATISFACTORY AND WORKMANLIKE MANNER.

AN ESTIMATED QUANTITY OF 100 EACH HAS BEEN CARRIED TO THE GENERAL SUMMARY FOR THIS PURPOSE.

ITEM 625 - HIGH VOLTAGE TEST

A HIGH VOLTAGE TEST, AS DESCRIBED IN 625.19, SHALL BE PERFORMED ON ALL DISTRIBUTION CABLE AND DUCT CABLE SYSTEMS TO BE INSTALLED ON THIS PROJECT.

LAMPS

ALL LAMPS SHALL BE SOLID STATE (LED) AS LISTED IN THE ODOT OFFICE OF ROADWAY ENGINEERING APPROVED LIST SUPPLEMENTAL SPECIFICATION 813: LUMINAIRE, SOLID STATE (LED), OR APPROVED EQUAL.

PADLOCKS AND KEYS

PADLOCKS FURNISHED SHALL BE EITHER BRASS OR BRONZE, EQUAL TO MASTER NO. 4BKA OR WILSON BOHANNAN 660A, AND SHALL BE KEYED IN ACCORDANCE WITH C&MS 631.06. PAYMENT SHALL BE INCLUDED IN THE BID FOR THE ITEM(S) BEING LOCKED.

ITEM 625 - LUMINAIRE, LOW MAST, SOLID STATE (LED), AS PER PLAN

LUMINAIRES FOR LOW-MAST SOLID STATE (LED) LIGHTING UNITS WITH SYMMETRIC DISTRIBUTION TYPE V 400W HPS EQUIVALENT SHALL BE HOLOPHANE "HMLD-II", CHM "CONDOR LED2", OR GE "EVOLVE HM", OR EQUAL AS APPROVED BY THE ENGINEER.

IN ADDITION, OTHER LUMINAIRES WILL BE CONSIDERED IF THE DESIGNED INTENSITY AND UNIFORMITY ARE PROVIDED USING THE DESIGNED POLE LOCATIONS AND THE DESIGNED NUMBER AND TYPE OF FIXTURES PER POLE AND APPROVED BY ODOT.

ITEM 625 - LUMINAIRE, CONVENTIONAL, SOLID STATE (LED), AS PER PLAN

LUMINAIRES FOR CONVENTIONAL SOLID STATE (LED) LIGHTING UNITS WITH ASSYMMETRIC DISTRIBUTION TYPE III, SHALL BE EQUIVALENT TO 250W HPS.

THE CONVENTIONAL SOLID STATE (LED) LUMINAIRES SHALL BE LISTED IN THE ODOT OFFICE OF ROADWAY ENGINEERING APPROVED LIST SUPPLEMENTAL SPECIFICATION 813: LUMINAIRE, SOLID STATE (LED), OR APPROVED EQUAL.

ITEM 625 - LUMINAIRE, UNDERPASS, SOLID STATE (LED), AS PER PLAN

LUMINAIRES FOR UNDERPASS SOLID STATE (LED) LIGHTING UNITS SHALL BE GE "EVOLVE EWS3", HOLOPHANE "TUNNELPASS", OR EATON/COOPER "GALLEON GWC", OR EQUAL AS APPROVED BY THE ENGINEER.

LUMINAIRES SHALL BE 150 WATT HPS EQUIVALENT WITH ASSYMMETRIC DISTRIBUTION TYPE III.

IN ADDITION, OTHER LUMINAIRES WILL BE CONSIDERED IF THE DESIGNED INTENSITY AND UNIFORMITY ARE PROVIDED USING THE DESIGNED POLE LOCATIONS AND THE DESIGNED NUMBER AND TYPE OF FIXTURES PER POLE AND APPROVED BY ODOT.

ITEM 625 - SPECIAL - MAINTAIN EXISTING LIGHTING

EXISTING ROADWAYS WHICH ARE TO REMAIN OPEN TO TRAFFIC DURING CONSTRUCTION OF THIS PROJECT AND WHICH ARE LIGHTED SHALL HAVE THE LIGHTING MAINTAINED AS DESCRIBED HEREIN.

BEFORE ANY WORK IS STARTED IN THE IMMEDIATE VICINITY OF THE EXISTING LIGHTING CIRCUITS, REPRESENTATIVES OF ODOT, THE MAINTAINING AGENCY AND THE CONTRACTOR SHALL MAKE A VISUAL INSPECTION OF THE EXISTING ROADWAY LIGHTING CIRCUITS TO BE MAINTAINED. DURING THIS INSPECTION, A WRITTEN RECORD OF THE CONDITION OF EXISTING LIGHTING SHALL BE MADE BY ODOT'S REPRESENTATIVE. THIS WRITTEN REPORT SHALL NOTE INDIVIDUAL LUMINAIRES WHICH ARE NOT IN WORKING ORDER, INDIVIDUAL POLES WHICH ARE STANDING, AND INDIVIDUAL CIRCUITS WHICH ARE NOT IN WORKING ORDER. THE COMPLETED REPORT SHALL BE SIGNED BY THE REPRESENTATIVES OF ODOT, THE MAINTAINING AGENCY AND THE CONTRACTOR.

IF, AS A RESULT OF THIS INSPECTION, IT IS DETERMINED THAT THE CONDITION OF THE EXISTING SYSTEM IS BELOW THAT REQUIRED FOR THE SAFETY OF THE TRAVELING PUBLIC, THEN THE MAINTAINING AGENCY SHALL MAKE THE REPAIRS NECESSARY TO RETURN THE SYSTEM TO AN ACCEPTABLE CONDITION. FOLLOWING THESE REPAIRS, THE SYSTEM SHALL AGAIN BE INSPECTED AND A REPORT SHALL BE MADE AND SIGNED AS OUTLINED HEREIN.

WHEN THE EXISTING SYSTEM IS IN AN ACCEPTABLE CONDITION, IT SHALL BE TURNED OVER TO THE CONTRACTOR WHO SHALL THEN BE REQUIRED TO MAINTAIN THE EXISTING LIGHTING TO THE CONDITION OUTLINED IN THIS REPORT WITH THE EXCEPTION OF KNOCKDOWNS DUE TO TRAFFIC ACCIDENTS.

REPLACEMENT OF KNOCKED DOWN UNITS SHALL BE DONE ONLY WHEN THE ENGINEER HAS DETERMINED THAT THE REPLACEMENT OF THE KNOCKED DOWN UNIT IS NECESSARY AND SHALL BE PAID SEPARATELY ON A UNIT BASIS.

BETTERMENTS SHALL BE COVERED IN ITEMS OF WORK PERTAINING TO THE CONSTRUCTION OF PERMANENT IMPROVEMENT.

WHEN THE SEQUENCE OF CONSTRUCTION ACTIVITIES REQUIRES, OR SHOULD THE CONTRACTOR DESIRE, THE REMOVAL OF THE EXISTING LIGHTING BEFORE THE NEW LIGHTING IS OPERATIONAL, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TEMPORARY LIGHTING OF THIS PORTION OF THE ROADWAY.

PRIOR TO INSTALLING SUCH LIGHTING, THE CONTRACTOR SHALL PREPARE AND SUBMIT FOUR SETS OF THE TEMPORARY LIGHTING PLAN TO THE ENGINEER FOR REVIEW AND APPROVAL.

THIS PLAN SHALL SHOW LOCATIONS OF POLES, LENGTHS OF BRACKET ARMS, STYLES OF LUMINAIRES, MOUNTING HEIGHTS, WIRING METHODS AND OTHER PERTINENT INFORMATION. THE TEMPORARY LIGHTING SHALL PROVIDE AN AVERAGE INITIAL INTENSITY OF 1.2 FOOTCANDLES WITH AN AVERAGE TO MINIMUM UNIFORMITY NOT TO EXCEED 3:1. MOUNTING HEIGHT OF TEMPORARY LUMINAIRES SHALL NOT BE LESS THAN 30 FEET, AND THE MINIMUM OVERHEAD CONDUCTOR CLEARANCE SHALL BE 20 FEET. TEMPORARY OVERHEAD CONSTRUCTION SHALL NOT BE LESS THAN GRADE "A" FOR STRENGTH REQUIREMENTS AS DEFINED BY THE NATIONAL ELECTRIC SAFETY CODE. WOOD POLES WITH OVERHEAD WIRING MAY BE USED. HOWEVER, TEMPORARY LIGHTING SHALL MEET FEDERAL AND STATE SAFETY CRITERIA. IF BREAKAWAY POLES ARE USED TO MEET THESE CRITERIA, THEN UNDERGROUND WIRING SHALL BE USED. RECONDITIONED OR USED MATERIALS MAY BE FURNISHED FOR TEMPORARY LIGHTING.

ALL MATERIALS NECESSARY TO COMPLETE THE TEMPORARY LIGHTING SHALL BE FURNISHED AND INSTALLED BY THE CONTRACTOR. WHEN NO LONGER NEEDED, THE TEMPORARY LIGHTING INSTALLATION SHALL BE REMOVED AND PROPERLY DISPOSED OF BY THE CONTRACTOR.

THE MAINTAINING AGENCY WILL PAY FOR ELECTRICAL ENERGY CONSUMED BY EXISTING POWER SERVICES AND BY PROPOSED PERMANENT POWER SERVICES AFTER ACCEPTANCE OF THE LIGHTING WORK. THE CONTRACTOR WILL PAY FOR ELECTRICAL ENERGY, INSTALLATION, REMOVAL AND MAINTENANCE OF ANY TEMPORARY POWER SERVICES.

LIGHTING SHALL BE MAINTAINED AT ALL TIMES THROUGH THE USE OF THE EXISTING LIGHTING, TEMPORARY LIGHTING, OR THE COMPLETED LIGHTING. ANY LIGHTING OUTAGE SHALL BE REPAIRED AND RESTORED WITHIN 24 HOURS OF NOTIFICATION. A DISINCENTIVE SHALL BE ASSESSED IN THE AMOUNT OF \$1,000 FOR EACH DAY LIGHTING IS NOT MAINTAINED BEYOND THE SPECIFIED LIMIT.

THE LUMP SUM PRICE BID FOR ITEM SPECIAL "MAINTAIN EXISTING LIGHTING" SHALL INCLUDE PAYMENT FOR ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO MAINTAIN THE EXISTING LIGHTING AS SPECIFIED HEREIN.

THE PRICE BID FOR ITEM SPECIAL, MAINTAIN EXISTING LIGHTING SHALL BE FULL PAYMENT FOR THE REPLACEMENT OF AN EXISTING LIGHTING UNIT WHICH HAS BEEN KNOCKED DOWN AFTER THE AFOREMENTIONED INSPECTION AND SHALL INCLUDE ALL LABOR, EQUIPMENT, MATERIALS AND INCIDENTALS NECESSARY TO PROVIDE A REPLACEMENT FOR SUCH UNIT.

ITEM 625 - STRUCTURE GROUNDING SYSTEM

THIS ITEM OF WORK SHALL CONSIST OF PROVIDING GROUND RODS AND GROUNDING CONDUCTOR RISER CABLES EMBEDDED IN THE PIERS TO THE STRUCTURE SUPPORT BEAMS AND PROVIDING GROUNDING CONNECTIONS FOR CONDUITS EMBEDDED IN THE STRUCTURES AT SHARON ROAD. IN ADDITION, PROVIDE BONDING JUMPERS AROUND STRUCTURE SUPPORT BEAM SPLICES AND HINGES AND ACROSS EXPANSION JOINTS. BOND PARALLEL BRIDGE SECTION TOGETHER.

PAYMENT WILL BE MADE AT THE UNIT PRICE BID FOR EACH ITEM 625, STRUCTURE GROUNDING SYSTEM AND SHALL BE FULL COMPENSATION FOR ALL LABOR, MATERIALS, AND INCIDENTALS REQUIRED TO COMPLETE THE WORK. AN ESTIMATED QUANTITY OF 2 EACH HAS BEEN CARRIED TO THE GENERAL SUMMARY.

LIGHT POLE, LOW MAST, AS PER PLAN

LIGHT POLES AND FIXTURES SHALL BE FURNISHED BY THE DEPARTMENT FOR CONTRACTOR INSTALLATION. POLES AND LIGHT FIXTURES ARE STORED IN THE VILLAGE OF EVENDALE MAINTENANCE FACILITY AT 1433 GLENDALE MILFORD ROAD (1/2 MILE WEST OF I-75). CONTRACTOR SHALL PICK THE LIGHT POLES AND FIXTURES UP AT THE LOCATION FOR INSTALLATION.



CALCULATED
JAW
CHECKED
PCG


LIGHTING PLAN - I-75 SB / NB
STA 335+50 TO STA 348+00

HAM-75-14.61

587
708

LEGEND

- LIGHT POLE, STATION, OFFSET, TRANSFORMER BASE CONVENTIONAL, SOLID STATE (LED), 20' ARM, 40' MOUNTING HEIGHT
- (A) POLE IDENTIFICATION NO.
(B) CONTROL CENTER NO.
(I) POLE NO. WITHIN CIRCUIT
- LUMINAIRE, UNDERPASS, SOLID STATE (LED)
- PROPOSED CONTROL CENTER/ POWER SERVICE
- PROPOSED LOW MAST SYMMETRIC LUMINAIRE, TRANSFORMER BASE, LOW MAST, SOLID STATE (LED), 50' MOUNTING HT.
- PULL BOX, IDENTIFICATION NO. W/OFFSET
- JUNCTION BOX, TYPE 1, IDENTIFICATION NO.
- INDICATES CIRCUIT & NO. OF SINGLE CONDUCTORS IN 1-1/2" DUCT/DISTRIBUTION CABLE IN 24" DEEP TRENCH/BARRIER UNDER PAVEMENT PLACE 3" CONDUIT, 725.04
- EXISTING LIGHT POLE TO BE REMOVED
- EXISTING LIGHT POLE
- EXISTING PULL BOX WITH IDENTIFICATION NUMBER
- EXISTING CABLE TO REMAIN IN PLACE



REMOVAL QUANTITIES:

ITEM 625 - LIGHT POLE REMOVED	6 EACH
ITEM 625 - LIGHT TOWER REMOVED	0 EACH
ITEM 625 - LIGHT POLE FOUNDATION REMOVED	6 EACH
ITEM 625 - LIGHT TOWER FOUNDATION REMOVED	0 EACH
ITEM 625 - POWER SERVICE REMOVED	0 EACH

\\useeast.ibigroup.com\j\CN\pre-int\06\06-386_HAM-75_HAM\00000\lighting_sheets\00000\P101.dgn_Sheet 2021-01-11 4:51:18 PM jason.watt

STANDARD DRAWINGS AND SUPPLEMENTAL SPECIFICATIONS

REFER TO THE FOLLOWING STANDARD BRIDGE DRAWING(S):

- AS-1-15 DATED/REVISED 7-17-15
- AS-2-15 DATED/REVISED 1-18-19
- PCB-91 DATED/REVISED 1-18-13
- PSID-1-13 DATED/REVISED 7-20-18
- SBR-1-13 DATED/REVISED 7-20-18
- SICD-1-96 DATED/REVISED 7-18-14
- SICD-2-14 DATED/REVISED 7-18-14

AND TO THE FOLLOWING SUPPLEMENTAL SPECIFICATIONS:

- 840 DATED 4-17-20
- 846 DATED 4-17-15
- 866 DATED 4-21-17
- 867 DATED 1-18-19
- 878 DATED 1-17-20

DESIGN SPECIFICATIONS

DESIGN SPECIFICATIONS: THIS STRUCTURE CONFORMS TO THE 8TH EDITION OF THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 2017 AND THE ODOT BRIDGE DESIGN MANUAL, 2020.

LOAD MODIFIER FOR OPERATIONAL IMPORTANCE

OPERATIONAL IMPORTANCE: A LOAD MODIFIER OF 1.00 HAS BEEN ASSUMED FOR THE DESIGN OF THIS STRUCTURE IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, ARTICLE 1.3.5 AND THE ODOT BRIDGE DESIGN MANUAL, 2007.

DESIGN LOADING

DESIGN LOADING: HL -13

FUTURE WEARING SURFACE (FWS) OF 0.060 KIPS/SQ.FT.

DESIGN DATA

- CONCRETE CLASS QC3 - COMPRESSIVE STRENGTH 4.5 KSI (BRIDGE DECK, DIAPHRAGM, APPROACH SLAB)
- CONCRETE CLASS CO SCC - COMPRESSIVE STRENGTH 4.5 KSI (PARAPETS)
- CONCRETE CLASS QC1 - COMPRESSIVE STRENGTH 4.0 KSI (SUBSTRUCTURE)
- REINFORCING STEEL - MINIMUM YIELD STRENGTH 60 KSI
- STEEL PIPE PILES - GRADE A 252 - GRADE 3 - YIELD STRENGTH 45 KSI
- STRUCTURAL STEEL - ASTM A709 GRADE 50 - YIELD STRENGTH 50 KSI

CONCRETE FOR PRESTRESSED BEAMS:
COMPRESSIVE STRENGTH (FINAL) - 9.5 KSI
COMPRESSIVE STRENGTH (RELEASE) - 7 KSI

WELDED WIRE FABRIC:
YIELD STRENGTH - 70 KSI

PRESTRESSING STRAND:
AREA = 0.217 IN²
ULTIMATE STRENGTH = 270 KSI
INITIAL STRESS = 202.5 KSI (LOW RELAXATION STRANDS)

DECK PROTECTION METHOD

EPOXY COATED REINFORCING STEEL

2.5" CONCRETE COVER

MONOLITHIC WEARING SURFACE

MONOLITHIC WEARING SURFACE IS ASSUMED, FOR DESIGN PURPOSES, TO BE 1 INCH THICK.

EXISTING STRUCTURE PLANS:

CONSTRUCTION PLANS FOR EXISTING BRIDGE ARE ON FILE AT THE DEPARTMENT OF TRANSPORTATION, DISTRICT 8 OFFICE, 505 SOUTH STATE ROUTE 741, LEBANON, OHIO AND ARE AVAILABLE FOR REFERENCE.

PILE DRIVING CONSTRAINTS

PRIOR TO DRIVING ABUTMENT PILES TO THE ULTIMATE BEARING VALUE (UBV), CONSTRUCT THE MSE WALL AND THE BRIDGE APPROACH EMBANKMENT UP TO THE BOTTOM OF THE FOOTINGS. PROVIDE A SURCHARGE FROM THE BOTTOM OF THE ABUTMENT FOOTING TO THE BOTTOM OF THE SUBGRADE FOR A MINIMUM DISTANCE OF 100 FEET BEHIND THE ABUTMENT. SURCHARGE LOADS SHALL REMAIN UNTIL THE REQUIRED SETTLEMENT HAS OCCURRED AND AS DIRECTED BY THE ENGINEER. COMPLETE THE MSE WALL CONSTRUCTION IMMEDIATELY FOLLOWING THE SURCHARGE REMOVAL.

THE CONTRACTOR MAY PRE-DRIVE ABUTMENT PILES BEFORE CONSTRUCTING MSE WALLS. PRE-DRIVING CONSISTS OF INSTALLING THE ABUTMENT PILES INTO THE SOIL ONLY AS FAR AS NECESSARY SO THAT THE PILE WILL REMAIN VERTICAL DURING MSE WALL CONSTRUCTION. IF PRE-DRIVING PILES, INSTALL PILE SLEEVES AROUND PILES BEFORE CONSTRUCTING THE MSE WALL. AT LEAST THREE FEET OF PILE MUST EXTEND ABOVE THE TOP OF THE PILE SLEEVE TO MEET THE REQUIREMENTS OF CMS 507.09 REGARDING SPLICES. DO NOT DRIVE ABUTMENT PILES TO THE UBV UNTIL AFTER THE ABOVE REQUIRED MSE WALL AND EMBANKMENT HAVE BEEN CONSTRUCTED AND THE SPECIFIED WAITING PERIOD HAS ELAPSED.

IF NOT PRE-DRIVING ABUTMENT PILES, INSTALL THE ABUTMENT PILES THROUGH PILE SLEEVES AFTER THE ABOVE REQUIRED MSE WALL AND EMBANKMENT HAVE BEEN CONSTRUCTED AND THE SPECIFIED WAITING PERIOD HAS ELAPSED.

ABUTMENT PILE DRIVING TO THE UBV (FOR PILES DRIVEN AFTER MSE CONSTRUCTION) OR PILE REDRIVING (FOR PILES PRE-DRIVEN BEFORE MSE CONSTRUCTION) MAY NOT BEGIN UNTIL A MINIMUM 30 DAY CALENDAR DAY WAITING PERIOD HAS ELAPSED AFTER THE COMPLETION OF EMBANKMENT AND SURCHARGE CONSTRUCTION. THE WAITING PERIOD BEGINS ONCE THE APPROACH EMBANKMENT HAS REACHED THE PROPOSED SUBGRADE ELEVATION. THE WAITING PERIOD WILL BE EVALUATED ON A PER READING BASIS AND MAY BE EXTENDED OR TERMINATED BY THE DEPARTMENT BASED ON THE SETTLEMENT PLATFORM READINGS. CONSECUTIVE SETTLEMENT READINGS SHOULD BE RECORDED AT LEAST ONE WEEK AFTER EMBANKMENT CONSTRUCTION IS COMPLETE. TERMINATION OF THE SETTLEMENT MONITORING WILL BE EVALUATED AFTER THE 30 DAY WAITING PERIOD, PROVIDED THE SETTLEMENT PLATFORMS HAVE INDICATED 1/8" OR LESS OF SETTLEMENT FOR EACH OF THE LAST TWO WEEKS OF READING.

AFTER THE SPECIFIED WAITING PERIOD HAS ELAPSED, DRIVE PILES TO THE UBV. IN ORDER TO REMOVE ANY NEGATIVE SKIN FRICTION THAT HAS DEVELOPED DURING THE WAITING PERIOD, DRIVE EACH ABUTMENT PILE A DISTANCE OF AT LEAST 0.5 INCH.

PROPRIETARY RETAINING WALL DATA

THE PROPRIETARY WALL SUPPLIER SHALL DESIGN THE INTERNAL STABILITY OF A MECHANICALLY STABILIZED EARTH (MSE) WALL IN ACCORDANCE WITH SS840 TO SUPPORT THE ABUTMENT. THE DESIGN FOR INTERNAL STABILITY SHALL INCLUDE A NOMINAL (I.E. UNFACTORED) HORIZONTAL STRIP LOAD DUE TO FRICTION (FR) FROM THE SUPERSTRUCTURE OF 6.0 K/FT APPLIED PERPENDICULAR TO THE FACE OF WALL AT THE BASE OF THE CONCRETE FOOTING. THIS STRIP LOAD DOES NOT INCLUDE EARTH PRESSURE LOADS FROM THE ABUTMENT BACKFILL. HOWEVER, THE PROPRIETARY WALL SUPPLIER SHALL INCLUDE EARTH PRESSURE LOADS FROM THE ABUTMENT BACKFILL IN THE DESIGN CALCULATIONS.

DECK PLACEMENT DESIGN ASSUMPTIONS:

THE FOLLOWING ASSUMPTIONS OF CONSTRUCTION MEANS AND METHODS WERE MADE FOR THE ANALYSIS AND DESIGN OF THE SUPERSTRUCTURE. THE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN OF THE FALSEWORK SUPPORT SYSTEM WITHIN THESE PARAMETERS AND WILL ASSUME RESPONSIBILITY FOR SUPERSTRUCTURE ANALYSIS FOR DEVIATION FROM THESE DESIGN ASSUMPTIONS.

AN EIGHT WHEEL FINISHING MACHINE WITH A MAXIMUM WHEEL LOAD OF 1.08 KIPS.

A MINIMUM OUT-TO-OUT WHEEL SPACING AT EACH END OF THE MACHINE OF 103".

A MAXIMUM SPACING OF OVERHANG FALSEWORK BRACKETS OF 48 IN.

A MAXIMUM DISTANCE FROM THE CENTERLINE OF THE FASCIA GIRDER TO THE FACE OF THE SAFETY HANDRAIL OF 65".

PILES DRIVEN TO TIP ELEVATION FOR PILE/SOIL SETUP

THE ULTIMATE BEARING VALUE IS 330 KIPS PER PILE FOR THE ABUTMENT PILES. PART OF THE ULTIMATE BEARING VALUE WILL BE ACHIEVED THROUGH PILE/SOIL SETUP, WHICH IS A TIME-DEPENDENT INCREASE IN RESISTANCE THAT OCCURS IN SOME SOILS.

NOTIFY THE ENGINEER AT LEAST 5 DAYS BEFORE DRIVING PILES SO THAT THE ENGINEER CAN NOTIFY THE DISTRICT GEOTECHNICAL ENGINEER, THE OFFICE OF CONSTRUCTION ADMINISTRATION, AND THE OFFICE OF STRUCTURAL ENGINEERING. DRIVE THE FIRST TWO PILES IN EACH SUBSTRUCTURE TO THE TIP ELEVATION GIVEN BELOW FOR THE SUBSTRUCTURE. DRIVE THE THIRD AND FORTH PILES TO 75% AND 85% OF THE LENGTH OF THE FIRST TWO PILES. PERFORM DYNAMIC LOAD TESTING ON ALL FOUR PILES WHILE DRIVING. AFTER DRIVING THE FOUR PILES, CEASE ALL DRIVING OPERATIONS AT THE SUBSTRUCTURE FOR A MINIMUM OF 7 DAYS. INCLUDE THE WAITING PERIOD AS A SEPARATE ACTIVITY IN THE PROGRESS SCHEDULE. AFTER THE WAITING PERIOD, PERFORM PILE RESTRIKES ON THE FOUR PILES (TWO RESTRIKE ITEMS). SUBMIT ALL TEST RESULTS TO THE ENGINEER. THE ENGINEER WILL REVIEW THE TEST RESULTS AND ESTABLISH DRIVING CRITERIA FOR THE PILING IN THE SUBSTRUCTURE WITH ASSISTANCE OF THE DISTRICT GEOTECHNICAL ENGINEER, THE OFFICE OF CONSTRUCTION ADMINISTRATION, AND THE OFFICE OF STRUCTURAL ENGINEERING.

IF THE DYNAMIC LOAD TESTING INDICATES A PILE HAS ACHIEVED THE ULTIMATE BEARING VALUE ABOVE THE TIP ELEVATION DURING THE INITIAL DRIVING (BEFORE THE WAITING PERIOD), STOP DRIVING AND NOTIFY THE ENGINEER. IF THE RESTRIKE TEST RESULTS ON THE FOUR PILES INDICATE THAT A PILE DID NOT ACHIEVE THE REQUIRED ULTIMATE BEARING VALUE, DRIVE THE PILE TO THE ESTABLISHED DRIVING CRITERIA.

REAR ABUTMENT PILES:
36 PILES 75 FEET LONG, ORDER LENGTH
TIP ELEVATION, 558.00 FEET
2 DYNAMIC LOAD TESTING ITEMS
2 RESTRIKES

FORWARD ABUTMENT PILES:
36 PILES 65 FEET LONG, ORDER LENGTH
TIP ELEVATION, 550.30 FEET
2 DYNAMIC LOAD TESTING ITEMS
2 RESTRIKES

ITEM 503. COFFERDAMS AND EXCAVATION BRACING, AS PER PLAN:

THE DESIGN SHOWN ON THE PLANS FOR TEMPORARY SUPPORT OF EXCAVATION IS ONE REPRESENTATIVE DESIGN THAT MAY BE USED TO CONSTRUCT THE PROJECT. THE CONTRACTOR MAY CONSTRUCT THE DESIGN SHOWN ON THE PLANS OR PREPARE AN ALTERNATE DESIGN TO SUPPORT THE SIDES OF EXCAVATIONS. IF CONSTRUCTING AN ALTERNATE DESIGN FOR TEMPORARY SUPPORT OF EXCAVATION, PREPARE AND PROVIDE PLANS IN ACCORDANCE WITH CMS 501.05. THE DEPARTMENT WILL PAY FOR THE TEMPORARY SUPPORT OF EXCAVATION AT THE CONTRACT LUMP SUM PRICE FOR COFFERDAMS AND EXCAVATION BRACING. NO ADDITIONAL PAYMENT WILL BE MADE FOR PROVIDING AN ALTERNATE DESIGN.

ITEM 202 - STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN

THE EXISTING STRUCTURE SHALL BE REMOVED IN ACCORDANCE WITH ITEM 202 EXCEPT THAT THE EXISTING ABUTMENTS SHALL BE REMOVED IN THEIR ENTIRETY.

ITEM 511 CLASS QC3 CONCRETE, MISC.: WITH QC/QA, BRIDGE DECK

THIS ITEM MODIFIES THE STANDARD 511 CONCRETE FOR STRUCTURES SPECIFICATION TO INCLUDE MACRO-SYNTHETIC INTO THE SUPERSTRUCTURE CONCRETE. THIS ITEM SHALL CONFORM TO CMS 511 WITH THE FOLLOWING CONDITIONS AND REVISIONS:

PROVIDE MATERIALS CONFORMING TO 511.02 EXCEPT AS MODIFIED BELOW:

PORTLAND CEMENT CONCRETE
499.03, CLASS QC 3 MEETING A DESIGN STRENGTH OF 4,500 PSI, WITH MACRO-SYNTHETIC FIBERS WITH MODIFICATION PER 511.02 FIBERS FOR CONCRETE: ASTM C 1116, TYPE III
CORROSION INHIBITOR: 515.15

THE CLASS QC3 CONCRETE FOR THE SUPERSTRUCTURE SHALL MEET THE FOLLOWING CRITERIA: WATER/CEMENT RATIO = 0.40 MAXIMUM; MINIMUM 4 LBS/CY MACRO-SYNTHETIC FIBERS (1.5 IN. MIN. TO 2.5 IN. MAX.) MEETING ASTM C1116 TYPE III SHALL BE ADDED TO THE MIX.

MIX SHALL INCLUDE A MIGRATING CORROSION INHIBITOR AS MANUFACTURED BY AN APPROVED SUPPLIER LISTED ON ODOT'S QUALIFIED APPROVED SUPPLIERS, ITEM 515.15. THE DOSAGE RATE LISTED ON THE ODOT QUALIFIED APPROVED SUPPLIERS LIST WILL APPLY.

ITEM 511 CLASS QC3 CONCRETE, MISC.: WITH QC/QA, BRIDGE DECK, AS PER PLAN CONTINUED

THE MACRO-SYNTHETIC FIBERS SHALL BE INCORPORATED INTO THE MIX IN SUCH A WAY THAT NO 'BALLING' OCCURS. UPON INSPECTION OF THE MIX AT THE TIME OF PLACEMENT, IF ANY 'BALLING' OCCURS, THE ENGINEER SHALL REJECT THE REMAINDER OF THE LOAD AT ANY TIME DURING THE POUR. IT IS IMPORTANT TO FOLLOW INDUSTRY STANDARDS AND ASTM SPECIFICATIONS ON THE PREMIXING OF THE CEMENT, AGGREGATE, AND MACRO-SYNTHETIC FIBERS PRIOR TO THE ADDITION OF WATER AND ADMIXTURES. PROVIDE MACRO-SYNTHETIC FIBERS THAT ARE MONOFILAMENT FIBERS MADE FROM VIRGIN POLYPROPYLENE, POLYETHYLENE, OR CO-POLYMERS THAT ARE INERT TO ALKALI ATTACK. ENSURE THE MACRO-SYNTHETIC FIBERS HAVE A MINIMUM TENSILE STRENGTH OF 70 KSI, A MINIMUM MODULUS OF ELASTICITY OF 800 KSI, A MINIMUM FILAMENT DIAMETER OF 0.012 INCHES, AND ASPECT RATIO BETWEEN 60 AND 100, AND ARE BETWEEN 1.0 AND 2.5 INCHES IN LENGTH. STORE THE MACRO-SYNTHETIC FIBERS ACCORDING TO THE MANUFACTURER'S RECOMMENDATION AND KEEP THE MATERIAL FREE FROM DUST, DIRT AND MOISTURE. PLACING THE BAG THAT THE FIBERS COME IN INTO THE CONCRETE MIX IS NOT PERMITTED.

USE A MINIMUM DOSAGE RATE OF MACRO-SYNTHETIC FIBERS OF 4.0 LBS/CY OF CONCRETE. DETERMINE THE FINAL PROPOSED DOSAGE RATE THROUGH MIX TESTING. ENSURE THE FIBER REINFORCED CONCRETE MEETS OR EXCEEDS A MINIMUM EQUIVALENT FLEXURAL STRENGTH RATIO OF 25% ACCORDING TO ASTM C 1609. ENSURE THE FINAL PROPOSED MIX IS WORKABLE AND ABLE TO BE PRODUCED SUCH THAT BALLING OR CLUMPING OF THE FIBERS IS NOT A PROBLEM AS DETERMINED BY THE ENGINEER. UTILIZE A LABORATORY REGULARLY INSPECTED BY THE CEMENT AND CONCRETE REFERENCE LABORATORY (CCRL) OF THE NATIONAL INSTITUTE OF STANDARDS AND TECHNOLOGY, OR OTHER APPROVED REFERENCE LABORATORY, TO PERFORM THE TESTING. BEFORE USE, SUBMIT DOCUMENTATION TO THE PROJECT ENGINEER CERTIFYING BOTH THE MACRO-SYNTHETIC FIBERS AND THE MIX MEET OR EXCEED THE REQUIRED PROPERTIES. SAMPLING WILL BE ALLOWED FOR TESTING PURPOSES. A DEMONSTRATION OF THE MIX PRODUCTION OR TRIAL MIX, MAY BE REQUIRED BY THE ENGINEER PRIOR TO PLACING ANY OF THE MIX ON THE PROJECT.

THE BATCH WEIGHTS SHALL BE CORRECTED TO COMPENSATE FOR THE MOISTURE CONTAINED IN THE AGGREGATE AT THE TIME OF USE. A CHEMICAL ADMIXTURE (705.12, TYPE A OR D) SHALL BE USED. THE TRANSIT MIXER CHARGE SHALL BE LIMITED TO 3/4 OF ITS RATED CAPACITY OR 6 CUBIC YARDS, WHICHEVER IS SMALLER. THE FIRST THREE TRANSIT MIXER LOADS ARE REQUIRED TO BE AT THE MINIMUM YARDAGE LISTED ABOVE TO SHOW PROOF OF THE SUCCESSFUL BATCHING OPERATION. AFTER CONSISTENCY IN THE DELIVERED MATERIAL HAS BEEN ESTABLISHED, THE CONCRETE SUPPLIER MAY INCREASE THE BATCH DELIVERED QUANTITIES AS LONG AS THE QUALITY REMAINS ACCEPTABLE TO THE ENGINEER. THE ENGINEER CAN REDUCE THE BATCH LOAD SIZE AT ANY TIME AS NEEDED TO CORRECT/IMPROVE CONCRETE QUALITY.

CONCRETE SUPPLIERS SHOULD RECOGNIZE THAT THE CORROSION INHIBITOR AND ADMIXTURES MAY HAVE AN EFFECT ON STRENGTH, ENTRAINED AIR CONTENT, WORKABILITY, ETC. OF THEIR CONCRETE MIXES. THE CORROSION INHIBITOR IS SUGGESTED TO BE A MCI PRODUCT BY CORTEC OR AN APPROVED EQUAL FROM THE QUALIFIED PRODUCTS LIST. THE CONCRETE SUPPLIER'S CHOICE OF ONE OF THESE CORROSION INHIBITORS DOES NOT ALLEVIATE MEETING DESIGN REQUIREMENTS. PLEASE BE ADVISED THAT SOME PRODUCTS ON THE LIST EFFECT THE DELIVERED MIX PROPERTIES GREATLY WHILE OTHER PRODUCTS DO NOT.

APPROACH SLABS, DIAPHRAGMS, AND BRIDGE RAILING CONCRETE (WHEN APPLICABLE) ARE TO USE THE SAME MIX DESIGN AS THE BRIDGE DECK. THE CONTRACTOR SHOULD BE ADVISED THAT CONCRETE RETARDING AGENTS MAY NEED TO BE ADDED TO OFFSET THE EFFECTS OF THE MIGRATING CORROSION INHIBITOR SELECTED. USE SELF-COMPACTING CONCRETE ON DECORATIVE RAILING SIMILAR TO TEXAS RAILING AND MACRO-SYNTHETIC CONCRETE PER THIS SPECIFICATION ON TRADITIONAL CONCRETE RAILING WHEN APPLICABLE.

THE CONTRACTOR SHALL PROVIDE TRADITIONAL BRIDGE DECK FORMS CONFORMING TO CMS 508. PERMANENT STAY-IN-PLACE (SIP) FORMS ARE NOT ALLOWED. THE PLACING OF THE DECK AND THE APPROACH SLABS IN THE SAME CONCRETE POUR IS NOT PERMITTED.

DESIGN AGENCY	TWO MIRANOVA PLACE SUITE 480 COLUMBUS, OHIO 43215	
		
DATE	4/24/20	FILE NUMBER
REVIEWED	MJZ	3110966
DRAWN	RLC	REVISED
DESIGNED	RLC	CHECKED
		SAP
GENERAL NOTES		
BRIDGE NO. HAM-75-1539R 1-75 NB OVER SHARON RD.		
HAM-75-14.61 PID No. 76256		
3/36		
645 708		

GENERAL NOTES

DESIGN SPECIFICATIONS:

THIS STRUCTURE CONFORMS TO THE "LRFD BRIDGE DESIGN SPECIFICATIONS" ADOPTED BY THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS, 5TH EDITION, INCLUDING THE 2010 INTERIM SPECIFICATIONS AND THE ODOT BRIDGE DESIGN MANUAL, 2007 EDITION.

DESIGN DATA:

THE FOLLOWING DESIGN DATA IS ASSUMED:

CONCRETE CLASS QC1 - COMPRESSIVE STRENGTH 4000 PSI (FOOTING, WINGWALL AND FORESLOPE WALL)

REINFORCING STEEL - ASTM A615, A616, OR A617 GRADE 60 MINIMUM YIELD STRENGTH 60,000 PSI (ALL REINFORCING SHALL BE EPOXY COATED)

POROUS BACKFILL WITH FILTER FABRIC:

1'-6" THICK SHALL BE PLACED BEHIND THE WINGWALLS ONLY AND SHALL EXTEND TO 12" BELOW THE EMBANKMENT SURFACE. GEOTEXTILE FABRIC SHALL BE PLACED BETWEEN THE POROUS BACKFILL AND REPLACED EXCAVATION ADJACENT TO THE STRUCTURE. IT SHALL TURN UNDER THE BOTTOM OF THE POROUS AND RETURN 6" ABOVE THE TOP ELEVATION OF THE WEEPHOLE. WEEPHOLES SHALL BE PLACED 6" TO 12" ABOVE THE NORMAL WATER ELEVATION OR GROUND LINE AND SHALL HAVE A MAXIMUM SPACING OF 10'-0". A MINIMUM OF ONE WEEPHOLE SHALL BE PROVIDED PER WINGWALL.

EXISTING STRUCTURE VERIFICATION:

DETAILS AND DIMENSIONS SHOWN ON THESE PLANS PERTAINING TO THE EXISTING STRUCTURE HAVE BEEN OBTAINED FROM PLANS OF THE EXISTING STRUCTURE AND FROM FIELD OBSERVATIONS AND MEASUREMENTS. CONSEQUENTLY, THEY ARE INDICATIVE OF THE EXISTING STRUCTURE AND THE PROPOSED WORK BUT THEY SHALL BE CONSIDERED TENTATIVE AND APPROXIMATE. THE CONTRACTOR IS REFERRED TO CMS SECTIONS 102.05 AND 105.02.

CONTRACT BID PRICES SHALL BE BASED UPON A RECOGNITION OF THE UNCERTAINTIES DESCRIBED ABOVE AND UPON PREBID EXAMINATION OF THE EXISTING STRUCTURE BY THE CONTRACTOR. HOWEVER, ALL PROJECT WORK SHALL BE BASED UPON ACTUAL DETAILS AND DIMENSIONS WHICH HAVE BEEN VERIFIED BY THE CONTRACTOR IN THE FIELD.

ITEM 843 - PATCHING CONCRETE STRUCTURES WITH TROWELABLE MORTAR, AS PER PLAN:

AN ESTIMATED QUANTITY FOR THIS ITEM HAS BEEN PROVIDED TO BE USED AS DIRECTED BY THE ENGINEER FOR PATCHING SPALLED AREAS ON THE EXISTING CONDUITS.

FOUNDATION BEARING RESISTANCE

FOUNDATION BEARING RESISTANCE: WINGWALL FOOTINGS, AS DESIGNED, PRODUCE A MAXIMUM SERVICE LOAD PRESSURE OF 1.68 KIPS PER SQUARE FOOT AND A MAXIMUM STRENGTH LOAD PRESSURE OF 2.36 KIPS PER SQUARE FOOT. THE FACTORED BEARING RESISTANCE IS 5.5 KIPS PER SQUARE FOOT.


ABBREVIATIONS:

THE FOLLOWING ABBREVIATIONS ARE USED THROUGHOUT THESE PLANS:

- B = BASELINE
- C = CENTERLINE
- CIP = CAST IN PLACE
- CMS = CONSTRUCTION AND MATERIAL SPECIFICATIONS
- EF = EACH FACE
- EL = ELEVATION
- EX = EXISTING
- FF = FAR FACE
- NF = NEAR FACE
- PEJF = PREFORMED EXPANSION JOINT FILLER
- TYP = TYPICAL

SEALING OF FORESLOPE WALL AND WINGWALLS:

ALL EXPOSED FORESLOPE WALL AND WINGWALL CONCRETE SHALL BE SEALED WITH EPOXY-URETHANE SEALER. THE LIMITS SHALL BE AS SHOWN IN THE DIAGRAMS BELOW. PAYMENT FOR THE EPOXY-URETHANE SEALER SHALL BE PER ITEM 512, SEALING OF CONCRETE SURFACES.



LIMITS OF ITEM 512 - SEALING CONCRETE SURFACES

(A) - SEAL ENTIRE CONCRETE SURFACE AREA

ESTIMATED QUANTITIES

ITEM	ITEM EXT	TOTAL	UNIT	DESCRIPTION
202	11200	LS		PORTIONS OF STRUCTURE REMOVED
202	35200	48	FT	PIPE REMOVED, OVER 24"
503	11100	LS		COFFERDAMS AND EXCAVATION BRACING
503	21300	LS		UNCLASSIFIED EXCAVATION
509	10000	10553	LB	EPOXY COATED REINFORCING STEEL
511	46210	113	CY	CLASS QC1 CONCRETE, RETAINING/WINGWALL INCLUDING FOOTING
512	10100	120	SY	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)
518	21230	LS		POROUS BACKFILL WITH GEOTEXTILE FABRIC
601	11000	75	SY	RIPRAP, TYPE D
601	32104	106	CY	ROCK CHANNEL PROTECTION, TYPE B WITH GEOTEXTILE FABRIC
611	30000	48	FT	96" CONDUIT, TYPE A 706.02
843	50001	40	SF	PATCHING CONCRETE STRUCTURES WITH TROWELABLE MORTAR, AS PER PLAN
TOTALS CARRIED TO GENERAL SUMMARY				

\\10.120.112.5\ibishare\pre-int\06\06-386_HAM-75\HAM\00000\structures\HAM075_1557\00000\0002A.dgn 2021-01-19 1:03:48 PM Shirwan,Saeed



DESIGNED	CHECKED	DRAWN	REVIEWED	DATE
SJF	SRB	AIS	JDH	02/03/16
				STRUCTURE FILE NUMBER
				310982

GENERAL NOTES & QUANTITIES

HAM-75-14.61
PID No. 76256